

Oracle® Retail Demand Forecasting

User Guide for the RPAS Fusion Client

Release 14.1.1

E68927-02

November 2015

Copyright © 2015, Oracle and/or its affiliates. All rights reserved.

Primary Author: Melissa Artley

This software and related documentation are provided under a license agreement containing restrictions on use and disclosure and are protected by intellectual property laws. Except as expressly permitted in your license agreement or allowed by law, you may not use, copy, reproduce, translate, broadcast, modify, license, transmit, distribute, exhibit, perform, publish, or display any part, in any form, or by any means. Reverse engineering, disassembly, or decompilation of this software, unless required by law for interoperability, is prohibited.

The information contained herein is subject to change without notice and is not warranted to be error-free. If you find any errors, please report them to us in writing.

If this is software or related documentation that is delivered to the U.S. Government or anyone licensing it on behalf of the U.S. Government, then the following notice is applicable:

U.S. GOVERNMENT END USERS: Oracle programs, including any operating system, integrated software, any programs installed on the hardware, and/or documentation, delivered to U.S. Government end users are "commercial computer software" pursuant to the applicable Federal Acquisition Regulation and agency-specific supplemental regulations. As such, use, duplication, disclosure, modification, and adaptation of the programs, including any operating system, integrated software, any programs installed on the hardware, and/or documentation, shall be subject to license terms and license restrictions applicable to the programs. No other rights are granted to the U.S. Government.

This software or hardware is developed for general use in a variety of information management applications. It is not developed or intended for use in any inherently dangerous applications, including applications that may create a risk of personal injury. If you use this software or hardware in dangerous applications, then you shall be responsible to take all appropriate fail-safe, backup, redundancy, and other measures to ensure its safe use. Oracle Corporation and its affiliates disclaim any liability for any damages caused by use of this software or hardware in dangerous applications.

Oracle and Java are registered trademarks of Oracle and/or its affiliates. Other names may be trademarks of their respective owners.

Intel and Intel Xeon are trademarks or registered trademarks of Intel Corporation. All SPARC trademarks are used under license and are trademarks or registered trademarks of SPARC International, Inc. AMD, Opteron, the AMD logo, and the AMD Opteron logo are trademarks or registered trademarks of Advanced Micro Devices. UNIX is a registered trademark of The Open Group.

This software or hardware and documentation may provide access to or information about content, products, and services from third parties. Oracle Corporation and its affiliates are not responsible for and expressly disclaim all warranties of any kind with respect to third-party content, products, and services unless otherwise set forth in an applicable agreement between you and Oracle. Oracle Corporation and its affiliates will not be responsible for any loss, costs, or damages incurred due to your access to or use of third-party content, products, or services, except as set forth in an applicable agreement between you and Oracle.

Licensing Note: This media pack includes a Restricted Use license for Oracle Retail Predictive Application Server (RPAS) - Enterprise Engine to support Oracle® Retail Demand Forecasting only.

Value-Added Reseller (VAR) Language

Oracle Retail VAR Applications

The following restrictions and provisions only apply to the programs referred to in this section and licensed to you. You acknowledge that the programs may contain third party software (VAR applications) licensed to Oracle. Depending upon your product and its version number, the VAR applications may include:

- (i) the **MicroStrategy** Components developed and licensed by MicroStrategy Services Corporation (MicroStrategy) of McLean, Virginia to Oracle and imbedded in the MicroStrategy for Oracle Retail Data Warehouse and MicroStrategy for Oracle Retail Planning & Optimization applications.
- (ii) the **Wavelink** component developed and licensed by Wavelink Corporation (Wavelink) of Kirkland, Washington, to Oracle and imbedded in Oracle Retail Mobile Store Inventory Management.
- (iii) the software component known as **Access Via™** licensed by Access Via of Seattle, Washington, and imbedded in Oracle Retail Signs and Oracle Retail Labels and Tags.
- (iv) the software component known as **Adobe Flex™** licensed by Adobe Systems Incorporated of San Jose, California, and imbedded in Oracle Retail Promotion Planning & Optimization application.

You acknowledge and confirm that Oracle grants you use of only the object code of the VAR Applications. Oracle will not deliver source code to the VAR Applications to you. Notwithstanding any other term or

condition of the agreement and this ordering document, you shall not cause or permit alteration of any VAR Applications. For purposes of this section, "alteration" refers to all alterations, translations, upgrades, enhancements, customizations or modifications of all or any portion of the VAR Applications including all reconfigurations, reassembly or reverse assembly, re-engineering or reverse engineering and recompilations or reverse compilations of the VAR Applications or any derivatives of the VAR Applications. You acknowledge that it shall be a breach of the agreement to utilize the relationship, and/or confidential information of the VAR Applications for purposes of competitive discovery.

The VAR Applications contain trade secrets of Oracle and Oracle's licensors and Customer shall not attempt, cause, or permit the alteration, decompilation, reverse engineering, disassembly or other reduction of the VAR Applications to a human perceivable form. Oracle reserves the right to replace, with functional equivalent software, any of the VAR Applications in future releases of the applicable program.

Contents

Send Us Your Comments	xxv
Preface	xxvii
Audience	xxvii
Documentation Accessibility	xxvii
Related Documents	xxvii
Supplemental Documentation	xxvii
Customer Support	xxviii
Review Patch Documentation	xxviii
Improved Process for Oracle Retail Documentation Corrections	xxviii
Oracle Retail Documentation on the Oracle Technology Network	xxix
Conventions	xxix
1 Introduction	
Forecasting Challenges and RDF Solutions	1-1
Selecting the Best Forecasting Method	1-2
Overcoming Data Sparsity Through Source Level Forecasting	1-2
Forecasting Demand for New Products and Locations	1-3
Managing Forecasting Results Through Automated Exception Reporting	1-3
Incorporating the Effects of Promotions and Other Event-Based Challenges on Demand	1-4
Managing and Forecasting for Floating Events	1-4
53 Week Calendar	1-5
Forecasting Returns	1-5
Oracle Retail Demand Forecasting Architecture	1-6
The Oracle Retail Predictive Application Server and RDF	1-6
Global Domain Versus Simple Domain Environment	1-7
Oracle Retail Demand Forecasting Workbook Groups	1-7
New Items & Locations	1-8
Promotional Planning	1-8
Core Forecasting	1-9
RDF Administration	1-10
Grade	1-10
Cross Promo Effect Module (CPEM)	1-11
RDF Solution and Business Process Overview	1-12
RDF and the Oracle Retail Enterprise	1-12

RDF Primary Workflow	1-12
RDF Batch Flow Process.....	1-13

2 Navigation

Before you Begin	2-1
Logging into RDF	2-1
Taskflow Pane	2-3
Access Based Visibility	2-6
Switching Between Multiple Tasks	2-6
Opening a Workbook	2-6
Deleting a Workbook	2-7
Permissible File Names	2-8
Renaming a Workbook	2-8
Understanding the Workbook Wizard Window	2-10
Accessing Online Help	2-11
Contents	2-12
Figures and Tables	2-12
Index.....	2-13
Search.....	2-13
Logging Out of RDF	2-14

3 Oracle Retail Demand Forecasting Methods

Forecasting Techniques Used in RDF	3-1
Exponential Smoothing	3-1
Regression Analysis.....	3-1
Bayesian Analysis.....	3-2
Prediction Intervals.....	3-2
Automatic Method Selection	3-2
Source Level Forecasting.....	3-2
Promotional Forecasting	3-2
Time Series (Statistical) Forecasting Methods	3-2
Why Use Statistical Forecasting?	3-3
Average.....	3-4
Bayesian Information Criterion (BIC)	3-4
AutoES Flowchart	3-5
Automatic Forecast Level Selection (AutoSource).....	3-6
The Forecast Level Selection Process	3-7
Determining the Best Source Level Forecast.....	3-7
Status and Scheduling	3-8
Using the System-Selected Forecast Level	3-8
Exponential Smoothing (ES) Forecasting Methods.....	3-8
Simple Exponential Smoothing.....	3-9
Croston's Method.....	3-10
Simple/Intermittent Exponential Smoothing.....	3-11
Holt Exponential Smoothing.....	3-11
Multiplicative Winters Exponential Smoothing.....	3-11
Oracle Winters.....	3-12

Oracle Winters Decomposition.....	3-12
Winters Standard	3-13
Winters Responsive	3-13
Additive Winters Exponential Smoothing	3-14
Seasonal Exponential Smoothing (SeasonalES)	3-15
Seasonal Regression	3-15
Profile-Based Forecasting	3-16
Forecast Method	3-16
Profile-Based Method and New Items	3-16
Bayesian Forecasting.....	3-17
Sales Plans versus Historic Data	3-18
Bayesian Algorithm	3-18
LoadPlan Forecasting Method	3-18
Copy Forecasting Method.....	3-18
Causal (Promotional) Forecasting Method.....	3-19
Causal Forecasting with Baselines.....	3-20
Causal Forecasting Using the Baseline Process	3-21
Causal Forecasting for Short-lifecycle Items	3-22
Causal Forecasting at the Daily Level.....	3-22
Example.....	3-23
Final Considerations About Causal Forecasting	3-24

4 Forecast Product/Location Cloning Administration Task

Product/Location Cloning Administration Workbook	4-2
Adjustment Parameters View	4-4
Measures: Adjustment Parameters View	4-4
Location Cloning View	4-4
Measures: Location Cloning View.....	4-5
Product Cloning View	4-6
Measures: Product Cloning View	4-7
Clone Mask View	4-7
Measures: Clone Mask View	4-8

5 Forecast Like-Item & Sister-Store Task

Forecast Like-Item& Sister-Store Workbook.....	5-1
Like-Item View	5-3
Measures: Like-Item View	5-4
Sister-Store View	5-4
Measures: Sister-Store View	5-4
Advanced Parameter View	5-5
Measures: Advanced Parameter View	5-5
Required Steps for Forecasting Using Each of the Like SKU/Sister-Store Methods.....	5-8
Procedures.....	5-8
Seasonality/SKU.....	5-8
Seasonality/STR.....	5-9
Seasonality/SKU_STR.....	5-9

Lifecycle/SKU	5-9
Lifecycle/STR	5-9
Lifecycle/SKU_STR	5-10

6 Promote (Promotional Forecasting) Task

About Promote	6-1
What Is Promotional Forecasting?	6-1
Comparison Between Promotional and Statistical Forecasting	6-2
Developing Promotional Forecast Methods.....	6-2
Promotional Forecasting Approach	6-3
Promotional Forecasting Terminology and Workflow.....	6-3
Examples of Promotion Events	6-4
Promote Tasks, Workbooks, and Views	6-4
Promo Effectiveness - Promotion Results Task	6-5
Promo Effectiveness - Promotion Results Workbook	6-6
Promotion Model Type View	6-8
Measures: Promotion Model Type View	6-9
Promotions View	6-9
Measures: Promotions View.....	6-9
Aggregated Promotion Lift Override View	6-10
Measures: Aggregated Promotion Lift Override View	6-10
Promotional Forecast View.....	6-10
Measures: Promotional Forecast View	6-11
Promotion Parameters View.....	6-12
Measures: Promotion Parameters View	6-12
Promo Planner Task	6-14
Promo Planner Workbook	6-14
Promotions View	6-17
Measures: Promotions View.....	6-17
Promotion Management Task	6-18
Promotion Management Workbook.....	6-19
Promo Variable Model Type View	6-20
Measure: Promo Variable Model Type View.....	6-20
Promotion Enable View	6-21
Measures: Promotion Enable View	6-21
Accept Negative Lift View.....	6-21
Measures: Accept Negative Lift View.....	6-22
Promo Effect Maintenance Task	6-22
Promo Effect Maintenance Workbook	6-22
Promotion Parameters View.....	6-25
Measures: Promotion Parameters View	6-25
Procedures in Promotional Forecasting	6-27
Setting Up the System to Run a Promotional Forecast	6-27
Viewing a Forecast That Includes Promotion Effects	6-28
Viewing and Editing Promotion System-Calculated Effects	6-28
Promotion Simulation (What-if?) and Analysis	6-28

7 Forecast Scorecard Task

Forecast Scorecard Workbook.....	7-1
Error Measure View	7-8
Measures: Error Measure View	7-8
Actuals versus Forecasts View	7-9
Measures: Actuals versus Forecasts View	7-10

8 Interactive Forecasting Task

Improve Performance for the Interactive Forecasting Workbook	8-1
Interactive Forecasting Workbook	8-1
Forecasting Parameter View	8-7
Measures: Forecasting Parameter View	8-7
Additional Information about the Interactive Forecasting View Parameters.....	8-8
Interactive Forecasting View.....	8-9
Measures: Interactive Forecasting View	8-9

9 Forecast Administration Task

Forecast Administration Task Components.....	9-1
Basic versus Advanced.....	9-1
Final versus Source Level Forecasts	9-1
Forecasting Methods Available in RDF	9-2
Forecast Administration Workbook	9-5
Forecast Administration Workbook: Basic Settings	9-6
Final Level View - Basic Settings	9-6
Measures: Final Level View - Basic Settings	9-7
Final and Source Level Parameters View - Basic Settings.....	9-8
Measures: Final and Source Level Parameters View - Basic Settings	9-8
Forecast Administration Workbook: Advanced Settings	9-10
Causal Parameters View - Advanced Settings.....	9-10
Measures: Causal Parameters View - Advanced Settings	9-11
Final Level Parameters View - Advanced Settings	9-15
Measures: Final Level Parameters View - Advanced Settings	9-15
Final and Source Level Parameters View - Advanced Settings	9-20
Measures: Source Level View - Advanced Settings.....	9-21
Regular Price Parameters View- Advanced Settings.....	9-26
Measures: Regular Price Parameters View- Advanced Settings.....	9-26
Promo Affinity Parameters View- Advanced Settings.....	9-28
Measures: Promo Affinity Parameters View- Advanced Settings.....	9-28
Demand Transference Parameters View- Advanced Settings.....	9-29
Measures: Demand Transference Parameters View- Advanced Settings	9-30

10 Forecast Maintenance Task

Forecast Maintenance Workbook.....	10-1
Forecast Maintenance Workbook: Basic Settings	10-4
Final and Source Level Views - Basic Settings	10-4

Measures: Final and Source Level Views - Basic Settings.....	10-5
Forecast Maintenance Workbook: Intermediate Settings	10-7
Final Return Forecast Intermediate Intersection Parameters View	10-7
Measures: Final Return Forecast Intermediate Intersection Parameters View	10-7
Forecast Maintenance Workbook: Advanced Settings	10-7
Advanced Final Parameter View	10-8
Measures: Advanced Final Parameter View	10-8

11 Preprocessing Administration Task

Preprocess Administration Tasks, Steps, and Views	11-2
Preprocess Admin Workbook	11-2
Preprocess Admin Step	11-3
Preprocess Admin View	11-4
Measures: Preprocess Admin View	11-4
Out of Stock and Outlier Threshold Step	11-4
Out of Stock and Outlier Threshold View	11-5
Measures: Out of Stock and Outlier Threshold View	11-5
Preprocess Parameters Step	11-6
Preprocess Panel for Baseline Data Source View	11-6
Measures: Preprocessing Panel for Baseline Data Source View	11-7
Preprocess Panel for Causal Data Source View	11-7
Measures: Preprocessing Panel for Causal Data Source View	11-8
Preprocess Method Parameters View	11-9
Measures: Preprocessing Methods Parameters View	11-9
Preprocess Method Parameters Override View	11-10
Measures: Preprocessing Method Parameters Override View	11-10

12 Preprocessing Review and What-if Task

Preprocess Workbook Functionality	12-1
Preprocess Review and What-if Tasks, Steps, and Views	12-2
Preprocess Review and What-if Workbook	12-2
Preprocess Admin Step	12-6
Preprocessing Admin View	12-6
Measures: Preprocessing Admin View	12-6
Out of Stock and Outlier Threshold Step	12-6
Out of Stock and Outlier Threshold View	12-7
Measures: Out of Stock and Outlier Threshold View	12-7
Preprocess Parameters Step	12-8
Preprocess Panel for Baseline Data Source View	12-8
Measures: Preprocessing Panel for Baseline Data Source View	12-9
Preprocess Panel for Causal Data Source View	12-9
Measures: Preprocessing Panel for Causal Data Source View	12-10
Preprocess Method Parameters View	12-11
Measures: Preprocessing Methods Parameters View	12-11
Preprocess Method Parameters Override View	12-12
Measures: Preprocessing Method Parameters Override View	12-12
What-if Step	12-13

What-if Data View.....	12-13
Measures: What-if Data View	12-14
What-if Plot View	12-15
Measures: What-if Plot View.....	12-15
13 Floating Event Administration Task	
Floating Event Administration Tasks, Steps, and Views	13-2
Floating Events Admin Workbook	13-2
Floating Event Admin Step	13-4
Floating Event Calendar Maintenance View	13-4
Measures: Floating Event Calendar Maintenance View	13-5
14 Extra Week Administration Task	
Extra Week Administration Workbook	14-1
Extra Week Indicator Setup View	14-3
Measures: Extra Week Indicator Setup View	14-3
15 Curve Task	
Curve Tasks and Wizards	15-1
Profile Administration Task	15-2
Profile Administration Workbook.....	15-2
Profile Parameter View	15-3
Measures: Profile Parameter View	15-4
Profile and Source Level Intersection View	15-6
Measures: Profile and Source Level Intersection View	15-7
Profile Approval Task	15-7
Profile Approval Workbook.....	15-8
Final Profile View.....	15-11
Measures: Final Profile View	15-11
Source Profile View.....	15-11
Measures: Source Profile View	15-12
Profile Approval View.....	15-12
Measures: Profile Approval View	15-12
Profile Maintenance Task.....	15-13
Profile Maintenance Workbook	15-13
Profile Maintenance: Final Approval and Sourcing View	15-16
Measures: Final Approval and Sourcing View.....	15-16
Profile Maintenance: Final Training Window View	15-17
Measures: Final Training Window	15-17
Run Batch Profile Task.....	15-17
Run Batch Profile Workbook.....	15-17
16 Run Batch Forecast Task	
Running a Batch Forecast Manually.....	16-1
Before You Begin	16-1

Procedure	16-1
Run Batch Forecast Workbook	16-2

17 Forecast Approval Task

Forecast Approval Workbook	17-2
Advanced Final Level View	17-10
Measures: Advanced Final Level View.....	17-10
Final Level View	17-12
Measures: Final Level View	17-12
Approval View	17-16
Measures: Approval View	17-17
Valid Forecast Run View	17-17
Measures: Valid Forecast Run View.....	17-17
Source Level View	17-18
Measures: Source Level View.....	17-18
Final or Source System Parameters View	17-18
Measures: Final or Source System Parameters View	17-19

18 Alert Thresholds Task

Defined Alerts.....	18-1
Forecast versus Recent Sales.....	18-1
Current Forecast versus Last Approved Forecast	18-2
Forecast Accuracy Alert	18-2
Alert Thresholds Workbook	18-3
Forecast Alert Default Parameters View	18-6
Measures: Forecast Alert Default Parameters View	18-6
Forecast Alert Intermediate Intersection Parameters View	18-7
Measures: Forecast Alert Intermediate Intersection Parameters View	18-8
Forecast Alert Final Level Intersection Parameters View	18-9
Measures: Forecast Alert Final Level Intersection Parameters View	18-10

19 Forecast Delete Task

Forecast Delete Wizard.....	19-1
------------------------------------	-------------

20 Grade Task

Cluster Methods in Grade	20-1
Breakpoint	20-2
Index to Average	20-2
Batch Neural Gas Algorithm (BaNG).....	20-2
BaNG versus Breakpoint.....	20-2
Grade in a Global Domain Environment	20-3
Grade Tasks and Wizards.....	20-3
Breakpoint Administration Task	20-3
Breakpoint Administration Workbook	20-3
Breakpoint Administration View.....	20-4
Delete Cluster Run Task.....	20-5

Delete Cluster Run Wizard.....	20-5
Cluster Review Task	20-5
Cluster Review Workbook.....	20-6
Cluster Input Summary View	20-6
Measures: Cluster Input Summary View	20-7
Generate Breakpoint Grades Task	20-8
Generate Breakpoint Grades Wizard	20-8
Generate Clusters Task	20-12
Generate Clusters Wizard.....	20-12

21 Cross Promotional Effects Module (CPEM)

About Promotional Effects	21-2
CPEM Workbooks and Wizards	21-3
Effect Estimation Administration Task	21-3
Effect Estimation Administration Workbook	21-3
Default Parameters View	21-6
Measures: Default Parameters View	21-6
Cannibalization Parameter Override View	21-7
Measures: Cannibalization Parameter Override View	21-7
Halo Parameter Override View	21-8
Measures: Halo Parameter Override View	21-8
Halo Products Mapping View.....	21-9
Measures: Halo Products Mapping View	21-9
Effect Estimation Review and Approval Task	21-9
Effect Estimation Review and Approval Workbook.....	21-10
Cannibalization Effects Drive View	21-12
Measures: Cannibalization Effects Drive View	21-12
Cannibalization Effects Percentage View	21-13
Measures: Cannibalization Effects Percentage View	21-13
Cannibalization Effects View	21-14
Measures: Cannibalization Effects View	21-14
Cannibalization History Data View	21-15
Measures: Cannibalization History Data View	21-16
Halo Effects Drive View	21-16
Measures: Halo Effects Drive View	21-16
Halo Effects Percentage View.....	21-17
Measures: Halo Effects Percentage View	21-17
Halo Effects View	21-18
Measures: Halo Effects View.....	21-18
Halo History Data View	21-19
Measures: Halo History Data View.....	21-19
Cannibalization Statistic Report View	21-20
Measures: Cannibalization Statistic Report View	21-20
Halo Statistic Report View	21-21
Measures: Halo Statistic Report View.....	21-21

A Appendix: Preprocessing

Preprocessing Methods	A-2
Standard Median	A-2
Retail Median	A-3
Standard Exponential Smoothing	A-3
Lost Sales Standard Exponential Smoothing	A-5
Override	A-7
Increment	A-7
Forecast Sigma	A-8
Forecast Sigma Event	A-8
DePrice	A-9
Clear	A-9
No Filtering	A-9
Preprocessing for Stock-outs	A-9
Preprocessing for Outliers	A-10
Preprocessing for Promotional Forecasting	A-10

B Appendix: RDF Workbooks (Fusion Client)

Forecast Product/Location Cloning Administration Task	B-1
Product/Location Cloning Administration Workbook	B-2
Forecast Like-Item, Sister-Store Task	B-2
Forecast Like-Item, Sister-Store Workbook	B-2
Promote (Promotional Forecasting)	B-3
Promo Effectiveness - Promotion Results Task	B-3
Promo Effectiveness - Promotion Results Workbook	B-3
Promo Effect Maintenance Task	B-4
Promo Effect Maintenance Workbook	B-4
Promotion Management Task	B-4
Promotion Management Workbook	B-5
Promo Planner Task	B-5
Promo Planner Workbook	B-5
Forecast Scorecard Task	B-5
Forecast Scorecard Workbook	B-5
Interactive Forecasting Task	B-6
Interactive Forecasting Workbook	B-6
Forecast Administration Task	B-7
Forecast Administration Workbook	B-7
Forecast Maintenance Task	B-9
Forecast Maintenance Workbook	B-9
Preprocessing Administration Task	B-10
Preprocessing Administration Workbook	B-10
Preprocessing Review and What-if Task	B-11
Preprocessing Review and What-if Workbook	B-11
Floating Event Administration Task	B-13
Floating Event Admin Workbook	B-13
Extra Week Administration Task	B-13
Extra Week Administration Workbook	B-14

Run Batch Forecast Task	B-14
Wizard	B-14
Forecast Approval Task	B-14
Forecast Approval Workbook	B-14
Alert Thresholds Task	B-15
Alert Thresholds Workbook	B-16
Forecast Delete Task	B-16
Wizard	B-17
Cross Promotional Effects Module (CPEM) Task	B-17
Effect Estimation Administration Workbook	B-17
Effect Estimation Review and Approval Workbook	B-17

C Appendix: Curve Workbooks (Fusion Client)

Profile Administration Task	C-1
Profile Administration Workbook	C-1
Profile Approval Task	C-1
Profile Approval Workbook	C-2
Profile Maintenance Task	C-2
Profile Maintenance Workbook	C-2
Run Batch Profile Task	C-2

D Appendix: Grade Workbooks (Fusion Client)

Breakpoints Administration Task	D-1
Delete Cluster Run Task	D-1
Cluster Review Task	D-1
Breakpoint Grades Task	D-2
Generate Clusters Task	D-2

Glossary

List of Tables

2-1	Description of Icons in the Taskflow Pane	2-5
2-2	Workbook Wizard Window User Interface Components.....	2-11
5-1	Substitute Methods for Forecasting	5-7
6-1	Promote Tasks, Workbooks, and Views	6-5
6-2	Promo Effect Types.....	6-26
9-1	Fallback Methods	9-23
9-2	Winters Forecasting Approaches.....	9-25
9-3	Comparison of Winters Forecasting Models	9-25
17-1	Views for the Forecast Approval Workbook	17-1
B-1	Product/Location Cloning Administration Workbook	B-2
B-2	Forecast Like-Item, Sister-Store Workbook.....	B-2
B-3	Promo Effectiveness - Promotion Results Workbook.....	B-3
B-4	Promo Effect Maintenance Workbook	B-4
B-5	Promotion Management Workbook	B-5
B-6	Promo Planner Workbook	B-5
B-7	Forecast Scorecard Workbook.....	B-6
B-8	Interactive Forecasting Workbook	B-6
B-9	Forecast Administration Workbook.....	B-7
B-10	Forecast Maintenance Workbook	B-10
B-11	Preprocessing Administration Workbook	B-11
B-12	Preprocessing Review and What-if Workbook	B-12
B-13	Floating Event Admin Workbook	B-13
B-14	Extra Week Administration Workbook.....	B-14
B-15	Forecast Approval Workbook.....	B-15
B-16	Alert Thresholds Workbook.....	B-16
B-17	Effect Estimation Administration Workbook	B-17
B-18	Effect Estimation Review and Approval Workbook	B-18
C-1	Profile Administration Workbook.....	C-1
C-2	Profile Approval Workbook.....	C-2
C-3	Profile Maintenance Workbook	C-2
D-1	Cluster Review Workbook.....	D-1

List of Figures

1-1	Final Level versus Source Level Forecasting	1-3
1-2	Calculating Returns	1-6
1-3	Global Domain versus Simple Domain Environment.....	1-7
1-4	New Item & Location Taskflow Pane	1-8
1-5	Promotional Planning Taskflow Pane	1-8
1-6	Core Forecasting Taskflow Pane.....	1-9
1-7	RDF Administration Taskflow Pane	1-10
1-8	Grade Taskflow Pane	1-11
1-9	CPEM Taskflow Pane	1-11
1-10	RDF and the Oracle Retail Enterprise	1-12
1-11	Batch Flow Process in RDF	1-13
2-1	RPAS Fusion Client Login Page.....	2-2
2-2	RPAS Fusion Client Login Page, Accessed Through SSO	2-2
2-3	RPAS Fusion Client Home Page	2-3
2-4	Illustration of Activity, Task, and Step	2-4
2-5	Taskflow Pane	2-4
2-6	Icons in the Taskflow Pane	2-5
2-7	Show List of Workbooks Icon	2-7
2-8	Open Workbook Window	2-7
2-9	Delete Warning Message	2-8
2-10	Renaming a Workbook.....	2-9
2-11	Rename Workbook Dialog Box.....	2-9
2-12	Renamed Workbook	2-10
2-13	Workbook Wizard	2-10
2-14	Online Help Link	2-12
2-15	Online Help Window, Book Field	2-12
2-16	Help Topic within Online Help	2-12
2-17	Online Help: Figure List	2-13
2-18	Online Help: Index.....	2-13
2-19	Online Help: Search.....	2-14
2-20	Logout Link.....	2-14
3-1	AutoES Flowchart	3-6
3-2	Forecast Level Selection Process	3-7
3-3	Simple Exponential Smoothing.....	3-10
3-4	Croston's Method	3-10
3-5	Holt Exponential Smoothing	3-11
3-6	Multiplicative Winters Exponential Smoothing	3-14
3-7	Baseline Process.....	3-21
4-1	Cloning Examples	4-2
4-2	New Item & Locations Task	4-2
4-3	Workbook Wizard: Select Product	4-3
4-4	Workbook Wizard: Select Locations	4-3

4-5	Adjustment Parameters View	4-4
4-6	Adjustment Ratio Formula	4-4
4-7	Cloned History Formula	4-4
4-8	Location Cloning View.....	4-5
4-9	Product Cloning View.....	4-7
4-10	Clone Mask View	4-8
5-1	Forecast Like-Item & Sister-Store Task.....	5-1
5-2	Workbook Wizard: Forecast Level	5-2
5-3	Workbook Wizard: Select Locations	5-2
5-4	Workbook Wizard: Select IProducts	5-3
5-5	Workbook Wizard: Select Extra Measures	5-3
5-6	Final Like-Item View	5-4
5-7	Final Sister-Store View	5-4
5-8	Advanced Parameter View.....	5-5
6-1	Promo Effectiveness - Promotion Results Task.....	6-6
6-2	Workbook Wizard: Causal Level.....	6-6
6-3	Workbook Wizard: Select Promotions.....	6-7
6-4	Workbook Wizard: Select Products.....	6-7
6-5	Workbook Wizard: Locations	6-8
6-6	Workbook Wizard: Select Calendar Positions.....	6-8
6-7	Promotion Model Type View.....	6-9
6-8	Promotions View.....	6-9
6-9	Aggregated Promotion Lift Override View	6-10
6-10	Promotional Forecast View	6-11
6-11	Promotion Parameters View	6-12
6-12	Promo Planner Task	6-15
6-13	Workbook Wizard: Select Promotions.....	6-15
6-14	Workbook Wizard: Select Products.....	6-16
6-15	Workbook Wizard: Select Location.....	6-16
6-16	Workbook Wizard: Select Days	6-17
6-17	Promotions View.....	6-17
6-18	Promotion Management Task.....	6-19
6-19	Workbook Wizard: Select Causal Level.....	6-19
6-20	Workbook Wizard: Select Promotions	6-20
6-21	Promo Variable Model Type View	6-20
6-22	Promotion Enable View	6-21
6-23	Accept Negative Lift View.....	6-22
6-24	Promo Effect Maintenance Task	6-22
6-25	Workbook Wizard: Causal Level	6-23
6-26	Workbook Wizard: Select Promotions.....	6-24
6-27	Workbook Wizard: Select Products.....	6-24
6-28	Workbook Wizard: Select Locations	6-25
6-29	Promotion Parameters View	6-25
7-1	Forecast Scorecard Task	7-1
7-2	Workbook Wizard: Forecast Level	7-2
7-3	Workbook Wizard: Forecast Generation Date	7-3
7-4	Workbook Wizard: Select Forecast Type.....	7-3
7-5	Workbook Wizard: Calculate Error Statistics	7-4
7-6	Workbook Wizard: Select IProducts	7-4
7-7	Workbook Wizard: Select Locations	7-5
7-8	Workbook Wizard: Select Workbook Start Date.....	7-5
7-9	Workbook Wizard: Select Forecast End Date	7-6
7-10	Workbook Wizard: Select Workbook End Date.....	7-7
7-11	Workbook Wizard: Select Extra Measures	7-7
7-12	Error Measure View	7-8

7-13	Actuals versus Forecast View	7-10
8-1	Interactive Forecasting Task.....	8-2
8-2	Workbook Wizard: Forecast Level	8-2
8-3	Workbook Wizard: Forecast Start Date	8-3
8-4	Workbook Wizard: History Start Date	8-3
8-5	Workbook Wizard: Forecast End Date	8-4
8-6	Workbook Wizard: Forecast Horizon End Date.....	8-5
8-7	Workbook Wizard: Select Locations	8-5
8-8	Workbook Wizard: Select IProducts	8-6
8-9	Workbook Wizard: Forecast Results.....	8-6
8-10	Workbook Wizard: Select Extra Measures	8-7
8-11	Forecast Parameter View	8-7
8-12	Interactive Forecasting View	8-9
9-1	Forecast Administration Task	9-5
9-2	Workbook Wizard: Select Forecast Level	9-6
9-3	Final Level Parameters View.....	9-7
9-4	Final and Source Level Parameters View	9-8
9-5	Causal Parameters View	9-11
9-6	Final Level Parameters View.....	9-15
9-7	Final and Source Level Parameters View	9-21
9-8	Regular Price Parameters View- Advanced Settings.....	9-26
9-9	Regular Price Decaying Effect	9-27
9-10	Promo Affinity Parameters View- Advanced Settings.....	9-28
9-11	Demand Transference Parameters View- Advanced Settings	9-30
9-12	Demand Transference Decaying Effect	9-31
10-1	Forecast Maintenance Task.....	10-2
10-2	Workbook Wizard: Causal Level	10-2
10-3	Workbook Wizard: Select Locations	10-3
10-4	Workbook Wizard: Select Products	10-3
10-5	Workbook Wizard: Select Extra Measures	10-4
10-6	Final Level View - Basic Settings	10-4
10-7	Source Level View - Basic Settings	10-5
10-8	Final Return Forecast Intermediate Intersection Parameters View	10-7
10-9	Advanced Final Parameter View	10-8
11-1	Preprocess Administration Task.....	11-2
11-2	Workbook Wizard: Locations	11-3
11-3	Workbook Wizard: Select Products	11-3
11-4	Preprocess Admin View	11-4
11-5	Out of Stock and Outlier Threshold View.....	11-5
11-6	Preprocess Panel for Baseline Data Source View	11-7
11-7	Preprocess Panel for Causal Data Source View.....	11-8
11-8	Preprocess Method Parameters View	11-9
11-9	Preprocess Method Parameters Override View	11-10
12-1	Preprocess Review and What-if Task	12-3
12-2	Workbook Wizard: Locations	12-4
12-3	Workbook Wizard: Select Products	12-5
12-4	Workbook Wizard: Calendar	12-5
12-5	Preprocessing Admin View.....	12-6
12-6	Out of Stock and Outlier Threshold View.....	12-7
12-7	Preprocess Panel for Baseline Data Source View	12-9
12-8	Preprocess Panel for Causal Data Source View.....	12-10
12-9	Preprocess Method Parameters View	12-11
12-10	Preprocess Method Parameters Override View	12-12
12-11	What-if Data View	12-14
12-12	What-if Plot View.....	12-15

13-1	Floating Events Administration Task	13-2
13-2	Workbook Wizard: Products.....	13-3
13-3	Workbook Wizard: Stores.....	13-3
13-4	Workbook Wizard: Select Weeks.....	13-4
13-5	Floating Event Calendar Maintenance View	13-4
14-1	Extra Week Administration Task	14-1
14-2	Workbook Wizard: Select Week	14-2
14-3	Workbook Wizard: Select Group.....	14-2
14-4	Extra Week Indicator Setup View	14-3
15-1	Profile Administration Task.....	15-2
15-2	Workbook Wizard: Curve Level.....	15-3
15-3	Profile Parameter View	15-3
15-4	Profile and Source Level Intersection View	15-7
15-5	Profile Approval Task	15-8
15-6	Workbook Wizard: Curve Level.....	15-9
15-7	Workbook Wizard: Select Item	15-9
15-8	Workbook Wizard: Select Stores.....	15-10
15-9	Workbook Wizard: Select Day	15-10
15-10	Final Profile View.....	15-11
15-11	Source Profile View	15-12
15-12	Profile Approval View	15-12
15-13	Profile Maintenance Task.....	15-13
15-14	Workbook Wizard: Curve Level.....	15-14
15-15	Workbook Wizard: Select Items.....	15-14
15-16	Workbook Wizard: Select Stores.....	15-15
15-17	Workbook Wizard: Select Day	15-15
15-18	Final Approval and Sourcing View	15-16
15-19	Final Training Window View.....	15-17
15-20	Run Batch Profile Task	15-18
15-21	Workbook Wizard: Curve Level.....	15-18
15-22	Workbook Wizard: Verify Curve level.....	15-19
16-1	Run Batch Forecast Task	16-2
16-2	Workbook Wizard: Select Final Forecast Level	16-3
16-3	Workbook Wizard: Verify	16-3
17-1	Forecast Approval Task	17-2
17-2	Workbook Wizard: Select Final Forecast Level	17-3
17-3	Workbook Wizard: Select Forecast Levels	17-3
17-4	Workbook Wizard: Select Forecast Generation Date.....	17-4
17-5	Workbook Wizard: Select Stores.....	17-5
17-6	Workbook Wizard: Select Item	17-6
17-7	Workbook Wizard: History First Date.....	17-7
17-8	Workbook Wizard: Forecast Horizon Last Date	17-8
17-9	Workbook Wizard: Calendar Last Date	17-9
17-10	Workbook Wizard: Additional Forecasting Measures.....	17-10
17-11	Advanced Final Level View	17-10
17-12	Final Level View.....	17-12
17-13	Approval View	17-16
17-14	Valid Forecast Run View	17-17
17-15	Source Level View.....	17-18
17-16	System Parameters View	17-19
18-1	Alert Thresholds Task	18-4
18-2	Workbook Wizard: Select Final Levels	18-4
18-3	Workbook Wizard: Select Products.....	18-5
18-4	Workbook Wizard: Select Locations	18-5
18-5	Forecast Alert Default Parameters View	18-6

18-6	Forecast Alert Intermediate Intersection Parameters View	18-8
18-7	Forecast Alert Final Level Intersection Parameters View	18-10
19-1	Forecast Delete Task	19-1
19-2	Workbook Wizard: Select Forecasts to Delete	19-2
19-3	Workbook Wizard: Verify Delete	19-2
20-1	Breakpoint Administration Task	20-4
20-2	Breakpoint Administration View	20-4
20-3	Delete Cluster Run Task	20-5
20-4	Cluster Review Task	20-6
20-5	Workbook Wizard: Select Grade Birth	20-6
20-6	Cluster Input Summary View	20-7
20-7	Generate Breakpoint Grades Task.....	20-8
20-8	Workbook Wizard: Source Measure for Cluster Analysis.....	20-8
20-9	Workbook Wizard: Hierarchy and Dimension to Cluster On.....	20-9
20-10	Workbook Wizard: Select Hierarchy and Dimension to Group By	20-10
20-11	Workbook Wizard: Select Items.....	20-10
20-12	Workbook Wizard: Select Stores.....	20-11
20-13	Workbook Wizard: Select Day	20-11
20-14	Workbook Wizard: Select Configuration Name	20-12
20-15	Generate Clusters Task	20-12
20-16	Workbook Wizard: Select Source Measure for Cluster Analysis.....	20-13
20-17	Workbook Wizard: Hierarchy and Dimension	20-14
20-18	Workbook Wizard: Select Hierarchy and Dimension to Group By	20-15
20-19	Workbook Wizard: Select Items.....	20-15
20-20	Workbook Wizard: Select Stores.....	20-16
20-21	Workbook Wizard: Select Day	20-16
20-22	Workbook Wizard: Set Name and Number of Clusters.....	20-17
20-23	Workbook Wizard: Cluster Run Succeeded	20-18
21-1	Effect Estimation Administration Task.....	21-4
21-2	Workbook Wizard: Select Products	21-4
21-3	Workbook Wizard: Locations	21-5
21-4	Workbook Wizard: Select RHS Products	21-5
21-5	Default Parameters View	21-6
21-6	Cannibalization Parameter Override View.....	21-7
21-7	Halo Parameter Override View	21-8
21-8	Halo Products Mapping View	21-9
21-9	Effect Estimation Review and Approval Task.....	21-10
21-10	Workbook Wizard: Select Products	21-10
21-11	Workbook Wizard: Locations	21-11
21-12	Workbook Wizard: Select RHS Products	21-11
21-13	Workbook Wizard: Select Dates	21-12
21-14	Cannibalization Effects Drive View	21-12
21-15	Cannibalization Effects Percentage View	21-13
21-16	Cannibalization Effects View	21-14
21-17	Cannibalization History Data View	21-15
21-18	Halo Effects Drive View.....	21-16
21-19	Halo Effects Percentage View	21-17
21-20	Halo Effects View.....	21-18
21-21	Halo History Data View.....	21-19
21-22	Cannibalization Statistic Report View	21-20
21-23	Halo Statistic Report View.....	21-21
A-1	Preprocessing for Stock-outs	A-1
A-2	Standard Median Formula.....	A-2
A-3	Standard Median Example	A-2
A-4	Retail Median Formula.....	A-3

A-5	Retail Median Example	A-3
A-6	Standard Exponential Smoothing Formula.....	A-4
A-7	Standard Exponential Smoothing Example	A-5
A-8	Lost Sales Standard Exponential Smoothing Formula	A-6
A-9	Lost Sales Standard Exponential Smoothing Example.....	A-6
A-10	Override Formula	A-7
A-11	Override Example	A-7
A-12	Increment Formula	A-8
A-13	Increment Example.....	A-8

Send Us Your Comments

Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client, Release 14.1.1.

Oracle welcomes customers' comments and suggestions on the quality and usefulness of this document.

Your feedback is important, and helps us to best meet your needs as a user of our products. For example:

- Are the implementation steps correct and complete?
- Did you understand the context of the procedures?
- Did you find any errors in the information?
- Does the structure of the information help you with your tasks?
- Do you need different information or graphics? If so, where, and in what format?
- Are the examples correct? Do you need more examples?

If you find any errors or have any other suggestions for improvement, then please tell us your name, the name of the company who has licensed our products, the title and part number of the documentation and the chapter, section, and page number (if available).

Note: Before sending us your comments, you might like to check that you have the latest version of the document and if any concerns are already addressed. To do this, access the Online Documentation available on the Oracle Technology Network Web site. It contains the most current Documentation Library plus all documents revised or released recently.

Send your comments to us using the electronic mail address: retail-doc_us@oracle.com

Please give your name, address, electronic mail address, and telephone number (optional).

If you need assistance with Oracle software, then please contact your support representative or Oracle Support Services.

If you require training or instruction in using Oracle software, then please contact your Oracle local office and inquire about our Oracle University offerings. A list of Oracle offices is available on our Web site at <http://www.oracle.com>.

Preface

The Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client describes the application's user interface and how to navigate through it.

Audience

This document is intended for the users and administrators of Oracle Retail Demand Forecasting. This may include merchandisers, buyers, and business analysts.

Documentation Accessibility

For information about Oracle's commitment to accessibility, visit the Oracle Accessibility Program website at <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=docacc>.

Access to Oracle Support

Oracle customers that have purchased support have access to electronic support through My Oracle Support. For information, visit <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=info> or visit <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=trs> if you are hearing impaired.

Related Documents

For more information, see the following documents in the Oracle Retail Demand Forecasting Release 14.1.1 documentation set:

- *Oracle Retail Demand Forecasting Installation Guide*
- *Oracle Retail Demand Forecasting Release Notes*
- *Oracle Retail Demand Forecasting User Guide for the RPAS Classic Client*
- *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*
- Oracle Retail Predictive Application Server documentation

The following documentation may also be needed when implementing RDF:

- *Oracle Retail Planning Batch Script Architecture Implementation Guide*

Supplemental Documentation

The following document is available through My Oracle Support at the following URL:

<https://support.oracle.com>

Oracle Retail Demand Forecasting 14.1.1 Cumulative Fixed Issues (Note ID 2000647.1)

This document details the fixed issues and defects for all RDF, Curve, and Grade patch releases prior to and including the current release.

Customer Support

To contact Oracle Customer Support, access My Oracle Support at the following URL:

<https://support.oracle.com>

When contacting Customer Support, please provide the following:

- Product version and program/module name
- Functional and technical description of the problem (include business impact)
- Detailed step-by-step instructions to re-create
- Exact error message received
- Screen shots of each step you take

Review Patch Documentation

When you install the application for the first time, you install either a base release (for example, 14.1) or a later patch release (for example, 14.1.1). If you are installing the base release, additional patch, and bundled hot fix releases, read the documentation for all releases that have occurred since the base release before you begin installation. Documentation for patch and bundled hot fix releases can contain critical information related to the base release, as well as information about code changes since the base release.

Improved Process for Oracle Retail Documentation Corrections

To more quickly address critical corrections to Oracle Retail documentation content, Oracle Retail documentation may be republished whenever a critical correction is needed. For critical corrections, the republication of an Oracle Retail document may at times not be attached to a numbered software release; instead, the Oracle Retail

document will simply be replaced on the Oracle Technology Network Web site, or, in the case of Data Models, to the applicable My Oracle Support Documentation container where they reside.

This process will prevent delays in making critical corrections available to customers. For the customer, it means that before you begin installation, you must verify that you have the most recent version of the Oracle Retail documentation set. Oracle Retail documentation is available on the Oracle Technology Network at the following URL:

<http://www.oracle.com/technetwork/documentation/oracle-retail-100266.html>

An updated version of the applicable Oracle Retail document is indicated by Oracle part number, as well as print date (month and year). An updated version uses the same part number, with a higher-numbered suffix. For example, part number E123456-02 is an updated version of a document with part number E123456-01.

If a more recent version of a document is available, that version supersedes all previous versions.

Oracle Retail Documentation on the Oracle Technology Network

Documentation is packaged with each Oracle Retail product release. Oracle Retail product documentation is also available on the following Web site:

http://www.oracle.com/technology/documentation/oracle_retail.html

(Data Model documents are not available through Oracle Technology Network. These documents are packaged with released code, or you can obtain them through My Oracle Support.)

Documentation should be available on this Web site within a month after a product release.

Conventions

The following text conventions are used in this document:

Convention	Meaning
boldface	Boldface type indicates graphical user interface elements associated with an action, or terms defined in text or the glossary.
<i>italic</i>	Italic type indicates book titles, emphasis, or placeholder variables for which you supply particular values.
monospace	Monospace type indicates commands within a paragraph, URLs, code in examples, text that appears on the screen, or text that you enter.

Introduction

Oracle Retail Demand Forecasting (RDF) is a statistical and promotional forecasting solution. It uses state-of-the-art modeling techniques to produce high quality forecasts with minimal human intervention. Forecasts produced by the RDF system enhance the retailer's supply-chain planning, allocation, and replenishment processes, enabling a profitable and customer-oriented approach to predicting and meeting product demand.

Today's progressive retail organizations know that store-level demand drives the supply chain. The ability to forecast consumer demand productively and accurately is vital to a retailer's success. The business requirements for consumer responsiveness mandate a forecasting system that more accurately forecasts at the point of sale, handles difficult demand patterns, forecasts promotions and other causal events, processes large numbers of forecasts, and minimizes the cost of human and computer resources.

Forecasting drives the business tasks of planning, replenishment, purchasing, and allocation. As forecasts become more accurate, businesses run more efficiently by buying the right inventory at the right time. This ultimately lowers inventory levels, improves safety stock requirements, improves customer service, and increases the company's profitability.

The competitive nature of business requires that retailers find ways to cut costs and improve profit margins. The accurate forecasting methodologies provided with RDF can provide tremendous benefits to businesses.

A connection from RDF to Oracle Retail's Planning and Optimization suite is built directly into the business process by way of the automatic approvals of forecasts, which may then be fed directly to any Planning and Optimization suite application. This process allows you to accept all or part of a generated sales forecast. Once that decision is made, the remaining business measures may be planned within an Planning and Optimization suite application such as Merchandise Financial Planning (MFP).

Forecasting Challenges and RDF Solutions

A number of challenges affect the ability of organizations to forecast product demand accurately. These challenges include selecting the best forecasting method to account for:

- Level
- Trending
- Seasonal demand

- Spiky demand
- Generating forecasts for items with limited demand histories
- Forecasting demand for new products and locations
- Incorporating the effects of promotions and other event-based challenges on demand
- Accommodating the need of operational systems to have sales predictions at more detailed levels than planning programs provide

Selecting the Best Forecasting Method


One challenge to accurate forecasting is the selection of the best model to account for level, trending, seasonal, and spiky demand. Oracle Retail's AutoES (Automatic Exponential Smoothing) forecasting method eliminates this complexity.

The AutoES method evaluates multiple forecast models, such as Simple Exponential Smoothing, Holt Exponential Smoothing, Additive and Multiplicative Winters Exponential Smoothing, Croston's Intermittent Demand Model, and Seasonal Regression forecasting to determine the optimal forecast method to use for a given set of data. The accuracy of each forecast and the complexity of the forecast model are evaluated in order to determine the most accurate forecast method. You simply select the AutoES forecast generation method and the system finds the best model.

Overcoming Data Sparsity Through Source Level Forecasting

It is a common misconception in forecasting that forecasts must be directly generated at the lowest levels (final levels) of execution. Problems can arise when historic sales data for these items is too sparse and noisy to identify clear selling patterns. In such cases, generating a reliable forecast requires aggregating the sales data from a final level up to a higher level (source-level) in the hierarchy in which demand patterns can be seen, and then generate a forecast at this source-level. After a forecast is generated at the source-level, the resulting data can be allocated (spread) back down to the lower level, based on the lower level's (final level) relationship to the total. This relationship can then be determined through generating an additional forecast (interim forecast) at the final level. RDF can be set up to dynamically generate a profile based on the interim forecasts. Also, a non-dynamic profile can be generated and approved in Curve to be used as this profile. It is this profile that determines how the source-level forecast is spread down to the final level. For more information on Curve, refer to [Chapter 15, "Curve Task"](#).

Figure 1–1 Final Level versus Source Level Forecasting



Some high-volume items may possess sufficient sales data for robust forecast calculations directly at the final forecast level. In these cases, forecast data generated at an aggregate level and then spread down to lower levels can be compared to the interim forecasts run directly at the final level. Comparing the two forecasts, each generated at a different hierarchy level, can be an invaluable forecast performance evaluation tool.

Your RDF system may include multiple final forecast levels. Forecast data must appear at a final level for the data to be approved and exported to another system for execution.

Forecasting Demand for New Products and Locations

RDF also forecasts demand for new products and locations for which no sales history exists. You can model a new product's demand behavior based on that of an existing similar product for which you do have a history. Forecasts can be generated for the new product based on the history and demand behavior of the existing one. Likewise, the sales histories of existing store locations can be used as the forecast foundation for new locations in the chain. For more details, refer to the [Forecast Like-Item& Sister-Store Workbook](#) section.

Managing Forecasting Results Through Automated Exception Reporting

The RDF end user may be responsible for managing the forecast results for thousands of items, at hundreds of stores, across many weeks at a time. The Oracle Retail Predictive Application Server (RPAS) provides users with an automated exception reporting process (called Alert Management) that indicates to you where a forecast value may lie above or below an established threshold, thereby reducing the level of interaction needed from you.

Alert management is a feature that provides user-defined and user-maintained exception reporting. Through the process of alert management, you define measures

that are checked daily to see if any values fall outside of an acceptable range or do not match a given value. When this happens, an alert is generated to let you know that a measure may need to be examined and possibly amended in a workbook.

The Alert Manager is a dialog box that is displayed automatically when you log on to the system. This dialog provides a list of all identified instances in which a given measure's values fall outside of the defined limits. You may pick an alert from this list and have the system automatically build a workbook containing that alert's measure. In the workbook, you can examine the actual measure values that triggered the alert and make decisions about what needs to be done next.

For more information on the Alert Manager, refer to the *Oracle Retail Predictive Application Server User Guide*.

Incorporating the Effects of Promotions and Other Event-Based Challenges on Demand

Promotions, non-regular holidays, and other causal events create another significant challenge to accurate forecasting. Promotions such as advertised sales and free gifts with purchase might have a significant impact on a product's sales history, as can fluctuating holidays such as Easter.

Using Promotional Forecasting (an optional, add-on module to RDF), promotional models of forecasting can be developed to take these and other factors into account when forecasts are generated. Promotional Forecasting attempts to identify the causes of deviations from the established seasonal profile, quantify these effects, and use the results to predict future sales when conditions in the selling environment is similar. This type of advanced forecasting identifies the behavioral relationship of the variable you want to forecast (sales) to both its own past and explanatory variables such as promotion and advertising.

Suppose that your company has a large promotional event during the Back To School season each year. The exact date of Back To School varies from year to year, as a result, the standard time-series forecasting model often has difficulty representing this effect in the seasonal profile. The Promotional Forecasting module allows you to identify the Back To School season in all years of your sales history, and then define the upcoming Back To School date. By doing so, you can causally forecast the Back To School-related demand pattern shift.

Managing and Forecasting for Floating Events

For some retailers, an RDF implementation with causal forecasting is necessary. Whenever price discount, marketing information (TV, flyer) or space information (front isle) need to be factored in the forecast, causal forecasting is the right tool.

However, in RDF implementations without the causal capability, some floating events still exist. For instance, an increase in sales leading to Easter will happen even if there is no promotion specifically associated with Easter (chocolate bunnies sell more during Easter even though they are not specifically promoted). And because it does not happen in the same time period every year, the Easter spike will appear 'randomly' any time in March or April. The spike is baked in the seasonality of each item/store, making its prediction, timing and magnitude, inaccurate at best.

RDF is able to handle such situations, not only thru its causal capabilities, but also for baseline forecasting.

To do that, a set of events has to be defined. This usually happens at configuration time. Then, a user has to flag the periods where an event was active in the past (history) and in the future (forecast horizon). Once the dates are set up, the effect of the

event is estimated based on past instances, and applied in the forecast horizon if the flag is active.

For the user interaction, that is the managing the periods when events were active, RDF provides the Floating Event Administration workbook. Its single worksheet lists events and you have the ability to flag periods when certain product/location combinations are active during an event.

53 Week Calendar

For the majority of retailers, the business is managed using a calendar (364 days organized into 13 week quarters) that periodically includes an extra 53rd week so that the year end stays in about the same time of the year. It is useful to have some control over how this 53rd week will be managed within the forecasting system's time dimension. Management of this issue causes customers the pain, time and cost of configuring their data every few years that this happens.

The problem described has two implications. The first case is when two years – each with 52 weeks – of historical sales are available, and the retailer needs to forecast for the following year, which has 53 weeks. The second case is when one of the years of historical sales has 52 weeks, and the other has 53 weeks.

The correction for the extra week happens as part of generate, in particular when the baseline is written out. This is necessary, such that all additional effects (promo, price change, demand transference) are layered on top of the baseline.

The information RDF needs to handle a 53rd week is the name of the measure that indicates which week is the extra week. The measure is loaded or populated through user input, and it is stored in the Forecast Administration parameter called **Extra Week Indicator Data Source**. On the same view (Advanced Final and Source Level Parameters) there is also the measure **Extra Week Interpret Method** that indicates how to calculate the forecast value for a week that was flagged as 53rd or extra week.

Forecasting Returns

RDF has the ability to calculate returns based on the unconstrained demand that it generates. The approach is based on the following assumptions:

- All returned items are re-sellable; in other words there is no damage or decomposition.
- Each week, the return is solely based on a previous week's sale, instead of weighting several weeks.

You need to enable the returns forecast generation, as well as input two parameters:

- The percentage of the merchandise that was returned
- The number of periods, t , from when the merchandise was sold until it was returned.

Given this information, the formula for the returns at time period t , is:

$$\text{Returns}(t) = \text{Forecast}(t - t) * \text{percentage}$$

In [Figure 1-2](#), the time shift is specified as 1 and the return rate is 5%. Given the forecast (Fcst), the returns are calculated as:

$$\text{Returns}(t) = \text{Forecast}(t-1) * 5\%$$

Note: The returns for the first week of forecast are based on the latest week of historical sales (HS), since no previous forecast value is available.

Figure 1–2 Calculating Returns

Logic	HS 107	HS 108	Forecast Start	Week 1	Week 2	Week 3	Week 4	Week 5
Fcst/Sls	50	50		50	80	80	100	60
Return = Fcst _{shifted time} * percentage	NA	NA		2.5	2.5	4	4	5

The parameters are set in the [Forecast Administration Workbook](#) and the [Forecast Maintenance Workbook](#). The returns forecast can be viewed in the [Forecast Approval Workbook](#).

Oracle Retail Demand Forecasting Architecture

This section includes these topics:

- [The Oracle Retail Predictive Application Server and RDF](#)
- [Global Domain Versus Simple Domain Environment](#)

The Oracle Retail Predictive Application Server and RDF

The RDF application is a member of the Planning and Optimization suite, including other solutions such as Merchandise Financial Planning, Item Planning, Category Management, and Advance Inventory Planning. The Planning and Optimization suite applications share a common platform called the Oracle Retail Predictive Application Server (RPAS). RDF leverages the versatility, power, and speed of the RPAS engine and user-interface.

These features characterize RPAS:


- Multidimensional databases and database components (dimensions, positions, hierarchies)
- Product, location, and calendar hierarchies
- Aggregation and spreading of sales data
- Client-server architecture and master database
- Workbooks and views for displaying and manipulating forecast data
- Wizards for creating and formatting workbooks and views
- Menus, quick menus, and toolbars for working with sales and forecast data
- An automated alert system that provides user-defined and user-maintained exception reporting
- Charting and graphing capabilities

More details about the use of these features can be found in the *Oracle Retail Predictive Application Server User Guide* and online help provided within your RDF solution.

Global Domain Versus Simple Domain Environment

A simple domain environment supports isolated partitions of data. This type of environment does not allow for data to be aggregated across partitions into a single view. Whereas a global domain environment allows for data partitions to exist, however, certain data may be edited and viewed across partitions. Within this structure we refer to data within a partition as the Local domain (or sub-domain) and the view to data across multiple local domains as the Master domain. [Figure 1–3](#) represents a global domain environment:

Figure 1–3 Global Domain versus Simple Domain Environment



Within this structure, batch forecast results across all domains may be viewed within the master domain. This is achieved by passing measures with the same forecast birth date (date/time stamp) to each Local Domain when the batch forecast is generated. It is important to note that this cannot be achieved through the use of the [Run Batch Forecast Workbook](#) wizard. The *Oracle Retail Demand Forecasting Implementation Guide* provides more information on execution of batch forecast processes to support a global domain environment.

The RDF solution in a global domain environment also supports centralized administration and maintenance of forecast parameters in the Master domain. Additional details on the availability and limitations of all of the workbooks in the Master domain environment are provided in the following sections.


Oracle Retail Demand Forecasting Workbook Groups

In addition to the standard RPAS Administration and Analysis workbook groups, there are several workbook groups that are associated with the RDF solution which may include: Forecast, Promote, Curve, or any Planning and Optimization suite application (available modules are based upon licensing agreement).

New Items & Locations

The New Items & Locations module consists of the workbooks and algorithms required to clone or copy history and model a new product's demand after an existing product.

Figure 1–4 New Item & Location Taskflow Pane



This module includes the:


- [Product/Location Cloning Administration Workbook](#)
- [Forecast Like-Item& Sister-Store Workbook](#)

For more information on these workbooks and views, refer to [Chapter 4, "Forecast Product/Location Cloning Administration Task"](#) and [Chapter 5, "Forecast Like-Item & Sister-Store Task."](#)

Promotional Planning

The Promotional Planning module consists of the workbooks and algorithms required to perform promotional forecasting, which uses both past sales data and promotional information (for example, advertisements, holidays) to forecast future demand.

Figure 1–5 Promotional Planning Taskflow Pane



This module includes the:

- [Promo Effectiveness - Promotion Results Task](#)
- [Promo Effect Maintenance Task](#)
- [Promotion Management Task](#)
- [Promo Planner Task](#)

For workbooks and views for these tasks, refer to [Promote Tasks, Workbooks, and Views.](#)


Core Forecasting

The Core Forecasting module refers to the primary RDF functionality and consists of the workbooks, measures, and forecasting algorithms that are needed to perform time-series forecasting.

Core Forecasting includes Curve workbooks and batch algorithms that are necessary for the creation, approval, and application of profiles that may be used to spread source-level forecasts down to final levels as well to generate profiles, which may be used in any RPAS solution. The types of profiles typically used to support forecasting are: store Contribution, Product, and Daily profiles. These profiles may also be used to support Profile-Based Forecasting, however; Curve may be used to generate profiles that are used by other Planning and Optimization suite applications for reasons other than forecasting. Profiles Types include Daily Seasonal, Lifecycle, Size, Hourly, and User-Defined profiles.

For more information on the Curve workbooks and views, refer to [Chapter 15, "Curve Task."](#)

Figure 1–6 Core Forecasting Taskflow Pane



This module includes the:

- [Forecast Scorecard Workbook](#)
- [Interactive Forecasting Workbook](#)
- [Forecast Administration Workbook](#)
- [Forecast Maintenance Workbook](#)
- [Preprocess Admin Workbook](#)
- [Preprocess Review and What-if Workbook](#)
- [Floating Events Admin Workbook](#)


- [Extra Week Administration Workbook](#)
- [Profile Administration Workbook](#)
- [Profile Maintenance Workbook](#)
- [Run Batch Forecast Workbook](#)
- [Profile Approval Workbook](#)
- [Forecast Approval Workbook](#)

The Forecast module also includes the batch forecasting routine and all of its component algorithms.

RDF Administration

The RDF Administration module consists of the workbooks and algorithms required to clone or copy history and model a new product's demand after an existing product.

Figure 1-7 *RDF Administration Taskflow Pane*



This module includes the:

- [Alert Thresholds Workbook](#)
- [Forecast Delete Wizard](#)
- [Run Batch Forecast Workbook](#)

Grade

The Grade module consists of the workbooks and wizards that are necessary for clustering. Typically, a retailer may cluster stores over item sales to create logical groupings of stores based upon sales of particular products. This provides increased visibility to where products are selling, and it allows the retailer to make more accurate decisions in merchandising. Beyond this traditional use of clusters, Grade is flexible enough to cluster any business measure based on products, locations, time, promotions, customers, or any hierarchy configured in the solution.

Figure 1–8 Grade Taskflow Pane

This module includes the:

- Breakpoint Administration Workbook
- Generate Breakpoint Grades Wizard
- Generate Clusters Wizard
- Cluster Review Workbook
- Delete Cluster Run Wizard

For more information on the Grade workbooks and views refer to [Chapter 20, "Grade Task."](#)

Cross Promo Effect Module (CPEM)

The Cross Promo Effect Module consists of the workbooks and algorithms that perform data mining which determines promotional Cannibalization, or Halo relationships, or both between items or groups of items.

Figure 1–9 CPEM Taskflow Pane

This module includes the:

- Effect Estimation Administration Task
- Effect Estimation Review and Approval Task

For more information on the CPEM workbooks and views, refer to [Chapter 21, "Cross Promotional Effects Module \(CPEM\)."](#)

RDF Solution and Business Process Overview


Oracle Retail has designed a forecasting solution separate from replenishment, allocation or planning. In order to provide a single version of the truth, it is crucial to free up your time and supply the tools to focus on the analysis of forecast exceptions, historical data, and different modeling techniques. This empowers you to make better decisions, thus improving overall accuracy and confidence in the forecast downstream.

RDF and the Oracle Retail Enterprise

Within the Oracle Retail Enterprise, Oracle Retail Merchandising System (RMS) supplies RDF with Point-of-Sale (POS) and hierarchy data that is used to create a forecast. Once the forecast is approved, it is exported to RMS in order to calculate a recommended order quantity. Forecasts can also be utilized (no export process required) in any RPAS solution to support merchandise, financial, collaborative, and price planning processes.

Figure 1–10 illustrates an overview of RDF and the Oracle Retail Enterprise.

Figure 1–10 RDF and the Oracle Retail Enterprise



RDF Primary Workflow

There are a number of core super-user/end-user forecasting steps in the RDF workflow that are essential for producing accurate forecasts for the millions of item and location combinations that exist in a domain.

RDF Batch Flow Process

RDF’s batch flow process follows six phases as shown in [Figure 1–11](#).

Figure 1–11 *Batch Flow Process in RDF*



This chapter provides a brief description of how to get started using RDF on the RPAS Fusion Client. It includes the following sections:

- [Before you Begin](#)
- [Logging into RDF](#)
- [Taskflow Pane](#)
- [Opening a Workbook](#)
- [Deleting a Workbook](#)
- [Permissible File Names](#)
- [Renaming a Workbook](#)
- [Understanding the Workbook Wizard Window](#)
- [Accessing Online Help](#)
- [Logging Out of RDF](#)

Before you Begin

Note: Before you log on to the RPAS Fusion Client, ensure that your system meets the recommended configuration. For more information, refer to the *Oracle Retail Predictive Application Server Installation Guide*.

Once you check the configuration, obtain the following information:

- Uniform Resource Locator, URL – Enter the URL or the Web address of the application in the Web browser to access the application. For example:
`http://<fullyqualifieddomainname>:<port>/aip`
- User name, Password, and Profile Name – Based on the tasks you want to perform, obtain a user account (that includes user name and password) to log on to the application.

Logging into RDF

To log on to the RPAS Fusion Client, follow these steps:

1. Start a supported browser such as IE, Firefox, or Chrome.

2. In the **Address** bar, enter the RPAS Fusion Client URL and press **Enter**. The RPAS Fusion Client Login page opens, as shown in [Figure 2-1](#).


Figure 2-1 RPAS Fusion Client Login Page



3. On the **Login** page, enter your Username and Password, and select your domain from the **Profile** drop-down list.


Note: If you have accessed the RPAS Fusion Client through a single sign-on environment such as the Oracle Retail Workspace portal, then only the profile field appears on the RPAS Fusion Client login page. Select your domain from the drop-down list, as shown in [Figure 2-2](#).

Figure 2-2 RPAS Fusion Client Login Page, Accessed Through SSO



4. Click **Login**. The window refreshes and the homepage of the RPAS Fusion Client is shown.

Figure 2–3 RPAS Fusion Client Home Page



Taskflow Pane

The taskflow pane opens on the left of your window and enables you to easily navigate through the activities in the application. It provides a pre-configured business workflow organized into expandable and collapsible activities, tasks, and steps.

Note: The taskflow pane also opens when you log on to the application.

Each activity consists of more than one task, and each task may consist of one or more steps. In the RPAS Fusion Client, each solution (spanning across multiple workbooks) is represented as a set of activities, tasks, and steps.

Note: The taskflow is configured for your domain during implementation. For more information on this configuration, refer to the *Oracle Retail Predictive Application Server Configuration Tools User Guide*.

Figure 2–4 shows an example of an RPAS solution configured with activities, tasks, and steps:

Figure 2–4 Illustration of Activity, Task, and Step



In the RPAS Fusion Client, the workflow shown in [Figure 2–5](#) opens in the following manner:

Figure 2–5 Taskflow Pane



When you are working with a specific step, a left arrow icon appears in the taskflow pane, indicating the current step and your position in the workflow.

The Create New Workbook, Open Latest Workbook, and Show List of Workbooks icons that appear next to each task or step enable you to create new workbooks or open existing workbooks. You can find more information on creating new workbooks and opening existing workbooks in the section [Opening a Workbook](#).

[Figure 2–6](#) illustrates the icons that appear in an RPAS taskflow.

Figure 2–6 Icons in the Taskflow Pane




Table 2–1 describes the icons that appear with all the entries in the taskflow.

Table 2–1 Description of Icons in the Taskflow Pane

Legend	Icon Name	Description
A	Activities	These tabs represent the predefined activities of the application.
B	Tasks	These are individual tasks within an activity. Tasks that have a workbook associated with them display a clipboard icon.
C	Steps	One or more steps make up each task.
D	Current Position Icon	Indicates the current step and your position in the workflow.
E	Create a New Workbook	Click this icon to create a new workbook. The new workbook wizard associated with the relevant task opens.
F	Open the Latest Workbook	Click this icon to view the latest workbook (associated with the relevant task/step) you worked on.

Table 2–1 (Cont.) Description of Icons in the Taskflow Pane

Legend	Icon Name	Description
G	Show List of Workbooks	Click this icon to view a list of all workbooks (associated with the relevant task/step) accessible to you. The Open Workbook window opens with a list of accessible workbooks. If you do not own any workbooks, a message appears allowing you to view all workbooks. In case there are no workbooks associated with the task/step, created by you or by someone else, a message appears that allows you to create a new workbook.
H	Collapse/Restore Icon	Click this icon to collapse or restore the taskflow pane. This allows you to view more content in the Contents area.
I	Dynamic Task	A dynamic task is a task that has been defined in the taskflow file but does not have a workbook associated with it. Dynamic tasks display a clipboard with a lightning bolt icon.

Access Based Visibility

The activity and tasks that appear in the taskflow pane are access-based. Depending upon the security settings, you may not have access to some tasks or activities. Access to a task is defined by whether you have access to the workbook that the task is assigned to.

The access to the workbook is maintained in the Security Administration step. Refer to the *Oracle Retail Predictive Application Server Administration Guide for the Fusion Client* for more information about the Administration activity. If you do not have access to a workbook, then you are not able to build the workbooks for the associated tasks and steps.

Hiding specific tasks or activities based on user access is configurable. In the configuration, a task can be set to either hidden or disabled. If it is hidden and you do not have access to it, then the task is not displayed. If it is disabled and you do not have access, then the task is displayed but the links to access the workbooks are disabled. For more information, refer to the *Oracle Retail Predictive Application Server Configuration Tools User Guide*.

Switching Between Multiple Tasks

When working within multiple steps or tasks, all changes you make in a specific step are maintained when you move to a step in the same task or a different task associated with the same workbook. In this case, you do not need to save your work when you switch between tasks within the same workbook.

If you switch to a task that is associated with a different workbook, you are prompted to save or discard the changes before opening or building a new workbook. To save your changes, use the Save As dialog box.

Opening a Workbook


After you log on to the application, a taskflow pane opens that enables you to navigate through the activities and tasks associated with your user account.

Note: This procedure outlines the basic steps for creating a new workbook. For detailed information about building specific RDF workbooks, refer to the specific chapter for that workbook in this guide.

To open a workbook:


1. On the taskflow pane, click the **Show List of Workbooks** icon next to the task or step you want. For more information on the taskflow pane, refer to the section [Taskflow Pane](#).

Figure 2–7 Show List of Workbooks Icon



The Open Workbook window opens.

Figure 2–8 Open Workbook Window



2. Select the workbook you want and click **Open Workbook**.


Deleting a Workbook

From the list of workbooks, you can delete any workbook you have write access to.

To delete a workbook:

1. On the Open Workbook window, select the workbook you want.
To delete more than one workbook, hold down the **Ctrl** key and select the workbooks you want to delete. Or, you can hold down **Shift** and select a group of workbooks.
2. Click **Delete**. A warning message appears.

Figure 2–9 Delete Warning Message



3. Review the warning message and then click **Delete** to delete the workbooks or click **Cancel** to cancel this operation.

Permissible File Names

When saving a workbook (or saving a copy using the **Save As** command), there are restrictions on the length of the file name and the characters that can be used,

- The file name can be a maximum of 32 characters.
- The filename can contain the following standard characters:
 - a - z
 - A - Z
 - 0 - 9
- The filename can contain the following special characters:
 - .
 - |
 - _
 - -
 - /
 - \$
 - &
 - spaces

Any file name not meeting these conditions results in an error message.

Renaming a Workbook

The new workbook wizard also enables you to rename existing workbooks without affecting the data within the workbook or the other workbook information such as the created date, modified date, formatting information, and so on.

There are a few key points to know about renaming workbooks:


- You can only rename workbooks that you have write access to.
- Workbook names can be no more than 32 characters.

- Workbook names cannot contain double or single quotation marks.
- Workbooks cannot be named *Untitled*. This name is reserved.

To rename a workbook in the new workbook wizard, perform the following steps:


1. Select the workbook you want to rename from the list. When selected, it becomes shaded, as shown in [Figure 2–10](#).
2. Click **Rename**.

Figure 2–10 Renaming a Workbook




3. The Rename Workbook dialog box appears. Enter the new name of the workbook and click **OK**.

Figure 2–11 Rename Workbook Dialog Box



4. The renamed workbook appears in the workbook list.

Figure 2–12 Renamed Workbook



You can also rename a workbook from the File menu.

Understanding the Workbook Wizard Window

Figure 2–13 highlights the various components of the workbook wizard window.

Figure 2–13 Workbook Wizard




Table 2–2 describes the components of the workbook wizard window.


Table 2–2 Workbook Wizard Window User Interface Components

Legend	Window Area Name	Position	Description
A	Available Items area	Center Left	Displays the positions that are available for you to select.
B	View menu	Center Left, within the Available Items area	Provides options for viewing the available positions. You can adjust the column setting, detach the list to view it in a larger window, expand or collapse the positions, or scroll to the beginning or end of the list.
C	Dimension menu	Center Left, within the Available Items area	Opens the Dimension options window where you can select the levels of the dimension you want to view in the Available Items list. You can also select the attributes that you would like to see and sort by in the list.
D	Find field, Previous and Next arrows	Center Left, within the Available Items area	Enables you to identify the positions with the keywords you entered in the Find field. Use the Previous and Next arrows to navigate between the workbooks matching the search pattern. The search is not case-sensitive.
E	Wizard Taskflow	Top Center	Displays the steps in the wizard process and shows you where you are within that process. The wizard taskflow is configured in the RPAS Configuration Tools. For more information, refer to the <i>Oracle Retail Predictive Application Server Configuration Tools User Guide</i> .
F	Selected Items area	Center Right	Displays the positions you selected. It also includes a toolbar that enables you to perform various functions.
G	Load Favorite icon	Center Right, within the Selected Items area	Enables you to select a previously saved group of positions to load into the workbook.
H	Save Favorite icon	Center Right, within the Selected Items area	Enables you to save the positions you have selected as group. The next time you build a new workbook, you can select and load that group rather than choosing the same positions individually again.
I	Add and Add All icons	Center	Enables you to add positions that are selected in the Available Items area. To add all positions in the Available Items area, click the Add All icon.
J	Remove and Remove All icons	Center	Enables you to remove positions in the Selected Items area. To remove all positions in the Selected Items area, click the Remove All icon.
K	Wizard Navigation icon	Bottom Right	Enables you to navigate from one wizard page to another. Once you have made the selections for the workbook and clicked Finish , the workbook builds with the selected positions.
L	Synchronize Hierarchies check box	Bottom Left	When selected, the shown levels within the Selected Items area match the ones in the Available Items area. This is selected by default.

Accessing Online Help


To access online help, click **Help** in the global header.

Figure 2–14 Online Help Link



The online help opens in a new browser window. If more than one help set is available, you can choose which one to view by selecting it from the Book drop-down field. If there is only one help set, the field is shaded.


Figure 2–15 Online Help Window, Book Field



Contents

The contents of the online help set are shown in the Contents section of the navigation bar on the left. Click the **Expand** icon next to the folders to drill down to the help topics. Click the page that you want to view. It appears in the content area.


Figure 2–16 Help Topic within Online Help



Figures and Tables

To view a list of figures or tables, click the **Figures** or **Tables** bar.


Figure 2–17 Online Help: Figure List



Index

In the Index, you can enter keywords to find topics that contain this keyword. Click the topic name to see the page.


Figure 2–18 Online Help: Index



Search

Use the Search field at the top of the online help window or the Search section within the navigation bar to search for words or phrases.

Figure 2–19 Online Help: Search



Logging Out of RDF

To log out of the application, click **Logout** in the global header.

Figure 2–20 Logout Link



Note: You may be prompted to save and commit the workbook data before logging out of the application.

Oracle Retail Demand Forecasting Methods

This chapter discusses the forecasting methods used in Oracle Retail Demand Forecasting in detail.

Forecasting Techniques Used in RDF

RDF uses a variety of predictive techniques to generate forecasts of demand. The technical methods used are driven by the goal to provide the most accurate forecasts possible in an automatic and efficient manner. These methods have been analyzed, optimized, and refined over years of research on retail-specific data.

The primary techniques RDF uses include:

- [Exponential Smoothing](#)
- [Regression Analysis](#)
- [Bayesian Analysis](#)
- [Prediction Intervals](#)
- [Automatic Method Selection](#)
- [Source Level Forecasting](#)
- [Promotional Forecasting](#)

Exponential Smoothing

Exponential smoothing models fit basic features of the demand pattern such as level, trend, and seasonality, and project these into the future. These models provide computational benefits and have been chosen for their ability to handle different types of time series, including short and/or noisy series that are characteristic of retail sales. They are smoothing models because they use weighted averages on historic data. They are exponential smoothing models because the weighting uses decays at an exponential rate. That is, more recent data is weighted more heavily than the past.

Regression Analysis

Regression analysis is another standard technique used in prediction. Regression uses a least-squares estimator to fit a model of predictor variables to another set of target variables. Seasonal Regression is an Oracle Retail specific extension of this procedure for use in seasonal models with between one and two years of history. Causal Forecasting uses stepwise regression to determine which causal variables are significant.

Bayesian Analysis

Bayesian analysis considers *a priori* information as a starting point in development of a prediction. Bayesian forecasting, as developed by Oracle Retail, uses a sales plan as the starting point that is adjusted based on observed data. This method fills a gap in standard time series forecasting when new, short lifecycle or products with significant lifecycles are being forecast.

Prediction Intervals

Predictions from these various models gives the estimated mean outcome. By using standard statistical distributional assumptions, RDF develops measures of uncertainty associated with forecast point estimates from these models. While this is of key concern for various optimization solutions of the forecast, the technical details are beyond the scope of this document. For further details on prediction interval calculations, refer to *Char&Yatfield, International Journal of Forecasting, March 1992*.

Automatic Method Selection

Providing multiple forecasting methods is only valuable if the appropriate model can be selected in an accurate and efficient manner. In order to make this feasible in a retail environment, Oracle Retail has developed a number of different meta-methods that can automatically select the best method among a number of competing models. Automatic Exponential Smoothing (AutoES) is an example of one such method that clients can select. The final selection between the competing models is made according to a performance criterion that involves a trade-off between the model's fit over the historic data and its complexity. A description of the competing models used within AutoES is described in "[Exponential Smoothing \(ES\) Forecasting Methods](#)" on page 3-8. In academia, this discipline is known as Information Theory and is used in the combination and selection of various competing models.

Source Level Forecasting

Sometimes it is difficult to capture seasonality, trend, or causal effects on the final-level (item/store) due to scarcity of the data. Also, time series are often too noisy at that level. To overcome these issues, RDF utilizes source-level forecasting. In source-level forecasting, data is aggregated first to a higher level across the product or location hierarchy (or both). Then the forecast is generated and proportionally spread down to the final-level. We have experimentally proven that source-level forecasting technique often improves the accuracy on the final-level.

Promotional Forecasting

In some instances, especially in retail, pure time series techniques are inadequate for forecasting demand. Instead of using only historic demand patterns to forecast future demand, additional causal or promotional factors are used to better explain past performance. With the help of a promotional calendar, an indication of when promotions is run in the future, these promotional forecasting techniques can better predict demand in the future.

Time Series (Statistical) Forecasting Methods

This section describes those techniques within RDF that generate forecasts directly from only a single time series. Generally the time series provided is past sales history for a given item/store that is used to predict what future demand might be. In actual

practice these algorithms have been and can be used to forecast a myriad of different data streams at any product/location level (shipment data at item/warehouse, financial data at dept./chain, and so on).

The following topics present fundamentals of the RDF statistical forecasting processes. Included is a discussion of the importance of confidence intervals and confidence limits, the time series methods used to generate forecasts, and how the best forecasting method is selected from a list of candidate models.

A wide variety of statistical forecasting techniques are available, ranging from very simple to very sophisticated. All of these methods attempt to best capture the statistical probability distribution previously discussed, and they do this by fitting quantitative models to statistical patterns from historical data. Put simply, the better the history of the variable being forecast, the stronger these statistical patterns are. Increased forecast accuracy depends on the strength of these patterns in relation to background irregularities.

RDF is able to use several time series methods to produce forecasts. Time series methods extrapolate features from the past (in this case, past sales data) to the future. The time series methods that the system offers include:

- [Average](#) (Simple Moving Average)
- [Bayesian Information Criterion \(BIC\)](#)
- [Exponential Smoothing \(ES\) Forecasting Methods](#) - Automatic Exponential Smoothing (AutoES)
 - [Simple Exponential Smoothing](#)
 - [Croston's Method](#)
 - [Simple/Intermittent Exponential Smoothing](#)
 - [Holt Exponential Smoothing](#)
 - [Multiplicative Winters Exponential Smoothing](#)
 - [Oracle Winters](#)
 - [Oracle Winters Decomposition](#)
 - [Winters Standard](#)
 - [Winters Responsive](#)
 - [Additive Winters Exponential Smoothing](#)
 - [Seasonal Exponential Smoothing \(SeasonalES\)](#)
 - [Seasonal Regression](#)

Why Use Statistical Forecasting?

The purpose of statistical forecasting is to make the process of predicting future events both objective and quantitative. Statistical forecasting utilizes information from the past (such as sales data) to predict what will happen in the future. Forecast accuracy depends on the degree to which a mathematical model can detect and extract statistical patterns from historic data. The most common statistical methodologies used are univariate. This means that they are based solely on the history of one variable, such as sales. Each forecast observation reflects a future value of the sole input variable. Statistical forecasting processes are relatively easy to implement, and the better the historical data, the better the resulting forecasts.

Businesses benefit greatly from the use of systematic statistical forecasting techniques that aim to accurately predict product demand, enabling these businesses to maintain sufficient product inventory levels. When inventory levels are optimized, lost sales due to product stock-outs are greatly reduced, as are the costs incurred by overstocking.

Average

A simple moving average forecast involves taking the average of the past n time periods and using that average as the forecast for all future time periods (where n is the length of fitting period). Simple moving average forecasts are frequently used in the system because they:

- Make few assumptions about the historical time series.
- Can be generated with little historical data.
- Are very fast to generate.

Typically, moving average forecasts are generated at the final forecast level (for example, item/store) and their results used to spread more sophisticated higher-level forecasts (for example, those generated with exponential smoothing).

A Simple Moving Average model assumes that historical data is too short or noisy to consider seasonal effects or local trend and is based on the level of the series. Since this model does not use a smoothing parameter to place added weight on more recent historic values, a Simple Moving Average model is not actually in the exponential smoothing family. However, it is an adequate model to use when low-level (final forecast) ratios are needed for RDF's spreading of high-level (aggregate) forecasts. That is, when aggregate forecasts can be calculated for long and less noisy aggregate time series, Simple Moving Average models provide an adequate (and computationally quick) forecast to determine the ratios needed for RDF spreading. User input in overriding the automatic training horizon further enhances the simple robustness of this model for base-level data.

Bayesian Information Criterion (BIC)

Within AutoES, the model that minimizes the Bayesian Information Criterion (BIC) is selected as the final model. The BIC criterion attempts to balance model complexity with goodness-of-fit over the historical data period (between history start date and forecast start date). The BIC criterion rewards a model for goodness-of-fit and penalizes a model for its complexity. The complexity penalty is necessary to avoid over fitting.

There are various equivalent versions of the Bayesian Information Criterion, but RDF minimizes the following:

$$BIC = s \cdot n^{k/2n}$$

where n is the number of periods in the available data history, k is the number of parameters to be estimated in the model (a measure of model complexity), and s is the root mean squared error computed with one-step-ahead forecast errors resulting from the fitted model (a measure of goodness-of-fit). Note that since each member of the model candidate list is actually a family of models, an optimization routine to select optimal smoothing parameters is required to minimize s for each model form (that is, to select the best model).


Within RDF, a few modifications to the standard selection criteria have been made. These include reducing the number of parameters the Winter's model is penalized by discounting seasonal indices that have little impact on the forecast (multiplicative indices close to one (1), additive indices close to zero (0)). These changes tend to favor the seasonal models to a slightly higher degree that improves the forecasts on retail data, especially for longer forecast horizons.

AutoES Flowchart

The following procedure outlines the processing routine steps that the system runs through to evaluate each time series set to forecast using the AutoES method. Refer to [Figure 3-1, "AutoES Flowchart"](#).

1. Filter all leading zeros in the input data that is within the training window.
2. Does the time series contain the minimum data points to qualify to forecast using the Croston's method? If yes, generate the forecast and statistics using the Croston's method and move on to the next time series. If no, move on to Step 3.
3. Does the time series contain enough relevant data to generate a forecast? If yes, generate a forecast and statistics using the SimpleES method and move on to Step 4. If no, do not forecast and go to the next time series.
4. Does the time series contain the minimum data points to qualify to forecast using the Holt method? If yes, generate a forecast and statistics using the Holt method and move on to Step 5. If no, move on to Step 9.
5. Does the time series contain more than 52 weeks of input data? If yes, generate a forecast and statistics using the Seasonal Regression method and move on to Step 6. If no, move on to Step 9.
6. Does the time series contain the minimum data points to qualify to forecast using Winters methods? If yes, move on to Step 7. If no, move on to Step 9.
7. Does the time series contain any data point with sales equal qualify to forecast using Additive Winters method? If yes, generate the forecast and statistics using the Additive Winters method and move on to Step 9. If no, move on to Step 8.
8. Does the time series qualify to forecast using the Multiplicative Winters method? If yes, generate the forecast and statistics using both the Additive Winters and Multiplicative Winters methods and move on to Step 9.
9. Compare all candidate forecasts using BIC Criterion.
10. Return the corresponding forecast and statistics for the system-selected forecast method and move on to the next time series.

Figure 3–1 AutoES Flowchart



Automatic Forecast Level Selection (AutoSource)

This section describes how the automatic forecast level selection (AutoSource) could help improve the accuracy of your forecasts.

In the system, one of the key elements to producing accurate forecasts is using the system's ability to aggregate and spread sales data and forecasts across the product and location hierarchies. Low selling or relatively new products can use aggregated data from similar products/locations at a higher level in the hierarchy, generate forecasts using this data, and then spread these higher level forecasts back down to provide more accurate forecasts. The difficulty comes in deciding which products/locations will benefit from this technique and from what level in the hierarchy these source-level forecasts should be spread.

The Automatic Forecast Level Selection feature of the system automates the selection of best aggregation level (forecast source-level) for each product/location combination. While providing invaluable information regarding the best aggregate level for source forecasts, the Automatic Forecast Level Selection process may be very CPU intensive. To solve this problem, the task of selecting best aggregation levels for product/location combinations is decomposed and processed piecemeal during times when the computer would normally be idle.

Identifying the best aggregation levels for sets of products and locations can be divided into a number of sub-problems:

- Forecasting
- Determining the best source-level forecast
- Status and scheduling


The Forecast Level Selection Process

The automatic source generation level selection subsystem selects the best source generation level for each product/location in a given final forecast level. In order to determine the best level, a final forecast is generated for each product/location using each candidate source generation level. As illustrated in [Figure 3–2](#), a final forecast is generated by:

1. Aggregating up from the base level to the source-level
2. Generating a source-level forecast
3. Spreading the source-level forecast down to the final-level

For example, assume base-level sales data is at the item/store level, the final forecast level is at the item/store level, and the candidate source generation level is at the style/store level. In this case, base-level sales data is aggregated from the item/store level up to the style/store level. A style/store forecast is generated, and the forecast data is spread back down to the item/store level. This forecast represents the final forecast.

Figure 3–2 Forecast Level Selection Process



Determining the Best Source Level Forecast

The selection of the best level is based on a train-test approach. In this process, historical data is used to generate a forecast for a test period for which actual sales data already exists. The forecast, generated over the train period, can be compared to

the actual sales figures in the test period to calculate the Percent Absolute Error (PAE) between the two.

A final-level forecast is generated for each product/location combination using each potential source generation level. Each time a source-level forecast is generated, a PAE is calculated for that level. If that PAE is better than the current best PAE (corresponding to the current best source generation level), the source generation level that generated that better PAE becomes the new best level.

Status and Scheduling

Identifying the best aggregation level for a given set of products and locations may take a significant amount of time (that is, an amount of time that is greater than the duration of the computer's shortest idle period). This task, however, can be partitioned meaning that the problem of selecting the best aggregation levels can be decomposed into smaller sub-problems to be solved piecemeal during times when the computer would normally be idle.

For each product/location combination at the final forecast level, the problem consists of:

- Generating forecasts at each unique aggregation level
- Using the train-test approach to evaluate the percent absolute error statistics for each

One or more of these subtasks is performed during each period that the computer is idle. The best aggregation status keeps track of which sub-problems have been performed and which sub-problems remain. In this way, when the best aggregation procedure is run, the procedure knows what the next sub-problem is.

Best aggregation level procedures are run during idle computer periods. The scheduling of the Automatic Forecast Level Selection process (AutoSource) must be integrated with the schedules of other machine processes. In general, you should select a schedule so that source generation-level selection does not conflict with other activities. The following is an example of a typical schedule for the Automatic Forecast Level Selection process: Monday through Thursday, the selection process starts at midnight and runs for eight hours. On Friday and Saturday, the process is allowed to run for 20 hours. Sunday is reserved for generating forecasts.

Using the System-Selected Forecast Level

You have the option of accepting the system-generated source-level selection or manually selecting a different source-level to be used. The value for the source forecast level can be manipulated in the Final Level view of the Forecast Maintenance workbook. For each product/location combination, the best source forecast level identified by RDF appears in the Optimal source-level measure on this view. You can enable the use of this level by placing a check mark in the Pick Optimal Level measure for that product/location. The absence of a check mark in this measure causes the system to default to the Default Source level or the Source Level Override value if this has been set by you.

Exponential Smoothing (ES) Forecasting Methods

The primary process by which RDF automatically fits an exponential smoothing model to a time series is called Automatic Exponential Smoothing (AutoES). When AutoES forecasting is chosen in RDF, a collection of candidate models is initially considered. The models in the candidate list include:

- [Simple Exponential Smoothing](#)

- Croston's Method
- Simple/Intermittent Exponential Smoothing
- Holt Exponential Smoothing
- Multiplicative Winters Exponential Smoothing
 - Oracle Winters
 - Oracle Winters Decomposition
 - Winters Standard
 - Winters Responsive
- Additive Winters Exponential Smoothing
- Seasonal Exponential Smoothing (SeasonalES)
- Seasonal Regression

These models include level information, level and trend information, and level, trend and seasonality information, respectively. The optimal smoothing parameters for each model form are determined automatically (that is, greater smoothing is applied to noisier data). The final selection between the resulting models is made according to a performance criterion that involves a trade-off between the model's fit over the historic data and its complexity.


The amount of available historic information can affect the complexity of the model that can be fit. For example, fitting a seasonal model would not be appropriate without a complete year of historic data. In fact, one prefers to see each season occur multiple times. For a particular series, even if the amount of available history allows one to fit a complex model (that is, one with seasonal components), the resulting model is not necessarily superior to a simpler model. If a simpler model (for example, a model with only a level component or level and trend components) fits as well as a seasonal model, the AutoES forecasting process finds the simpler model to be preferable. In such a case, the simpler model captures the basic features supported by the data without over fitting and therefore generally projects better forecasts.

Simple Exponential Smoothing

Simple Exponential Smoothing does not consider seasonality or trend features in the demand data (if they exist). It is the simplest model of the exponential smoothing family, yet still adequate for many types of RDF demand data. Forecasts for short horizons can be estimated with Simple Exponential Smoothing when less than a year of historic demand data is available and acts-like associations are not assigned in RDF.

Figure 3–3 is an example of a forecast in which data seems to be un-trended and un-seasonal; note the flat appearance of the forecast.

Figure 3–3 Simple Exponential Smoothing



Croston's Method


Croston's method is used when the input series contains a large number of zero data points (that is, intermittent demand data). The method involves splitting the original time series into two new series:

- Magnitude series
- Frequency series

The magnitude series contains all the non-zero data points, while the frequency series consists of the time intervals between consecutive non-zero data points. A Simple Exponential Smoothing model is then applied to each of these newly created series to forecast a magnitude level as well as a frequency level. The ratio of the magnitude estimate over the frequency estimate is the forecast level reported for the original series.

Figure 3–4 shows a sales history of data where the demand for a given period is often zero.

Figure 3–4 Croston's Method



Simple/Intermittent Exponential Smoothing


This method is a combination of the SimpleES and Croston's (IntermittentES) methods. The SimpleES model is applied to the time series unless a large number of zero data points are present. In this case, the Croston's model is applied.

Holt Exponential Smoothing

Holt exponential smoothing treats data as linearly trended but non-seasonal. The Holt model provides forecast point estimates by combining an estimated trend (for the forecast horizon - h) and the smoothed level at the end of the series. RDF uses a damped Holt model that decays the trend component so that it disappears over the first few weeks. This improves forecasts created using Holt over longer forecast horizons.

When this forecasting method is selected, the forecasts are seen as trending either up or down, as shown in [Figure 3-5](#).

Figure 3-5 Holt Exponential Smoothing



Multiplicative Winters Exponential Smoothing

RDF now offers a choice of four different forecasting approaches within the Multiplicative Seasonal Forecasting Method.

The Winter's forecasting approaches, including the current seasonal approach, are:

- Oracle Winters (current or default approach)
- Oracle Winters Decomposition
- Winters Standard
- Winters Responsive

All four approaches use the same calculation for arriving at forecasts.

Overall, a forecast point estimate is evaluated as:

$$\hat{Y}_t(h) = \left(L_t + \left[\sum_{i=1}^h \varphi^i \right] T_t \right) \hat{S}_t(h),$$

a function of level, trend, seasonality, and trend dampening factor.

Winters Standard and Winters Responsive both use a basic Winter's method:

The Level at the end of the series (time t) is:

$$L_t = \alpha \frac{Y_t}{S_{t-p}} + (1 - \alpha)(L_{t-1} + T_{t-1})$$

The Trend at the end of the series (time t) is:

$$T_t = \gamma(L_t - L_{t-1}) + (1 - \gamma)T_{t-1}$$

The Seasonal Index for the time series (applied to the forecast horizon) is:

$$S_t = \delta \frac{Y_t}{L_t} + (1 - \delta)S_{t-p}$$

The difference between the two approaches is how these values are optimized within the optimization routine.

Oracle Winters and Oracle Winters Decomposition use a Winters-based decomposition approach to update the level, trend, and Seasonal Indexes. Each of these methods calculates initial seasonal indices from a baseline Holt forecast. Seasonal indices, level, and trend are then updated in separate stages, using Winter's model as a basis for the updates. The difference between the two approaches is which parameters are optimized and in which stages seasonal indices are updated.

Oracle Winters

Oracle Winters is the current seasonal forecasting approach, which uses a combination of Winters approach and decomposition. Decomposition allows level and trend to be optimized independently while maintaining a seasonal curve.

From sufficient data, RDF extracts seasonal indexes that are assumed to have multiplicative effects on the de-seasonalized series.

Note: The component describing the de-seasonalized values, which is multiplied by the seasonal index:

$$\hat{S}_t(h)$$

is the Holt model previously described.

In this case, three parameters are used to control smoothing of the components of level, trend, and seasonality.

Oracle Winters Decomposition

Like the Oracle Winters seasonal forecasting approach, Oracle Winters Decomposition uses a combination of Winters approach and decomposition.

From sufficient data, RDF extracts seasonal indexes that are assumed to have multiplicative effects on the de-seasonalized series.

Note: The component describing the de-seasonalized values, which is multiplied by the seasonal index:

$$\hat{S}_i(h)$$

is the Holt model previously described.

The key difference between Oracle Winters and Oracle Decomposition is that the Seasonal smoothing parameter is also optimized, and the calculation of Seasonal Indices and de-seasonalizing of data is done with in the optimization routine for Oracle Winters Decomposition.

Also, the optimization routine with in Oracle Winters Decomposition, while minimizing forecast errors, tends to weigh more recent Forecast errors heavier.

As with Oracle Winters, three parameters are used to control smoothing of level, trend, and seasonality.

Key differences between Oracle Winters and Oracle Winters Decomposition include:

- Seasonal smoothing factor is optimized.
- The optimization places more importance on recent sales than historical sales.
- Seasonal indices are recalculated based on optimization.

When this forecasting approach is selected, the forecasts tend to be more responsive to recent changes in levels while maintaining a substantial seasonal component.

Winters Standard

The Winters Standard uses a standard Winters model, with no additional calculations. All three smoothing parameters are optimized here.

Initial Seasonal Indices are set to one. Initial level and trend are calculated from average selling levels over initial periods. The optimization routine chooses optimal level, trend, and smoothing parameters that minimize Forecast Errors in the fit region. All forecast errors within the fit region are weighed equally.

Seasonal Indices, level, and trend are calculated based on the optimal values of level, trend, and Seasonal Smoothing parameters:

$$\alpha, \gamma, \delta$$

When this forecasting approach is selected, the forecasts tend to be responsive to changes in levels. In cases where there is no obvious correlation in seasonality from period to period or where there are significant changes in level, these forecasts may generate smoother, less seasonal forecasts.


Winters Responsive

Winters Responsive is similar to Winters Standard except the Optimization routine, while minimizing forecast errors, weighs more recent Forecast errors heavier. Winters Responsive, like Standard Winters, optimizes all three smoothing parameters.

When this forecasting approach is selected, the forecasts tend to be more responsive to recent changes in levels. In cases where there are significant shift in levels, resulting in high responsiveness to levels, these forecasts tend to be smoother, with less seasonality.

When the Multiplicative Seasonal forecasting method is selected, the forecasts tend to look squiggly, as shown in [Figure 3-6](#).

Figure 3-6 Multiplicative Winters Exponential Smoothing



Additive Winters Exponential Smoothing

RDF now offers a choice of four different Forecasting approaches within the Additive Seasonal Forecasting Method.

The Winters forecasting approaches, including the current seasonal approach, are:

- Oracle Winters (current or default approach)
- Oracle Winters Decomposition
- Winters Standard
- Winters Responsive

All four approaches use the same calculation for arriving at forecasts.

Overall, a forecast point estimate is evaluated as:

$$\hat{Y}_t(h) = L_t + \left[\sum_{i=1}^h \varphi^i \right] T_t + \hat{S}_t(h)$$

a function of level, trend, seasonality and trend dampening factor.

Winters Standard and Winters Responsive both use a basic Winter's method.

The Level at the end of the series (time t) is:

$$T_t = \gamma(L_t - L_{t-1}) + (1 - \gamma)T_{t-1}$$

and the Trend at the end of the series (time t) is:

$$T_t = \gamma(L_t - L_{t-1}) + (1 - \gamma)T_{t-1}$$

and the Seasonal Index for the time series (applied to the forecast horizon) is:

$$S_t = \delta(Y_t - L_t) + (1 - \delta)S_{t-p}$$

The difference between the two approaches is how these values are optimized within the optimization routine.

Oracle Winters and Oracle Winters Decomposition use a Winters-based decomposition approach to update the level, trend, and seasonal indexes.

Refer to Multiplicative Winters Exponential Smoothing in this document for a description of each of the forecasting approaches.

Seasonal Exponential Smoothing (SeasonalES)

A combination of several seasonal methods. This method is generally used for known seasonal items or forecasting for long horizons. This method lets the Multiplicative Seasonal and Additive Seasonal models compete and picks the one with the better fit. If less than two years of data is available, a Seasonal Regression model is used. If there is too little data to create a seasonal forecast (in general, less than 52 weeks), the system selects from the Simple ES, Trend ES, and Intermittent ES methods.

Seasonal Regression

A common benchmark in seasonal forecasting methods is sales last year. A sales last year forecast is based entirely on sales from the same time period of last year. Forecasting using only sales last year involves simple calculations and often outperforms other more sophisticated seasonal forecasting models. This method performs best when dealing with highly seasonal sales data with a relatively short sales history.

The seasonal models used in earlier releases of RDF (Additive and Multiplicative Winters) were designed to determine seasonality. However, they were not designed to work with sales histories of shorter than two years. Because sales histories of longer than two years are often difficult to obtain, many retail environments need a seasonal forecast that can accommodate sales data histories of between one and two years. In addition, the Additive and Multiplicative Winters models search for short-term trends and have difficulties with trends occurring inside the seasonal indices themselves.

The current RDF Seasonal Regression forecasting model is designed to address these needs.

The Seasonal Regression Model uses simple linear regression with last year's data as the predictor variable and this year's sales as the target variable. The system determines the multiplicative and additive weights that best fit the data on hand. When optimizing the Seasonal Regression Model, the sales last year forecast is inherently considered, and it will automatically be used if it is the model that best fits the data. If there have been significant shifts in the level of sales from one year to the next, the model learns that shift and appropriately weigh last year's data (keeping the same shape from last year, but adjusting its scale).

As with other seasonal models, you can forecast demand for products with insufficient sales histories using this method if:

- You paste in fake history as needed, providing a seasonal profile for the previous year.
- You also forecast for a source-level (with the same seasonality profile as the forecast item and with more than one year of history) using seasonal regression and spread these forecast results down to the member products.

The Seasonal Regression Model is included in the AutoES family of forecasting models and is thus a candidate model that is selected if it best fits the data.

This method captures the trend of a series through the slope of the regression line while the series shifted by a cycle provides its seasonal profile. Using this method, the resulting forecast for the original series is calculated. The regression method provides a much better forecast of the series than was possible with the other exponential smoothing algorithms.

Based on the assumptions of the model that this method is trying to describe, versus the noisy data it is likely to receive, several exceptions to this regression technique are caught and corrected. First, since it is logically impossible to receive a negative value for the slope (such a value suggesting an inverse seasonality), whenever a negative slope is detected, the regression is rerun with the intercept fixed to zero. This guarantees that a positive slope is calculated and thus a more logical forecast is given.

The second noise-driven concession is to check the slope to determine if it is either too slight or too great. If this is the case, the method rejects itself out of hand and allows one of the other competing methods to provide the forecast.

Profile-Based Forecasting

The Profile-based forecasting method generates a forecast based on a seasonal profile. The profile may be loaded, manually entered, or generated by Curve. It can also be copied from another profile and adjusted.

Forecast Method

The Profile-based forecasting method proceeds as follows:

1. The historical data and the profile are loaded.
2. The data is de-seasonalized using the profile and then fed to Simple method.
3. The alpha is capped by 0.5.
4. The Simple forecast is re-seasonalized using the profiles.

Profile-Based Method and New Items

The Profile-based forecasting method can be successfully used to forecast new items. In order to do that, we need to have a profile (which can be copied from an item that shares the same seasonality) and a number that specifies the de-seasonalized demand (DD value). The forecast is calculated using the DD value multiplied by the profile. The confidence interval is set to 1/3 of the DD value.

If the DD value is used to forecast, the history (if it exists) of the product is ignored. Once we have enough history (number of data points exceed a global parameter), the forecast stops using the DD value, and it defaults to the normal Profile Based method.

Note: The Profile-based forecasting method is intended for a final forecasting level and not a source level.

Bayesian Forecasting

The Bayesian Forecasting method is based on combining historic sales data with sales plan data. It is especially effective for new products with little or no historic sales data.

Your sales plan can incorporate expert knowledge in two ways — shape and scale.

- Shape is the selling profile or lifecycle that can be derived from a sales plan. For example, the shape for certain fashion items might show sales ramping up quickly for the first four weeks and then trailing off to nothing over the next eight weeks.
- Scale, or magnitude, of a sales plan is the total quantity expected to be sold over the plan's duration.

Bayesian Forecasting assumes that the shape that sales takes is known, but the scale is uncertain. In Bayesian Forecasting, when no sales history is available, the sales forecast figures are equal to the sales plan figures. At this point, there is no reason to mistrust the sales plan. As point-of-sale data becomes available, the forecast is adjusted and the scale becomes a weighted average between the initial plan's scale and the scale reflected by known sales history. Confidence in the sales plan is controlled by the amount of sales data on hand and a Bayesian sensitivity constant (Bayesian Alpha), which you can set between zero and infinity.

Unlike standard time series forecasting, which requires only sales history to produce a forecast, Bayesian Forecasting requires a sales plan and sales history (if available). Because of this difference, Bayesian Forecasting is not included in AutoES. You must select it manually as a forecasting method in Forecast Administration or Forecast Maintenance.

Obtaining accurate short life-cycle product forecasts is very difficult, and standard statistical time series forecasting models frequently do not offer an adequate solution for many retailers. The following are major problems in automatically developing these forecasts:

- The lack of substantial sales history for a product (which especially makes obtaining seasonal forecasts very difficult).
- The difficulty of automatically matching a new product to a previous product or profile.
- The inability to include planners' intuition into a forecasting model. For example, the overall sales level of the product, how quickly the product takes off, how the product's sales is affected by planned promotions.

Using a Bayesian approach, a short life-cycle forecasting algorithm was developed that begins with a product's seasonal sales plan (that is developed externally to the system by the planner).

As sales information arrives during the first few days or weeks of the season, the model generates a forecast by merging the information contained in the sales plan with the information contained in the initial sales data. These forecast updates can be critical to a company's success and can be used to increase or cancel vendor orders.

As forecasting consultants and software providers, Oracle Retail assists clients in obtaining good forecasts for future demands for their products based upon historical sales data and available causal information. Depending on the information available, Oracle Retail's software supports various forms of exponential smoothing and regression-based forecasting. Frequently, clients already have some expectations of future demands in the form of sales plans. Depending on the quality of their plans, they can provide very useful information to a forecasting algorithm (especially when only limited historical sales data is available). A forecasting algorithm was developed

that merges a customer's sales plans with any available historical sales in a Bayesian fashion (that is, it uses new information to update or revise an existing set of probabilities).

Sales Plans versus Historic Data

In most retail situations, clients are interested in obtaining good product forecasts automatically with little or no human intervention. For stable products with years of historic sales data, our time series approaches (Simple, Holt, Winters, Regression based Causal, and so on) produce adequate results. The problem arises when attempting to forecast products with little or no history. In such instances, expert knowledge (generally in the form of sales plans) is required. Given that both sales plans and time series forecasts are available, an obvious question exists: When should the transition from sales plan to time series forecasting occur? In answering that question (in a particular scenario), suppose that we have determined that 13 weeks of history is the transition point. Does that mean that at 12 weeks the time series results are irrelevant and that at 14 weeks the sales plan has no value? Our intuition tells us that instead of a hard-edge boundary existing, there is actually a steady continuum where the benefits from the sales plan decrease as we gather more historic sales data. This was the motivation for developing an approach that would combine the two forecasts in a reasonable manner.

Bayesian Algorithm

Bayesian forecasting is primarily designed for product/location positions for which a plan exists. These product/locations can be, but are not limited to: items new in the assortment, fashion items, and so on. The following guidelines should be followed:

1. No more than one plan should exist for a given product/location position. If multiple plans are to be set up for different time periods, the domain should be set up with different forecasting levels for each time period of interest.
2. Any time period with non-zero Actuals for a given product/location position should have a corresponding plan component. Otherwise, the system assumes a plan exists and equals zero and acts accordingly.
3. The time period of interest for the Bayesian algorithm starts with the first non-zero value of the plan or the history start date (whichever is more recent), and ends at the end of the forecast horizon.

LoadPlan Forecasting Method

LoadPlan Forecasting Method copies the measure that was specified as Data Plan in the [Forecast Administration Workbook](#) into the Forecast measure. This method does not generate confidence and cumulative intervals when it is the final level method and no source level is specified. This method only generates confidence and cumulative intervals when a source level is specified and the source and final levels are the same.

Copy Forecasting Method

Copy Forecasting Method copies the measure that was specified as Forecast Data Source in the [Forecast Administration Workbook](#) into the Forecast measure. This method does not generate confidence and cumulative intervals.

Causal (Promotional) Forecasting Method

Causal, or promotional, forecasting requires four input streams:

- Time Series Data
- Historical Promotional Calendar
- Baseline Forecasts
- Future Promotional Calendar

Promote decomposes the problem of promotional forecasting into two sub-tasks:

- Estimating the effect that promotions have on demand
- Applying the effects on the baseline forecasts

To accomplish the first task, a stepwise regression sub-routine is used. This routine takes a time series and a collection of promotional variables and determines which variables are most relevant and what effect those relevant variables have on the series.

A promotion variable can represent an individual promotion or a combination of overlapping promotions. An individual promotion represents the case where for a particular time period a single promotion is enabled. Overlapping promotions represents the case where there are two or more promotions that happen at the same time period at the same location for the same product. Causal Forecasting Method can calculate not only each individual promotion effect, but also the overlapping promotions effects.

Thus, the output from the algorithm is a selection of promotional variables and the effects of those variables on the series. In the second step, knowing the effects and the baseline forecasts, we can generate a promotional forecast by applying the effects wherever the promotion or the overlapping promotion are active in the future.

The causal forecasting process has been simplified by first estimating the effects of promotions. Then the effects are applied on top of a baseline that is created externally from the causal forecasting process. For example, the baseline can be a loaded measure, or it can be generated in RDF using AutoES and source-level techniques.

It should be noted that just because promotional forecasting is selected, it does not necessarily imply that a promotional forecast results. In some instances, no promotional variables are found to be statistically significant. In these cases, the forecast ends up equivalent to standard time series forecasts.

If you want to force certain promotional variables into the model, this can be managed through forecasting maintenance parameters.


The Oracle Retail experience in promotional forecasting has led us to believe that there are a few requirements that are necessary to successfully forecast retail promotions:

- Baseline forecasts need to consider seasonality; otherwise normal seasonal demand is attributed to promotional effects.
- Promotional Effects need to be able to be analyzed at higher levels in the retail product and location hierarchies. This produces cleaner signals and alleviates issues involved in forecasting new items and new stores and issues involving data sparsity.
- Users need to be aware that the forecasting models cannot tell the difference between causal effects and correlated effects. What this means is that users should be wary of promotional effects attributed to an event that occurs at the same time every year. The system cannot distinguish between the promotional effect and the normal seasonality of the product. The same can be said for any two events that

always occur at the same time. The combined effect is most likely attributed to one or the other event.

Causal Forecasting with Baselines

Rather than use a sales history that may not have sufficient or accurate data, users can load a baseline into the RDF Causal Engine instead. Baselines are often generated using data that is rolled up to a higher dimension than item/store, providing a greater depth of data and hence a less-noisy sales history. The sales data used to generate the baseline can be corrected for out-of-stock, promotional, and other short-term event information using Preprocessing. These baselines are then spread back to the item/store level and then loaded in the RDF Causal Engine. The Engine uses the baseline along with the historic promotional data and future planned promotions data to create the system forecast, which is the baseline with the lifts, which were calculated from the promotional data, applied on top.

Figure 3–7 Baseline Process

Causal Forecasting Using the Baseline Process

When a baseline is used, the AutoES binary code executes in the following manner:

1. The binary reads the history of the time series.
2. The binary reads the type of each promotional variable into the system.
3. The binary reads in all the promotional variables that apply to the series.
4. The binary creates an internal promotional variable to allow the modeling of trend.
5. Promotional variables, internal promotional variables, promotional variable types, and the series itself are passed to the stepwise regression routine, with the historic data serving as the dependent variables.

6. If the regression finds no significant promotional variables, the casual method is considered to have failed to fit. In this case, the forecast equals the baseline.
7. The fit at time t , $fit(t)$, is defined in terms of b_o , the intercept of the regression, b_1 , the effect corresponding to promotional variable i , and $p_i(t)$, is the value of promo variable I , in time t as:
$$fit(t) = b_o + \sum b_o * p_i(t)$$
8. The forecast is obtained by re-causalizing the baseline. This is done by adding back the causal effects for the product/location/time positions, where the corresponding promo variables are on in the forecast region.
9. The binary writes the winning promotional variables effects back to the database.
10. The selected model is recorded in the database.
11. The binary records the forecast and the baseline in the database.

Causal Forecasting for Short-lifecycle Items

To forecast short-lifecycle promotional items, Causal deprices, depromotes, and smoothes the forecasting data source to generate the short lifecycle forecast causal baseline. In essence, this is the causal forecasting process where the generation of the baseline and the estimation of the promotional lifts are modified for items with short lifecycle.

First, the baseline is generated. Then the forecast data source is depriced, depromoted and smoothed. The resulting feed is aggregated and then spread down using rate of sales as a profile to create a lifecycle curve. The lifecycle curve is shifted and stretched or shrunk to fit the new season length. This curve represents the pre-season baseline forecast. In season, the pre-season forecast serves as a forecast plan to the Bayesian forecasting method. The Bayesian forecast is the causal baseline for short lifecycle items. The next step is to calculate the promotional lifts.

To do this, the promotional lifts are filtered from the historical sales and applied on top of the item's rate of sale. The resulting measure is regressed against the promotional variables to determine the promotion effects. Finally, the promotion effects are applied on top of the short-lifecycle causal baseline to generate the final forecast.

Causal Forecasting at the Daily Level

The causal forecasting at the daily level is calculated by spreading the weekly causal forecast down to day. The spreading utilizes causal daily profiles, thus obtaining a causal forecast at the day granularity.

The daily casual forecast process executes in the following manner:

1. Preprocess the day-level promotional variables by multiplication with daily profiles. Aggregate the preprocessed continuous day level promotional variables to the week level.
2. Calculate the causal forecast at the weekly level. Set promotional effects if desired. Use the RDF causal engine to generate the forecast.
3. Calculate the multiplicative promotional effects at the item/store level for every promo variable. The effects can be either:
 - Manually preset (See Step 1).
 - Calculated. When calculating the causal forecast, the calculated causal effects are written back to the database. If the effects are calculated at higher level

than item/store, the effects are replicated down to item/store since the effects are multiplicative. If source-level forecasting is used and causal method is used both at the source-level and at the final-level, the effects from the final-level is used.

4. Daily profiles are calculated using the Curve module. Since as much history as possible is used and is averaged over seven days, it's assumed that these profiles are de-causalized. The de-causalized daily profiles capture the day-of-week effect and should be quite stable.
5. Causal effects are applied to the daily profiles. The profiles are multiplied by the causal effects and then the profiles have to renormalize.

Example

For every item/store combination, calculate a normal week-to-day profile based on historic data. Note that this profile is already computed for spreading the weekly forecasts to the day level. Suppose for a certain product, the profile is as follows:

Mon	Tues	Wed	Thu	Fri	Sat	Sun	Week
10%	10%	10%	10%	20%	30%	10%	100%

Suppose that in the past, the promotion was held on Wednesday, Thursday, and Friday of week w6:

Mon	Tues	Wed	Thu	Fri	Sat	Sun
		P	P	P		

Then the continuous weekly indicator for this promotion in w6 should be set to 0.4, which is the sum of the weights of Wednesday, Thursday, and Friday.

Now assume that the same promotion is held in a future week (w36), but only on Thursday:

Mon	Tues	Wed	Thu	Fri	Sat	Sun
			P			

Then the continuous weekly indicator for w36 should be set to 0.1, which is the weight of Thursday only.

The approach to use the continuous promotion indicators to generate an accurate causal forecast at the day level is as follows:

- Calculate the weekly multiplicative effect for the promotion using the standard causal forecasting system with continuous indicators.
- Calculate the forecast for w36 using the standard causal forecasting system with continuous indicators.
- Update the week-to-day profile of w36 so that the weight of Thursday is doubled (the multiplicative factor is 2):

Mon	Tues	Wed	Thu	Fri	Sat	Sun	Week
10%	10%	10%	20%	20%	30%	10%	110%

- Normalize the profile for w36:

Mon	Tues	Wed	Thu	Fri	Sat	Sun	Week
9%	9%	9%	18%	18%	27%	9%	100%

Finally, spread the forecast of w36 using the normalized profile.

Final Considerations About Causal Forecasting

In the Oracle Retail approach to causal forecasting, the causal effects are obtained by fitting a stepwise linear regression model that determines which variables are most relevant and what effect those relevant variables have on the series. The data used to fit the regression is the fit history of each time series, so basically a model is fit per time series. A problem arises due to potential lack of significant data (that is, when a promotional variable is not represented in the history, but it is present in the forecast region). In that case, the effect for that variable would not be computed at all, thus affecting the accuracy of the forecast. There are a few solutions that make use of the effects from other similar time series. One solution would be to do source-level causal forecasting and then spread down to the final-level.

This would be equivalent to using the effects at the source-level for time series that have no causal variable instances in the history. This has a serious conceptual drawback. By aggregating the promotional variables at the source-level, we would force the effects on the other time series in the same aggregation class that would otherwise not have the causal variables on at the same time. An alternate solution is whenever a causal effect cannot be computed because of lack of significant data. An averaged effect from another time-series in the same aggregation class is going to be used instead. Refer to [Table 6-2, "Promo Effect Types"](#) for information on the Override Higher Level type.

Forecast Product/Location Cloning Administration Task

The Product/Location Cloning Administration task allows you to specify parameters to clone or copy history for new items or locations from existing items and locations. Since RDF needs history for forecasting, this functionality allows you to specify clone items and clone stores for these new Product/Locations.

Cloning is different from Like-item/Sister-Store functionality. Like-item/Sister-Store functionality copies forecasts or history of the Like-item or Sister-Store as the forecasts for the new SKU/store. However, in cases where the two items have different promotion calendars, it is necessary to forecast based on history data and promotion calendar. Item/Location Cloning functionality facilitates this process.

Also, by copying history from the parent product, you can start forecasting almost immediately after the launch of the new product.

Product/Location Cloning Administration can be performed from the Master or Local domain. The actual cloning or copying of history can be performed as part of batch run.

Note: Clone is available as a special expression that can be configured to be called as a batch run to perform the actual copying of history.

When the Cloning administration task is built in the Master domain, if clone assignments are made such that a product is assigned a clone that belongs to a different local domain, then at the time of batch run RDF does not clone that specific product and continue processing after logging a message.

Note: This task is only valid at final-levels. Therefore, this task may include hierarchy dimensions that are at higher positions than item or store (for example, subclass or region).

Using Product and Location Cloning

This section describes examples of cloning as illustrated in [Figure 4-1](#).


An owner of multiple stores is opening a new store (Store N) and wants to replicate some of the items (#1-5) from an established store (Store A) to the new store (Store N).

Location cloning occurs when the owner clones the same items (#1-2) from Store A to Store N.

Product cloning occurs when the owner clones a similar item (#3) to (#5) from within Store N.

Product and location cloning occurs when the owner clones a similar item from Store A (#5) to Store N (#4).

Figure 4–1 Cloning Examples



Product/Location Cloning Administration Workbook

To build the Product/Location Cloning Administration workbook, perform these steps:


1. Click the New Workbook icon in the Product/Location Cloning Administration task in the New Item & Locations activity.

Figure 4–2 New Item & Locations Task




2. The Workbook wizard opens. Select the products you want to work with and click **Next**.

Figure 4–3 Workbook Wizard: Select Product



3. Select the locations you want to work with and click **Finish**.

Figure 4–4 Workbook Wizard: Select Locations




The Product/Location Cloning Administration workbook is built.

Adjustment Parameters View

The Adjustment Parameters view allows you to specify parameters that determine how much the cloned history is adjusted to match the level of the actual sales.

Figure 4–5 Adjustment Parameters View



Measures: Adjustment Parameters View

The Adjustment Parameters view contains the following measures:

Cloned History Adjustment - Alpha (Range 0-1)

This parameter is used to calculate the ratio that is applied to the cloned history. If this parameter is close to zero (0), then the cloned sales will be scaled so that they are aligned with the sales level. If this parameter is close to one (1), then little scaling of the cloned history will occur.

Cloned History Adjustment - Recent Sales Threshold

This parameter represents a specific number of periods. If it is less than the number of periods from the first sale date to the current date, then the cloned history is adjusted. If it is greater than the number of periods from the first sale date to the current date, then no adjustment is made to the cloned history.

Cloned History Adjustment - Calculation Window Length

This parameter is the number of periods that are considered when adjusting the cloned history.

Figure 4–6 Adjustment Ratio Formula

$$\text{adjustment ratio} = \left(\frac{\text{sum of first } M \text{ periods of sales}}{\text{sum of last } M \text{ periods of cloned history}} \right)^{(1-\alpha)}$$

Figure 4–7 Cloned History Formula

$$\text{cloned history} = \text{adjustment ratio} * \text{unadjusted cloned history}$$


Location Cloning View

Location Cloning view allows you to make clone Location assignments for new Locations. Location Cloning view allows you to specify up to three Clone Locations for a given Location that is being cloned. Also, it allows you to specify different parent

Locations for different products. For example, the Beverly Hills store sells like the Miami store for swimwear and sells like the New York store for electronics. The Location Cloning view thus is at Location and Product intersection.

You have the ability to specify associated contributions for each of the Parent Locations and have the ability to specify an overall Adjustment Ratio.

Figure 4–8 Location Cloning View



Location Clone 1	
Location Clone 2	
Location Clone 3	
Location Clone Contribution 1	0.00
Location Clone Contribution 2	0.00
Location Clone Contribution 3	0.00
Clone Location Adjustment Ratio	1.00

Measures: Location Cloning View

The Location Cloning view contains the following measures:

Location Clones

Location Clone1, Location Clone 2, Location Clone 3

Parent Locations for the new Location being cloned. It is optional to specify more than one parent clone. The selection or assignment of Location Clone is made by clicking this measure, and a Single Hier Select wizard opens. Assignments are made by selecting a Location and clicking **OK**. Refer to the *Oracle Retail Predictive Application Server User Guide* for more details on the Single Hier Select wizard.

Location Clone Contributions

Location Clone Contribution1, Location Clone Contribution2, Location Clone Contribution3

Relative contributions of all Clone Locations. If user does not specify contributions, but makes selections for Location Clones and commits the changes, at the time of commit the contributions are calculated to have equal weights for all specified Location Clones. If user specifies contributions, at the time of commit, Location clone contributions get normalized so that they add up to one (1). Location Clone contributions with no associated Location Clone values get set to zero at the time of commit.

Clone Location Adjustment Ratio

You may enter an Adjustment Ratio to apply to the cloned history of the new location. This is a real number between [zero (0), infinity). The default (NA) value is 1.00 (in other words 100%), which translates to no adjustment.

Example 4–1 Clone Location Adjustment Ratio

If demand for a new store is expected to be 30% greater than its clone store, the Adjustment Ratio would be set to 1.30. If demand for a new store is expected to be 30% less than its clone store, the Adjustment percent would set to 0.70.

Note: Adjustment Ratios and Clone Contributions specified in the Product Cloning and Location Cloning views are used together while evaluating the result for a given item/store.

Example 4–2 Adjustment Ratios and Clone Contributions

SKU1	
SKU2	SKU3
20%	80%
Adjustment Ratio = 1	


STR1:	
STR2	STR3
50%	50%
Adjustment Ratio = 0.5	
The contributions are calculated as:	
SKU2/STR2 at 5% (=20% x 0.5x50%), SKU2/STR3 at 5%,SKU3/STR2 at 20%(=80%x0.5x50%),SKU3/STR3 at 20%	

Product Cloning View

The Product Cloning view allows you to make Clone Product assignments for new Products. From this view, you can specify up to three parent Products for a given Product that is being cloned. Also, it allows you to specify different parent Products for different Locations. For example, CS Spring Water 1 sells like Diet Soda single in North America, but sells like Regular Soda in Asia. The Product Cloning view thus is at Product and Location intersection.

You have the ability to specify associated contributions for each of the Clone Products and have the ability to specify an overall Adjustment Ratio.

Figure 4–9 Product Cloning View



Measure	Value
Product Clone 1	10000016Leather Loafer - Black 9 B
Product Clone 2	
Product Clone 3	
Product Clone Contribution 1	0.00
Product Clone Contribution 2	0.00
Product Clone Contribution 3	0.00
Clone Product Adjustment Ratio	1.00

Measures: Product Cloning View

The Product Cloning view contains the following measures:

Product Clones

Product Clone1, Product Clone 2, Product Clone 3

Parent Products for the new Product being cloned. It is optional to specify more than one product clone. The selection or assignment of product clone is made by clicking this measure, and a Single Hier Select wizard opens. Assignments are made by selecting a product and clicking OK. Refer to the *Oracle Retail Predictive Application Server User Guide* for more details on the Single Hier Select wizard.

Product Clone Contributions

Product Clone Contribution1, Product Clone Contribution2, Product Clone Contribution3

Relative contributions of all clone products. If user does not specify contributions, but makes selections for product clones and commits the changes, at the time of commit the contributions are calculated to have equal weights for all specified product clones. If user specifies Product clone contributions, they get normalized such that they add up to one at the time of commit. Product clone contributions with no associated product clone values get set to zero at the time of commit.

Clone Product Adjustment Ratio

You may enter an Adjustment Ratio to apply to the cloned history of the new product. This is a real number between [zero (0), infinity]. The default (NA) value is 1.00 (in other words 100%), which translates to no adjustment.

Example 4–3 Clone Product Adjustment Ratio


If demand for a new item is expected to be 30% greater than its clone item, the Adjustment Ratio would be set to 1.30. If demand for a new item is expected to be 30% less than its clone item, the Adjustment percent would set to 0.70.

Clone Mask View

This view allows you to enable cloning for product/locations by setting the Clone Mask measure to True.

Note: Clone Mask measure can also be brought in using the Show/Hide option in the Product Cloning and Location views. The clone mask can also be set based on business rules by configuring RPAS rules.

Figure 4–10 Clone Mask View



Measures: Clone Mask View

The Clone Mask view contains the following measures:

Clone Mask

This measure specifies if cloning should be performed for the item/store combination.

Forecast Like-Item & Sister-Store Task

The Forecast Like-Item & Sister-Store task provides the ability to model a new product's demand after an existing product. Forecasts can thus be generated for the new product based on the selected history or the forecast of the existing product plus an Adjustment Ratio. Likewise, the sales history or the forecast of existing store locations can be used as the forecast foundation for new locations. This task includes the following views:

- [Like-Item View](#)
- [Sister-Store View](#)
- [Advanced Parameter View](#)


Note: This task is only valid at final-levels. Therefore, this task may include hierarchy dimensions that are at higher positions than item or store (for example, subclass or region).

Forecast Like-Item& Sister-Store Workbook

To build the Forecast Like-Item & Sister-Store workbook, perform these steps:


1. Click the New Workbook icon in the Forecast Like-Item & Sister-Store task in the New Item & Locations activity.

Figure 5–1 Forecast Like-Item & Sister-Store Task




2. The Workbook wizard opens. Select the forecast level that you want to evaluate and click **Next**.

Figure 5–2 Workbook Wizard: Forecast Level




3. Select the specific locations that you want to view and click **Next**.

Figure 5–3 Workbook Wizard: Select Locations




4. Select the products you want to work with and click **Next**.

Figure 5–4 Workbook Wizard: Select IProducts



5. Select any additional measures and click **Finish**.


Figure 5–5 Workbook Wizard: Select Extra Measures



The Forecast Like-Item & Sister-Store workbook is built.

Like-Item View

The Like-Item view is used to forecast a new item by modeling it after an existing item.

Figure 5–6 Final Like-Item View

Measures: Like-Item View

The Like-Item view contains the following measure:


Like SKU

The Like SKU field displays the items selected during the wizard process. In the example shown in the [Final Like-Item View](#), the like-item (existing item) is selected on the right from a pick-list across from the new item. The like-item's forecast or sales is used for the new item based on the parameters selecting in the Advance Parameter view. In the previous example, Leather Loafer - Black 8 B is a new item, and Leather Lace-up Boat Shoes 8 B is being selected as the existing item that is used to Leather Loafer - Black 8 B model's forecast.

Note: When working with both the Like SKU and Sister-Store views, making a selection in one of the views requires Calculate to be run before the pick-list options are available in the other view.

Sister-Store View

The Sister-Store view is used to forecast demand for a new store by modeling it after an existing store.

Figure 5–7 Final Sister-Store View

Measures: Sister-Store View

The Sister-Store view contains the following measures:

Sister Store


Displays the locations selected during the wizard process. In the example shown in [Figure 5-7](#), the Sister-Store (existing store) is selected on the right from a pick-list across from the new store. The sister store's forecast or sales is used for the new store based on the parameters selecting in the Advance Parameter view.

Note: When working with both the Like SKU and Sister-Store views, if a selection is made in one of the views, Calculate must be run before the pick-list options are available in the other view.

Advanced Parameter View

The Advanced Parameter view is used to manage item/locations in which the Forecast Start Date, Forecast End Date, or History Start Date varies from the default settings in the [Forecast Administration Workbook](#) and to set the Adjustment Ratio for the new item or location being forecast.

Figure 5-8 Advanced Parameter View



Measures: Advanced Parameter View

The Advanced Parameter view contains the following measures:

Adjustment Ratio

You may enter an Adjustment Ratio to apply to the forecast for the new product/location combination displayed. This is a real number between [zero (0), infinity]. The default (NA) value is 1.00, (in other words 100%) which translates to no adjustment.

Note: If demand for a new item is expected to be 30% greater than its like-item, the Adjustment Ratio would be set to 1.30. If demand for a new item is expected to be 30% less than its like-item, the Adjustment percent would set to 0.70.

Base Rate of Sales

This measure represents the average sales of a new item/store combination. It is used when specifying 'Base Rate of Sales New SKU' as the Substitution Method to create a

forecast for the new item/store combination. The measure can be generated in another application and loaded into RDF, or it can be manually entered by a user.

Forecast Start Date Override

This parameter represents the date to start forecasting for an item/location combination. This parameter can be set in the future if using like-item or Sister-Store functionality, and, upon reaching that time, the forecast is generated. If this date is set to the past, it is ignored in favor of the Forecast Start Date from the [Forecast Administration Workbook](#). This means that the Forecast Start Date for this intersection needs to be edited once it is no longer in the future. For like-item or sister store, the Forecast Start Date and the History Start Date should be set to the same date. It is important to understand how Forecast Start Date should be used in conjunction with Forecast End Date (Refer to the [Forecast End Date Override](#) section). No value is in this measure if the system default set in the [Forecast Administration Workbook](#) is to be used.

Note: This measure can also be set in the [Forecast Maintenance Workbook](#). Changes to this measure can be seen in the Forecast Maintenance task and the [Forecast Like-Item& Sister-Store Workbook](#). The most recent commit (between either of the tasks) is the value used by the system.

Forecast End Date Override

This parameter represents the last point in time for which the Forecasting Engine forecasts for an item/location combination. Should this parameter be set to a date less than the Forecast Start Date plus the Forecast Length (in the [Forecast Administration Workbook](#)), the engine forecasts zero (0) past this date. If Forecast End Date is more than Forecasting Start Date plus Forecasting Length, no forecast is generated outside Forecasting Start Date plus Forecasting Length window. In other words, both Forecast Start Date and Forecasting End Date are relevant for time periods within the forecast horizon set at the global level. No value is in this measure if the system default set in the [Forecast Administration Workbook](#) is to be used.

Forecast End Date can be used for new item or location forecasting if the item or location needs to be forecast for a period shorter than the Like TS Duration (set globally in [Forecast Administration Workbook](#)).

Note: This measure can also be set in the [Forecast Maintenance Workbook](#). Changes to this measure can be seen in the [Forecast Maintenance Workbook](#) and the [Forecast Like-Item& Sister-Store Workbook](#). The most recent commit (between either of the tasks) is the value used by the system.

History Start Date Override

This parameter represents the first point in time from which the Forecasting Engine begins training and modeling (that is, if there are two years of history, but only one year is required, set the start date to a year ago). This parameter overrides at the item/store level from the global settings in the [Forecast Administration Workbook](#). This can be used to level out past sales. For example, if there is a large spike in the first three weeks of sales for an item was on sale, set the Historical Start Date to one week past that period. Those first few weeks are not used when generating the forecast.

It is also important to note that the system ignores leading zeros that begin at the history start date. For example, if your history start date is January 1, 2011 and an item/location does not have sales history until February 1, 2011, the system considers the starting point in that item/location's history to be the first data point where there is a non-zero sales value.

The History Start Date for the new item or new store should be set with the same date as the Forecast Start Date.

Note: When using any of the Lifecycle Methods (refer to [Substitute Methods](#)); the History Start Date for the substitute item or location must be set to the point in the sales history that the new item or location begins using as its sales.

Note: This measure can also be set in the [Forecast Maintenance Task](#) workbook. Changes to this measure can be seen in the [Forecast Maintenance Task](#) workbook and the [Forecast Like-Item & Sister-Store Workbook](#). The most recent commit (between either of the tasks) is the value used by the system.

Substitute Methods

Displays a list from which you can select the substitute method. When a Substitute Method is used to forecast, the method set for an intersection is cleared once the Default Forecast Start Date is greater than the Forecast Start Date Override plus the Like TS Duration for the intersection. Valid options are:

Table 5–1 Substitute Methods for Forecasting

Option	Description
None	There is no substitution for this product/location combination. This is the default value.
Seasonality SKU	You provide a like-item that has a similar seasonality pattern that sells at the same store. The new product's forecast is the like-item's demand forecast with the applied adjustment. The forecast is set to zero (0) for all dates before the new product's start date.
Seasonality Store	You provide a Sister-Store that has a similar seasonality pattern that sells the same product. The product's forecast at the new store is the demand forecast of the same product at the Sister-Store with the applied adjustment. The forecast is set to zero (0) for all dates before the new store's open date.
Seasonality SKU/Store	You provide a like-item that sells at a Sister-Store that has a similar seasonality pattern. The new product's forecast at the new store is the demand forecast of the like-item at the Sister-Store with the applied adjustment. The forecast is set to zero (0) for all dates before the new product's start date after the new store opens.
Lifecycle SKU	You provide a like-item that had a similar lifecycle pattern that sells at the same store. The new product's forecast is the like-items actual sales with the applied adjustment shifted such that the like-item's first sales matches the new product's start date.

Table 5–1 (Cont.) Substitute Methods for Forecasting

Option	Description
Lifecycle Store	You provide a Sister-Store that had a similar lifecycle pattern that sells the same product. The product's forecast at the new store is the products actual sales at the Sister-Store with the applied adjustment shifted such that the sister store's first sales matches the new store's open date.
Lifecycle SKU/Store	You provide a like-item that sells at a Sister-Store that has a similar lifecycle pattern. The new product's forecast at the new store is like-item's actual sales at a Sister-Store with the applied adjustment shifted such that the like-item's first sales at the Sister-Store matches the new product's start date after the new store opens.
Base Rate of Sales New SKU	<p>You provide a base rate of sales for a new item/store combination. The new product's forecast is a combination of the seasonality of the forecast at the corresponding source level and the base rate of sales. Specifically, the formula to calculate the forecast is:</p> <p><i>Forecast at time t = source level forecast at time t divided by the average of the source level forecast times the base rate of sales.</i></p> <p>The base rate of sale is a convenient way to generate (seasonal) forecasts for a new item. No Like item or Clone item is needed. What is necessary is a value for how much the item is selling on average per period. That value works as the interim forecast used to spread the source level forecast down to final level.</p> <p>Because this item is new, the system knows that as you have specified a history start date.</p> <p>The base rate of sale forecast is generated until the TS duration is reached.</p> <p>The TS duration is the difference between forecast start date and history start date.</p> <p>Usually the default history start date is empty, which means it is the beginning of the calendar.</p> <p>If the history start date override is also empty, the forecast start date less the beginning of the calendar (>=2 years) is probably much more than the TS duration, so the item is not considered new.</p> <p>In this case base rate of sales or any new item method, will not work.</p>

Required Steps for Forecasting Using Each of the Like SKU/Sister-Store Methods

To support Like SKU /Sister-Store functionality, the Like TS Duration must be set in the [Forecast Administration Workbook](#) - Advance tab. This parameter sets the number of weeks of history required after which RDF stops using the substitution method and starts using the system forecast generated by the forecast engine.

Procedures

The following procedures outline the steps required for using each of the methods described in [Table 5–1, "Substitute Methods for Forecasting"](#):

Seasonality/SKU

Introduces a new item at an existing store (Like-item with a similar forecast):

1. From the Like-Item view, select a like-item from the list across from the new item.
2. From the Advanced Parameter view, Set the Forecast Start Date for the new item at an existing store.
3. From the Advanced Parameter view, Set the History Start Date for the new item at the existing store to the same date as the Forecast Start Date.

4. From the Advance Parameter view, Set the Adjustment percent (optional) for the new item at the existing store.

Seasonality/STR

Introduces an existing item at a new store (Sister-Store with similar forecast):

1. From the Sister-Store view, Select a Sister-Store from the list across from the new store.
2. From the Advanced Parameter view, Set the Forecast Start Date for the existing item at the new store.
3. From the Advanced Parameter view, Set the History Start Date for the existing item at the new store to the same date as the Forecast Start Date.
4. From the Advance Parameter view, Set the Adjustment percent (optional) for the existing item at the new store.

Seasonality/SKU_STR

Introduces a new item at a new store (Like-item and Sister-Store with a similar forecast):

1. From the Like-Item view, Select a like-item from the list across from the new item.
2. From the Sister-Store view, Select a Sister-Store from the list across from the new store.
3. From the Advanced Parameter view, Set the Forecast Start Date at the intersection of the new item and the new store.
4. From the Advanced Parameter view, Set the History Start at the intersection of the new item and new store.
5. From the Advance Parameter view, Set the Adjustment percent (optional) at the intersection of the new item and new store.

Lifecycle/SKU

Introduces a new item at an existing store (Like-item's sales history to be used as the forecast for the new item):

1. From the Like-Item view, Select a like-item from the drop-down list across from the new item.
2. From the Advanced Parameter view, Set the Forecast Start Date for the new item at the existing store.
3. From the Advanced Parameter view, Set the History Start Date for the new item at the existing store to the same date as the Forecast Start Date.
4. From the Advanced Parameter view, Set the History Start Date for the like-item at the existing store to the point in its sales history that maps to the new item's forecast.
5. From the Advance Parameter view, Set the Adjustment percent (optional) for the new item at the existing store.

Lifecycle/STR

Introduces an existing item at new store (Sister store's sales history to be used as the forecast for the new store):

1. From the Sister-Store view, Select a Sister-Store from the list across from the new store.
2. From the Advanced Parameter view, Set the Forecast Start Date for the existing item at the new store.
3. From the Advanced Parameter view, Set the History Start Date for the existing item at the new store to the same date as the Forecast Start Date.
4. From the Advanced Parameter view, Set the History Start Date at the intersection of the Sister-Store and existing item to the date in its sales history that maps to the new store's forecast.
5. From the Advance Parameter view, Set the Adjustment percent (optional) for the existing item at the new store.

Lifecycle/SKU_STR

Introduces a new item at a new store (Like-item's and sister store's sales history to be used as the forecast for a new item at a new store:

1. From the Like-Item view, Select a like-item from the list across from the new item.
2. From the Sister-Store view, Select a Sister-Store from the list across from the new store.
3. From the Advanced Parameter view, Set the Forecast Start Date at the intersection of the new item and new store.
4. From the Advanced Parameter view, Set the History Start Date at the intersection of the new item and new store to the same date as the Forecast Start Date.
5. From the Advanced Parameter view, Set the History Start Date at the intersection of the Like-item and Sister-Store to the date in its sales history that maps to the new item and new store's forecast.
6. From the Advance Parameter view, Set the Adjustment percent (optional) at the intersection of the new item and new store.

Promote (Promotional Forecasting) Task

This chapter provides an introduction to promotional forecasting and explains how it differs from the traditional statistical forecasting methodology. It discusses the advantages and limitations of both statistical and promotional forecasting models, and it outlines the use of Oracle Retail's Causal method of forecasting demand. It describes terminology used in the context of promotional forecasting, and it concludes with detailed descriptions of the tasks contained in Promote.

About Promote

Promote is an optional add-on automated predictive solution that allows you to incorporate the effects of promotional and causal events (such as radio advertisements and holiday occurrences) into your time-series forecasts. The promotional forecasting process uses both past sales data and promotional information to forecast future demand.

What Is Promotional Forecasting?

Traditional statistical forecasting methods provide significant benefits to the process of forecasting consumer demand because they are good at predicting level, trend, and seasonality based on sales history. The limitation of traditional statistical methods is that they forecast with less accuracy when there are special events that cause significant deviations in selling patterns.

For example, the Easter holiday, for which companies often run promotions, occurs on a different date each year. Traditional statistical forecast methods can identify seasonality in sales history, but this seasonality is based on periodic similarities in the sales pattern. Since Easter occurs on different dates from year to year (that is, its period of recurrence is not regular), manual intervention is required to predict change in demand using the traditional statistical forecasting method. Events like this are called promotion events. Promotion events, such as advertisements, irregularly occurring holidays, competitor information, free gift with purchase offers, and so on are events that drive businesses from the normal selling cycle.

The goal of a promotional forecasting system is to improve time series forecasting by:

- Providing the forecasting system with visibility as to when certain promotion events were active in the past (for example, identifying which weeks of a given year were affected by an Easter promotion).
- Automatically determining the statistical effect, if any, of these events.
- Incorporating significant effects into the future forecasts for time periods also associated with the observed promotion event.

The Promote module combines the automation of statistical time series forecasting with the improved accuracy found in customized causal forecasting. Promote uses both past sales data and promotional information (for example, advertisements, holidays) to forecast future demand. In order to understand the underlying rationale for the promotional forecasting process, it is important to understand the advantages and limitations of its underlying components.

Comparison Between Promotional and Statistical Forecasting

Statistical time series forecasting uses past demand to predict future demand. The most basic component of the time series forecast is the level of sales. This is usually determined by looking at demand in the recent past. There often exists an underlying trend that can be detected within sales history. This is usually determined by looking at the change in demand in the recent past. A third factor influencing retail demand is seasonality. A forecasting algorithm trying to determine the effects of seasonality can only look for periodic similarities in the sales pattern. For example, December sales from previous years can be used to adjust the forecast for December only because December occurs regularly every 12 months. At every step, the time series approach is limited to using historical demand to predict future demand without regard to the underlying causes that are driving demand in the first place.

Promotional events, however, can create problems in estimating level, trend, and seasonality. Certain events, such as irregularly occurring holidays, newspaper/radio advertisements, free gift with purchase offers, and special discounts can cause significant deviations from the selling pattern.

Promotional forecasting, unlike statistical forecasting, attempts to predict future demand by identifying the factors that influence spikes and dips of past demand. Once these factors are known, the magnitude and direction of their effect can be evaluated. Their presence can then be incorporated into forecasting models for use during times when the causal factors are again expected to be present.

Developing Promotional Forecast Methods

This section describes how custom promotional forecast models have been developed in the past, leading to the discovery of several consistent findings. These findings have been incorporated into Oracle Retail's development of the Promote forecasting module.

Promotional forecasting uses promotional factors to predict future demand. The first step is to determine all of the pertinent information affecting sales and transform this information into variables that the system understands. Seasonality, for instance, can be represented by a single seasonal continuous variable, such as the number of daylight hours or average daily temperature.

Alternatively, it can be represented by 12 different indicator variables representing each of the months. An indicator variable consists only of 0's and 1's (1 indicates that the event is on). For example, a monthly indicator variable for January would consist of a 1 during the first month of the year and 0's for the remaining months.

Once a list of variables is determined, the model needs to represent the promotion events in terms of their influence on overall demand. For example, if a set of promotional variables has a multiplicative promotional effect on demand, a log transformation may be needed to improve the model. After a suitable model is developed, it must be implemented using multivariate linear regression or neural network architecture with custom code handling the data loading and variable transformations. The final custom model may be quite accurate over the data set on which it was developed.

However, this model may not be general enough to be used universally across all data sets, thus requiring the development of multiple custom models to cover a client's entire domain. This has been found to be very time consuming and costly.

The process of developing custom promotional models has, however, brought to light a number of consistent patterns:

- Level, trend, and seasonality are universal components of almost any forecast.
- Including a time-series forecast as an input variable often improves promotional models.
- Indicator variables are robust in that they can represent both additive and multiplicative effects.

These findings have led Oracle Retail to develop a novel approach to promotional forecasting that combines the automation and generalization of time series forecasting with the improved (albeit data set specific) accuracy met through customized causal forecasting.

Promotional Forecasting Approach

Oracle Retail combines time series forecast methods with causal forecast methods, resulting in a new forecast method supported by the promotional forecasting module. Promote uses the AutoES method of forecast generation to determine a baseline time series forecast and then uses indicator variables to represent promotional events of interest. By giving the forecasting routine visibility as to when certain events occurred in the past, the system can correlate changes in the sales demand with these events and determine each promotional event's effect on sales. Then whenever these events occur in the future, the promotional effects can be incorporated into the forecast.

The Promotional Forecasting module has been developed to produce generalized promotional models automatically with little human intervention. Combined with the system's ability to allow you to develop your own data loading routines, Promotional Forecasting provides a cost-effective means for producing forecasts using promotional information.

Promotional Forecasting Terminology and Workflow

Promotional Forecasting is designed to produce sales forecasts using both past sales history and event on/off information, both of which you provide. Using the sales data, the system first determines a seasonal time series model to describe the purchasing behavior of consumers. Differences between the seasonal model and the actual sales are then correlated with known events. Events that are found to have a statistically significant impact on sales are then included in a promotional forecast model as promotion events. For each promotion event, its promotion effect on sales is determined. The final promotional model consists of the seasonal model, promotion event on/off information, and each promotion event's resulting effect on sales. By combining these three, a final promotional forecast is computed.

Note: More detailed information on the Causal forecasting algorithm is provided in the [Forecasting Methods Available in RDF](#) section.

Examples of Promotion Events

The following are examples of promotional variables that could be created and the manner in which their associated on/off event status is specified:

Example 6–1 Promotion Event 1

Christmas Day applies to all products/locations. The Christmas promotional variable therefore has only one dimension, Day." Because Christmas Day falls on the 359th day of each non-leap year, the Day359 variable is set to True for every such year (all other days it is set to False).

Example 6–2 Promotion Event 2

A television advertisement is run locally in the New York/New Jersey area for the four weeks at the beginning of the spring fashion season. The TVAD promotional variable has two associated dimensions, State and Week. Week13, Week14, Week15, and Week16 is set to True only for states NY and NJ (all other states/weeks is set to False). Since no product dimension exists, the TV ad is assumed to have an effect on all products.

Example 6–3 Promotion Event 3

A holiday promotion is run involving all sporting goods items for the two weeks prior to Father's Day. The Father's Day promotional variable has two associated dimensions - item and Week. For this year, Week23 and Week24 is set to True only for individual items related to sporting goods items (all other weeks and all other items is set to False). Since no location dimension exists, the Father's Day promotion is assumed to apply to all stores.

After promotional variables have been loaded into RDF, you can use the Promotion Planner task to view, edit, and update associated values without having to reload new data.

Promote Tasks, Workbooks, and Views

The Promote tasks, workbooks and views allow you to manage the promotion events used in the system's promotional forecasting processes, and view/edit the system's analysis of the effects of these events on demand.

Note: External to Promote, the [Forecast Administration Workbook](#) includes several parameters that may be used as additional configuration options for promotional forecasting. For additional information, refer to [Procedures in Promotional Forecasting](#).

Table 6–1 lists the Promote tasks, workbooks, and views in the Promotional Planning activity.

Table 6–1 Promote Tasks, Workbooks, and Views

Task Workbooks	Workbook and Description	Views
Promo Effectiveness - Promotion Results Task	<p>Promo Effectiveness - Promotion Results Workbook</p> <p>Our promotional What-if task. This allows you to analyze the performance of previous promotions and simulate future promotions by editing when promotional events are active for an item/location and by modifying the promotion lift effects.</p>	<p>Promotion Model Type View</p> <p>Promotions View</p> <p>Aggregated Promotion Lift Override View</p> <p>Promotional Forecast View</p> <p>Promotion Parameters View</p>
Promo Planner Task	<p>Promo Planner Workbook</p> <p>Allows you to specify when certain promotional events were active in the past, and when they are active in the future.</p>	<p>Promotions View</p>
Promotion Management Task	<p>Promotion Management Workbook</p> <p>Allows you to enable and disable promotions for causal forecast levels and to specify whether promotions can have a negative effect.</p>	<p>Promo Variable Model Type View</p> <p>Promotion Enable View</p> <p>Accept Negative Lift View</p>
Promo Effect Maintenance Task	<p>Promo Effect Maintenance Workbook</p> <p>Allows you to review the system-calculated promotional lift effects, edit these effects, and determine how changes are factored into the promotional model.</p>	<p>Promotion Parameters View</p>

Promo Effectiveness - Promotion Results Task

The Promo Effectiveness - Promotion Results task is a historical and future view to the effects of a planned promotion.

This task has these views:

- [Promotion Model Type View](#)
- [Promotions View](#)
- [Aggregated Promotion Lift Override View](#)
- [Promotional Forecast View](#)
- [Promotion Parameters View](#)

In this task, you view the promotional forecast. There is also the ability to analyze the effects on the forecast if a promotion does or does not occur. This analysis is performed by turning a promotional event or attribute on or off for dates in the future plans, and/or by modifying the Simulated Effect. This task is intended for simulation and analysis purposes only. There is no Commit functionality.

Note: Changes to the Promo Effectiveness - Promotion Results task cannot be committed back to the master database; however, this task is useful for reporting on the performance of past promotions and simulating the effects of future promotions to support more accurate promotional modeling.

Promo Effectiveness - Promotion Results Workbook

To build the Promo Effectiveness - Promotion Results workbook, perform these steps:


1. Click the New Workbook icon in the Promo Effectiveness - Promotion Results task in the Promotional Planning activity

Figure 6–1 Promo Effectiveness - Promotion Results Task



2. The Workbook wizard opens. Select the causal level and click **Next**.


Figure 6–2 Workbook Wizard: Causal Level



3. Select the promotions to include and click **Next**.


Note: If RDF detects cross-promotional effects for your selected causal level, then RDF uses those promotions and the wizard skips to "[Workbook Wizard: Select Products](#)".

Figure 6-3 Workbook Wizard: Select Promotions




4. Select the products to include and click Next.

Figure 6-4 Workbook Wizard: Select Products




5. Select the locations and click Next.

Figure 6–5 Workbook Wizard: Locations



6. Select the days you want to work with and click **Finish**.

Figure 6–6 Workbook Wizard: Select Calendar Positions




The Promo Effectiveness - Promotion Results workbook is built.

Promotion Model Type View

The Promotion Model Type view allows you to review the model type.

Figure 6-7 Promotion Model Type View



Measures: Promotion Model Type View

The Promotion Model Type view contain the following measures:

Model Type for Promotional Variable

This measure stores the model type for the selected promotion variables. The choices are exponential and linear. An exponential model type is displayed if the promotion type is exponential. A linear model type is displayed when the promotion types are Real or Boolean.


For additional information, see "Promotion Variables" on page 6-17.

Promotions View

The Promotions view allows you to review and enable or disable promotions for item/locations for desired periods. Once the changes in the promo calendar have been made, click Calculate to update the forecast values in the Promotional Forecast view.

The promotions must be enabled for the chosen causal level. Note that multiple Promotions views are possible. Namely, there is one view for every distinct promotion intersection. Promotions with identical intersections are displayed in the same view.

Figure 6-8 Promotions View



Measures: Promotions View

The Promotions view contain the following measure:

Promotion Variables

Promotion Variables are defined as either Boolean, Exponential, or Real types during the configuration process in the Promote Plug-In. Refer to the Oracle Retail Demand Forecasting Configuration Guide for additional details on configuring the Promote solution.

For additional information, see "Promotion Variables" on page 6-17.

Aggregated Promotion Lift Override View

The Aggregated Promotion Lift Override view allows you to review the promotional lift overrides, which can be generated at a low as well as an aggregate level in the hierarchy.

Figure 6–9 Aggregated Promotion Lift Override View

	10/9/2009	10/16/2009	10/23/2009	10/30/2009	11/6/2009	11/13/2009
Aggregated Promotion Lift	0.00	0.00	0.00	0.00	0.00	0.00
Promotional Lift Override 1 -	0.00	0.00	0.00	0.00	0.00	0.00

Measures: Aggregated Promotion Lift Override View

The Aggregated Promotion Lift Override view contains the following measures:

Aggregated Promotion Lift Override

This measure allows you to override (in units) the system generated promotional lift. The override is at an aggregate level and spread down to the forecast level.

Promotional Lift Override

This read-only measure allows you to override (in units) the system generated promotional lift. The override is at the same intersection as the forecast.

This measure can be equal to the [Aggregated Promotion Lift Override](#) or zero (0). It is generated based on the Aggregated Promotion Lift Override and the Apply Promotion Lift Override Indicator. If the indicator is set to *True* (which applies the override), then this value should be the same as the spread down [Aggregated Promotion Lift Override](#). If the indicator is *False* (which does not apply the override), then this value equals zero (0).

Promotional Forecast View

The Promotional Forecast view allows you visibility to all components of the forecast, like Self, Halo, and Cannibalization effects for both regular price changes, as well as promotions. This is the place the user reviews the impact of the promo-related parameters set in the Promotions and Promotion Parameters views. The process of changing parameters, re-generating the promo forecast, and reviewing the impact in this view, implements the promotional what-if functionality.

Figure 6–10 Promotional Forecast View

	10/9/2009	10/16/2009	10/23/2009	10/30/2009	11/6/2009	11/13/2009
Forecasted Baseline 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Promotional Forecast with Promote Lift Override 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Total Promotional Lift Unit 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Total Regular Price Lift Unit 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Price Self Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Price Halo Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Price Cannibalization Lift Unit 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Self Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Halo Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Cannibalization Lift Unit 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
Promotional Lift Override 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00

Measures: Promotional Forecast View

The Promotional Forecast view can contain the following measures:

Forecast Baseline

The Forecast Baseline is a forecast generated on past sales data that contains no promotions (that is, normal demand given no causal effects).

Price Cannibalization Lift Unit

This measure displays the negative effect, measured in units, that a price change of certain items has on this item.

Price Halo Lift Units

This measure displays the positive effect, measured in units, that a price change of certain items has on this item.

Price Self Lift Units

This measure displays the effect that a price change has on the sales units of an item.

Promotion Cannibalization Lift Units

This measure displays the negative effect, measured in units, that the promotion of certain items has on this item.

Promotion Halo Lift Units

This measure displays the positive effect, measured in units, that the promotion of certain items has on this item.

Promotion Self Lift Units

This measure displays the effect that promotions have on the sales units of an item. The value is expected to reflect the overlapping promotions effect. More information is available in the Forecast Administration workbook.

Promotional Forecast with Promote Lift Override

This measure displays the promotional forecast where the promotional peaks are not calculated by RDF, but imported as lift overrides.

Promotional Lift Override

Override, in units, of the system generated promotional lift. The override is at the same intersection as the forecast.

This measure can be equal to the [Aggregated Promotion Lift Override](#) or zero (0). It is generated based on the Aggregated Promotion Lift Override and the Apply Promotion Lift Override Indicator. If the indicator is set to *True* (which applies the override), then this value should be the same as the spread down [Aggregated Promotion Lift Override](#). If the indicator is *False* (which does not apply the override), then this value equals zero (0).

Total Promotional Lift Unit

This measure displays the total effect that a promotion can have on an item's sales units. It is the sum of Promotion Self Lift Units, Promotion Halo Lift Units, and Promotion Cannibalization Lift Units.

Total Regular Price Lift Unit

This measure displays the total effect that a regular price change can have on an item's sales units. It is the sum of Regular Price Self Lift, Regular Price Halo Lift, and Regular Price Cannibalization Lift.

Promotion Parameters View

The Promotion Parameters view allows you to set up rules that need to be followed when forecast is simulated. For instance, you may not want to apply regular price change effects when an item is on promotion or you may want to incorporate Halo and no Cannibalization effects in the forecast. click **Calculate** to update the forecast values in the Promotional Forecast view.

Figure 6–11 Promotion Parameters View

The screenshot shows a software interface titled "Promotion Parameters for Level 1 - itm/str/week-Final". It includes a navigation bar with "Location" (Atlanta, GA) and "Product" fields. Below is a table with columns for "24 X 16 oz", "Fruit in the", and "Fruit in the" (repeated four times). The table lists various parameters with values or checkboxes.

	24 X 16 oz	Fruit in the				
System Calculated Effect 1 - itm/str/week-Final Circular	1.00	1.00	1.00	1.00	1.00	1
System Effect Override 1 - itm/str/week-Final Circular	1.00	1.00	1.00	1.00	1.00	1
Promo Effect Type 1 - itm/str/week-Final Circular	Automatic	Automatic	Automatic	Automatic	Automatic	Automatic
Apply Regular Price Lift Final 1 - itm/str/week-Final	Apply Sytem	Apply Syte				
Apply Regular Price Lift over Promotion Final 1 - itm/str/week-Final	<input type="checkbox"/>					
Apply Regular Price Self Lift Final 1 - itm/str/week-Final	<input checked="" type="checkbox"/>					
Apply Regular Price HALO Lift Final 1 - itm/str/week-Final	<input checked="" type="checkbox"/>					
Apply Regular Price Cannibalization Lift Final 1 - itm/str/week-Final	<input checked="" type="checkbox"/>					
Apply Promotion Halo Lift Final 1 - itm/str/week-Final	<input type="checkbox"/>					
Apply Promotion Cannibalization Lift Final 1 - itm/str/week-Final	<input type="checkbox"/>					
Apply Promotional Lift Override 1 - itm/str/week-Final	<input type="checkbox"/>					

Measures: Promotion Parameters View

The Promotion Parameters view contains the following measures:

Apply Promotion Cannibalization Lift

Select this parameter (set to *True*) if the application of Cannibalization Lifts is enabled for the forecast level.

Apply Promotion Halo Lift

Select this parameter (set to *True*) if the application of Halo lifts is enabled for the forecast level.

Apply Promotional Lift Override

Select this parameter (set to *True*) if you want RDF to ignore the system calculated lifts and apply the overrides.

Apply Regular Price Cannibalization Lift

Is only effective if [Apply Regular Price Lift](#) is set to Apply System or Apply Override. Select this parameter (set to *True*) if the application of Regular Price Cannibalization Lifts is enabled for the forecast level.

Apply Regular Price Halo Lift

Is only effective if [Apply Regular Price Lift](#) is set to Apply System or Apply Override. Select this parameter (set to *True*) if the application of regular price Halo lifts is enabled for the forecast level.

Apply Regular Price Lift

If regular price lifts are enabled for the forecast level, select one of the following options:

Option	Description
Do Not Apply	Does not apply regular price effects (including Self, Cannibalization, and Halo effects)
Apply System	Applies system calculated effects
Apply Override	Ignores system calculated effects and applies overrides

Apply Regular Price Lift Over Promotion

Is only effective if [Apply Regular Price Lift](#) is set to Apply System or Apply Override. Select this parameter (set to *True*) if the application of regular price lifts is enabled for time periods that are promoted. If the parameter is clear, then regular price lifts are not applied for periods with promotions.

Apply Regular Price Self Lift

Is only effective if [Apply Regular Price Lift](#) is set to Apply System or Apply Override. Select this parameter (set to *True*) if the application of regular price lifts is enabled for the forecast level.

Promo Effect Type

Causal variable types define how causal variables are treated in the causal model-fitting process (which includes a call to the lower-level regression engine) and the forecast generation process where the model is used to extend the forecast over the forecast horizon.

[Table 6–2](#) lists the Causal variable types.

System Calculated Effect

The System Calculated Effect is a read-only measure indicating the lift effect generated by the system.

System Effect Override

The user-specified lift effect. This user-entered effect is active if used in conjunction with the Override All and Override Future Only Promotion Effect Types. Otherwise, it equals 1.00.

Promo Planner Task

In order to correlate deviations from the seasonal forecast with the occurrence of historic promotion events, the system needs visibility as to when these events were active. The system must also be informed of dates on which the status of upcoming promotion events will again be on, so the anticipated promotion effects can be built into the forecasting model.

The Promo Planner task allows you to indicate to the system when certain events were active in the past and when they are active in the future. All promotional events should be represented as accurately as possible so the modeling routine can more precisely detect correlations between event occurrences and changes in sales values.

The Promo Planner task consists of as many views as are necessary to represent all unique dimensional intersections associated with the promotion events contained in the task. A separate view is constructed for each of the required intersections. For example, promotion events such as Advertisement and Gift with Purchase may be loaded at the item/store/week intersection, while an event such as Christmas is loaded at the [Day] level.

In this setup, the Advertisement and Gift with Purchase promotions would appear on one view, and Christmas would appear on another. Whenever a hierarchy is not included in the base intersection (as in the case of the Christmas promotional event) the event is assumed to apply to all positions in the undefined hierarchy. Thus, Christmas is assumed to apply to all products and all locations, but only to the Day-level calendar positions specified in the [Promotions View](#).

This task has this view:


- [Promotions View](#)

Promo Planner Workbook

To build the Promo Planner workbook, perform these steps:


1. Click the New Workbook icon in the Promo Planner task in the Promotional Planning activity.

Figure 6–12 Promo Planner Task




2. The Workbook wizard opens. Select the promotion events to include and click Next.

Figure 6–13 Workbook Wizard: Select Promotions




3. Select the products to include and click Next.

Figure 6–14 Workbook Wizard: Select Products




4. Select the locations to include and click **Next**.

Figure 6–15 Workbook Wizard: Select Location



5. Select the days you want to work with and click **Finish**

Figure 6–16 Workbook Wizard: Select Days




The Promo Planner workbook is built.

Promotions View

The Promotions view allows you to view and edit the on/off information associated with each configured promotional event. This view provides an interface in which you can specify the time periods (and possibly products or locations) for which certain promotional variables are active.

Figure 6–17 Promotions View



Measures: Promotions View

The Promotions view contains the following measures:

Promotion Variables

Promotion Variable Type is defined through setting both Data Type and Model Type during the configuration process in the Promote Plug-in. The Promotion Variable Type includes Boolean, Exponential, and Real. The following table explains how Promotion Variable Type is defined through Data Type and Model Type settings.

When the Type is	And the Model is	Then the Promotion Variable Type is
Boolean	either Linear or Exponential	Boolean
Real	Linear	Real
Real	Exponential	Exponential

The Data Type includes Boolean and Real types. The Model Type includes Linear and Exponential types. When Data Type is set to Boolean, the Promotion Variable Type is Boolean. When Data Type is set to Real and the Model Type is set to Linear, the Promotion Variable Type is Real. If Data Type is set to Real and the Model Type is set to Exponential, the Promotion Variable Type is Exponential.

Refer to the *Oracle Retail Demand Forecasting Configuration Guide* for additional details on configuring the Promote solution.

Promotion Variable Type	Description
Boolean	<p>A check in a given cell indicates that the associated promotion event's status is on (or 100% of the lift effect applies) for that intersection. If no check is indicated, the event's status is off.</p> <p>Boolean promotions can be enabled together with other types of promotions at the same time.</p>
Exponential	<p>Real numbers are expected in the cells. The value specified here is used in an exponential model which is an input to the stepwise regression sub-routine.</p> <p>A typical example of a metric modeled as exponential is the percent price change. Note how the percent price change can be positive (price increase) or negative (price decrease).</p> <p>Exponential promotions can be enabled together with Boolean promotions at the same time. However, they can not be enabled together with Real promotions.</p>
Real	<p>Non-negative values are expected in the cells.</p> <p>A value of 0 indicates that the event's status is off. A value greater than 0 will act as a weight when calculating the effects during the stepwise regression.</p> <p>Real promotions can be enabled together with Boolean promotions at the same time. However, they can not be enabled together with Exponential promotions.</p>

About Implementation

Among the ways Causal variables can be implemented include price or discount percent. Your Oracle Retail Consultant can best determine the most accurate setup of promotion variables based upon your promotional forecasting requirements.

Promotion Management Task

The Promotion Management task allows you to enable and disable promotions for causal forecast levels and to specify whether promotions can have a negative effect.

This task has these views:

- [Promo Variable Model Type View](#)
- [Promotion Enable View](#)


- [Accept Negative Lift View](#)

Promotion Management Workbook

To build the Promotion Management workbook, perform these steps:


1. Click the New Workbook icon in the Promotion Management task in the Promotional Planning activity.

Figure 6–18 Promotion Management Task




2. The Workbook wizard opens. Select the causal level and click **Next**.

Figure 6–19 Workbook Wizard: Select Causal Level



3. Select the promotions you want to work with and click **Finish**.

Figure 6–20 Workbook Wizard: Select Promotions



The Promotion Management workbook is built.

Promo Variable Model Type View

The Promo Variable Model Type view allows you to view the model type for the selected promotion variables.

Figure 6–21 Promo Variable Model Type View

	Circular	In-Store	New Years	Signage
Model Type for promotional variable	Linear	Linear	Linear	Linear

Measure: Promo Variable Model Type View

The Promo Variable Model Type view contains the following measure:

Model Type for Promotional Variable

This measure stores the model type for the selected promotion variables. The choices are exponential and linear. An exponential model type is displayed if the promotion type is exponential. A linear model type is displayed when the promotion types are Real or Boolean.

For additional information, see "[Promotion Variables](#)" on page 6-17.

Promotion Enable View

The Promotion Enable view allows you to enable or disable a promotion for the causal forecast levels. The Promotion Enable view is built at the hierarchy intersections of the promotion variables and the causal levels selected during the wizard process.

Figure 6–22 Promotion Enable View

	1 - itm/str/week-Final	2 - itm/str/week	6 - itm/str/day-Final
Back to School	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Christmas	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Christmas Season	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Circular	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Cover	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Direct Mail	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Easter	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
In-Store Display	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Multibuy	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
New Years Day	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Promotional Price	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Signage	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TV Ad	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Measures: Promotion Enable View

The Promotion Enable view contains the following measure:

Enable Promotions

This is a read/write Boolean measure. The Enable Promotions measure allows you to enable a subset of promotions for a certain causal forecast level. It defaults to *True* for all causal forecast levels.


Note: Exponential promotions and Real promotions can not be enabled at the same time for the same level. In another word, Real promotions and Exponential promotions are not valid combinations. The valid promotion combinations are Boolean and Exponential promotions, as well as Boolean and Real promotions.

Each promotion's type is defined in the Configuration Tool. For additional information, see "[Promotion Variables](#)" on page 6-17.

Accept Negative Lift View

The Accept Negative Lift view allows you to specify whether a promotion is allowed to have negative effect. The Promotion Enable view is built at the hierarchy intersections of the promotion variables selected during the wizard process.

Figure 6–23 Accept Negative Lift View



Measures: Accept Negative Lift View

The Accept Negative Lift view contains the following measure:

Promotion Allow Negative Lift

This is a read/write Boolean measure. The Promotion Allow Negative Lift measure allows you to specify whether a promotion is allowed to have negative effect. When this measure is set to *False* for a promotion, the forecast engine does not allow that promotion to have any negative lift (Effect < 1). It defaults to *True* for all promotions.

Promo Effect Maintenance Task

The Promo Effect Maintenance task provides a view to the system-calculated and adjusted lift effects. You can edit effects at any product/location intersection and determine how these changes are factored into the promotional models. The Promo Effect Maintenance task contains one view. There may be multiple versions of this view, defined at various causal levels.

This task has this view:


- [Promotion Parameters View](#)

Promo Effect Maintenance Workbook

To build the Promo Effect Maintenance workbook, perform these steps:


1. Click the New Workbook icon in the Promo Effect Maintenance task in the Promotional Planning activity.

Figure 6–24 Promo Effect Maintenance Task



2. The Workbook wizard opens. Select the causal level and click **Next**.


Figure 6–25 Workbook Wizard: Causal Level



3. Select the promotion events to include and click **Next**.


Note: If RDF detects cross-promotional effects for your selected causal level, then RDF uses those promotions and the wizard skips to "Workbook Wizard: Select Products".

Figure 6–26 Workbook Wizard: Select Promotions




4. Select the products you want to work with and click **Next**.

Figure 6–27 Workbook Wizard: Select Products



5. Select the locations you want to work with and click **Finish**.

Figure 6–28 Workbook Wizard: Select Locations



The Promo Effect Maintenance workbook is built.

Promotion Parameters View

The Promotion Parameters view allows you to view and modify the system-calculated effects of a given promotion.

Note: Changes that are committed in the Promo Effect Maintenance task are not incorporated into the forecast until another forecast is generated in RDF batch forecast process.

Figure 6–29 Promotion Parameters View

Promotion Parameters for Level 1 - itm/str/week-Final						
Product						Location
Coca Cola 2 ltr/Coke Zero						Measure
	Albany, NY	Albuquerque, NM	Anchorage, AK	Boston, MA	Burlington, VT	
Promo Effect Type 1 - itm/str/week-Final Circular	Automatic	Automatic	Automatic	Automatic	Automatic	
System Effect Override 1 - itm/str/week-Final Circular	1.00	1.00	1.00	1.00	1.00	
System Calculated Effect 1 - itm/str/week-Final Circular	1.00	1.00	1.00	1.00	1.00	

Measures: Promotion Parameters View

The Promotion Parameters view contains the following measures:

Promo Effect Type

Causal variable types define how causal variables are treated in the causal model-fitting process (which includes a call to the lower-level regression engine) and the forecast generation process where the model is used to extend the forecast over the forecast horizon. [Table 6–2](#) lists the options.

System Calculated Effect

The System Calculated Effect is a read-only measure indicating the lift effect generated by the system.

System Effect Override

The user-specified lift effect. This user-entered effect is active if used in conjunction with the Override All and Override Future Only Promotion Effect Types. Otherwise, it equals 1.00.

Table 6–2 Promo Effect Types

Causal Variable Type	Description
Automatic	The inclusion of the Promo Effect is decided by regression. If the Promo Effect is found to be significant on the training set, it is included in the model. Otherwise, it is rejected. Automatic is the system default Promotion Effect Type.
Forced In	The Promo Effect is forced in to the model, thus regression is not given a choice to reject even if the effect is considered insignificant by regression. As a result, we will always return an effect even if it has a negative impact to the demand forecast.
Disabled	The variable is excluded from the model, hence no effect is returned either.
Override All	This type allows you to specify a causal effect that is used during the forecasting process. For Promo Effects specified as Override All, you also specify the corresponding causal effect in the Promotion Effect Override. The causal engine de-causalizes the training data using the user-specified effect. During forecast generation, the user-specified effect is used to determine the causal forecast. Therefore, you must change the Promotion Effect Type when this user-specified effect is no longer to be used.
Override Future Only	This type allows you to specify a causal effect that is used during the forecasting process. For Promo Effects specified as Override Future, you also specify the corresponding causal effect in the Promotion Effect Override. The calculated effect is not written back to the effects measure, but it is used to de-causalize the data. During forecast generation the calculated effect is ignored, and, instead, the user-specified effect is used to produce a causal forecast. Therefore, you must change the Promotion Effect Type when this user-specified effect is no longer to be used.
Override from Higher Level	This promotion type is used in conjunction with the Causal Higher Intersection set in the Forecast Administration Workbook . If the Causal Higher Intersection is not specified, no promotional effect is calculated. It allows the system to use the geometric mean of causal effects computed from product/location combination in the same group (the intersection level specified in the Causal Higher Intersection during system setup) for product/location combinations for which from sales history alone a causal effect is unable to be computed for that Promo Effect. The way the system handles this, is by having the override effects measure filled in with higher-level effects for those variables specified as Override Higher Level. During forecast generation the effect calculated as average of low level effects is used to produce a causal forecast. Note that if no effects are found for any of the product/locations in the Causal Higher intersection group, then the system uses the geometric mean of causal effects calculated from all Product/Locations as the override effect being passed in.
Automatic Boolean	If the promotion variable is always be set to 0.00 or 1.00 (meaning inactive or active, respectively), this type produces the same results as the Automatic type; however, Automatic Boolean improves the performance (speed) of the forecasting engine during the batch run of the forecast.

Procedures in Promotional Forecasting

The following list outlines the standard procedures performed in order to set up the system to run a promotional forecast:

- [Setting Up the System to Run a Promotional Forecast](#)
- Setting forecast parameters in the [Forecast Administration Workbook](#)
- Setting forecast parameters in the [Forecast Maintenance Workbook](#)
- Setting promotions to be active in the [Promo Planner Task](#)
- Running the batch forecast
- Viewing and Edit Causal Forecast results
- Analyzing forecasts in the [Forecast Approval Workbook](#)
- Analyzing and editing causal effects in the [Promo Effect Maintenance Task](#)
- [Viewing a Forecast That Includes Promotion Effects](#)
- [Viewing and Editing Promotion System-Calculated Effects](#)
- [Promotion Simulation \(What-if?\) and Analysis](#)

Setting Up the System to Run a Promotional Forecast

Perform the following procedure to set up the system to run a promotional forecast.

1. Build a [Forecast Administration Workbook](#).
 - a. In the [Forecast Administration Workbook: Final Level Parameters View - Advanced Settings](#), select [Generate Baseline Forecasts](#).
 - b. Optional: **Set the Default Forecast Method to Causal** for the desired level if the level is to be use only for Promotional Forecasting.
 - c. Optional: **Set the Causal Higher Intersection** for the desired level if the Override from Higher Level promotion type is used.
 - d. Optional for use with Daily Causal Forecasting: Set the values for the following parameters:
 - Causal Aggregation Profile
 - Causal Calculation Intersection
 - Causal Calculation Intersection Periodicity
 - e. Commit your changes to the master database by selecting **Commit Now** from the File menu.
2. Build a [Forecast Maintenance Workbook](#).
 - a. Set the [Forecast Method Override](#) to **Causal** for any items/locations at the desired levels that use Promotional Forecasting.
 - b. Commit your changes to the master database by selecting **Commit Now** from the File menu.
3. Build a [Promo Planner Workbook](#).
 - a. Set causal variables for items and locations historically in that the selected promotions are active.

- b. Commit your changes to the master database by selecting **Commit Now** from the File menu.
4. Select **Run Batch** and generate a Forecast.

Viewing a Forecast That Includes Promotion Effects

Perform this procedure to view a forecast that includes promotion effects.

1. Build a [Forecast Approval Workbook](#) and include System Baseline in your task.
2. In the [Final Level View](#), review the System Baseline and the System Forecast. The System Baseline is predicted demand given no causal effects. The System Forecast is the sum of the System Baseline and the Promotional Peak calculated during the forecast generation process based on the causal data and settings.

Viewing and Editing Promotion System-Calculated Effects

Perform this procedure to view and edit promotion system-calculated effects.

1. Build a [Promo Effect Maintenance Workbook](#).
 - a. In the [Promotion Parameters View](#) PromoEffects view, review the [System Calculated Effect](#).
 - b. If the [System Calculated Effect](#) is to be modeled using a method other than Automatic, edit the [Promo Effect Type](#).
 - c. If you choose to adjust the system-calculated effect, adjustments can be made to the [System Effect Override](#). You must also set the [Promo Effect Type](#) to **Override All** or **Override Future Only**.
2. Select **Run Batch** and generate a Forecast.

Promotion Simulation (What-if?) and Analysis

Follow this procedure to perform analysis on past promotions and simulate the effects of historic or future promotions:

1. Build a [Promo Effectiveness - Promotion Results Workbook](#).
2. In the [Promotion Parameters View](#), review the [System Calculated Effect](#) and edit the [System Effect Override](#) then select **Calculate** to recalculate the Future Forecast.

Note: Changes to the [Promo Effectiveness - Promotion Results Workbook](#) cannot be committed; however, this task is useful for:

- Reporting on the performance of past promotions.
 - Simulating the effects of future promotions to support more accurate promotional modeling.
-
-

Forecast Scorecard Task

This chapter describes the purpose and content of the Forecast Scorecard and the steps required in order to create and access this task. This chapter also discusses the two types of views contained in the Forecast Scorecard task, as well as the definitions of parameters that exist in each. Evaluating forecast accuracy through the use of error statistics is discussed, as is the process of comparing historical forecasts to actual sales data.

The purpose of the Forecast Scorecard is to monitor the accuracy of both system-generated forecasts and approved final forecasts. Once a forecast has been generated and actual point-of-sale data is received for the forecast period, statistical information can be reviewed to help you analyze the accuracy of forecasting models and methods.

The Forecast Scorecard consists of a wizard and two views.

Based on your selections in the wizard, the Forecast Scorecard provides statistical information and comparison data that allow you to monitor the accuracy of system-generated forecasts and final approved forecasts.


- The Final Error Measure view displays statistical information, such as mean error and root mean squared error, that reflects the accuracy of the forecast.
- The Final Actuals versus Forecasts view displays forecast results and actual point-of-sale values for specified product/location/calendar combinations.

Forecast Scorecard Workbook

To build the Forecast Scorecard workbook, perform these steps:


1. Click the New Workbook icon in the Forecast Scorecard task in the Core Forecasting activity.

Figure 7-1 Forecast Scorecard Task




2. The Workbook wizard opens. Select the forecast level that you want to evaluate and click **Next**.


Figure 7–2 Workbook Wizard: Forecast Level



3. Select the generation date of the forecast you wish to review and click **Next**:
 - Click **Use the most recent generated forecast** to build a task containing the most recent forecast values.
 - Click **Select from a list of forecast** to select from a list of previously generated forecasts stored in the system.


Figure 7-3 Workbook Wizard: Forecast Generation Date

4. Select the forecast type and click **Next**.

Figure 7-4 Workbook Wizard: Select Forecast Type


5. Check the boxes corresponding to the error statistics that you want calculated for the forecast data. and click **Next**.

Figure 7-5 Workbook Wizard: Calculate Error Statistics




6. Select the products you want to work with and click **Next**.

Figure 7-6 Workbook Wizard: Select IProducts




7. Select the specific locations that you want to view and click **Next**.

Figure 7–7 Workbook Wizard: Select Locations



8. Select the first date of history to include in the task. You may either choose to set the **Forecast Start Date minus the number of periods** or select the first date of history from the displayed list. It is recommended that the **Forecast Start Date minus the number of periods** is set if the task supports an AutoTask build. Make your selection and click **Next**.


Figure 7–8 Workbook Wizard: Select Workbook Start Date



9. Select the last date to include of the horizon from the displayed list and click **Next**.

Note: It is recommended that **Include the following number of time periods of the forecast horizon** is set if the task supports an AutoTask build.

Figure 7–9 Workbook Wizard: Select Forecast End Date



10. Select the last date in the calendar to include and click **Next**.

Note: It is recommended that **Forecast end date plus the following number of time periods** is set if the task supports an AutoTask build.

Figure 7–10 Workbook Wizard: Select Workbook End Date

Workbook Wizard

Forecast Level Selection Forecast Selection Forecast Type Selection Statistic Selection Product Selection Location Selection Workbook Start Date Selection Forecast End Date Selection **Workbook End Date Selection** ...

Select the last date in the calendar to include in the workbook.

Forecast end date plus the following number of time periods (≥ 0)

From list below

- 10/4/2013
- 10/11/2013
- 10/18/2013
- 10/25/2013
- 11/1/2013
- 11/8/2013
- 11/15/2013
- 11/22/2013
- 11/29/2013
- 12/6/2013
- 12/13/2013

Cancel Previous Next Finish

11. Select any additional measure to include and click **Finish**.

Figure 7–11 Workbook Wizard: Select Extra Measures

Workbook Wizard

Forecast Level Selection Forecast Selection Forecast Type Selection Statistic Selection Product Selection Location Selection Workbook Start Date Selection Forecast End Date Selection Workbook End Date Selection **Extra Measure Selection**

Please select additional measures to be included in the workbook.

- Aggregated Shifted Sales - SLC
- Aggregated ROS - SLC
- Anchor Price
- Approval Method 01 - itm/str/week-Baseline Forecast Final
- Approval Method 06 - itm/str/day- Daily Causal Final
- Approval Method 07 - itm/str/week-Weekly Causal Final
- Approval Method 08 - itm/str/week -Floating Event Final
- Approval Method 09 - itm/str/week-Final - SLC baseline
- Approval Method 10 - itm/str/week-Final - Causal SLC
- Approval Method 11 - itm/str/week- Final
- Approval Method Override 01 - itm/str/week-Baseline Forecast Final
- Approval Method Override 06 - itm/str/day- Daily Causal Final
- Approval Method Override 07 - itm/str/week-Weekly Causal Final
- Approval Method Override 08 - itm/str/week -Floating Event Final
- Approval Method Override 09 - itm/str/week-Final - SLC baseline
- Approval Method Override 10 - itm/str/week-Final - Causal SLC
- Approval Method Override 11 - itm/str/week- Final
- Approved Cumulative Interval 01 - itm/str/week-Baseline Forecast Final
- Approved Cumulative Interval 06 - itm/str/day- Daily Causal Final

Cancel Previous Next Finish

The Forecast Scorecard workbook is built.

Error Measure View

The Final Error Measure view displays statistical information that reflects the accuracy of the forecast measures selected in the wizard process. You may need to evaluate a variety of such statistics to verify and compare forecast accuracy.

Given the situation, different levels of forecast accuracy can be useful. For example, in a situation with noisy data and no forecast previously available, a 200% error can be considered excellent and useful. In another situation with smooth data, if an old method of forecasting provided forecasts with a 10% error, a new method of forecasting with a 20% error would not be considered useful.

Different levels of forecasting accuracy are obtained at different levels of product aggregation. Item level forecasts with a 200% error can roll up into division-level forecasts with a 10% error. Therefore, the error measures are most useful when comparing different methods of forecasting or when looking at a particular model's accuracy over time. Accurate forecasts should lead to a reduction in inventory holding costs or to an increase in customer service levels; forecast errors should be converted into dollars saved.

Note: All error statistics are calculated over the first period in the forecast to the last period in the forecast for which forecast data is available.

Figure 7–12 Error Measure View

Measure	Value
History Data for Forecast Window 1 - itm/str/week-Final	11.00
System Forecast 1 - itm/str/week-Final	9.37
System Forecast Mean Error 1 - itm/str/week-Final	0.54
Approved Forecast for Forecast Window 1 - itm/str/week-Final	
Interim Forecast 1 - itm/str/week-Final	0.00
Interim Forecast Mean Error 1 - itm/str/week-Final	3.67

Measures: Error Measure View

The Error Measure view contains the following measures:

History Data for Forecast Window

The sum of all actual sales from the first period in the forecast to the last period in the forecast for which point-of-sale data is available.

Forecast Measures

Your task may include one or all of the forecast measures: System Forecast, Adjusted Forecast, Approved Forecast, Approved System Forecast, or Interim Forecast. These measures are selected in the wizard process. This is the average value of these measures over the forecast horizon select in the wizard process.

Mean Error

The error of a forecast observation is the difference between the forecast value and the actual POS value. The Mean Error statistic is a measure of the average error over time.

This is calculated by summing the errors for all observations, and then dividing by the number of observations to obtain the average. It measures forecast accuracy by calculating the error in units. Because a positive error in one period can cancel out a negative error in another period, this measure is useful when you are interested in how well the forecast predicts over the forecast horizon rather than on a period-to-period basis. Mean error is useful as a measure of forecast bias. A negative mean error suggests that overall the forecasting model overstates the forecast, while a positive mean error indicates forecasts that are generally too low.

Mean Absolute Error

The absolute error of a forecast observation is the absolute value of the difference between the forecast value and the actual POS value. The Mean Absolute Error statistic is a measure of the average absolute error. This is calculated by summing the absolute errors for all observations and then dividing by the number of observations to obtain the average. Mean Absolute Error gives you a better indication of how the forecast performed period by period because the absolute value function ensures that negative errors in one period are not canceled out by positive errors in another. Mean Absolute Error is most useful for comparing two forecast methods for the same series.

Root Mean Squared Error

This is the square root of the Mean Squared Error. The Root Mean Squared Error is one of the most commonly used measures of forecast accuracy because of its similarity to the basic statistical concept of a standard deviation. It evaluates the magnitude of errors in a forecast on a period-by-period basis, and it is best used to compare alternative forecasting models for a given series.

Mean Absolute Percentage Error

The percentage error of a forecast observation is the difference between the actual POS value and the forecast value, divided by the actual POS value. The result of this calculation expresses the forecast error as a percentage of the actual value. The Mean Absolute Percentage Error statistic measures forecast accuracy by taking the average of the sum of the absolute values of the percentage error calculations across all observations. This method is useful when comparing the accuracy of forecasts for different volume products (it normalizes error by volume).

Percentage Absolute Error

The absolute error of a forecast observation is the absolute value of the difference between the forecast value and the actual POS value. The Percentage Absolute Error statistic measures forecast accuracy by calculating the total absolute error as a percentage of the total actual POS. It is calculated by summing the absolute errors for all observations, dividing this value by the absolute value of the sum of all Actuals, and dividing the result by the number of observations in the series. Finally, multiply the total by 100 to obtain a percentage result.

Actuals versus Forecasts View

This view displays forecast results and actual point-of-sale values for each product, location, and time period specified in the Forecast Scorecard wizard. This view allows you to compare the results of both system-generated forecasts and final approved forecasts to actual sales quantities.

Figure 7–13 Actuals versus Forecast View

	1/4/2002	1/11/2002	1/18/2002	4/5/2002	4/12/2002
History Data - Weekly Sales	3.00	4.00	4.00	4.00	4.00
System Forecast 1 - itm/str/week-Final	3.10	3.18	3.09	0.00	0.00
Interim Forecast 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00
Actual - System Forecast 1 - itm/str/week-Final	-0.10	0.82	0.91	4.00	4.00
Actual - Interim Forecast 1 - itm/str/week-Final	3.00	4.00	4.00	4.00	4.00

Measures: Actuals versus Forecasts View

The Actuals versus Forecasts view may contain the following measures:

Actuals

These Actuals do not include: System Forecast, Adjusted Forecast, Approved Forecast, Approved System Forecast, or Interim Forecast.

This displays the difference between the actual sales quantities and the committed forecast values for the forecast measures selected during the wizard process. Negative values indicate that the final forecast exceeded actual sales.

History Data

History Data displays the actual point-of-sale quantities for the product, location, and calendar combinations displayed.

Forecast Measures

Your task may include one or all of these forecast measures: System Forecast, Adjusted Forecast, Approved Forecast, Approved System Forecast, or Interim Forecast. These measures are selected in the wizard process. These measures display the forecast quantity for the product, location, and calendar combinations included in the task.

Interactive Forecasting Task

The Interactive Forecasting task is a forecast simulation tool that allows you to make changes to forecast parameters and see the results without having to wait for the batch run. In this workbook, you can edit various forecast parameters including sales history and forecast method. A new forecast is produced based on the changed parameters. In addition to forecasts, the Interactive Forecasting workbook can also generate fit in historical region and the system picked model if an ES forecast method is used.

Improve Performance for the Interactive Forecasting Workbook

Interactive Forecasting assumes that the historical data is contained in the measure *posxlsx*. All forecasts generated by interactive forecasting are based on this data.

Performance may be improved by utilizing a mask measure. Interactive forecasting uses the measures `mask<forecast level>xb`; for example *mask01xb*. Here, `<forecast level>` corresponds to the forecast level chosen in the wizard when opening the Interactive Forecasting workbook. The mask is a boolean measure. Only cells with the value *True* are included in the forecast. This is useful when desiring to focus on only a few product/locations.


The Interactive Forecast method is intended to be a quick way to view results produced by different forecast methods. It allows you to gauge, in a qualitative way, the suitability of a particular forecast method for a given set of sales history data. Even though it uses the exact same forecast methods as the full forecast, only the parameters listed previously will affect the results. No other user-input values are used. Users wishing to vary a larger number of parameters are encouraged to use the regular forecast functionality.

Interactive Forecasting Workbook

To build the Interactive Forecasting workbook, perform these steps:


1. Click the New Workbook icon in the Interactive Forecasting task in the Core Forecasting activity.

Figure 8–1 Interactive Forecasting Task




2. The Workbook wizard opens. Select the forecast level that you want to evaluate and click **Next**.


Figure 8–2 Workbook Wizard: Forecast Level




3. Select the forecast start date you wish to review and click **Next**:

Figure 8–3 Workbook Wizard: Forecast Start Date

4. Select the history start date and click **Next**.

Figure 8–4 Workbook Wizard: History Start Date


5. Select the end date for the forecast and click **Next**.

Figure 8–5 Workbook Wizard: Forecast End Date


6. Select the end date for the forecast horizon and click **Next**.

Choose one of the following options:

- Specify future time periods beyond the forecast horizon to include in your workbook.
- Select **Do not include dates** after the horizon if no future dates are to be included in the workbook.


Figure 8–6 Workbook Wizard: Forecast Horizon End Date

7. Select the specific locations that you want to view and click **Next**.

Figure 8–7 Workbook Wizard: Select Locations


8. Select the products and click **Next**.

Figure 8–8 Workbook Wizard: Select IProducts




9. Select the forecast results to view and click **Next**.

Figure 8–9 Workbook Wizard: Forecast Results



10. Select any additional measures to include and click **Finish**.

Figure 8–10 Workbook Wizard: Select Extra Measures

The Interactive Forecasting workbook is built.

Once the wizard is completed, the forecast is generated based on your selections in the wizard and the Default Forecast Method set for the specified forecast level in the [Forecast Administration Workbook](#).

Forecasting Parameter View

The Forecasting Parameter view is based on the intersection of the Product and Location dimensions for the select forecast level.

The Forecasting Parameter view contains the following measures. Of these measures, all but System picked model are editable. Changes can be made to the editable parameters, that is, History Start Date, Forecast Method, Forecast Start Date, and Forecast End Date, to regenerate a forecast of the time series.

Figure 8–11 Forecast Parameter View

The screenshot shows the 'Forecast Parameter View' worksheet. The worksheet title is '1 - itm/str/week-Final Forecast Parameter Worksheet'. The worksheet contains the following data:

Parameter	Value
Forecast Method 1 - itm/str/week-Final	Simple
Forecast Picked Method 1 - itm/str/week-Final	No Generated Forecast
History Start Date 1 - itm/str/week-Final	1/10/1998
Forecast Start Date 1 - itm/str/week-Final	3/14/1998
Forecast End Date 1 - itm/str/week-Final	5/15/1998

Measures: Forecasting Parameter View

The Forecasting Parameter view contains the following measures:

Forecast Method

A list from which you can select the method used to generate the forecast. The workbook defaults to the method selected in the [Forecast Administration Workbook](#) for the specified level if the method is supported by Interactive Forecasting. Otherwise, it defaults to *No Forecast*.

Note: The Forecast Method list does not include Causal, Bayesian, Components, Copy, LoadPlan, or Profile-based forecast methods.

Forecast Picked Method

This is the method that was used to generate the forecast for the given product/location combination. This field is useful when combined methods are requested (for example, ES methods). Then this field displays the actual method the system picked from the combined methods. In case stand-alone methods are chosen, generally this field is the same as the method chosen in Forecast Administration or Forecast Maintenance. However, if the requested method is unable to produce a good fit, the system defaults to a simpler method, and that method is displayed here.

History Start Date

This is the starting date for historical sales data. For example, if your system start date is January 1, 2003, but you only want to use historical sales data from the beginning of 2011, you need to set your History Start Date to January 1, 2011. Only history after this date is used for generating the forecast. The default is the system start date unless otherwise specified. If sales data is collected weekly, RDF generates forecasts only using data from sales periods after the one containing the history start date.

It is also important to note that the system ignores leading zeros that begin at the history start date. For example, if your history start date is January 1, 2011, and an item/location does not have sales history until February 1, 2011, the system considers the starting point in that item/location's history to be the first data point where there is a non-zero sales value.

Forecast Start Date

This is first date of the forecast horizon. The default is the start date selected in the wizard.

Forecast End Date

This is the last date of the forecast horizon. The default is the end date selected in the wizard.

Additional Information about the Interactive Forecasting View Parameters

Interactive Forecasting assumes that the historical data are contained in the measure *pos_{xl}xb*. All forecasts generated by interactive forecasting are based on these data.

Performance may be improved by utilizing a mask measure. Interactive forecasting uses the measures *mask<forecast level>xb*; for example *mask01xb*. Here, *<forecast level>* corresponds to the forecast level chosen in the wizard when opening the Interactive Forecasting workbook. The mask is a boolean measure. Only cells with the value *True* are included in the forecast. This is useful when desiring to focus on only a few product/locations.

The Interactive Forecast method is intended to be a quick way to view results produced by different forecast methods. It allows the user to gauge, in a qualitative way, the suitability of a particular forecast method for a given set of sales history data.

Even though it uses the exact same forecast methods as the full forecast, only the parameters listed previously will affect the results. No other user-input values are used. Users wishing to vary a larger number of parameters are encouraged to use the regular forecast functionality.

Also, the Winters Method has a pre-established minimum history of 104 periods.

Interactive Forecasting View

The Interactive Forecasting view is based on the intersection of the Product, Location, and Calendar dimensions for the forecast level selected in the wizard process. The Interactive Forecasting view contains the History Data and the System Forecast. Of these measures, only History Data is editable.

Figure 8–12 Interactive Forecasting View

	1/16/1998	1/23/1998	1/30/1998	2/6/1998	2/13/1998	2/20/1998
History Data - Weekly Sales	0.00	0.00	0.00	0.00	0.00	0.00
Forecast Cumulative Interval 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00
System Forecast 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00

Measures: Interactive Forecasting View

The Interactive Forecasting view contains the following measures:

History Data

This is the historical sales data set in the [Forecast Administration Workbook](#). This field is editable so you can change out-of-character sales if needed. For example, if your battery sales went up during a major power outage, you can lower the sales data back to a more normal level so the unusually high sales adversely affects your forecast. However these changes are for simulation purposes only and cannot be committed.

System Forecast

The quantity that the system predicts is required for the product, location, and calendar combination displayed. Changes to History Data, History Start Date, Forecast Start Date, Forecast End Date, and Forecast Method causes the System Forecast to re-calculate when *Calculate* is selected from the toolbar.

Forecast Administration Task

The Forecast Administration task allows you to set up RDF to generate forecasts.

Forecast Administration Task Components

This section describes the components of the Forecast Administration.

Basic versus Advanced

Forecast Administration is the first task used in setting up RDF to generate forecasts. It provides access to forecast settings and parameters that govern the whole domain (database). These settings and parameters are divided into two areas, Basic and Advanced, and are available beneath the Forecast Administration task.

The Basic Settings are used to establish a final-level forecast horizon, the commencement and frequency of forecast generation, and the specification of aggregation levels (Source Levels) and spreading (Profile) methods used to yield the final-level forecast results. For information on the views in Basic Settings, refer to [Forecast Administration Workbook: Basic Settings](#).

The Advanced Settings are used to set default values for parameters affecting the algorithm and other forecasting techniques used to yield final-level and source-level forecasts, thus eliminating the need to define these parameters individually for each product and location. If certain products or locations require parameter values other than the defaults, these fields can be amended on a case-by-case basis in the [Forecast Maintenance Workbook](#). For information on the views in Advanced Settings, refer to [Forecast Administration Workbook: Advanced Settings](#).

Final versus Source Level Forecasts

Often, forecast information is required for items at a very low level in the hierarchy. However, problems can arise in that data is often too sparse and noisy to identify clear patterns at these lower levels. For this reason, it sometimes becomes necessary to aggregate sales data from a low level to a higher level in the hierarchy in order to generate a reasonable forecast. Once this forecast is created at the higher or source-level, the results can be allocated to the lower-level or final-level dimension based on the lower level's relationship to the total.

In order to spread this forecast information back down to the lower level, it is necessary to have some idea about the relationship between the final-level and the source-level dimensions. Often, an additional interim forecast is run at the low level in order to determine this relationship. Forecast data at this low level might be sufficient to generate reliable percentage-to-whole information, but the actual forecast numbers are more robust when generated at the aggregate level.

The Final Level view represents forecast parameters for the lower (final) level, the level to which source forecast values are ultimately spread. Forecast data must appear at some final-level in order for the data to be approved or exported to other systems. The Source Level view represents the default values for forecast parameters at the more robust aggregate (source) level.

Forecasting Methods Available in RDF

A forecasting system's main goal is to produce accurate predictions of future demand. The RDF solution utilizes the most advanced forecasting algorithms to address many different data requirements across all retail verticals. Furthermore, the system can be configured to automatically select the best algorithm and forecasting level to yield the most accurate results.

Following is a summary of the various forecasting methods employed in RDF. Some of these methods may not be visible in your solution based on configuration options set in the RPAS Configuration Tools. More detailed information on these forecasting algorithms is provided in [Chapter 3, "Oracle Retail Demand Forecasting Methods"](#)

Average

RDF uses a simple average model to generate forecasts.

Moving Average

RDF uses a simple moving average model to generate forecasts. You can specify a Moving Average Window length.

IntermittentES

RDF fits the data to the Croston's model of exponential smoothing. This method should be used when the input series contains a large number of zero data points (that is, intermittent demand data). The original time series is split into a Magnitude and Frequency series, and then the SimpleES model is applied to determine level of both series. The ratio of the magnitude estimate over the frequency estimate is the forecast level reported for the original series.

TrendES

RDF fits the data to the Holt model of exponential smoothing. The Holt model is useful when data exhibits a definite trend. This method separates base demand from trend and then provides forecast point estimates by combining an estimated trend and the smoothed level at the end of the series. For instance, where the forecast engine cannot produce a forecast using the TrendES method, the Simple/IntermittentES method is used to evaluate the time series.

Causal

Causal is used for promotional forecasting and can only be selected if Promote is implemented. Causal uses a Stepwise Regression sub-routine to determine the promotional variables that are relevant to the time series and their lift effect on the series. AutoES and source-level forecasting are used to generate future baseline forecasts. By combining the future baseline forecast and each promotion's effect on sales (lift), a final promotional forecast is computed. For instances where the forecasting engine cannot produce a forecast using the Causal method, the system evaluates the time series using the SeasonalES method.

To forecast short lifecycle, promotional items, Causal deprices, depromotes, and smoothes the forecasting data source to generate the short-lifecycle forecast causal baseline. The promotion effects are calculated using the same Stepwise Regression

code as Causal. However, the promo lifts are first filtered from the sales and applied on top of the item's rate of sale. The resulting measure is regressed against the promotional variables to determine the promotion effects. Finally, the promotion effects are applied on top of the short lifecycle baseline to generate the final forecast.

No Forecast

No forecast is generated for the product/location combination.

Bayesian

Useful for short lifecycle forecasting and for new products with little or no historic sales data, the Bayesian method requires a product's known sales plan (created externally to RDF) and considers a plan's shape (the selling profile or lifecycle) and scale (magnitude of sales based on Actuals). The initial forecast is equal to the sales plan, but as sales information comes in, the model generates a forecast by merging the sales plan with the sales data. The forecast is adjusted so that the sales magnitude is a weighted average between the original plan's scale and the scale reflected by known history. A Data Plan must be specified when using the Bayesian method. For instances where the Data Plan equals zero (0), the system evaluates the time series using the SeasonalES method.

Profile-based

RDF generates a forecast based on a seasonal profile that can be created in RPAS or legacy system. Profiles can also be copied from another profile and adjusted. Using historic data and the profile, the data is de-seasonalized and then fed to the SimpleES method. The Simple forecast is then re-seasonalized using the profiles. A Seasonal Profile must be specified when using the Profile-Based method. For instances where the Seasonal Profile equals zero, the system evaluates the time series using the SeasonalES method.

Components

The Components forecast method multiplies pre-calculated baseline, promotional lifts, and regular price lifts to generate the forecast. These components are specified in Forecast Administration task, Advanced Settings activity, Final Level Parameters view. The following table lists the components and their referenced measures.

Component	Measure
Baseline	Components - Baseline
Regular Price Lifts	Components - Regular Price Lifts
Promotional Lifts	Components - Promotional Lifts
Interval	Components - Baseline Interval

Intervals are not generated and need to be provided. This method is useful when the forecast components are available since the forecast can be quickly generated.

Automatic Exponential Smoothing (AutoES)

RDF fits the sales data to a variety of exponential smoothing models of forecasting, and the best model is chosen for the final forecast. The candidate methods considered by AutoES are:

- [SimpleES](#)
- [Croston's Method](#)

- [Simple/IntermittentES](#)
- [HoltES](#)
- [Multiplicative Seasonal](#)
- [Additive Seasonal](#)
- [SeasonalES](#)
- [Seasonal Regression](#)

The final selection between the models is made according to a performance criterion (Bayesian Information Criterion) that involves a trade-off between the model's fit over the historic data and its complexity.

SimpleES

RDF uses a simple exponential smoothing model to generate forecasts. SimpleES ignores seasonality and trend features in the demand data and is the simplest model of the exponential smoothing family. This method can be used when less than one year of historic demand data is available. For more information, see [Simple Exponential Smoothing](#).

Croston's Method

Croston's Method is used when the input series contains a large number of zero data points (that is, intermittent demand data). For more information, see [Croston's Method](#).

Simple/IntermittentES

Simple/IntermittentES is a combination of the SimpleES and IntermittentES methods. This method applies the SimpleES model unless a large number of zero data points are present, in which case the Croston's model is applied. For more information, see [Simple/Intermittent Exponential Smoothing](#).

HoltES

Holt exponential smoothing treats data as linearly trended but non-seasonal. The Holt model provides forecast point estimates by combining an estimated trend (for the forecast horizon - h) and the smoothed level at the end of the series. RDF uses a damped Holt model that decays the trend component so that it disappears over the first few weeks. This improves forecasts created using Holt over longer forecast horizons. For more information, see [Holt Exponential Smoothing](#).

Multiplicative Seasonal

Also referred to as Multiplicative Winters Model, this model extracts seasonal indices that are assumed to have multiplicative effects on the un-seasonalized series. For more information, see [Multiplicative Winters Exponential Smoothing](#) which includes:

- Oracle Winters
- Oracle Winters Decomposition
- Winters Standard
- Winters Responsive

Additive Seasonal

Also referred to as Additive Winters Model, this model is similar to the Multiplicative Winters model, but is used when zeros are present in the data. This model adjusts the

un-seasonalized values by adding the seasonal index (for the forecast horizon). For more information, see [Additive Winters Exponential Smoothing](#).

SeasonalES

This method, a combination of several Seasonal methods, is generally used for known seasonal items or forecasting for long horizons. This method applies the Multiplicative Seasonal model unless too many zeros are present in the data, in which case the Additive Winters model of exponential smoothing is used. If less than two years of data is available, a Seasonal Regression model is used. If there is too little data to create a seasonal forecast (in general, less than 52 weeks), the system selects from the SimpleES, TrendES, and IntermittentES methods. For more information, see [Seasonal Exponential Smoothing \(SeasonalES\)](#).

Seasonal Regression

Seasonal Regression cannot be selected as a forecasting method, but is a candidate model that is used only when the SeasonalES method is selected. This model requires a minimum of 52 weeks of history to determine seasonality. Simple Linear Regression is used to estimate the future values of the series based on a past series.


The independent variable is the series history one-year or one cycle length prior to the desired forecast period, and the dependent variable is the forecast. This model assumes that the future is a linear combination of itself one period before plus a scalar constant. For more information, see [Seasonal Regression](#).

Forecast Administration Workbook

To build the Forecast Administration workbook, perform these steps:

1. Click the New Workbook icon in the Forecast Administration task in the Core Forecasting activity.


Figure 9–1 Forecast Administration Task



2. The Workbook wizard opens. Select the forecast level you want to work with and click **Finish**.

Note: The final forecast level is a level at which approvals and data exports can be performed. Depending on your organization's setup, you may be offered a choice of several final forecast levels. Make the appropriate selection.

Figure 9–2 Workbook Wizard: Select Forecast Level



The Forecast Administration workbook is built.


Forecast Administration Workbook: Basic Settings

The Forecast Administration Basic Settings workbooks contains two views:

- [Final Level View - Basic Settings](#)
- [Final and Source Level Parameters View - Basic Settings](#)

Final Level View - Basic Settings

The Final Level view allows you to set the forecast horizon information, frequency of review, and all default parameters for the lower or final-level forecast (the level to which aggregate forecast data is ultimately spread). Forecast approvals and data exports can only be performed on forecasts at a final-level. [Figure 9–3](#) provides an example of a view of the Final Level Parameters view in a master domain with three partitions/local domains, partitioned based on group.

Figure 9–3 Final Level Parameters View

Measures: Final Level View - Basic Settings

The Final Level View - Basic Settings contains the following measures:

Default Approval Method

This field is a list from which you select the default automatic approval policy for forecast items. Valid values are:

Field	Description
Manual	The system-generated forecast is not automatically approved. Forecast values must be manually approved by accessing and amending the Forecast Approval Workbook .
Automatic	The system-generated quantity is automatically approved as is.
By Alert	This list of values may also include any Forecast Approval alerts that have been configured for use in the forecast approval process. Alerts are configured during the implementation. Refer to the <i>Oracle Retail Predictive Application Server Configuration Tools User Guide</i> for more information on the Alert Manager.

Default Return Forecast Flag

If this Boolean measure is checked, it indicates that a returns forecast will be generated.

Default Return Forecast Percentage

This measure indicates the percentage of the merchandise sold in a time period that is expected to be returned to the store. A value of zero indicates that no returns will be calculated.

Default Return Forecast Time Shift

This measure indicates the number of time periods between when the merchandise was sold until it was returned. For instance, if the measure is set to one, the merchandise is expected to be returned one week after it was sold.

Default Source Level

The pick list of values displayed in this field allows you to change the forecast level that is used as the primary level to generate the source forecast. The source-levels are set up in the RPAS Configuration Tools. A value from the pick list is required in this field at the time of forecast generation.

Forecast Cycle

The Forecast Cycle is the amount of time (measured in days) that the system waits between each forecast generation. Once a scheduled forecast has been generated, this field is used to automatically update the Next Run Date field. A non-zero value is required in this field at the time of forecast generation.

Forecast Start Date

This is the starting date of the forecast. If no value is specified at the time of forecast generation, the system uses the data/time at which the batch is executed as the default value. If a value is specified in this field and it is used to successfully generate the batch forecast, this value is cleared.

Forecast Length

The Forecast Length is used with the Forecast Start Date to determine forecast horizon. The forecast length is based on the calendar dimension of the final-level. For example, if the forecast length is to be 10 weeks, the setting for a final-level at day is 70 (10 x 7 days).

Next Run Date

The Next Run Date is the date on which the next batch forecast generation process automatically runs. RDF automatically triggers a set of batch processes to be run at a pre-determined time period. When a scheduled batch is run successfully, the Next Run Date automatically updates based on the Start Date value and the Forecast Cycle. No value is required in this field when the [Run Batch Forecast Workbook](#) wizard is used to generate the forecast or if the batch forecast is run from the back-end of the domains using the override *True* option. Refer to the *Oracle Retail Demand Forecasting Implementation Guide* for more information on forecast generation.

Final and Source Level Parameters View - Basic Settings

The Final and Source Level view allows you to set the default parameters that are common to both the final and source-level forecasts.

Figure 9–4 Final and Source Level Parameters View

	1 - itm/str	2 -	3 -	4 -	5 -	9 -
Forecast Data Source	pos	pos	pos	pos	pos	pos
Default History Start Date						
Default Forecast Method	Simple	AutoE5	AutoE5	AutoE5	AutoE5	AutoE5
Data Plan						
Seasonal Profile						
Spreading Profile			01	03	05	19

Measures: Final and Source Level Parameters View - Basic Settings

The Final and Source Level Parameters View - Basic Settings contains the following measures:

Forecast Data Source

This is a read-only value that displays the sales measure (the measure name) that is the data used for the generation of forecasts (for example, POS). The measure that is displayed here is determined at configuration time in the RPAS Configuration Tools. Different Data Sources can be specified for the Final and Source Levels.

Default History Start Date

This field indicates to the system the point in the historical sales data at which to use in the forecast generation process. If no date is indicated, the system defaults to the first date in your calendar. It is also important to note that the system ignores leading zeros that begin at the history start date. For example, if your history start date is January 1, 2011 and an item/location does not have sales history until February 1, 2011, the system considers the starting point in that item/location's history to be the first data point where there is a non-zero sales value. Different History Start Dates can be specified for the Final and Source Levels.

Data Plan

Used in conjunction with the Bayesian forecast method, Data Plan is used to input the measure name of a sales plan that should be associated with the final-level forecast. Sales plans, when available, provide details of the anticipated shape and scale of an item's selling pattern. If the Data Plan is required, this field should include the measure name associated with the Data Plan.

Default Forecast Method

The Default Forecast Method is a complete list of available forecast methods from which you can select the primary forecast method that is used to generate the forecast. A summary of methods is provided in [Forecasting Methods Available in RDF](#). The chapter, "[Oracle Retail Demand Forecasting Methods](#)", covers each method in greater detail.

It is important to note that Causal should not be selected unless the forecast level was set as a Causal level during the configuration. Refer to the *Oracle Retail Demand Forecasting Configuration Guide* for more information on configurations using the Causal forecast method.

Seasonal Profile

Used in conjunction with the Profile-Based forecasting method, this is the measure name of the seasonal profile that is used to generate the forecast at either the source or final-level. Seasonal profiles, when available, provide details of the anticipated seasonality (shape) of an item's selling pattern. The seasonal profile can be generated or loaded, depending on your configuration. The original value of this measure is set during the configuration of the RDF solution.

Spreading Profile

Used for source-level forecasting, the value of this measure indicates the profile level that is used to determine how the source-level forecast is spread down to the final-level. No value is needed to be entered at the final-level. For dynamically generated profiles, this value is the number associated with the final profile level (for example, 01). Note that profiles one (1) through 9 have a zero (0) preceding them in Curve—this is different than the forecasting level numbers.

For profiles that must be approved, this is the measure associated with the final profile level. This measure is defined as apvp +level (for example, apvp01 for the approved profile for level 01 in Curve).

Source Level Forecast Data Source

You can specify a measure to serve as a forecast data source at the source-level. If the measure is left blank for a certain source-level, the source measure from the corresponding final-level is used.

Source Level History Start Date

This is the starting date for historical sales data at the source-level. For example, if your system start date is January 1, 2003, but you only want to use historical sales data from the beginning of 2011, you need to set your History Start Date to January 1, 2011. Only history after this date is used for generating the forecast. The default is the system start date unless otherwise specified. If sales data is collected weekly or monthly, RDF generates forecasts only using data from sales periods after the one containing the history start date.

It is also important to note that the system ignores leading zeros that begin at the history start date. For example, if your history start date is January 1, 2011, and an item/location does not have sales history until February 1, 2011, the system considers the starting point in that item/location's history to be the first data point where there is a non-zero sales value.

Note: History start dates for final and source-levels can be different.

Forecast Administration Workbook: Advanced Settings

The Forecast Administration Advanced Settings workbooks contain these views:

- [Causal Parameters View - Advanced Settings](#)
- [Final Level Parameters View - Advanced Settings](#)
- [Final and Source Level Parameters View - Advanced Settings](#)
- [Regular Price Parameters View- Advanced Settings](#)
- [Promo Affinity Parameters View- Advanced Settings](#)
- [Demand Transference Parameters View- Advanced Settings](#)

The Forecast Administration Advanced Settings workflow activity is used to set parameters related to either the data that is stored in the system or the forecasting methods that are used at the final or source-levels. The parameters on this workflow activity are not as likely to be changed on a regular basis as the ones on the Basic Settings workflow activity.

Causal Parameters View - Advanced Settings

The Causal Parameters view allows you to set the parameters that support promotional forecasting. The parameters that support overlapping promotions are also specified in this view. Overlapping promotions are promotions that happen at the same time period at the same location for the same product. This view only includes the causal forecast levels for the final-level selected during the wizard process. This view is not visible if Promote/Promotional Forecasting is not implemented in your RDF environment.

Figure 9–5 Causal Parameters View

Parameter	Value
Causal Aggregation Profile	07 - itm1str
Causal Data Source	
Causal Calculation Intersection	
Causal Calculation Intersection Periodicity	0
Causal Higher Intersection	
Disable Causal	<input type="checkbox"/>
Causal Spread Profile	
Use Causal Capping	<input type="checkbox"/>
Causal Capping Number	
Causal Capping Ratio	
Minimum Causal Capping History (Periods)	0
Causal External Baseline	
Causal SLC - ROS	
Causal - Effects Only	<input type="checkbox"/>
Default Overlapping Promotions Behavior	Adjustable ...
Default Overlapping Promotion Adjustment Factor	1.00

Measures: Causal Parameters View - Advanced Settings

The Causal Parameters View - Advanced Settings contains the following measures:

Aggregated Promotional Lift Override

This parameter contains the name of the measure that stores the higher level (aggregated) promotional peak override. The name is implementation specific. If populated, during the causal forecasting generation the aggregated lift is spread down to the appropriate final level intersection.

Causal - Effects Only

If Causal - Effects Only is set to *True*, the Causal forecasting method will only calculate promotional effects, and will not generate the forecast. If the measure is not set to *True*, then the Causal forecasting method generates promotional effects and forecasts.

Causal - Lift Estimate

The parameter gives you the option to use either the multiplicative or hybrid models to decausalize the sales history.

- **Multiplicative**—this model extracts promotional lifts that are assumed to have multiplicative effects in order to de-causalized the history.
- **Hybrid**—this model extracts the promotional lifts as additive effects in the de-causalized phase to decausalize the history. Then later in the forecast phase, it applies the promotional lifts as multiplicative effect to the forecast baseline. This is the system default value.

Causal Aggregation Profile

Used only for Daily Causal Forecasting, the Causal Aggregation Profile is measure name of the profile used to aggregate promotions defined at day up to the week. The value entered in this field is the measure name of profile. If this profile is generated within Curve, the format of the measure name is apvp+level (for example, apvp01). Note that the only aggregation of promotion variables being performed here is along the Calendar hierarchy. RDF does not support aggregation of promotion variables along other hierarchies such as product and location hierarchies.

Causal Beta Scale

As part of the causal forecasting process, the average sales of non-promo periods in history are divided by the Beta Scale. If the resulting ratio is less than beta zero, the

causal forecasting method succeeds. If not, the causal forecasting method fails and the baseline serves as the forecast for the time series.

Causal Calculation Intersection

Used only for Daily Causal Forecasting, the Causal Calculation Intersection is the intersection at which the causal forecast is run. The format needs to match the hierarchy dimension names set in the RPAS Configuration Tools (such as itemstr_week). Each dimension must have only four characters. The order of the dimension does not matter. There is no validation of correct format of this intersection.

Causal Calculation Intersection Periodicity

Used only for Daily Causal Forecasting, the Causal Calculation Intersection Periodicity must be set to the periodicity of Causal Calculation Intersection. Periodicity is the number of periods within one year that correspond to the calendar dimension (for example, 52 if the Causal Calculation Intersection is defined with the week dimension).

Causal Capping Number

The value of this parameter is a measure based on the same product and location intersection as the forecast level. This measure contains the maximum value to use for calculating the causal forecast for time series that meet the Causal Capping conditions. If Use Causal Capping is set to *True*, the history for the time series is greater than or equal to the Minimum Causal Capping History, and the preliminary forecast is greater than or equal to the value in the Causal Capping Number measure, then the forecast is recalculated to be the value in the Causal Capping Number measure multiplied by the value in the Causal Capping Ratio measure.

Causal Capping Ratio

The value of this parameter is a measure based on the same product and location intersection as the forecast level. This measure contains the ratio to be used to calculate the forecasts for time series that meet the Causal Capping conditions. If Use Causal Capping is set to *True*, the history for the time series is greater than or equal to the value in the Minimum Causal Capping History measure, and the preliminary forecast is greater than or equal to the value in the Causal Capping Number measure, then the forecast is recalculated to be the Causal Capping Number multiplied by the value in the Causal Capping Ratio measure.

Causal Data Source

Used only for Daily Causal Forecasting, the Causal Data Source is an optional setting that contains the measure name of the sales data to be used if the data for causal forecasting is different than the Data Source specified at the Final level. If needed, this field should contain the measure name of the source data measure (for example, DPOS).

If set to *True*, Seasonal Regression is excluded from the choice of methods for baseline calculation within Causal.

Note: This parameter does not impact the choice of forecast methods within Seasonales.

Causal External Baseline

Enter the measure name that you want to serve as the baseline for the causal forecast at this level. The measure can be loaded or it can be generated in a different forecast run.

Causal Higher Intersection

An optional setting for Causal Forecasting, this intersection is the aggregate level to model promotions if the causal intersection cannot produce a meaningful causal effect. This intersection applies to promotions that have a Promotion Type is set to Override From Higher Level (set in the [Promo Effect Maintenance Workbook](#)). The format of this intersection needs to match the hierarchy dimension names set in the RPAS Configuration Tools such as sclsrn_ (Subclass/Region), and it must not contain the calendar dimension. Each dimension must have only four characters. The order of the dimension does not matter. There is no validation of correct format of this intersection.

Causal SLC - ROS

Enter the name of the measure that stores the rate of sale values for item/locations that are forecast using the Causal short life cycle methodology.

Causal Spread Profile

Used only for Daily Causal Forecasting, the Causal Spread Profile is the measure name of the profile used to spread the causal baseline forecast from the Causal Calculation Intersection to the Final Level. If this profile is generated in Curve, this measure value is apvp+level (for example, apvp01).

Default Overlapping Promotion Adjustment Factor

The Overlapping Promotion Behavior measure is applied only if [Adjustable Approach](#) is selected for [Default Overlapping Promotions Behavior](#).

This Default Overlapping Promotion Adjustment Factor specifies at a high level how the individually calculated promotions interact with each other when they are overlapping in the forecast horizon. This parameter serves as a global setting, but can be overridden at lower levels. The default value is 1.

- A value greater than 1 means the promotion effects will be compressed when applied in the model, instead of linearly summing up to get the total promotion effect. The larger the value is, the larger the compression effect will be, meaning the smaller the total effect will be.
- A value between 0 and 1 means the promotion effects will be amplified when applied in the model, instead of linearly summing up to get the total promotion effect. The smaller the value is, the larger the amplification effect will be, meaning the larger the total effect will be.
- If a value less than or equal to 0 is put in the cell, the calculation engine will find the best adjustment factor to fit the history data. This factor is then used to combine overlapping promotions in the forecast horizon. With few exceptions, the value should be anywhere from 1 to 5. This factor is then used to combine overlapping promotions in the forecast horizon

Caution: The process to find the best adjustment factor can be time consuming and introduce performance issues.

Default Overlapping Promotions Behavior

The Overlapping Promotion Behavior measure allows you to specify if overlapping promotions function should be activated during the batch run. If so, the causal algorithm will create a new promotion for each unique combination of promotions in the history. The new promotions are used in the stepwise regression, and they are used in calculating the forecast if they are found significant. The new promotion combinations are temporary. This parameter serves as a global setting, but can be overridden at lower levels.

The Default Overlapping Promotions Behavior allows you to specify at a high level if overlapping promotion calculate engine should be called during the batch run. The options are Enhanced Approach and Adjustable Approach:

- **Enhanced Approach**

This approach means overlapping promotion function will be activated and the calculation engine will search in the sales history to create new promotions for different promotion combinations.

This approach should be selected if the retailer has well established, reliable promotion history.

- **Adjustable Approach**

This approach means that overlapping promotion function will not be activated. Each promotion's effect is calculated individually in the stepwise regression, and RDF will apply the Adjustable Factor (link) when overlapping happens in the forecast horizon.

This approach should be used when the promotion history is not well established and less reliable.

It should be noted that just because the overlapping promotion function is activated, it does not necessarily imply an overlapping promotional forecast result. In some instances, it is possible that no overlapping promotions are found to be statistically significant. The indicator of the significant overlapping promotions' existence can be viewed within the [Forecast Approval Workbook](#).

Note: Only Boolean type promotions and Real type promotions with the value of one (1) can be considered the candidates of overlapping promotions. Other types of promotions effect will be applied separately.

Disable Causal

Place a check in this parameter (set to *True*) if causal forecasting is to be disabled for the forecast level. This parameter serves as a global override. This parameter can also help with performance when not running Causal forecast method.

Minimum Causal Capping History

Used only in Causal forecasting, this parameter is the minimum number of historical time periods that are required for Causal Capping to be used to produce the Causal forecast. Otherwise, no capping is applied. The algorithm currently uses 52 weeks of history as the default for this parameter.

Minimum Causal Capping History (Periods)

If Use Causal Capping is set to *True*, this parameter is used to set minimum number of historical time periods required before the system considers a time series for causal capping.

Use Causal Capping

Place a check in this parameter (set to *True*) if capping is to be applied to the causal forecast. Also required for causal capping are the following parameters:


- Causal Capping Number
- Causal Capping Ratio
- Minimum Causal Capping History

Note: More detailed information on the Causal forecasting algorithm is provided in [Forecasting Methods Available in RDF](#).

Final Level Parameters View - Advanced Settings

The Final Level view allows you to set the advanced parameters for the final-level forecasts. [Figure 9–6](#) provides an example of a view of this view in a master domain with three partitions/Local Domains, partitioned based on group.

Figure 9–6 Final Level Parameters View



Measures: Final Level Parameters View - Advanced Settings

The Final Level Parameters view - Advanced Settings contains the following measures:

Components - Baseline

This measure stores the name of the measure that serves as baseline in the Components forecasting measure. If no measure is specified, the Components forecasting method assesses the value as one (1).

Components - Baseline Interval

This measure stores the name of the measure that serves as baseline interval in the Components forecasting measure. If no measure is specified, the Components forecasting method assesses the value as one (1).

Components - Regular Price Lifts

This measure stores the name of the measure that serves as regular price lifts in the Components forecasting measure. If no measure is specified, the Components forecasting method assesses the value as one (1).

Components - Promotional Lifts

This measure stores the name of the measure that serves as promotional lifts in the Components forecasting measure. If no measure is specified, the Components forecasting method assesses the value as one (1).

Days to Keep Forecasts

This field is used to set the number of days that the system stores forecasts based on the date/time the forecast is generated. The date/time of forecast generation is also referred to as birth date of the forecast. A forecast is deleted from the system if the birth date plus the number of days since the birth date is greater than the value set in the Days to Keep Forecast parameter. This process occurs when either the [Run Batch Forecast Workbook](#) wizard is used to generate the forecast or when PreGenerateForecast is executed.

When you start the [Run Batch Forecast Workbook](#), one of the first steps that RDF takes is to remove forecasts older than the value given in the Days to Keep Forecasts parameter. RDF uses the value of that parameter in your local domain. However, because forecasts are registered globally, the Forecast Delete has a global effect. That is, if you set the parameter to some low value, for example, one day, all forecasts in all local domains older than one day are removed. This can adversely impact other users of the system if done without consideration.

When the PreGenerate utility is used, typically for automated batch production of forecasts, RDF uses the value for the Days to Keep Forecasts parameter in the first local domain. Again, if this is set to a value that is not expected by the other users, it can cause unintended disruption.

Refer to the *Oracle Retail Demand Forecasting Implementation Guide* for more information on PreGenerateForecast.

Default Apply Interaction Factor

When generating the forecast, there are three possible lifts added on top of the baseline to get the final result. They are promotion lift, regular price change lift, and demand transference lift. The Default Apply Interaction Factor measure allows you to specify at a high level if these individually calculated lifts should interact with each other during the forecast generation. This parameter serves as a global setting, but can be overridden at lower levels.

A check in this field (set to True) indicates if you want RDF to combine the promotion, regular price, and demand transference lifts. The impact of the combination can be adjusted in the [Default Interaction Factor](#) measure.

Otherwise, by clearing the box (set to False) these effects will be linearly added to the baseline to generate the forecast. By default, the value is set to False. The calculated lifts can be viewed in the [Forecast Approval Workbook](#).

Default Interaction Factor

The Interaction Factor is applied only if the [Default Apply Interaction Factor](#) measure is set to True.

This Default Interaction Factor specifies at a high level how the individually calculated promotion lift, regular price change lift and demand transference lift interact with each other during the forecast generation process. This parameter serves as a global setting, but can be overridden at lower levels. The default value is 2.

- A value equal to 1 means that each lift will be summed up to calculate the total lift.
- A value greater than 1 means the lifts will be compressed when applied in the model, instead of linearly summing up to get the total lift. The larger the value is, the larger the compression effect will be, meaning the smaller the total lift will be.
- A value between 0 and 1 means the lifts will be amplified when applied in the model, instead of linearly summing up to get the total lift. The smaller the value is, the larger the amplification effect will be, meaning the larger the total lift will be.

Note that if Apply Interaction Factor is set to True and the Interaction Factor is set to a value other than 1, you should expect to see the combined effects for Demand Transference, Promotion, and Regular Price in the [Forecast Approval Workbook](#).

Default Keep Last Changes

This field is a list from which you select the default change policy for forecast items. Valid values are:

Field	Description
Keep Last Changes (None)	There are no changes that are introduced into the adjusted forecast. The adjusted forecast is equal to the system forecast.
Keep Last Changes (Total)	This method allows you to keep previous adjusted forecast value if there is any adjustment existing. For each product/location/week in the forecast horizon, when the last approved system forecast is different from last approved forecast, it means that you have made an adjustment previously. The last approved forecast is used to populated the current adjusted forecast. If the last approved system forecast is the same as last approved forecast, it means that you have not made any adjustment previously and the current adjusted forecast will be populated with current system forecast.
Keep Last Changes (Diff)	This method allows you to keep the difference between previous adjusted forecast and system forecast if there is any adjustment existing. For each product/location/week in the forecast horizon, when last approved system forecast is different from last approved forecast, it means that you have made an adjustment previously. The last approved forecast minus the last approved forecast plus the current system forecast is used to populated the current adjusted forecast. If the last approved system forecast is the same as last approved forecast, it means that you have not made any adjustment previously and the current adjusted forecast will be populated with current system forecast.

Field	Description
Keep Last Changes (Ratio)	This method allows you to keep the ratio of last adjusted forecast versus the last system forecast if there is any adjustment existing. For each product/location/week in the forecast horizon, when the last approved system forecast is different from last approved forecast, it means that you have made an adjustment previously. The last approved forecast/last approved system forecast multiplied by the current system forecast is used to populated the current adjusted forecast. If the last approved system forecast is the same as last approved forecast, it means that you have not made any adjustment previously and the current adjusted forecast will be populated with current system forecast.

Note: Populating adjusted forecast is the 5th step of the "[Batch Flow Process in RDF](#)". Populating adjusted forecast happens before forecast approval. At the time of applying keep last changes, the approved forecast and approved system forecast contains forecast values from last batch. At that moment, RDF checks the value of approved forecast, approved system forecast and current system forecast to populate the adjusted forecast. Once forecast approval is done, approved forecast and approved system forecast is populated with current forecast values.

Generate Baseline Forecasts

A check should be indicated in this field (set to *True*) if the baseline forecast is to be generated to be viewed in any task. This parameter should be set if the level is used for Causal forecasting and the baseline is needed for analysis purposes.

Generate Cumulative Interval

A check in this field (set to *True*) specifies whether you want RDF to generate cumulative intervals (this is similar to cumulative standard deviations) during the forecast generation process. Cumulative Intervals are a running total of Intervals and are typically required when RDF is integrated with the Oracle Retail Merchandising System. If you do not need cumulative intervals, you can eliminate excess processing time and save disk space by clearing the check box. The calculated cumulative intervals can be viewed within the [Forecast Approval Workbook](#).

Generate Intervals

A check in this field (set to *True*) indicates that intervals (similar to Standard Deviations) should be stored as part of the batch forecast process. Intervals can be displayed in the [Forecast Approval Workbook](#). If you do not need intervals, excess processing time and disk space may be eliminated by clearing the check box. For many forecasting methods, intervals are calculated as standard deviation, but for Simple, Holt, and Winters the calculation is more complex. Intervals are not exported.

Generate Methods

A check in this field (set to *True*) indicates that when an ES forecast method is used, the chosen forecast method for each fitted time series should be stored. The chosen method can be displayed in the [Forecast Approval Workbook](#).

Generate Parameters

A check in this field (set to *True*) indicates that the alpha, level, and trend parameters for each fitted time series should be stored. These parameters can be displayed in the [Forecast Approval Workbook](#).

Interval Cap Lower Ratio

The value entered in this field multiplied by the forecast represents the lower bound of the confidence interval for a given period in the forecast horizon.

Interval Cap Upper Ratio

The value entered in this field multiplied by the forecast represents the upper bound of the confidence interval for a given period in the forecast horizon.

Item End Date Action

This parameter allows the option for items with end dates within the horizon to have zero demand applied to time series before or after the interim forecast is calculated. The two options are:

Option	Description
Apply 0 After Spreading	This is the default value. Spreading ratios are calculated for time series with no consideration made to the end date of an item. It is after the source forecast is spread to the final-level when zero is applied to the System Forecast.
Apply 0 to Interim	For items that have an end date within the forecast horizon, zero is applied to the Interim Forecast before the spreading ratios are calculated. This ensures that no units are allocated to the final-level for time series that have ended.

Like TS Duration (Periods)

The Like TS Duration is the number of periods of history required, after which RDF stops using the substitution method and starts using the system forecast generated by the forecast engine. A value must be entered in this field if using Like-item/Sister-Store functionality. When the difference between the forecast start date and the history start date is greater than the Like TS Duration, RDF starts using the system forecast for the item.

The Like TS Duration determines for how long RDF applies the Like-item/Sister-Store functionality. In general, the difference between history start date and the forecast start date is compared to the Like TS Duration. If the difference is larger than the Like TS Duration, it means that the new item has been selling for a period long enough, such that RDF can create the forecast based on its own history.

The forecast start date has an override, which is usually used whenever the forecast start date is checked.

However, in the case of Like-item/Sister-Store, if the override references a date prior to the forecast start date, the forecast start date - instead of the override - is used when calculating the difference and comparing it to the Like TS Duration.

The reason behind this exception is that the override does not change unless it is initiated by a user. Hence, the difference between forecast start date override and history start date is always the same, so the Like-item functionality is always in effect.

If the override is ignored, the forecast start date is advancing every period, so the difference between it and history start date is always growing. Eventually it will

become larger than the Like TS Duration, and thus turning off the Like-item functionality for the item.

Store Interim Forecast

A check should be placed in this field (set to *True*) if the interim forecast is stored. The Interim Forecast is the forecast generated at the Final Level. This forecast is used as the Source Data within Curve to generate the profile (spreading ratios) for spreading the source-level forecast to the final-level. The interim forecast should only be stored if it is necessary for any analysis purposes.

Updating Last Week Forecast

This field is a list from which you can select the method for updating the Approved Forecast for the last specified number of weeks of the forecast horizon. This option is valid only if the Approval Method Override (set in the [Forecast Administration Workbook](#)) is set to Manual or Approve by alert, and the alert was rejected. This parameter is used with the Updating Last Week Forecast Number of Weeks parameter.

Method	Description
No Change	When using this method, the last week in the forecast horizon does not have an Approved Forecast value. The number of weeks is determined by the value set in the Updating Last Week Forecast Number of Weeks parameter.
Replicate	When using this method the last week in the forecast horizon is forecast using the Approved Forecast for the week prior to this time period. To determine the appropriate forecast time period, the value set in Updating Last Week Forecast Number of Weeks is subtracted from the Forecast Length. For example, if your Forecast Length is set to 52 weeks and Updating Last Week Forecast Number of Weeks is set to 20, week 32's Approved Forecast is copied into the Approved Forecast for the next 20 weeks.
Use Forecast	When using this method, the System Forecast for the last weeks in the forecast horizon is approved.

Updating Last Week Forecast Number of Weeks

The Approved Forecast for the last weeks in the forecast horizon is updated using the method specified from the Updating Last Week Forecast list.

Final and Source Level Parameters View - Advanced Settings

The Final and Source Level view allows you to set the advanced parameters that are common to both the final and source-level forecasts.

Figure 9–7 Final and Source Level Parameters View

	11 - itm/str/week-	12 - sclcs/rgn/week
Default Bayesian Alpha	1.00	1.00
Bayesian Cap Ratio	1.50	1.50
DD Duration (Periods)	0	0
Max Alpha (Profile)	1.00	1.00
Max Alpha (Simple Holt)	1.00	1.00
Max Alpha (Winters)	1.00	1.00
Crostons Min Gaps	5	5
Holt Min Hist (Periods)	13	13
Winters Min Hist (Periods)	104	104
Trend Damping Factor	0.50	0.50
Fall Back Method	Default	Default
Seasonal Smooth Index	0.80	0.80
Default Winters Mode	Oracle Winters	Oracle Winters
Default Moving Average Window Length	0	0
Max Gamma (Winters)	0.20	0.20
Max Gamma (Holt)	0.20	0.20
Deseasonalized Demand Array		
Extra Week Interpret Method	Use average	Use average
Extra Week Indicator Data Source	week53mask	week53mask
Fit Error Factor Source		

Measures: Source Level View - Advanced Settings

The Source Level View - Advanced Settings contains the following measures:

Bayesian Alpha (range (0, infinity))

When using the Bayesian forecasting method, historic data is combined with a known sales plan in creating the forecast. As POS data comes in, a Bayesian forecast is adjusted so that the sales magnitude is a weighted average between the original plan's scale and the scale reflected by known history. This parameter displays the value of alpha (the weighted combination parameter). An alpha value closer to one (or infinity) weights the sales plan more in creating the forecast, whereas alpha closer to zero weights the known history more. The default is one (1).

Bayesian Cap Ratio

The Bayesian Cap ratio is used to cap the resulting Bayesian forecast if it deviates significantly from the sale plan. The Bayesian Cap ratio is used as follows:

Example 9–1

```
If forecast I > Bayesian Cap ratio * Max value of Past Sales AND
forecast I > Bayesian Cap ratio * Max value of Past Plan AND
forecast I > Bayesian Cap ratio * Plan I
then
forecast I = Plan I
```

It defaults to a value of 1.5.

Croston's Min Gaps

The Croston's Min Gaps is the default minimum number of gaps between intermittent sales for the batch forecast to consider Croston's (Simple/IntermittentES) as a potential AutoES forecasting method for a time series. If there are not enough gaps between sales in a given product's sales history, the Croston's model is not considered a valid candidate model. The system default is five minimum gaps between intermittent sales.

The value must be set based on the calendar dimension of the level. For example, if the value is to be 5 weeks, the setting for a final-level at day is 35 (5x7days) and a source-level at week is 5.

DD Duration (weeks)

Used with Profile Based forecast method, the DD Duration is the number of weeks of history required after which the system stops using the DD (De-seasonalized Demand) approach and defaults to the normal Profile-Based method. The value must be set based on the calendar dimension of the level. For example, if the value is to be 10 weeks, the setting for a final-level at day is 70 (10x7days) and a source-level at week is 10.

Default Moving Average Window Length

Used with Moving Average forecast method, this is the Default number of data points in history used in the calculation of Moving Average. This parameter can be overwritten at item/location from the [Forecast Maintenance Workbook](#).

Deseasonalized Demand Array

Enter the name of the measure that serves as the deseasonalized data source in the profile-based forecasting method. If left blank, the system uses the forecast data source in combination with a seasonal profile to generate the deseasonalized demand.

Extra Week Interpret Method

This measure indicates how the forecasting value should be calculated if for a week that was flagged extra, or 53rd. This is necessary when an extra week is added within the forecast horizon, because initially no value is calculated for that week.

The options to calculate the value are:

- Use average: the value for the extra week is calculated as the average of the values of the weeks immediately prior and after the flagged week.
- Use before: the value for the extra week is a replication of the value in the previous week
- Use after: the value for the extra week is equal to the value of the following week

Extra Week Indicator Data Source

This measure stores the name of the measure that indicates which week is the 53rd, or extra week. To set this measure, use the [Extra Week Indicator](#) found in the [Extra Week Administration Workbook](#).

Fit Error Factor Source

The measure stores the measure name that error factor of sales vs forecast. This measure needs to be at the intersection of the final forecast level, less the calendar dimension, example, item/store.

The Error Factor is necessary for the calculation of the Confidence Intervals.

For the majority of the forecasting methods, the error factor is calculated during forecast generation, but for the following methods the calculation is not possible and needs to be input:

- Copy
- LoadPlan
- Component

Fallback Method

Set this parameter only if the Fallback Method is to vary from the default Fallback Methods used by the selected forecasting algorithm. If the method selected as the Default Forecast Method or Forecast Method Override does not succeed for a time series, this method is used to calculate the forecast and the default Fallback Methods in the forecasting process is skipped entirely. The default Fallback Methods are as follows:

Table 9–1 Fallback Methods

Fallback Method	Steps
If either the Causal, Bayesian, or Profile-Based are selected as the Default Forecast Method or Forecast Method Override and the method does not fit the data.	<ol style="list-style-type: none"> 1. RDF attempts to fit SeasonalES 2. RDF attempts to fit TrendES 3. RDF attempts to fit Simple/IntermittentES
If the SeasonalES is selected as the Default Forecast Method or Forecast Method Override and neither Multiplicative Seasonal or Additive Seasonal fits the data.	<ol style="list-style-type: none"> 1. RDF attempts to fit TrendES 2. RDF attempts to fit Simple/IntermittentES
If either the Multiplicative Seasonal or Additive Seasonal are selected as the Default Forecast Method or Forecast Method Override and the method does not fit the data.	<ol style="list-style-type: none"> 1. RDF attempts to fit TrendES 2. RDF attempts to fit Simple/IntermittentES
If the TrendES is selected as the Default Forecast Method or Forecast Method Override and the method does not fit the data.	<ol style="list-style-type: none"> 1. RDF attempts to fit Simple/IntermittentES

Holt Min Hist (Periods)

Used with the AutoES forecast method, Holt Min Hist is the minimum number of periods of historical data necessary for the system to consider Holt (TrendES) as a potential forecasting method. RDF fits the given data to a variety of AutoES candidate models in an attempt to determine the best method; if not enough periods of data are available for a given item, Holt is not be considered as a valid option.

The system default is 13 periods. The value must be set based on the calendar dimension of the level. For example, if the value is to be 13 weeks, the setting for a final-level at day is 91 (13x7days) and a source-level at week is 13.

Max Alpha (Profile) (range [0,1])

In the Profile-based model-fitting procedure, alpha, which is a model parameter capturing the level, is determined by optimizing the fit over the de-seasonalized time series. The time series is de-seasonalized based on a seasonal profile. This field displays the maximum value (that is, cap value) of alpha allowed in the model-fitting process. An alpha cap value closer to one (1) allows more reactive models (alpha = 1, repeats the last data point), whereas alpha cap closer to zero (0) only allows less reactive models. The default is one (1).

Max Alpha (Simple, Holt) (range [0,1])

In the Simple or Holt (TrendES) model-fitting procedure, alpha (a model parameter capturing the level) is determined by optimizing the fit over the time series. This field displays the maximum value (cap value) of alpha allowed in the model-fitting process. An alpha cap value closer to one (1) allows more reactive models (alpha = 1, repeats the last data point), whereas alpha cap closer to zero (0) only allows less reactive models. The default is one (1).

Max Alpha (Winters) (range [0,1])

In the Winters (SeasonalES) model-fitting procedure, alpha (a model parameter capturing the level) is determined by optimizing the fit over the time series. This field displays the maximum value (cap value) of alpha allowed in the model-fitting process. An alpha cap value closer to one (1) allows more reactive models (alpha = 1, repeats the last data point), whereas alpha cap closer to zero (0) only allows less reactive models. The default is one (1).

Max Gamma (Holt) (range [0,1])

In the Holt (TrendES) model-fitting procedure, gamma (a model parameter capturing the trend) is determined by optimizing the fit over the time series. This field displays the maximum value (cap value) of gamma allowed in the model-fitting process.

Max Gamma (Winters) (range [0,1])

In the Winters (SeasonalES) model-fitting procedure, gamma (a model parameter capturing the trend) is determined by optimizing the fit over the time series. This field displays the maximum value (cap value) of gamma allowed in the model-fitting process.

Seasonal Smooth Index

This parameter is used in the calculation of seasonal index. The current default value used within forecasting is 0.80. Changes to this parameter impacts the value of seasonal index directly and impact the level indirectly. When seasonal smooth index is set to one (1), seasonal index is closer to the seasonal index of last year sales. When seasonal smooth index is set to zero (0), seasonal index is set to the initial seasonal indexes calculated from history.

This parameter is used when the Winters Mode is set to Oracle Winters.

If the Winters Mode is Winters Standard, Winters Responsive, or Oracle Winters Decomposition, this parameter is optimized and your input value is ignored.

Trend Damping Factor (range [0,1])

This parameter determines how reactive the forecast is to trending data. A value close to zero (0) is a high damping, while a value of one (1) implies no damping. The default is 0.5.

Winters Min Hist (Periods)

Used with the AutoES forecast method, the value in this field is the minimum number of periods of historical data necessary for Winters to be considered as a potential forecast method. If not enough years of data are available for a given time series, Winters is not used. The system default is two years of required history. The value must be set based on the calendar dimension of the level. For example, if the value is to be 104 weeks/2 years, the setting for a final-level at day is 728 (104 weeks x 7 days) and a source-level at week is 104.

Winters Mode

When any forecast method calls multiplicative or additive Winters, the system executes the Winters forecasting approach indicated by the Winters Mode.

The Winters forecasting approaches are listed in [Table 9-2](#).

Table 9–2 Winters Forecasting Approaches

Winters Forecasting Approaches	Description
Oracle Winters (default approach)	Current or default seasonal forecasting approach, which uses a combination of Winters approach and decomposition. Decomposition allows level and trend to be optimized independently while maintaining a seasonal curve.
Oracle Winters Decomposition	Like Oracle Winters seasonal forecasting approach, Oracle Winters Decomposition uses a combination of Winters approach and decomposition. Key differences between Oracle Winters and Oracle Winters Decomposition include: <ul style="list-style-type: none"> ■ Seasonal smoothing factor is optimized. ■ The optimization places more importance on recent sales than historical sales. ■ Seasonal indices are recalculated based on optimization.
Winters Standard	The Standard Winters uses a standard Winters model, with no additional calculations. All three smoothing parameters are optimized.
Winters Responsive	Responsive Winters, like Standard Winters does not use decomposition and all three smoothing parameters are optimized. This approach is recommended for forecasting items with significant trends in the more recent historic sales. The difference between Winters Responsive and Winters Standard is: <ul style="list-style-type: none"> ■ Winters Responsive optimization places more importance on recent sales than historical sales.

Table 9–3 illustrates the key differences between the models.

Table 9–3 Comparison of Winters Forecasting Models

Forecasting Approach	Optimized to Recent Sales	Decomposition	Seasonal Smoothing Parameter Optimized
Oracle Winters	No	Yes	No
Oracle Winters Decomposition	Yes	Yes	Yes
Winters Standard	No	No	Yes
Winters Responsive	Yes	No	Yes

Winters Mode Impact on AutoES and Causal

The Winters Mode measure determines which Forecasting Approach to use within AutoES and Causal. Also, the errors that are used to calculate the BIC may be different for different Forecasting Approaches and could impact the choice of Forecast Method within AutoES and Causal.


It is recommended that you choose a Forecasting Approach that best suits the nature of your business. The default forecasting approach is Oracle Winters. For additional information on the forecasting approaches, refer to the [Forecasting Methods Available in RDF](#) section.

Note: If patching this change into a domain, in order to view this measure in the [Forecast Administration Workbook](#), you must add it to the [Final and Source Level Parameters View - Basic Settings](#) by selecting it from the Show/Hide dialog within the RPAS Client.

Regular Price Parameters View- Advanced Settings

The Regular Price Parameters view allows you to set the parameters that allow you to incorporate the effects of regular price changes within the forecast.

Figure 9–8 Regular Price Parameters View- Advanced Settings



Measures: Regular Price Parameters View- Advanced Settings

The Regular Price Parameters View- Advanced Settings contains the following measures:

Apply Regular Price Lift

This parameter serves as a global setting, but can be overridden at lower levels.

Select a value from the list for this parameter:

- **Do Not Apply**— no regular price lifts are incorporated in the forecast
- **Apply System** — the effects calculated in RDF are incorporated in the forecast
- **Apply Override** — the lifts calculated in RDF are ignored and the override lifts are incorporated

There are three components to the Regular Price Lift:

- **Self Lift** — determined by the regular price self elasticity
- **Cannibalization** — determined by the regular price cannibalization cross elasticity
- **Halo** — determined by the regular price halo cross elasticity

Apply Regular Price Lift over Promotion

Is only effective if [Apply Regular Price Lift](#) is set to **Apply System** or **Apply Override**. Place a check in this parameter (set to *True*) if the application of regular price lifts is enabled for time periods that are promoted. If the parameter is not checked, regular price lifts will not be applied for periods with promotions. This parameter serves as a global setting, but can be overridden at lower levels.


Regular Price Decaying Factor

This parameter determines how the magnitude of the price effects is applied over time.

A regular price change usually triggers a change in demand. However, the effect can be seen only for a few periods following the price change. An adjustable damping mechanism ensures that the regular price effect trends down as time goes by. The decaying factor is a number between zero (0) and one (1).

The closer the decaying factor is to zero (0), the faster the regular price effect decays.

Figure 9–9 Regular Price Decaying Effect



Apply Regular Price Self Lift

Is only effective if [Apply Regular Price Lift](#) is set to **Apply System** or **Apply Override**. Place a check in this parameter (set to *True*) if the application of regular price self lifts is enabled for the forecast level. This parameter serves as a global setting, but can be overridden at lower levels.

Apply Regular Price Halo Lift

Is only effective if [Apply Regular Price Lift](#) is set to **Apply System** or **Apply Override**. Place a check in this parameter (set to *True*) if the application of regular price Halo lifts is enabled for the forecast level. This parameter serves as a global setting, but can be overridden at lower levels.

Apply Regular Price Cannibalization Lift

Is only effective if [Apply Regular Price Lift](#) is set to **Apply System** or **Apply Override**. Place a check in this parameter (set to *True*) if the application of regular price cannibalization lifts is enabled for the forecast level. This parameter serves as a global setting, but can be overridden at lower levels.

Regular Price Effective Periods

Specifies the number of periods for which the regular price effect is applied.


Price Elasticity Matrix Data Source

Specifies the name of the measures that stores the regular price elasticities, such as gammas (rdfgamma). The measure name is implementation specific.

Promo Affinity Parameters View- Advanced Settings

The Promo Affinity Parameters View- Advanced Settings allows you to set parameters to decide if cross promotional elasticities are incorporated in the forecast.

Figure 9–10 Promo Affinity Parameters View- Advanced Settings



Measures: Promo Affinity Parameters View- Advanced Settings

The Promo Affinity Parameters View- Advanced Settings contains the following measures:

Apply Promotion Cannibalization Lift

Select this parameter (set to True) if the application of Cannibalization lifts is enabled for the forecast level. This parameter serves as a global setting, but can be overridden at lower-levels.

Apply Promotion Halo Lift

Select this parameter (set to True) if the application of Halo lifts is enabled for the forecast level. This parameter serves as a global setting, but can be overridden at lower-levels.

Cross Promo Cannibalization Change Ratio Source

This parameter contains the name of the measure that determines the percentage of the promotional lift that is going to cannibalize related items.

Note: This measure is specified at an intersection higher than item/store. The content of the measure is visible if you roll up to All Products on the product hierarchy. At a lower intersection the cell appears as a hash mark.

Cross Promo Cannibalization Max Change Ratio Source

This parameter contains the name of the measure that determines an item's maximum allowed drop in sales due to cannibalization. For instance if the sales of an item for a given period are 20 units, and the maximum allowed percentage is 20%, the drop in sales due to cannibalization for the period can not exceed 4 units.

Note: This measure is specified at an intersection higher than item/store. The content of the measure is visible if you roll up to All Products on the product hierarchy. At a lower intersection the cell appears as a hash mark.

Cross Promo Halo Change Ratio Source

This parameter contains the name of the measure that determines the percentage of the promotional lift that is going to increase demand of complimentary items due to halo effect.

Note: This measure is specified at an intersection higher than item/store. The content of the measure is visible if you roll up to All Products on the product hierarchy. At a lower intersection the cell appears as a hash mark.

Cross Promo Halo Max Change Ratio Source

This parameter contains the name of the measure that determines an item's maximum allowed increase in sales due to halo. For instance if the sales of an item for a given period are 15 units, and the maximum allowed percentage is 20%, the increase in sales due to halo for the period can not exceed 3 units.

Note: This measure is specified at an intersection higher than item/store. The content of the measure is visible if you roll up to All Products on the product hierarchy. At a lower intersection the cell appears as a hash mark.

Promo Cannibalized Matrix Data Source

This parameter contains the name of the measure that is used to spread the cannibalization lift caused by a promoted item to the related items.

Note: This measure is specified at an intersection higher than item/store. The content of the measure is visible if you roll up to All Products on the product hierarchy. At a lower intersection the cell appears as a hash mark.

Promo Halo Matrix Data Source

This parameter contains the name of the measure that is used to estimate the Halo effects between items. The measure name is implementation specific.

Note: The content of the measure is visible if you roll up to All Products on the product hierarchy. At a lower intersection the cell is unavailable.

Demand Transference Parameters View- Advanced Settings

The Demand Transference Parameters View- Advanced Settings allows you to set parameters to decide if and how demand transference is incorporated in the forecast.

Figure 9–11 Demand Transference Parameters View- Advanced Settings

	1 - itm/str/week-Final
Demand Transference Enabled	<input checked="" type="checkbox"/>
Default Apply Demand Transference Effects	<input type="checkbox"/>
Default Demand Transference Effects Applying Period	5
Default Demand Transference Effect Decay Factor	0.50
Default Minimum Assortment Multipliers	0.50
Default Maximum Assortment Multipliers	2.00

Measures: Demand Transference Parameters View- Advanced Settings

The Demand Transference Parameters View- Advanced Settings contains the following measures:

Default Apply Demand Transference Effects

A check in this field (set to True) indicates that RDF will incorporate demand transference in the forecast. Otherwise, by clearing the box (set to False), no demand transference is incorporated in the forecast generation process. The Demand transference function will be enabled if Demand Transference Enabled is specified during implementation, and Default Apply Demand Transference is set to True. This measure serves as a global setting, but can be overridden at lower levels.

RDF loads assortment multipliers from ORME (Oracle Retail Modeling Engine). The demand transference effects are derived from these assortment multipliers, at a prod/loc/cldn intersection. Before RDF incorporates the effects in the forecast, the value of the assortment multipliers can be checked and capped.

- If the loaded value is smaller than the Maximum Assortment Multiplier, but greater than the Minimum Assortment Multiplier, the loaded value is applied for the demand transference effect calculation.

Default Demand Transference Effect Decay Factor

This measure is applied if and only if the demand transference function is enabled and applied. This parameter serves as a global setting, but can be overridden at lower levels.

This parameter determines how the magnitude of the demand transference effects is applied over time. An assortment change usually triggers a transference in demand. However, the effect can be seen only for a few periods following the assortment change. In addition, an adjustable damping mechanism ensures that the demand transference effect trends down as time goes by. The decaying factor is a number between zero (0) and one (1).

RDF loads assortment multipliers from ORME (Oracle Retail Modeling Engine). The demand transference effects are derived from these assortment multipliers, at a prod/loc/cldn intersection. Before RDF incorporates the effects in the forecast, the value of the assortment multipliers can be checked and capped.


The closer the decaying factor is to zero (0), the faster the demand transference effect decays.

Default Demand Transference Effects Applying Period

This measure is applied only if the demand transference function is enabled and applied. This parameter serves as a global setting, but can be overridden at lower levels.

This integer measure specifies the number of periods for which the demand transference effect is applied. An assortment change usually triggers a transference in demand. However, the effect is usually seen only for a few periods following the assortment change. The number of periods is specified as an integer in this cell.

Figure 9–12 Demand Transference Decaying Effect



Default Maximum Assortment Multipliers

This measure is applied if and only if demand transference function is enabled and applied. This parameter serves as a global setting, but can be overridden at lower levels. It is used to set the maximum threshold of the assortment multipliers.

- If the loaded value is greater than the Maximum Assortment Multiplier, the Maximum Assortment Multiplier is applied for the demand transference effect calculation.
- If the loaded value is smaller than the Maximum Assortment Multiplier but greater than the Minimum Assortment Multiplier (link), the loaded value is applied for the demand transference effect calculation.

Default Minimum Assortment Multipliers

This measure is applied if and only if demand transference function is enabled and applied. This parameter serves as a global setting, but can be overridden at lower levels. It is used to set the minimum threshold of the assortment multipliers.

- If the loaded value is smaller than the Minimum Assortment Multiplier, the Minimum Assortment Multiplier is applied for the demand transference effect calculation.
- If the loaded value is greater than the Minimum Assortment Multiplier but smaller than the Maximum Assortment Multiplier (link), the loaded value is applied for the demand transference effect calculation.

Demand Transference Enabled

This read-only measure specifies if demand transference is configured for the final level. The decision to enable demand transference is made in the Configuration Tools.

Note: The content of the measure is visible if you roll up to All Products on the product hierarchy. At a lower intersection the cell is unavailable.

Forecast Maintenance Task

The Forecast Maintenance task allows you to select and modify forecasting parameters for product/location combinations when the values of these parameters differ from the default values that are assigned in the [Forecast Administration Workbook](#).

Suppose, for example, that the default forecast method of all the products in the database was set in the [Forecast Administration Workbook](#) to be AutoES. For a particular product, however, you know that a SeasonalES model is a better predictor of sales performance. To make this change, you must access the Forecast Maintenance task, select the product/location intersection to be reviewed, and make the appropriate change to the forecast method.


The Forecast Maintenance task is split into three workflow activities:

- Basic Settings - Includes all Final Level views and their respective Source Level views.
- Intermediate Settings - To better manage returns forecast, an intermediate level was introduced for the subclass/region intersection so that some parameters can be managed.
- Advanced Settings - Includes the Forecast Start Date, End Date, and History Start Date measures for the selected Final Level.


Forecast Maintenance Workbook

To build the Forecast Maintenance workbook, perform these steps:

1. Click the New Workbook icon in the Forecast Maintenance task in the Core Forecasting activity.

Figure 10–1 Forecast Maintenance Task

2. The Workbook wizard opens. Select the forecast level that you want to evaluate and click **Next**.

Figure 10–2 Workbook Wizard: Causal Level

3. Select the specific locations that you want to view and click **Next**.

Figure 10–3 Workbook Wizard: Select Locations

Workbook Wizard

Final Forecast Level Selection Location Selection ...

Available Locations

Available Items

View - Dimension Find... Detach

Label
3 Crystal
5th Avenue
6 Glendale
7 Westland
8 Fridley
✓ 9 West St Paul
✓ 20 Knollwood
✓ 50 Bloomington
✓ 68 East St Paul
✓ 90 West St Paul
✓ 160 Midway
✓ 220 Ridgedale
✓ 260 St.Louis Park, MN
662 Cottage Grove
694 Woodbury
862 Chanhassen, MN
1111 Charlotte
1121 Atlanta
1131 Jacksonville
1141 Nashville

Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Synchronize Hierarchies

Cancel Previous Next Finish

4. Select the products you want to work with and click **Next**.

Figure 10–4 Workbook Wizard: Select Products

Workbook Wizard

Final Forecast Level Selection Location Selection Product Selection ...

Available Products

Available Items

View - Dimension Find... Detach

Label
10000328Marlboro KSF box 200
10000536Benson & Hedges 200 Pack
✓ 10000537Merit 200 Pack
✓ 10000539Parliament Pack 200
✓ 10000629Marlboro light's Single Pack
✓ 10002328Marlboro KSF box 200
✓ 10002536Benson & Hedges 200 Pack
✓ 10002537Merit 200 Pack
✓ 10002539Parliament Pack 200
10002629Marlboro light's Single Pack


Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Synchronize Hierarchies

Cancel Previous Next Finish

5. Select any additional measures with and click **Finish**.

Figure 10–5 Workbook Wizard: Select Extra Measures



The Forecast Maintenance workbook is built.

Forecast Maintenance Workbook: Basic Settings

The Forecast Maintenance Basic Settings workbook includes [Final and Source Level Views - Basic Settings](#).


Final and Source Level Views - Basic Settings

The Final Level View and Source Level view allows for certain parameters set at a global level (in Forecast Administration) to vary at different item/locations. [Figure 10–6](#) and [Figure 10–7](#) show the Final Level and Source Level views.

Figure 10–6 Final Level View - Basic Settings

Parameter	5 pocket						
Approval Method Override 01 - itm/str/week-Baseline Forecast Final	5 pocket						
Forecast Method Override 01 - itm/str/week-Baseline Forecast Final	No Override						
Keep Last Changes Override 01 - itm/str/week-Baseline Forecast Final							
Source Level Override 01 - itm/str/week-Baseline Forecast Final							
Optimal Source Levels 01 - itm/str/week-Baseline Forecast Final							
Pick Optimal Level 01 - itm/str/week-Baseline Forecast Final	<input type="checkbox"/>						
Winters Mode Override 01 - itm/str/week-Baseline Forecast Final	No Override						
Moving Average Window Length Override 01 - itm/str/week-Baseline Forecast Final	0	0	0	0	0	0	0
Bayesian Alpha Override 01 - itm/str/week-Baseline Forecast Final	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Return Forecast Flag Override 01 - itm/str/week-Baseline Forecast Final	<input type="checkbox"/>						
Return Forecast Percentage Override 01 - itm/str/week-Baseline Forecast Final							
Return Forecast Time Shift Override 01 - itm/str/week-Baseline Forecast Final							

Figure 10–7 Source Level View - Basic Settings



Measures: Final and Source Level Views - Basic Settings

The Final and Source Level Views - Basic Settings contains the following measures:

Approval Method Override

Set only at the final-level, the Approval Method Override is a list from which you select the approval policy for individual product/location combinations. No value is in this field if the system default set in the [Forecast Administration Workbook](#) is to be used. Valid values are:

Field	Description
Manual	The System Forecast and Adjusted Forecast are not automatically approved. Forecast values must be manually approved by accessing and amending the Forecast Approval Workbook .
Automatic	The Adjusted Forecast is automatically approved as is.
By Alert <name of the alert>	This list of values may also include any Forecast Approval alerts that have been configured for use in the forecast approval process. Alerts are configured during the implementation. Refer to the <i>Oracle Retail Predictive Application Server Configuration Tools User Guide</i> for more information on the Alert Manager and the <i>Oracle Retail Demand Forecasting Configuration Guide</i> for more information on configuring Forecast Approval Alerts.

Note: If you select a specific alert as your approval method and later on you delete the alert, the approval works as manual. The same happens if the alert is on a wrong intersection.

Bayesian Alpha Override

This is the override of the Bayesian Alpha parameter that is specified globally in the [Forecast Administration Workbook](#). The override can be specified at every forecasting level, that is, final and source-levels.

An alpha value closer to one (or infinity) weights the sales plan more in creating the forecast, whereas alpha closer to zero weights the known history more. The default is one (1).

Forecast Method Override

Set at both final and source-levels, the Forecast Method Override is a list from which you can select a different forecast method than the Default Forecast Method set in the [Forecast Administration Workbook](#). *No Override* appears in this field if the system default set in the [Forecast Administration Workbook](#) is to be used. Valid options depend on your system setup.

Keep Last Changes Override

Set only at final-levels, Keep Last Changes Override field may be used to override the default setting at a product/location intersection. *None* appears in this field if there is no override applied to the intersection.

Moving Average Window Length Override

Used with Moving Average forecast method, this is the number of data points in history used in the calculation of Moving Average. This parameter, when set to a non-zero value, overrides the value in the [Forecast Administration Workbook](#).

Optimal Source Levels

Displayed only at final-levels, a value is populated in this field if AutoSource has been run on the final-level. The AutoSource executable evaluates all levels associated to a final-level and returns the source-level that yields the optimal forecast results. For more information on AutoSource, refer to the *Oracle Retail Demand Forecasting Implementation Guide*.

Note: For item/stores that are new or highly seasonal, AutoSource may not return the best recommendation since new items may not have an adequate sales history length and highly seasonal items may only sell for a short period during the year. For these items, you should not set the AutoSource recommendation as default at the final-level. Only use AutoSource recommendations for item/stores that have an adequate sales history.

Pick Optimal Level

Set only at final-levels, a check in this field (set to *True*) indicates that the batch forecast should use the Optimal Source Level selected by AutoSource. For more information on AutoSource, refer to the *Oracle Retail Demand Forecasting Implementation Guide*.

Return Forecast Flag Override

If this Boolean measure is checked, it indicates that a returns forecast will be generated for the desired product/location combinations.

Return Forecast Percentage Override

This measure overrides the default value of the percentage of the merchandise sold in a time period that is expected to be returned to the store. A value of zero indicates that no returns will be calculated.

Return Forecast Time Shift Override

This measure overrides the default value of the number of time periods between when the merchandise was sold until it was returned. For instance, if the measure is set to one, the merchandise is expected to be returned one week after it was sold.

Source Level Override

Set only at final-levels, the Source Level Override is the level at which the aggregate, more robust forecast is run. Forecast data from this level is spread down to the lowest level based on the relationship between the two levels in the hierarchy. *No Override* appears in this field if the system default set in the [Forecast Administration Workbook](#) is to be used.

Winters Mode Override

Used only by Forecasting Methods calling Additive or Multiplicative Winters. This parameter allows you to override the Winters Mode setting assigned in the [Forecast Administration Workbook](#). The default setting for this parameter is No Override.

Forecast Maintenance Workbook: Intermediate Settings

The Advanced Settings workflow activity is used to better manage returns forecast for the subclass/region intersection so that some parameters can be managed. in the [Forecast Administration Workbook](#).

Final Return Forecast Intermediate Intersection Parameters View

[Figure 10–8](#) shows the Final Return Forecast Intermediate Intersection Parameters view.

Figure 10–8 *Final Return Forecast Intermediate Intersection Parameters View*

Location	Product	Measure
13 Midwest US	111Fashion	
Intermediate Return Forecast Percentage 01 - itm/str/week-Baseline Forecast Final		
Intermediate Return Forecast Time Shift 01 - itm/str/week-Baseline Forecast Final		

Measures: Final Return Forecast Intermediate Intersection Parameters View

The Final Return Forecast Intermediate Intersection Parameters view contains the following measures:

Intermediate Return Forecast Percentage

This measure overrides the default value of the percentage of the merchandise sold in a time period that is expected to be returned to the store. A value of zero indicates that no returns will be calculated. The intersection of the measure is subclass/region.

Intermediate Return Time Shift

This measure overrides the default value of the number of time periods between when the merchandise was sold until it was returned. For instance, if the measure is set to one, the merchandise is expected to be returned one week after it was sold. The intersection of the measure is subclass/region.

Forecast Maintenance Workbook: Advanced Settings

The Advanced Settings workflow activity is used to override the dates that are used in the forecast generation process as well as historical start dates for any intersection at the final-level that varies from the default settings in the [Forecast Administration Workbook](#).

Advanced Final Parameter View

Figure 10–9 shows the Advanced Final Parameter view.

Figure 10–9 Advanced Final Parameter View

Parameter Name	Value
Forecast Start Date Override 1 - itm/str/week-Final	
Forecast End Date Override 1 - itm/str/week-Final	
History Start Date Override 1 - itm/str/week-Final	
Apply Promotional Lift Override 1 - itm/str/week-Final	<input type="checkbox"/>
Apply Interaction Factor Override 1 - itm/str/week-Final	
Interaction Factor Override 1 - itm/str/week-Final	
Overlapping Promotions Behavior Override 1 - itm/str/week-Final	No Override
Overlapping Promotion Adjustment Factor Override 1 - itm/str/week-Final	0.00
Apply Regular Price Lift Override 1 - itm/str/week-Final	No Override
Apply Regular Price Lift over Promotion Override 1 - itm/str/week-Final	No Override
Regular Price Decaying Factor Override 1 - itm/str/week-Final	
Apply Regular Price Self Lift Override 1 - itm/str/week-Final	No Override
Apply Regular Price Halo Lift Override 1 - itm/str/week-Final	No Override
Apply Regular Price Cannibalization Lift Override 1 - itm/str/week-Final	No Override
Regular Price Effective Periods Override 1 - itm/str/week-Final	
Apply Promotion Halo Lift Override 1 - itm/str/week-Final	No Override
Apply Promotion Cannibalization Lift Override 1 - itm/str/week-Final	No Override
Apply Demand Transference Effects Override 1 - itm/str/week-Final	
Demand Transference Effects Decaying Factor Override 1 - itm/str/week-Final	
Demand Transference Effects Applying Period Override 1 - itm/str/week-Final	

Measures: Advanced Final Parameter View

The Advanced Final Parameter view contains the following measures:

Apply Interaction Factor Override

When generating the forecast there are three possible lifts added on top of the baseline to get the final result. They are promotion lift, regular price change lift, and demand transference lift. The Apply Interaction Factor measure allows the user to specify at a low level if these individually calculated lifts should be combined together during the forecast generation. More details can be found in Default Interaction Factor Override in the [Forecast Administration Workbook](#).

For this parameter, select a value from the list to instruct RDF to apply or override the globally selected Default Apply Interaction Factor.

- None— uses the default setting from Forecast Administration
- Yes — applies the interaction factor indicated in [Interaction Factor Override](#)
- No — does not apply any interaction factor

Apply Demand Transference Effects Override

This measure is applied only if demand transference function is enabled and applied. This is an override of the global setting.

For this parameter, select a value from the list to instruct RDF to apply or override the globally selected Default Apply Interaction Factor.

- None— uses the default setting from Forecast Administration
- Yes — applies the interaction factor indicated in [Interaction Factor Override](#)
- No — does not apply any interaction factor

Apply Promotion Cannibalization Lift Override

This parameter is only effective if the Apply Promotional Lift override is selected (set to *True*).

For this parameter, select a value from the list to instruct RDF to apply or override the system generated Cannibalization effects.

- **Yes** — applies the system generated Cannibalization effects
- **No** — does not apply any Cannibalization lifts
- **No Override** — uses the default setting from Forecast Administration

This is an override of the global setting.

Apply Promotion Halo Lift Override

This parameter is only effective if the Apply Promotional Lift override is selected (set to *True*).

For this parameter, select a value from the list to instruct RDF to apply or override the system generated Halo effects.

- **Yes** — applies the system generated Halo effects
- **No** — does not apply any Halo lifts
- **No Override** — uses the default setting from Forecast Administration

This is an override of the global setting.

Apply Promotional Lift Override

Select this parameter (set to *True*) if you want RDF to ignore the system calculated lifts, and apply the overrides.

Apply Regular Price Cannibalization Lift Override

This parameter is only effective if:

- **Apply Regular Price Lift Override** is set to Apply System or Apply Override
or
- **Apply Regular Price Lift Override** is set to No Override and [Apply Regular Price Lift](#) is set to Apply System or Apply Override

For this parameter, select a value from the list to instruct RDF to override the system generated Cannibalization effects.

- **Yes** — overrides the system generated Cannibalization effects
- **No** — does not apply any Cannibalization lifts
- **No Override** — applies the system generated Cannibalization effects

This is an override of the global setting.

Apply Regular Price Halo Lift Override

This parameter is only effective if:

- **Apply Regular Price Lift Override** is set to Apply System or Apply Override
or

- **Apply Regular Price Lift Override** is set to No Override and [Apply Regular Price Lift](#) is set to Apply System or Apply Override

For this parameter, select a value from the list to instruct RDF to override the system generated Halo effects.

- **Yes** — overrides the system generated Halo effects
- **No** — does not apply any Halo lifts
- **No Override** — applies system generated Halo effects

This is an override of the global setting.

Apply Regular Price Lift Over Promotion Override

This parameter is only effective if:

- **Apply Regular Price Lift Override** is set to Apply System or Apply Override
or
- **Apply Regular Price Lift Override** is set to No Override and [Apply Regular Price Lift](#) is set to Apply System or Apply Override

For this parameter, select a value from the list to instruct RDF to override the system generated Cannibalization effects.

- **Yes** — overrides the system generated Cannibalization effects
- **No** — does not apply any Cannibalization lifts
- **No Override** — applies the system generated Cannibalization effects

This is an override of the global setting.

Apply Regular Price Lift Override

For this parameter, select a value from the list to instruct RDF to apply or override regular price lifts:

- **Do Not Apply** — does not apply regular price effects (including Self, Cannibalization, and Halo effects)
- **Apply System** — applies system calculated effects
- **Apply Override** — ignores system calculated effects and applies overrides
- **No Override** — applies the default setting from Forecast Administration

This is an override of the global setting.

Apply Regular Price Self Lift Override

This parameter is only effective if:

- **Apply Regular Price Lift Override** is set to Apply System or Apply Override
or
- **Apply Regular Price Lift Override** is set to No Override and [Apply Regular Price Lift](#) is set to Apply System or Apply Override.

For this parameter, select a value from the list to instruct RDF to apply or override the system generated Cannibalization:

- **Yes** — overrides the system generated Cannibalization effects
- **No** — does not apply any Cannibalization lifts
- **No Override** — applies the system generated Cannibalization effects

This is an override of the global setting.

Demand Transference Effects Applying Period Override

This measure is applied only if demand transference function is enabled and applied. This is an override of the global setting.

This integer measure specifies the number of periods for which the demand transference is applied. An assortment change usually triggers transference in demand. However, the effect can be seen only for a few periods following an assortment change. The applying period can be specified as an integer in this cell. This is an override of the global setting.

Demand Transference Effects Decaying Factor Override

This measure is applied only if demand transference function is enabled and applied. This is an override of the global setting.

This parameter determines how the magnitude of the demand transference is applied over time. An assortment change usually triggers a change in demand. However, the effect can be seen only for a few periods following an assortment change. An adjustable damping mechanism ensures that the demand transference effect trends down as time goes by. The decaying factor is a number between zero (0) and one (1). The closer the decaying factor is to zero, the faster the demand transference effect decays.

Forecast End Date Override

This parameter represents the last point in time for which the forecasting engine forecasts for a particular intersection. Should this parameter be set to a date less than the Forecast Start Date plus the Forecast Length (in Forecast Administration), the engine forecasts zero (0) past this date. If Forecast End Date is more than Forecasting Start Date plus Forecasting Length, you do not get a forecast outside Forecasting Start Date plus Forecasting Length. In other words, both Forecast Start Date and Forecasting End Date are relevant for time periods within the forecast horizon set at the global level. No value is in this measure if the system default set in the [Forecast Administration Workbook](#) is to be used.

Note: This measure can also be set in the [Forecast Like-Item& Sister-Store Workbook](#). Changes to this measure can be seen in the [Forecast Maintenance Workbook](#) and the [Forecast Like-Item& Sister-Store Workbook](#). The most recent commit (in either task) is the value used by the system.

Forecast Start Date Override

This parameter represents the date to start forecasting at a particular intersection. If this date is set to the past, it is ignored in favor of the Forecast Start Date from the [Forecast Administration Workbook](#). This means that you do not need to change the Forecast Start Date once it is no longer in the future. It is important to understand how Forecast Start Date should be used in conjunction with [Forecast End Date Override](#).

No value is in this measure if the system default set in the [Forecast Administration Workbook](#) is to be used.

Note: This measure can also be set in the [Forecast Like-Item& Sister-Store Workbook](#). Changes to this measure can be seen in the [Forecast Maintenance Workbook](#) and the [Forecast Like-Item& Sister-Store Workbook](#). The most recent commit (between either task) is the value used by the system.

History Start Date Override

This parameter represents the first point in time from which the Forecasting Engine begins training and modeling (that is, if there are two years of history, but you only want to use one year, you set the start date to a year ago). This parameter overrides the History Start Date set in the [Forecast Administration Workbook](#) to the desired item/location intersection. For example, if you have a large spike in the first three weeks of sales for an item on sale, you can set the Historical Start Date to one week past that period, and those first few weeks are not used when generating the forecast.

It is also important to note that the system ignores leading zeros that begin at the history start date. For example, if your history start date is January 1, 2003, and an item/location does not have sales history until February 1, 2003, the system considers the starting point in that item/location's history to be the first data point where there is a non-zero sales value.

If this parameter is set into the future, there would be no forecast, as the history training window is read as zero.

Note: This measure can also be set in the [Forecast Like-Item& Sister-Store Workbook](#). Changes to this measure can be seen in the [Forecast Maintenance Workbook](#) and the [Forecast Like-Item& Sister-Store Workbook](#). The most recent commit (between either task) is the value used by the system.

Interaction Factor Override

The Interaction Factor is applied if the Apply Interaction Factor is set to True (with the [Apply Interaction Factor Override](#) set to Yes, or [Apply Interaction Factor Override](#) is set to None while [Default Apply Interaction Factor](#) is set to True). This is an override of the global setting.

This Interaction Factor Override specifies at an item/location level how the individually calculated promotion lift, regular price change lift and demand transference lift interact with each other during the forecast generation process. More details can be found in Default Interaction Factor in the [Forecast Administration Workbook](#).

This is an override of the global setting.

Overlapping Promotion Adjustment Factor Override

The Overlapping Promotion Adjustment Factor Override measure is applied if Adjustable Approach is selected for Overlapping Promotion Behavior for the item/location level. This is an override of the global setting.

The Overlapping Promotion Adjustment Factor Override specifies at an item/location how the individually calculated promotion effects are combined with each other when

the promotions are overlapped in the forecast horizon. The default value is 1. More details can be found in Forecast Administration Task ([link](#))

Overlapping Promotions Behavior Override

The Overlapping Promotion Behavior measure allows you to specify that the overlapping promotions function should be activated during the batch run. More details can be found in Default Overlapping Promotions Behavior in the [Forecast Administration Workbook](#).

For this parameter, select a value from the list to instruct RDF to apply or override the globally selected Default Overlapping Promotions Behavior.

- Enhanced Approach — applies the Enhanced Approach
- Adjustable Approach — applies the Adjustable Approach
- No Override— uses the default setting from Forecast Administration

This is an override of the global setting.

Regular Price Decaying Factor Override

This parameter determines how the magnitude of the price effects is applied over time. A regular price change usually triggers a change in demand. However, the effect can be seen only for a few periods following the price change. An adjustable damping mechanism ensures that the regular price effect trends down as time goes by. The decaying factor is a number between zero (0) and one (1). The closer the decaying factor is to zero, the faster the regular price effect decays. This is an override of the global setting.

Regular Price Effective Periods Override

Specifies the number of periods for which the regular price effect is applied. This is an override of the global setting.

Preprocessing Administration Task

This chapter describes how the preprocessing functionality is implemented in RDF using the [Preprocess Admin Workbook](#).

Use the [Preprocess Admin Workbook](#) to perform the steps for this task:

- [Preprocess Admin Step](#)
- [Out of Stock and Outlier Threshold Step](#)
- [Preprocess Parameters Steps](#)

Note: Similar to the [Preprocess Admin Workbook](#) is the [Preprocess Review and What-if Workbook](#). For functionality differences, see [Preprocess Workbook Functionality](#).

About Preprocessing

Preprocessing is an optional module that is used to correct historical data prior to forecast generation when history does not represent general demand patterns. It is meant to automatically make adjustments to the raw POS (Point Of Sales) data so the next demand forecasts do not replicate undesired patterns.

Data Preprocessing is commonly used to:

- Correct for lost sales due to stock-outs
- Cleanse data for effects of promotions and short-term price changes (optional)
- Correct for outliers – unusually high or low values introduced by human error or special events (hurricane that left a store closed for a week)
- Scrub data manually to fake history and override user history
- Adjust demand for the occasional 53rd calendar week
- Manage demand created during events and holidays that do not occur in the same period every year, for example, Back to School.

Preprocessing runs after the data has been loaded from the host system and prior to forecast generation. Use the [Preprocess Admin Workbook](#) to produce and review data. It is common for an environment to require preprocessing to run multiple times to properly smooth the history.

Preprocessing Data in the RDF Workflow

Preprocessing offers a variety of Algorithm methods to support the business requirements. The main reason for preprocessing is to transform the raw sales data into a measure that gets as close as possible to unconstrained demand.

The preprocessing step is most often implemented in batch, by invoking a preprocessing special expression. The special expression takes several measures as input. For instance, one needs to specify the measure to be corrected, the desired algorithm, and the number of periods to be considered. However, you can go into more detail, and specify several filter window lengths, or exponential smoothing parameters.

Preprocess Administration Tasks, Steps, and Views

The following table lists the workbooks, steps, and views for the Preprocess Administration task.


Workbook	Steps	Views
Preprocess Admin Workbook	Preprocess Admin Step	Preprocess Admin View
	Out of Stock and Outlier Threshold Step	Out of Stock and Outlier Threshold View
	Preprocess Parameters Step	Preprocess Panel for Baseline Data Source View Preprocess Panel for Causal Data Source View Preprocess Method Parameters View Preprocess Method Parameters Override View

Preprocess Admin Workbook

To build the Preprocess Admin workbook, perform these steps:


1. Click the New Workbook icon in the Preprocess Administration task in the Core Forecasting activity.

Figure 11–1 Preprocess Administration Task




2. The Workbook wizard opens. Select the specific locations that you want to view and click **Next**.

Figure 11–2 Workbook Wizard: Locations



3. Select the products you want to work with and click **Finish**.

Figure 11–3 Workbook Wizard: Select Products



The Preprocess Administration workbook is built.


Preprocess Admin Step

This step contains the Preprocess Admin view.

Preprocess Admin View

The Preprocess Admin view allows you to define the scope of the preprocessing run, as well as filter out item/locations where preprocessing does not make sense because of lack of enough historical sales.

Figure 11–4 Preprocess Admin View



Measures: Preprocess Admin View

The Preprocess Admin view contains the following editable measures:

Deseasonalized Flag

This parameter defines the scope of the preprocessing runs. The options are:

- Preprocess demand to create the data source necessary to forecast baseline demand
- Preprocess demand to create the data source for promotional forecasting
- Generate both data source measures

Min Number of Weeks in System

This parameter defines the number of periods from when an item was introduced in the system. Usually the introduction time is considered to be the date when the item first sold. This check is also introduced to stop making data corrections for items that are very new, and where cleansing would be unreliable.

Min Number of Weeks with Sales

This parameter defines the number of weeks with sales that an item/store combination needs to have to qualify for data cleansing. The reasoning behind this check is that for items without enough data, corrections may not be reliable. Once there is enough data, and trends become clearer, corrections can be made.

Out of Stock and Outlier Threshold Step

This step contains a view that allows you to manage parameters used to create out of stock and outlier flags. Ideally, a retailer knows when stockouts occurred, or when special events created outliers in demand. These flags are usually interfaced in RDF and used in the preprocessing special expression. Many times, though, outages and outliers are not tracked, or they are not very exact. However, it is always beneficial to correct for those unwanted cases, to get closer to unconstrained demand. To make sure corrections are made, RDF has rules configured to create the flags, based on demand, and the parameters defined in this view.

Out of Stock and Outlier Threshold View

The Out of Stock and Outlier Threshold view displays stock and outlier flags.

Figure 11–5 Out of Stock and Outlier Threshold View

	5 pocket								
High Seller Minimum Number	10	10	10	10	10	10	10	10	10
Low Seller Minimum Number	10	10	10	10	10	10	10	10	10
High Seller Minimum Number	10	10	10	10	10	10	10	10	10
Low Seller Minimum Number	20	20	20	20	20	20	20	20	20
Outlier Factor	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
High Seller Out of Stock	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10
Low Seller Out of Stock	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10	0.10
Sales Volume Threshold High	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
Sales Volume Threshold Low	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

Measures: Out of Stock and Outlier Threshold View

The Out of Stock and Outlier Threshold view contains the following measures:

High Seller Out of Stock Factor

This measure defines the threshold for when a high selling item is considered out of stock. For instance if the sales of an item are less than the rate of sales of the item multiplied with this value, this can be an indication that there was a stockout.

High Sellers Minimum Number of Sales Periods

This a condition on the number of periods a high seller has been selling. For instance if the number of periods the item has been selling is less than the value, the history is deemed to be too short, and no out of stock calculation will occur for the item.

High Sellers Minimum Number of Zero Sales

This a condition on the number of periods when a high selling item had zero sales. For instance if the number of periods with zero sales is larger than this value, this can be an indication that there was a stockout

Low Seller Out of Stock Factor

This measure defines the threshold for when a low selling item is considered out of stock. For instance if the sales of an item are less than the rate of sales of the item multiplied with this value, this can be an indication that there was a stockout.

Low Sellers Minimum Number of Sales Periods

This a condition on the number of periods a low seller has been selling. For instance if the number of periods the item has been selling is less than the value, the history is deemed to be too short, and no out of stock calculation will occur for the item.

Low Sellers Minimum Number of Zero Sales

This a condition on the number of periods when a low selling item had zero sales. For instance if the number of periods with zero sales is larger than this value, this can be an indication that there was a stockout

Outlier Factor

This measure defines the threshold for when the sales of an item are considered outliers. For instance if the sales of an item are more than the rate of sales of the item multiplied with this value, this can be an indication that there was an outlier.

Sales Volume Threshold High

If the rate of sale of an item is larger than value stored in this measure, it is considered a high selling item; this measure is part of the calculation when the out of stock indicator needs to be created using rules.

Sales Volume Threshold Low

If the rate of sale of an item is less than value stored in this measure, it is considered a low selling item; this measure is part of the calculation when the out of stock indicator needs to be created using rules. The rules that populate the Out of Stock and Outlier flags can be found in [Appendix A, "Appendix: Preprocessing."](#)

Preprocess Parameters Step

This step has four views:


- [Preprocess Panel for Baseline Data Source View](#)
- [Preprocess Panel for Causal Data Source View](#)
- [Preprocess Method Parameters View](#)
- [Preprocess Method Parameters Override View](#)

These views make available the preprocessing parameters for four rounds of preprocessing runs, necessary to calculate the data source for baseline forecasting and promotional forecasting.

Preprocess Panel for Baseline Data Source View

The view displays the measures necessary to create the data source for baseline forecasting. This involves four rounds of preprocessing that run in batch or online in this order:

1. Correcting for stockouts
2. Correcting for outliers
3. Depromoting sales
4. Smooth sales

Figure 11–6 Preprocess Panel for Baseline Data Source View

Measures: Preprocessing Panel for Baseline Data Source View

Note: Measures are replicated for each round of preprocessing.

The Preprocessing Panel for Baseline Data Source view contains the following measures:

Event Indicator

Indicates the measure name that represents the event flag.

Input Data Source Measure

Indicates the measures that will be corrected.

Output Data Measure

Indicates the measure that stores the result of the preprocessing run.

Preprocess Method

Name of the preprocessing method to be used. This method is fixed, but this can be expanded to a list.

Preprocessing Label

A label denoting the purpose of the preprocessing run, for example, Out-of-Stock Correction.

Run Preprocess Flag

Boolean measure indicating if this rule should be run or skipped.


Preprocess Panel for Causal Data Source View

This view displays the measures necessary to create the data source for baseline forecasting. This involves three rounds of preprocessing that run in this order:

1. Correcting for stockouts
2. Correcting for outliers
3. Deseasonalizing the measure to create the causal data source

The first two runs are the same used to generate the baseline data source. Hence they use the same parameters as the ones in the [Preprocess Panel for Baseline Data Source View](#). The third run deseasonalizes the demand.

Figure 11–7 Preprocess Panel for Causal Data Source View



Measures: Preprocessing Panel for Causal Data Source View

Note: Measures are replicated for each round of preprocessing.

The Preprocessing Panel for Causal Data Source view contains the following measures:

Event Indicator

Indicates the measure name that represents the event flag.

Input Data Source Measure

Indicates the measures that will be corrected.

Output Data Measure

Indicates the measure that stores the result of the preprocessing run.

Preprocess Method

Name of the preprocessing method to be used. This method is fixed, but this can be expanded to a list.

Preprocessing Label

A label denoting the purpose of the preprocessing run, for example, Out-of-Stock Correction.

Run Preprocess Flag

Boolean measure indicating if this rule should be run or skipped.

Preprocess Method Parameters View

In this view, you can enter values for parameters specific for some of the preprocessing methods available in the special expression. There are four sets of parameters, corresponding to the four runs of the preprocessing special expression. The parameters are entered at the class/store intersection

Figure 11–8 Preprocess Method Parameters View

	9 West	20 Knollwood	50	68 East	90 West St	160 Midway	220	260 St.Louis	662 Cottage	694
1. Last Date	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*
1. Future Weeks	2	2	2	2	2	2	2	2	2	2
1. Past Weeks	2	2	2	2	2	2	2	2	2	2
1. Standard Median Window	13	13	13	13	13	13	13	13	13	13
1. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
1. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70
2. Last Date										
2. Future Weeks	2	2	2	2	2	2	2	2	2	2
2. Past Weeks	2	2	2	2	2	2	2	2	2	2
2. Standard Median Window	13	13	13	13	13	13	13	13	13	13
2. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
2. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70
3. Last Date										
3. Future Weeks	2	2	2	2	2	2	2	2	2	2
3. Past Weeks	2	2	2	2	2	2	2	2	2	2
3. Standard Median Window	13	13	13	13	13	13	13	13	13	13
3. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
3. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70
4. Last Date										
4. Future Weeks	2	2	2	2	2	2	2	2	2	2
4. Past Weeks	2	2	2	2	2	2	2	2	2	2
4. Standard Median Window	13	13	13	13	13	13	13	13	13	13
4. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
4. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70

Measures: Preprocessing Methods Parameters View

The Preprocessing Methods Parameters view contains the following measures:

Alpha

Exponential smoothing coefficient used to calculate past and future velocities.

Future Weeks

This represents the maximum number of data points to calculate the future velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Last Date

This represents the end date of the preprocessing window; it is typically today's date, but can be any date in the past.

Past Weeks

This represents the maximum number of data points to calculate the past velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Preprocessing Window

Number of historical data points that are preprocessed.

Standard Median Window


Filter window length for the Standard Median preprocessing method.

Preprocess Method Parameters Override View

In this view, you can override values for parameters specific for some of the preprocessing methods available in the special expression. There are four sets of parameters, corresponding to the four runs of the preprocessing special expression.

After all parameters are set and committed back to the domain, usually a batch job will run the pre-processing steps and prepare the source data for forecast generation.

Figure 11–9 Preprocess Method Parameters Override View



Measures: Preprocessing Method Parameters Override View

The Preprocessing Method Parameters Override view contains the following measures:

Alpha Override

Exponential smoothing coefficient used to calculate past and future velocities.

Future Weeks Override

This represents the maximum number of data points to calculate the future velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Last Date Override

This represents the end date of the preprocessing window; it is typically today’s date, but can be any date in the past.

Past Weeks Override

This represents the maximum number of data points to calculate the past velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Preprocessing Window Override

Number of historical data points that are preprocessed.

Standard Median Window Override

Filter window length for the Standard Median preprocessing method.

Preprocessing Review and What-if Task

This chapter describes how the preprocessing functionality is implemented in RDF using the [Preprocess Review and What-if Workbook](#).

The functionality in the [Preprocessing Review and What-if Task](#) is a superset of the functionality in the [Preprocessing Administration Task](#). The purpose and functionality between the two is described in [Preprocess Workbook Functionality](#).

Use the [Preprocess Review and What-if Workbook](#) to perform the steps for this task:

- [Preprocess Admin Step](#)
- [Out of Stock and Outlier Threshold Step](#)
- [Preprocess Parameters Step](#)
- [What-if Step](#)

Note: For information about preprocessing and RDF, see [Preprocessing Data in the RDF Workflow](#)

Preprocess Workbook Functionality

The main difference in the [Preprocess Review and What-if Workbook](#) versus the [Preprocess Admin Workbook](#) lies in the ability to run custom menus to create out-of-stock and outlier flags, as well as run the preprocessing special expression to create the two data sources: for the causal forecasting run, as well as for forecasting baseline demand. To do this, time-phased measures are necessary, which are inputs and outputs of the preprocessing runs.

Due to their additional dimension of *week*, these measures add to the size of the workbook, and also make workbook operations slower. For instance, workbook build, refresh, commit, and so on, take longer than in the otherwise similar [Preprocess Admin Workbook](#).

Preprocessing Administration Workbook

The [Preprocess Admin Workbook](#) is at the product/location intersection, so it can be built with a lot of positions, without experiencing poor performance. The purpose is to set preprocessing parameters, which are inputs to the special expression that is run in batch.

Preprocess Review and What-if Workbook

The [Preprocess Review and What-if Workbook](#) is at the product/location/calendar intersection, and is a lot more data intensive. The purpose is to set preprocessing

parameters and run the data filtering online, with the ability to review the results without having to wait for an overnight batch. If the results are not as expected, or you want to experiment with different settings, you can make changes to the parameters and rerun the custom menus. To achieve this it is expected that only a small subset of the available product/locations is included in the workbook.

Preprocess Review and What-if Tasks, Steps, and Views

The following table lists the workbooks, steps, and views for the Preprocess Review and What-if task.


Workbook	Steps	Views
Preprocess Review and What-if Workbook	Preprocess Admin Step	Preprocessing Admin View
	Out of Stock and Outlier Threshold Step	Out of Stock and Outlier Threshold View
	Preprocess Parameters Step	Preprocess Panel for Baseline Data Source View Preprocess Panel for Causal Data Source View Preprocess Method Parameters View Preprocess Method Parameters Override View
	What-if Step	What-if Data View What-if Plot View

Preprocess Review and What-if Workbook

To build the Preprocess Review and What-if workbook, perform these steps:


1. Click the New Workbook icon in the Preprocess Review and What-if task in the Core Forecasting activity.

Figure 12–1 Preprocess Review and What-if Task



2. The Workbook wizard opens. Select the specific locations that you want to view and click **Next**.

Note: It is important to include all locations that are members of the location dimensions in the forecast levels to be analyzed. For example, if you select to view a forecast level that is defined at item/chain/week, you should include all locations that are members of the particular chain to be analyzed. It is recommended that Position Query functionality or selection from aggregate levels in the location hierarchy is employed if the task supports an AutoTask build.

Figure 12–2 Workbook Wizard: Locations

3. Select the products you want to work with and click **Next**.

Note: It is important to include all products that are members of the Merchandise dimensions in the forecast levels to be analyzed. For example, if you select to view a forecast level that is defined at subclass/store/week, you must include all items that are members of the particular subclass to be analyzed. It is recommended that Position Query functionality or selection from aggregate levels in the Merchandise hierarchy is employed if the task supports an AutoTask build.

Figure 12–3 Workbook Wizard: Select Products

Workbook Wizard

Select Locations Select Product Select Calendar

Select Products

Available Items

View	Dimension	Find...	Detach
Label			
4 X 6X 1L Still Water			
5 pocket capri - Antique 8 Ank			
5 pocket capri - Antique 10 An			
<input checked="" type="checkbox"/> 5 pocket capri - Antique 12 An			
<input checked="" type="checkbox"/> 5 pocket capri - Bandblasted 1			
<input checked="" type="checkbox"/> 5 pocket capri - Bandblasted 8			
<input checked="" type="checkbox"/> 5 pocket capri - Black 8 Ankle			
<input checked="" type="checkbox"/> 5 pocket capri - Black 10 Ankl			
<input checked="" type="checkbox"/> 5 pocket capri - Black 12 Ankl			
5 pocket capri - Blasted 8 Ank			
5 pocket capri - Blasted 10 An			
5 pocket capri - Blasted 12 An			
5 pocket capri - Denim 8 Ankle			
5 pocket capri - Denim 10 Ankl			
5 pocket capri - Denim 12 Ankl			
5 pocket capri - Lightweight A			
5 pocket capri - Lightweight A			
5 pocket capri - Lightweight A			
5 pocket capri - Raw 8 Ankle			

Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Synchronize Hierarchies

Selected Products

Selected Items

View	Dimension	Find...	Detach
Label			
<input checked="" type="checkbox"/> 5 pocket capri - Antique 12 An			
<input checked="" type="checkbox"/> 5 pocket capri - Bandblasted 1			
<input checked="" type="checkbox"/> 5 pocket capri - Bandblasted 8			
<input checked="" type="checkbox"/> 5 pocket capri - Black 8 Ankle			
<input checked="" type="checkbox"/> 5 pocket capri - Black 10 Ankl			
<input checked="" type="checkbox"/> 5 pocket capri - Black 12 Ankl			

Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Cancel Previous Next Finish

4. Select the weeks of the forecast you wish to review and click **Finish**:

Figure 12–4 Workbook Wizard: Calendar

Workbook Wizard

Select Locations Select Product Select Calendar

Select Weeks

Available Items

View	Dimension	Find...	Detach
Label			
1/11/2013			
1/18/2013			
1/25/2013			
2/1/2013			
<input checked="" type="checkbox"/> 2/8/2013			
<input checked="" type="checkbox"/> 2/15/2013			
<input checked="" type="checkbox"/> 2/22/2013			
<input checked="" type="checkbox"/> 3/1/2013			
<input checked="" type="checkbox"/> 3/8/2013			
<input checked="" type="checkbox"/> 3/15/2013			
<input checked="" type="checkbox"/> 3/22/2013			
<input checked="" type="checkbox"/> 3/29/2013			
<input checked="" type="checkbox"/> 4/5/2013			
<input checked="" type="checkbox"/> 4/12/2013			
<input checked="" type="checkbox"/> 4/19/2013			
<input checked="" type="checkbox"/> 4/26/2013			
<input checked="" type="checkbox"/> 5/3/2013			
<input checked="" type="checkbox"/> 5/10/2013			
5/17/2013			
5/24/2013			

Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Synchronize Hierarchies

Selected Weeks

Selected Items

View	Dimension	Find...	Detach
Label			
<input checked="" type="checkbox"/> 2/8/2013			
<input checked="" type="checkbox"/> 2/15/2013			
<input checked="" type="checkbox"/> 2/22/2013			
<input checked="" type="checkbox"/> 3/1/2013			
<input checked="" type="checkbox"/> 3/8/2013			
<input checked="" type="checkbox"/> 3/15/2013			
<input checked="" type="checkbox"/> 3/22/2013			
<input checked="" type="checkbox"/> 3/29/2013			
<input checked="" type="checkbox"/> 4/5/2013			
<input checked="" type="checkbox"/> 4/12/2013			
<input checked="" type="checkbox"/> 4/19/2013			
<input checked="" type="checkbox"/> 4/26/2013			
<input checked="" type="checkbox"/> 5/3/2013			
<input checked="" type="checkbox"/> 5/10/2013			

Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Cancel Previous Next Finish

The Preprocess Review and What-if workbook is built.

Preprocess Admin Step

This step contains the Preprocess Admin view that allows you to define the scope of the preprocessing run, as well as filter out item/locations where preprocessing does not make sense because of lack of enough historical sales.

Preprocessing Admin View

The Preprocessing Admin view displays the scope of the preprocessing run.

Figure 12–5 Preprocessing Admin View

Preprocess Admin	
Product	
Measure	
Find...	
Group 1	
Min Number of Weeks with Sales	10
Min Number of Weeks In System	10

Measures: Preprocessing Admin View

The Preprocessing Admin view contains the following measures:

Deseasonalized Flag

This parameter defines the scope of the preprocessing runs. The options are:

- Preprocess demand to create the data source necessary to forecast baseline demand
- Preprocess demand to create the data source for promotional forecasting
- Generate both data source measures

Min Number of Weeks in System

This parameter defines the number of periods from when an item was introduced in the system. Usually the introduction time is considered to be the date when the item first sold. This check is also introduced to stop making data corrections for items that are very new, and where cleansing would be unreliable.

Min Number of Weeks with Sales

This parameter defines the number of weeks with sales that an item/store combination needs to have to qualify for data cleansing. The reasoning behind this check is that for items without enough data, corrections may not be reliable. Once there is enough data, and trends become clearer, corrections can be made.

Out of Stock and Outlier Threshold Step

This step contains a view that allows you to manage parameters used to create out of stock and outlier flags. Ideally, a retailer knows when stockouts occurred, or when special events created outliers in demand. These flags are usually interfaced in RDF and used in the preprocessing special expression. Many times, though, outages and outliers are not tracked, or they are not very exact. However, it is always beneficial to

correct for those unwanted cases, to get closer to unconstrained demand. To make sure corrections are made, RDF has rules configured to create the flags, based on demand, and the parameters defined in this view.

Out of Stock and Outlier Threshold View

The Out of Stock and Outlier Threshold view displays stock and outlier flags.

Figure 12–6 *Out of Stock and Outlier Threshold View*

	5 pocket					
High Seller Minimum Number	10	10	10	10	10	10
Low Seller Minimum Number	10	10	10	10	10	10
High Seller Minimum Number	10	10	10	10	10	10
Low Seller Minimum Number	20	20	20	20	20	20
Outlier Factor	5.00	5.00	5.00	5.00	5.00	5.00
High Seller Out of Stock	0.10	0.10	0.10	0.10	0.10	0.10
Low Seller Out of Stock	0.10	0.10	0.10	0.10	0.10	0.10
Sales Volume Threshold High	5.00	5.00	5.00	5.00	5.00	5.00
Sales Volume Threshold Low	1.00	1.00	1.00	1.00	1.00	1.00

Measures: Out of Stock and Outlier Threshold View

The Out of Stock and Outlier Threshold view contains the following measures:

High Seller Out of Stock Factor

This measure defines the threshold for when a high selling item is considered out of stock. For instance if the sales of an item are less than the rate of sales of the item multiplied with this value, this can be an indication that there was a stockout.

High Sellers Minimum Number of Sales Periods

This is a condition on the number of periods a high seller has been selling. For instance if the number of periods the item has been selling is less than the value, the history is deemed to be too short, and no out of stock calculation will occur for the item.

High Sellers Minimum Number of Zero Sales

This is a condition on the number of periods when a high selling item had zero sales. For instance if the number of periods with zero sales is larger than this value, this can be an indication that there was a stockout.

Low Seller Out of Stock Factor

This measure defines the threshold for when a low selling item is considered out of stock. For instance if the sales of an item are less than the rate of sales of the item multiplied with this value, this can be an indication that there was a stockout.

Low Sellers Minimum Number of Sales Periods

This is a condition on the number of periods a low seller has been selling. For instance if the number of periods the item has been selling is less than the value, the history is deemed to be too short, and no out of stock calculation will occur for the item.

Low Sellers Minimum Number of Zero Sales

This a condition on the number of periods when a low selling item had zero sales. For instance if the number of periods with zero sales is larger than this value, this can be an indication that there was a stockout

Outlier Factor

This measure defines the threshold for when the sales of an item are considered outliers. For instance if the sales of an item are more than the rate of sales of the item multiplied with this value, this can be an indication that there was an outlier.

Sales Volume Threshold High

If the rate of sale of an item is larger than value stored in this measure, it is considered a high selling item; this measure is part of the calculation when the out of stock indicator needs to be created using rules.

Sales Volume Threshold Low

If the rate of sale of an item is less than value stored in this measure, it is considered a low selling item; this measure is part of the calculation when the out of stock indicator needs to be created using rules. The rules that populate the Out of Stock and Outlier flags can be found in [Appendix A, "Appendix: Preprocessing."](#)

Preprocess Parameters Step

This step has four views:


- [Preprocess Panel for Baseline Data Source View](#)
- [Preprocess Panel for Causal Data Source View](#)
- [Preprocess Method Parameters View](#)
- [Preprocess Method Parameters Override View](#)

These views make available the preprocessing parameters for four rounds of preprocessing runs, necessary to calculate the data source for baseline forecasting and promotional forecasting.

Preprocess Panel for Baseline Data Source View

The view displays the measures necessary to create the data source for baseline forecasting. This involves four rounds of preprocessing that run in batch or online.in this order:

1. Correcting for stockouts
2. Correcting for outliers
3. Depromoting sales
4. Smooth sales

Figure 12–7 Preprocess Panel for Baseline Data Source View

Measures: Preprocessing Panel for Baseline Data Source View

Note: Measures are replicated for each round of preprocessing.

The Preprocessing Panel for Baseline Data Source view contains the following measures:

Event Indicator

Indicates the measure name that represents the event flag.

Input Data Source Measure

Indicates the measures that will be corrected.

Output Data Measure

Indicates the measure that stores the result of the preprocessing run.

Preprocess Method

Name of the preprocessing method to be used. This method is fixed, but this can be expanded to a list.

Preprocessing Label

A label denoting the purpose of the preprocessing run, for example, Out-of-Stock Correction.

Run Preprocess Flag

Boolean measure indicating if this rule should be run or skipped.

Preprocess Panel for Causal Data Source View

This view displays the measures necessary to create the data source for baseline forecasting. This involves three rounds of preprocessing that run in this order:

1. Correcting for stockouts
2. Correcting for outliers
3. Deseasonalizing the measure to create the causal data source

The first two runs are the same used to generate the baseline data source. Hence they use the same parameters as the ones in the [Preprocess Panel for Baseline Data Source View](#). The third run deseasonalizes the demand.

Figure 12–8 Preprocess Panel for Causal Data Source View

Group 1	
1. Preprocess Label	Out-of-stock correction
1. Run Preprocess Flag	<input checked="" type="checkbox"/>
1. Input Data Source Measure	totaldjsls
1. Output Data Measure Name	precorsts
1. Preprocess Method	STD ES LS
1. Event Indicator	preosind

2. Preprocess Label	Correct for outliers
2. Run Preprocess Flag	<input checked="" type="checkbox"/>
2. Input Data Source Measure	precorsts
2. Output Data Measure Name	preoutsts
2. Method	STD ES
2. Event Indicator	preoutind

Deseasonalization Preprocess Label	Deseasonalization Sales
Deseasonalization Run Preprocess Flag	<input checked="" type="checkbox"/>
Deseasonalization Input Data Source Measure	preoutsts
Deseasonalization Seasonal Profile	preseaprof
Deseasonalization Output Data Measure Name	predeseastls

Measures: Preprocessing Panel for Causal Data Source View

Note: Measures are replicated for each round of preprocessing.

The Preprocessing Panel for Causal Data Source view contains the following measures:

Event Indicator

Indicates the measure name that represents the event flag.

Input Data Source Measure

Indicates the measures that will be corrected.

Output Data Measure

Indicates the measure that stores the result of the preprocessing run.

Preprocess Method

Name of the preprocessing method to be used. This method is fixed, but this can be expanded to a list.

Preprocessing Label

A label denoting the purpose of the preprocessing run, for example, Out-of-Stock Correction.

Run Preprocess Flag

Boolean measure indicating if this rule should be run or skipped.

Preprocess Method Parameters View

In this view, you can enter values for parameters specific for some of the preprocessing methods available in the special expression. There are four sets of parameters, corresponding to the four runs of the preprocessing special expression. The parameters are entered at the class/store intersection

Figure 12–9 Preprocess Method Parameters View

	3 Crystal	5th Avenue	6 Glendale	7 Westland	8 Fridley	9 West	20 Knollwood	50	68 East	90 West
1. Last Date	1141Jeans*	1141Jeans*	1141Jeans*	1141Jeans*						
1. Future Weeks	2	2	2	2	2	2	2	2	2	2
1. Past Weeks	2	2	2	2	2	2	2	2	2	2
1. Standard Median Window	13	13	13	13	13	13	13	13	13	13
1. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
1. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70
2. Last Date										
2. Future Weeks	2	2	2	2	2	2	2	2	2	2
2. Past Weeks	2	2	2	2	2	2	2	2	2	2
2. Standard Median Window	13	13	13	13	13	13	13	13	13	13
2. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
2. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70
3. Last Date										
3. Future Weeks	2	2	2	2	2	2	2	2	2	2
3. Past Weeks	2	2	2	2	2	2	2	2	2	2
3. Standard Median Window	13	13	13	13	13	13	13	13	13	13
3. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
3. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70
4. Last Date										
4. Future Weeks	2	2	2	2	2	2	2	2	2	2
4. Past Weeks	2	2	2	2	2	2	2	2	2	2
4. Standard Median Window	13	13	13	13	13	13	13	13	13	13
4. Preprocessing Window	100	100	100	100	100	100	100	100	100	100
4. Alpha	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.70

Measures: Preprocessing Methods Parameters View

The Preprocessing Methods Parameters view contains the following measures:

Alpha

Exponential smoothing coefficient used to calculate past and future velocities.

Future Weeks

This represents the maximum number of data points to calculate the future velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Last Date

This represents the end date of the preprocessing window; it is typically today's date, but can be any date in the past.

Past Weeks

This represents the maximum number of data points to calculate the past velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Preprocessing Window

Number of historical data points that are preprocessed.

Standard Median Window

Filter window length for the Standard Median preprocessing method.

Preprocess Method Parameters Override View

In this view, you can override values for parameters specific for some of the preprocessing methods available in the special expression. There are four sets of parameters, corresponding to the four runs of the preprocessing special expression.

After all parameters are set and committed back to the domain, usually a batch job will run the pre-processing steps and prepare the source data for forecast generation.

Figure 12–10 Preprocess Method Parameters Override View

	Location	Product	Measure
3 Crystal			
1. Last Date Override	5 pocket	5 pocket	5 pocket
1. Future Weeks Override			
1. Past Weeks Override			
1. Standard Median Window			
1. Preprocessing Window			
1. Alpha Override			

2. Last Date Override			
2. Future Weeks Override			
2. Past Weeks Override			
2. Standard Median Window			
2. Preprocessing Window			
2. Alpha Override			

3. Last Date Override			
3. Future Weeks Override			
3. Past Weeks Override			
3. Standard Median Window			
3. Preprocessing Window			
3. Alpha Override			

4. Last Date Override			
4. Future Weeks Override			
4. Past Weeks Override			
4. Standard Median Window			
4. Preprocessing Window			
4. Alpha Override			

Measures: Preprocessing Method Parameters Override View

The Preprocessing Method Parameters Override view contains the following measures:

Alpha Override

Exponential smoothing coefficient used to calculate past and future velocities.

Future Weeks Override

This represents the maximum number of data points to calculate the future velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Last Date Override

This represents the end date of the preprocessing window; it is typically today's date, but can be any date in the past.

Past Weeks Override

This represents the maximum number of data points to calculate the past velocity, when using the Standard Exponential Smoothing or Lost Sales Standard Exponential Smoothing preprocessing methods.

Preprocessing Window Override

Number of historical data points that are preprocessed.

Standard Median Window Override

Filter window length for the Standard Median preprocessing method.

What-if Step

The main purpose of this step is to display time-phased measures that represent input and output to the preprocessing stages, run by the two available custom menus:

- Calculate Out of Stock (OOS) and Outliers
- Preprocess Simulation

Calculate OOS and Outliers

This menu generates the two measures necessary to correct for out of stock and outliers. The calculations triggered by the custom menu populate the:

- **Out of Stock Indicator:** the measure necessary for the out of stock correction
- **Outliers Indicator:** the measure necessary for outlier correction

Note: For additional information, refer to [Preprocessing for Outliers](#).

Preprocess Simulation

This custom menu performs the following actions:

- Correcting for stockouts
- Correcting for outliers
- Depromoting sales
- Smooth sales

The ultimate goal for Preprocess Simulation is to create the source data for generating forecasts:

- Baseline Sales: source data for baseline forecast generation
- Deseasonalized Sales: source data for causal forecast generation

What-if Data View

This view displays measures that represent input and output of the preprocessing runs, in table format.

Figure 12–11 What-if Data View

	2/8/2013	2/15/2013	2/22/2013	3/1/2013	3/8/2013	3/15/2013	3/22/2013	3/29/2013	4/5
Weekly Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Out of Stock Indicator	<input type="checkbox"/>								
Corrected Sales for OOS	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Outliers Indicator	<input type="checkbox"/>								
Corrected Sales for Outliers	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Indicator	<input type="checkbox"/>								
Seasonal Profile	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Depromoted Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Deseasonalized Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Baseline Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Measures: What-if Data View

The What-if Data view contains the following measures:

Baseline Sales

This measure is the result of the preprocessing run that smoothes the Depromoted Sales. Note how seasonality is preserved. This measure is used as the data source for the baseline forecasting generation.

Corrected Sales for OOS

This measure is the result of the preprocessing run that corrects for lost sales. It becomes the input to the preprocessing run that corrects for outliers.

Corrected Sales for Outliers

This measure is the result of the preprocessing run that corrects for outliers. Its purpose is twofold. It can be used as input to the preprocessing run that removes promotional sales, to eventually become the data source for baseline forecasting. It can also be used in conjunction with a seasonal profile, to remove seasonality, to become the data source for promotional forecasting.

Depromoted Sales

This measure is the result of the preprocessing run that removes promotional sales. It becomes the input to the preprocessing run that will smooth the sales.

Deseasonalized Sales

This measure is the result of the step where the Corrected Sales for Outliers and the Seasonal Profile have been combined to create sales with seasonality removed, but with promo information. This measure is used as the data source for the causal forecasting generation.

Out of Stock Indicator

This measure is either loaded or calculated by the rules in the custom menu. It is used during the pre-processing run that corrects sales for lost sales.

Outliers Indicator

This measure is either loaded or calculated by the rules in the custom menu. It is used during the pre-processing run that corrects the sales for outliers.

Promotion Indicator

This measure is usually calculated as the or of all available Boolean promotional variables. It is used during the preprocessing run that removes promotional sales.

Seasonal Profile

This measure represents the seasonal profile that is used to deseasonalize the Corrected Sales for Outliers. This happens using a simple RPAS rule — a call to the preprocessing special expression is not necessary. Note how the promotional sales are not removed.

What-if Plot View

This view displays measures that represent input and output of the preprocessing runs, in table format. The measures are the same as in the [What-if Data View](#), but displayed in chart form.

Note: This view needs to be formatted to display the measures in chart form. The user interface cannot be formatted using Configuration Tools.

Figure 12–12 What-if Plot View

	2/8/2013	2/15/2013	2/22/2013	3/1/2013	3/8/2013	3/15/2013	3/22/2013	3/29/2013	4/5/2013
Total Adjusted Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Out of Stock Indicator	<input type="checkbox"/>								
Corrected Sales for OOS	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Outliers Indicator	<input type="checkbox"/>								
Corrected Sales for Outliers	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Indicator	<input type="checkbox"/>								
Depromoted Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Seasonal Profile	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Deseasonalized Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Baseline Sales	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Measures: What-if Plot View

The What-if Plot view contains the following measures:

Baseline Sales

This measure is the result of the preprocessing run that smoothes the Depromoted Sales. Note how seasonality is preserved. This measure is used as the data source for the baseline forecasting generation.

Corrected Sales for OOS

This measure is the result of the preprocessing run that corrects for lost sales. It becomes the input to the preprocessing run that corrects for outliers.

Corrected Sales for Outliers

This measure is the result of the preprocessing run that corrects for outliers. Its purpose is twofold. It can be used as input to the preprocessing run that removes promotional sales, to eventually become the data source for baseline forecasting. It can also be used in conjunction with a seasonal profile, to remove seasonality, to become the data source for promotional forecasting.

Depromoted Sales

This measure is the result of the preprocessing run that removes promotional sales. It becomes the input to the preprocessing run that will smooth the sales.

Deseasonalized Sales

This measure is the result of the step where the Corrected Sales for Outliers and the Seasonal Profile have been combined to create sales with seasonality removed, but with promo information. This measure is used as the data source for the causal forecasting generation.

Out of Stock Indicator

This measure is either loaded or calculated by the rules in the custom menu. It is used during the pre-processing run that corrects sales for lost sales.

Outliers Indicator

This measure is either loaded or calculated by the rules in the custom menu. It is used during the pre-processing run that corrects the sales for outliers.

Promotion Indicator

This measure is usually calculated as the or of all available Boolean promotional variables. It is used during the preprocessing run that removes promotional sales.

Seasonal Profile

This measure represents the seasonal profile that is used to deseasonalize the Corrected Sales for Outliers. This happens using a simple RPAS rule – a call to the preprocessing special expression is not necessary. Note how the promotional sales are not removed.

Floating Event Administration Task

This chapter describes managing events and holidays for forecast generation in RDF using the [Floating Events Admin Workbook](#).

Use the [Floating Events Admin Workbook](#) to perform the step for this task:

- [Floating Event Admin Step](#)

About Floating Events

When managing periods when events are active, RDF has the [Floating Events Admin Workbook](#). Its one worksheet lists the events and you have the ability to flag periods when certain product/location combinations are active during an event.

A possible task scheduled to run before forecast generation is managing events and holidays, which may heavily impact a retailer's business. Some annual events such as Easter occur at a slightly offset week of the year from year to year. RDF needs to have some control over how these floating events and holidays will be managed along the time dimension so that their impact is not forecasted in the wrong time period. A lift associated with the event needs to be calculated, so it can be applied to the correct periods in the forecast horizon.

Management of this issue causes customers the pain, time and cost of configuring their data as this happens every year. This is a basic retail system requirement that the system should be able to address.

In a RDF causal implementation, an annual event that does not occur in the same period every year, but has a spike in demand associated with it, is handled by associating a causal factor to it. The system then determines the associated lift, and applies it to the relevant point in time in the forecast horizon.

In a RDF implementation, where there is no causal, these events still exist. For instance, an increase for sales leading to Easter will happen even if there is no promotion specifically associated with Easter (chocolate bunnies sell more during Easter even though they are not specifically promoted). And because it does not happen in the same time period every year, the Easter spike will appear randomly any time in March or April. The spike is baked in the seasonality of each item/store, making its prediction, timing, and magnitude; inaccurate at best.

RDF is able to handle such situations, not only through its causal capabilities, but also for baseline forecasting.

To do that, a set of events has to be defined. This usually happens at configuration time. Then, a user has to flag the periods where an event was active in the past (history) and in the future (forecast horizon). Once the dates are set up, the effect of the event is estimated based on past instances, and applied in the forecast horizon if the flag is active.

Floating Event Administration Tasks, Steps, and Views

The following table lists the workbooks, steps, and views for the Floating Event Administration task.


Workbook	Steps	Views
Floating Events Admin Workbook	Floating Event Admin Step	Floating Event Calendar Maintenance View

Floating Events Admin Workbook

To build the Floating Events Admin workbook, perform these steps:


1. Click the New Workbook icon in the Floating Events Administration task in the Core Forecasting activity.

Figure 13–1 Floating Events Administration Task




2. The Workbook wizard opens. Select the specific products that you want to view and click **Next**.

Figure 13–2 Workbook Wizard: Products




3. Select the specific stores that you want to view and click **Next**.

Figure 13–3 Workbook Wizard: Stores



4. Select the weeks you want to work with and click **Finish**.

Figure 13–4 Workbook Wizard: Select Weeks



The Floating Events Admin workbook is built.

Floating Event Admin Step

This step contains the Floating Event Calendar Maintenance view.

Floating Event Calendar Maintenance View

The Floating Event Calendar Maintenance view allows you to flag periods when certain product/location combinations are active during an event.

Figure 13–5 Floating Event Calendar Maintenance View

	4/19/2013	4/26/2013	5/3/2013	5/10/2013	5/17/2013	5/24/2013	5/31/2013	6/7/2013	6/14/2013
5 pocket capri - Bandblasted 1									
Float Event 01 Indicator	<input type="checkbox"/>								
Float Event 02 Indicator	<input type="checkbox"/>								
Float Event 03 Indicator	<input type="checkbox"/>								
Float Event 04 Indicator	<input type="checkbox"/>								
Float Event 05 Indicator	<input type="checkbox"/>								
Float Event 06 Indicator	<input type="checkbox"/>								
Float Event 07 Indicator	<input type="checkbox"/>								
Float Event 08 Indicator	<input type="checkbox"/>								
Float Event 09 Indicator	<input type="checkbox"/>								
Float Event 10 Indicator	<input type="checkbox"/>								
Float Event 11 Indicator	<input type="checkbox"/>								
Float Event 12 Indicator	<input type="checkbox"/>								
Float Event 13 Indicator	<input type="checkbox"/>								
Float Event 14 Indicator	<input type="checkbox"/>								
Float Event 15 Indicator	<input type="checkbox"/>								
Float Event 16 Indicator	<input type="checkbox"/>								
Float Event 17 Indicator	<input type="checkbox"/>								
Float Event 18 Indicator	<input type="checkbox"/>								
Float Event 19 Indicator	<input type="checkbox"/>								
Float Event 20 Indicator	<input type="checkbox"/>								

Measures: Floating Event Calendar Maintenance View

The Floating Event Admin view contains the following measures:

Float Event Indicator (01-20)

These measures, numbered 1-20, allow you to flag up to 20 float events as active in history or to be active in the future.

Extra Week Administration Task


The Extra Week Administration task allows you to manage forecasts for years that include an extra 53rd week. For additional information, see the section, [53 Week Calendar](#).

Extra Week Administration Workbook

To build the Extra Week Administration workbook, perform these steps:


1. Click the New Workbook icon in the Extra Week Administration task in the Core Forecasting activity.

Figure 14–1 Extra Week Administration Task




2. The Workbook wizard opens. Select the weeks you want to work with and click Next.

Figure 14–2 Workbook Wizard: Select Week



3. Select the groups you want to work with and click **Finish**.

Figure 14–3 Workbook Wizard: Select Group




The Extra Week Administration workbook is built.

Extra Week Indicator Setup View

The Extra Week Indicator Setup view allows you to set which week is the 53rd, or extra week. The measure can be selected in the [Extra Week Indicator Data Source](#) found in the [Final and Source Level Parameters View - Advanced Settings](#).

Figure 14–4 Extra Week Indicator Setup View



Measures: Extra Week Indicator Setup View

The Extra Week Indicator Setup view contains the following measure:

Extra Week Indicator

This indicator sets which week is the 53rd, or extra week. The [Extra Week Indicator Data Source](#) references the Extra Week Indicator.

Curve is an optional automated predictive solution that can generate ratio arrays from historical data at user-specified intersections. The profiles generated by Curve can be used for various purposes; for example, to convert the organization-level assortment plans into base-level weekly sales forecasts and to generate seasonal forecasts, daily forecasts, or new product forecasts using lifecycle profiles.

Curve meets the need of operational systems (such as Oracle Retail Demand Forecasting (RDF) and Oracle Retail Merchandising System (RMS)) to have sales unit predictions at a more detailed level than those provided by planning programs. The planning process attempts to establish the correct balance between different products in order to maximize sales opportunities in the available sales space. The planning process is supported by the generation of an assortment plan, which provides details of your anticipated sales volumes and stock requirements at aggregated levels. However, operational systems like RDF require data to be at the lowest level of execution (that is, item/store/week or item/store/day) because these systems are responsible for ensuring that the right quantity of each product is in the right store at the right time.

In the most basic sense, a profile represents the ratio of an aggregate dimension to the dimension for execution. For example, you may have a forecast generated at the item/store/week level, but for execution purposes the data must be spread down to the item/store/day level. It is the point of aggregation (source-level) and the desired destination intersection (final profile) that are the unique identifiers of each profile. Using this example, the point of aggregation of the data (where the data equals 100%) is item/store/week, and the desired destination intersection (where all data ratios sum to 100%) is item/store/day.

There are several parameters within RDF that may take a Curve-generated profile as an input. These are: Causal Aggregation Profile, Causal Spread Profile, Seasonal Profile, and Spreading Profile. The most common input from Curve that is used in RDF is the Spreading Profile. This profile can be manually generated and approved by you. It can also be dynamically generated as part of the RDF batch forecast process when the Curve solution is not necessary. For more information on the different profile parameters in RDF, refer to the section, "[Measures: Causal Parameters View - Advanced Settings](#)" on page 9-11.

Curve Tasks and Wizards

The Curve tasks and wizards allow you to manage the promotion events used in the system's promotional forecasting processes and view/edit the system's analysis of the effects of these events on demand.

The Curve tasks include:

Task Workbooks	Description
Profile Administration Task	Allows you to set default parameters for profile generation, which is the first step in profile generation.
Profile Approval Task	Allows you to view, analyze, revise, and approve generated profiles at historic levels.
Profile Maintenance Task	Allows you to set values for any subset of positions in Profile Administration.
Run Batch Profile Task	Allows you to generate batch profiles for all hierarchy positions set in the Profile Intersection.

Profile Administration Task


The Profile Administration Task allows you to set default parameters for profile generation, which is the first step in profile generation. These parameters are typically set during system implementation and are configured based on your business practices and needs. This configuration can be updated if you need to change certain parameters over time. However, it is not practical to change the configuration on a regular basis. The Profile Administration Task gives you the flexibility to change profiling parameters as the need arises to improve both forecasting accuracy and computational efficiency.

Profile Administration Workbook

To build the Profile Administration workbook, perform these steps:


1. Click the New Workbook icon in the Profile Administration task in the Core Forecasting activity.

Figure 15–1 Profile Administration Task



- The Workbook wizard opens. Select the Curve level and click **Finish**.

Figure 15–2 Workbook Wizard: Curve Level




The Profile Administration workbook is built.

Profile Parameter View

The Profile Parameter View allows you to specify default values for parameters affecting profile generation. [Figure 15–3](#) provides an example of the Profile Parameters view in a Master Domain with three partitions/Local Domains, partitioned on Group.

Figure 15–3 Profile Parameter View



Measures: Profile Parameter View

The following is a description of the measures that are contained in the Profile Parameter View:

Default Phase End

The Default Phase End defines the end date of the period in which profile results will be applied. Click the pop-up calendar to change the value in this field. If phase definitions are unavailable, the default phase end date will be used. When calculating time profiles, default dates are used for intermediate computations. For computational efficiency, use the most common phase definition as the default value.

Default Phase Start

The Default Phase Start defines the first date of the period in which profile results will be applied. Click the pop-up calendar to change the value in this field. If phase definitions are unavailable, the default phase start date will be used. When calculating time profiles, default dates are used for intermediate computations. For computational efficiency, use the most common phase definition as the default value.

Default Profile Approval Method

The Default Profile Approval Method displays the primary approval policy to be used for the profile. Select *Approve Use System* if the profile results are to be automatically approved during the batch profile generation. Select *Do Not Approve* if the profile results are to be manually approved by you. If a profile is being generated dynamically (to support Source Level Forecasting) as part of the RDF batch forecast process, the Default Profile Approval Method should be set to Approve Use System.

Default Source Profile

The Default Source Profile determines the primary source-level that will be used to generate the profile. When only a single source is configured for a profile, all profile results will be calculated using the same intersections. When multiple sources are defined for a profile, some profile results will be calculated using different intersections. The Profile Maintenance Task may be used to define exceptions to the Default Source Profile.

Default Training Window End

The Default Training Window End defines the last date in history that will be used to calculate profile results. Click the pop-up calendar to change the value in this field. The default date will be used only if the training window method is set to Defaults and Overrides.

Default Training Window Start

The Default Training Window Start defines the first date in history that will be used to calculate profile results. Click the pop-up calendar to change the value in this field. The default date will only be used if the training window method is set to Defaults and Overrides.

Normal Value

If the profile is aggregated to the Aggregation Intersection, this will be the value in all the cells (or zero outside of the phase window). The desired setting for Normal Value is usually 1.00 (100%); however, there may be instances where it is desired to have the profile normalize to a value different than 1.00. For example, when generating seasonal profiles, such as by Week of Year, the Normal Value needs to be set to 52.

Profile Data Source

The Profile Data Source displays the name of the measure that contains the data to be used to generate the profile.

Note: For Dynamic profiles used by RDF, the profile Data Source can be left blank. Curve will use the Interim Forecast generated by RDF as the Data Source for generating the profile, and the value specified here will be ignored.

Profile Type

The Profile Type is a read-only measure that displays the value for this measure set in the Curve Plug-In. The Profile Type is used to determine the profile algorithm and validation required by the profile level. Profile Types are represented with pre-defined configuration information.

The following Profile Types share the same profile algorithm. The rationale for providing different types that have the same behavior is strictly to remind you of the intent of the profile while using this task:

- **Store Contribution Profile** - The Store Contribution Profile is used to determine the data relationship between stores to aggregate dimensions in the location hierarchy.
- **Daily Profile** - The Daily Profile is used to determine the data relationship between a given day to the week in which it belongs.
- **Hourly Profile** - The Hourly Profile is used to determine the spreading ratios from aggregate dimensions to the hour, hour of day, or hour of week dimensions.
- **Product Profile** - The Product Profile is used to determine the data relationship between any two dimensions along the product hierarchy.
- **Size Profile** - Size profiles are used to determine the data relationship between any size in the product hierarchy and another dimension in the product hierarchy. Note that size can be configured as a dimension along an alternate roll-up along the product hierarchy, such as itemParent-size.
- **User Defined Profile** - The User Defined Profile may be used to support any basic profile configuration.

The following Profile Types have unique behavior:

- **Diff Profile** - Diff Profiles are used to determine spreading ratios from aggregate dimensions in the Product hierarchy to diff dimensions. Used to support the spreading of data in RMS Allocation, Diff Profiles exhibit the same behavior as the previous profile types. However, unique to Diff Profiles is special validation of the relationship between the defined diff dimensions to dimensions along the main branch of the Product hierarchy. Refer to the *Oracle Retail Demand Forecasting Implementation Guide* for more information on validation criteria.
- **Daily Seasonal Profile** - The Daily Seasonal Profile is used to determine the data relationship between a given day of the week to aggregate dimensions in the calendar hierarchy. This profile type uses training window data to compute the profile. The resulting profile is then clipped to fit within the defined phase window.
- **Life Cycle Profile** - The Life Cycle Profile uses data along a user-defined training window and then stretches or shrinks data to fit a user-defined phase window.

Renormalize

Renormalize is a Boolean measure. When set to *True*, it automatically renormalizes the calculated profile result at the corresponding final-level. Typically, the renormalization is not necessary. For example, if you have a source profile at week of season and its final profile is at day of season, you would need to renormalize the final-level because going from week to day will do replication. At day level, the profile will sum up to greater than one (1) for a season. Since it was a week to day, it will probably sum up to seven. The renormalize will force the final profile to sum to 1.00 (100%).

System Training Window Length

The System Training Window Length is necessary when Use Training Window is set as the Training Window Method for the profile. This field specifies the number of weeks of the most recent data to use as the training window for calculating the profile. The System Training Window Length defaults to 10 weeks.

Training Window Method

The Training Window Method is used to determine the default method that is used to define the training window. The options are:

- **Default and Overrides** - Uses the default dates as set in the Training Window Start Date and Training Window End Date measures.
- **Phase Definitions and Overrides** - Calculates the Training Window Start Date and Training Window End Date based on the Phase Start Date and Phase End Date measures.
- **Use Training Window** - Used with System Training Window Length to specify the number of weeks of the most recent data to use for calculating the profile.

Use Advanced Profile Features

This parameter is selected by default; however, if dynamic profiles are being generated during the RDF batch process, setting this parameter to *False* (unchecked) improves batch performance by skipping unnecessary processes in the creation of the dynamic profiles.

When this is cleared, RDF automatically rolls the Training window and Phase windows forward with the forecasts for Dynamic profiles. When selected, you must manually manage the Phase Date windows for which the profile is generated.

Note: When the Use Advanced Profile Features is cleared, then the approved profile is just a direct copy of the system generated profile. Advanced Profile Features must be enabled to use the [Profile Approval Method](#).

Profile and Source Level Intersection View

The Profile and Source Level Intersection View is a read-only view to the different intersections defined for the Profile and Source level configured in the Curve Plug-in. Refer to the *Oracle Retail Predictive Application Server Solution Extension Configuration Guide* for more information on defining these intersections during configuration of the Curve Solution.

Figure 15–4 Profile and Source Level Intersection View

	01 chn->str	02 chn-str
Profile Agg Intersection	weekitemchn_	weekitemchn_
Profile Approval Intersection	weekitemchn_	
Profile Intersection	weekitemstr_	weekitemstr_
Stored Intersection	weekitemstr_	weekitemstr_

Measures: Profile and Source Level Intersection View

The following is a description of the measures that are contained in the Profile and Source Level Intersection View:

Profile Agg Intersection

The Profile Agg Intersection is the intersection where the profile will sum to one (or 100%). If the profile is being used as the Spreading Profile in RDF, this Aggregation Intersection should be the same as the Source Forecast Level.

Profile Approval Intersection

Assigned only at the Final Profile, the Approval Intersection is the intersection where the profile is approved. Approval Intersection should be higher than or equal to the Aggregation Intersection. If the profile is being used as the Spreading Profile in RDF, this Approval Intersection should be the same as the Aggregation Intersection.

Profile Intersection

The Profile Intersection is the intersection where an intermediate profile is calculated. This intermediate profile is then replicated down or aggregated up to the Stored Intersection. If the Store Intersection is the same as the Profile Intersection, the values in intermediate profile are copied to the Stored Intersection. The Profile Intersection must be lower than the Aggregation Intersection.

If the profile is being used as the Spreading Profile in RDF, this Profile Intersection should be the same as the Final Forecast Level.

Stored Intersection

The Stored Intersection is the destination intersection of the profile. The intermediate profile produce at the Profile Intersection is either replicated down to or aggregated up to the Stored Intersection. If the Store Intersection is the same as the Profile Intersection, the values in intermediate profile are copied to the Stored Intersection. The Stored Intersection should not be greater than the Aggregation Intersection. If the profile is being used as the Spreading Profile in RDF, this Stored Intersection should be the same as the Profile Intersection.

Profile Approval Task

The profiles generated at the historic levels must be viewed, analyzed, revised, and approved using the Profile Approval Task. In the approval process, you select the appropriate source-level for each product/location combination. After you make any necessary changes to the profiles and commit the task, the profiles are normalized to preserve the appropriate ratios. At this time, Curve automatically spreads the source-level profiles to the final-level and combines them. After you commit your

changes, you can refresh the data in your task to display the newly generated final-level profiles.

Use the Profile Approval Task to view, analyze, revise, and approve the profiles generated at the historic levels. This task contains three tabs for each view displayed:


- [Final Profile View](#)
- [Source Profile View](#)
- [Profile Approval View](#)

Profile Approval Workbook

To build the Profile Approval workbook, perform these steps:


1. Click the New Workbook icon in the Profile Approval task in the Core Forecasting activity.

Figure 15–5 Profile Approval Task




2. The Workbook wizard opens. Select the Curve level and click **Next**.

Figure 15-6 Workbook Wizard: Curve Level




3. Select the items you want to work with and click Next.

Figure 15-7 Workbook Wizard: Select Item




4. Select the stores you want to work with and click Next.

Figure 15–8 Workbook Wizard: Select Stores



5. Select the days you want to work with and click **Finish**.

Figure 15–9 Workbook Wizard: Select Day



The Profile Approval workbook is built.

Final Profile View

Through this view, you can view the system- calculated final profile and make adjustments to this profile. [Figure 15–10](#) is an example of the Final Profile View.

Figure 15–10 Final Profile View

	1/2/1998
Adjusted Profile 01 chn->str Final	0.00
System Profile 01 chn->str Final	0.00
Approved Profile 01 chn->str Final	0.00

Measures: Final Profile View

The Final Profile view contains the following measures:

Adjusted Profile

This is the user-adjusted profile. If edits are necessary to the Adjusted Profile, it is first required to lock the Adjust Profile at the Aggregation Intersection. This prevents the Normal Value from recalculating to a value different than 1.00 (100%) when the adjustments are made. To determine the Aggregation Intersection, view the intersection displayed on the Approval view.

Once adjustments are made to the profile, you must go to the Final Profile View and set the approval method to *Do Not Approve* for the adjusted profile intersection. The Approved Profile measure updates with these changes.

Approved Profile

The Approve Profile displays the approved profile values. If a profile intersection is set to Do Not Approve, no value will be displayed in this field. The system automatically approves all profile intersections set to Approve Use System. If changes are made to the Adjusted Profile, the values in this measure update once the Manually Approved flag is set to *True* in the Final Profile View.


System Profile

A read-only measure that displays the system-generated profiles calculated at the final profile's profile intersection.

Source Profile View

The Source Profile View displays the profiles generated at the source-level for all product/location/calendar combinations selected to appear in the task. This view displays the source system profiles (that is, the profiles that are calculated by the system during the profile generation process).

Figure 15–11 Source Profile View



Measures: Source Profile View

The following measure is contained in the Source Level View:


System Profile

A read-only measure that displays the system-generated profiles calculated at the source profile's profile intersection for each product/location combination displayed.

Profile Approval View

The Profile Approval View allows you to review and approve final profiles.

Figure 15–12 Profile Approval View



Measures: Profile Approval View

The Profile Approval View contains the following measures.

Profile Approved By

This measure displays who approved the profile for a given product/location combination. For all profile intersections with an Approval Method set to Approve Use System and no adjustment occurs, the Approved By measure will contain System.

Profile Approval Date

Displays the date on which a profile was approved, whether it is automatically approved by the system or manually approved by you.

Manually Approve

A Boolean measure that must be activated (checked) for all profile intersections that are set to *Do Not Approve* or for intersections in which you make changes to the Adjusted Profile on the Final Profile view.

Source Profile Override

This field displays the source-level that was used to generate the profile. If the Default Source Level was used, this measure will display No Override.

Profile Maintenance Task


After setting default parameters for profile generation in the [Profile Administration Task](#), the next step in profile generation is to select any subset of positions for which the values set in Profile Administration differ from the defaults. This step is necessary in those situations where it is not efficient to use the same parameters for all positions in the hierarchy data.

Profile Maintenance Workbook

To build the Profile Maintenance workbook, perform these steps:


1. Click the New Workbook icon in the Profile Maintenance task in the Core Forecasting activity.

Figure 15–13 Profile Maintenance Task




2. The Workbook wizard opens. Select the Curve level and click **Next**.

Figure 15–14 Workbook Wizard: Curve Level




3. Select the products you want to work with and click **Next**.

Figure 15–15 Workbook Wizard: Select Items




4. Select the locations you want to work with and click **Next**.

Figure 15–16 Workbook Wizard: Select Stores



5. Select the days you want to work with and click **Finish**.

Figure 15–17 Workbook Wizard: Select Day



The Profile Maintenance workbook is built.

Profile Maintenance: Final Approval and Sourcing View

The Final Approval and Sourcing view allows edits to intersections that vary from the default values set in the Profile Administration Task.

Figure 15–18 Final Approval and Sourcing View

	10000013Leather	10000014Leather	10000015Leather	10000016Leather	10000017Leather
Profile Approval Method 01 chn->str Final	No Override				
Source Profile Override 01 chn->str Final	No Override				

Measures: Final Approval and Sourcing View

Profile Approval Method

The Profile Approval Method displays the primary approval policy that is used for the profile. No Override is displayed in this field if the Default Approval Method is used. *Select Approve Use System* if profile results are to be automatically approved during the batch profile generation. Select *Do Not Approve* if profile results are to be manually approved by you. If a profile is being generated dynamically (to support Source Level Forecasting) as part of the RDF batch forecast process, the Default Profile Approval Method should be set to Approve Use System.

Note: The Profile Approval Method is only used when the [Use Advanced Profile Features](#) are enabled.

Source Profile Override

Make edits to the Source Profile Override if the source-level for an intersection varies from the Default Source Profile. No Override is displayed in this field if the value set in the Default Source Profile is to be used. When only a single source is configured for a profile, all profile results are calculated using the same intersections. Therefore, edits to this parameter are not required. When multiple sources are defined for a profile, some profile results are calculated using different intersections. Select the appropriate source-level for an intersection.

Profile Maintenance: Final Training Window View

Figure 15–19 Final Training Window View

	10000013Leather	10000014Leather	10000015Leather	10000016Leather	10000017Leather
System Training Window Begin 01 chn->str Final					
System Training Window End 01 chn->str Final					

Measures: Final Training Window

The following is a description of the measures contained in the Final Approval and Sourcing View:

System Training Window Begin

Select a date in this field if this date is different from the default value set in the Training Window Start date in Profile Administration. Click the pop-up calendar to change the value in this field.

System Training Window End

Select a date in this field if this date is different from the default value set in the Training Window End date in Profile Administration. Click the pop-up calendar to change the value in this field.

Run Batch Profile Task

The batch profile generation process creates profile results for all hierarchy positions set in the Profile Intersection. Profiles may be run from the back-end of the domain using the *curvebatch* executable or run manually using the Run Batch Profile workbook. For more information on *curvebatch*, refer to the *Oracle Retail Predictive Application Server Administrators Guide*.


Run Batch Profile Workbook

The Run Batch Profile wizard automatically executes *curvebatch* within the Simple or Local Domain. If **Next** is selected from the last wizard window, the wizard will not advance to the completion message until the profiles have been generated. Depending on the data set, this process may take a several minutes before the system advances to the final window.

To run the Run Batch Profile wizard, perform these steps:


1. Click the New Workbook icon in the Run Batch Profile task in the Core Forecasting activity.

Figure 15–20 Run Batch Profile Task




- The Workbook wizard opens. Select the Curve level and click **Next**.

Figure 15–21 Workbook Wizard: Curve Level



- Verify the Curve level and click **Finish**.

Figure 15-22 Workbook Wizard: Verify Curve level



The Run Batch Profile workbook is built.

Run Batch Forecast Task

The Run Batch Forecast Task wizard allows you to manually execute the forecast generation process at a time other than the regularly scheduled batch job. If a global domain environment is implemented, forecasts generated in the Local domain can be viewed in the Master domain; however this forecast is isolated to the data in the Local domain. The execution of PreGenerateForecast at the Master domain, then passing the output of the process to Generate from the back-end of each Local domain allows for the Local domains to share a birth date, thus supporting a view to forecast data across Local domains in the Master domain. Refer to the *Oracle Retail Demand Forecasting Implementation Guide* for more information on PreGenerateForecast and Generate.

Running a Batch Forecast Manually

The following sections describe the procedures to manually run a batch forecast.

Before You Begin

Prior to using the Run Batch Forecast Task wizard, at minimum the following tasks must be performed:

1. Create or access a [Forecast Administration Workbook](#).
2. In the Forecast Start Date measure, enter the starting date of the forecast horizon; otherwise the system defaults to the system date (today).
3. Set a Default Forecasting Method for the Final and Source Level.
4. Set a Default Source Level for the Final Level.
5. Set the Forecast Length if there is no value already in this measure.
6. Set the Spreading Profile if the Source Levels are at aggregate dimensions above the Final Level.
7. Commit any changes by selecting from the **File** menu, then select **Commit Now**.
8. Close the task.

Procedure

Follow these steps to manually run a batch forecast:

1. Within the Local or Simple domain, select **New** from the File menu.
2. Select the Forecast tab to display a list of task workbooks for statistical forecasting. Highlight Run Batch Forecast and click **OK**.

3. The Run Batch Forecast wizard opens and prompts you to select the Final Levels to forecast. Select **Next** or **Finish**.

The Run Batch wizard automatically executes PreGenerateForecast and Generate within the Simple or Local Domain. If **Next** is selected from the last wizard window, the wizard does not advance to the completion message until the forecast has been generated. Depending on the amount of product/locations to be forecast and the forecast horizon, it may take a several minutes before the system advances to the final window. When the forecast generation is completed, the wizard displays a window that notifies you of the forecast generation ID.

After a forecast is generated, the Forecast Start Date field is cleared. This ensures that the same forecast is not generated again on the same date. The Next Run Date field is also updated based on the birth date of the forecast plus the Forecast Cycle. Both fields can be viewed in the [Forecast Administration Workbook](#).

Run Batch Forecast Workbook


To build the Run Batch Forecast workbook, perform these steps:

1. Click the New Workbook icon in the Run Batch Forecast task in the RDF Administration activity.

Figure 16–1 Run Batch Forecast Task



2. The Workbook wizard opens. Select the levels to work with and click **Next**.

Figure 16–2 Workbook Wizard: Select Final Forecast Level

3. Verify and click **Finish**.

Figure 16–3 Workbook Wizard: Verify

The Run Batch wizard automatically executes `PreGenerateForecast` and `Generate` within the Simple or Local Domain. Depending on the amount of product/locations to be forecast and the forecast horizon, it may take a several minutes before the system advances to the final window. When the forecast generation is completed, the wizard displays a window that notifies you of the forecast generation ID.

After a forecast is generated, the Forecast Start Date field is cleared. This ensures that the same forecast is not generated again on the same date. The Next Run Date field is also updated based on the birth date of the forecast plus the Forecast Cycle. Both fields can be viewed in the [Forecast Administration Workbook](#).

Forecast Approval Task

After the forecast is generated, the next steps in the forecasting process are analysis and approval. Approval of forecasts is required before the forecast data can be exported to other processes, such as replenishment programs. The Forecast Approval task allows you to view, analyze, adjust, and approve forecast results.

Some system forecasts may be set to be automatically approved by the system. The default approval method for items in a forecast is set in the [Forecast Administration Workbook](#), and these policies can be amended for individual product/location combinations in the [Forecast Maintenance Workbook](#). Any forecasts not set to Automatic Approval may require evaluation, adjustments, and ultimately approval before subsequent processes are executed.

You can view and analyze forecast data at multiple forecast levels (source-level and final-level) simultaneously. Revisions to and approvals of final-level forecast values are made on the appropriate views in the Forecast Approval task. The Forecast Approval task can contain these views:

Table 17–1 Views for the Forecast Approval Workbook

View	Description
Advanced Final Level View	This view displays all the regular price and promotional forecasting components
Final Level View	This view allows you to review final-level system-forecast quantities and make revisions to them if needed.
Approval View	This view allows you to specify the manual approval policy of forecasts by product and location.
Valid Forecast Run View	This view allows you to review the partition dimensions in which the generated forecast was run.
Source Level View	This view displays the system-generated source-level forecast and allows you to compare this data with final-level forecast values.
Final or Source System Parameters View	<p>The <i>Final System Parameters</i> view is only available if Generate System Parameters or Generate Methods is turned on in the Forecast Administration Workbook.</p> <p>The <i>Source System Parameters</i> view is only available if Generate System Parameters or Generate Methods is turned on in the Forecast Administration Workbook, and a Source Level was designated in Forecast Administration.</p>

When the Forecast Approval task is displayed, you may review the system-generated forecast and measures for any levels included in the task and make adjustments to forecast values at the final-level. Forecast values are overwritten in the Adjusted Forecast measure on the Final Forecast view. Approvals are made for each

product/location combination in the Approval Method measure of the Forecast Approval view.


After you complete your work, you can save the task using the Save function on the File menu. To update the master database with the approved forecast values, you must commit the task using the Commit Now or Commit Later option on the File menu. Once the task is committed, the forecast values are stored in the master database and can be used by other processes.

Forecast Approval Workbook


To build the Forecast Approval workbook, perform these steps:

1. Click the New Workbook icon in the Forecast Approval task in the Core Forecasting activity.


Figure 17–1 Forecast Approval Task



2. The Workbook wizard opens. Select the final forecast level you want to work with and click **Next**.

Figure 17–2 Workbook Wizard: Select Final Forecast Level

3. Select the forecast levels you want to work with and click **Next**. Select as many forecast levels as necessary for comparison.

Figure 17–3 Workbook Wizard: Select Forecast Levels

4. Select the forecast generation date you want to work with and click **Next**.
 - Select **Use the most recently generated forecast** to build a task containing the most recent forecast values.

Note: Use the most recently generated forecast - it must be selected if the task supports an AutoTask build.

- Click **Select from a list of forecast** to select from a list of previously generated forecasts stored in the system. Note that if this option is selected, the system automatically highlights the first forecast in the list, and if no further selections are made by you, this first forecast is used.
- If no selection is made by you, the birth date defaults to the latest generated generation ID.


Figure 17-4 Workbook Wizard: Select Forecast Generation Date



5. Select the stores you want to work with and click **Next**.

Note: It is important to include all locations that are members of the location dimensions in the forecast levels to be analyzed. For example, if you select to view a forecast level that is defined at item/chain/week, you should include all locations that are members of the particular chain to be analyzed. It is recommended that Position Query functionality or selection from aggregate levels in the Location hierarchy is employed if the task is generated using AutoTask build.


Figure 17-5 Workbook Wizard: Select Stores



6. Select the items you want to work with and click **Next**.

Note: It is important to include all products that are members of the Merchandise dimensions in the forecast levels to be analyzed. For example, if you select to view a forecast level that is defined at subclass/store/week, you must include all items that are members of the particular subclass to be analyzed. It is recommended that Position Query functionality or selection from aggregate levels in the Merchandise hierarchy is employed if the task is generated using AutoTask build.


Figure 17–6 Workbook Wizard: Select Item



7. Select the first date of history you want to work with and click **Next**.


You may choose to either set the **Forecast Start Date minus the number of periods** or select the first date of history from the displayed list. It is recommended that the **Forecast Start Date minus the number of periods** is set if the task is generated using AutoTask build.

Note: If you make no selection, the system uses the forecast start date.

Figure 17-7 Workbook Wizard: History First Date

8. Select the last date in the forecast horizon you want to work with and click **Next**.


You may either choose to **Include the following number of time periods** of the forecast horizon or select the last date to include of the horizon from the displayed list. It is recommended that **Include the following number of time periods of the forecast horizon** is set if the task is generated using AutoTask build. The value entered must be within the forecast horizon. Click **Next**.

Figure 17–8 Workbook Wizard: Forecast Horizon Last Date

9. Select the last date in the calendar you want to work with and click **Next**.

You may choose to either set the **Forecast end date plus the following number of time periods** or select the last date to include of the post-horizon calendar from the displayed list. It is recommended that **Forecast end date plus the following number of time periods** is set if the task is generated using AutoTask build. Click **Next**.


Note: If you make no selection, the system uses the last date in the forecast horizon chosen by you in the previous wizard window.

Figure 17–9 Workbook Wizard: Calendar Last Date

10. Select any additional forecast measures you want to work with in your task. The valid values of these measures may only be viewed if **Generate Intervals**, **Generate Cumulative Intervals**, **Generate Methods**, **Generate Parameters**, **Generate Baselines**, or **Store Interim Forecasts** were selected in the [Forecast Administration Workbook](#). Click **Finish**.

Note: If any of these parameters are included in the Forecast Approval task using AutoTask build and are later deselected for generation in the [Forecast Administration Workbook](#), AutoTask must be set again.

Figure 17–10 Workbook Wizard: Additional Forecasting Measures



The Forecast Approval workbook is built.

Advanced Final Level View

This view displays all the regular price and promotional forecasting components. These include Self Lifts, as well as Halo and Cannibalization Effects for Regular Price and Promotions. This information is read-only.

Figure 17–11 Advanced Final Level View

	12/21/2001	12/28/2001	1/4/2002	1/11/2002	1/18/2002	1/25/2002	2
Regular Price 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Regular Price Cannibalization Lift 1 - itm/str/week-Final							
Regular Price HALO Lift 1 - itm/str/week-Final							
Regular Price Self Lift 1 - itm/str/week-Final							
Total Regular Price Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Self Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Halo Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Cannibalization Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total Promotion Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Promotion Indicator 1 - itm/str/week-Final	<input type="checkbox"/>						

Measures: Advanced Final Level View

The Advanced Final Level view contains the following measures:

Promotion Cannibalization Lift Units

This measure displays the negative effect, measured in units, that the promotion of certain items has on this item. The [Default Apply Interaction Factor](#) is set to True and the [Default Interaction Factor](#) is set to a value other than 1. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

Promotion Halo Lift Units

This measure displays the positive effect, measured in units, that the promotion of certain items has on this item. If the [Default Apply Interaction Factor](#) is set to True and the [Default Interaction Factor](#) is set to a value other than 1, the displayed lift is the result of the combination of various lift types. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

Promotion Indicator

If this measure is checked (*True*), it indicates that a given item/location has any promotion active for a time period

Promotion Self Lift Units

This measure displays the effect that a promotion has on the sales units of an item. If the [Default Apply Interaction Factor](#) is set to True and the [Default Interaction Factor](#) is set to a value other than 1, the displayed lift is the result of the combination of various lift types. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

Regular Price

This measure displays the price for which the item has sold at the given store. This is a time-phased measure, and you can see how a change in price drives the regular price effects.

Regular Price Cannibalization Lift

This measure displays the negative effect, measured in units, that a price change of certain items has on this item. If the [Default Apply Interaction Factor](#) is set to True and the [Default Interaction Factor](#) is set to a value other than 1, the displayed lift is the result of the combination of various lift types. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

Regular Price Halo Lift

This measure displays the positive effect, measured in units, that a price change of certain items has on this item. If the [Default Apply Interaction Factor](#) is set to True and the [Default Interaction Factor](#) is set to a value other than 1, the displayed lift is the result of the combination of various lift types. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

Regular Price Self Lift

This measure displays the effect that a price change has on the sales units of an item. If the [Default Apply Interaction Factor](#) is set to True and the [Default Interaction Factor](#) is set to a value other than 1, the displayed lift is the result of the combination of various lift types. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

Total Promotion Lift Units

This measure displays the total effect that promotions can have on an item's sales units. It is the combination of Promotion Self Lift Units, Promotion Halo Lift Units and Promotion Cannibalization Lift Units. The default way to combine the promotional lifts is to sum them up. However, if the Default Apply Interaction Factor is set to True and the Default Interaction Factor is set to a value other than one, the Total Promotion Lift Units is not the straight summation of the three promotion lift measures.

Note: If the measure, [Apply Promotional Lift Override](#), is selected in the [Advanced Final Parameter View](#), then RDF ignores the system calculated lifts and applies the [Aggregated Promotion Lift Override](#). It only applies the override in the week that has a promotion.

Total Regular Price Lift Units

This measure displays the total effect that regular price changes can have on an item's sales units. It is the sum of Regular Price Self Lift, Regular Price Halo Lift, and Regular Price Cannibalization Lift.

Final Level View

The Final Level view allows you to review the forecast quantities and make adjustments to forecasts if needed. The primary objective in the Forecast Approval task is to review and edit forecast values using the Adjusted Forecast field on the Final Level view and ultimately approve forecasts that have been user-adjusted or require manual approval.

Figure 17–12 Final Level View

	7/6/2001	7/13/2001	7/20/2001	7/27/2001	8/3/2001	8/10/2001	8/17/2001	8/24/2001	8/31/2001
Adjusted Forecast 1 - itm/str/week-Final	0.00	155.77	149.54	41.59	37.81	19.00	19.00	18.00	18.00
System Forecast 1 - itm/str/week-Final	0.00	155.77	149.54	41.59	37.81	19.00	19.00	18.00	18.00
Approved Forecast 1 - itm/str/week-Final	0.00	155.77	149.54	41.59	37.81	19.00	19.00	18.00	18.00
Last Approved Forecast 1 - itm/str/week-Final	0.00	155.77	149.54	41.59	37.81	19.00	19.00	18.00	18.00
Approved System Forecast 1 - itm/str/week-Final	0.00	155.77	149.54	41.59	37.81	19.00	19.00	18.00	18.00
History Data - Weekly Sales	25.00	22.00	19.00	17.00	20.00	17.00	22.00	19.00	17.00
Overlapping Promotion Flag 1 - itm/str/week-Final	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>					
Total Regular Price Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Demand Transference Lift Units 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interaction Multipliers 1 - itm/str/week-Final	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total Promotion Lift Units 1 - itm/str/week-Final	0.00	130.77	125.54	19.59	17.81	0.00	0.00	0.00	0.00
System Baseline 1 - itm/str/week-Final	0.00	25.00	24.00	22.00	20.00	19.00	19.00	18.00	18.00
Adjusted Baseline 1 - itm/str/week-Final	0.00	25.00	24.00	22.00	20.00	19.00	19.00	18.00	18.00
Total Peak 1 - itm/str/week-Final	0.00	130.77	125.54	19.59	17.81	0.00	0.00	0.00	0.00
Adjusted Peak 1 - itm/str/week-Final	0.00	130.77	125.54	19.59	17.81	0.00	0.00	0.00	0.00

Measures: Final Level View

The Final Level view contains the following measures:

Adjusted Cumulative Interval

When changes are made to the Adjusted Forecast, the value of the Forecast Cumulative Interval is recalculated in this measure. The values in this measure are read-only. To view and store this measure:

- Generate Cumulative Intervals must be selected in the [Forecast Administration Workbook](#).
- Cumulative Intervals must be selected to be viewed in the Forecast Approval wizard.

Adjusted Forecast

The value in this field initially defaults to the System Forecast if the forecast is automatically approved by the system or through a Forecast Approval Alert. Otherwise, the value in the Adjusted Forecast is different than the System Forecast if:

- Adjusted Forecast has been updated by you.
- Keep Last Changes is set to Total, Difference or Ratio.
- Update Last Weeks Forecast is set to Replicate.

Changes to the Adjusted Forecast are automatically approved. The Approval view updates with the date of the adjustment and the name of the user who made the adjustment.

Note: Changes to the Adjusted Forecast for periods outside of the forecast horizon are not committed.

Edits to any non-committed values in the [Forecast Approval Workbook](#) are overwritten when data is refreshed.

Approved Cumulative Interval

The Approved Cumulative Interval is the cumulative interval that was approved at the time of the task build. The values contained in this measure are read-only. If changes are made to the Adjusted Forecast, the Approved Cumulative Interval reflects the recalculated values when the task is committed and data is refreshed.

Approved Forecast

The Approved Forecast is the forecast quantity that was approved at the time of the task build. The values contained in this measure are read-only. If changes are made to the Adjusted Forecast, then click **Calculate** to show the new value in the Approved Forecast.

Approved System Forecast

The Approved System Forecast is populated with the last System Forecast approved for a time series:

1. Approval Method set to Automatic Approval
2. Approval Method set to a Forecast Approval Alert and the alert is not triggered
3. Update Last Weeks Forecast is set to Use Forecast

The values in this measure are read-only.

Demand Transference Lift Units

This measure displays the total lift caused by assortment changes. This is a time-phased measure, and you can see how assortment changes drive the demand transference lift in unit.

If the Default Apply Interaction Factor is set to True and the Default Interaction Factor is set to a value other than 1, the displayed lift is the result of the combination of

various lift types. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

Forecast Cumulative Interval

Cumulative Intervals are used in safety stock calculation within allocation and replenishment systems. This value is similar to a running total of the Forecast Interval and is read-only. To see this measure:

- Generate Cumulative Intervals must be selected in the [Forecast Administration Workbook](#).
- Cumulative Intervals must be selected to be viewed in the Forecast Approval wizard.

Forecast Interval

The Forecast Interval is calculated on the particular forecast region as capped standard deviation for some methods. It takes into consideration the system forecast for capping as well.

The forecast interval for any given week i is capped to a maximum of:

$$\text{Forecast}(i) * \text{upperCapRatio}$$

This cap is applied once the interval exceeds the system forecast, and it is applied for every value of the interval after that. The upperCapRatio (Interval Cap Upper Ratio) is a parameter set in the [Forecast Administration Workbook](#).

The forecast interval is capped to a minimum of $\text{Forecast}(i) * \text{lowerCapRatio}$ whenever the interval is less than this quantity. The lowerCapRatio (Interval Cap Lower Ratio) is another parameter set in the [Forecast Administration Workbook](#).

When forecasts are approved, the corresponding Intervals and Cumulative Interval measures are approved. To see this measure:

- Generate Intervals must be selected in the [Forecast Administration Workbook](#).
- Intervals must be selected to be viewed in the Forecast Approval wizard.

Forecast vs. Last Approved Forecast Workbook Alert

This measure is the target measure of a real time alert. It compares current forecast with the forecast generated last period, and if the difference is more than a threshold, the alert is triggered which is visible by the different format of the cells.

Forecast vs. Recent Sales Workbook Alert

This measure is the target measure of a real time alert. It compares forecast with recent/ past sales, and if the difference is more than a threshold, the alert is triggered which is visible by the different format of the cells.

History Data

History Data (a read-only measure) is the sales data used to generate the forecast. This allows you to compare Actuals to forecast values. When the task is created, the Data Source measure is copied into History Data.

Interaction Multiplier

The measure displays the interaction factor's impact when the [Default Apply Interaction Factor](#) is set to True and the [Default Interaction Factor](#) is set to a value other than 1. The value in this field equals to the combined total lift divided by the linearly added up lifts

If Apply Interaction Factor is set to False, or the Interaction Factor is set to 1, the value in this field will equal to 1.

Interim Forecast

The Interim Forecast is the forecast generated at the final-level that is used as the Data Source in Curve to produce the Spreading Profile. This profile determines how the Source Forecast is spread down to the Final Forecast level. The values in this measure are read-only. To see this measure:

- Generate Interim Forecast must be selected in the [Forecast Administration Workbook](#).
- Interim Forecast must be selected to be viewed in the Forecast Approval wizard.

Last Approved Forecast

The Last Approved Forecast is the approved system forecast value when an approval occurred on a previous batch forecast for the time series. The values contained in this measure are read-only.

Overlapping Promotion Flag

If this read-only measure is checked (True), it indicates that a given item/location has active overlapping promotions for at least one time period in the forecast horizon. To view and store this measure:

- Enhanced Approach must be selected for Overlapping Promotion Behavior in the [Forecast Administration Workbook](#)) or overwritten in [Forecast Maintenance Workbook](#)
- A specific overlapping promotion is found significant during the stepwise regression.
- The significant overlapping promotion is in the forecast horizon.

Return Forecast

If the Return Forecast option is enabled, this measure displays the units per week that are returned to the store.

System Baseline

The System Baseline is a forecast generated on past sales data that contains no promotions (that is, normal demand given no causal effects). To see a generated Baseline Forecast:

- Promotional Forecasting must be implemented.
- Generate Baseline must be selected in the [Forecast Administration Workbook](#).
- The System Baseline must be selected to be viewed in the Forecast Approval wizard.

System Forecast

The System Forecast displays the system-generated forecast for the time series. The values contained in this field are read-only. This measure includes baseline as well as promotional, regular price change, and demand transference lifts, if applicable.

If the Interaction function is enabled, the displayed lift is the result of the combination of various lift types.

If the Interaction function is enabled, the displayed lift is the result of the combination of various lift types.

Total Peak

This measure stores the total lift that an item can have on top of its baseline demand. The total lift is the sum of the Total Promotion Lift Units, the Total Regular Price Lift Units and the Demand Transference lift.

Total Promotion Lift Units

This measure displays the total effect that promotions can have on an item's sales units. It is the combination of Promotion Self Lift Units, Promotion Halo Lift Units and Promotion Cannibalization Lift Units. The default way to combine the promotional lifts is to sum them up. However, if the Default Apply Interaction Factor is set to True and the Default Interaction Factor is set to a value other than one, the Total Promotion Lift Units is not the straight summation of the three promotion lift measures.

Total Regular Price Lift Units

This measure displays the total effect that regular price changes can have on an item's sales units. If the Default Apply Interaction Factor is set to True and the Default Interaction Factor is set to a value other than 1, the displayed lift is the result of the combination of regular price change self and cross lifts.

The total regular price change effect can consist of the item's self lift, and Halo and Cannibalization cross lifts coming from complementary and/or similar items. When the Interaction function is enabled, you should expect to see the displayed lift unit adjusted by the Interaction Factor calculation.

More information on the total lift and its components can be found in the Advanced Final Level view.

Approval View

The Forecast Approval view allows for non-adjusted System Forecast to be approved. This view can also be used to view the approval date of forecast values and to display the name of the user that manually approved forecast values for a given product/location combination. The default Approval Method is set in [Forecast Administration Workbook](#), and for product/location combinations that vary from the default, the [Forecast Maintenance Workbook](#) can be used.

Figure 17–13 Approval View

	Sth	Albany	Albuquerque	Anchorage	Atlanta	Austin	Baltimore	Barcelona
Manually Approved 1 - itm/str/week-Final	<input type="checkbox"/>							
Approved By 1 - itm/str/week-Final								
Approval Comment 1 - itm/str/week-Final								
Approval Date 1 - itm/str/week-Final								

Measures: Approval View

The Approval view contains the following measures:

Approval Comment

Approval Comment is a field in which notes may be entered regarding the forecast values or any pertinent information for specified product/location combinations.

Approval Date

Approval Date is a read-only field that displays the date that the forecast quantity is approved either automatically during the batch forecast process or when changes are made to the Adjusted Forecast. This information is necessary for RDF to carry out any subsequent processes, such as replenishment procedures.

Approved By

Approved By is a read-only field that displays the name of the user to approve forecasts for an item/location. This field may be populated with *Sys* if the system was set to automatically approve forecasts during the batch forecast process.


Manually Approved

Manually Approved is a Boolean flag. This field may be checked if you want to accept the System Forecast quantity for a time series that has yet to be approved. The flag is also activated when a change is made to the Adjusted Forecast and *Calculate* occurs. When this flag is activated, the time series for an item/location are approved and both the Approval Date and Approved By fields are updated.

Valid Forecast Run View

In a global domain environment, the Valid Forecast Run view allows you to identify which Local domains share the forecast birth date selected in the wizard when viewed in the Master domain. If in a Local domain, only the single position of the partition dimension is displayed.

Figure 17–14 Valid Forecast Run View



Measures: Valid Forecast Run View

The measure displayed on this view is viewed at the final-level/partition intersection. The Valid Forecast Run view includes the following standard measure:

Final Level Run Flag

The Final Level Run Flag is a read-only Boolean measure. A check (set to *True*) displayed in this field indicates which positions from the partition dimension had a successful forecast run for the birth date selected in the Forecast Approval wizard.

Note: Edits to the Adjusted Forecast can only be committed for partitions that have an activated Final Level Run Flag.

Source Level View

The Source Level view displays the system-generated source-level forecast. Final-level forecast values in the Final Level view can be viewed alongside and compared with their corresponding source-level forecasts.

Figure 17–15 Source Level View

	12/14/2001	12/21/2001	12/28/2001	1/4/2002	1/11/2002	1/18/2002	1/25/2002	2/1/2002	2/8/2002
System Forecast 3 - itm/chn/week	0.00	0.00	0.00	359.17	372.22	361.54	358.37	341.41	365.69
History Data - Weekly Sales	368.00	358.00	358.00	367.00	347.00	332.00	350.00	356.00	325.00
System Baseline 3 - itm/chn/week	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Measures: Source Level View

The Source Level view contains the following measures:

History Data

History Data (a read-only measure) is the sales data used to generate the forecast. This allows you to compare Actuals to forecast values. When the task is created, the Data Source measure is copied into History Data.

System Baseline

The System Baseline is a forecast generated on past sales data that contains no promotions (that is, normal demand given no causal effects). To see a generated Baseline Forecast:

- Promote must be implemented.
- Generate Baseline must be selected in the [Forecast Administration Workbook](#).
- The System Baseline must be selected to be viewed in the Forecast Approval wizard.

System Forecast

The System Forecast displays the system-generated forecast for the time series. The values contained in this field are read-only.

Final or Source System Parameters View

The Final or Source Parameters views allow you to view the alpha, level, and trend parameters for each fitted time series. These parameters are only available to be viewed if Generate Parameters or Generate Methods are available in the Advanced settings of the [Forecast Administration Workbook](#).

Figure 17–16 System Parameters View

	Bricks & Mortar	Catalog	E-osc	E-store	Retailer
Forecast Picked Method 3 - itm/chn/week	Multiplicative Seasonal	Multiplicative Seasonal	Multiplicative Seasonal	Multiplicative Seasonal	No Generated Forecast
System Generated Level 3 - itm/chn/week	391.84	44.95	4.46	13.33	0.00
System Generated Alpha 3 - itm/chn/week	0.05	0.05	0.00	0.01	0.00
System Generated Trend 3 - itm/chn/week	0.00	0.00	-0.00	0.00	0.00
System Generated Gamma 3 - itm/chn/week	0.00	0.00	0.05	0.04	0.00

Measures: Final or Source System Parameters View

The Final or Source Parameters view contains the following measures.

To see these measures:

- **Generate Parameters** must be selected in the [Forecast Administration Workbook](#).
- **System Generated Parameters** must be selected to be viewed in the Forecast Approval wizard.

Fit Error Factor

This is the a relative error calculated at source level and transformed to become the error factor for the final level.

The transformation is a two step process. First, the source level error is replicated at the final level intersection. Then it is multiplied with a profile - still at the final level intersection, to add some variability for each product/location combination.

The value is multiplied with the forecast to create the confidence intervals.

Forecast Method Picked

This is the system-calculated alpha value (which is an internal optimization parameter that corresponds to the rate of decay of the weighting on the historical values) for the corresponding product/location combination if the chosen method is one of the following methods: Simple, Holt, Additive Winters, Multiplicative Winters, and Profile Based.

System Generated Alpha

This is the system-calculated alpha value (which is an internal optimization parameter that corresponds to the rate of decay of the weighting on the historical values) for the corresponding product/location combination if the chosen method is one of the following methods: Simple, Holt, Additive Winters, Multiplicative Winters, and Profile Based.

System Generated Level

This is the system-calculated level (which is the constant baseline forecast) if the chosen method is one of the following methods: Simple, Holt, Additive Winters, Multiplicative Winters, and Seasonal Regression.

System Generated Gamma

This is the system-calculated gamma value for the corresponding product/location combination if the chosen method is one of the following methods: Simple, Holt, Additive Winters, Multiplicative Winters, and Profile Based.

System Generated Trend

This is the system-calculated trend (which is the rate of change of the baseline forecast with time) if the chosen method is one of the following methods: Holt, Additive Winters, Multiplicative Winters, and Seasonal Regression.

Alert Thresholds Task

The Alert Thresholds task allows you to manage the thresholds used in the batch and workbook alerts included in RDF. The thresholds can be set at three levels:

- Domain level
- Intermediate level (lower than all Product in the merchandise hierarchy)
- Item/store level (allows threshold values to be overwritten)

Defined Alerts

The following alerts are defined in RDF.

Forecast versus Recent Sales

Usually it is not expected that demand values differ very much from period to period. This also implies that the forecast magnitude generally is in line with the magnitude of the most recent sales. There are exceptions to this case. For instance, when an item enters a season, the forecast is probably higher than the sales in periods leading to the season. Or when an item is towards the end of the season, the forecast will be lower than sales in peak periods. For these exceptions, you can be alerted to review the forecast, rather than automatically approving it.

This alert is both a batch and a workbook alert.

Alert Expression

Where *length*, *threshold1*, and *threshold2* are adjustable parameters.

$$\frac{\sum_{today}^{today+length} system\ forecast(t)}{length} > threshold1$$

&&

$$\left| \frac{\sum_{today}^{today+length} adjusted\ forecast(t)}{\sum_{today-1-length}^{today-1} forecast\ source(t)} - 1 \right| > threshold2$$

Note: The calculations are not performed for the entire forecast horizon, but rather by the number of periods determined by the length parameter. The reason is that the forecast horizon can sometimes be very long (52 weeks) and average demand over such a long time period can not be used as in-season versus out of season rate of sales.

Current Forecast versus Last Approved Forecast

Typically RDF generates forecasts weekly. Every week, new sales data is loaded and the forecast is regenerated. While the latest data points are expected to make the forecast more accurate, it is not expected that the difference in forecasts generated in two consecutive weeks to vary too much. If the forecasts differ, you are alerted to review the forecasts.

This alert is both a batch and a workbook alert.

Alert Expression

Where *length*, *threshold1*, and *threshold2* are adjustable parameters.

$$\left| \frac{\sum_{today}^{today+forecast\ length-1} system\ forecast(t)}{\sum_{today}^{today+forecast\ length-1} lappf(t)} - 1 \right| > threshold1$$

&&

$$\frac{\sum_{today}^{today+forecast\ length-1} system\ forecast(t)}{forecast\ length - 1} > threshold2$$

Note: Summation of forecasts are not performed over the entire forecast length. It stops one period prior to the forecast horizon end, because this is the last populated period of the last approved forecast.

Forecast Accuracy Alert

The following steps implement the accuracy and alert calculations:

1. Calculate rate of sales (ROS) per item/store. There are several places where average sales are calculated. If available, reuse an available measure that stores the desired rate of sales.

2. Define thresholds for buckets of ROS. For example:

Low ROS value = 1

Medium ROS value = 10

High ROS value >10

3. Define error values by low/medium/high ROS. For example:

Low ROS error value = 10000%

Medium ROS error value = 100%

High ROS error value = 40%

4. Define the alert thresholds per rate of sales at the item/store intersection. For example, an item/store that has average sales of half a unit per week, is not worth the effort to be reviewed even if the forecast error is more than 100%. The logic for calculating the threshold is:

If ROS < Low ROS error value

Alert threshold = Low error value

Else if ROS < Medium ROS value

Alert threshold = Medium ROS error value

Else

Alert threshold = High ROS error value

5. Calculate the forecast error:

If ROS is less or equal to Low ROS error value for error calculation

Forecast error = $(\text{abs}(\text{sum of forecast}) - \text{abs}(\text{sum of sales})) / \text{sum of sales} * 100$

Else

Forecast error = $(\text{sum}(\text{abs}(\text{forecast} - \text{sales})) / \text{sum of sales} * 100$

Note: The second formula yields a higher error. This formula is applied to medium and high ROS items.

The calculation of the forecast error should happen on a window starting the period prior to today and going back an adjustable number of periods.

6. Trigger the alert if the error is larger than the threshold (calculated in Step 4).

If Forecast error > Alert threshold


Trigger alert

Alert Thresholds Workbook

To build the Alert Thresholds workbook, perform these steps:


1. Click the New Workbook icon in the Alert Thresholds task in the RDF Administration activity.

Figure 18–1 Alert Thresholds Task



2. The Workbook wizard opens. Select the final levels you want to work with and click **Next**.

Figure 18–2 Workbook Wizard: Select Final Levels



3. Select the products you want to work with and click **Next**.

Figure 18–3 Workbook Wizard: Select Products

Workbook Wizard

Final Level Selection Product Selection Location Selection

Available Product

Available Items

View	Dimension	Find...	Detach
Label			
4 X 6X 1L Still Water			
5 pocket capri - Antique 8 Ank			
5 pocket capri - Antique 10 An			
✓ 5 pocket capri - Antique 12 An			
✓ 5 pocket capri - Bandblasted 1			
✓ 5 pocket capri - Bandblasted 1			
✓ 5 pocket capri - Bandblasted 8			
✓ 5 pocket capri - Bandblasted 8			
✓ 5 pocket capri - Black 8 Ankle			
✓ 5 pocket capri - Black 10 Ankl			
✓ 5 pocket capri - Black 12 Ankl			
✓ 5 pocket capri - Blasted 8 Ank			
✓ 5 pocket capri - Blasted 10 An			
✓ 5 pocket capri - Blasted 12 An			
✓ 5 pocket capri - Denim 8 Ankle			
✓ 5 pocket capri - Denim 10 Ankl			
5 pocket capri - Denim 12 Ankl			
5 pocket capri - Lightweight A			
5 pocket capri - Lightweight A			
5 pocket capri - Lightweight A			
5 pocket capri - Raw 8 Ankle			

Add Add All Remove Remove All

Selected Product

Selected Items

View	Dimension	Find...	Detach
Label			
✓ 5 pocket capri - Antique 12 An			
✓ 5 pocket capri - Bandblasted 1			
✓ 5 pocket capri - Bandblasted 1			
✓ 5 pocket capri - Bandblasted 8			
✓ 5 pocket capri - Black 8 Ankle			
✓ 5 pocket capri - Black 10 Ankl			
✓ 5 pocket capri - Black 12 Ankl			
✓ 5 pocket capri - Blasted 8 Ank			
✓ 5 pocket capri - Blasted 10 An			
✓ 5 pocket capri - Blasted 12 An			
✓ 5 pocket capri - Denim 8 Ankle			
✓ 5 pocket capri - Denim 10 Ankl			
✓ 5 Year Maintenance Free Battery			

Rows Selected 1

Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Synchronize Hierarchies

Cancel Previous Next Finish

4. Select the locations you want to work with and click **Finish**.

Figure 18–4 Workbook Wizard: Select Locations

Workbook Wizard

Final Level Selection Product Selection Location Selection

Available Locations

Available Items

View	Dimension	Find...	Detach
Label			
3 Crystal			
5th Avenue			
6 Glendale			
7 Westland			
8 Fridley			
✓ 9 West St Paul			
✓ 20 Knollwood			
✓ 50 Bloomington			
✓ 68 East St Paul			
✓ 90 West St Paul			
✓ 160 Midway			
✓ 220 Ridgedale			
✓ 260 St.Louis Park, MN			
✓ 662 Cottage Grove			
✓ 694 Woodbury			
✓ 862 Chanhassen, MN			
✓ 1111 Charlotte			
1121 Atlanta			
1131 Jacksonville			
1141 Nashville			

Add Add All Remove Remove All

Selected Locations

Selected Items

View	Dimension	Find...	Detach
Label			
✓ 9 West St Paul			
✓ 20 Knollwood			
✓ 50 Bloomington			
✓ 68 East St Paul			
✓ 90 West St Paul			
✓ 160 Midway			
✓ 220 Ridgedale			
✓ 260 St.Louis Park, MN			
✓ 662 Cottage Grove			
✓ 694 Woodbury			
✓ 862 Chanhassen, MN			
✓ 1111 Charlotte			
✓ New York City			

Use Drag and Drop to add Available Items to Selected Items, use shift-click and Add for multiple selections, or Add All for all items.

Synchronize Hierarchies

Cancel Previous Next Finish

The Alert Thresholds workbook is built.

Forecast Alert Default Parameters View

The Forecast Alert Default Parameters view allows you to adjust the default values for alert thresholds.

Figure 18–5 Forecast Alert Default Parameters View

Parameter Name	Value
Default Forecast vs. Recent Sales Threshold	999999.00
Default Forecast vs. Recent Sales - Average Sales Threshold	999999.00
Default Forecast vs. Recent Sales Forecast Length	1.00
Default Forecast vs. Last Approved Forecast Threshold	999999.00
Default Forecast vs. Last Approved Forecast: Average Sales Threshold	999999.00
Default Forecast vs. Last Approved Forecast Length	1.00
Default Low Rate of Sales Value	0.00
Default Medium Rate of Sales Value	0.00
Default High Rate of Sales Value	0.00
Default Low Forecast Error Value	0.00
Default Medium Forecast Error Value	0.00
Default High Forecast Error Value	0.00
Default Forecast Length for Forecast Accuracy	0.00

Measures: Forecast Alert Default Parameters View

Note: All information in this view can be edited and represent domain level values.

The Forecast Alert Default Parameters view contains the following measures:

Default Forecast Length for Forecast Accuracy

This parameter defines the time frame over which the calculations are performed for the forecast accuracy alert.

Default Forecast vs Last Approved Forecast - Average Sales Threshold

This parameter defines the minimum rate of sales a product/location must have in order to be considered in the alert calculation. If the rate of sales condition is met and the forecast error is higher than allowed, the alert is triggered for the product/location.

Default Forecast vs Last Approved Forecast Length

This parameter defines the time frame over which the alert calculations are performed. The value should not exceed the forecast length. The calculation is still performed but will likely not be accurate.

Default Forecast vs Last Approved Forecast Threshold

This parameter defines the allowable relative error between system forecast and last approved forecast. If the error is higher than the threshold and the condition on the average rate of sales is met, the alert is triggered for the product/location.

Default Forecast vs Recent Sales - Average Sales Threshold

This parameter defines the minimum rate of sales a product/location must have in order to be considered in the alert calculation. If the rate of sales condition is met and the forecast error is higher than allowed, the alert is triggered for the product/location.

Default Forecast vs Recent Sales - Forecast Length

This parameter defines the time frame over which the alert calculations are performed. The value should not exceed the forecast length. The calculation is still performed but will likely not be accurate.

Default Forecast vs Recent Sales Threshold

This parameter defines the allowable relative error between system forecast and forecast data source. If the error is higher than the threshold and the condition on the average rate of sales is met, the alert is triggered for the product/location.

Default High Forecast Error Value

Forecast accuracy for items with high rate of sales, as defined by the Default Medium Rate of Sales Value, is tested against this parameter to determine if an alert is triggered.

Default Low Forecast Error Value

Forecast accuracy for items with low rate of sales, as defined by the Default Medium Rate of Sales Value, is tested against this parameter to determine if an alert is triggered.

Default Low Rate of Sales Value

If the rate of sales is less than this value, the item is considered to have a low rate of sale. Its forecast accuracy is tested against the Default Low Forecast Error Value, to determine if an alert is triggered.

Default Medium Forecast Error Value

Forecast accuracy for items with medium rate of sales, as defined by the Default Medium Rate of Sales Value, is tested against this parameter to determine if an alert is triggered.

Default Medium Rate of Sales Value

If the rate of sales is less than this value, the item is considered to have a medium rate of sale. Its forecast accuracy is tested against the Default Medium Forecast Error Value, to determine if an alert is triggered. If the rate of sales is more than this value, the item is considered to have a high rate of sale. Its forecast accuracy is tested against the Default High Forecast Error Value, to determine if an alert is triggered.

Forecast Alert Intermediate Intersection Parameters View

The Forecast Alert Intermediate Intersection Parameters view allows you to adjust the values for alert thresholds at an intermediate intersection.

Figure 18–6 Forecast Alert Intermediate Intersection Parameters View

Location	Product	Measure
Enterprise	Women's	Auto
Intermediate Forecast vs. Recent Sales Threshold 01 - itm/str/week-Baseline Forecast Final	1140	2890
Intermediate Forecast vs. Recent Sales - Average Sales Threshold 01 - itm/str/week-Baseline Forecast Final		
Intermediate Forecast vs. Recent Sales Forecast Length 01 - itm/str/week-Baseline Forecast Final		
Intermediate Forecast vs. Last Approved Forecast Threshold 01 - itm/str/week-Baseline Forecast Final		
Intermediate Forecast vs. Last Approved Forecast: Average Sales Threshold 01 - itm/str/week-Baseline Forecast Final		
Intermediate Forecast vs. Last Approved Forecast Length 01 - itm/str/week-Baseline Forecast Final		
Intermediate Low Rate of Sales Value 01 - itm/str/week-Baseline Forecast Final		
Intermediate Medium Rate of Sales Value 01 - itm/str/week-Baseline Forecast Final		
Intermediate High Rate of Sales Value 01 - itm/str/week-Baseline Forecast Final		
Intermediate Low Forecast Error Value 01 - itm/str/week-Baseline Forecast Final		
Intermediate Medium Forecast Error Value 01 - itm/str/week-Baseline Forecast Final		
Intermediate High Forecast Error Value 01 - itm/str/week-Baseline Forecast Final		
Intermediate Forecast Length for Forecast Accuracy 01 - itm/str/week-Baseline Forecast Final		

Measures: Forecast Alert Intermediate Intersection Parameters View

Note: All information in this view can be edited. All are defined for measures at an intermediate intersection and are meant to serve as an override of the default level values.

The Forecast Alert Intermediate Intersection Parameters view contains the following measures:

Intermediate Forecast Length for Forecast Accuracy

This parameter defines the time frame over which the calculations are performed for the forecast accuracy alert.

Intermediate Forecast vs Last Approved Forecast Average Sales Threshold

This parameter defines the minimum rate of sales a product/location must have in order to be considered in the alert calculation. If the rate of sales condition is met and the forecast error is higher than allowed, the alert is triggered for the product/location.

Intermediate Forecast vs Last Approved Forecast Length

This parameter defines the time frame over which the alert calculations are performed. The value should not exceed the forecast length. The calculation is still performed but will likely not be accurate.

Intermediate Forecast vs Last Approved Forecast Threshold

This parameter defines the allowable relative error between system forecast and last approved forecast. If the error is higher than the threshold and the condition on the average rate of sales is met, the alert is triggered for the product/location.

Intermediate Forecast vs Recent Sales Forecast Length

This parameter defines the time frame over which the alert calculations are performed. The value should not exceed the forecast length. The calculation is still performed but will likely not be accurate.

Intermediate Forecast vs Recent Sales Average Sales Threshold

This parameter defines the minimum rate of sales a product/location must have in order to be considered in the alert calculation. If the rate of sales condition is met and the forecast error is higher than allowed, the alert is triggered for the product/location.

Intermediate Forecast vs Recent Sales Threshold

This parameter defines the allowable relative error between system forecast and forecast data source. If the error is higher than the threshold and the condition on the average rate of sales is met, the alert is triggered for the product/location.

Intermediate High Forecast Error Value

Forecast accuracy for items with high rate of sales, as defined by the Intermediate Medium Rate of Sales Value, is tested against this parameter to determine if an alert is triggered.

Intermediate Low Forecast Error Value

Forecast accuracy for items with low rate of sales, as defined by the Intermediate Low Rate of Sales Value, is tested against this parameter to determine if an alert is triggered.

Intermediate Low Rate of Sales Value

If the rate of sales is less than this value, the item is considered to have a low rate of sale. Its forecast accuracy is tested against the Intermediate Low Forecast Error Value, to determine if an alert is triggered.

Intermediate Medium Forecast Error Value

Forecast accuracy for items with medium rate of sales, as defined by the Intermediate Medium Rate of Sales Value, is tested against this parameter to determine if an alert is triggered.

Intermediate Medium Rate of Sales Value

If the rate of sales is less than this value, the item is considered to have a medium rate of sale. Its forecast accuracy is tested against the Intermediate Medium Forecast Error Value, to determine if an alert is triggered. If the rate of sales is more than this value, the item is considered to have a high rate of sale. Its forecast accuracy is tested against the Intermediate High Forecast Error Value, to determine if an alert is triggered.

Forecast Alert Final Level Intersection Parameters View

The Forecast Alert Final Level Intersection Parameters view allows you to adjust the values for alert thresholds at the final level intersection.

Figure 18–7 Forecast Alert Final Level Intersection Parameters View

	Product	Measure
Forecast vs. Recent Sales Threshold - override 01 - itm/str/week-Baseline Forecast Final	5 pocket	5 pocket
Forecast vs. Recent Sales - Average Sales Threshold - override 01 - itm/str/week-Baseline Forecast Final	5 pocket	5 pocket
Forecast vs. Recent Sales Forecast Length - override 01 - itm/str/week-Baseline Forecast Final	5 pocket	5 pocket
Forecast vs. Last Approved Forecast Threshold - override 01 - itm/str/week-Baseline Forecast Final	5 pocket	5 pocket
Forecast vs. Last Approved Forecast: Average Sales Threshold - override 01 - itm/str/week-Baseline Forecast Final	5 pocket	5 pocket
Forecast vs. Last Approved Forecast Length - override 01 - itm/str/week-Baseline Forecast Final	5 pocket	5 pocket
Low Rate of Sales Value - override 01 - itm/str/week-Baseline Forecast Final		
Medium Rate of Sales Value - override 01 - itm/str/week-Baseline Forecast Final		
High Rate of Sales Value - override 01 - itm/str/week-Baseline Forecast Final		
Low Forecast Error Value - override 01 - itm/str/week-Baseline Forecast Final		
Medium Forecast Error Value - override 01 - itm/str/week-Baseline Forecast Final		
High Forecast Error Value - override 01 - itm/str/week-Baseline Forecast Final		
Forecast Length for Forecast Accuracy - override 01 - itm/str/week-Baseline Forecast Final		

Measures: Forecast Alert Final Level Intersection Parameters View

Note: All information in this view can be edited. All are defined for measures at the final level intersection, and are meant to serve as an override of the default and intermediate intersection values.

The Forecast Alert Final Level Intersection Parameters view contains the following measures:

Forecast Length for Forecast Accuracy - override

This parameter defines the time frame over which the calculations are performed for the forecast accuracy alert.

Forecast vs Last Approved Forecast Average Sales Threshold - override

This parameter defines the minimum rate of sales a product/location must have in order to be considered in the alert calculation. If the rate of sales condition is met and the forecast error is higher than allowed, the alert is triggered for the product/location.

Forecast vs Last Approved Forecast Length - override

This parameter defines the time frame over which the alert calculations are performed. The value should not exceed the forecast length. The calculation is still performed but will likely not be accurate.

Forecast vs Last Approved Forecast Threshold - override

This parameter defines the allowable relative error between system forecast and last approved forecast. If the error is higher than the threshold and the condition on the average rate of sales is met, the alert is triggered for the product/location.

Forecast vs Recent Sales Average Sales Threshold - override

This parameter defines the minimum rate of sales a product/location must have in order to be considered in the alert calculation. If the rate of sales condition is met and the forecast error is higher than allowed, the alert is triggered for the product/location.

Forecast vs Recent Sales Forecast Length - override

This parameter defines the time frame over which the alert calculations are performed. The value should not exceed the forecast length. The calculation is still performed but will likely not be accurate.

Forecast vs Recent Sales Threshold - override

This parameter defines the allowable relative error between system forecast and forecast data source. If the error is higher than the threshold and the condition on the average rate of sales is met, the alert is triggered for the product/location.

High Forecast Error Value - override

Forecast accuracy for items with high rate of sales, as defined by the Medium Rate of Sales Value – override, is tested against this parameter to determine if an alert is triggered.

Low Forecast Error Value - override

Forecast accuracy for items with low rate of sales, as defined by the Low Rate of Sales Value – override, is tested against this parameter to determine if an alert is triggered.

Low Rate of Sales Value - override

If the rate of sales is less than this value, the item is considered to have a low rate of sale. Its forecast accuracy is tested against the Low Forecast Error Value – override, to determine if an alert is triggered.

Medium Forecast Error Value - override

Forecast accuracy for items with medium rate of sales, as defined by the Medium Rate of Sales Value – override, is tested against this parameter to determine if an alert is triggered.

Medium Rate of Sales Value - override

If the rate of sales is less than this value, the item is considered to have a medium rate of sale. Its forecast accuracy is tested against the Medium Forecast Error Value – override, to determine if an alert is triggered. If the rate of sales is more than this value, the item is considered to have a high rate of sale. Its forecast accuracy is tested against the High Forecast Error Value – override, to determine if an alert is triggered.

Forecast Delete Task

The Days to Keep Forecasts parameter (set in the [Forecast Administration Workbook](#)) supports the automatic deletion of old forecasts when the Run Batch wizard or PreGenerateForecast is executed. Occasionally, a user may need to manually delete a forecast. Some reasons might include:

- A forecast was run with the wrong source-levels selected.
- The forecast horizon was not properly set.
- Old forecasts need to be deleted to save space on the server.

The Delete Forecasts wizard guides you through the process of deleting unwanted forecasts from the system. Deletions of forecasts are permanent.

Forecast Delete Wizard

If the Forecast Delete wizard is used in a global domain environment. Deleting a forecast in the Master domain deletes the selected birth date within all domains. Deleting a forecast in the Local domain deletes the selected birth date only within the Local domain.

Note: The deletion of forecasts from RDF is permanent.

To use the Forecast Delete wizard, perform these steps:


1. Click the New Workbook icon in the Forecast Delete task in the RDF Administration activity.

Figure 19–1 Forecast Delete Task




2. The Workbook wizard opens. Select the forecasts to delete and click **Next**.

Figure 19–2 Workbook Wizard: Select Forecasts to Delete



3. Select **Finish** to verify forecast deletion or **Cancel** to cancel deletion and exit the Forecast Delete wizard.

Figure 19–3 Workbook Wizard: Verify Delete



If **Finish** was selected on the final wizard window, the forecast is deleted.

Grade is a clustering tool that provides insight into how various parts of a retailer's operations can be grouped together. Typically, a retailer may cluster stores over item sales to create logical groupings of stores based upon sales of particular products. This provides increased visibility to where products are selling, and it allows the retailer to make more accurate decisions in merchandising.

Beyond this traditional use of clusters, Grade is flexible enough to cluster any business measure based on products, locations, time, promotions, customers, or any hierarchy configured in the solution.

Key Grade functionality includes:

- Two methods of creating Grades/Clusters:
 - Breakpoints—the sorting of data points into groups based on user-defined indexes
 - Clustering (or the BaNG) Algorithm—the optimization of data points into clusters based on the user-defined number of clusters
- *Group By* capabilities: support the segmentation of clusters for more detailed and focused cluster generation
- Clustering statistics: provide insight into the relationship of members within a cluster and how all clusters relate to one another
- Cluster What-if: allows user changes to members assigned to clusters and the review of recalculated clustering statistics

Regardless of the method employed to create clusters, Grade is designed to support the decision-making process necessary to create effective and actionable groupings of data. This chapter describes the process to generate grades/clusters and analyze results. All of Grade's functionality exists in the:

- [Breakpoint Administration Workbook](#)
- [Delete Cluster Run Wizard](#)
- [Cluster Review Workbook](#)
- [Generate Breakpoint Grades Wizard](#)
- [Generate Clusters Wizard](#)

Cluster Methods in Grade

Grade supports two cluster methods: Breakpoint and BaNG. The following sections describe these two methods.

Breakpoint

Breakpoint method clusters, or groups, data points based on user-defined thresholds, or breakpoints. Breakpoints are properly defined by entering a decreasing sequence of real numbers that terminate in a value of zero. Breakpoints are entered in the Breakpoints Administration Workbook. Breakpoints are then used to cluster data points based on the index to average of each data point.

Example 20–1 Breakpoint

While clustering stores, if the user has entered the breakpoints 2.0, 1.5, 1.0, 0.5, and 0.0, the system will generate five grades. Stores that sell more than 2.0 times the average sales (over all stores) will be assigned to the highest grade, and stores that sell less than 0.5 times the average will be assigned to the lowest grade.

Index to Average

Index to Average is the average sales of the stores in each grade divided by the average sales of all stores. This value provides a relative indication of how well a grade performed compared to the total store average. A value of 1.00 indicates that average sales in the grade were the same as average sales across the chain. A value of 3.74, for example, indicates that average sales in the grade were 3.74 times the chain average.

Batch Neural Gas Algorithm (BaNG)

The BaNG algorithm automatically generates optimal clusters based on user-specified number of clusters and clustering criteria. The algorithm provides a means for clustering data based on data distributions. For example, while clustering on weekly store sales data, the BaNG algorithm considers the Euclidean distance of the individual Store/week level data points from a cluster center to determine the clusters. This is different from the Breakpoint method, where clustering is performed based on average sales.

The BaNG algorithm iteratively updates cluster centers while considering the distance of each data vector from the cluster centers and its contribution to each cluster center. For every data point, cluster centers are ranked based on their distance from the data point within each iteration.

Additionally, the cluster centers are guided, using a control parameter, to gradually spread from the center of the distribution to their optimal locations.

The BaNG algorithm is a non-trivial extension of the K-means clustering approach. It is usually faster than the K-means and is guaranteed to converge.

BaNG versus Breakpoint

The BaNG algorithm generates statistically optimal clusters based on the number of clusters specified by the user. Breakpoint generates clusters based on user input breakpoints, and the number of clusters generated depends on the breakpoints.

In order to generate store clusters that vary by Dept, users need to specify a Group By option of Dept. Breakpoint will cluster stores based on the ratio of total store sales versus the average total store sales within each Group By intersection. BaNG can consider an additional dimension for generating the clusters. For example, BaNG can cluster based on weekly sales of each stores within the Dept. Here, weekly sales are the coordinates over which the clustering is performed.

Grade in a Global Domain Environment

When implemented in a global domain environment, the following workbooks are available to be accessed from the Master domain:

- [Breakpoint Administration Workbook](#)

Note: The Breakpoint Administration workbook is accessible from the Master domain to allow for the centralized administration of breakpoints.

The remaining Grade workbooks can only be accessed from local domains. These include:

- [Delete Cluster Run Wizard](#)
- [Cluster Review Workbook](#)
- [Generate Breakpoint Grades Wizard](#)
- [Generate Clusters Wizard](#)

Grade Tasks and Wizards

The Grade tasks and wizards allow you to generate grades/clusters and analyze results.

The Grade tasks and wizards include:

Task Workbooks	Description
Breakpoint Administration Task	Allows you to set the index to average for each breakpoint.
Delete Cluster Run Task	Allows you to delete clusters from the system based on Cluster Run Label and generation date (birth date).
Cluster Review Task	Allows you to support Grade/cluster What-if functionality; the re-assignment of members to grades/clusters on the fly and the recalculation of clustering statistics.
Generate Breakpoint Grades Task	Allows you to range the input data and hierarchies that will be used to produce grades based on the Breakpoints method.
Generate Clusters Task	Allows you to range the input data and hierarchies that will be used to produce clusters based on the Clustering (BaNG) method.


Breakpoint Administration Task

The Breakpoint Administration task is used with the breakpoints method of grading. In this task, you set the index to average for each breakpoint. This includes the ability to set multiple breakpoint configurations to allow for Grades to be produced and compared using different breakpoint settings.

Breakpoint Administration Workbook

To build the Breakpoint Administration workbook, perform these steps:

1. Click the New Workbook icon in the Breakpoint Administration task in the Grade activity.


Figure 20–1 Breakpoint Administration Task

The [Breakpoint Administration View](#) opens.

Breakpoint Administration View

If the breakpoints method is to be used to generate grades, you must go through the process of setting of the Index to Average for each grade's breakpoint range.

[Figure 20–2](#) displays an example of the Breakpoint Administration view:

Figure 20–2 Breakpoint Administration View

On the Breakpoint Administration view, for a Configuration/Cluster intersection, set the Index to Average to be used by the Breakpoints algorithm for sorting data points into grades. The number of configurations available in this view is based on the Maximum Number of Clusters configured in the Grade Plug-In. Only one configuration is required for use with the breakpoints method.

Breakpoints should be set from high Index to Average to low Index to Average, starting with the first Cluster ordered in the list of available clusters.

Note: The Cluster Labels may vary based on the configuration.

Example: If the Index to Average is set for Configuration 01 as:

- 1 Cluster01: 1.25
- 2 Cluster02: 0.75
- 3 Cluster03: 0.50
- 4 Cluster04: 0.25
- 5 Cluster05: 0.00

Using this example, the Breakpoints algorithm groups data based on the following:

Data	Description
1 Cluster01	Sort all data with an Index to Average at or above 1.25 into 1 Cluster01.
2 Cluster02	Sort all data with an Index to Average from 0.75 to 1.24 into 2 Cluster02.
3 Cluster03	Sort all data with an Index to Average from 0.50 to 0.74 into 3 Cluster03.
4 Cluster04	Sort all data with an Index to Average from 0.25 to 0.49 into 4 Cluster04.
5 Cluster05	Sort all data with an Index to Average from 0.00 to 0.24 into 5 Cluster05.
Junk Cluster	Using the previous example, all data points with an Index to Average that is less than 0.00 will be sorted into the Junk Cluster.
No Cluster	Any data points with null values in history (no loaded history) will not be graded. Refer to the Cluster Review Task for more information on Cluster Membership results.

Delete Cluster Run Task


The Delete Cluster Run wizard allows you to delete clusters from the system based on Cluster Run Label and generation date (birth date).

Delete Cluster Run Wizard

To run the Delete Cluster Run wizard, perform these steps:

1. Click the New Workbook icon in the Delete Cluster Run task in the Grade activity.

Figure 20–3 Delete Cluster Run Task



2. This wizard window is a single select pick-list that includes the Cluster Run Label and the date/time stamp (birth date) for all cluster runs currently stored in the system. Select the Cluster Run Label to be deleted.
3. Select **Next** or **Finish**.

If **Next** is selected, Delete Cluster Run Succeeded is displayed once the cluster deletion process is completed.

Cluster Review Task

The Cluster Review workbook is a view of grade or cluster results and statistics. This workbook supports Grade/cluster What-if, the re-assignment of members to Grades/clusters on the fly, and the recalculation of clustering statistics. In addition, measures from different cluster runs may be inserted into the workbook to compare results.

Cluster Review Workbook

To run the Cluster Review wizard, perform these steps:


1. Click the New Workbook icon in the Cluster Review task in the Grade activity.

Figure 20–4 Cluster Review Task



2. The Workbook wizard opens. Select the Grade Birth you want to review and click **Finish**.

Figure 20–5 Workbook Wizard: Select Grade Birth



The Cluster Review workbook is built.

Cluster Input Summary View

The Cluster Input Summary view allows you to see the settings used to generate the grades/clusters being reviewed in the workbook.

Figure 20–6 Cluster Input Summary View

Property	Value
Number Of Clusters	3
Dimension to Cluster Over	DSTR
Cluster Run Name	Sample
Cluster Method	BANG
Measure to Cluster	DPOS
Dimension to Cluster	WEEK
Cluster By Group Intersection	MNTH

Measures: Cluster Input Summary View

Number of Clusters

Displays the number of clusters used during the cluster generation process.

Dimension to Cluster Over

Displays the Cluster Over dimension selected by the user during the cluster generation process.

The algorithm uses the positions in this dimension as the coordinates when clustering. Internally, data will be aggregated to this level before performing the clustering.

For example, when using the item/store/week level sales data to generate store clusters, the user has the option of specifying a dimension, such as Week, that will be used to aggregate the sales data to. In this case, the algorithm considers Store/Week positions and clusters stores based on their weekly sales.

A value will only be displayed in this field if the BaNG method was used.

Cluster Run Name

Displays the name assigned by the user to the cluster run at the time the clusters were generated.

Measure to Cluster

Displays the measure selected as the clustering Data Source during the cluster generation process.

Dimension to Cluster

Displays the Cluster dimension selected by the user during the cluster generation process.

Cluster By Group Intersection

Displays Group By dimensions if selected during the cluster generation process. For example, while clustering stores by time period, such as quarter, the Cluster By Group is Quarter (Qtr) within the Calendar hierarchy. This means that clusters are generated one quarter at a time.

Generate Breakpoint Grades Task


The Generate Breakpoint Grades wizard allows you to range the input data and hierarchies that will be used to produce grades based on the Breakpoints method.

Generate Breakpoint Grades Wizard

To run the Generate Breakpoint Grades wizard, perform these steps:

1. Click the New Workbook icon in the Generate Breakpoint Grades task in the Grade activity.


Figure 20–7 Generate Breakpoint Grades Task



2. The Workbook wizard opens. Select the source measure for Cluster Analysis and click **Next**.

The options include all source measures defined at the time of the configuration.

Figure 20–8 Workbook Wizard: Source Measure for Cluster Analysis




3. Select the Hierarchy and Dimension to Cluster On and click **Next**.

The Cluster On dimension is the dimension that will be clustered. For example, while generating store clusters, store would be the Cluster On dimension. All positions in this dimension are sorted into grades based on the Breakpoints Configuration that will be selected later in this wizard process.

Note: The dimension chosen should be at or higher than the base intersection of the selected Source Measure.

Figure 20–9 Workbook Wizard: Hierarchy and Dimension to Cluster On




4. Optional Step

Select the Hierarchy and Dimension to Group By and click **Next**.

By Group is an optional setting that is used to partition data along a hierarchy dimension. This functionality allows for grades to be further segmented along multiple hierarchy dimensions. Grades are generated independently for each position within the selected dimensions. The dimensions displayed are equal to or higher than the Cluster On dimension.


For example, while clustering stores by Dept, that is, cluster stores by a Department at a time, the Cluster By Group is Department.

Figure 20–10 Workbook Wizard: Select Hierarchy and Dimension to Group By




5. Select the products for which you want to generate clusters and click **Next**.

Figure 20–11 Workbook Wizard: Select Items




6. Select the locations for which you want to generate clusters and click **Next**.

Figure 20–12 Workbook Wizard: Select Stores



7. Select the time periods that you want to be considered when generating clusters and click **Next**.


Figure 20–13 Workbook Wizard: Select Day



8. Select the Breakpoint Configuration that will be used to produce the grades. These configurations must be set prior to generating grades using the Breakpoint Administration task.

Click **Next**.

Figure 20–14 Workbook Wizard: Select Configuration Name



9. Set the Grade Run Name. Assign a label that will be used to identify the clustering run.
10. Select **Next** or **Finish**.
If **Next** is selected, Break Point Run Succeeded is displayed once the grading process is completed. If **Finish** is selected this message will be skipped.

Generate Clusters Task


The Generate Clusters wizard allows you to range the input data and hierarchies that will be used to produce clusters based on the Clustering (BaNG) method.

Generate Clusters Wizard

To run the Generate Clusters wizard, perform these steps:

1. Click the New Workbook icon in the Generate Clusters task in the Grade activity.


Figure 20–15 Generate Clusters Task



2. The Workbook wizard opens. Select the source measure for Cluster Analysis and click **Next**.

The options include all source measures defined at the time of the configuration.

Figure 20–16 Workbook Wizard: Select Source Measure for Cluster Analysis




3. Select the Hierarchy and Dimension to Cluster On and click **Next**.

The Cluster Over dimension allows you to define the dimension that will be used for clustering. The algorithm uses the positions in this dimension as the co-ordinates when clustering. Internally, data will be aggregated to this level before performing the clustering. For example, when using item/store/week level sales data to generate store clusters, the user has the option of specifying a dimension, such as Week, to which sales data will be aggregated. In this case, the algorithm considers Store/Week positions and clusters stores based on their weekly sales.

Note: The hierarchies presented in this wizard window include all hierarchies associated with the base intersection of the source measure except the hierarchy and dimension chosen to Cluster On.

Note: The dimension chosen should be at or higher than the base intersection of the selected Source Measure.

Figure 20–17 Workbook Wizard: Hierarchy and Dimension


4. Optional Step

Select the Select Hierarchy and Dimension to Group By and click **Next**.

By Group is an optional setting that is used to partition data along a hierarchy dimension. This functionality allows for clusters to be further segmented along multiple hierarchy dimensions. Clusters are generated independently for each position within the selected dimensions. The dimensions displayed are equal to or higher than the Cluster On and Cluster Over dimensions.


For example, while clustering stores by Dept, that is, cluster stores by a Department at a time, the Cluster By Group is Department.

Figure 20–18 Workbook Wizard: Select Hierarchy and Dimension to Group By




5. Select the products for which you want to generate clusters and click **Next**.

Figure 20–19 Workbook Wizard: Select Items




6. Select the locations for which you want to generate clusters and click **Next**.

Figure 20–20 Workbook Wizard: Select Stores




7. Select the time periods that you want to be considered when generating clusters and click Next.

Figure 20–21 Workbook Wizard: Select Day



8. Assign a label that will be used to identify the clustering run.
Click Next.

Figure 20–22 Workbook Wizard: Set Name and Number of Clusters

9. Set the name and number of clusters:
 - a. Set the name. Assign a label that will be used to identify the clustering run.
 - b. Set the number of clusters. Define the number of clusters that are generated during the cluster generation process. If a Group By dimension was selected, this is the number of clusters that will be generated for each data partition within the dimension. The number of clusters that may be generated is based on the maximum number of clusters configured in the Grade configuration. refer to the *Oracle Retail Grade Configuration Guide* for more information on the Grade solution configuration.
10. Select **Next** or **Finish**.

If **Next** is selected, Cluster Run Succeeded is displayed once the grading process is completed as shown in [Figure 20–23](#). If **Finish** is selected this message will be skipped.

Figure 20–23 Workbook Wizard: Cluster Run Succeeded



Cross Promotional Effects Module (CPEM)

This chapter provides an introduction to Cross Promotional Effects Module (CPEM). CPEM is a data mining solution that determines promotional Cannibalization, or Halo relationships, or both between items or groups of items.

Refer to [Appendix B, "Appendix: RDF Workbooks \(Fusion Client\)"](#) for a complete list of RDF workbooks, and their respective tabs, views, and measures.

RDF was launched with Promotional Halo and Cannibalization capabilities in January 2013. The functionality has had limited adoption due to various factors including necessary data required to support reliable results, market maturity and implementation complexity. In an attempt to share lessons learnt with our experience so far, we would recommend the following to our customers considering implementing this functionality:

Starting Conditions

Both Halo and Cannibalization deal with the cross item effects of running promotions, that is, the impact of promoting an item on the sales of other related items. The most important inputs for estimating these cross effects are a robust baseline forecast and self-promotion effects from RDF Causal. Hence, we recommend that CPEM be considered for implementation only after RDF Causal has been up and live for a 12-18 month period, delivering reliable baseline and causal forecasts to drive business decisions.

- **Replacement SKUs** — All historical SKUs that are replacement or promotional variants of each other need to be grouped together into a Plan SKU. The Plan SKU level needs to be used within RDF for estimating both baseline forecasts and causal forecasts.
- **Appropriate pre-processing** — That corrects for missing sales periods and other factors that might bias the estimated baseline forecast and hence impact that quality of CPEM output.

Set Up for Cannibalization

Careful configuration and pre-implementation set up is required for Cannibalization to run. It is important to note that Cannibalization (though configurable) is designed to run at an item-group level (as defined in the following list) and not the individual SKU level.

Note: Cannibalization needs to stay inside a local domain.

- **Item-group or L1 Set Up** — This is the level at which Cannibalization is estimated. SKUs have to be grouped (outside the system and fed in). These are groups of

items that are typically promoted together. For example, in the yogurt Category, SKUs of a particular brand, size, fat content but different flavor variants. An attribute analysis exercise, should inform this L1-grouping. What are the key combinations of attributes that need to be the same for all items in an L1-group and what attributes can be different? It is important to note that these attributes will vary significantly, from Category to Category.

- **Cannibalization-group Or L2 Set Up** — L2 is the level where the cannibalization is estimated. Only item group or L1 within a Cannibalization group are analyzed for possible Cannibalization, when one or more items are promoted. This could be a grouping of one or more classes or sub-classes. Note that L2 grouping needs to be a roll up of L1 groupings, that is, every L1 item-group needs to cleanly map to one and only one L2 grouping (many to one mapping from L1 to L2).
- **L1-pairing Set Up** — In addition to set up of L1 or Item-groups, RDF's CPEM also needs to be told of legal/possible L1-pairs. This requires careful analysis on a Category by Category basis. For example, SKUs within a certain regular price range could be considered Cannibalistic and hence valid L1-pairs. It is recommended that this analysis be conducted carefully, ideally in conjunction with Customer Decision Trees (CDTs) to ensure the correct pairings are set up for each Category.
- **Co-promotion Effects are Turned Off** — A system flag that effectively looks for conditions when both L1 pairings are promoted at the same time and accounts for it appropriately.

Halo effects

Current functionality is designed for a limited use case for businesses with minimal promotional activity. The solution aims to estimate Halo effects by observing the impact on sales of other subclasses when a subclass is promoted. As we vetted this with a broad set of retail use cases with significant promotional activities, we recognized that this functionality is not adequate. We are revisiting our approach to estimating Halo effects and welcome partnerships with retailers.

About Promotional Effects

We refer to Cannibalization effects when a promoted item causes a drop in sales of a similar item. An example of this behavior is when a brand of mustard is promoted, it likely experiences an increase in sales and other mustard brands' demand decreases. After the promotional period the demand pattern of the entire mustard category returns to pre-promotion levels.

Conversely, we refer to Halo effects when a promoted item, or group of items causes an increase in sales of a complementary item or items. A typical case is when hot dogs are promoted, hot dog buns are likely to see a peak in sales as well.

Cannibalization is expected to happen at low levels in the merchandise hierarchy, like style or subclass. However, Halo is detected at much higher levels, like category or department.

Implementing CPEM

CPEM is a module within RDF, but it is implemented separately of a RDF forecasting environment. The nature of the problem that mining for cross promotional relationships poses, that is, search for relationships among items in different areas of business, is not compatible with the master/local domain structure of a typical RDF environment. CPEM is implemented in a single domain, such that mining for Halo effects can span multiple departments.

The inputs to CPEM are sales and promotion information for which there is formal integration with the forecasting solution.

The output of CPEM is the promotional elasticity among items, which is location specific. The intersection of the output is item/item/location.

Currently, RDF Causal is predicting promotional sales based on item Self Promo Lifts. Basically the promotion of an item is considered to affect only sales of that item. With information about cross promotional elasticities, the promotion planners have the complete picture on how a promotion affects the entire business, and can act accordingly.

CPEM Workbooks and Wizards

The CPEM wizards allow you to setup the [Effect Estimation Administration Task](#) and [Effect Estimation Review and Approval Task](#).

CPEM includes these workbooks and views:

Workbooks	Description	Views
Effect Estimation Administration Task	Allows you to setup parameters and thresholds, and their overrides, before the batch run.	Default Parameters View Cannibalization Parameter Override View Halo Parameter Override View Halo Products Mapping View
Effect Estimation Review and Approval Task	Allows you to review the cross promotional elasticities and statistical information related to the analysis. Based on the statistics, you can approve the elasticities or adjust them based on business knowledge.	Cannibalization Effects View Cannibalization Effects Drive View Cannibalization History Data View Halo Effects View Halo Effects Drive View Halo History Data View Cannibalization Statistic Report View Halo Statistic Report View

Effect Estimation Administration Task

The Effect Estimation Administration task allows you to setup parameters and thresholds, and their overrides, before the batch run.

This task has these views:


- [Default Parameters View](#)
- [Cannibalization Parameter Override View](#)
- [Halo Parameter Override View](#)
- [Halo Products Mapping View](#)

Effect Estimation Administration Workbook

To build the Effect Estimation Administration workbook, perform these steps:


1. Click the New Workbook icon in the Effect Estimation Administration task in the Cross Promo Effects Module.

Figure 21–1 Effect Estimation Administration Task




2. The Workbook wizard opens. Select the products for promotion effect estimation and click **Next**.

Figure 21–2 Workbook Wizard: Select Products




3. Select the locations for promotion effect estimation and click **Next**.

Figure 21–3 Workbook Wizard: Locations



4. Select the right-hand-side (RHS) products for promotion effect estimation and click **Finish**.

Figure 21–4 Workbook Wizard: Select RHS Products




The Effect Estimation Administration workbook is built.

Default Parameters View

The Default Parameters view allows you to setup Default parameters and thresholds, and their overrides, before the batch run.

Figure 21–5 Default Parameters View



Measures: Default Parameters View

The Default Parameters view contains the following measures:

Default Cannibalization P-Value

The P-value is used in statistics to measure the confidence one can have in an estimate. The Default Cannibalization P-value represents the minimum confidence threshold. During the cannibalization effects estimation process, any effects with P-values below the threshold are deemed insignificant and discarded.

Default Cannibalization Self Elasticity Check

Place a check in this parameter (set to True) if you want to ensure that the cannibalization elasticity is less than its shelf elasticity. If checked, the calculated elasticity which is higher than its own elasticity will be discarded. This parameter serves as a global override.

Default Halo P-Value

The P-value is used in statistics to measure the confidence one can have in an estimate. The Default Halo P-value represents the minimum confidence threshold. During the Halo effects estimation process, any effects with P-values below the threshold are deemed insignificant and discarded.

Default Halo Self Elasticity Check

Place a check in this parameter (set to True) if you want to ensure that the halo elasticity is less than its self elasticity. If checked, the calculated elasticity which is higher than its own elasticity will be discarded. This parameter serves as a global override.

History Start Date

The first calendar date considered in the analysis. All measure data prior to this date is discarded.

History End Date

The last calendar date considered in the analysis. All measure data after this date is discarded.

Cannibalization Ancestor Level

This is the dimension in the merchandise hierarchy where Cannibalization is mined for. Only item pairs within this dimension are evaluated.

Cannibalization Lower Bound

Minimum Cannibalization value threshold. Cannibalization values that are below the threshold are discarded.

Cannibalization Upper Bound

Maximum Cannibalization value threshold. Cannibalization values that are higher than the threshold are discarded (set to zero).

Halo Lower Bound

Minimum Halo value threshold. Halo values that are below the threshold are discarded.


Halo Upper Bound

Maximum Halo value threshold. Halo values that are higher than the threshold are discarded (set to zero).

Cannibalization Parameter Override View

The Cannibalization Parameter Override view allows you to setup Cannibalization parameters and thresholds, and their overrides, before the batch run.

Figure 21–6 Cannibalization Parameter Override View

**Measures: Cannibalization Parameter Override View**

The Cannibalization Parameter Override view contains the following measures:

Cannibalization P-Value - Override

Override of the Default Cannibalization P-Value threshold. The cannibalization effects whose p-values are below the threshold are discarded.

Cannibalization Self Elasticity Check - Override

This is an override of the global setting. If checked (set to True), the calculated cannibalization elasticity which is higher than its self elasticity will be discarded.

Cannibalization Lower Bound - Override

Override of the minimum Cannibalization value threshold. Cannibalization values that are below the threshold are discarded (set to zero). The override intersection is typically higher than item/store, for example, subclass/region.


Cannibalization Upper Bound - Override

Override of the maximum Cannibalization value threshold. Cannibalization values that are higher than the threshold are discarded (set to zero). The override intersection is typically higher than item/store, for example, subclass/region.

Halo Parameter Override View

The Halo Parameter Override view allows you to setup Halo parameters and thresholds, and their overrides, before the batch run.

Figure 21–7 Halo Parameter Override View

**Measures: Halo Parameter Override View**

The Halo Parameter Override view contains the following measures:

Halo P-Value - Override

Override of the Default Halo P-Value threshold. The Halo effects whose P-values are below the threshold are discarded.

Halo Self Elasticity Check - Override

This is an override of the global setting. If checked (set to True), the calculated halo elasticity which is higher than its self elasticity will be discarded.

Halo Lower Bound - Override

Override of the minimum Halo value threshold. Halo values that are below the threshold are discarded (set to zero). The override intersection is typically higher than item/store, for example, class/region.


Halo Upper Bound - Override

Override of the maximum Halo value threshold. Halo values that are higher than the threshold are discarded (set to zero). The override intersection is typically higher than item/store, for example, class/region.

Halo Products Mapping View

The Halo Products Mapping view allows you to specify item pairs for which a Halo relationship is mined for. For item pairs that do not have the check box selected, the system will not attempt to look for a Halo relationship.

Figure 21–8 Halo Products Mapping View



Measures: Halo Products Mapping View

The Halo Products Mapping view contains the following measures:

Halo Mask

This measure defines item groupings that are analyzed for Halo relationship. The item groupings are typically bound to the merchandise hierarchy and can be class to class, as in [Figure 21–8](#). This is a writeable measure, and you are expected to use your business knowledge to mark pairs that could have Halo relationships.

Effect Estimation Review and Approval Task

The Effect Estimation Review and Approval workbook provides you the ability to review the cross promotional elasticities and statistical information related to the analysis. Based on the statistics, you can approve the elasticities or adjust them based on your business knowledge.

This task has two tabs with these views:

Cross Promotion Effects tab:

- [Cannibalization Effects Drive View](#)
- [Cannibalization Effects Percentage View](#)
- [Cannibalization Effects View](#)
- [Cannibalization History Data View](#)
- [Halo Effects Drive View](#)
- [Halo Effects Percentage View](#)
- [Halo Effects Percentage View](#)
- [Halo History Data View](#)

Cross Effect Statistics Reports tab:


- [Cannibalization Statistic Report View](#)
- [Halo Statistic Report View](#)

Effect Estimation Review and Approval Workbook

To build the Effect Estimation Review and Approval workbook, perform these steps:


1. Click the New Workbook icon in the Effect Estimation Review and Approval task in the Cross Promo Effects Module.

Figure 21–9 Effect Estimation Review and Approval Task




2. The Workbook wizard opens. Select the products for promotion effect estimation review and approval and click Next.


Figure 21–10 Workbook Wizard: Select Products



3. Select the locations for promotion effect estimation review and approval and click Next.


Figure 21–11 Workbook Wizard: Locations

4. Select the right-hand-side (RHS) products for promotion effect estimation review and approval and click **Next**.

Figure 21–12 Workbook Wizard: Select RHS Products

5. Select the dates for promotion effect estimation review and approval and click **Finish**.

Figure 21–13 Workbook Wizard: Select Dates



The Effect Estimation Review and Approval workbook is built.

Cannibalization Effects Drive View

The Cannibalization Effects Drive View contains the same information as the [Cannibalization Effects View](#), but has a different layout and a position query defined.

Figure 21–14 Cannibalization Effects Drive View

Cannibalization Effects Drive View	
Location	Product RHS
Northeast	3 Whisky
Measure	Product
System Calculated Cannibalization Effect	301Peanut Butter
	512Still
	622Caffeinated
	Cola*
	Cranberry
	Tomatoes
Approved Cannibalization Effect	301Peanut Butter
	512Still
	622Caffeinated
	Cola*
	Cranberry
	Tomatoes

Measures: Cannibalization Effects Drive View

The Cannibalization Effects Drive view contains the following measures:

System Calculated Cannibalization Effect

This measure displays the system calculated Cannibalization effects at product/product/location level.

Approved Cannibalization Effect

This measure stores the Cannibalization value that you want to commit. By default it is the same value as the system calculated effect, but you may adjust it.

Cannibalization Effects Percentage View

The Cannibalization Effects Percentage view allows you to review the reactions of the impacted item's demand change given a change in the driver item's demand. The percentage changes due to cannibalization effects will be displayed for a series of self lifts of the driver item.

Figure 21–15 Cannibalization Effects Percentage View

	2970Chocolate*	3420Filter Tipped	Cola*	Cranberry	Diced*
Approved Cannibalization Effect					
RHS Product Sales increase 10 %					
RHS Product Sales increase 20 %					
RHS Product Sales increase 30 %					
RHS Product Sales increase 40 %					
RHS Product Sales increase 50 %					
RHS Product Sales increase 60 %					
RHS Product Sales increase 70 %					
RHS Product Sales increase 80 %					
RHS Product Sales increase 90 %					
RHS Product Sales increase 100 %					

Measures: Cannibalization Effects Percentage View

The Cannibalization Effects Percentage View view contains the following measures:

Approved Cannibalization Effect

This measure stores the approved cannibalization effects.

RHS Product Sales Increase 10%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 10%.

RHS Product Sales Increase 20%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 20%.

RHS Product Sales Increase 30%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 30%.

RHS Product Sales Increase 40%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 40%.

RHS Product Sales Increase 50%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 50%.

RHS Product Sales Increase 60%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 60%.

RHS Product Sales Increase 70%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 70%.

RHS Product Sales Increase 80%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 80%.

RHS Product Sales Increase 90%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 90%.


RHS Product Sales Increase 100%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 100%.

Cannibalization Effects View

The Cannibalization Effects view allows you to review and adjust the Cannibalization cross elasticities.

Figure 21–16 Cannibalization Effects View



Measures: Cannibalization Effects View

The Cannibalization Effects view contains the following measures:

Approved Cannibalization Effect

This measure stores the Cannibalization value that you want to commit. By default it is the same value as the system calculated effect, but you may adjust it.

System Calculated Cannibalization Effect

This measure displays the system calculated Cannibalization effects at product/product/location level.

System Calculated Cannibalization T Statistic

This measure displays the system calculated T-Statistics for each cannibalization effect at product/product/location level.

System Calculated Cannibalization Coefficient Standard Error

This measure displays the system calculated standard error for each cannibalization effect at product/product/location level.

System Calculated Cannibalization P Value

This measure displays the system calculated P-value for each cannibalization effect at product/product/location level.

Selected Cannibalization P Value

This measure displays the user selected P-value for each cannibalization effect at product/product/location level.

Cannibalization History Data View

The Cannibalization History Data view allows you to view the historical facts used to estimate the Cannibalization effects.

Figure 21–17 Cannibalization History Data View

		4/24/2009	5/1/2009	5/8/2009	5/15/2009	5/22/2009	5/29/2009
Weekly Sales Baseline - Cannibalization	301Peanut Butter						
	512Still						
	622Caffeinated						
	Cola*						
	Cranberry						
	Tomatoes						
Weekly Sales history - Cannibalization	301Peanut Butter						
	512Still						
	622Caffeinated						
	Cola*						
	Cranberry						
	Tomatoes						
Weekly Normalized Price - Cannibalization	301Peanut Butter						
	512Still						
	622Caffeinated						
	Cola*						
	Cranberry						
	Tomatoes						
Weekly Promotion Variable - Cannibalization	301Peanut Butter						
	512Still						
	622Caffeinated						
	Cola*						
	Cranberry						
	Tomatoes						

Measures: Cannibalization History Data View

The Cannibalization History Data view contains the following measures:

Weekly Sales Baseline - Cannibalization

This measure represents the sales history cleansed of Promo Self Effects. It is typically at an intersection higher than the final level intersections in RDF, for example, subclass/region/week.

Weekly Sales History - Cannibalization

This measure represents the total sales history. It is typically at an intersection higher than the final level intersections in RDF, for example, subclass/region/week.

Weekly Normalized Price - Cannibalization

This measure stores the normalized price. It is typically at an intersection higher than the final level intersections in RDF, for example, subclass/region/week. There is no guarantee that all items in a subclass (or region) have the same price, hence the need to normalize them.


Weekly Promotion Variable - Cannibalization

This measure stores the information if any promotion was active for a given time period. It is typically at an intersection higher than the final level intersections in RDF, for example, subclass/region/week.

Halo Effects Drive View

The Halo Effects Drive View contains the same information as the [Halo Effects View](#), but has a different layout and a position query defined.

Figure 21–18 Halo Effects Drive View



Measures: Halo Effects Drive View

The Halo Effects Drive View contains the following measures:

System Calculated Halo Effect

This measure displays the system calculated Halo effects at product/product/location level.

Approved Halo Effect

This measure stores the Halo value that you want to commit. By default it is the same value as the system calculated effect, but you may adjust it.

Halo Effects Percentage View

The Halo Effects Percentage view allows you to review the reactions of the impacted item's demand change given a change in the driver item's demand. The percentage change due to Halo effects will be displayed for a series of self lifts of the driver item.

Figure 21–19 Halo Effects Percentage View

Measure [Label]	lonated*	4121Beer*	4123Spirits*	4311Detergents*	Cola*	Cranberry
Approved Halo Effect						
RHS Product Sales increase 10 %						
RHS Product Sales increase 20 %						
RHS Product Sales increase 30 %						
RHS Product Sales increase 40 %						
RHS Product Sales increase 50 %						
RHS Product Sales increase 60 %						
RHS Product Sales increase 70 %						
RHS Product Sales increase 80 %						
RHS Product Sales increase 90 %						
RHS Product Sales increase 100 %						

Measures: Halo Effects Percentage View

The Halo Effects Percentage view contains the following measures:

Approved Halo Effect

This measure stores the approved Halo effects.

RHS Product Sales Increase 10%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 10%.

RHS Product Sales Increase 20%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 20%.

RHS Product Sales Increase 30%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 30%.

RHS Product Sales Increase 40%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 40%.

RHS Product Sales Increase 50%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 50%.

RHS Product Sales Increase 60%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 60%.

RHS Product Sales Increase 70%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 70%.

RHS Product Sales Increase 80%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 80%.

RHS Product Sales Increase 90%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 90%.

RHS Product Sales Increase 100%

This measure displays the impacted item's sales percentage change when the driver item's (the RHS) sales increase by 100%.

Halo Effects View

The Halo Effects view allows you to review and adjust the Halo cross elasticities.

Figure 21–20 Halo Effects View

60Soup*	
System Calculated Halo Effect	
Approved Halo Effect	
System Calculated Halo T Statistic	
System Calculated Halo Coefficient Standard Error	0.00
System Calculated Halo P Value	
Selected Halo P Value	No P Value Test

Measures: Halo Effects View

The Halo Effects view contains the following measures:

Approved Halo Effect

This measure stores the Halo value that you want to commit. By default it is the same value as the system calculated effect, but you may adjust it.

System Calculated Halo Effect

This measure displays the system calculated Halo effects at product/product/location level.

System Calculated Halo T-Statistic

This measure displays the system calculated T-Statistics for each Halo effect at product/product/location level.

System Calculated Halo Coefficient Standard Error

This measure displays the system calculated standard error for each Halo effect at product/product/location level.

System Calculated Halo P-Value

This measure displays the system calculated P-value for each Halo effect at product/product/location level.

Selected Halo P-Value

This measure displays the user selected P-value for each Halo effect at product/product/location level.

Halo History Data View

The Halo History Data view allows you to view the historical facts used to estimate the Halo effects.

Figure 21–21 Halo History Data View

		4/24/2009	5/1/2009	5/8/2009	5/15/2009	5/22/2009
Weekly Sales Baseline - Halo	80Jams/Jellies*					
	4111Bottled Water*					
	4112Carbonated*					
	Cola*					
	Cranberry					
	Tomatoes					
Weekly Sales history - Halo	80Jams/Jellies*					
	4111Bottled Water*					
	4112Carbonated*					
	Cola*					
	Cranberry					
	Tomatoes					
Weekly Normalized Price - Halo	80Jams/Jellies*					
	4111Bottled Water*					
	4112Carbonated*					
	Cola*					
	Cranberry					
	Tomatoes					
Weekly Promotion Variable - Halo	80Jams/Jellies*					
	4111Bottled Water*					
	4112Carbonated*					
	Cola*					
	Cranberry					
	Tomatoes					

Measures: Halo History Data View

The Halo History Data view contains the following measures:

Weekly Sales Baseline - Halo

This measure represents the sales history cleansed of Promo Self Effects. It is typically at an intersection higher than the final level intersections in RDF, for example, class/region/week.

Weekly Sales History - Halo

This measure represents the total sales history. It is typically at an intersection higher than the final level intersections in RDF, for example, class/region/week.

Weekly Normalized Price - Halo

This measure stores the normalized price. It is typically at an intersection higher than the final level intersections in RDF, for example, class/region/week. There is no guarantee that all items in a subclass (or region) have the same price, hence the need to normalize them.

Weekly Promotion Variable - Halo

This measure stores the information if any promotion was active for a given time period. It is typically at an intersection higher than the final level intersections in RDF, for example, class/region/week.

Cannibalization Statistic Report View

The Cannibalization Statistic Report view allows you to view Cannibalization statistics on the cross effects.

Figure 21–22 Cannibalization Statistic Report View

	301Peanut	512Still	622Caffeinate	Cola*	Cranberry	Tomatoes
Number of Effects Found						
Minimum Effect Found						
Maximum Effect Found						

Measures: Cannibalization Statistic Report View

The Cannibalization Statistic Report view contains the following measures:

Number of Effects Found

This measure displays the number of Cannibalization cross effects found for a given intersection. A typical example for an intersection would be subclass/region.

Minimum Effect Found

This measure displays the minimum value of the Cannibalization effects found for a given intersection. A typical example for an intersection would be subclass/region.

Maximum Effect Found

This measure displays the maximum value of the Cannibalization effects found for a given intersection. A typical example for an intersection would be subclass/region.

Halo Statistic Report View

The Halo Statistic Report view allows you to view Halo statistics on the cross effects.

Figure 21–23 Halo Statistic Report View

	80Jams/Jellies	4111Bottled	4112Carbonati	Cola*	Cranberry	Tomatoes
Number of Effects Found						
Minimum Effect Found						
Maximum Effect Found						

Measures: Halo Statistic Report View

The Halo Statistic Report view contains the following measures:

Number of Effects Found

This measure displays the number of Halo cross effects found for a given intersection. A typical example for an intersection would be class/region.

Minimum Effect Found

This measure displays the minimum value of the Halo effects found for a given intersection. A typical example for an intersection would be class/region.

Maximum Effect Found

This measure displays the maximum value of the Halo effects found for a given intersection. A typical example for an intersection would be class/region.

Appendix: Preprocessing

Preprocessing is a filtering module that automatically adjusts historical data to correct data points that do not represent general demand pattern. Essentially, it smoothes out spikes and dips in historical sales data, replacing stock-out data and data from short term events, such as promotions and temporary price changes, with data points that more accurately represent typical sales for that period. By adjusting the historical sales, Preprocessing can provide smarter data to the RDF Causal Engine, thus creating a smarter baseline forecast.


Note: There are no workbooks associated with Preprocessing - it is available as a configuration option.

Common Preprocessing corrections are:

- Out of stock - Interfaced from RMS, weekly or daily
- Outliers - Indicator not required, depends on method
- Short term events - Promotions, temporary price changes

For example, [Figure A-1](#) illustrates how Preprocessing adjusts for stock-outs.

Figure A-1 Preprocessing for Stock-outs



In [Figure A-1](#), RMS sends historical sales data to the Preprocessing module of RDF. In that sales data, RMS has flagged out-of-stock instances with indicators (the gray

portion of the first data set). Preprocessing takes note of that out-of-stock indicator and adjusts the sales for that time period to reflect a more typical sales quantity, taking into account trending and seasonality. Note in [Figure A-1](#) that Preprocessing has removed the dip in sales in the second data set and has replaced it with a new data point.

Preprocessing Methods

Preprocessing uses several methods to massage historical data. The following sections detail these methods:

- [Standard Median](#)
- [Retail Median](#)
- [Standard Exponential Smoothing](#)
- [Lost Sales Standard Exponential Smoothing](#)
- [Override](#)
- [Increment](#)
- [Forecast Sigma](#)
- [Forecast Sigma Event](#)
- [DePrice](#)
- [Clear](#)
- [No Filtering](#)

Standard Median

Standard Median calculates baselines on long time ranges.

Input: None

Optional parameter: Window length

Figure A-2 *Standard Median Formula*

$$LSOVER(t) = \text{median value over} \left(t - \frac{\text{window}}{2}, t + \frac{\text{window}}{2} \right)$$

Figure A-3 *Standard Median Example*



When data points for the full window are not available, Preprocessing pads the beginning and end of the time series with the first and the last data points, respectively, so that there are values for the full window.

Retail Median

Retail Median calculates baselines on long time ranges and improves side effects by making five standard median filter passes.

Input: none

Optional parameter: window length

Figure A–4 Retail Median Formula

$$\text{Median1} = \text{StdMedian}(\text{Src})$$

$$\text{Median2} = \text{StdMedian}(\text{Median1})$$

$$\text{Diff1}(t) = \text{Median2}(t) - \text{Median2}(t-1)$$

$$\text{Median_Diff1} = \text{StdMedian}(\text{Diff1})$$


$$\text{Smooth1}(t) = \text{Smooth1}(t-1) + \text{Median_Diff1}(t)$$

$$\text{Diff2}(t) = \text{Smooth1}(t) - \text{Smooth1}(t-1)$$

$$\text{Avg_Diff2} = \text{StdMedian}(\text{Diff2})$$

$$\text{Smooth2}(t) = \text{Smooth2}(t-1) + \text{Avg_Diff2}(t)$$

Figure A–5 Retail Median Example



Standard Exponential Smoothing

Standard Exponential Smoothing removes spikes (such as promotional promo, temporary price changes, and so on), as well as filling the gaps (out of stock, unusual events such as a fire or hurricane).

Input: An Event Indicator that indicates which periods should be preprocessed.


Optional Parameters:

The following table details the optional parameters for Standard Exponential Smoothing.

Optional Parameters	Description
ES (Exponential Smoothing)	The alpha parameter that determines the weight put on observations of periods included in the calculations.
Number of future periods (n _{fut})	The number of periods after an outage periods that are considered in the calculation of the future velocity. Note that if during these periods an event flag or a event indicator is on, the particular period is excluded from the calculation.
Number of past periods (n _{past})	The number of periods before an outage periods that are considered in the calculation of the past velocity. Note that if during these periods an event flag or a event indicator is on, the particular period is excluded from the calculation.
Event flag	This parameter indicates if a period should be excluded from the calculation of past/future velocities.
Stop at event flag	This parameter determines which periods are included in the calculation of past/future velocities. If the flag is set to True, then the algorithm only includes periods before the first event flag or event indicator. If the flag is False, then all available, non-flagged periods, within the windows defined by n _{fut} and n _{past} , are used in the calculation of the past and future velocities. The default setting for the flag is False.

Figure A-6 Standard Exponential Smoothing Formula

$$\begin{aligned}
 \text{past velocity} &= \frac{\sum_{i=1}^{np} (1-\alpha)^{i-1} * src(t_f - i)}{\sum_{i=1}^{np} (1-\alpha)^{i-1}} \\
 \text{future velocity} &= \frac{\sum_{i=1}^{nf} (1-\alpha)^{i-1} * src(t_l + i)}{\sum_{i=1}^{nf} (1-\alpha)^{i-1}} \\
 LSOVER(t) &= \text{past velocity} + \frac{\text{future velocity} - \text{past velocity}}{t_l - t_f + 2} * (t - t_f + 1), \text{ where } t \in [t_f, t_l]
 \end{aligned}$$

Figure A-7 Standard Exponential Smoothing Example

When event flags exist within the future and past velocity windows, rather than consider the entire window, Preprocessing only considers unflagged data points after the last event flag in the history window to compute the past velocity. It does a similar process for the future window by using the unflagged data points prior to the first event flag in the future window to compute the future velocity. Consecutive events are smoothed using the same velocities. A data point becomes flagged, and hence not part of the future/past velocity calculation, if either the event indicator or the optional event flag are on.

If future velocities cannot be calculated, then the past velocities, if they exist, are used as future and past velocities, and vice versa. When neither of the velocities can be calculated, there is no adjustment.

If the velocity window contains all zero values, then the calculated velocity is zero. A velocity of zero is a legitimate value if it occurs within the selling window. A velocity of zero is not acceptable if it is calculated based on values outside of the selling window.

Lost Sales Standard Exponential Smoothing

Lost Sales Standard Exponential Smoothing calculates baselines on long time ranges. Lost Sales Standard Exponential Smoothing makes positive adjustments to the flagged periods and to the period immediately following the flagged period.

Input: An Out-of-stock indicator that indicates which periods should be preprocessed.

Optional parameters:

The following table details the optional parameters for Lost Sales Standard Exponential Smoothing.

Optional Parameters	Description
ES (Exponential Smoothing)	The alpha parameter that determines the weight put on observations of periods included in the calculations.
Number of future periods (nfut)	The number of periods after an outage periods that are considered in the calculation of the future velocity. Note that if during these periods an event flag or a event indicator is on, the particular period is excluded from the calculation.

Optional Parameters	Description
Number of past periods (npast)	The number of periods before an outage periods that are considered in the calculation of the past velocity. Note that if during these periods an event flag or a event indicator is on, the particular period is excluded from the calculation.
Event flag	This parameter indicates if a period should be excluded from the calculation of past/future velocities.
Partial outage flag	A scalar parameter indicating if the period immediately following an out-of-stock period should be adjusted. The default behavior is for the flag to be True.
Stop at event flag	This parameter determines which periods are included in the calculation of past/future velocities. If the flag is set to True, then the algorithm only includes periods before the first event flag or event indicator. If the flag is False, then all available, non-flagged periods, within the windows defined by nfut and npast, are used in the calculation of the past and future velocities. The default setting for the flag is False.


Figure A–8 Lost Sales Standard Exponential Smoothing Formula

$$past\ velocity = \frac{\sum_{i=1}^{np} (1-\alpha)^{i-1} * src(t_f - i)}{\sum_{i=1}^{np} (1-\alpha)^{i-1}}$$

$$future\ velocity = \frac{\sum_{i=1}^{nf} (1-\alpha)^{i-1} * src(t_l + i)}{\sum_{i=1}^{nf} (1-\alpha)^{i-1}}$$

$$LSOVER(t) = \max \{src(t), past\ velocity + \frac{future\ velocity - past\ velocity}{t_l - t_f + 2} * (t - t_f + 1)\}, \text{ where } t \in [t_f, t_l]$$

Figure A–9 Lost Sales Standard Exponential Smoothing Example



When event flags exist within the future and past velocity windows, rather than consider the entire window, Preprocessing only considers unflagged data points after

the last event flag in the history window to compute the past velocity. It does a similar process for the future window by using the unflagged data points prior to the first event flag in the future window to compute the future velocity. Consecutive events are smoothed using the same velocities. A data point becomes flagged, and hence not part of the future/past velocity calculation, if either the event indicator or the optional event flag is on.

If future velocities cannot be calculated, then the past velocities, if they exist, are used as future and past velocities, and vice versa. When neither of the velocities can be calculated, there is no adjustment.

If the velocity window contains all zero values, then the calculated velocity is zero. A velocity of zero is a legitimate value if it occurs within the selling window. A velocity of zero is not acceptable if it is calculated based on values outside of the selling window. Note that by default, the periods being adjusted are the periods flagged by an out-of-stock indicator and the period immediately following any such period. If the optional scalar parameter POA (Partial Outage Allowed) is set to *False*, then this extra period will not be adjusted, and only the out-of-stock periods will be adjusted.

Override

Override fills gaps in data when a reference measure exists.

Input: reference measure ($R(t)$) to copy data from

Optional parameter: outage/mask ($M(i)$), adjustment ratio (a)


Formula: Overrides $LSOVER$ with the Src adjusted by the adjustment ratio according to the mask:

Figure A–10 *Override Formula*

$$LSOVER(t) = a * R(t) \quad \text{if } M(i) \text{ is true}$$

$$LSOVER(t) = Src(t) \quad \text{if } M(i) \text{ is false}$$

Figure A–11 *Override Example*



Increment

Increment updates gaps or outliers in data when a reference measure exists.

Input: reference measure ($R(t)$) to copy data from

Optional parameter: outage/mask ($M(i)$), adjustment ratio (a)


Increments the Src with the reference adjusted by the adjustment ratio according to the mask:

Figure A–12 Increment Formula

$$LSOVER(t) = SRC(t) + a * R(t) \quad \text{if } M(i) \text{ is true}$$

$$LSOVER(t) = Src(t) \quad \text{if } M(i) \text{ is false}$$

Figure A–13 Increment Example



Forecast Sigma

Forecast Sigma removes spikes in recent data when no indicators are available.

Inputs: forecast and confidence intervals

Optional parameters:

- number of stddev for upper bound
- number of stddev for lower bound
- forecast lower bound
- minimum history required for filtering

Formula: If the difference in the sales and forecast is larger than a threshold, the override value is brought within some bounds of the forecast.

Forecast Sigma Event

Like Forecast Sigma, Forecast Sigma Event removes spikes in recent data when no indicators are available but also takes outage as input.

Inputs: outage, forecast, confidence intervals

Optional parameters:

- number of stddev for upper bound
- number of stddev for lower bound
- forecast lower bound
- minimum history required for filtering

Formula:

If outage is on:

LSOVER = forecast

Otherwise, if the difference in the sales and forecast is larger than a threshold, the override value is brought within some bounds of the forecast.

DePrice

DePrice removes the pricing effects.

Inputs: price, maximum price

Optional parameters: none

Formula:

*Smoothed = original * (price/maxprice) ^2*

Clear

This Preprocessing method clears the Preprocessing adjustments from previous runs.

No Filtering

This Preprocessing method does not filter the source data.

Preprocessing for Stock-outs

When using Preprocessing to correct for stock-outs, the system expects out-of-stock indicators from a merchandising system like RMS. The system can be set up for automatic adjustment of sales history to correct for stock-outs as well as for manual user overrides under exception cases.

When set to automatically adjust sales history to correct stock-outs, Preprocessing takes into account trending and seasonality and adjusts the sales that were flagged by the out-of-stock indicator to reflect a more typical sales quantity.

When out-of-stock flags are not interfaced, RDF uses the Preprocessing Review and What-if workbook to generate such a flag. The logic in pseudocode used to create the measure is:

```

If Sales Volume Threshold Low < rate of sales < Sales Volume Threshold
High
    If minimum number of sales periods > Low Seller Minimum Number of Sales
    Periods
        &&
        number of periods with zero sales < Low Seller Minimum Number of
    Zero Sales
        &&
        sales < Low Seller Out of Stock Factor * rate of sales * seasonal
    index
        then OOS = TRUE
    elseif rate of sales > Sales Volume Threshold High
        If minimum number of sales periods > High Seller Minimum Number of
    Sales Periods
            &&
  
```

```
number of periods with zero sales < High Seller Minimum Number of  
Zero Sales  
  
    &&  
sales < High Seller Out of Stock Factor * rate of sales * seasonal  
index  
  
then out of stock flag = TRUE
```

Note that the words in italics are the parameters/thresholds defined in the Out of Stock & Outlier Thresholds worksheet.

Other measures, like rate of sales, or sales, are measures existent in the environment but are not preprocessing-specific.

Preprocessing for Outliers

When using Preprocessing to correct for outliers, the system expects outlier indicators. These can be loaded, but they can also be created if they are not available elsewhere. The logic in pseudocode to create the outlier measure is:

```
If sales > rate of sales * Outlier Factor  
  
    &&  
    Period is not promoted  
Then outlier flag = TRUE
```

Note that the words in italics are the parameters/thresholds defined in the Out of Stock & Outlier Thresholds worksheet.

Other measures, like rate of sales, or sales, are measures existent in the environment but are not preprocessing-specific.

Preprocessing for Promotional Forecasting

Preprocessing adjusts promotional data in a similar way that it does stock-outs. Typically, historical data shows a higher rate of sales during promotional periods. Were these spikes in sales to be left in historical sales data and loaded in the RDF Causal Engine, the baseline forecast created from this data would reflect similar spikes in future sales.

Appendix: RDF Workbooks (Fusion Client)

This appendix provides a convenient reference of all the RDF workbooks on the RPAS Fusion Client and their respective views and measures by task:

- [Forecast Product/Location Cloning Administration Task](#)
- [Forecast Like-Item, Sister-Store Task](#)
- [Promote \(Promotional Forecasting\)](#)
 - [Promo Effectiveness - Promotion Results Task](#)
 - [Promo Effect Maintenance Task](#)
 - [Promotion Management Task](#)
 - [Promo Planner Task](#)
- [Forecast Scorecard Task](#)
- [Interactive Forecasting Task](#)
- [Forecast Administration Task](#)
- [Forecast Maintenance Task](#)
- [Preprocessing Administration Task](#)
- [Preprocessing Review and What-if Task](#)
- [Floating Event Administration Task](#)
- [Extra Week Administration Task](#)
- [Run Batch Forecast Task](#)
- [Forecast Approval Task](#)
- [Alert Thresholds Task](#)
- [Forecast Delete Task](#)
- [Cross Promotional Effects Module \(CPEM\) Task](#)

Forecast Product/Location Cloning Administration Task

This section lists the workbook found in [Chapter 4, "Forecast Product/Location Cloning Administration Task,"](#) and its respective views and measures.

Product/Location Cloning Administration Workbook

[Table B-1](#) lists the views and measures for the [Product/Location Cloning Administration Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-1 Product/Location Cloning Administration Workbook

View	Measures
Adjustment Parameters View	Cloned History Adjustment - Alpha (Range 0-1) Cloned History Adjustment - Recent Sales Threshold Cloned History Adjustment - Calculation Window Length
Location Cloning View	Location Clones Location Clone Contributions Clone Location Adjustment Ratio
Product Cloning View	Product Clones Product Clone Contributions Clone Product Adjustment Ratio
Clone Mask View	Clone Mask

Forecast Like-Item, Sister-Store Task

This section lists the workbook found in [Chapter 5, "Forecast Like-Item & Sister-Store Task,"](#) and its respective views and measures.

Forecast Like-Item, Sister-Store Workbook

[Table B-2](#) lists the views and measures for the [Forecast Like-Item& Sister-Store Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-2 Forecast Like-Item, Sister-Store Workbook

View	Measures
Like-Item View	Like SKU
Sister-Store View	Sister Store

Table B–2 (Cont.) Forecast Like-Item, Sister-Store Workbook

View	Measures
Advanced Parameter View	Adjustment Ratio Base Rate of Sales Forecast Start Date Override Forecast End Date Override History Start Date Override

Promote (Promotional Forecasting)

This section lists the tasks and workbooks found in [Chapter 6, "Promote \(Promotional Forecasting\) Task,"](#) and their respective views and measures.

Promo Effectiveness - Promotion Results Task

This section lists the workbook found in the [Promo Effectiveness - Promotion Results Task](#) and its respective views and measures.

Promo Effectiveness - Promotion Results Workbook

[Table B–3](#) lists the views and measures for the [Promo Effectiveness - Promotion Results Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–3 Promo Effectiveness - Promotion Results Workbook

View	Measures
Promotion Model Type View	Model Type for Promotional Variable
Promotions View	Promotion Variables

Table B-3 (Cont.) Promo Effectiveness - Promotion Results Workbook

View	Measures	
Aggregated Promotion Lift Override View	Aggregated Promotion Lift Override Promotional Lift Override	
Promotional Forecast View	Forecast Baseline Price Cannibalization Lift Unit Price Halo Lift Units Price Self Lift Units Promotion Cannibalization Lift Units Promotion Halo Lift Units	Promotion Self Lift Units Promotional Forecast with Promote Lift Override Promotional Lift Override Total Promotional Lift Unit Total Regular Price Lift Unit
Promotion Parameters View	Apply Promotion Cannibalization Lift Apply Promotion Halo Lift Apply Promotional Lift Override Apply Regular Price Cannibalization Lift Apply Regular Price Halo Lift Apply Regular Price Lift	Apply Regular Price Lift Over Promotion Apply Regular Price Self Lift Promo Effect Type System Calculated Effect System Effect Override

Promo Effect Maintenance Task

This section lists the workbook found in the [Promo Effect Maintenance Task](#) and its respective views and measures.

Promo Effect Maintenance Workbook

[Table B-4](#) lists the views and measures for the [Promo Effect Maintenance Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-4 Promo Effect Maintenance Workbook

View	Measures
Promotion Parameters View	Promo Effect Type System Calculated Effect System Effect Override

Promotion Management Task

This section lists the workbook found in the [Promotion Management Task](#) and its respective views and measures.

Promotion Management Workbook

Table B–5 lists the views and measures for the [Promotion Management Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–5 Promotion Management Workbook

View	Measures
Promo Variable Model Type View	Model Type for Promotional Variable
Promotion Enable View	Enable Promotions
Accept Negative Lift View	Promotion Allow Negative Lift

Promo Planner Task

This section lists the workbook found in the [Promo Planner Task](#) and its respective views and measures.

Promo Planner Workbook

Table B–6 lists the views and measures for the [Promo Planner Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–6 Promo Planner Workbook

View	Measures
Promotions View	Promotion Variables

Forecast Scorecard Task

This section lists the workbook found in [Chapter 7, "Forecast Scorecard Task,"](#) and its respective views and measures.

Forecast Scorecard Workbook

Table B–7 lists the views and measures for the [Forecast Scorecard Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-7 Forecast Scorecard Workbook

View	Measures
Error Measure View	History Data for Forecast Window Forecast Measures Mean Error Mean Absolute Error Root Mean Squared Error Mean Absolute Percentage Error Percentage Absolute Error
Actuals versus Forecasts View	Actuals History Data Forecast Measures

Interactive Forecasting Task

This section lists the workbook found in [Chapter 8, "Interactive Forecasting Task,"](#) and its respective views and measures.

Interactive Forecasting Workbook

[Table B-8](#) lists the views and measures for the [Interactive Forecasting Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-8 Interactive Forecasting Workbook

View	Measures
Forecasting Parameter View	Forecast Method Forecast Picked Method History Start Date Forecast Start Date Forecast End Date
Interactive Forecasting View	History Data System Forecast

Forecast Administration Task

This section lists the workbook found in [Chapter 9, "Forecast Administration Task,"](#) and its respective views and measures.

Forecast Administration Workbook

[Table B-9](#) lists the settings, views, and measures for the [Forecast Administration Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-9 Forecast Administration Workbook

Settings	View	Measures	
Basic Settings	Final Level View - Basic Settings	Default Return Forecast Flag	Forecast Cycle
		Default Return Forecast Percentage	Forecast Start Date
		Default Return Forecast Time Shift	Forecast Length
		Default Source Level	Next Run Date
	Final and Source Level Parameters View - Basic Settings	Forecast Data Source	Seasonal Profile
		Default History Start Date	Spreading Profile
		Data Plan	Source Level Forecast Data Source
		Default Forecast Method	Source Level History Start Date
Advanced Settings	Causal Parameters View - Advanced Settings	Aggregated Promotional Lift Override	Causal External Baseline
		Causal - Effects Only	Causal Higher Intersection
		Causal - Lift Estimate	Causal SLC - ROS
		Causal Aggregation Profile	Causal Spread Profile
		Causal Beta Scale	Default Overlapping Promotion Adjustment Factor
		Causal Calculation Intersection	Default Overlapping Promotions Behavior
		Causal Calculation Intersection Periodicity	Disable Causal
		Causal Capping Number	Minimum Causal Capping History
		Causal Capping Ratio	Minimum Causal Capping History (Periods)
		Causal Data Source	Use Causal Capping

Table B-9 (Cont.) Forecast Administration Workbook

Settings	View	Measures	
Advanced Settings	Final Level Parameters View - Advanced Settings	Components - Baseline Components - Baseline Interval Components - Regular Price Lifts Components - Promotional Lifts Days to Keep Forecasts Default Apply Interaction Factor Default Interaction Factor Default Keep Last Changes Generate Baseline Forecasts Generate Cumulative Interval	Generate Intervals Generate Methods Generate Parameters Interval Cap Lower Ratio Interval Cap Upper Ratio Item End Date Action Like TS Duration (Periods) Store Interim Forecast Updating Last Week Forecast Updating Last Week Forecast Number of Weeks
	Final and Source Level Parameters View - Advanced Settings	Bayesian Alpha (range (0, infinity)) Bayesian Cap Ratio Croston's Min Gaps DD Duration (weeks) Default Moving Average Window Length Deseasonalized Demand Array Extra Week Interpret Method Extra Week Indicator Data Source Fit Error Factor Source Fallback Method Holt Min Hist (Periods)	Max Alpha (Profile) (range [0,1]) Max Alpha (Simple, Holt) (range [0,1]) Max Alpha (Winters) (range [0,1]) Max Gamma (Holt) (range [0,1]) Max Gamma (Winters) (range [0,1]) Seasonal Smooth Index Trend Damping Factor (range [0,1]) Winters Min Hist (Periods) Winters Mode Winters Mode Impact on AutoES and Causal

Table B–9 (Cont.) Forecast Administration Workbook

Settings	View	Measures	
	Regular Price Parameters View-Advanced Settings	Apply Regular Price Lift Apply Regular Price Lift over Promotion Regular Price Decaying Factor Apply Regular Price Self Lift	Apply Regular Price Halo Lift Apply Regular Price Cannibalization Lift Regular Price Effective Periods Price Elasticity Matrix Data Source
	Promo Affinity Parameters View- Advanced Settings	Apply Promotion Cannibalization Lift Apply Promotion Halo Lift Cross Promo Cannibalization Change Ratio Source Cross Promo Cannibalization Max Change Ratio Source	Cross Promo Halo Change Ratio Source Cross Promo Halo Max Change Ratio Source Promo Cannibalized Matrix Data Source Promo Halo Matrix Data Source
	Demand Transference Parameters View- Advanced Settings	Default Apply Demand Transference Effects Default Demand Transference Effect Decay Factor Default Demand Transference Effects Applying Period	Default Maximum Assortment Multipliers Default Minimum Assortment Multipliers Demand Transference Enabled

Forecast Maintenance Task

This section lists the workbook found in [Chapter 10, "Forecast Maintenance Task,"](#) and its respective views and measures.

Forecast Maintenance Workbook

[Table B–10](#) lists the settings, views, and measures for the [Forecast Maintenance Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–10 Forecast Maintenance Workbook

Settings	View	Measures	Measures
Basic Settings	Final and Source Level Views - Basic Settings	Approval Method Override Bayesian Alpha Override Forecast Method Override Keep Last Changes Override Moving Average Window Length Override Optimal Source Levels	Pick Optimal Level Return Forecast Flag Override Return Forecast Percentage Override Return Forecast Time Shift Override Source Level Override Winters Mode Override
Advanced Settings	Advanced Final Parameter View	Apply Promotion Cannibalization Lift Override Apply Promotion Halo Lift Override Apply Promotional Lift Override Apply Regular Price Cannibalization Lift Override Apply Regular Price Halo Lift Override Apply Regular Price Lift Over Promotion Override Apply Regular Price Lift Override Apply Regular Price Self Lift Override Demand Transference Effects Applying Period Override Demand Transference Effects Decaying Factor Override	Forecast End Date Override Forecast Start Date Override History Start Date Override Interaction Factor Override Overlapping Promotion Adjustment Factor Override Overlapping Promotions Behavior Override Regular Price Decaying Factor Override Regular Price Effective Periods Override

Preprocessing Administration Task

This section lists the workbook found in [Chapter 11, "Preprocessing Administration Task,"](#) and its respective views and measures.

Preprocessing Administration Workbook

[Table B–11](#) lists the views and measures for the [Preprocess Admin Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–11 Preprocessing Administration Workbook

View	Measures	Measures
Preprocess Admin View	Deseasonalized Flag Min Number of Weeks in System	Min Number of Weeks with Sales
Out of Stock and Outlier Threshold View	High Seller Out of Stock Factor High Sellers Minimum Number of Sales Periods High Sellers Minimum Number of Zero Sales Low Seller Out of Stock Factor Low Sellers Minimum Number of Sales Periods	Low Sellers Minimum Number of Zero Sales Outlier Factor Sales Volume Threshold High Sales Volume Threshold Low
Preprocess Panel for Baseline Data Source View	Event Indicator Input Data Source Measure Output Data Measure	Preprocess Method Preprocessing Label Run Preprocess Flag
Preprocess Panel for Causal Data Source View	Event Indicator Input Data Source Measure Output Data Measure	Preprocess Method Preprocessing Label Run Preprocess Flag
Preprocess Method Parameters View	Alpha Future Weeks Last Date	Past Weeks Preprocessing Window Standard Median Window
Preprocess Method Parameters Override View	Alpha Override Future Weeks Override Last Date Override	Past Weeks Override Preprocessing Window Override Standard Median Window Override

Preprocessing Review and What-if Task

This section lists the workbook found in [Chapter 12, "Preprocessing Review and What-if Task,"](#) and its respective views and measures.

Preprocessing Review and What-if Workbook

[Table B–12](#) lists the views and measures for the [Preprocess Review and What-if Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–12 *Preprocessing Review and What-if Workbook*

View	Measures	Measures
Preprocessing Admin View	Deseasonalized Flag Min Number of Weeks in System	Min Number of Weeks with Sales
Out of Stock and Outlier Threshold View	High Seller Out of Stock Factor High Sellers Minimum Number of Sales Periods High Sellers Minimum Number of Zero Sales Low Seller Out of Stock Factor Low Sellers Minimum Number of Sales Periods	Low Sellers Minimum Number of Zero Sales Outlier Factor Sales Volume Threshold High Sales Volume Threshold Low
Preprocess Panel for Baseline Data Source View	Event Indicator Input Data Source Measure Output Data Measure	Preprocess Method Preprocessing Label Run Preprocess Flag
Preprocess Panel for Causal Data Source View	Event Indicator Input Data Source Measure Output Data Measure	Preprocess Method Preprocessing Label Run Preprocess Flag
Preprocess Method Parameters View	Alpha Future Weeks Last Date	Past Weeks Preprocessing Window Standard Median Window

Table B–12 (Cont.) Preprocessing Review and What-if Workbook

View	Measures	Measures
Preprocess Method Parameters Override View	Alpha Override Future Weeks Override Last Date Override	Past Weeks Override Preprocessing Window Override Standard Median Window Override
What-if Data View	Baseline Sales Corrected Sales for OOS Corrected Sales for Outliers Depromoted Sales Deseasonalized Sales	Out of Stock Indicator Outliers Indicator Promotion Indicator Seasonal Profile
What-if Plot View	Baseline Sales Corrected Sales for OOS Corrected Sales for Outliers Depromoted Sales Deseasonalized Sales	Out of Stock Indicator Outliers Indicator Promotion Indicator Seasonal Profile

Floating Event Administration Task

This section lists the workbook found in [Chapter 13, "Floating Event Administration Task,"](#) and its respective views and measures.

Floating Event Admin Workbook

[Table B–13](#) lists the views and measures for the [Floating Events Admin Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–13 Floating Event Admin Workbook

View	Measures
Floating Event Calendar Maintenance View	Float Event Indicator (01-20)

Extra Week Administration Task

This section lists the workbook found in [Chapter 14, "Extra Week Administration Task,"](#) and its respective views and measures.

Extra Week Administration Workbook

[Table B-14](#) lists the views and measures for the [Extra Week Administration Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-14 *Extra Week Administration Workbook*

View	Measures
Extra Week Indicator Setup View	Extra Week Indicator

Run Batch Forecast Task

This section describes the wizard found in [Chapter 16, "Run Batch Forecast Task,"](#).

Wizard

The [Run Batch Forecast Workbook](#) is a wizard that automatically executes PreGenerate Forecast and Generate within the Simple or Local Domain.

Forecast Approval Task

This section lists the workbook found in [Chapter 17, "Forecast Approval Task,"](#) and its respective views and measures.

Forecast Approval Workbook

[Table B-15](#) lists the views and measures for the [Forecast Approval Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-15 Forecast Approval Workbook

View	Measures	
Advanced Final Level View	Promotion Cannibalization Lift Units Promotion Halo Lift Units Promotion Indicator Promotion Self Lift Units Regular Price	Regular Price Cannibalization Lift Regular Price Halo Lift Regular Price Self Lift Total Promotion Lift Units Total Regular Price Lift Units
Final Level View	Adjusted Cumulative Interval Adjusted Forecast Approved Cumulative Interval Approved Forecast Approved System Forecast Forecast Cumulative Interval Forecast Interval Forecast vs. Last Approved Forecast Workbook Alert Forecast vs. Recent Sales Workbook Alert History Data	Interaction Multiplier Interim Forecast Last Approved Forecast Overlapping Promotion Flag Return Forecast System Baseline System Forecast Total Peak Total Promotion Lift Units Total Regular Price Lift Units
Approval View	Approval Comment Approval Date	Approved By Manually Approved
Valid Forecast Run View	Final Level Run Flag	
Source Level View	History Data System Baseline	System Forecast
Final or Source System Parameters View	Fit Error Factor Forecast Method Picked System Generated Alpha	System Generated Level System Generated Gamma System Generated Trend

Alert Thresholds Task

This section lists the workbook found in [Chapter 18, "Alert Thresholds Task,"](#) and its respective views and measures.

Alert Thresholds Workbook

Table B–16 lists the views and measures for the [Extra Week Administration Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–16 Alert Thresholds Workbook

View	Measures	
Forecast Alert Default Parameters View	Default Forecast Length for Forecast Accuracy Default Forecast vs Last Approved Forecast - Average Sales Threshold Default Forecast vs Last Approved Forecast Length Default Forecast vs Last Approved Forecast Threshold Default Forecast vs Recent Sales - Average Sales Threshold Default Forecast vs Recent Sales - Forecast Length	Default Forecast vs Recent Sales Threshold Default High Forecast Error Value Default Low Forecast Error Value Default Low Rate of Sales Value Default Medium Forecast Error Value Default Medium Rate of Sales Value
Forecast Alert Intermediate Intersection Parameters View	Intermediate Forecast Length for Forecast Accuracy Intermediate Forecast vs Last Approved Forecast Average Sales Threshold Intermediate Forecast vs Last Approved Forecast Length Intermediate Forecast vs Last Approved Forecast Threshold Intermediate Forecast vs Recent Sales Forecast Length Intermediate Forecast vs Recent Sales Average Sales Threshold	Intermediate Forecast vs Recent Sales Threshold Intermediate High Forecast Error Value Intermediate Low Forecast Error Value Intermediate Low Rate of Sales Value Intermediate Medium Forecast Error Value Intermediate Medium Rate of Sales Value
Forecast Alert Final Level Intersection Parameters View	Forecast Length for Forecast Accuracy - override Forecast vs Last Approved Forecast Average Sales Threshold - override Forecast vs Last Approved Forecast Length - override Forecast vs Last Approved Forecast Threshold - override Forecast vs Recent Sales Average Sales Threshold - override Forecast vs Recent Sales Forecast Length - override	Forecast vs Recent Sales Threshold - override High Forecast Error Value - override Low Forecast Error Value - override Low Rate of Sales Value - override Medium Forecast Error Value - override Medium Rate of Sales Value - override

Forecast Delete Task

This section describes the wizard found in [Chapter 19, "Forecast Delete Task,"](#).

Wizard

The [Forecast Delete Wizard](#) is used in a global domain environment. Deleting a forecast in the Master domain deletes the selected birth date within all domains. Deleting a forecast in the Local domain deletes the selected birth date only within the Local domain.

Cross Promotional Effects Module (CPEM) Task

This section lists the workbooks found in [Chapter 21, "Cross Promotional Effects Module \(CPEM\),"](#) and their respective tabs, views, and measures.

Effect Estimation Administration Workbook

[Table B–17](#) lists the tabs, views, and measures for the [Effect Estimation Administration Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B–17 Effect Estimation Administration Workbook

Tabs	Views	Measures	
Effect Estimation Administration	Default Parameters View	History Start Date History End Date Cannibalization Ancestor Level Cannibalization Lower Bound	Cannibalization Upper Bound Halo Lower Bound Halo Upper Bound
	Cannibalization Parameter Override View	Cannibalization Lower Bound - Override	Cannibalization Upper Bound - Override
	Halo Parameter Override View	Halo Lower Bound - Override	Halo Upper Bound - Override
	Halo Products Mapping View	Halo Mask	

Effect Estimation Review and Approval Workbook

[Table B–18](#) lists the tabs, views, and measures for the [Effect Estimation Review and Approval Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table B-18 Effect Estimation Review and Approval Workbook

Tabs	Views	Measures	
Cross Promo Effect	Cannibalization Effects Drive View	System Calculated Cannibalization Effect	Approved Cannibalization Effect
	Cannibalization Effects Percentage View	Approved Cannibalization Effect RHS Product Sales Increase 10% RHS Product Sales Increase 20% RHS Product Sales Increase 30% RHS Product Sales Increase 40% RHS Product Sales Increase 50%	RHS Product Sales Increase 60% RHS Product Sales Increase 70% RHS Product Sales Increase 80% RHS Product Sales Increase 90% RHS Product Sales Increase 100%
	Cannibalization Effects View	Approved Cannibalization Effect System Calculated Cannibalization Effect System Calculated Cannibalization T Statistic System Calculated Cannibalization Coefficient Standard Error	System Calculated Cannibalization P Value Selected Cannibalization P Value Approved Cannibalization Effect
	Cannibalization History Data View	Weekly Sales Baseline - Cannibalization Weekly Sales History - Cannibalization	Weekly Normalized Price - Cannibalization Weekly Promotion Variable - Cannibalization
	Halo Effects Drive View	System Calculated Halo Effect	Approved Halo Effect
	Halo Effects Percentage View	Approved Halo Effect RHS Product Sales Increase 10% RHS Product Sales Increase 20% RHS Product Sales Increase 30% RHS Product Sales Increase 40% RHS Product Sales Increase 50%	RHS Product Sales Increase 60% RHS Product Sales Increase 70% RHS Product Sales Increase 80% RHS Product Sales Increase 90% RHS Product Sales Increase 100%
	Halo Effects View	Approved Halo Effect System Calculated Halo Effect System Calculated Halo T-Statistic	System Calculated Halo Coefficient Standard Error System Calculated Halo P-Value Selected Halo P-Value

Table B-18 (Cont.) Effect Estimation Review and Approval Workbook

Tabs	Views	Measures	
	Halo History Data View	Weekly Sales Baseline - Halo Weekly Sales History - Halo	Weekly Normalized Price - Halo Weekly Promotion Variable - Halo
Cross Effect Statistics Reports	Cannibalization Statistic Report View	Number of Effects Found Minimum Effect Found	Maximum Effect Found
	Halo Statistic Report View	Number of Effects Found Minimum Effect Found	Maximum Effect Found

Appendix: Curve Workbooks (Fusion Client)

This appendix provides a convenient reference of all the Curve workbooks on the RPAS Fusion Client and their respective views and measures by task.

The following sections list the workbooks, views, and measures found in [Chapter 15, "Curve Task"](#):

- [Profile Administration Task](#)
- [Profile Approval Task](#)
- [Profile Maintenance Task](#)
- [Run Batch Profile Task](#)

Profile Administration Task

This section lists the workbook found in the [Profile Administration Task](#) and its respective views and measures.

Profile Administration Workbook

[Table C-1](#) lists the views and measures for the [Profile Administration Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table C-1 Profile Administration Workbook

View	Measures	
Profile Parameter View	Default Phase End Default Phase Start Default Profile Approval Method Default Source Profile Default Training Window End Default Training Window Start Normal Value	Profile Data Source Profile Type Renormalize System Training Window Length Training Window Method Use Advanced Profile Features
Profile and Source Level Intersection View	Profile Agg Intersection Profile Approval Intersection	Profile Intersection Stored Intersection

Profile Approval Task

This section lists the workbook found in the [Profile Approval Task](#) and its respective views and measures.

Profile Approval Workbook

[Table C-2](#) lists the views and measures for the [Profile Approval Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table C-2 Profile Approval Workbook

View	Measures
Final Profile View	Adjusted Profile Approved Profile System Profile
Source Profile View	System Profile
Profile Approval View	Profile Approved By Profile Approval Date Manually Approve Source Profile Override

Profile Maintenance Task

This section lists the workbook found in the [Profile Maintenance Task](#) and its respective views and measures.

Profile Maintenance Workbook

[Table C-3](#) lists the views and measures for the [Profile Maintenance Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Fusion Client*.

Table C-3 Profile Maintenance Workbook

View	Measures
Profile Maintenance: Final Approval and Sourcing View	Profile Approval Method Source Profile Override
Profile Maintenance: Final Training Window View	System Training Window Begin System Training Window End

Run Batch Profile Task

The [Run Batch Profile Task](#) allows you to run the [Run Batch Profile Workbook](#); a wizard that automatically executes curvebatch within the Simple or Local Domain.

Appendix: Grade Workbooks (Fusion Client)

This appendix provides a convenient reference of all the Grade tasks, wizards, and workbooks on the RPAS Fusion Client.

The following sections list the tasks found in [Chapter 20, "Grade Task"](#):

- [Breakpoints Administration Task](#)
- [Delete Cluster Run Task](#)
- [Cluster Review Task](#)
- [Breakpoint Grades Task](#)
- [Generate Clusters Task](#)

Breakpoints Administration Task

Use the [Breakpoint Administration Task](#) to generate the [Breakpoint Administration Workbook](#) that allows you to set multiple breakpoint configurations to allow for grades to be produced and compared using different breakpoint settings.

Delete Cluster Run Task

The [Delete Cluster Run Wizard](#) allows you to delete clusters from the system based on Cluster Run Label and generation date (birth date).

Cluster Review Task

The [Cluster Review Task](#) is a wizard that generates the [Cluster Review Workbook](#), which allows you to view grade or cluster results and statistics.

[Table D-1](#) lists the views and measures for the [Cluster Review Workbook](#). For additional information, click any link to go to that section of the *Oracle Retail Demand Forecasting User Guide for the RPAS Classic Client*.

Table D-1 Cluster Review Workbook

View	Measures	
Cluster Input Summary View	Number of Clusters	Measure to Cluster
	Dimension to Cluster Over	Dimension to Cluster
	Cluster Run Name	Cluster By Group Intersection

Breakpoint Grades Task

The [Generate Breakpoint Grades Task](#) is a wizard that allows you to range the input data and hierarchies, which is used to produce grades based on the Breakpoints method.

Generate Clusters Task

The [Generate Clusters Task](#) is a wizard that allows you to range the input data and hierarchies which is used to produce clusters based on the Clustering (BaNG) method.

Glossary

Note: With a few exceptions, this glossary contains definitions of terms specific to RDF. For further definitions of terms and concepts relating to the RPAS user interface, refer to the *Oracle Retail Predictive Application Server Online Help* or *Oracle Retail Predictive Application Server User Guide*.

Additive Seasonal Method

Also referred to as Additive Winters Model, this model is similar to the Multiplicative Winters model but it is used when zeros are present in the data. This model adjusts the un-seasonalized values by adding the seasonal index for the forecast horizon.

Alert

A notice displayed to system users that a forecast value is above or below user-defined limits (an exception).

Alert Manager Window

A window that displays the alerts assigned to you. This dialog provides a list of all identified instances in which a monitored measure's values fall outside a set of defined limits. You may pick an alert from this list and have RCS automatically build a workbook containing the measure values that triggered the alert.

AutoES Method or Automatic Exponential Smoothing Method

RDF fits the sales data to a variety of exponential smoothing (time series) models of forecasting, and the best model is chosen for the final forecast. The candidate methods considered by AutoES are:

- SimpleES
- IntermittentES
- TrendES
- Multiplicative Seasonal
- Additive Seasonal and SeasonalES

The final selection between the models is made according to a performance criterion (Bayesian Information Criterion) that involves a trade-off between the model's fit over the historic data and its complexity.

Bayesian Method

Useful for short lifecycle forecasting and for new products with little or no historic sales data. The Bayesian method requires a product's known sales plan (created externally to RDF) and considers a plan's shape (the selling profile or lifecycle) and scale (magnitude of sales based on Actuals). The initial forecast is equal to the sales plan, but as sales information comes in, the model generates a forecast by merging the sales plan with the sales data. The forecast is adjusted so that the sales magnitude is a weighted average between the original plan's scale and the scale reflected by known history.

Causal Method

Causal is a forecasting method used for promotional forecasting and can only be selected if Promote is implemented. Typically, the Causal method is used at the Final Levels (that is, item/week/week). Causal uses a Stepwise Regression sub-routine to determine the promotional variables that are relevant to the time series and their lift effect on the series. AutoES utilizes the time series data and the future promotional calendar to generate future baseline forecasts. By combining the future baseline forecast and each promotion's effect on sales (lift), a final promotional forecast is computed.

Croston's Model of Exponential Smoothing

See [IntermittentES](#) or [Intermittent Exponential Smoothing](#).

Curve

An optional automated predictive solution that transforms organization-level assortment plans into base-level weekly sales forecasts.

Exception

A forecast value that is greater than or less than a user-defined limit.

Exponential Smoothing

A form of a weighted moving average. Its weight declines in data exponentially. Most recent data is weighted more heavily. It requires the smoothing constant. It ranges from 0 to 1 and is subjectively chosen.

Final Forecast Level

A low level in a hierarchy from which a forecast is generated and at which approvals and data exports can be performed. Often, data from forecasts at a low level is insufficient to generate reliable forecasts without first aggregating the data to a higher level and then spreading the data back to the low level.

Forecast

In RDF, Forecast refers to RDF's statistical forecasting capabilities.

Forecast-Driven Planning

Planning that keys off of forecasts fed directly into a planning system. Connection to RDF is built directly into the business process supported by Oracle Retail Predictive Planning through an automatic approval of a forecast that is fed directly in the planning system. This allows you to accept all or part of Sales Value forecast. Once that decision is made, the balance of business measures are planned within Oracle Retail Predictive Planning.

Halo

Used to explain the bias shown by customers towards certain products because of a favorable experience with other products.

Holt's Model of Exponential Smoothing

See [Trend Exponential Smoothing](#) or [TrendES](#).

Interactive Forecasting

A workbook in RDF that is used to simulate forecast by modifying parameters such as Forecast Method and History Start Date.

IntermittentES or Intermittent Exponential Smoothing

RDF fits the data to the Croston's model of exponential smoothing. This method should be used when the input series contains a large number of zero data points (that is, intermittent demand data). The original time series is split into a Magnitude and Frequency series, and then the SimpleES model is applied to determine level of both series. The ratio of the magnitude estimate over the frequency estimate is the forecast level reported for the original series.

Like-item or Like SKU

An item that is used as a model to forecast a new item introduction.

Lost Sales

Periods in sales data in which there was no inventory to meet consumer demand.

Measure

Any item of data that can be represented on a grid in a view.

Measure Description

The description of the measure that can be viewed in a workbook. This description may contain relationships and calculations.

Measure Function

Internal functions that can be used to simplify building calculations for a measure.

Measure Identifier

The combination of role, version, metric, and units that uniquely specifies a single measure.

Metric

A measure definition with the role, version, and units omitted.

Moving Average

For each period t , the moving average method takes the average of the periods from $t-2$ to $t+2$ as the smoothed baseline.

Multiplicative Seasonal

Also referred to as Multiplicative Winters Model, this model extracts seasonal indices that are assumed to have multiplicative effects on the un-seasonalized series.

Preprocessing

In RDF, Preprocessing refers to a module that processes data before forecasts are generated to adjust for situations, such as lost sales and unusually high demand.

Profile

Spreading ratios that are used in the Curve process. Typical profiles can include store participation, size distribution, and time (phase-to-week) profiles, as well as other information. Profiles are generated using historical data and phase definitions based on your system configuration.

Profile Based

RDF generates a forecast based on a seasonal profile that can be created in Curve or a legacy system. Profiles can also be copied from another profile and adjusted. Using historic data and the profile, the data is de-seasonalized and then fed to the SimpleES method. The Simple forecast is then re-seasonalized using the profiles.

Profile Spread

Used at the final-level to utilize a profile (either generated externally or with Curve) to determine the spreading ratios from the Source-level forecast down to the Final-level forecast.

Promote

Promote is an optional add-on automated predictive solution that allows you to incorporate the effects of promotional and causal events, such as radio advertisements and holiday occurrences, into your time series forecasts. The promotional forecasting process uses both past sales data and promotional information to forecast future demand.

Promotion Planning

A workbook and simulation process used within the context of promotional forecasting. Promotion planning involves specifying whether the event status for a particular promotional variable is active (on) or inactive (off) for a specific product/location/calendar combination. When past promotional events are represented as accurately as possible, the modeling routine can more precisely detect correlation between event occurrences and changes in sales values.

Promotional Effectiveness

A workbook used in the context of promotional forecasting. This workbook allows you to analyze the effects of promotions on items at both the micro and the macro level. What-if analysis can also be performed on the results of promotional forecasts, as you can modify future and past promotional inputs, the system-estimated effects of promotions, and the promotional forecasts themselves.

Promotional Forecasting

Promote's forecasting technique (also referred to as Causal forecasting) uses promotional factors and events to predict future demand. Promotion events are events, such as advertisements, holidays, competitor information, and other factors that affect the normal selling cycle for a business.

Promotion Group

A set of products or locations that are believed to exhibit similar effects during common causal events. Promotion groups should be established to maximize the number of time series for each group (so each promotional event can be evaluated from as many different observations as possible), while ensuring that each time series is affected by causal events to the same degree.

SeasonalES Method

A combination of several Seasonal methods. This method is generally used for known seasonal items or forecasting for long horizons. This method applies the Multiplicative Seasonal model unless zeros are present in the data, in which case the Additive Winters model of exponential smoothing is used. If less than two years of data is available, a Seasonal Regression model is used. If there is too little data to create a seasonal forecast (in general, less than 52 weeks), the system selects from the SimpleES, TrendES, and IntermittentES methods.

Seasonal Regression

Seasonal Regression cannot be selected as a forecasting method, but it is a candidate model used when the SeasonalES method is selected. This model requires a minimum of 52 weeks of history to determine seasonality. Simple Linear Regression is used to estimate the future values of the series based on a past series. The independent variable is the series history one-year or one cycle length prior to the desired forecast period, and the dependent variable is the forecast. This model assumes that the future is a linear combination of itself one period before plus a scalar constant.

Simple/IntermittentES Method

A combination of the SimpleES and IntermittentES methods. This method applies the SimpleES model unless a large number of zero data points are present. In this case, the Croston's model is applied.

SimpleES or Simple Exponential Smoothing Method

RDF uses a simple exponential smoothing model to generate forecasts. SimpleES ignores seasonality and trend features in the demand data, and it is the simplest model of the exponential smoothing family. This method can be used when less than one year of historic demand data is available.

Simple Moving Average

See [Moving Average](#).

Sister Store

A store that is used as a model to forecast a new store.

Source Level Forecast

The level at which the aggregate, more robust forecast is run.

Time Series

Set of evenly spaced numerical data obtained by observing response variable at regular time periods. This data is used to forecast based only on past values. It assumes that factors influencing past and present continues influence in future.

Training Window

The number of weeks of historical sales data to use in generating a forecast.

Trend Exponential Smoothing or TrendES

Also referred to as Holt's Model, RDF fits the data to the Holt model of exponential smoothing. The Holt model is useful when data exhibits a definite trend. This method separates out base demand from trend and then provides forecast point estimates by combining an estimated trend and the smoothed level at the end of the series.

Wizard

A set of windows that guide you through the process of creating a new workbook or performing other actions in a solution by asking you various questions and having you select values.

Workbook

The framework used for displaying data and user functions. Workbooks are task-specific and may contain one or more views. Users define the format of their workbooks. Also see [Workbook Template](#), [View](#).

Workbook Template

The framework for creating a workbook. You build each new workbook from an existing workbook template, such as Pre-Season Financial Plan or Forecasting Administration. Several workbook templates are supplied with the Oracle Retail Predictive Solutions and are available for selection when you choose **File - New** to create a new workbook.

View

A multidimensional spreadsheet used to display workbook-specific information. View data can also be displayed in chart format.