

Oracle® Analytics

Designing and Publishing Pixel-Perfect Reports in Oracle Analytics Server



5.9.0

F24233-04

March 2021

The Oracle logo, consisting of a solid red square with the word "ORACLE" in white, uppercase, sans-serif font centered within it.

ORACLE®

Oracle Analytics Designing and Publishing Pixel-Perfect Reports in Oracle Analytics Server, 5.9.0

F24233-04

Copyright © 2020, 2021, Oracle and/or its affiliates.

Primary Author: Hemala Vivek

Contributing Authors: Pete Brownbridge, Nick Fry, Rosie Harvey, Christine Jacobs, Stefanie Rhone, Jenny Smalling

Contributors: Oracle Analytics Server development, product management, and quality assurance teams

This software and related documentation are provided under a license agreement containing restrictions on use and disclosure and are protected by intellectual property laws. Except as expressly permitted in your license agreement or allowed by law, you may not use, copy, reproduce, translate, broadcast, modify, license, transmit, distribute, exhibit, perform, publish, or display any part, in any form, or by any means. Reverse engineering, disassembly, or decompilation of this software, unless required by law for interoperability, is prohibited.

The information contained herein is subject to change without notice and is not warranted to be error-free. If you find any errors, please report them to us in writing.

If this is software or related documentation that is delivered to the U.S. Government or anyone licensing it on behalf of the U.S. Government, then the following notice is applicable:

U.S. GOVERNMENT END USERS: Oracle programs (including any operating system, integrated software, any programs embedded, installed or activated on delivered hardware, and modifications of such programs) and Oracle computer documentation or other Oracle data delivered to or accessed by U.S. Government end users are "commercial computer software" or "commercial computer software documentation" pursuant to the applicable Federal Acquisition Regulation and agency-specific supplemental regulations. As such, the use, reproduction, duplication, release, display, disclosure, modification, preparation of derivative works, and/or adaptation of i) Oracle programs (including any operating system, integrated software, any programs embedded, installed or activated on delivered hardware, and modifications of such programs), ii) Oracle computer documentation and/or iii) other Oracle data, is subject to the rights and limitations specified in the license contained in the applicable contract. The terms governing the U.S. Government's use of Oracle cloud services are defined by the applicable contract for such services. No other rights are granted to the U.S. Government.

This software or hardware is developed for general use in a variety of information management applications. It is not developed or intended for use in any inherently dangerous applications, including applications that may create a risk of personal injury. If you use this software or hardware in dangerous applications, then you shall be responsible to take all appropriate fail-safe, backup, redundancy, and other measures to ensure its safe use. Oracle Corporation and its affiliates disclaim any liability for any damages caused by use of this software or hardware in dangerous applications.

Oracle and Java are registered trademarks of Oracle and/or its affiliates. Other names may be trademarks of their respective owners.

Intel and Intel Inside are trademarks or registered trademarks of Intel Corporation. All SPARC trademarks are used under license and are trademarks or registered trademarks of SPARC International, Inc. AMD, Epyc, and the AMD logo are trademarks or registered trademarks of Advanced Micro Devices. UNIX is a registered trademark of The Open Group.

This software or hardware and documentation may provide access to or information about content, products, and services from third parties. Oracle Corporation and its affiliates are not responsible for and expressly disclaim all warranties of any kind with respect to third-party content, products, and services unless otherwise set forth in an applicable agreement between you and Oracle. Oracle Corporation and its affiliates will not be responsible for any loss, costs, or damages incurred due to your access to or use of third-party content, products, or services, except as set forth in an applicable agreement between you and Oracle.

Contents

Preface

| | |
|-----------------------------|-----|
| Audience | xxx |
| Documentation Accessibility | xxx |
| Conventions | xxx |

Part I Model Data for Pixel-Perfect Reports

1 Use the Data Model Editor

| | |
|--|------|
| What Is a Data Model? | 1-1 |
| Components of a Data Model | 1-1 |
| About the Data Source Options | 1-2 |
| Process Overview for Creating a Data Model | 1-3 |
| Features of the Data Model Editor | 1-4 |
| Launch the Data Model Editor | 1-5 |
| About the Data Model Editor Toolbar | 1-5 |
| About the Interface | 1-6 |
| Data Model Properties | 1-8 |
| XML Output Options | 1-11 |
| XML Data Chunking | 1-12 |
| Add Attachments to the Data Model | 1-12 |
| Attach Sample Data | 1-12 |
| Attach Schema | 1-13 |
| Data Files | 1-13 |
| Manage Private Data Sources | 1-13 |

2 Create Data Sets

| | |
|--|-----|
| Create a Data Set Using a Visualized Data Set | 2-1 |
| Create a Data Set Using a Visualized Data Flow | 2-2 |
| Create a Data Set | 2-2 |
| Create Data Sets Using SQL Queries | 2-2 |

| | |
|---|------|
| Enter SQL Queries | 2-3 |
| Use the SQL Query Builder | 2-3 |
| Overview of the Query Builder | 2-4 |
| Build a Query Using Query Builder | 2-4 |
| Supported Column Types | 2-4 |
| Add Objects to the Design Pane | 2-5 |
| Remove or Hide Objects in the Design Pane | 2-5 |
| Query Conditions | 2-6 |
| Create Relationships Between Objects | 2-6 |
| Save a Query | 2-7 |
| Edit a Saved Query | 2-8 |
| Add a Bind Variable to a Query | 2-8 |
| Add a Bind Variable Using a Text Editor | 2-9 |
| Add Lexical References to SQL Queries | 2-10 |
| About Defining SQL Queries Against the Oracle BI Server | 2-12 |
| Define SQL Queries Against the Oracle BI Server | 2-12 |
| Notes for Queries Against Oracle Fusion Applications Tables | 2-13 |
| Create a Data Set Using an LDAP Query | 2-14 |
| Create a Data Set Using a MDX Query Against an OLAP Data Source | 2-15 |
| Create a Data Set Using a MDX Query | 2-15 |
| Use MDX Query Builder | 2-16 |
| Understand the MDX Query Builder Process | 2-16 |
| Use the Select Cube Dialog | 2-17 |
| Select Dimensions and Measures | 2-17 |
| Perform MDX Query Actions | 2-18 |
| Apply MDX Query Filters | 2-19 |
| Select MDX Query Options and Save MDX Queries | 2-19 |
| Create a Data Set Using an Analysis | 2-20 |
| Additional Notes on Analysis Data Sets | 2-21 |
| Create a Data Set Using a View Object | 2-21 |
| Additional Notes on View Object Data Sets | 2-22 |
| Create a Data Set Using a Web Service | 2-22 |
| Web Service Data Source Options | 2-22 |
| Create a Data Set Using a Simple Web Service | 2-22 |
| Create a Data Set Using a Complex Web Service | 2-23 |
| Additional Information on Web Service Data Sets | 2-23 |
| Create a Data Set Using a XML File | 2-23 |
| About Supported XML Files | 2-23 |
| Upload a XML File Stored Locally | 2-24 |
| Refresh and Delete an Uploaded XML File | 2-24 |
| Create a Data Set Using a Content Server | 2-25 |

| | |
|---|------|
| Create a Data Set Using a Microsoft Excel File | 2-26 |
| About Supported Excel Files | 2-26 |
| Access Multiple Tables per Sheet | 2-26 |
| Use a Microsoft Excel File Stored in a File Directory Data Source | 2-27 |
| Upload a Microsoft Excel File Stored Locally | 2-28 |
| Refresh and Delete an Uploaded Excel File | 2-29 |
| Create a Data Set Using a CSV File | 2-30 |
| About Supported CSV Files | 2-30 |
| Create a Data Set from a Centrally Stored CSV File | 2-31 |
| Upload a CSV File Stored Locally | 2-31 |
| Edit the Data Type | 2-32 |
| Refresh and Delete an Uploaded CSV File | 2-32 |
| Create a Data Set from an HTTP XML Feed | 2-33 |
| Create a Data Set from an HTTP XML Data Set | 2-34 |
| Use Data Stored as a Character Large Object (CLOB) in a Data Model | 2-34 |
| How the Data Is Returned | 2-36 |
| Additional Notes on Data Sets Using CLOB Column Data | 2-37 |
| Handle XHTML Data Stored in a CLOB Column | 2-37 |
| Retrieve XHTML Data Wrapped in CDATA | 2-37 |
| Wrap the XHTML Data in CDATA in the Query | 2-38 |
| Test Data Models and Generate Sample Data | 2-38 |
| Edit an Existing Data Set | 2-39 |
| Include User Information Stored in System Variables in Your Report Data | 2-40 |
| Add the User System Variables as Elements | 2-41 |
| Sample Use Case: Limit the Returned Data Set by User ID | 2-41 |
| Create Bind Variables from LDAP User Attribute Values | 2-42 |

3 Structure Data

| | |
|--|-----|
| Work with Data Models | 3-1 |
| About Multipart Unrelated Data Sets | 3-1 |
| About Multipart Related Data Sets | 3-3 |
| Guidelines for Working with Data Sets | 3-5 |
| Create Links Between Data Sets | 3-6 |
| About Element-Level Links | 3-6 |
| Create Element-Level Links | 3-6 |
| Delete Element-Level Links | 3-7 |
| Delete Group-Level Links | 3-7 |
| Create Subgroups | 3-7 |
| Move an Element Between a Parent Group and a Child Group | 3-9 |
| Create Group-Level Aggregate Elements | 3-9 |

| | |
|---|------|
| Create Group Filters | 3-14 |
| Perform Element-Level Functions | 3-15 |
| Set Element Properties | 3-15 |
| Sort Data | 3-15 |
| Perform Group-Level Functions | 3-16 |
| The Group Action Menu | 3-16 |
| Edit the Data Set | 3-17 |
| Remove Elements from the Group | 3-17 |
| Edit the Group Properties | 3-17 |
| Perform Global-Level Functions | 3-18 |
| Add a Global-Level Aggregate Function | 3-19 |
| Add a Group-Level or Global-Level Element by Expression | 3-20 |
| Add a Global-Level Element by PL/SQL | 3-21 |
| Use the Structure View to Edit Your Data Structure | 3-22 |
| Rename Elements | 3-23 |
| Add Value for Null Elements | 3-23 |
| Function Reference | 3-23 |

4 Add Parameters and Lists of Values

| | |
|---|------|
| About Parameters | 4-1 |
| Add a New Parameter | 4-3 |
| Create a Text Parameter | 4-3 |
| Create a Menu Parameter | 4-4 |
| Customize the Display of Menu Parameters | 4-5 |
| Define a Date Parameter | 4-6 |
| Create a Point of View Parameter (POV) | 4-7 |
| Include a POV Parameter Value in an MDX Query | 4-7 |
| Create a Search Parameter | 4-8 |
| About Lists of Values | 4-8 |
| Add Lists of Values | 4-8 |
| Create a List from a SQL Query | 4-9 |
| Create a List from a Fixed Data Set | 4-11 |
| Create a List from an MDX Query | 4-11 |
| Add Flexfield Parameters | 4-12 |
| Prerequisites for Using Flexfields | 4-12 |
| Add a Flexfield Parameter and List of Values | 4-13 |
| Add the Flexfield List of Values | 4-13 |
| Add the Menu Parameter for the Flexfield List of Values | 4-14 |
| Use the Flexfield Parameter to Pass Values to a Flexfield Defined in the Data Model | 4-15 |
| Reference the Flexfield in the SQL Query | 4-16 |

5 Add Event Triggers

| | |
|---|-----|
| About Triggers | 5-1 |
| Add Before Data and After Data Triggers | 5-1 |
| Order of Execution | 5-2 |
| Create Schedule Triggers | 5-2 |

6 Add Flexfields

| | |
|--|-----|
| About Flexfields | 6-1 |
| Use Flexfields in Your Data Model | 6-1 |
| Add Key Flexfields | 6-2 |
| Enter Flexfield Details | 6-3 |
| Add Descriptive Flexfields | 6-5 |
| Include Descriptive Flexfield Reference in SQL Queries | 6-6 |

7 Add Bursting Definitions

| | |
|---|------|
| Prerequisites for Adding Bursting Definition | 7-1 |
| Use a Visualized Data Set to Add a Bursting Definition to Your Data Model | 7-2 |
| About Bursting | 7-2 |
| What is the Bursting Definition? | 7-3 |
| Use SQL Query to Add a Bursting Definition to Your Data Model | 7-3 |
| Attach PDF to Reports using Bursting Engine | 7-4 |
| Define the Query for Delivery XML | 7-4 |
| Pass a Parameter to the Bursting Query | 7-9 |
| Define the Split By and Deliver By Elements for a CLOB/XML Data Set | 7-11 |
| Configure a Report to Use a Bursting Definition | 7-12 |
| Sample Bursting Query | 7-12 |
| Create a Table to Use as a Delivery Data Source | 7-13 |

8 Add Custom Metadata for Oracle WebCenter Content Server

| | |
|---|-----|
| About Custom Metadata Mapping | 8-1 |
| Prerequisites | 8-1 |
| Map Data Fields to Custom Metadata Fields | 8-1 |
| Delete Unused Metadata Fields | 8-4 |

9 Performance Best Practices

| | |
|--|------|
| Know Oracle WebLogic Server Default Time Out Setting | 9-1 |
| Best Practices for SQL Data Sets | 9-1 |
| Only Return the Data You Need | 9-2 |
| Use Column Aliases to Shorten XML File Length | 9-2 |
| Avoid Using Group Filters by Enhancing Your Query | 9-2 |
| Avoid PL/SQL Calls in WHERE Clauses | 9-3 |
| Avoid Use of the System Dual Table | 9-3 |
| Avoid PL/SQL Calls at the Element Level | 9-3 |
| Avoid Including Multiple Data Sets | 9-4 |
| Avoid Nested Data Sets | 9-4 |
| Avoid In-Line Queries as Summary Columns | 9-5 |
| Avoid Excessive Parameter Bind Values | 9-5 |
| Tips for Multi-value Parameters | 9-6 |
| Group Break and Sort Data | 9-7 |
| Limit Lists of Values | 9-8 |
| Work with Lexicals/Flexfields | 9-8 |
| Work with Date Parameters | 9-10 |
| Run Report Online/Offline (Schedule) | 9-10 |
| Set Data Model Properties to Prevent Memory Errors | 9-11 |
| Query Time Out | 9-11 |
| Enable SQL Pruning | 9-11 |
| DB Fetch Size | 9-11 |
| Scalable Mode | 9-11 |
| Tune SQL Query | 9-12 |
| Generate Explain Plan | 9-13 |
| Explain Plan for a Single Query | 9-13 |
| Explain Plan for Reports | 9-13 |
| Guidelines for Tuning Queries | 9-14 |
| Tips for Database Tuning | 9-14 |
| Validate Data Models | 9-15 |
| Data Model Validation Messages | 9-15 |

Part II Create Pixel-Perfect Reports and Layouts

10 Introduction to Designing Reports

| | |
|--------------------------------|------|
| Overview for Report Designers | 10-1 |
| Define Summary Text for Tables | 10-1 |
| About the Layout Types | 10-1 |

| | |
|-----------------------------------|------|
| About Setting Run-Time Properties | 10-2 |
| About Translations | 10-2 |
| About Style Templates | 10-3 |
| About Sub Templates | 10-3 |

11 Create and Edit Reports

| | |
|--|-------|
| About Report Components | 11-1 |
| Create Reports: Process Overview | 11-2 |
| Create Reports | 11-2 |
| Select a Data Source | 11-3 |
| Choose Guide Me or Use Report Editor | 11-3 |
| Select the Report Layout | 11-4 |
| Choose Columns for Report Layouts | 11-4 |
| Table Layout | 11-5 |
| Chart Layout | 11-6 |
| Chart and Table Layout | 11-7 |
| Pivot Table Layout | 11-7 |
| Chart and Pivot Table Layout | 11-8 |
| Two Charts and Table Layout | 11-8 |
| Save the Report | 11-8 |
| Create Reports Using a Direct Connection to a Subject Area | 11-9 |
| Create Subject Area Reports | 11-9 |
| Add Parameters to Subject Area Reports | 11-10 |
| Create a Report Against Multiple Subject Areas | 11-12 |
| Edit Reports | 11-13 |
| Add Layouts to the Report Definition | 11-14 |
| Add a Layout Using the Layout Editor | 11-15 |
| Add a Layout by Uploading a Template File | 11-15 |
| Add a Layout by Generating a Template File | 11-15 |
| Configure Layouts Using the List View | 11-16 |
| Apply a Style Template to the Layout | 11-16 |
| About the Layouts Toolbar | 11-16 |
| Configure the Layout Settings Using the List View | 11-16 |
| Select Output Formats | 11-17 |
| Edit a Layout | 11-19 |
| Configure Parameter Settings for the Report | 11-19 |
| Configure Report Properties | 11-22 |
| Set the General Properties | 11-22 |
| Run Report Online | 11-22 |
| Advanced Options | 11-23 |

| | |
|-----------------------------------|-------|
| Set the Caching Properties | 11-23 |
| Set the Formatting Properties | 11-25 |
| Configure Font Mapping | 11-25 |
| Configure Currency Formats | 11-25 |
| Access Reports via a URL | 11-26 |
| Report URL Format | 11-26 |
| Report URL Parameters | 11-27 |
| About the Layout Editor Interface | 11-29 |
| About the Data Source Pane | 11-30 |
| About the Components Pane | 11-31 |
| About the Properties Pane | 11-32 |
| About the Tabbed Toolbar | 11-33 |
| Select and Delete Layout Objects | 11-33 |
| About the Insert Tab | 11-34 |

12 Create Publisher Layout Templates

| | |
|---|-------|
| Overview of Publisher Layouts | 12-1 |
| When to Use a Publisher Layout | 12-2 |
| Prerequisites, Recommendations, and Limitations | 12-3 |
| Launch the Layout Editor | 12-3 |
| Create a New Report | 12-3 |
| Edit a Report | 12-3 |
| View a Report | 12-4 |
| Select a Predefined Layout | 12-4 |
| Add Shared Templates for All Users | 12-4 |
| Add Personal Predefined Layouts | 12-5 |
| Page Layout Tab | 12-5 |
| Paper Options | 12-6 |
| Header/Footer Options | 12-6 |
| Set Properties for Headers and Footers | 12-6 |
| View Options | 12-7 |
| Display Unit | 12-7 |
| Configure Events | 12-7 |
| Example of Filter Event Configuration | 12-8 |
| Configure Automatic Filtering | 12-8 |
| Example: Show Selection Only | 12-9 |
| Set Page Margins | 12-10 |
| Set Maximum Connections for an Interactive Report | 12-11 |
| Insert Layout Components | 12-12 |
| Insert Layout Grids | 12-13 |

| | |
|--|-------|
| Add a Border or Background Color | 12-14 |
| About the Insert Options | 12-14 |
| About the Join and Unjoin Options | 12-14 |
| Add Expand and Collapse Option | 12-15 |
| About Repeating Sections | 12-15 |
| Set Page Break Options for a Repeating Section | 12-16 |
| How Repeating Sections Display in Interactive Mode | 12-17 |
| Show All Values in a Repeating Section | 12-18 |
| About Data Tables | 12-20 |
| Insert a Data Table | 12-20 |
| Set Alternating Row Colors | 12-22 |
| About the Table Tab | 12-23 |
| Set the Rows to Display Option | 12-23 |
| About Filters | 12-24 |
| Set Filters for a Table | 12-24 |
| Manage Filters | 12-25 |
| About Conditional Formats | 12-25 |
| Apply Conditional Formats to a Table | 12-25 |
| Manage Formats | 12-27 |
| Control the Display of the Total Row | 12-28 |
| About the Table Column Header Tab | 12-28 |
| About Grouping | 12-29 |
| Example: Group Left | 12-30 |
| Apply Subtotals | 12-31 |
| Example: Group Above | 12-31 |
| About the Column Tab | 12-32 |
| About the Data Formatting Options for Columns | 12-33 |
| Apply Formatting to Numeric Data Columns | 12-33 |
| Apply Formatting to Date Type Data Columns | 12-34 |
| Custom and Dynamic Formatting Masks | 12-34 |
| About the Formula Option | 12-35 |
| About the Sort Option | 12-35 |
| Remove a Sort Order | 12-36 |
| About the Total Cell Tab | 12-36 |
| Apply Data Formatting to a Total Cell | 12-37 |
| Apply a Formula | 12-37 |
| Insert Dynamic Hyperlinks | 12-37 |
| Apply Custom Data Formatting | 12-38 |
| About Charts | 12-39 |
| Insert a Chart | 12-40 |
| About the Chart Tab | 12-42 |

| | |
|---|-------|
| Apply and Manage Filters | 12-42 |
| Convert a Chart to a Pivot Table | 12-42 |
| Change the Formula Applied to a Chart Measure Field | 12-43 |
| Sort a Chart Field | 12-44 |
| Use Advanced Chart Features | 12-44 |
| Format Time Series Axis | 12-44 |
| Hide Axis Option | 12-46 |
| Format Independent Axis | 12-46 |
| Scale Axis | 12-46 |
| Format Pie Slice | 12-47 |
| About Gauge Charts | 12-47 |
| Insert a Gauge Chart | 12-47 |
| Apply and Manage Filters | 12-48 |
| About Pivot Tables | 12-48 |
| Insert a Pivot Table | 12-48 |
| Customize a Pivot Table Menu | 12-50 |
| About the Pivot Table Tab | 12-50 |
| Apply Filters | 12-50 |
| Customize the Display of Totals | 12-50 |
| Convert a Pivot Table to a Chart | 12-50 |
| Switch Rows and Columns | 12-51 |
| Customize the Pivot Table Headers | 12-52 |
| Customize the Pivot Table Data | 12-52 |
| About Text Items | 12-52 |
| Display a Data Field Side-by-Side with a Text Item | 12-53 |
| About the Text Toolbar | 12-54 |
| Edit Font Properties | 12-54 |
| Insert Page Numbers | 12-55 |
| Insert the Date and Time | 12-55 |
| Insert a Hyperlink | 12-56 |
| About Images | 12-56 |
| Add BLOB Image | 12-58 |
| About Lists | 12-58 |
| Insert a List | 12-59 |
| Customize a List | 12-61 |
| Customize the Font Style and the Selected Font Style Commands | 12-61 |
| Customize Behavior of Selected Items | 12-62 |
| Set Predefined or Custom Formulas | 12-64 |
| About the Predefined Formulas | 12-65 |
| Apply a Custom Formula | 12-65 |
| About the Basic Math Functions | 12-66 |

| | |
|--------------------------------------|-------|
| About the Statistical Math Functions | 12-67 |
| Apply a Custom Formula: Examples | 12-67 |
| Save a Layout | 12-73 |

13 Create RTF Templates

| | |
|--|-------|
| Get Started | 13-2 |
| What Are RTF Templates? | 13-2 |
| Prerequisites for Designing Templates | 13-2 |
| What is XSLT Compatibility? | 13-3 |
| Key Concepts | 13-3 |
| Design the Template Layout | 13-3 |
| About Adding Publisher Code | 13-3 |
| Associate the XML Data to the Template Layout | 13-4 |
| Use an XML Input File | 13-4 |
| Identify Placeholders and Groups | 13-5 |
| Use Placeholders | 13-6 |
| Identify the Groups of Repeating Elements | 13-6 |
| Add Markup to the Template Layout | 13-7 |
| Create Placeholders | 13-7 |
| Use the Basic RTF Method | 13-7 |
| Use the Form Field Method | 13-8 |
| Complete the Example | 13-10 |
| Define Groups | 13-11 |
| Group Scenarios | 13-11 |
| Use the Basic RTF Method | 13-11 |
| Use the Form Field Method | 13-12 |
| Complete the Example | 13-13 |
| Define Headers and Footers | 13-14 |
| Native Support for Headers and Footers | 13-14 |
| Insert Placeholders in the Headers and Footers | 13-14 |
| Create Multiple or Complex Headers and Footers | 13-14 |
| Define Different First Page and Different Odd and Even Pages | 13-15 |
| Insert Images and Charts | 13-16 |
| Directly Insert Images | 13-16 |
| Insert Images with URL References | 13-16 |
| Insert Images with an Element Reference from an XML File | 13-17 |
| Render an Image Retrieved from BLOB Data | 13-17 |
| Add Charts to Templates | 13-18 |
| Add a Sample Chart | 13-18 |
| Insert the Dummy Image | 13-20 |

| | |
|--|-------|
| Add Code to the Alternative Text Box | 13-21 |
| Add Chart Samples | 13-24 |
| Horizontal Bar Chart Sample | 13-25 |
| Change the Appearance of the Chart | 13-26 |
| Add Drawings, Shapes, and Clip Art | 13-28 |
| Add Freehand Drawings | 13-28 |
| Add Hyperlinks | 13-28 |
| Layer Shapes | 13-28 |
| Use 3-D Effects | 13-29 |
| Add Microsoft Equations | 13-29 |
| Add Organization Charts | 13-29 |
| Add WordArt | 13-30 |
| Add Data-Driven Shapes | 13-30 |
| Include Manipulation Commands | 13-31 |
| Replicate Shapes | 13-31 |
| Add Text to Shapes | 13-32 |
| Add Text Along a Path | 13-32 |
| Move a Shape | 13-32 |
| Rotate a Shape | 13-32 |
| Skew a Shape | 13-33 |
| Change the Size of Shapes | 13-34 |
| Combine Commands | 13-34 |
| CD Ratings Example | 13-35 |
| Grouped Shape Example | 13-37 |
| Supported Formatting Features of Microsoft Word | 13-40 |
| General Features of Microsoft Word | 13-40 |
| Align Objects | 13-41 |
| Insert Tables | 13-41 |
| Insert Date Fields | 13-43 |
| Insert Multiple Columns on Pages | 13-43 |
| Insert Backgrounds and Watermarks | 13-44 |
| Add a Background Using Microsoft Word 2000 | 13-44 |
| Add a Text or Image Watermark Using Microsoft Word 2002 or later | 13-45 |
| Microsoft Word Features That Are Not Supported | 13-45 |
| Template Features | 13-45 |
| Insert Page Breaks | 13-46 |
| Insert an Initial Page Number | 13-47 |
| Specify Last Page Only Content | 13-48 |
| End on Even or Odd Pages | 13-51 |
| Skip Pages and Page Numbers | 13-52 |
| Insert Hyperlinks | 13-53 |

| | |
|---|--------|
| Insert Internal Links | 13-55 |
| Include a Table of Contents | 13-56 |
| Generate Bookmarks in PDF Output | 13-56 |
| Insert Check Boxes | 13-58 |
| Insert Drop-Down Lists | 13-59 |
| Repeat Row Headers After Page Break | 13-62 |
| Use Conditional Formatting | 13-62 |
| Use If Statements | 13-63 |
| Use If Statements in Boilerplate Text | 13-64 |
| Use If-Then-Else Statements | 13-65 |
| Insert Choose Statements | 13-66 |
| Conditional Formatting Example | 13-66 |
| Format Columns | 13-67 |
| Format Rows | 13-69 |
| Highlight Cells | 13-71 |
| Insert Page-Level Calculations | 13-73 |
| Display Page Totals | 13-73 |
| Insert Brought Forward and Carried Forward Totals | 13-76 |
| Insert Running Totals | 13-79 |
| Handle Data | 13-80 |
| Sort Data | 13-81 |
| Check for Null Values | 13-81 |
| Regroup the XML Data | 13-82 |
| XML Sample | 13-82 |
| Regroup Syntax | 13-83 |
| Template Example | 13-84 |
| Regroup by an Expression | 13-85 |
| Set Variables, Parameters, and Properties | 13-88 |
| Set Variables | 13-88 |
| Set Parameters | 13-89 |
| Set Properties | 13-91 |
| Use Advanced Report Layouts | 13-92 |
| Create Batch Reports | 13-93 |
| Handle No Data Found Conditions | 13-94 |
| Insert Pivot Tables | 13-95 |
| Construct Dynamic Data Columns | 13-97 |
| Define Columns to Repeat Across Pages | 13-98 |
| Example of Dynamic Data Columns | 13-98 |
| Format Numbers, Dates, and Currencies | 13-100 |
| Format Numbers | 13-100 |
| Data Source Requirements | 13-101 |

| | |
|--|--------|
| Localization Considerations | 13-101 |
| Use the Microsoft Number Format Mask | 13-101 |
| Supported Microsoft Format Mask Definitions | 13-101 |
| Use the Oracle Format Mask | 13-103 |
| Format Dates | 13-104 |
| Data Source Requirements | 13-104 |
| Use the Microsoft Date Format Mask | 13-105 |
| Use the Oracle Format Mask | 13-106 |
| Default Format Mask | 13-108 |
| Oracle Abstract Format Masks | 13-109 |
| Display the System Date (sysdate) in Reports | 13-109 |
| Format Currencies | 13-110 |
| Apply a Currency Format to a Field | 13-111 |
| Example: Display Multiple Currency Formats in a Report | 13-111 |
| Example: Display Multiple Currency Codes in a Single Report | 13-112 |
| Support Calendars and Time Zones | 13-113 |
| Calendar Specification | 13-113 |
| Specify Time Zone | 13-113 |
| Specify No Time Zone Conversion | 13-114 |
| Use External Fonts | 13-114 |
| Use the Barcode Fonts Shipped with Publisher | 13-115 |
| Implement Custom Barcode Formats | 13-116 |
| Register the Barcode Encoding Class | 13-117 |
| Encode the Data | 13-117 |
| Control the Placement of Instructions Using the Context Commands | 13-118 |
| Use XPath Commands | 13-120 |
| Locate Data | 13-121 |
| Start Reference | 13-123 |
| Specify Context and Parents | 13-123 |
| Declare Namespaces | 13-123 |
| Use FO Elements and XSL Elements | 13-124 |
| Use FO Elements | 13-124 |
| Use XSL Elements | 13-124 |
| Apply a Template Rule | 13-124 |
| Copy the Current Node | 13-124 |
| Call a Named Template | 13-125 |
| Declare a Template | 13-125 |
| Declare a Variable | 13-125 |
| Import a Style Sheet | 13-125 |
| Define the Root Element of the Style Sheet | 13-125 |
| Format Native XSL Numbers | 13-126 |

| | |
|--|--------|
| Guidelines for Designing RTF Templates for Microsoft PowerPoint Output | 13-126 |
| Guidelines for Designing RTF Templates for Microsoft Excel 2007 Output | 13-127 |
| Create Multiple Sheets | 13-127 |
| Specify a Sheet Name | 13-127 |
| Specify Number and Date Formatting | 13-128 |
| Render HTML Formatted Data in a Report | 13-128 |
| Supported HTML Features | 13-128 |
| Data Model Requirements | 13-129 |
| RTF Template Requirements | 13-129 |
| Example | 13-129 |
| Embed PCL Commands for Check Printing | 13-130 |
| Procedure Overview | 13-130 |
| Embed PCL Commands in RTF Templates | 13-130 |
| Specifications and Restrictions | 13-133 |
| 2D Barcode Functions | 13-133 |

14 Create RTF Templates Using the Template Builder for Word

| | |
|---|-------|
| Overview | 14-1 |
| Before You Get Started | 14-2 |
| Prerequisites and Limitations | 14-2 |
| Get Started Using the Template Builder | 14-3 |
| Features of the Publisher Template Builder for Word | 14-3 |
| Build and Upload a Template | 14-3 |
| Work in Connected Mode | 14-3 |
| Work in Disconnected Mode | 14-4 |
| Access Data for Building Templates | 14-5 |
| Load XML Data from a Local File | 14-5 |
| Load Data from the Publisher Catalog | 14-5 |
| Insert Components to the Template | 14-6 |
| Insert a Field | 14-6 |
| About the Insert Field Dialog | 14-7 |
| Find | 14-7 |
| Example | 14-7 |
| Force LTR (Left-to-Right) Direction | 14-8 |
| Calculation | 14-8 |
| Insert a Table Using the Table Wizard | 14-9 |
| Step 1: Select Report Format | 14-9 |
| Step 2: Select Table Data | 14-9 |
| Step 3: Select Data Fields | 14-10 |
| Step 4: Group the Table | 14-11 |

| | |
|--|-------|
| Step 5: Insert a Break for the Group | 14-13 |
| Step 6: Sort the Table | 14-13 |
| Step 7: Click Finish | 14-13 |
| Step 8: Customize the Table Using Microsoft Word Functionality | 14-14 |
| Insert a Table or Form Using the Insert Table/Form Dialog | 14-14 |
| Select Data Fields | 14-14 |
| Define the Layout | 14-14 |
| Data Field Properties | 14-15 |
| Data Group Properties | 14-15 |
| Insert Tables and Forms | 14-16 |
| Group Nodes | 14-16 |
| Understand the Fields Inserted to the Template | 14-17 |
| Insert a Chart | 14-17 |
| Chart Type | 14-18 |
| Values | 14-18 |
| Aggregation | 14-18 |
| Labels | 14-19 |
| Color | 14-19 |
| Chart is Inside Group | 14-19 |
| Style | 14-19 |
| Properties | 14-19 |
| Preview | 14-19 |
| Group Data | 14-19 |
| Edit an Inserted Chart | 14-19 |
| Insert a Repeating Group | 14-20 |
| Create Grouping Fields Around an Existing Block | 14-22 |
| Insert a Pivot Table | 14-22 |
| Manually Edit a Pivot Table | 14-25 |
| Insert a Pivot Table in a Repeating Group | 14-29 |
| Insert and Edit Conditional Regions | 14-31 |
| Insert Conditional Formatting | 14-32 |
| Preview a Template | 14-33 |
| Template Editing Tools | 14-33 |
| Edit and View Field Properties | 14-34 |
| About the Properties Tab | 14-34 |
| About the Advanced Tab | 14-34 |
| About the Word Properties Button | 14-35 |
| Validate a Template | 14-35 |
| Use the Field Browser | 14-35 |
| Check Accessibility | 14-37 |
| Upload a Template to Publisher | 14-37 |

| | |
|---|-------|
| Use the Template Builder Translation Tools | 14-37 |
| About Translations | 14-37 |
| Extract Text to an XLIFF File for Translation | 14-38 |
| Preview the Template and Translation File | 14-38 |
| Localize a Template | 14-39 |
| Set Options for the Template Builder | 14-39 |
| Set UI Options | 14-39 |
| Set Preview Options | 14-40 |
| Set Build Options | 14-41 |
| Set Connection Options | 14-43 |
| Set Up a Configuration File | 14-43 |
| Publisher Menu Reference | 14-43 |
| About the Online Group | 14-44 |
| About the Load Data Group | 14-44 |
| About the Insert Group | 14-45 |
| About the Preview Group | 14-46 |
| About the Tools Group | 14-47 |
| About the Options Group | 14-48 |

15 Create Excel Templates

| | |
|---|------|
| Introduction to Excel Templates | 15-1 |
| Features of Excel Templates | 15-1 |
| Limitations of Excel Templates | 15-2 |
| Prerequisites | 15-2 |
| Supported Output | 15-2 |
| Desktop Tools for Excel Templates | 15-2 |
| Install the Template Builder for Excel | 15-3 |
| Sample Excel Templates | 15-3 |
| Understand the Mappings Between Template and Data | 15-3 |
| Use the Template Builder for Excel | 15-3 |
| Work in Connected Mode | 15-4 |
| Log In Through the Template Builder | 15-4 |
| Online Features of the Template Builder | 15-5 |
| Upload Templates from the Template Builder | 15-6 |
| Work in Disconnected Mode | 15-6 |
| Obtain Sample Data | 15-6 |
| Load Sample Data in Disconnected Mode | 15-7 |
| Upload Templates to the Report | 15-7 |
| Insert Fields | 15-7 |
| More Features of the Field Dialog | 15-9 |

| | |
|---|-------|
| Insert Repeating Groups | 15-9 |
| Use the Field Browser to View, Edit, and Delete Fields | 15-10 |
| Preview Templates | 15-11 |
| Import Excel Analyzer Templates | 15-11 |
| Build a Basic Template Using the Template Builder | 15-12 |
| Step 1: Load Sample Data to the Template Builder | 15-12 |
| Step 2: Design the Layout in Excel | 15-13 |
| Step 3: Use the Template Builder to Insert Fields | 15-13 |
| Step 4: Use the Template Builder to Insert Repeating Groups | 15-15 |
| Step 5: Insert the Calculated Salary Field | 15-16 |
| Step 6: Test the Template | 15-17 |
| Format Dates | 15-18 |
| Understand Excel Template | 15-22 |
| Map Data Fields and Groups | 15-22 |
| Use Excel Defined Names for Mapping | 15-22 |
| Use "XDO_" Prefix to Create Defined Names | 15-23 |
| Use Native Excel Functions with the "XDO_" Defined Names | 15-23 |
| About the XDO_METADATA Sheet | 15-23 |
| Create the XDO_METADATA Sheet | 15-23 |
| Format of the XDO_METADATA Sheet | 15-23 |
| Hide the XDO_METADATA Sheet | 15-24 |
| Enable Excel Template Scalability | 15-24 |
| Enable Excel Template Scalability at the Template Level | 15-25 |
| Enable Excel Template Scalability at the System Level | 15-25 |
| Enable Excel Template Scalability at the Report Level | 15-25 |
| Use Advanced Publisher Functions | 15-26 |
| Reporting Functions | 15-26 |
| Split Data from Reports into Multiple Sheets | 15-26 |
| Declare and Pass Parameters | 15-29 |
| Define a Link | 15-31 |
| Import and Call a Subtemplate | 15-32 |
| Reference Java Extension Libraries | 15-34 |
| Format Functions That Rely on Specific Data Attribute Values | 15-35 |
| Define Border and Underline Styles | 15-35 |
| Skip a Row | 15-40 |
| Group Functions | 15-42 |
| Group Data | 15-42 |
| Handle the Generated XDO Define Names in Nested Groups | 15-42 |
| Regroup the Data | 15-43 |
| Preprocess the Data Using an XSL Transformation (XSLT) File | 15-44 |
| XSLT Preprocessing Examples: Split Flat Data into Multiple Sheets | 15-45 |

| | |
|------------------------------------|-------|
| Split the Data by a Specific Field | 15-46 |
| Split the Data by Count of Rows | 15-47 |

16 Create PDF Templates

| | |
|---|-------|
| Overview | 16-1 |
| Requirements | 16-2 |
| Design the Template | 16-2 |
| Add Markup to the Template | 16-4 |
| Create a Placeholder | 16-4 |
| Name the Placeholder | 16-5 |
| Create a Text Placeholder | 16-5 |
| Supported Field Properties Options | 16-5 |
| Create a Check Box | 16-6 |
| Create a Radio Button Group | 16-6 |
| Define Groups of Repeating Fields | 16-7 |
| Repeat a PDF Template by Using the document-repeat-elementname Form Field | 16-8 |
| Add Page Numbers and Breaks | 16-10 |
| Add Page Numbers | 16-10 |
| Add Page Breaks | 16-11 |
| Perform Calculations | 16-14 |
| Completed PDF Layout Example | 16-15 |
| Runtime Behavior | 16-16 |
| Placement of Repeating Fields | 16-16 |
| Set Fields as Updatable or Read Only | 16-16 |
| Overflow Data | 16-18 |
| Create a Layout from a Predefined PDF Form | 16-18 |
| Determine If a PDF Has Form Fields Defined | 16-18 |
| Use a Predefined PDF Form as a Layout by Renaming the Form Fields | 16-18 |
| Use the Comb of Characters Option | 16-19 |
| Add or Designate a Field for a Digital Signature | 16-21 |
| About Signature Field Options | 16-21 |
| Add a Signature Field | 16-22 |
| Configure the Report to Insert the Digital Signature at Runtime | 16-22 |
| PDF Template Limitations | 16-23 |

17 Create eText Templates

| | |
|------------------------------|------|
| Overview | 17-1 |
| Prerequisites | 17-2 |
| Structure of eText Templates | 17-2 |

| | |
|---|-------|
| Command Rows, Data Rows, and Data Column Header Rows | 17-3 |
| Data Column Header Rows | 17-4 |
| Data Rows | 17-4 |
| Construct the Data Tables | 17-5 |
| Command Rows | 17-5 |
| Level Command | 17-5 |
| New Record Command | 17-8 |
| Sort Ascending and Sort Descending Commands | 17-8 |
| Display Condition Command | 17-8 |
| Structure of the Data Rows | 17-9 |
| Position | 17-9 |
| Length/Maximum Length | 17-9 |
| Format Column | 17-10 |
| Number Data Type | 17-10 |
| Date Data Type | 17-11 |
| Map EDI Delimiter-Based Data Types to eText Data Types | 17-11 |
| Pad | 17-12 |
| Data | 17-12 |
| Tag | 17-12 |
| Comments | 17-12 |
| Set Up Command Tables | 17-12 |
| TEMPLATE TYPE Command | 17-14 |
| DEFINE LEVEL Command | 17-15 |
| DEFINE SEQUENCE Command | 17-18 |
| RESET AT LEVEL | 17-18 |
| INCREMENT BASIS | 17-19 |
| MINIMUM | 17-19 |
| Define Concatenation Command | 17-19 |
| Base Level Subcommand | 17-19 |
| Element Subcommand | 17-20 |
| Delimiter Subcommand | 17-20 |
| Use the SUBSTR Function | 17-20 |
| Invalid Characters and Replacement Characters Commands | 17-21 |
| Output Character Set and New Record Character Commands | 17-22 |
| Output Length Mode | 17-22 |
| Number Thousands Separator and Number Decimal Separator | 17-22 |
| CASE CONVERSION | 17-22 |
| Create a Filler Block | 17-23 |
| Expressions, Control Structures, and Functions | 17-25 |
| Expressions | 17-25 |
| Control Structures | 17-25 |

| | |
|--|-------|
| Functions | 17-26 |
| Identifiers, Operators, and Literals | 17-29 |
| Key Words | 17-29 |
| Command and Column Header Key Words | 17-29 |
| Command Parameter and Function Parameter Key Words | 17-30 |
| Field-Level Key Words | 17-31 |
| Expression Key Words | 17-31 |
| Operators | 17-31 |
| Reference to XML Extract Fields and XPATH Syntax | 17-32 |
| Notes on Viewing eText Output from a Browser | 17-33 |

18 Set Report Processing and Output Document Properties

| | |
|--|-------|
| Overview | 18-1 |
| PDF Output Properties | 18-2 |
| PDF Digital Signature Properties | 18-6 |
| PDF Accessibility Properties | 18-8 |
| PDF/A Output Properties | 18-8 |
| PDF/X Output Properties | 18-9 |
| DOCX Output Properties | 18-11 |
| RTF Output Properties | 18-11 |
| PPTX Output Properties | 18-12 |
| HTML Output Properties | 18-12 |
| FO Processing Properties | 18-14 |
| RTF Template Properties | 18-17 |
| XPT Template Properties | 18-18 |
| PDF Template Properties | 18-19 |
| Excel Template Properties | 18-19 |
| CSV Output Properties | 18-20 |
| Excel Output Properties | 18-20 |
| EText Output Properties | 18-22 |
| All Outputs Properties | 18-22 |
| Define Font Mappings | 18-22 |
| Make Fonts Available to Publisher | 18-22 |
| Set Font Mapping at the Site Level or Report Level | 18-22 |
| Create a Font Mapping | 18-23 |
| Publisher's Predefined Fonts | 18-23 |
| Included Barcode Fonts | 18-25 |

Part III Create Style Templates and Subtemplates

19 Create and Implement Style Templates

| | |
|---|------|
| Understand Style Templates | 19-1 |
| About Styles Defined in the Style Template | 19-1 |
| Style Template Process | 19-2 |
| Create a Style Template RTF File | 19-2 |
| Define Styles for Paragraphs and Headings | 19-2 |
| Define Styles for Tables | 19-3 |
| Define a Header and Footer | 19-4 |
| Upload a Style Template File to the Catalog | 19-4 |
| Assign a Style Template to a Report Layout | 19-5 |
| Update a Style Template | 19-6 |
| Add Translations to a Style Template Definition | 19-6 |

20 Understand Subtemplates

| | |
|---|------|
| What is a Subtemplate? | 20-1 |
| About RTF Subtemplates | 20-1 |
| About XSL Subtemplates | 20-2 |
| Supported Locations for Subtemplates | 20-2 |
| Test Subtemplates from the Desktop | 20-2 |
| Upload a Subtemplate | 20-2 |
| Call a Subtemplate from an External Source | 20-3 |
| Import a Subtemplate Outside the Catalog over HTTP or FTP | 20-3 |
| Import Subtemplates Outside the Catalog on the Same Server | 20-4 |
| Required Settings To Run Sub Templates Stored Outside the Catalog | 20-4 |

21 Design RTF Subtemplates

| | |
|--|------|
| Understand RTF Subtemplates | 21-1 |
| Process Overview for Creating and Implementing RTF Sub Templates | 21-2 |
| Create an RTF Subtemplate File | 21-2 |
| Call a Subtemplate from a Main Template | 21-3 |
| Import the Subtemplate to the Main Template | 21-3 |
| Call the Subtemplate to Render Its Contents | 21-4 |
| Import a Localized Subtemplate | 21-4 |
| Example | 21-5 |
| When to Use RTF Subtemplates | 21-5 |
| Reuse a Common Layout | 21-6 |

| | |
|---|------|
| Conditionally Display a Layout Based on a Value in the Data | 21-6 |
| Example | 21-6 |
| Conditionally Display a Layout Based on a Parameter Value | 21-7 |
| Example | 21-7 |
| Handle Simple Calculations or Repeating Formulae | 21-8 |
| Example | 21-8 |
| Add Translations to an RTF Subtemplate | 21-9 |

22 Design XSL Subtemplates

| | |
|--|------|
| Understand XSL Subtemplates | 22-1 |
| Where to Put XSL Code in the RTF Main Template | 22-1 |
| Process Overview for Creating and Implementing XSL Sub Templates | 22-1 |
| Create an XSL Subtemplate File | 22-2 |
| Call an XSL Subtemplate from the Main Template | 22-3 |
| Import the Subtemplate | 22-3 |
| Call the Subtemplate | 22-3 |
| Pass Parameters to an XSL Subtemplate | 22-4 |
| Create the Sub Template Object in the Catalog | 22-4 |
| Example Uses of XSL Subtemplates | 22-4 |
| Handle XML Data with HTML Formatting | 22-5 |
| Dynamically Apply Formatting to a Portion of Data | 22-6 |

Part IV Translate Objects in Pixel-Perfect Reports

23 Translation Support Overview and Concepts

| | |
|--|------|
| Translation Support Overview | 23-1 |
| What Is Catalog Translation? | 23-1 |
| What Is Template Translation? | 23-2 |
| About Supported Languages | 23-2 |
| Work with Translation Files | 23-2 |
| What Is an XLIFF? | 23-2 |
| Structure of the XLIFF File | 23-2 |
| Source-language and target-language Attributes | 23-3 |
| Embedded Data Fields | 23-4 |
| <source> and <target> Elements | 23-4 |
| Locale Selection Logic | 23-5 |

24 Translate Individual Templates

| | |
|--|------|
| Overview | 24-1 |
| Types of Translations | 24-1 |
| Use the XLIFF Option | 24-2 |
| Generate the XLIFF from a Template | 24-3 |
| Generate the XLIFF from the Template Builder | 24-3 |
| Generate the XLIFF from the Layout Properties Page | 24-3 |
| Translate the XLIFF | 24-4 |
| Upload the Translated XLIFF to Publisher | 24-4 |
| Use the Localized Template Option | 24-4 |
| Design the Localized Template File | 24-4 |
| Upload the Localized Template to Publisher | 24-5 |

25 Translate Catalog Objects, Data Models, and Templates

| | |
|-------------------------------------|------|
| Overview | 25-1 |
| What Can Be Translated? | 25-1 |
| About Source Language Limitations | 25-2 |
| Export the XLIFF File | 25-2 |
| Identify and Update the Object Tags | 25-2 |
| Import the XLIFF File | 25-3 |

Part V Reference Information

26 Techniques for Handling Large Output Files

| | |
|---|------|
| Reuse Static Content | 26-1 |
| What Is Static Content Reuse? | 26-1 |
| Limitations of this Feature | 26-2 |
| Define Reusable Content in an RTF Template | 26-2 |
| Example | 26-3 |
| Generate Zipped PDF Output | 26-3 |
| Limitations and Prerequisites | 26-4 |
| Design Time Considerations | 26-4 |
| Select the Output Type | 26-4 |
| Implement PDF Splitting for an RTF Template | 26-5 |
| Enter the Commands in an RTF Template | 26-5 |
| Example - split by each department | 26-6 |
| Implement PDF Splitting for a PDF Template | 26-7 |

27 Extended Function Support in RTF Templates

| | |
|--------------------------------|-------|
| Extended SQL and XSL Functions | 27-1 |
| Number-To-Word Conversion | 27-8 |
| XSL Equivalents | 27-9 |
| Use FO Elements | 27-10 |

28 Design Accessible Reports

| | |
|---|------|
| Design for Accessibility | 28-1 |
| Obtain General Information | 28-1 |
| Avoid Common Misconceptions | 28-1 |
| Follow General Guidelines for Accessible Content | 28-2 |
| Color Selection | 28-2 |
| Color Contrast | 28-2 |
| Font Selection | 28-3 |
| Use the Template Builder to Verify Report Accessibility | 28-3 |
| Design Accessible Reports Using RTF Templates | 28-3 |
| Avoid Nested Tables or Separated Tables | 28-4 |
| Examples | 28-4 |
| Table Headers Must Not Be Separated from the Table Body | 28-5 |
| Define a Document Title | 28-5 |
| Define Alternative Text for an Image | 28-5 |
| Define a Table Summary | 28-6 |
| Define a Table Column Header | 28-6 |
| Define a Table Row Header | 28-6 |
| Sample Supported Tables | 28-7 |
| Convert Charts to Tables | 28-8 |
| Design Accessible Reports Using Publisher Layouts | 28-8 |
| Define Document Titles | 28-9 |
| Define Alternative Text for Images | 28-9 |
| Define Summary Text for Tables | 28-9 |
| Define Table Row Headers | 28-9 |
| Define Text Header Levels | 28-9 |
| Define a Layout Table | 28-9 |

29 Supported XSL-FO Elements

| | |
|---------------------------|------|
| Supported XSL-FO Elements | 29-1 |
|---------------------------|------|

30 Generate PDF/A and PDF/X Output

| | |
|------------------------------|------|
| Generate PDF/A Output | 30-1 |
| Requirements and Limitations | 30-1 |
| Additional Resources | 30-2 |
| Generate PDF/X output | 30-2 |
| Prerequisites | 30-2 |
| Requirements and Limitations | 30-2 |
| Additional Resources | 30-4 |

31 Generate Accessible PDF Output

| | |
|---|------|
| Configure Accessible PDF Output for Reports | 31-2 |
|---|------|

32 Generate CSV Output

| | |
|--------------------------------|------|
| Extract a Large Volume of Data | 32-2 |
|--------------------------------|------|

33 PDF Version Support

| | |
|---|------|
| About PDF Version Support | 33-1 |
| Supported Utilities | 33-1 |
| Limitations | 33-1 |
| Limitations That Apply to All PDF Utilities | 33-2 |
| FormProcessor Limitations | 33-2 |
| PDFDocMerger and PDFBookBinder Limitations | 33-2 |
| PDFSignature Limitations | 33-2 |

34 Test Templates with Template Viewer

| | |
|--|------|
| About Template Viewer | 34-1 |
| Debug Templates | 34-2 |
| Generate Reports in PDF/A, PDF/X, and PDF/UA Formats | 34-3 |
| Set the Font Directory | 34-3 |
| Add Key and Value Pairs for PDF/A Output | 34-3 |
| Add the Optional Property Settings for PDF/A and PDF/X Outputs | 34-4 |
| Monitor Memory Usage | 34-4 |
| Profile XSLT | 34-5 |
| Validate XML Documents | 34-5 |

Preface

Learn how to model data and design pixel-perfect reports.

Topics:

- [Audience](#)
- [Documentation Accessibility](#)
- [Conventions](#)

Audience

This document is intended for data modelers and report designers for creating pixel-perfect reports.

Documentation Accessibility

For information about Oracle's commitment to accessibility, visit the Oracle Accessibility Program website at <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=docacc>.

Access to Oracle Support

Oracle customers that have purchased support have access to electronic support through My Oracle Support. For information, visit <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=info> or visit <http://www.oracle.com/pls/topic/lookup?ctx=acc&id=trs> if you are hearing impaired.

Conventions

This document uses the standard Oracle text and image conventions.

Text Conventions

| Convention | Meaning |
|-----------------|--|
| boldface | Boldface type indicates graphical user interface elements associated with an action, or terms defined in text or the glossary. |
| <i>italic</i> | Italic type indicates book titles, emphasis, or placeholder variables for which you supply particular values. |
| monospace | Monospace type indicates commands within a paragraph, URLs, code in examples, text that appears on the screen, or text that you enter. |

Videos and Images

Skins and styles customize the look and feel of Oracle Analytics Cloud, dashboards, reports, and other objects. Videos and images used in this guide may not have the same skin or style that you're using, but the behavior and techniques shown are the same.

Part I

Model Data for Pixel-Perfect Reports

This part describes how to model data for pixel-perfect reports.

Topics:

- [Use the Data Model Editor](#)
- [Create Data Sets](#)
- [Structure Data](#)
- [Add Parameters and Lists of Values](#)
- [Add Event Triggers](#)
- [Add Flexfields](#)
- [Add Bursting Definitions](#)
- [Add Custom Metadata for Oracle WebCenter Content Server](#)
- [Performance Best Practices](#)

1

Use the Data Model Editor

This topic describes the components and features supported by the data model editor.

Topics:

- [What Is a Data Model?](#)
- [Components of a Data Model](#)
- [Features of the Data Model Editor](#)
- [About the Data Source Options](#)
- [Process Overview for Creating a Data Model](#)
- [Launch the Data Model Editor](#)
- [Data Model Properties](#)
- [Manage Private Data Sources](#)

What Is a Data Model?

A data model is an object that contains a set of instructions to retrieve and structure data for a pixel-perfect report. Data models reside as separate objects in the catalog.

A data model can be simple with one data set retrieved from a single data source (for example, the data returned from the columns in the employees table) or can be complex with parameters, triggers, and bursting definitions and using multiple data sets.

Use the data model editor to build a data model.

Components of a Data Model

A data model supports the following components:

- Data set

A data set contains the logic to retrieve data from a single data source. A data set can retrieve data from a variety of data sources (for example, a database, an existing data file, a web service call to another application, or a URL/URI to an external data provider). A data model can have multiple data sets from multiple sources.

- Event triggers

A trigger checks for an event. When the event occurs the trigger runs the PL/SQL code associated with it. The data model editor supports before data and after data triggers as well as schedule triggers. Before data and after data triggers consist of a call to execute a set of functions defined in a PL/SQL package stored in an Oracle database. A schedule trigger is executed for scheduled reports and tests for a condition that determines whether or not to run a scheduled report job.

- Flexfields
A flexfield is a structure specific to Oracle Applications. The data model editor supports retrieving data from flexfield structures defined in your Oracle Application database tables.
- Lists of values
A list of values is a menu of values from which report consumers can select parameter values to pass to the report.
- Parameters
A parameter is a variable whose value can be set at runtime. The data model editor supports several parameter types.
- Bursting Definitions
Bursting is a process of splitting data into blocks, generating documents for each data block, and delivering the documents to one or more destinations. A single bursting definition provides the instructions for splitting the report data, generating the document, and delivering the output to its specified destinations.
- Custom Metadata (for Web Content Servers)
If you've configured a web content server as a delivery destination and enabled custom metadata, the custom metadata component displays in the data model editor. Use this component to map data fields from your data model to the custom metadata fields set up for a set of rules defined in a Content Profile.

About the Data Source Options

Data source types supported for creating data sets can be categorized into three general types.

Data set types that can use the full range of editor functions in data model

The full range of editor functions in data model are supported for these data set types:

- SQL queries submitted against Oracle BI Server, an Oracle Database, or other supported databases. Publisher can retrieve the metadata information from these SQL queries.
See [Create Data Sets Using SQL Queries](#).
- Multidimensional (MDX) queries against an OLAP data source
See [Create a Data Set Using a MDX Query Against an OLAP Data Source](#).
- Queries against your LDAP repository to retrieve user data
You can report on this data directly, or join this to data retrieved from other sources. See [Create a Data Set Using an LDAP Query](#).
- Microsoft Excel spreadsheet data sources
You can store the Excel spreadsheet in a file directory set up as a data source by your administrator, or you can upload it directly from a local source to the data model. See [Create a Data Set Using a Microsoft Excel File](#).
- XML data file data sources

You can store the XML file in a file directory set up as a data source by your administrator, or you can upload it directly from a local source to the data model. See [Create a Data Set Using a XML File](#).

- CSV (comma separated value) file data sources

You can store the CSV file in a file directory set up as a data source by your administrator, or you can upload it directly from a local source to the data model. See [Create a Data Set Using a CSV File](#).

Data set types that can use partial editor functions in data model

Publisher can retrieve the column names and data type information from the data source of these data set types, but it can't process or structure the data. Only a subset of the full range of editor functions in data model are supported for data set types:

- Analysis
See [Create a Data Set Using an Analysis](#).
- View objects created using Oracle Application Development Framework (ADF).
See [Create a Data Set Using a View Object](#).

Data set types that can't be modified in the data model editor

For these data set types, Publisher can retrieve the data generated and structured at the source. You can't apply additional modifications in the data model editor for these data set types:

- HTTP XML feeds off the web
See [Create a Data Set from an HTTP XML Feed](#).
- Web services
See [Create a Data Set Using a Web Service](#).

To use a web service to return data for the report, supply the web service WSDL to Publisher and then define the parameters in Publisher.

Process Overview for Creating a Data Model

Follow the steps below to create a data table.

| Step | Reference |
|---|--|
| Launch the data model editor. | Launch the Data Model Editor |
| Set properties for the data model. (Optional) | Data Model Properties |
| Create the data sets for the data model. | Create Data Sets |
| Define the data output structure. (Optional) | Structure Data |
| Define the parameters to pass to the query, and define lists of values for users to select parameter values. (Optional) | Add Parameters and Lists of Values |
| Define Event Triggers. (Optional) | About Triggers |
| (Oracle Applications Only) Define Flexfields. (Optional) | Add Flexfields |

| Step | Reference |
|---|---|
| Test your data model and add sample data. | Test Data Models and Generate Sample Data |
| Add a bursting definition. (Optional) | Add Bursting Definitions |
| Map Custom Metadata for documents to be delivered to Web Content Servers (Optional) | Add Custom Metadata for Oracle WebCenter Content Server |

Features of the Data Model Editor

The data model editor enables you to combine data from multiple data sets into a single XML data structure.

Data sets from multiple data sources can be merged either as sequential XML or at line-level to create a single combined hierarchical XML. Using the data model editor you can easily combine data from the following data set types: SQL query, OLAP (MDX query), LDAP, and Microsoft Excel.


The data model editor is designed with a component pane on the left and work pane on the right. Selecting a component on the left pane launches the appropriate fields for the component in the work area.

The data model editor supports the following

- **Group data** - Create groups to organize the columns in your report. Groups can do two things: separate a query's data into sets, and filter a query's data.

When you create a query, the data engine creates a group that contains the columns selected by the query; you can create groups to modify the hierarchy of the data appearing in a data model. Groups are used primarily when you want to treat some columns differently than others. For example, you create groups to produce subtotals or create breaks.
- **Link data** - Define master-detail links between data sets to group data at multiple levels.
- **Aggregate data** - Create group level totals and subtotals.
- **Transform data** - Modify source data to conform to business terms and reporting requirements.
- **Create calculations** - Compute data values that are required for your report that are not available in the underlying data sources.

The data model editor provides functions at the element level, the group level, and the global level. Note that not all data set types support all functions. See the Important Notes section that accompanies your data set type for limitations. The figure below highlights some of the features and actions available in the data model editor.



Launch the Data Model Editor

Launch the data model editor from the header or from the Home page.

To launch the Data Model Editor:

- Use one of these ways:
 - Click **New** and then click **Data Model**.
 - Under the **Create** region, click **Data Model**.

About the Data Model Editor Toolbar


The data model editor toolbar on the top provides you the options to manage private data sources, view data, create report, and save the data model.

| Option | Description |
|------------------------------------|--|
| Validate | Validate the queries used for data sets, LOVs, and bursting definitions. |
| Manage Private Data Sources | Connect to private data sources for your personal use that do not require setup by an administrator. |
| View Data | Display the Data tab where you view and generate sample data. |
| Create Report | Create a new report with this data model. |

| Option | Description |
|-----------------------|---|
| Save / Save As | <p>Select Save to save your work in progress to the existing data model object or select Save As to save the data model as a new object in the catalog.</p> <p>If you create a data model and then navigate out of the data model editor without saving it, a draft or temporary data model entry may display in the Recent section of the Home page. These entries cannot be manually deleted, but are automatically deleted after 24 hours.</p> |
| Help | View online help. |

About the Interface

By default, the data sets that you created are shown in the Diagram View as separate objects.



The data set structure builder has three views:

- **Diagram View** - The **Diagram View** displays data sets and enables graphically creating links and filters, adding elements based on expressions, adding aggregate functions and global-level functions, editing element properties, and deleting elements. The Diagram View is typically the view you use to build your data structure.

- **Structure View** - The **Structure View** has two modes:

Table View and Output

The table view displays element properties in a table and enables updating XML element alias names, presentation names of the elements, sorting, null values, and reset options. The image below shows the structure Table View.

| Data Source | XML View | | | Business View | |
|-----------------|-----------------|---------|---------------|-----------------|-----------|
| | XML Tag Name | Sorting | Value If Null | Display Name | Data Type |
| Report Data | | | | | |
| Data Structure | DATA_DS | | | | |
| Departments | G_2 | | | | |
| DEPARTMENT_NAME | DEPARTMENT_NAME | | | DEPARTMENT_NAME | A |
| DEPARTMENT_ID | DEPARTMENT_ID | | | DEPARTMENT_ID | # |
| MANAGER_ID | MANAGER_ID | | | MANAGER_ID | # |
| Employees | G_1 | | | | |
| FIRST_NAME | FIRST_NAME | | | FIRST_NAME | A |
| LAST_NAME | LAST_NAME | | | LAST_NAME | A |
| MANAGER_ID | MANAGER_ID | | | MANAGER_ID | # |
| SALARY | SALARY | | | SALARY | #e |
| HIRE_DATE | HIRE_DATE | | | HIRE_DATE | e |
| DEPARTMENT_ID | DEPARTMENT_ID | | | DEPARTMENT_ID | # |
| JOB_TITLE | JOB_TITLE | | | JOB_TITLE | A |

The **Output** view provides a clear view of the XML structure that is generated. The Output view cannot be updated. The figure shows the Output view.

| XML output | Descriptive XML output |
|-----------------|------------------------|
| DATA_DS | DATA_DS |
| G_2 | G_2 |
| DEPARTMENT_NAME | DEPARTMENT_NAME |
| DEPARTMENT_ID | DEPARTMENT_ID |
| MANAGER_ID | MANAGER_ID |
| G_1 | G_1 |
| FIRST_NAME | FIRST_NAME |
| LAST_NAME | LAST_NAME |
| MANAGER_ID | MANAGER_ID |
| SALARY | SALARY |
| HIRE_DATE | HIRE_DATE |
| DEPARTMENT_ID | DEPARTMENT_ID |
| JOB_TITLE | JOB_TITLE |

- **Code View** - The **Code View** displays the data structure code created by the data structure builder that is read by the data engine. You can update the content in code view. The figure shows the code view.

```
<output rootName="DATA_DS" uniqueRowName="false">
<nodeList name="data-structure">
<dataStructure tagName="DATA_DS">
<group name="G_2" label="G_2" source="Departments">
<element name="DEPARTMENT_NAME" value="DEPARTMENT_NAME" label="DEPARTMENT_NAME"
dataType="xsd:string" breakOrder="" fieldOrder="1"/>
<element name="DEPARTMENT_ID" value="DEPARTMENT_ID" label="DEPARTMENT_ID"
dataType="xsd:integer" breakOrder="" fieldOrder="2"/>
<element name="MANAGER_ID" value="MANAGER_ID" label="MANAGER_ID" dataType="xsd:integer"
breakOrder="" fieldOrder="3"/>
</group>
<group name="G_1" label="G_1" source="Employees">
<element name="FIRST_NAME" value="FIRST_NAME" label="FIRST_NAME" dataType="xsd:string"
breakOrder="" fieldOrder="1"/>
<element name="LAST_NAME" value="LAST_NAME" label="LAST_NAME" dataType="xsd:string"
breakOrder="" fieldOrder="2"/>
<element name="MANAGER_ID" value="MANAGER_ID" label="MANAGER_ID" dataType="xsd:integer"
breakOrder="" fieldOrder="3"/>
<element name="SALARY" value="SALARY" label="SALARY" dataType="xsd:double" breakOrder=""
fieldOrder="4"/>
<element name="HIRE_DATE" value="HIRE_DATE" label="HIRE_DATE" dataType="xsd:date"
breakOrder="" fieldOrder="5" formatMask=""/>
<element name="DEPARTMENT_ID" value="DEPARTMENT_ID" label="DEPARTMENT_ID"
dataType="xsd:integer" breakOrder="" fieldOrder="6"/>
<element name="JOB_TITLE" value="JOB_TITLE" label="JOB_TITLE" dataType="xsd:string"
breakOrder="" fieldOrder="7"/>
</group>
</dataStructure>
</nodeList>
</output>
```

Data Model Properties

You can access the Data Model Properties page when you click **Properties** in the components pane.

Enter the following properties for the data model:

| Property | Description |
|----------------------------------|---|
| Description | Enter a description for the data model. The catalog displays the descriptions of data models. This description is translatable. |
| Default Data Source | Select the data source from the list. Data models can include multiple data sets from one or more data sources. The default data source you select here is presented as the default for each new SQL data set you define. Select Refresh Data Source List to see any new data sources added since your session was initiated. |
| Oracle DB Default Package | Enter a default PL/SQL package for data models that include event triggers or a PL/SQL group filter. The package must exist on the default data source. If you define a query against an Oracle Database, then you can include before or after data triggers (event triggers) in your data model. Event triggers make use of PL/SQL packages to execute RDBMS level functions. |

| Property | Description |
|-----------------------------------|--|
| Database Fetch Size | Enter the number of rows to be fetched at a time through the JDBC connection. This value overrides the value set in the system properties. If neither this value nor the server setting is defined, then the server default value of 20 is used. If the server property Enable Auto DB fetch size mode is set to True , this value is ignored. |
| Query Time Out | Enter a time limit in seconds within which the database must execute SQL statements. This property applies to SQL query-based data models for scheduled reports. If the SQL query is still processing when the time out value is met, the error <code>Failed to retrieve data xml.</code> is returned. Enter a value in seconds. If you do not enter a value for this data model, the server property value is used. |
| Scalable Mode | Select this property to process large data sets that require large amounts of RAM. To prevent running out of memory, activate scalable mode for the data engine. In scalable mode, the data engine takes advantage of disk space when it processes the data. Setting this to On will impact performance, but guard against out of memory errors. Note that Enable Data Model Scalable Mode is also a server-level property therefore by default the data model-level property is set to Instance Level to inherit the server or instance level setting. To turn scalable mode on or off for this particular data model, select On or Off from the list. |
| Enable SQL Pruning | Select this property to enhance processing time and reduces memory usage. This property applies to Oracle Database queries only that use standard SQL. If your query returns many columns but only a subset are used by your report template, SQL pruning returns only those columns required by the template. Note that Enable SQL Pruning is also a server-level property. Therefore, by default the data model-level property is set to Instance Level to inherit the server or instance level setting. To turn SQL pruning on or off for this particular data model, select On or Off from the list. SQL pruning is not applicable for PDF, Excel, and E-text template types. |
| Skip Unused Data Set Query | Select this property to omit the execution of any unused data sets in the layout, so you can reduce processing time and memory usage. By default, all data sets in a data model are executed whether a data set is required for the output. When a data model contains multiple data sets for different layouts, each layout might not require all the data sets defined in the data model. You must set the Enable SQL Pruning property to On to use the Skip Unused Data Set Query property. |

| Property | Description |
|---------------------------------|---|
| Enable SQL Session Trace | <p>Select this property to enable SQL session trace. For each SQL statement, the trace contains:</p> <ul style="list-style-type: none">• Parse, execute, and fetch counts• CPU time and elapsed time• Physical reads and logical reads• Number of rows processed• Library cache failures• User name for which each parse occurred• Each commit and rollback <p>This property applies to Oracle Database queries that use standard SQL.</p> |
| SQL Trace Name | Enter a name for the SQL trace. |
| Enable XML Pruning | <p>Select On to prune XML data sets larger than 2GB. If you enable XML data pruning, Publisher removes the unnecessary data elements and builds the XML structure using only the data fields that are mapped to the layout fields. Data pruning improves performance, especially for extremely large data extractions.</p> <p>Report consumers can configure XML data pruning when scheduling a job. XML data pruning isn't supported for XPT template (Publisher Layout).</p> |
| Backup Data Source | <p>Select the Enable Backup Connection property to use the backup data source.</p> <ul style="list-style-type: none">• To use the backup data source only when the primary is down, select Switch to Backup Data Source when Primary Data Source is unavailable. Note that when the primary data source is down, the data engine must wait for a response before switching to the backup.• To always use the backup data source when executing this data model, select Use Backup Data Source Only. Using the backup database may enhance performance. <p>You must enable a backup for the data source.</p> |
| Enable CSV Output | Select this property to generate report output only in a CSV file. |
| Optimize Query Execution | <p>Select this property to allow the data processor to optimize the execution of SQL queries of parent and child data sets.</p> <p>Select this property only when the data model includes a parent-child hierarchy structure in a SQL data set. Don't select this option for non-structured and non-SQL data sets.</p> |

| Property | Description |
|------------------------------------|--|
| Multithread Query Execution | <p>Select this property to create multiple database connections to query the child data sets in parallel. If you select this property, the number of database connections per data model increases.</p> <p>This property is enabled only when:</p> <ul style="list-style-type: none"> • Optimize Query Execution is set to true. • Data model has more than one data set. • Data model has parallel child data set queries linked to the parent data set. • Data model uses the default data source. <p>This property cannot be used when:</p> <ul style="list-style-type: none"> • Data model uses event triggers. • Data model has a data set query linearly linked to the parent data set. • Data model uses multiple data sources. |

XML Output Options

These options define the characteristics of the XML data structure. Any changes to these options can impact layouts that are built on the data model.

- **Include Parameter Tags** — If you define parameters for your data model, select this option to include the parameter values in the XML output file. See [Add Parameters and Lists of Values](#) for adding parameters to your data model. Enable this option when you want to use the parameter value in the report.
- **Include Empty Tags for Null Elements** — Select this option to include elements with null values in your output XML data. When you include a null element, then a requested element that contains no data in your data source is included in your XML output as an empty XML tag as follows: <ELEMENT_ID>. For example, if the element MANAGER_ID contained no data and you chose to include null elements, it would appear in your data as follows: <MANAGER_ID />. If you do not select this option, no entry is displayed for MANAGER_ID.
- **Include Open & Close Tags** — Select this option to include the open and close tags in your output XML data.
- **Include Group List Tag** — (This property is for 10g backward compatibility and Oracle Report migration.) Select this option to include the rowset tags in your output XML data. If you include the group list tags, then the group list displays as another hierarchy within your data.
- **Exclude Tags for LOB Columns** — Select this property to exclude the XML element tags for LOB columns. The data model must contain a single data set of SQL query type and a single Character Large Object data element containing data extracted from an XML file. You can't use global level, summary, or aggregate functions, elements based on expressions, or group filters.
- **Exclude Line Feed And Carriage Return for LOB** — Select this option to exclude carriage returns and line feeds in the data.
- **XML Tag Display** — Select the display format to generate the XML data tags - uppercase, lowercase, or to preserve the definition you supplied in the data structure.

XML Data Chunking

XML data chunking supports distributed processing.

XML data chunking is suitable for large and long-running reports. If the administrator selects the **Enable Data Chunking** runtime property at the instance level, you can enable XML data chunking for individual data models, reports, and scheduled jobs.

In a data model, if you select **Enable Chunking** and specify an attribute in the **Split By** field, the data model pre-processor uses the split key to split large amounts of XML data into several chunks of data of manageable size.

Before you enable XML data chunking, understand its limitations and recommended usage.

XML data chunking:

- Is best suited for listing reports using a table and with no cross-references.
- Supports sorting, grouping, aggregation, and cross-referencing operations only within the individual chunked output. The merged output doesn't support these data operations.
- Adds page numbers to the PDF pages of the merged output. In the report template, remove the page numbering element to avoid duplicate or overlapping page numbers in the PDF output.
- Supports running totals, and other functions only within the individual chunked output, and each is reset with each chunked output.
- Supports only RTF, XPT, and eText, and XSL templates.
- Supports only PDF, XLSX, and Text output formats.
- Doesn't support multiple output formats. If you select XML chunking for a scheduled job, multiple outputs aren't allowed.
- Isn't supported for online reports.

Add Attachments to the Data Model

The Attachment region of the page displays data files that you've uploaded or attached to the data model.

Attach Sample Data

After you build your data model, you must attach a small, but representative set of sample data generated from your data model. The sample data is used by Publisher's layout editing tools. Using a small sample file helps improve performance during the layout design phase.

The data model editor provides an option to generate and attach the sample data. See [Test Data Models and Generate Sample Data](#).

The administrator can set a limit to the size of the sample data file.

Attach Schema

The data model editor enables you to attach sample schema to the data model definition.


Publisher doesn't use the schema file. However, you can attach the schema for developer reference. The data model editor doesn't support schema generation.

Data Files

If you upload a local Microsoft Excel, CSV, or XML file as a data source for this report, the file displays here.

Use the refresh button to refresh this file from the local source. For information on uploading files to use as data sources, see [Create Data Sets](#).

The figure below shows the Attachments region with sample data and data files attached:



Manage Private Data Sources

Data model developers can create and manage private JDBC, OLAP, web service, and HTTP data source connections without having to depend on an Administrator user. However, Administrator users can still view, modify, and delete private data source connections, if needed.

Private data source connections are identified by the word (Private) appended to the end of the data source name. For example, if you create a private JDBC connection called My JDBC Connection, it's displayed as My JDBC Connection (Private) in the data source drop-down lists.

If your user has the Administrator role, you can only create public data sources, even if you create the data source from the Manage Private Data Sources page.

To create a private data source connection:

1. From the data model editor toolbar, click **Manage Private Data Sources**.
2. Select the connection type tab, and click **Add Data Source**.

If you are logged in as an Administrator, the dialog displays all the data source connections; however, you can only create or modify JDBC, OLAP, HTTP, and web service data sources from this dialog.

3. Enter the private connection name, and the connection information.
4. Click **Test Connection**. A confirmation is displayed.
5. Click **Apply**. The private data source connection is now available for use in your data sets.

2

Create Data Sets

This topic describes creating data sets, testing data models, and saving sample data.

Topics:

- [Create a Data Set](#)
- [Edit an Existing Data Set](#)
- [Create Data Sets Using SQL Queries](#)
- [Create a Data Set Using a MDX Query Against an OLAP Data Source](#)
- [Use MDX Query Builder](#)
- [Create a Data Set Using an Analysis](#)
- [Create a Data Set Using a Web Service](#)
- [Create a Data Set Using a XML File](#)
- [Create a Data Set Using a Microsoft Excel File](#)
- [Create a Data Set Using a CSV File](#)
- [Create a Data Set from an HTTP XML Feed](#)
- [Use Data Stored as a Character Large Object \(CLOB\) in a Data Model](#)
- [Test Data Models and Generate Sample Data](#)
- [Include User Information Stored in System Variables in Your Report Data](#)

Create a Data Set Using a Visualized Data Set

You can create data sets using the data sets created after you visualize data.

You can upload data from a variety of sources (for example, spreadsheets, CSV files, and many databases) to your system, and explore your data to find correlations, discover patterns, and see trends. You can't upload data sets that contain multiple tables.

After you analyze a large set of data and discover important trends in your data, you can capture this information in data sets, and use these visualized data sets to create pixel-perfect reports, publish reports (online or to multiple destinations), schedule reports, and burst reports.

After you import a visualized data set, if you change the structure of the visualized data set, you must manually edit and refresh the visualized data set. You can't import the expressions and user-calculated elements from a visualized data set to a Publisher data model and you can't link between data sets.

To create a data set by using a visualized data set:

1. On the component pane of the data model editor, select **Data Set** and select **DV Data**.

The Data Sets tab lists all the data sets you visualized.

2. In the Data Sets tab, select the data set you want to use for pixel-perfect reporting.
3. Click **Next**.
4. Enter a name for the data set.
5. If you want to configure parameters, perform these steps for each parameter:
 - a. Click **Add Parameter**.
 - b. Select a column from the **Column Name** list.
 - c. If you want to change the name of the parameter, edit the name in the **Parameter** field.
6. Click **Finish**.

Create a Data Set Using a Visualized Data Flow

You can use visualized data flows to create data sets.

You can't use these types of data flows to create data sets:

- Data flows created with the **Save Model** option.
- Data flows with branched data sets.

To create a data set using visualized data flows:

1. Select **Data Sets**, click **New Data Set** in the Diagram tab, and then select **DV Data**.
2. In the Data Flows tab, select a data flow you want to use and click **Next**.
3. Enter a name for the data set.
4. If you want to configure parameters, perform these steps for each parameter:
 - a. Click **Add Parameter**.
 - b. Select a column from the **Column Name** list.
 - c. If you want to change the name of the parameter, edit the name in the **Parameter** field.
5. Click **Finish**.

Create a Data Set

Publisher can retrieve data from multiple types of data sources.

To create a data set:

1. On the component pane of the data model editor, click **New Data Set** and select your source data set type.
2. Complete the required fields. Refer the help topic for the data set type you want to create.

Create Data Sets Using SQL Queries

These topics explain how to create data sets using SQL queries.

- [Enter SQL Queries](#)
- [Use the SQL Query Builder](#)
- [Add a Bind Variable to a Query](#)
- [Add Lexical References to SQL Queries](#)
- [Define SQL Queries Against the Oracle BI Server](#)

Enter SQL Queries

Use these steps to enter SQL queries.

To enter an SQL query:

1. Click **New Data Set** and then click **SQL Query**.
2. In the dialog to create a new data set, enter a name for the data set.
3. The data source defaults to the default data source that you selected on the Properties page. If you aren't using the default data source for this data set, select the **Data Source** from the list.

You can also use your private data source connections as data sources for SQL query data sets.

4. Select **Standard SQL** from the **Type of SQL** drop-down list. Standard SQL is used for normal SELECT statements interpreted to understand database schema.
5. Enter the SQL query or click **Query Builder** to launch the Query Builder page.
6. If you are using Flexfields, bind variables, or other special processing in your query, edit the SQL code returned by the Query Builder to include the required statements.

If you include lexical references for text that you embed in a SELECT statement, then you must substitute values to get a valid SQL statement.

7. After entering the query, click **OK** to save. For Standard SQL queries, the data model editor validates the query.

If your query includes a bind variable, you're prompted to create the bind parameter. Click **OK** to have the data model editor create the bind parameter.

Use the SQL Query Builder

Use the Query Builder to build SQL queries without coding. The Query Builder enables you to search and filter database objects, select objects and columns, create relationships between objects, and view formatted query results with minimal SQL knowledge.

This section describes how to use the Query Builder and includes the following topics:

- [Overview of the Query Builder](#)
- [Build a Query Using Query Builder](#)
- [Supported Column Types](#)
- [Add Objects to the Design Pane](#)
- [Remove or Hide Objects in the Design Pane](#)
- [Query Conditions](#)

- [Create Relationships Between Objects](#)
- [Save a Query](#)
- [Edit a Saved Query](#)

Overview of the Query Builder

The Query Builder page is divided into an Object Selection pane and a design and output pane.

- Object Selection pane contains a list of objects from which you can build queries. Only objects in the current schema are displayed.
- Design and output pane consists of four tabs:
 - **Model** — Displays selected objects from the Object Selection pane.
 - **Conditions** — Enables you to apply conditions to your selected columns.
 - **SQL** — Displays the query.
 - **Results** — Displays the results of the query.

Build a Query Using Query Builder

You can build a query using Query Builder.

To build a query using Query Builder:

1. Select a schema.

The Schema list displays all available schemas in the data source. You might not have access to all schemas in that list.
2. Add objects to the Design pane and select columns.

The Object Selection pane lists the tables, views, and materialized views from the selected schema. For an Oracle Database, the pane also lists synonyms. When you select an object from the list, it's displayed on the Design pane. Use the Design pane to specify how to use selected objects in the query.

You might need to use the Search field to enter a search string. If the data source includes more than 100 tables, use the Search features to locate and select objects.
3. Optional: Establish relationships between objects.
4. Add a unique alias name for any duplicate column.
5. Optional: Create query conditions.
6. Execute the query and view results.

Supported Column Types

Columns of all types display as objects in the Design pane. You can't select more than 60 columns for each query.

| Supported Column Type | Restrictions |
|-----------------------|--------------|
| VARCHAR2, CHAR | NA |
| NUMBER | NA |

| Supported Column Type | Restrictions |
|-------------------------------|---|
| DATE, TIMESTAMP | The <code>TIMESTAMP WITH LOCAL TIMEZONE</code> data type isn't supported. |
| Binary Large Object (BLOB) | The BLOB can be an image, text, or XML data. When you execute the query in the Query Builder, the BLOB doesn't display in the Results pane; however, the query is constructed correctly when saved to the data model editor. BLOB data isn't supported for an Oracle BI EE data source due to limitations of the BIJDBC driver. Use an RTF template if you want to use a BLOB data column with an Image data type. |
| Character Large Object (CLOB) | Publisher doesn't support querying of CLOB columns in an Oracle Analytics Server data source. |

Add Objects to the Design Pane

Select each object you want to add to the Design pane.

- When you add an object, an icon representing the data type displays next to each column name.
- When you select a column, it appears on the **Conditions** tab. The **Show** check box on the **Conditions** tab controls whether a column is included in query results. By default, this check box is selected.
- To select the first twenty columns, click the small icon in the upper left corner of the object and then select **Check All**.
- You can also execute a query by pressing the **CTRL + ENTER** keys.

To add objects to the design pane:

1. Select an object.
2. Select the check box for each column to include in your query.
3. To execute the query and view results, select **Results**.

Remove or Hide Objects in the Design Pane

You can remove or hide objects in the Design pane.

To remove an object:

1. Click **Remove** in the upper right corner of the object.

To temporarily hide the columns within an object:

- Click **Show/Hide Columns**.

Query Conditions

Conditions enable you to filter and identify the data you want to work with.

As you select columns within an object, you can specify conditions on the Conditions tab. You can modify the column alias, apply column conditions, sort columns, or apply functions.

| Condition Attribute | Description |
|---------------------|---|
| Condition | The condition modifies the query's WHERE clause. When specifying a column condition, you must include the appropriate operator and operand. All standard SQL conditions are supported. For example: ≥ 10 $= 'VA'$ IN (SELECT dept_no FROM dept) BETWEEN SYSDATE AND SYSDATE + 15 |
| Function | Specifies the functions. Available argument functions include: <ul style="list-style-type: none"> • Number columns — COUNT, COUNT DISTINCT, AVG, MAXIMUM, MINIMUM, SUM • VARCHAR2, CHAR columns — COUNT, COUNT DISTINCT, INITCAP, LENGTH, LOWER, LTRIM, RTRIM, TRIM, UPPER • DATE, TIMESTAMP columns— COUNT, COUNT DISTINCT |
| Group By | Specifies the columns to be used for grouping when an aggregate function is used. Only applicable for columns included in output. |

As you select columns and define conditions, Query Builder writes the SQL for you. To view the underlying SQL, select the **SQL** tab.

Create Relationships Between Objects

You can create relationships between objects by creating a join. A join identifies a relationship between two or more tables, views, or materialized views.

- [About Join Conditions](#)
- [Join Objects Manually](#)

About Join Conditions

When you write a join query, you specify a condition that conveys a relationship between two objects. This condition is called a join condition.

A join condition specifies how the rows from one object combine with the rows from another object.

Query Builder supports inner, outer, left, and right joins.

- An inner join, also called a simple join, returns the rows that satisfy the join condition.
- An outer join extends the result of a simple join.

An outer join returns all rows that satisfy the join condition and returns some or all of those rows from one table for which no rows from the other satisfy the join condition.

Join Objects Manually

Create a join manually by selecting the Join column in the Design pane.

To join objects manually:

1. From the Object Selection pane, select the objects you want to join.
2. Identify the columns you want to join.

You create a join by selecting the **Join** column adjacent to the column name. The **Join** column displays to the right of the data type. When your cursor is in the appropriate position, the following help tip displays:


Click here to select column for join

3. Select the appropriate **Join** column for the first object.

When selected, the **Join** column is darkened. To deselect a **Join** column, simply select it again or press **ESC**.

4. Select the appropriate **Join** column for the second object.

When joined, a line connects the two columns. An example is shown below.




5. Select the columns to be included in your query. You can view the SQL statement resulting from the join by positioning the cursor over the join line.
6. Click **Results** to execute the query.

Save a Query

Save queries after building them.

Once you've built a query, click **Save** to return to the data model editor. The query appears in the SQL Query box. Click **OK** to save the data set.



Edit a Saved Query

When you save a query from the Query Builder to the data model editor, you can also use the Query Builder to edit the query.

If you've made modifications to the query, or did not use the Query Builder to construct it, you may receive an error when launching the Query Builder for editing the query. If the Query Builder can't parse the query, you can edit the statements directly in the text box.

You cannot edit a customized or an advanced query by using Query Builder.

To edit a saved query:

1. Select the SQL data set.
2. On the toolbar, click **Edit Selected Data Set** to launch the **Edit Data Set** dialog.
3. Click **Query Builder** to load the query to the Query Builder.
4. Edit the query and click **Save**.

Add a Bind Variable to a Query

After creating a query, you may want users to be able to pass a parameter to the query to limit the results.

To add a bind variable to a query:

1. In the Query Builder, click the **Conditions** tab.


- For the column you want to add a bind variable, enter the parameter name in the following format:

```
in (:PARAMETER_NAME)
```

After you edit the query, the Query Builder can no longer parse it. You must make any additional edits manually.

For example, in the employee listing, you want users to choose a specific department.

The image shows the columns in the department table.



Add a Bind Variable Using a Text Editor

Use the Data Model Editor to update a SQL query.


- In the Edit Data Set text box, update the SQL query by adding the following after the where clause in your query:

```
and "COLUMN_NAME" in (:PARAMETER_NAME)
```


for example:

```
and "DEPARTMENT_NAME" in (:P_DEPTNAME)
```

where P_DEPTNAME is the name you choose for the parameter, as shown below.



2. Click Save.
3. In the data model editor, create the parameter that you entered with the bind variable syntax as shown in the image.



4. Select the parameter, and click **OK** to enable the data model editor create the parameter entry for you.

Add Lexical References to SQL Queries

You can use lexical references to replace the clauses appearing after SELECT, FROM, WHERE, GROUP BY, ORDER BY, or HAVING.

Use a lexical reference when you want the parameter to replace multiple values at runtime. You can also use lexical references to include flexfields in your query. Lexical references are supported in queries against Oracle applications only.

Create a lexical reference in the SQL query using the following syntax:

¶metername

1. Before creating your query, define a parameter in the PL/SQL default package for each lexical reference in the query. The data engine uses these values to replace the lexical parameters.
2. In the data model editor, on the Properties page, specify the **Oracle DB Default Package**.
3. In the data model editor, create a **Before Data** event trigger to call the PL/SQL package.
4. Create your SQL query containing lexical references.
5. When you click **OK** to close your SQL query, you are prompted to enter the parameter.

For example, create a package called `employee`. In the `employee` package, define a parameter called `where_clause`:


```
Package employee
AS
  where_clause varchar2(1000);
  .....

Package body employee
AS
  .....
where_clause := 'where DEPARTMENT_ID=10';
  .....
```

Reference the lexical parameter in the SQL query where you want the parameter to be replaced by the code defined in the package, for example:

```
select      "EMPLOYEES"."EMPLOYEE_ID" as "EMPLOYEE_ID",
           "EMPLOYEES"."FIRST_NAME" as "FIRST_NAME",
           "EMPLOYEES"."LAST_NAME" as "LAST_NAME",
           "EMPLOYEES"."SALARY" as "SALARY",
from        "OE"."EMPLOYEES" "EMPLOYEES"
&where_clause
```

When you click **OK** on the Create SQL Data Set dialog box, the lexical reference dialog box prompts you to enter a value for lexical references you entered in the SQL query, as shown in the image that follows. Enter the value of the lexical reference as it's defined in the PL/SQL package.



At runtime, the data engine replaces `&where_clause` with the contents of `where_clause` defined in the package.

About Defining SQL Queries Against the Oracle BI Server

This topic describes the points you need to remember when you define SQL queries against the Oracle BI Server.

Keep the following points in mind when creating a data set against the Oracle BI Server:

- When you create a SQL query against the Oracle BI Server using the SQL Data Editor or the Query Builder, logical SQL is generated, not physical SQL like other database sources.
- Hierarchical columns aren't supported. The highest level is always returned.
- Within a subject area, the join conditions between tables are already created; therefore you don't have to create joins in the Query Builder. The Query Builder doesn't expose the primary key.

You can link data sets using the data model editor's **Create Link** function. See [Create Element-Level Links](#). For data sets created from the Oracle BI Server, there's a limit of two element-level links for a single data model.

- In the Query Builder, the functions **Sort Order** and **Group By** shown on the Conditions tab aren't supported for queries against the Oracle BI Server. If you enter a Sort Order or select the Group By check box, the Query Builder constructs the SQL, and writes it to the Publisher SQL Query text box, but when you attempt to close the Data Set dialog, the query fails validation.

To apply grouping to the data retrieved by the SQL query, you can use the data model editor's **Group by** function instead. See [Create Subgroups](#).

- If you pass parameters to the Oracle BI Server and you choose Null Value Passed for Can Select All, make sure you handle the null value in your query.

Define SQL Queries Against the Oracle BI Server

When you launch the Query Builder against the Oracle BI Server, the Query Builder displays the subject areas from the catalog. You can drag the subject areas to the


Query Builder workspace to display the columns. Select the columns to include in your data model.

To define SQL queries against the Oracle BI Server :

1. In the data model editor, click **New Data Set** and then click **SQL Query**.
2. Enter a name for the data set.
3. From the Data Source list, select the Oracle BI Server connection, usually shown as Oracle Analytics Server.
4. Click **Query Builder** to launch the Query Builder page.

You can also enter the SQL syntax manually in the SQL Query text box, however you must use the Logical SQL syntax used by the Oracle BI Server.

5. From the Catalog drop-down list, select a subject area as shown below. The list displays the subject areas defined in the Oracle BI Server.



6. Select tables and columns for the query.
7. Click **Save**.
8. Click **OK** to return to the data model editor. The generated SQL is Logical SQL that follows a star schema (that is, it isn't physical SQL).
9. Save your changes to the data model.

Notes for Queries Against Oracle Fusion Applications Tables

Special considerations for Oracle Fusion Applications customers apply when writing queries against the Oracle Fusion Applications tables

- You cannot return month name from `sysdate` using `to_char(sysdate, "mon")`. This function returns the month number. To display month name, use one of the following solutions:
 - Format the date field in your layout using the following syntax: `<?format_date:fieldname;MASK)?>`
 - To display month name based on month number, use the following syntax in your layout: `<?xdoxslt:month_name(month, [abbreviate?], $_XDOLocale)?>`

where `month` is the numeric value of the month (January = 1) and
[abbreviate?] is the value 0 for do not abbreviate or 1 for abbreviate.

For example:

```
<?xdoxslt:month_name(1, 0, $_XDOLOCALE)?>
```

returns January

- To add an expression in the data model, use the following expression:

```
Format_date(date, format_String)
```

For example:

```
SUBSTRING(FORMAT_DATE(G_1.SYSDATE,MEDIUM),0,3)
```


returns Nov (when the current SYSDATE is November)

Create a Data Set Using an LDAP Query

You can use Lightweight Directory Access protocol (LDAP) data sources.

You can query user information stored in LDAP directories and then use the data model editor to link the user information with data retrieved from other data sources.

For example, to generate a report that lists employee salary information that is stored in the database application and also include employee e-mail addresses that are stored in the LDAP directory in the report, you can create a query against each and then link the two in the data model editor to display the information in a single report. The figure below shows a sample LDAP query.



To create a data set using an LDAP query:

1. Click the **New Data Set** toolbar button and select **LDAP Query**.

2. In the New Data Set - LDAP Query dialog, enter a name for this data set.
3. Select the **Data Source** for this data set.
4. In the **Search Base** field, enter the starting point for the search in the directory tree.

Search Base is required when the LDAP provider is Microsoft Active Directory. The Search Base defines the starting point of the search in the directory tree. For example, if you want to query the entire directory, specify the root.

To specify the starting point, enter each hierarchical object separated by a comma, starting with the lowest level in the hierarchy, for example, to search the Sales container in the *mycompany.com* domain, enter:

```
ou=Sales,dc=mycompany,dc=com
```

5. In the **Attributes** entry box, enter the attributes whose values you want to fetch from the LDAP data source.
For example: mail,cn,givenName
6. To filter the query, enter the appropriate syntax in the **Filter** entry box. The syntax is as follows:

```
(Operator (Filter)through(Filter))
```

For example: (objectclass=person)

LDAP search filters are defined in the Internet Engineering Task Force (IETF) Request for Comments document 2254 (RFC 2254) on the IETF Web site.

7. Link the data from this query to the data from other queries or modify the output structure.

Create a Data Set Using a MDX Query Against an OLAP Data Source

Publisher supports Multidimensional Expressions (MDX) queries against OLAP data sources.

MDX enables you to query multidimensional objects, such as Essbase cubes, and return multidimensional cell sets that contain the cube's data. You create MDX queries by manually entering the MDX query or by using MDX Query Builder to build the query.

- [Create a Data Set Using a MDX Query](#)
- [Use MDX Query Builder](#)

Create a Data Set Using a MDX Query


You create MDX queries either by manually entering the MDX query or by using MDX Query Builder to build the query.

In your OLAP data source, do not use Unicode characters from the range U+F900 to U+FFFE to define any metadata attributes such as column names or table names. This Unicode range includes half-width Japanese Katakana and full-width ASCII variants. Using these characters results in errors when generating the XML data for a pixel-perfect report.

To create a data set using a MDX query:

1. On the toolbar, click **New Data Set** and then select **MDX Query**.

The New Data Set - MDX Query dialog is shown below.



2. Enter a name for the data set.
3. Select the data source for the data set. Only the data sources defined as OLAP connections are displayed in the list.
Any private OLAP data source connections that you created will also be available in the Data Source drop-down list.
4. Enter the MDX query or click **Query Builder**.
5. Click **OK** to save. The data model editor validates the query.

Use MDX Query Builder

Use MDX Query Builder to build MDX basic queries without having to code them. MDX Query Builder enables you to add dimensions to columns, rows, pages, and point of view axes and preview the query results.

MDX Query Builder only enables you to build data sets against Essbase data sources. For all other OLAP data sources, you must manually create the query.

- [Understand the MDX Query Builder Process](#)
- [Use the Select Cube Dialog](#)
- [Select Dimensions and Measures](#)
- [Perform MDX Query Actions](#)
- [Apply MDX Query Filters](#)
- [Select MDX Query Options and Save MDX Queries](#)

Understand the MDX Query Builder Process

You create MDX queries either by manually entering the MDX query or by using MDX Query Builder to build the query.

To use MDX Query Builder to build a MDX query:

1. On the toolbar, click **New Data Set** and then select **MDX Query** to launch the New Data Set - MDX Query dialog.
2. Enter a name for the data set.
3. Select a data source.
4. Launch MDX Query Builder.
5. Select an Essbase cube for the query.
6. Select dimensions and measures by dragging and dropping them to the Columns, Rows, Slicer/POV, and the Pages axes.
7. Optional: Use actions to modify the query.
8. Optional: Apply filters.
9. Set the query options and save the query.

Use the Select Cube Dialog

In the Select Cube dialog, select the Essbase cube that you want to use to build the MDX query.

The MDX data source connection that you selected previously drives which Essbase cubes are available for selection.

Select Dimensions and Measures

You build MDX queries by selecting dimensions for the Columns, Rows, Slicer/POV, and Pages axes.

Account dimension members are listed individually by member name. All other dimension members are represented by generation name as shown below.

You can drag dimension generations and individual measures from the Account dimension to the Columns, Rows, Slicer/POV, and Pages axes.

The screenshot shows the MDX Query Builder interface. On the left is the 'Dimensions' panel with a tree view of dimensions: Market, Gen2, Market, Gen3, Market, Product, Gen2, Product, Gen3, Product, Scenario, Gen2, Scenario, Year, Gen2, Year, Gen3, Year, Accounts, Profit, Margin, Sales, Cost_of_Goods, Total_Expenses, Marketing, Payroll, Miscellaneous, Profit_%, and Margin_%. The main area shows the query configuration: Columns (Gen2, Market), Rows (Gen3, Product, Margin, Sales, Total_Expenses), Slicer/POV (Scenario (Budget)), and Pages (Gen3, Year). Below this is the MDX query text:

```
SELECT
NON EMPTY Hierarchize([Market].Generations(2).Members) ON Axis(0),
NON EMPTY CROSSJOIN(Hierarchize([Product].Generations(3).Members),{[Accounts].[Margin],[Accounts].[Sales],[Accounts].[Total_Expenses]}) ON Axis(1),NON EMPTY [Year].Generations(3).Members ON Axis(2)
FROM Demo.Basic
WHERE ((Budget))
```

Below the query is a data table for the month of January:

| | | East | West | South |
|--------------|----------------|----------|----------|----------|
| Stereo | Margin | 1,239.00 | 1,680.00 | |
| | Sales | 2,950.00 | 4,000.00 | |
| | Total_Expenses | 1,145.00 | 1,580.00 | |
| Compact_Disc | Margin | 2,139.00 | 2,914.00 | |
| | Sales | 3,450.00 | 4,700.00 | |
| | Total_Expenses | 1,040.00 | 1,250.00 | |
| Television | Margin | 2,880.00 | 3,060.00 | 2,040.00 |
| | Sales | 4,800.00 | 5,100.00 | 3,400.00 |
| | Total_Expenses | 1,640.00 | 1,900.00 | 1,220.00 |
| VCR | Margin | 2,646.00 | 2,851.00 | 2,142.00 |
| | Sales | 4,200.00 | 4,650.00 | 3,400.00 |
| | Total_Expenses | 1,180.00 | 1,415.00 | 895.00 |
| Camera | Margin | 2,023.00 | 2,874.50 | 1,707.00 |
| | Sales | 2,850.00 | 4,050.00 | 2,400.00 |
| | Total_Expenses | 1,495.00 | 1,856.00 | 1,301.00 |

Build the query by dragging dimension members or measures from the Dimensions panel to one of the following axes areas:

- **Columns**— Axis (0) of the query
- **Rows** — Axis (1) of the query
- **Slicer/POV**— The slicer axis enables you to limit a query to only a specific slice of the Essbase cube. This represents the optional WHERE clause of a query.
- **Pages** — Axis (2) of the query

You can nest dimension members in the Columns and Rows axes, but you can only add a single dimension to the Slider/POV axis.

Add Dimension Members to the Slicer/POV Axis

When you add a dimension to the Slicer/POV axis, the Member Selection dialog launches.

You can only select one dimension member for this axis. Simply select the dimension in the Member Selection dialog, and then click **OK**.

The Member Selection dialog doesn't display if you add a measure to the Slicer/POV axis.

Perform MDX Query Actions


The MDX Query Builder toolbar contains the following buttons for modifying the MDX query:

- Click **Swap Rows and Columns** to flip dimensions between columns and rows.
- Click **Actions** to display the following menu items for selection:

- **Select Cube** - Selects a different Essbase cube for the query.
- **Set Alias Table** - Selects the alias table used for dimension display names. Alias names are used for display only and are not used in the query.
- **Auto Refresh** - Displays the results as dimension members are placed in the Columns, Rows, Slicer/POV, and Pages axes and automatically refreshes the MDX query syntax.
- **Clear Results** - Clears the results and removes member selections from all of the axes and any filters added to the query.
- **Show Empty Columns** - Displays columns that do not contain data.
- **Show Empty Rows** - Displays rows that do not contain data.
- **Show Query** - Displays the MDX query syntax resulting from how the dimensions are placed in the Columns, Rows, Slicer/POV, and Pages axes.

Apply MDX Query Filters

You can create filters for dimensions on the Columns, Rows, and Pages axes in MDX Query Builder to further streamline your MDX query.



You can create multiple filters for a query, but you can only create one filter for each Columns, Rows, or Pages axis.

- To create a filter, click the down-arrow button to the right of a dimension in the Columns, Rows, or Pages axes to display it in the Filters area. You create the filter by selecting the desired dimension member as shown below.

Select MDX Query Options and Save MDX Queries

Use the Options dialog to select the dimension properties to include in the query for each of the dimensions in the Columns, Rows, and Pages axes.

To select the MDX query options and save the query:

1. Once you've built the query, click **Save** to display the Options dialog.
2. Select the dimension properties.

The dimension properties are as follows:

- **Member Alias** — Dimension member alias names as listed in the Essbase outline.
- **Ancestor Names** — Ancestor dimension names as listed in the Essbase outline.
- **Level Number** — Dimension level numbers as listed in the Essbase outline.
- **Gen Number** — Generation number of the dimensions as listed in the Essbase outline.

For example, if you select the Member Alias and Level Number properties for Columns, the MDX query results are as follows:

```
SELECT
NON EMPTY Hierarchize([Market].Generations(2).Members)
PROPERTIES MEMBER_ALIAS,LEVEL_NUMBER ON Axis(0),
NON EMPTY CROSSJOIN(Hierarchize([Product].Generations(3).Members),
{[Accounts].[Margin],[Accounts].[Sales],[Accounts].
[Total_Expenses]})ON Axis(1),
NON EMPTY [Year].Generations(3).Members ON Axis(2) FROM Demo.Basic
```

3. Click **OK** to return to the New Data Set - MDX Query dialog and review the MDX query output as shown below.
4. Click **OK** to return to the data model editor, and save your changes.

If you modify a MDX query after you save it in Publisher, Oracle recommends that you manually change the syntax and not use MDX Query Builder to do so.

Create a Data Set Using an Analysis

You can use the Oracle BI Presentation Catalog to select an analysis as a data source.

An analysis is a query against an organization's data that provides answers to business questions. A query contains the underlying SQL statements that are issued to the Oracle BI Server.

Hierarchical columns aren't supported in Publisher data models.

Create a data set using an analysis:

1. Click the **New Data Set** toolbar button and select **Analysis**.
2. In the New Data Set - Analysis dialog, enter a name for this data set.
3. Click the browse icon to connect to the Oracle BI Presentation Catalog.
4. When the catalog connection dialog launches, navigate through the folders to select the analysis to use as the data set for the report.
5. Enter a **Time Out** value in seconds. If Publisher hasn't received the analysis data after the time specified in the time out value has elapsed, then Publisher stops attempting to retrieve the analysis data.
6. Click **OK**.

Additional Notes on Analysis Data Sets

Parameters and lists of values are inherited from the analysis and are displayed at runtime.

The analysis must have default values defined for filter variables. If the analysis contains presentation variables with no default values, then you can't use it as a data source for reports in Publisher.

You can't use group breaks, group filters, data links and group-level functions when structuring data based on data sets for an analysis. You can use global-level functions and you can set values for null elements.

Create a Data Set Using a View Object

Publisher enables you to connect to your custom applications built with Oracle Application Development Framework and use view objects in your applications as data sources for reports.

Performance of the query execution is better as the SQL is executed directly against the database.

Before you can create an Publisher data model using a view object, you must first create the view object in your application.

1. Click the **New Data Set** toolbar button and select **View Object**.
2. In the New Data Set - View Object dialog, enter a name for this data set.
3. Select the Data Source from the list. The data sources that you defined in the `providers.xml` file display.
4. Do one of the following:
 - Select **Yes** for **Execute as SQL** to extract the SQL query form the View Object and execute it on the Oracle Analytics Server domain.
 - Select **No** to execute the view object on the Oracle Applications domain through the ADF layer. The XML data is then streamed to the Oracle Analytics Server domain in chunks. This method results in poorer performance, but enables execution on the Applications domain. You can invoke some service interface layers to allow custom data manipulation.
5. Enter the fully qualified name of the application module, for example, `example.apps.pa.entity.applicationModule.AppModuleAM`.
6. Click **Load View Objects**.

Publisher calls the application module to load the view object list.
7. Select the **View Object**.

Any bind variables defined are retrieved.
8. Create a parameter to map to this bind variable.
9. Click **OK** to save your data set.

Additional Notes on View Object Data Sets

To structure data based on view object data sets, the group breaks, data links and group-level functions are not supported.

The following is supported: Setting the value for elements if null.

For more information about this supported feature, see [Structure Data](#).

Create a Data Set Using a Web Service

Publisher supports data sets that use simple and complex web service data sources to return valid XML data. Only document/literal web services are supported.

It's recommended that you define your parameters first, so that the methods are available for selection when setting up the data source. The parameters must be set up in the Parameters section of the report definition.

Multiple parameters are supported. Ensure the method name is correct and the order of the parameters matches the order in the method. To call a method in the web service that accepts two parameters, you must map two parameters defined in the report to the two parameters in the method. Note that only parameters of simple type are supported, for example, string and integer.

Web Service Data Source Options

Administrator can set up a web service data as a data source.

- Administrator can set up connections to web service data sources and then you can use the data source in multiple data models.
- You can set up a private connection accessible only to you. See [Manage Private Data Sources](#) for information about private data source connections.

You must set up the connection before you create the data model.

Publisher supports data sets that use simple and complex web service data sources to return valid XML data.

Create a Data Set Using a Simple Web Service

If you aren't familiar with the available methods and parameters in the web service to call, you can open the URL in a browser to view them.

To create a data set by using a simple web service:

1. Click the **New Data Set** toolbar button, and then select **Web Service**.
2. Enter the data set name.
3. Select the data source and the method.
4. Click **OK**.
5. On the Data Model pane, select **Parameters**, click **Create New Parameter**, and define the parameters to make them available to the web service data set.
6. Edit the web service data set and add the parameters to the data set.

7. Click **Save**.

Create a Data Set Using a Complex Web Service

You can use complex web service data sources to return valid XML data. A complex web service type internally uses `soapRequest /soapEnvelope` to pass the parameter values to the destination host.

To create a data set by using a complex web service:

1. Click the **New Data Set** toolbar button, and then select **Web Service**.
2. Enter the data set name, data source, and the method.

The methods available for selection are based on the complex web service data source. When you select a method, the **Parameters** are displayed. To view optional parameters, select **Show optional parameters**.

If you aren't familiar with the available methods and parameters in the web service, open the WSDL URL in a browser to view them.

3. If the start of the XML data for the report is deeply embedded in the response XML generated by the web service request, in the **Response Data XPath** field, specify the path to the data to use in the report.
4. Add the parameters required for the web service.
5. Test the web service.

Additional Information on Web Service Data Sets

There's no metadata available from web service data sets, therefore grouping and linking are not supported.

Create a Data Set Using a XML File

You can use an XML file to create a data source.

Do one of the following:

- Place the XML file in a directory that your administrator has set up as a data source.
- Upload the XML file to the data model from a local directory.

To use layout editor and interactive viewer, save sample data from the XML file source to the data model.

About Supported XML Files

Support of XML files as a data set type in Publisher follows certain guidelines.

- The XML files that you use as input to the Publisher data engine must be UTF-8 encoded.
- Do not use the following characters in XML tag names: `~, !, #, $, %, ^, &, *, +, `, |, :, \", \\, <, >, ?, ,, /`. If your data source file contains any of these characters, use the data model editor Structure tab to change the tag names to an acceptable one.

- Use valid XML files. Oracle provides many utilities and methods for validating XML files.
- There's no metadata available from XML file data sets, therefore grouping and linking are not supported.

Upload a XML File Stored Locally

You can create data sets using locally stored XML files.


To create a data set using a XML file stored locally:

1. On the toolbar, click **New Data Set** and select **XML File**.
2. Enter a name for this data set.
3. Select **Local** to enable the Upload button.
4. Click **Upload** next to the **File Name** field to browse and upload the XML file from a local directory. If the file has been uploaded to the data model, you can select it from the **File Name** list.
5. Click **Upload**.
6. Click **OK**.
7. (Required) Save sample data to the data model.

Refresh and Delete an Uploaded XML File

You can refresh and delete uploaded local XML files.

After uploading the file, it's displayed on the **Properties** pane of the data model under the **Attachments** region, as shown below.



To refresh the local file in the data model:

1. In the component pane, click **Data Model** to view the Properties page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Refresh**.

4. In the Upload dialog, browse for and upload the latest version of the file. The file must have the same name or it won't replace the older version.
5. Save the data model.

To delete the local file:

1. In the component pane, click **Data Model** to view the Properties page.
2. In the **Attachment** region of the page, locate the file in the Data Files list.
3. Click **Delete**.
4. Click **OK** to confirm.
5. Save the data model.

Create a Data Set Using a Content Server


You can set up connections to Content Server data source on the Administration page and then use that in multiple data models.

You must set up the connection before you create a data model. Create a data model by creating the SQL Query data set (required) first and then create the Content Server data set.

1. Click the New Data Set toolbar button and select **Content Server**.

In the New Data Set, Content Server dialog do the following:

2. Enter a name for the data set in the **Name** field.
3. Select the content server data source in the **Data Source** field.
4. Select the **Parent Group** from the LOV.
5. Select the **Document ID** from the LOV.
6. Select the **Content Type** from the LOV.



7. Click **OK**.

Create a Data Set Using a Microsoft Excel File

These topics describe requirements, options, and procedures for using Microsoft Excel files as a data source.

- [About Supported Excel Files](#)
- [Access Multiple Tables per Sheet](#)
- [Use a Microsoft Excel File Stored in a File Directory Data Source](#)
- [Upload a Microsoft Excel File Stored Locally](#)

About Supported Excel Files

Support of Microsoft Excel files as a data set type in Publisher follows certain guidelines.

- Save Microsoft Excel files in the Excel 97-2003 Workbook (*.xls) format by Microsoft Excel. Files created by a third party application or library are not supported.
- The source Excel file can contain a single sheet or multiple sheets.
- Each worksheet can contain one or multiple tables. A table is a block of data that is located in the continuous rows and columns of a sheet.

In each table, Publisher always considers the first row to be the heading row for the table.

- The first row under the heading row must not be empty and is used to determine the column type of the table. The data type of the data in the table may be number, text, or date/time.
- If multiple tables exist in a single worksheet, the tables must be identified with a name for Publisher to recognize each one. See [Access Multiple Tables per Sheet](#).
- If all tables in the Excel file are not named, only the data in the first table is recognized and fetched.
- When the data set is created, Publisher truncates all trailing zeros after the decimal point for numbers in all cases. To preserve the trailing zeros in your final report, you must apply a format mask in your template to display the zeroes.
- Single value parameters are supported, but multiple value parameters are not supported.

Access Multiple Tables per Sheet


If the Microsoft Excel worksheet contains multiple tables that you want to include as data sources, then you must define a name for each table in Microsoft Excel.

The name that you define must begin with the prefix: *BIP_*, for example, *BIP_SALARIES*.

To access multiple tables per sheet:

1. Insert the table in Microsoft Excel.
2. Select the table and define a name that is prefixed with *BIP_*.

For example, you could use the Define Name command in Microsoft Excel 2007 to name a table *BIP_Salaries*.




Use a Microsoft Excel File Stored in a File Directory Data Source

Create data sets using Microsoft Excel files stored in file directories.

Note that to include parameters for your data set, you define the parameters first, so that they're available for selection when defining the data set. The Excel data set type supports one value per parameter. It doesn't support multiple selection for parameters.

To create a data set using a Microsoft Excel file from a file directory data source:

1. Click the **New Data Set** toolbar button and select **Microsoft Excel File**. The New Data Set - Microsoft Excel File dialog launches.
2. Enter a name for this data set.
3. Click **Shared** to enable the Data Source list.
4. Select the data source where the Microsoft Excel File resides.
5. To the right of the **File Name** field, click the browse icon to browse for the Microsoft Excel file in the data source directories. Select the file.
6. If the Excel file contains multiple sheets or tables, select the appropriate **Sheet Name** and **Table Name** for this data set, as shown below.



7. If you added parameters for this data set, click **Add Parameter**. Enter the **Name** and select the **Value**. The Value list is populated by the parameter Name defined in the Parameters section. Only single value parameters are supported.
8. Click **OK**.
9. Link the data from this query to the data from other queries or modify the output structure.


Upload a Microsoft Excel File Stored Locally

To use a local Microsoft Excel file as a data source, you first upload it.

Note that to include parameters for the data set, you define the parameters first, so that they're available for selection when defining the data set. The Excel data set type supports one value per parameter. It doesn't support multiple selection for parameters.

To create a data set using a Microsoft Excel file stored locally:

1. Click the **New Data Set** toolbar button and select Microsoft Excel File. The Create Data Set - Excel dialog launches.
2. Enter a name for this data set.
3. Select **Local** to enable the upload button.
4. Click the **Upload** icon to browse for and upload the Microsoft Excel file from a local directory. If the file has been uploaded to the data model, you can select it from the **File Name** list.
5. If the Excel file contains multiple sheets or tables, select the appropriate **Sheet Name** and **Table Name** for this data set, as shown below.




6. If you added parameters for this data set, click **Add Parameter**. Enter the **Name** and select the **Value**. The **Value** list is populated by the parameter **Name** defined in the **Parameters** section. Only single value parameters are supported.
7. Click **OK**.
8. Link the data from this query to the data from other queries or modify the output structure.

Refresh and Delete an Uploaded Excel File

You can refresh and delete uploaded local Excel files.

After uploading the file, it's displayed on the **Properties** pane of the data model under the **Attachments** region, as shown below.



To refresh the local file in the data model:

1. Click **Data Model** in the component pane to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Refresh**.
4. In the **Upload** dialog, browse for and upload the latest version of the file. The file must have the same name or it won't replace the older version.
5. Save the data model.

To delete the local file:

1. Click **Data Model** in the component pane to view the **Properties** page.
2. In the **Attachment** region of the page, locate the file in the **Data Files** list.
3. Click **Delete**.
4. Click **OK** to confirm.
5. Save the data model.

Create a Data Set Using a CSV File

Publisher supports data sets that use CSV file data sources to return valid XML data.

The following topics describe using requirements and procedures for using a CSV as a data source:

- [About Supported CSV Files](#)
- [Create a Data Set from a Centrally Stored CSV File](#)
- [Upload a CSV File Stored Locally](#)

About Supported CSV Files

Support of CSV files as a data set type in Publisher follow certain guidelines.


- You can use a CSV file that is located in a directory that your administrator has set up as a data source.
You can upload a file from a local directory.
- The supported CSV file delimiters are Comma, Pipe, Semicolon, and Tab.
- If your CSV file contains headers, the header names are used as the XML tag names. The following characters aren't supported in XML tag names: ~, !, #, \$, %, ^, &, *, +, -, |, :, \", \\, <, >, ?, ,, /. If your data source file contains any of these characters in a header name, use the data model editor Structure tab to edit the tag names.
- CSV data sets support editing the data type assigned by the data model editor. See [Edit the Data Type](#). If you update the data type for an element in the data set, you must ensure that the data in the file is compliant with the data type that you selected.
- The CSV files that you use as input to the Publisher data engine must be UTF-8 encoded and cannot contain empty column headers.
- Group breaks, data links, expression and group-level functions aren't supported.

- Data fields in CSV files must use the canonical ISO date format for mapped date elements, for example, 2012-01-01T10:30:00-07:00, and #####.## for mapped number elements.
- CSV files aren't validated.

Create a Data Set from a Centrally Stored CSV File

You can use a CSV file from a file directory to create a data set.

1. On the data model editor toolbar, click **New Data Set** and select **CSV File**. The New Data Set - CSV File dialog launches.




2. Enter a name for this data set.
3. Click **Shared** to enable the Data Source list.
4. Select the **Data Source** where the CSV file resides.
The list is populated from the configured File Data Source connections.
5. Click **Browse** to connect to the data source, browse the available directories, and select the file.
6. Select **The first row a column header** to specify if the first row in the file contains column names.
If you do not select this option, the columns are assigned a generic name, for example, *Column1*, *Column2*. You can edit the XML tag names and display names in the data model editor Structure tab.
7. Select the **CSV delimiter** used in the file.
The default selection is Comma (,).
8. Click **OK**.

Upload a CSV File Stored Locally

Create data sets using CSV files stored in local file directories.

To create a data set using a CSV file stored locally:

1. On the toolbar, click **New Data Set** and select **CSV File**. The New Data Set - CSV File dialog launches, as shown below.



2. Enter a name for this data set.
3. Select **Local** to enable the Upload button.
4. Click **Upload** to browse for and upload the CSV file from a local directory.
5. Optional: Select **The first row a column header** to specify if the first row in the file contains column names. If you don't select this option, the columns are assigned a generic name, for example, Column1, Column2. The XML tag names and display names assigned can be edited in the data model editor Structure tab.
6. Select the **CSV Delimiter** used in the file. The default selection is Comma (,).
7. Click **OK**.

Edit the Data Type

After uploading a CSV file data type, you can edit it as needed.

To edit the data type for a CSV file element, click the data type icon or update it from the element Properties dialog.


The data for an element must be compliant with the data type that you assign. The user interface doesn't validate the data when you update the data type. If the data doesn't match, for example, a string value is present for an element you defined as Integer, errors may occur in the layout editing tools and or at runtime.

You can only update the data types for CSV file data sources.

Refresh and Delete an Uploaded CSV File

You can refresh and delete uploaded local CSV files.

After uploading the file, it is displayed on the Properties pane of the data model under the Attachments region, as shown below.



To refresh the local file in the data model:

1. In the component pane, click **Data Model** to view the Properties page.
2. In the Attachment region of the page, locate the file in the Data Files list.
3. Click **Refresh**.
4. In the Upload dialog, browse for and upload the latest version of the file. The file must have the same name or it won't replace the older version.
5. Save the data model.

To delete the local file:

1. In the component pane, click **Data Model** to view the Properties page.
2. In the Attachment region of the page, locate the file in the Data Files list.
3. Click **Delete**.
4. Click **OK** to confirm.
5. Save the data model.

Create a Data Set from an HTTP XML Feed

Using the HTTP (XML Feed) data set type, you can create data models from RSS and XML feeds over the Web by retrieving data through the HTTP GET method.

To include parameters for the data set, it's recommended that you define the parameters first, so that they're available for selection when you define the data set. See [Add Parameters and Lists of Values](#).


There's no metadata available from HTTP XML feed data sets, therefore grouping and linking aren't supported.

You might require additional configuration to access external data source feeds depending on your system's security. For example, if the RSS feed is protected by Secure Sockets Layer (SSL).

Create a Data Set from an HTTP XML Data Set

You can set up an HTTP (XML Feed) data sources in two different ways.

- On the Administration page:
Connections to HTTP data sources can be set up on the Administration page and then used in multiple data models.
 - As a private data source:
You can also set up a private connection accessible only to you.
1. On the toolbar, click **New Data Set** and select **HTTP (XML Feed)**. The New Data Set - HTTP (XML Feed) dialog launches, as shown below.



The screenshot shows a dialog box titled "New Data Set - HTTP (XML Feed)". It has the following fields and controls:

- * Name:** A text input field containing "News".
- * Data Source:** A dropdown menu showing "EMTest" with a refresh icon to its right.
- * URL Suffix:** A text input field containing "http://rss.news.yahoo.com/rss/topstories".
- Method:** A dropdown menu showing "GET".
- Parameters:** A section with an "Add Parameter" button and a table with two columns: "Name" and "Value (Parameter)".
- At the bottom right, there are "OK" and "Cancel" buttons.

2. Enter a name for this data set.
3. Select a data source.
4. Enter the URL Suffix for the source of the RSS or XML feed.
5. Select the Method: GET.
6. To add a parameter, click **Add Parameter**. Enter the **Name** and select the **Value**. The **Value** list is populated by the parameter **Name** defined in the **Parameters** section.
7. Click **OK** to close the data set dialog.

Use Data Stored as a Character Large Object (CLOB) in a Data Model

Publisher supports using data stored as a character large object (CLOB) data type in your data models. This feature enables you to use XML data generated by a separate process and stored in your database as input to a Publisher data model.

Use the Query Builder to retrieve the column in your SQL query, then use the data model editor to specify how you want the data structured. When the data model is executed, the data engine can structure the data either as:


- A plain character set within an XML tag name that can be displayed in a report (for example, an Item Description)
- Structured XML

Ensure that your data doesn't include line feeds or carriage returns. Line feeds and carriage returns in your data may not render as expected in the report layouts.


To create a data set from data stored as a CLOB:

1. On the toolbar, click **New Data Set** and then select **SQL Query**. The New Data Set - SQL Query dialog launches.
2. Enter a name for the data set.
3. If you are not using the default data source for this data set, select the **Data Source** from the list.
4. Enter the SQL query or use the **Query Builder** to construct your query to retrieve the CLOB data column.

For example, you could create a query in which the CLOB data is stored in a column named "DESCRIPTION".



5. After entering the query, click **OK** to save. Publisher validates the query.
6. By default, the data model editor assigns the CLOB column the "CLOB" data type. To change the data type to XML, click the data type icon and select XML.



How the Data Is Returned

When you execute the query, if the CLOB column contains well-formed XML, and you select the XML data type, the data engine returns the XML data, structured within the CLOB column tag name.

Example output when data type is XML:

Note the <DESCRIPTION> element contains the XML data stored in the CLOB column, as shown below.

```

- <DATA_DS>
  - <G_1>
    <EMPLOYEE_ID>102</EMPLOYEE_ID>
  - <DESCRIPTION>
    - <DATA_DS>
      - <G_Q1>
        <DEPTNO>10</DEPTNO>
        <DNAME>PURCHASE</DNAME>
        <LOC>HQ</LOC>
      - <G_Q2>
        <DEPTNO_1>10</DEPTNO_1>
        <EMPNO>10001</EMPNO>
        <ENAME>SCOTT</ENAME>
        <SAL>5000</SAL>
      </G_Q2>
      + <G_Q2></G_Q2>
    </G_Q1>
  - <G_Q1>
    <DEPTNO>20</DEPTNO>
    <DNAME>FINANCE</DNAME>
    <LOC>HQ</LOC>
  
```

Example output when data type is CLOB:

If you select to return the data as the CLOB data type, the returned data is structured as shown below.

```

-<DATA_DS>
  -<G_1>
    <EMPLOYEE_ID>102</EMPLOYEE_ID>
    -<DESCRIPTION>
      <DATA_DS> <G_Q1> <DEPTNO>10</DEPTNO>
      <DNAME>PURCHASE</DNAME> <LOC>HQ</LOC> <G_Q2> <DEPTNO_1>10</DEPTNO_1>
      <EMPNO>10001</EMPNO> <ENAME>SCOTT</ENAME> <SAL>5000</SAL> </G_Q2> <G_Q2>
      <DEPTNO_1>10</DEPTNO_1> <EMPNO>10002</EMPNO> <ENAME>SMITH</ENAME>
      <SAL>3000</SAL> </G_Q2> </G_Q1> <G_Q1> <DEPTNO>20</DEPTNO>
      <DNAME>FINANCE</DNAME> <LOC>HQ</LOC> <G_Q2> <DEPTNO_1>20</DEPTNO_1>
      <EMPNO>10003</EMPNO> <ENAME>AMY</ENAME> <SAL>5500</SAL> </G_Q2> <G_Q2>
      <DEPTNO_1>20</DEPTNO_1> <EMPNO>10004</EMPNO> <ENAME>MARLIN</ENAME>
      <SAL>4000</SAL> </G_Q2> </G_Q1> <G_Q1> <DEPTNO>30</DEPTNO>
      <DNAME>CORPORATE</DNAME> <LOC>HQ</LOC> </G_Q1> </DATA_DS>
    </DESCRIPTION>
  </G_1>
</DATA_DS>

```

Additional Notes on Data Sets Using CLOB Column Data

More information is available on CLOB column data.

For specific notes on using CLOB column data in a bursting query, see [Use SQL Query to Add a Bursting Definition to Your Data Model](#).

Handle XHTML Data Stored in a CLOB Column

Data from the XHTML documents stored in a database CLOB column can render the markup in the generated report.

To enable the report rendering engine to handle the markup tags, you must wrap the XHTML data in a CDATA section within the XML report data that's passed by the data engine.

It's recommended that you store the data in the database wrapped with the CDATA section. You can then use a simple select statement to extract the data. If the data isn't wrapped in the CDATA section, then you must include in your SQL statement instructions to wrap it.

The following sections describe how to extract XHTML data in each case:

- [Retrieve XHTML Data Wrapped in CDATA](#)
- [Wrap the XHTML Data in CDATA in the Query](#)

Only the RTF templates support rendering of the HTML markup in a report.

Retrieve XHTML Data Wrapped in CDATA

This exercise assumes you have the following data stored in a database column called "CLOB_DATA".

```

<![CDATA[
<p><font style="font-style: italic; font-weight: bold;" size="3">
<a href="http://www.oracle.com">oracle</a></font> </p>
<p><font size="6"><a href="http://docs.oracle.com/">Oracle
Documentation</a>


```

```
</font></p>
]]>
```

Retrieve the column data using a simple SQL statement, for example:

```
select CLOB_DATA as "RTECODE" from MYTABLE
```

In the data model editor, set the data type of the **RTECODE** column to **XML**, as shown below.



Wrap the XHTML Data in CDATA in the Query

This exercise assumes that you've the following data stored in a database column called "CLOB_DATA".

```
<p><font style="font-style: italic; font-weight: bold;" size="3">
<a href="http://www.oracle.com">oracle</a></font> </p>
<p><font size="6"><a href="http://docs.oracle.com/">Oracle
Documentation</a>
</font></p>
```

Use the following syntax in your SQL query to retrieve it and wrap it in the CDATA section:

```
select '<![CDATA' || '[' || CLOB_DATA || ']' || '>' as "RTECODE" from
MYTABLE
```

In the data model editor, set the data type of the **RTECODE** column to **XML**.

Test Data Models and Generate Sample Data

The data model editor enables you to test your data model and view the output to ensure your results are as expected.

After running a successful test, you can choose to save the test output as sample data for your data model. You can also use the Export feature to export sample data to a file. If your data model fails to run, you can view the data engine log.

To test your data model:

1. In the data model editor, select the **Data** tab, as shown below.



2. For SQL Query, Analysis, and View Object data sets: On the Data tab, select the number of rows to return. If you included parameters, enter the desired values for the test.
3. Click **View** to display the XML that is returned by the data model.
4. Select one of the following options to display the sample data:
 - Use **Tree View** to view the sample data in a data hierarchy. This is the default display option.
 - Use **Table View** to view the sample data in a formatted table like you see in Publisher reports.

You can create a report based on this data model.

To save the test data set as sample data for the data model:

1. After the data model has successfully run, click **Save as Sample Data**. The sample data is saved to the data model.

To export the test data:

1. For SQL Query, Analysis, and View Object data sets: On the Data tab, select the number of rows to return.
2. After the data model has successfully run, click **Export**. You are prompted to open or save the file to a local directory.

To view the data engine log:

1. Click **View Data Engine Log**. You are prompted to open or save the file to a local directory. The data engine log file is an XML file.

To test UCM dataset:


For Content Server, based on the document ID and the content type, the document content is retrieved from the content (UCM) server. However, if the Document ID is empty or null, then the document content will be empty.

Edit an Existing Data Set

You can modify data models by editing the data sets of a data model.

To edit an existing data set:

1. On the component pane of the data model editor, click **Data Sets**. All data sets of this data model is displayed.
2. Click the data set that you want to edit.
3. Click **Edit Selected Data Set**. The dialog for the data set opens.



4. Make changes to the data set and click **OK**.
5. Save the data model.
6. Test your edited data model and add new sample data.

Include User Information Stored in System Variables in Your Report Data

Publisher stores information about the current user that can be accessed by your report data model.

The user information is stored in system variables as described below.

| System Variable | Description |
|---------------------------------|---|
| xdo_user_name | User ID of the user submitting the report. For example: Administrator |
| xdo_user_roles | Roles assigned to the user submitting the report. For example: XMLP_ADMIN, XMLP_SCHEDULER |
| xdo_user_report_oracle_language | Report language from the user's account preferences. For example: ZHS |
| xdo_user_report_locale | Report locale from the user's account preferences. For example: en-US |
| xdo_user_ui_oracle_lang | User interface language from the user's account preferences. For example: US |
| xdo_user_ui_locale | User interface locale from the user's account preferences. For example: en-US |

Publisher populates the system variables in an online report. In a scheduled job, Publisher doesn't populate the XDO_USER_REPORT_LOCALE, XDO_USER_UI_LOCALE, and XDO_USER_UI_ORACLE_LANG system variables.

Add the User System Variables as Elements

To add the user information to the data model, you can define the variables as parameters and then define the parameter value as an element in your data model.

You can also simply add the variables as parameters then reference the parameter values in your report.

The following query:

```
select
:xdo_user_name as USER_ID,
:xdo_user_roles as USER_ROLES,
:xdo_user_report_oracle_lang as REPORT_LANGUAGE,
:xdo_user_report_locale as REPORT_LOCALE,
:xdo_user_ui_oracle_lang as UI_LANGUAGE,
:xdo_user_ui_locale as UI_LOCALE
from dual
```

returns the following results:

```
<?xml version="1.0" encoding="UTF-8"?>
<!-- Generated by Publisher -->
<DATA_DS>
<G_1>
<USER_ROLES>XMLP_TEMPLATE_DESIGNER, XMLP_DEVELOPER,
XMLP_ANALYZER_EXCEL, XMLP_ADMIN, XMLP_ANALYZER_ONLINE, XMLP_SCHEDULER </
USER_ROLES>
<REPORT_LANGUAGE>US</REPORT_LANGUAGE>
<REPORT_LOCALE>en_US</REPORT_LOCALE>
<UI_LANGUAGE>US</UI_LANGUAGE>
<UI_LOCALE>en_US</UI_LOCALE>
<USER_ID>administrator</USER_ID>
</G_1>
</DATA_DS>
```

Sample Use Case: Limit the Returned Data Set by User ID

The following example limits the data returned by the user ID.

```
select EMPLOYEES.LAST_NAME as LAST_NAME,
EMPLOYEES.PHONE_NUMBER as PHONE_NUMBER,
EMPLOYEES.HIRE_DATE as HIRE_DATE,
:xdo_user_name as USERID
from HR.EMPLOYEES EMPLOYEES
where lower(EMPLOYEES.LAST_NAME) = :xdo_user_name
```

Notice the use of the lower() function, the xdo_user_name is always be in lowercase format. Publisher doesn't have a USERID so you must use the user name and either use it directly in the query; or alternatively you could query against a lookup table to find a user id.

Create Bind Variables from LDAP User Attribute Values

To bind user attribute values stored in your LDAP directory to a data query you can define the attribute names to Publisher to create the bind variables required.

Prerequisite

The attributes that can be used to create bind variables must be defined in the Security Configuration page by an administrator.

The attributes are defined in the Attribute Names for Data Query Bind Variables field of the LDAP Security Model definition. Any attribute defined for users can be used (for example: memberOf, sAMAccountName, primaryGroupID, mail).

How Publisher Constructs the Bind Variable

You can reference the attribute names that you enter in the **Attribute Names for Data Query Bind Variables** field of the LDAP Security Model definition in the query.

The following shows how bind variables are constructed:

```
xdo_<attribute name>
```

Assume that you've entered the sample attributes: memberOf, sAMAccountName, primaryGroupID, mail. These can then be used in a query as the following bind variables:

```
xdo_memberof  
xdo_SAMACCOUNTNAME  
xdo_primaryGroupID  
xdo_mail
```

Note that the case of the attribute is ignored; however, the "xdo_" prefix must be lowercase.

Use these in a data model as follows:

```
SELECT  
:xdo_user_name AS USER_NAME,  
:xdo_user_roles AS USER_ROLES,  
:xdo_user_ui_oracle_lang AS USER_UI_LANG,  
:xdo_user_report_oracle_lang AS USER_REPORT_LANG,  
:xdo_user_ui_locale AS USER_UI_LOCALE,  
:xdo_user_report_locale AS USER_REPORT_LOCALE,  
:xdo_SAMACCOUNTNAME AS SAMACCOUNTNAME,  
:xdo_memberof as MEMBER_OF,  
:xdo_primaryGroupID as PRIMARY_GROUP_ID,  
:xdo_mail as MAIL  
FROM DUAL
```

The LDAP bind variables return the values stored in the LDAP directory for the user that's logged in.

3

Structure Data

This topic describes techniques for structuring the data that is returned by Publisher's data engine, including grouping, linking, group filters, and group-level and global-level functions.

Topics:

- [Work with Data Models](#)
- [Features of the Data Model Editor](#)
- [About the Interface](#)
- [Create Links Between Data Sets](#)
- [Create Element-Level Links](#)
- [Create Subgroups](#)
- [Move an Element Between a Parent Group and a Child Group](#)
- [Create Group-Level Aggregate Elements](#)
- [Create Group Filters](#)
- [Perform Element-Level Functions](#)
- [Set Element Properties](#)
- [Sort Data](#)
- [Perform Group-Level Functions](#)
- [Perform Global-Level Functions](#)
- [Use the Structure View to Edit Your Data Structure](#)
- [Function Reference](#)

Work with Data Models


The Data Model diagram helps you to quickly and easily define data sets, break groups, and totals for a report based on multiple data sets.

- [About Multipart Unrelated Data Sets](#)
- [About Multipart Related Data Sets](#)
- [Guidelines for Working with Data Sets](#)

About Multipart Unrelated Data Sets

If you don't link the data sets (or queries), the data engine produces a multipart unrelated query data set.

For example, in the data model, image shown below, one query selects *products* and another selects *customers*. There's no relationship between the products and customers.



The result is shown in the data structure as depicted in the following image.


The screenshot shows the Oracle Data Modeler interface with the 'Structure' tab selected. Below the tabs, there are two views: 'Table View' and 'Output'. The 'Output' view is active and displays two columns: 'XML output' and 'Descriptive XML output'. Both columns show a hierarchical tree structure starting with 'DATA_DS', which branches into 'G_1' and 'G_2'. Under 'G_1', the following attributes are listed: PRODUCT_ID, PRODUCT_NAME, CATEGORY_ID, SUPPLIER_ID, PRODUCT_STATUS, and LIST_PRICE. Under 'G_2', the following attributes are listed: CUSTOMER_ID, CUST_FIRST_NAME, CUST_LAST_NAME, CUST_ADDRESS, PHONE_NUMBERS, CUST_EMAIL, and ACCOUNT_MGR_ID.

About Multipart Related Data Sets


Data fetched for one part of a data set or query can be determined by the data fetched for another part. The result is often called a *master/detail*, or *parent/child* relationship that's defined with a data link between two data sets or queries.

When you run a master/detail data model, each row of the master (or parent) query executes a query against the detail (or child) to retrieve only matching rows.

In the example, image below, two data sets are linked by the element Customer ID. The Orders data set is a child of the Customers data set.



The example produces the data structure shown in the following image.



Guidelines for Working with Data Sets

Certain guidelines are recommended for building data models.

- Reduce the number of data sets or queries in your data model as much as possible. In general, the fewer data sets and queries you have, the faster your data model will run. While multi-query data models are often easier to understand, single-query data models tend to execute more quickly. It's important to understand that in parent-child queries, for every parent, the child query is executed.
- You should only use multi-query data models in the following scenarios:
 - To perform functions that the query type, such as a SQL query, doesn't support directly.

- To support complex views, for example, distributed queries or GROUP BY queries.
- To simulate a view when you don't have or want to use a view.

Create Links Between Data Sets

You can use the Publisher data engine to combine and structure data after you extract it from the data source.

Joining and structuring data at the source into one combined data set is sometimes not possible. For example, you cannot join data at the source when data resides in disparate sources such as Microsoft SQL Server and an Oracle Database. Even if your data is coming from the same source, if you are creating large reports or documents with potentially hundreds of thousands of rows or pages, structuring your data so that it matches the intended layout optimizes document generation.

Create a link to define a master-detail or parent-child relationship between two data sets. You can create links as element-level links. Group-level links are provided for backward compatibility with data templates from earlier versions of Publisher. For the migrated data sets, delete the group links and create element links. If you create group-level links between data sets, your data can get corrupted.

A data link or parent-child relationship relates the results of multiple queries. A data link can establish these relationships:

- Between one query's column and another query's column.
- Between one query's group and another query's group, useful when you want the child query to know about its parent's data.

About Element-Level Links

Element-level links create a bind (join) between two data sets and define a master-detail (parent-child) relationship between them.

Create element-level links, the preferred method, to define master detail relationships between data sets. When you use element-level links to link data sets, you do not need to code a join between the two data sets through a bind variable.


Create Element-Level Links

Link data sets to define a master-detail or parent-child relationship between two data sets.

Defining an element-level link enables you to establish the binding between the elements of the master and detail data sets.

1. Open the element action menu and click **Create Link**.
2. In the Create Link dialog, choose the element, and click **OK** to create the link.

The Create Link dialog is shown below.



Delete Element-Level Links

You can delete both group-level and element-level links between data sets.

- Do one of the following:
 - Open the element action menu for either element and click **Delete Link**
 - Select the element connector to display the linked element names and click the delete button.

Delete Group-Level Links

You can delete both group-level and element-level links between data sets.


1. In the parent group, click **Menu**.
2. Click **Delete Group Link**.
3. In the **Delete Group Link** dialog, select the **Child Group** from the list and click **OK**.

Create Subgroups


In addition to creating parent-child structures by linking two data sets, you can also group elements in the same data set by other elements.

Creating subgroups might be helpful if your query returns data that has header data repeated for each detail row. By creating a subgroup you can shape the XML data for better, more efficient document generation.

1. Select the element to group with the other elements in the data set.
2. Click the element action menu icon to open the menu and select **Group by** as shown.



This creates a new group within the displayed data set. The following figure shows the G_2 data set grouped by the element COMPANY. This creates a new group called G_3 that contains the other five elements in the data set. The following figure shows how the grouped data set is displayed in the Diagram View along with the structure.



XML output

```

└─ DATA_DS
  └─ G_2
    └─ COMPANY
      └─ G_3
        └─ OFFICE
          └─ OFFICE_DESCRIPTION
            └─ ORGANIZATION
              └─ DEPARTMENT
                └─ LANGUAGE_ID
  
```

You can perform any of the group actions on the group you've created.

3. To ungroup, click **Menu** on the group's title bar, and then click **Ungroup**.


Move an Element Between a Parent Group and a Child Group

Once you've created a group within your data set, two new options display on the element action menu that enable you to move elements between the parent and child groups.

For the element that you want to move, click the element action icon to open the menu. If the element is in the parent group and you want to move it to the child group, select **Move selected elements to Child Group**.

If the element is in the child group and you want to move it to the parent group, select **Move selected elements to Parent Group**. In the figure below, the element action menu for OFFICE_DSC displays the option to move the element to the parent group.

Before moving an element be aware of any dependencies on other elements.



Create Group-Level Aggregate Elements


You can use the data model editor to aggregate data at the group or report level.

For example, if you group sales data by Customer Name, you can aggregate sales to get a subtotal for each customer's sales. You can only aggregate data at the parent level for a child element.

The aggregate functions are:


- **Average** - Calculates the average of all the occurrences of an element.
 - **Count** - Counts the number of occurrences of an element.
 - **First** - Displays the value of the first occurrence of an element in the group.
 - **Last** - Displays the value of the last occurrence of an element in the group.
 - **Maximum** - Displays the highest value of all occurrences of an element in the group.
 - **Minimum** - Displays the lowest value of all occurrences of an element in a group.
 - **Summary** - Sums the value of all occurrences of an element in the group.
1. Drag the element to the **Drop here for aggregate function** field in the parent group.

The figure below shows creating a group-level aggregate function in the G_DEPT based on the SALARY element.




Once you drop the element, a new element is created in the parent group. By default, the Count function is applied. The icon next to the name of the new aggregate element indicates the function. Pause your cursor over the icon to display the function.


The figure below shows the new aggregate element, CS_1, with the default Count function defined.




2. To change the function, click the function icon to view a list of available functions and choose from the list, as shown below.



3. To rename the element or update other properties, click the element's **Action** menu icon. Check if the element has a dependency on other elements, before renaming it.



On the menu, click **Properties**. The Properties dialog is shown below.



4. On the Edit Properties dialog, set the properties as needed.

- **Column Name** - The internal name assigned to the element by the Publisher data model editor. This name cannot be updated.
- **Alias (XML Tag Name)** - Publisher assigns a default tag name for the element in the XML data file. You can update this tag name to assign a more user-friendly name within the data file.
- **Display Name** - The Display Name appears in the report design tools. Update this name to be meaningful to your business users.
- **Function** - If you haven't already selected the desired function, then you can select it from the list here.
- **Data Type** - Publisher assigns a default data type of Integer or Double depending on the function. Some functions also provide the option of Float.
- **Value if Null** - If the value returned from the function is null, you can supply a default value here to prevent having a null in your data.
- **Round** - By default, the value is rounded to the nearest third decimal. You can change the round value, if needed.
- **Do Not Reset** - By default, the function resets at the group level. For example, if your data set is grouped by DEPARTMENT_ID, and you've defined a sum function for SALARY, then the sum is reset for each group of DEPARTMENT_ID data, giving you the sum of SALARY for that department only. If instead you want the function to reset only at the global level, and not at the group level, select **Do Not Reset**. This creates a running total of SALARY for all departments. This property is for group level functions only.

Create Group Filters

Filters enable you to conditionally remove records selected by your queries.

Groups can have two types of filters:

- Expression — Create an expression using predefined functions and operators
- PL/SQL Function — Create a custom filter

After you add a group filter, the data set object displays the filter indicator.

To create group filters:

1. Click **Menu**, and then select **Create Group Filter**.
2. Select the Group Filter Type: **Expression** or **PL/SQL**. For PL/SQL filters, ensure that you specify the PL/SQL Package as the **Oracle DB Default Package** in the data model properties.
3. Enter the Filter:
 - To enter an expression, select the elements and move the elements to the Group Filter definition box. Click the predefined functions and operators to insert them in the Group Filter box. Click **Validate Expression** to ensure that the entry is valid.
 - To enter a PL/SQL function, select the PL/SQL package from the Available box and move the function to the Group Filter box. Your PL/SQL function in the default package must return a Boolean type.

Perform Element-Level Functions

You can perform various functions at the element level.

- Group by an element to create a subgroup, as described in [Create Subgroups](#)
- Create element-level links between data sets, as described in [Create Element-Level Links](#)
- Set element properties, as described in [Set Element Properties](#)

Set Element Properties

You can set properties for individual elements.

Note that these properties are also editable from the Structure View. If you need to update multiple element properties, it may be more efficient to use the Structure View.

To set element-level properties using the element dialog:

1. Click the element's action menu icon. From the menu, select **Properties**.
2. Set the properties as needed.
 - **Alias** - Publisher assigns a default tag name to the element in the XML data file. You can update this tag name to assign a more user-friendly name within the data file.
 - **Display Name** - The Display Name appears in the report design tools and the column name in reports. Update this name to be meaningful to your business users.
 - **Data Type** - Publisher assigns a default data type. Valid values are String, Date, Integer, Double, Float.
 - **Sort Order** - You can sort XML data in a group by one or more elements. For example, if in a data set employees are grouped by department and manager, you can sort the XML data by department. Within each department you can group and sort data by manager, and within each manager subgroup, employees can be sorted by salary. If the element isn't in a parent group, the **Sort Order** property isn't available.
 - **Value if Null** - If the value of an occurrence of the element is null, you can supply a default value here to prevent having a null in your data.

Sort Data

Sorting is supported for parent group break columns only.


For example, if a data set of employees is grouped by department and manager, you can sort the XML data by department. Within each department you can group and sort data by manager. If you know how the data should be sorted in the final report, you specify sorting at data generation time to optimize document generation.

To apply a sort order to a group:

1. Click the action menu icon of the element you want to sort by. From the menu, select **Properties**.

2. Select the **Sort Order**.

The figure below shows the Properties dialog for the DEPARTMENT_ID element with the Sort Order list displayed.



Perform Group-Level Functions

This section describes how to perform group-functions.

Topics include:

- [The Group Action Menu](#)
- [Edit the Data Set](#)
- [Remove Elements from the Group](#)
- [Edit the Group Properties](#)

The Group Action Menu

The **Menu** button is available at the group level and enables to perform various functions.

- Create, edit, and delete group filters, as described in [Create Group Filters](#).
- Add an element to the group based on an expression, as described in [Add a Group-Level or Global-Level Element by Expression](#).
- Edit the data set, as described in [Edit the Data Set](#).
- Remove elements from the group, as described in [Remove Elements from the Group](#).
- Edit group properties, as described in [Edit the Group Properties](#).

Edit the Data Set

Launch the data set editor to modify properties of selected data sets.

To edit the data set at group-level:


1. Click the group-level menu.
2. Select **Edit Data Set** to launch the data set editor.

Remove Elements from the Group

You can remove elements from groups as needed.

To remove an element from the group:

- On the element row, click the menu and then click **Remove Element**. An example is shown below. You can only remove elements added as a group function (sum, count, and so on) or added as an expression.



Edit the Group Properties

Edit the properties of a group as needed.

1. Click **Menu** and select **Properties**.
2. Edit the **Group Name** or **Display Name** and click **OK**, as shown below.



Perform Global-Level Functions


The global-level functions enable you to add elements to your report data set at the top report level.

You can add the following types of elements as top-level data:

- Elements based on aggregate functions
- Elements based on expressions
- Elements based on PL/SQL statements (for Oracle Database data sources)

Make sure you order the global-level functions correctly. The global-level functions execute sequentially.

If you select a data type of Integer for any calculated element and the expression returns a fraction, the data isn't truncated. The **Global Level Functions** object is shown below. To add elements based on aggregate functions, drag the element to the "Drop here for aggregate function" space of the object. To add an element based on an expression or PL/SQL, click **Menu**, and choose the appropriate action.



Add a Global-Level Aggregate Function


You can add global-level aggregate functions based on selected elements.

Available functions are as follows:

- Count
- Average
- First
- Last
- Maximum
- Minimum
- Summary


1. Drag and drop the data element from the data set to the **Drop here for aggregate function** area of the Global Level Functions object.

For example, the image below shows creating a global level aggregate function based on the Salary element.



2. When you release the mouse, the data model editor assigns a default name to the aggregate element and assigns Count as the default function.

The figure below shows the function for the new global level element CS_1 being modified from Count to Average.




3. Click the function icon to the left of the new element name and choose the function from the list.
4. To change the default name, click the actions icon to the right of the element name and click **Properties** to launch the **Edit Properties** dialog.


Add a Group-Level or Global-Level Element by Expression

You can add group-level or global-level aggregate functions by expressions.

1. To add a group-level element, on the **Group** object, click **Menu** and select **Add Element by Expression**.



2. In the **Add Element by Expression** dialog, enter fields and operators.




3. In the **Display Name** field, enter a name that is meaningful to your business users.
4. Optional: Select a data type.
5. Use the shuttle arrow to move the data elements required for the expression from the **Available** box to the **Expression** box.
6. Click an operator to insert it in the **Expression** box, or choose from the function list.
7. Click **Validate Expression** to validate the expression.

Add a Global-Level Element by PL/SQL

The PL/SQL function must return a VARCHAR data type.

1. On the Properties page, specify the PL/SQL Package as the **Oracle DB Default Package** in the data model properties. .
2. On the **Global Level Functions** object, click **Menu**, and then click **Add Element by PL/SQL**.
3. In the **Add Element by PL/SQL** dialog, enter the following fields:
 - **Name** - Enter a meaningful name for the element.
 - **Display Name** - Enter a display name. This appears in the report design tools. Enter a name that is meaningful to your business users.
 - **Data Type** - Select **String**.



4. Select the PL/SQL package from the Available box and click the shuttle button to move the function to the Group Filter box.

Use the Structure View to Edit Your Data Structure

The Structure view enables you to preview the structure of your data model.

The Data Source column displays the date elements in a hierarchical tree that you can collapse and expand. Use this view to verify the accuracy of the data model structure and to perform the following edits:

- [Rename Elements](#)
- [Add Value for Null Elements](#)

The Structure view is shown below.

| Diagram Structure Data Code | | | | | | |
|-----------------------------|-------------------|---------|---------------|-------------------|-----------|--|
| Table View Output | | | | | | |
| Data Source | XML View | | | Business View | | |
| | XML Tag Name | Sorting | Value If Null | Display Name | Data Type | |
| Report Data | | | | | | |
| Data Structure | DATA_DS | | | | | |
| Employees | G_1 | | | | | |
| DEPARTMENT_NAME | DEPARTMENT_NAME | | | DEPARTMENT_NAME | A | |
| Salary_projection | Salary_projection | | | Salary_projection | # | |
| Departments | G_2 | | | | | |
| DEPARTMENT_NAME | DEPARTMENT_NAME | | | DEPARTMENT_NAME | A | |
| MANAGER_ID | MANAGER_ID | | | MANAGER_ID | # | |
| FIRST_NAME | FIRST_NAME | | | FIRST_NAME | A | |
| LAST_NAME | LAST_NAME | | | LAST_NAME | A | |
| PHONE_NUMBER | PHONE_NUMBER | | | PHONE_NUMBER | A | |

Rename Elements

Use the Structure page to define user-friendly names for elements in the data model.

You can rename both the XML element tag name (XML View) and the name that displays in the report layout tools (Business View). The figure below shows renaming the Data Source elements to friendlier Business View names.

| Data Source | XML View | | | Business View | |
|-------------------|-------------------|---------|---------------|-------------------|-----------|
| | XML Tag Name | Sorting | Value If Null | Display Name | Data Type |
| Report Data | | | | | |
| Data Structure | DATA_DS | | | | |
| Employees | G_1 | | | | |
| DEPARTMENT_NAME | DEPARTMENT_NAME | | | Department | A |
| Salary_projection | Salary_projection | | | Salary Projection | # |
| Departments | G_2 | | | | |
| DEPARTMENT_NAME | DEPARTMENT_NAME | | | Department | A |
| MANAGER_ID | MANAGER_ID | | | Manager | # |
| FIRST_NAME | FIRST_NAME | | | First | A |
| LAST_NAME | LAST_NAME | | | Last | A |
| PHONE_NUMBER | PHONE_NUMBER | | | Phone | A |

Add Value for Null Elements

The Structure also enables you to enter a value to use for an element if the data model returns a null value for the element.

1. Click the **Structure** tab.
2. Enter the value to use in the **Value if Null** field for the element.

Function Reference

The table below describes the usage of supported functions available from the Add Element by Expression dialog and the Edit Group Filter dialog.

| Function | Description | Syntax | Example |
|----------|--|---|---|
| IF | Logical IF operator Evaluates <code>boolean_expr</code> , and returns <code>true_return</code> if <code>boolean_expr</code> is true, and <code>false_return</code> if <code>boolean_expr</code> is false. | IF (<code>boolean_expr</code> , <code>true_return</code> , <code>false_return</code>) | IF (G_1.DEPARTMENT_ID == 10, 'PASSED', 'FAIL')returns 'PASSED' if DEPARTMENT_ID = 10, otherwise returns 'FAIL' |

| Function | Description | Syntax | Example |
|----------|---|---|--|
| NOT | Logical NOT operator Evaluates <code>boolean_expr</code> , and returns true if <code>boolean_expr</code> is false. | <code>STRING(NOT(boolean_expr))</code> | <code>STRING(NOT(G_1.JOB_ID == 'MANAGER'))</code> returns 'TRUE' if <code>JOB_ID = MANAGER</code> , otherwise returns 'FALSE' |
| AND | Logical AND operator Evaluates <code>boolean_expr1</code> and <code>boolean_expr2</code> , and returns true if both Boolean expressions are true, otherwise returns false. | <code>STRING(AND(boolean_expr1, boolean_expr2, ...))</code> | <code>STRING(AND(G_1.JOB_ID == 'MANAGER', G_1.DEPARTMENT_ID == 10))</code> returns 'TRUE' if both <code>JOB_ID = MANAGER</code> and <code>DEPARTMENT_ID = 10</code> , otherwise returns 'FALSE' |
| && | Logical AND operator Evaluates <code>boolean_expr1</code> and <code>boolean_expr2</code> , and returns true if both Boolean expressions are true, otherwise returns false. | <code>STRING(boolean_expr1 && boolean_expr2)</code> | <code>STRING(G_1.JOB_ID == 'MANAGER' && G_1.DEPARTMENT_ID == 10)</code> returns 'TRUE' if both <code>JOB_ID = MANAGER</code> and <code>DEPARTMENT_ID = 10</code> , otherwise returns 'FALSE' |
| | Logical OR operator Evaluates <code>boolean_expr1</code> and <code>boolean_expr2</code> and returns true if either or both the Boolean expressions is true, otherwise returns false. | <code>STRING(OR(boolean_expr1, boolean_expr2))</code> | <code>STRING(OR(G_1.JOB_ID == 'MANAGER', G_1.DEPARTMENT_ID == 10))</code> returns 'TRUE' if either <code>JOB_ID = MANAGER</code> or <code>DEPARTMENT_ID = 10</code> , otherwise returns 'FALSE' |
| MAX | Returns the maximum value of the element in the set. | <code>MAX(expr1, expr2, expr3, ...)</code> | <code>MAX(G1_Salary, 10000)</code> returns max of salary or 10000 |
| MIN | Returns the minimum value of the element in the set. | <code>MIN(expr1, expr2, expr3, ...)</code> | <code>MIN(G1_Salary, 5000)</code> returns min of salary or 5000 |
| ROUND | Returns a number rounded to the integer places right of the decimal point. | <code>ROUND(number[, integer])</code> If integer is omitted, number is rounded to 0 places. Integer can be negative to round off digits left of the decimal point. Integer must be an integer. | <code>ROUND(2.777)</code> returns 3 <code>ROUND(2.777, 2)</code> returns 2.78 |
| FLOOR | Returns the smallest integer equal to or less than n. | <code>FLOOR(n)</code> | <code>FLOOR(2.777)</code> returns 2 |

| Function | Description | Syntax | Example |
|----------|---|---|---|
| CEILING | Returns the largest integer greater than or equal to n. | CEILING(n) | CEILING(2.777) returns 3 |
| ABS | Returns the absolute value of n. | ABS(n) | ABS(-3) returns 3 |
| AVG | Returns the average value of the expression. | AVG(expr1, expr2, expr3, ...) | AVG(G_1.SALARY,G_1.COMMISSION_PCT*G_1.SALARY) returns the average of SALARY and COMMISSION For example, if SALARY = 14000 and COMMISSION_PCT = .4, the expression evaluates to 9800.0 |
| LENGTH | Returns the length of an array. The LENGTH function calculates the length using characters as defined by the input character set. If char is null, the function returns null. If char is an array, it returns the length of the array. | LENGTH(expr) | Example to return the length of an array: LENGTH{1, 2, 4, 4}) returns 4 Example to return the length of a string: LENGTH('countries') returns 9 |
| SUM | Returns the sum of the value of the expression. | SUM(expr1, expr2, ...) | SUM (G_1.SALARY, G_1.COMMISSION_PCT* G_1.SALARY) returns sum of salary and commission For example, if SALARY = 14000 and COMMISSION_PCT =.4, the expression evaluates to 19,600.0 |
| NVL | Replaces null (returned as a blank) with a string in the results of a query. | NVL(expr1, expr2) If expr1 is null, then NVL returns expr2. If expr1 is not null, then NVL returns expr1. | NVL(G_1.COMMISSION_PCT, .3) returns .3 when G_1.COMMISSION_PCT is null |
| CONCAT | Returns char1 concatenated with char2. | CONCAT(char1, char2) | CONCAT(CONCAT(First_Name, ' '), Last_Name) where First_Name = Joe and Last_Name = Smith returns Joe Smith |
| STRING | Returns char as a string data type. | STRING(expr) | STRING(G1_SALARY) where salary = 4400 returns 4400 as a string |

| Function | Description | Syntax | Example |
|---------------|--|--|---|
| SUBSTRING | Extracts a substring from a string. | SUBSTRING(string, start_pos, end_pos) string is the source string. start_pos is the position to start the extraction. end_pos is the end position of the string to extract (optional). | SUBSTRING('this is a test', 5, 7) returns "is" (that is, characters 6 through 7) SUBSTRING('this is a test', 5) returns "is a test" |
| INSTR | Returns the position/location of the first character of a substring in a string. | INSTR(string1, string2) string1 is the string to search. string2 is the substring to search for in string1. | INSTR('this is a test', 'is a') returns 5 |
| DATE | Converts a valid Java date string to a date data type in canonical format. | DATE(char, format_string) where (1) char is any valid Java date string (for example, 13-JAN-2013) (2) format_string is the Java date format of the input string (for example, dd-MMM-yyyy) The input and format strings must be a valid Java date format string. | DATE('01-Jan-2013', 'dd-MMM-yyyy') returns 2013-01-01T08:00:00.000+00:00 |
| FORMAT_DATE | Converts a date argument in the Java date format to a formatted string. | FORMAT_DATE(date, format_string) | FORMAT_DATE(SYSDATE, 'dd-MMM-yyyy') where the value of SYSDATE = 2013-01-24T16:32:45.000-08:00 returns 24-Jan-2013 |
| FORMAT_NUMBER | Converts a number or numeric string to a string in the specified number format. | FORMAT_NUMBER(number, format_string) | FORMAT_NUMBER(SOME_NUMBER, '\$9,999.00') where the value of SOME_NUMBER = 12345.678 returns \$12,345.68 |

| Function | Description | Syntax | Example |
|----------|--|--|---|
| DECODE | Replaces the value of an expression with another value based on the specified search and replace criteria. | DECODE(expr, search, result [, search, result]... [, default]) | DECODE(PROD_FAMILY_CODE, 100, 'Colas', 200, 'Root Beer', 300, 'Cream Sodas', 400, 'Fruit Sodas', 'Other') returns (1) 'Colas' if PROD_FAMILY_CODE = 100 (2) 'Root Beer' if PROD_FAMILY_CODE = 200 (3) 'Cream Sodas' if PROD_FAMILY_CODE = 300 (4) 'Fruit Sodas' if PROD_FAMILY_CODE = 400 (5) 'Other' if PROD_FAMILY_CODE is any other value |
| REPLACE | Replaces a sequence of characters in a string with another set of characters. | REPLACE(expr, string1, string2) where string1 is the string to search for and string2 is the string to replace. | REPLACE(G_1.FIRST_NAME, 'B', 'L') where G_1.FIRST_NAME = Barry returns Larry |

4

Add Parameters and Lists of Values

This topic describes how to add parameters and lists of values to a data model.

Topics:

- [About Parameters](#)
- [Add a New Parameter](#)
- [About Lists of Values](#)
- [Add Lists of Values](#)
- [Add Flexfield Parameters](#)

About Parameters

Parameters in a data model enables you to interact with data when you view reports.

Supported parameter types:

- **Text** - Enables entering a text string to pass as the parameter.
- **Menu** - Enables making selections from a list of values. A list of values can contain fixed data that you specify or a list created using a SQL query that is executed against any of the defined data sources. This option supports multiple selection, a **Select All** option, and partial page refresh for cascading parameters.

To create a menu type parameter, define the list of values, and then define the parameter and associate it to the list of values.
- **Date** - Enables you to select a date as a parameter. You must use the data type *Date* and the Java date format.
- **POV** - Enables you to use an hierarchical point of view as a parameter to select Essbase data. You can view a cube dimension, expand a data structure node, and drill down to select data from a POV. You must use an MDX query to create a list of values for a POV parameter.
- **Search** - Enables you to specify search text and to select one value from a long list of values.

You can define mandatory parameters for your report. An asterisk symbol next to a parameter label indicates that the parameter is marked as mandatory in the data model. You must provide values for the mandatory parameters of a report, if you want to run the report online or schedule the report.

After defining the parameters in the data model, you can configure how the parameters are displayed in the report.

You can use parameters in various ways, depending on the type of the data set. For example, you can use all parameter features with data sets from SQL queries. With other types of data sets, you can use all, none, or a subset of the parameter features, as described in this table.

| Data Set Type | Parameter Support | Multiple Selection | Can Select All | Refresh Other Parameters on Change |
|----------------------|---|----------------------------------|----------------------------------|------------------------------------|
| SQL Query | Yes Supports all parameter types | Yes | Yes | Yes |
| LDAP Query | Yes Supports only Text type parameter | No | No | No |
| MDX Query | Yes Supports Text and POV parameter types that return a text value | No | No | No |
| Analysis | Inherited from Analysis | Yes (using Oracle BI Dashboards) | Yes (using Oracle BI Dashboards) | Yes (using Oracle BI Dashboards) |
| DV Data Set | Yes Supports all parameter types | Yes | Yes | No |
| HTTP (XML Feed) | Yes Supports only Text and Date parameter types | No | No | No |
| View Object | Yes, provided that the view object supports and is designed for it | No | No | Yes (view object parameters only) |
| Web Service | Yes Supports only Text and Date parameter types | No | No | No |
| CSV File | No | No | No | No |
| Microsoft Excel File | Yes Supports only Text and Date parameter types | No | No | No |
| XML File | No | No | No | No |
| Content Server | No | No | No | No |

Add a New Parameter

Create a parameter by assigning it a name and other properties.

The parameter name you choose must not exceed the maximum length allowed for an identifier by your database. Refer to your database documentation for identifier length limitations.

When you design report layouts using the Layout Editor, the preview of the report output uses the default values of the parameters.

You can configure row placement at the report level. The report definition supports additional display options for parameters.

To add a new parameter:

1. On the Data Model components pane, click **Parameters** and then click **Create new Parameter**.
2. Enter a **Name** for the parameter.
The name must match any references to this parameter in the data set.
3. Select the **Data Type** from the list. A **Date** data type only supports a **Date Parameter Type**.
4. Enter a **Default Value** for the parameter. This is recommended to prevent long running queries.
5. Select the **Parameter Type**.
6. To mark the parameter as mandatory, select **Mandatory**.

Without providing values for the mandatory parameters, you can't test a report using the View Data option, or run the report online, or schedule the report.

7. In the **Row Placement** setting configure the number of rows for displaying the parameters and in which row to place each parameter.

For example, if your report has six parameters, you can assign each parameter to a separate row, 1 - 6, with one being the top row; or, you can assign two parameters each to rows 1, 2, 3. By default, all parameters are assigned to row 1.

Create a Text Parameter

The **Text** type parameter provides a text box to prompt the user to enter a text entry to pass as the parameter to the data source.

To create a text parameter:

1. Select **Text** from the Parameter Type list.
2. Enter the **Display Label**. For example, Department.
3. Enter the **Text Field Size** as an integer. This field determines the size (width) of the field, but doesn't limit the number of characters that the user can enter into the text box.
4. Enable the following **Options** if required:

- **Text field contains comma-separated values** - Enables the user to enter multiple comma-delimited values for this parameter. The parameter in your data source must be defined to support multiple values.
- **Refresh other parameters on change** - Performs a partial page refresh to refresh any other parameters whose values are dependent on the value of this one.


Create a Menu Parameter

A Menu type parameter presents a list of values to the user.

You must define the list of values first. The Menu type parameter supports the data types of String and Integer only.

To create a menu parameter:

1. Select **Menu** from the **Parameter Type** list. The lower pane displays the appropriate fields.
2. In **Data Type**, select *String* or *Integer*.
3. Enter the **Display Label**. The display label is the label that displays to users when they view the report. For example: Department.
4. Select the **List of Values** that you defined for this parameter.
5. Enter the **Number of Values to Display in List**. If the number of values in the list exceeds the entry in this field, the user must click **Search** to find a value not displayed, as shown in the figure below. This field defaults to 100.




6. Enable the following **Options** if required:
 - **Multiple Selection** - Allows the user to select multiple entries from the list. Your data source must be able to support multiple values for the parameter. The display of a menu parameter that supports multiple selection differs. See the two figures below.
 - **Can select all** - Inserts an *All* option in the list. When the user selects *All* from the list of values, you can pass a null value for the parameter or all list values. Choose **NULL Value Passed** or **All Values Passed**.


Using * passes a null, so you must handle the null in your data source. A method to handle the null would be the standard Oracle NVL command, for example: `where customer_id = nvl(:cstid, customer_id)` where `cstid` is a value passed from the list of values, and when the user selects *All* it passes a null value.

- **Refresh other parameters on change** — Performs a partial page refresh to refresh any other parameters whose values are dependent on the value of this one.

The figure below shows how the Department menu type parameter displays to the report consumer when multiple selection isn't enabled.



The figure below shows how the Department menu type parameter displays to the report consumer when multiple selection is enabled.



Customize the Display of Menu Parameters

The display of menu parameters in the report can be further customized in the report definition.


Menu type parameters support the additional display option as a static list of checkboxes or radio buttons.

Define a Date Parameter

The Date type parameter provides a date picker to prompt the user to enter a date to pass as the parameter to the data source.

1. Select Date from the Parameter Type list. The lower pane displays the appropriate fields for your selection.
2. Enter the **Display Label**. The display label is the label that displays to users when they view the report. For example: Hire Date.
3. Enter the **Text Field Size** as an integer. This field determines the number of characters that the user can enter into the text box for the date entry. For example: 10.
4. Optional: Select **Ignore User Timezone** if you want to display the date parameter value in UTC.
5. Enter the **Date Format String**. The format must be a Java date format, for example, *MM-dd-yyyy*.
6. Optional: Enter a **Date From** and **Date To**. The dates entered here define the date range that are presented to the user by the date picker. For example if you enter the **Date From** as 01-01-1990, the date picker doesn't allow the user to select a date before 01-01-1990. Leave the **Date To** blank to enable all future dates.

The figure shows how the Hire Date parameter displays to the report consumer.



Create a Point of View Parameter (POV)

The POV (Point of View) type parameter provides you a multidimensional view.

You can directly specify a POV parameter in an MDX query and create POV parameter, or you can create a POV parameter first and then update an MDX query to include the POV parameter in the WHERE clause. Before you create a POV type parameter in a data model, define the list of values for the POV parameter.

To create a POV parameter:

1. On the Data Model components pane, click **Parameters**.
2. Click **Create New Parameter**.
3. Enter a name for the parameter in the **Name** field.
4. Select **POV** from the **Parameter Type** list.
5. From the **Data Type** list, select **Text**.
6. Enter a default value for the parameter in the **Default Value** field.
7. In the **Row Placement** setting, configure the number of rows for displaying the parameters.
8. Use the **Reorder** column to specify the order for the parameter.
9. Enter a label in the **Display Label** field.
10. Select a LOV for the POV parameter from the **List of Values** list.

Include a POV Parameter Value in an MDX Query

You can search a dimension in a cube and include a POV parameter value in an MDX query.

If you include a POV parameter in an MDX query of a data model, and if that POV parameter doesn't exist in the data model, Publisher creates that POV parameter in the data model when you save the query.

To include a POV parameter value in an MDX query:

1. On the component pane of the data model editor, click **Data Sets**.
2. Click the MDX Query data set that you want to edit.
3. Click **Edit Selected Data Set**.
4. In the WHERE clause of the MDX query, enter the name of the POV parameter enclosed in `${ }`.

For example, if you want to create a POV parameter with name as P_Year or if the P_Year POV parameter exists in the data model, specify the condition as `WHERE ([Year].[${P_Year}]`

5. In the parameter value binding dialog, click the search icon next to the parameter.
6. In the select dimension dialog, select the cube, dimension, and value for the parameter.
7. Click **Select**.
8. Click **OK**.

9. Save the data model.

Create a Search Parameter

You can use the Search type parameter to provide a box for entering search text and a search icon to search and list the values that match the search so that users can select.

Use the Search type parameter to find a value within a long list of values. You must create a LOV for the parameter before you define the Search type parameter.

To create a Search type parameter:

1. On the Data Model components pane, click **Parameters**, and then click **Create new Parameter**.
2. Enter a name for the parameter, select **String** from the **Data Type** list, and enter a default value for the parameter.
3. Select **Search** from the **Parameter Type** list.
4. Enter a label for the parameter in the **Display Label** field.
5. Select the LOV for the parameter from the **List of Values** list.
6. Optional: Select **Refresh other parameters on change**.

About Lists of Values

A list of values is a defined set of values that a report consumer can select from to pass a parameter value to your data source.

If you define a menu type parameter, the list of values provides the menu of choices. You must define the list of values before you define the menu parameter.

Populate the list using one of the following methods:


- **SQL Query** — Retrieves the values from a database using a SQL query.
- **Fixed Data** — Retrieves the values that a user manually enters.
- **MDX Query** — Retrieves the values from a POV or Slicer.
- **Flexfield**

Retrieves the values from a key flexfield defined in Oracle E-Business Suite. The flexfield option is only available when Publisher is using the Oracle E-Business Suite security model.

Add Lists of Values

You can create lists of SQL Query or Fixed Data values .

1. In the Data Model components pane, click **List of Values** and then click **Create new List of Values**.




2. Enter a Name for the list and select a **Type**.

Create a List from a SQL Query


The data engine expects a (display) name-value pair from the list of values query. In the list of values select statement, the column listed first is used as the display name and the second is used for the value that is passed to the parameter in the data set query by the data engine.

If the query returns only one column, then the same column value is used both as the list of values display name shown to the user and as the value that is passed to the parameter.

1. Select a **Data Source** from the list.
2. In the lower pane, select **Cache Result** (recommended) if you want the results of the query cached for the report session.
3. Enter the SQL query or use the Query Builder. The figure below shows a SQL query type list of values.



The SQL query shown below selects only the DEPARTMENT_NAME column from the DEPARTMENTS table. In this case the list of values both displays the results of the query in the list and passes the same value to the parameter in the data set. The figure below shows the list of values display entries and the values passed to the data set. The menu items and the values shown for P_DEPT are the DEPARTMENT_NAME values.




If instead you wanted to pass the DEPARTMENT_ID to the parameter in the data set, and display the DEPARTMENT_NAME in the list, construct your SQL query as follows:

```

Select      "DEPARTMENTS"."DEPARTMENT_NAME" as "DEPARTMENT_NAME" ,
           "DEPARTMENTS"."DEPARTMENT_ID" as "DEPARTMENT_ID"
from        "DEMO"."DEPARTMENTS" "DEPARTMENTS"
  
```

The figure below shows the list of values display entries and the values passed to the data set. The menu lists the DEPARTMENT_NAME while the values shown for P_DEPT are the DEPARTMENT_ID values.



Create a List from a Fixed Data Set

Create a list from a fixed data set for each label-value pair required.

When you create a label-value pair, the label is displayed to the user in the list. The value is passed to the data engine.

1. In the lower pane, click the **Create new List of Values** icon to add a Label and Value pair.
2. Repeat for each label-value pair required.

The figure below shows fixed data type list of values.

The screenshot shows the Oracle BI tool interface. On the left is the 'Data Model' pane with a tree view of properties including 'List of Values'. The main area is titled 'List of Values' and contains a table with columns: Name, Type, Data Source, and Reorder. The 'List of Depts' entry is selected, showing a 'Fixed Data' type. Below this, a sub-table titled 'List of Depts: Type: Fixed Data' displays the following data:

| Label | Value |
|----------------|-------|
| Administration | 10 |
| Marketing | 20 |
| IT | 30 |
| Sales | 40 |
| Purchasing | 50 |

Create a List from an MDX Query

You can use an MDX query to create a list of multidimensional values by specifying the slice of an Essbase cube.

To create a list from an MDX query:

1. In the Data Model components pane, click **List of Values**.
2. Click **Create New List of Values**.
3. Enter a name for the list in the **Name** field.
4. Select **MDX Query** from the **Type** list.
5. Select an OLAP data source from the **Data Source** list.
6. In the lower pane, select **Cache Result** (recommended) if you want the results of the query cached for the report session.

7. Select the POV / Slicer for the MDX query.
 - a. Click the POV / Slicer search icon.
 - b. Select a cube.
 - c. Select a dimension.


The POV / Slicer field displays the selected cube and dimension in the *cube.dimension* format.

Add Flexfield Parameters


Oracle E-Business Suite customers who have configured Publisher to use E-Business Suite security can create reports that leverage key flexfields as parameters.

When you define a data model to pass a key flexfield as a parameter, Publisher presents a dialog to the report consumer to make selections for the flexfield segments to pass as parameters to the report, similar to the way flexfields are presented when running reports through the concurrent manager in the E-Business Suite.

The flexfield list of values displays in the report viewer as shown below.



The flexfield list of values displays as a dialog from which you select the segment values, as shown below.



Prerequisites for Using Flexfields

When defining a list of values, E-Business Suite customers see a list Type called "Flexfield".

To enable the flexfield type list of values, configure to use E-Business Suite Security. The flexfield must already be defined in the E-Business Suite.

Add a Flexfield Parameter and List of Values

Add flexfield parameters by adding the list of values.

The flexfield type list of values retrieves the flexfield metadata definition to present the appropriate values for each segment in the flexfield list of values selection dialog. Use the flexfield parameter to pass values to the Flexfield defined in the Data Model.

At runtime the `&flexfield_name` reference is replaced with the lexical code constructed based on the values in the Flexfield component definition.

1. Add the flexfield list of values (LOV).
2. Add a parameter and associate it with the flexfield LOV by selecting your flexfield list of values as the source menu for the parameter.
3. Add the Flexfield component to the data model.
4. Reference the Flexfield in your SQL query using the `&flexfield_name` syntax.


Add the Flexfield List of Values

Add a list of values retrieved from a flexfield definition.

When you choose Flexfields as the Type, the **Data Source** option is no longer editable. All flexfields type lists of values use the Oracle E-Business Suite as the data source.

1. On the Data Model components pane, click **List of Values** and then click **Create new List of Values**.
2. Enter a **Name** for the list and choose Flexfields as the **Type**.
3. In the Flex_Acct_List: Type: Flexfields pane, enter the following:
 - **Application Short Name** - E-Business Suite application short name, for example: SQLGL.
 - **ID Flex Code** - Flexfield code defined for this flexfield in the Register Key Flexfield form, for example: GL#.
 - **ID Flex Number** - Name of the source column or parameter that contains the flexfield structure information, for example: 101 or :STRUCT_NUM. If you use a parameter, ensure that you define the parameter in the data model.

The image shows a sample flexfield type, *LOV*.



Add the Menu Parameter for the Flexfield List of Values

Define the parameter to display the flexfield list of values and capture the values selected by the user.


The Flexfield type parameter definition includes an additional field called **Range** to support range flexfields. A range flexfield supports low and high values for each key segment rather than just single values. You can customize the default value of the flexfield and row placement in the report definition. The row placement determines where this parameter appears in the report viewer.

The following options are disabled for flexfield parameters: **Number of Values to Display in List**, **Multiple Selection**, **Can select all**, and **Refresh other parameters on change**.

1. On the Data Model components pane, click **Parameters** and then click **Create new Parameter**.
2. Select **Menu** from the **Parameter Type** list.
3. Choose *String* or *Integer* as the **Data Type**.
4. Enter a **Default Value** for the flexfield parameter.
5. Enter the **Row Placement**.
6. Enter the **Display Label**. The display label is the label that displays to users when they view the report. For example: *Account From*.
7. Select the **List of Values** that you defined for this parameter.

When you select a list of values that is the Flexfield type, an additional field labeled **Range** displays.

The image shows a parameter definition for the flexfield list of values.




Use the Flexfield Parameter to Pass Values to a Flexfield Defined in the Data Model

After adding the Menu parameter to the flexfield list of values, you can pass the parameter values to a flexfield component in the data model.

To define the Flexfield in the data model:

1. On the Data Model components pane, click **Flexfields** and then click **Create new Flexfield**.
2. Enter the following:
 - **Name** — Enter a name for the flexfield component.
 - **Type** — Select the flexfield type from the list. The type you select here determines the additional fields required.
 - **Application Short Name** — Enter the short name of the Oracle Application that owns this flexfield (for example, GL).
 - **ID Flex Code** — Enter the flexfield code defined for this flexfield in the Register Key Flexfield form (for example, GL#).
 - **ID Flex Number** — Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM.
3. In the lower region of the page, enter the details for the type of flexfield you selected. For the field that is to take the parameter value, enter the parameter name prefixed with a colon, for example, :P_Acct_List.


In the figure below the Flexfield component is defined as a "Where" **Type**. The parameter :P_Acct_List is entered in the Operand1 field. At runtime, values selected by the user for the parameter P_Acct_List will be used to create the where clause.



Reference the Flexfield in the SQL Query

Finally, create the SQL query against the E-Business Suite database.

Use the lexical syntax in the SQL query. In the figure below &Acct_Flex is the Flexfield lexical called in the where condition of the SQL query.




Pass a Range of Values

To define the parameters for the flexfield lists of values when you want to pass a range of values you create two menu parameters that both reference the same flexfield LOV.

At runtime users choose a high value from the list of values and a low value from the same list of values. These two values are then passed as operands to the flexfield component of the data model.


1. Create one flexfield LOV.
2. Create the high range parameter. For the **Range** field, select **High** to designate this parameter as the high value.
3. Create the low range parameter. For the **Range** field, select **Low** to designate this parameter as the low value. Both parameters reference the flexfield list of values that you created in Step 1. The figure below shows creating the parameters to define the range.



4. Create the Flexfield in the data model.

In the lower region of the page, enter the details for the type of flexfield you selected. Enter the parameter prefixed with a colon for example, :P_Acct_List.


In the figure below the Flexfield component is defined as a "Where" **Type**. The parameters :P_FLEX_LOW and :P_FLEX_HIGH are entered in the Operand1 and Operand2 fields. At runtime, values selected by the user for the parameters P_FLEX_LOW and P_FLEX_HIGH will be used to create the where clause.



When the report associated with this data model is displayed in the report viewer, the report consumer sees the two flexfield parameters as shown below.



When the report consumer clicks either the high or low flexfield indicator (...), a dialog launches enabling input of both the high and low values as shown below.



The display characteristics in the report viewer of the range flexfield parameter resemble closely the presentation of range flexfields in the E-Business Suite.

5

Add Event Triggers

This topic describes how to define triggers in your data model. Data models support before data and after data event triggers and schedule triggers.

Topics:

- [About Triggers](#)
- [Add Before Data and After Data Triggers](#)
- [Create Schedule Triggers](#)

About Triggers

An event trigger checks for an event and when the event occurs, it runs the code associated with the trigger.

Publisher supports three types:

- **Before Data** - Fires right before the data set is executed.
- **After Data** - Fires right after the data engine executes all data sets and generates the XML.
- **Schedule Trigger** - Fires when a scheduled job is triggered and before it runs.

Before data and after data triggers execute a PL/SQL function stored in a PL/SQL package in your Oracle Database. The return data type for a PL/SQL function inside the package must be a Boolean type and the function must explicitly return TRUE or FALSE.

A schedule trigger is associated with a scheduled job. It's a SQL query that executes at the time a report job is scheduled to run. If the SQL returns any data, the report job runs. If the SQL query returns no data, the job instance is skipped.

Event triggers aren't used to populate data used by a bursting definition. See [Add Bursting Definitions](#).

Add Before Data and After Data Triggers


You can add event triggers that fire before and after data.

If you define a default package then you must define all parameters as a global PL/SQL variable in the PL/SQL package. You can then explicitly pass parameters to your PL/SQL function trigger or all parameters are available as a global PL/SQL variable, see [Data Model Properties](#)

1. On the data model **Properties** pane, enter the **Oracle DB Default Package** that contains the PL/SQL function signature to execute when the trigger fires. .
2. From the task pane, click **Event Triggers**.
3. From the **Event Triggers** pane, click **Create New Event Trigger**.

4. Enter the following for the trigger:
 - **Name** - Name the trigger something meaningful.
 - **Type** - Select Before Data or After Data.
 - **Language** - Select PL/SQL.

The figure below shows an event trigger.



5. Select the package from the **Available Functions** box and click the arrow to move a function to the **Event Trigger** box.

The name appears as PL/SQL <package name>.<function name>.

Order of Execution

If you define multiple triggers of the same type, they fire in the order that they appear in the table (from top to bottom).

To change the order of execution:

- Use the **Reorder** arrows to place the triggers in the correct order.

Create Schedule Triggers

A schedule trigger fires when a report job is scheduled to run. Schedule triggers are of type SQL Query.

When a report job is scheduled to run, the schedule trigger executes the SQL statement defined for the trigger. If data is returned, then the report job is submitted. If data isn't returned from the trigger SQL query, the report job is skipped.

The schedule trigger that you associate with a report job can reside in any data model in the catalog. You don't need to create the schedule trigger in the data model of the report for which you want to execute the trigger. You can reuse schedule triggers across multiple report jobs.

1. In the data model editor task pane, click **Event Triggers**.
2. From the **Event Triggers** pane, click the **Create New** icon.
3. Enter the following for the trigger:
 - **Name** - Enter a name for the trigger.
 - **Type** - Select **Schedule**.
 - **Language** - Accept the default value, SQL Query.
4. In the lower pane, enter the following:
 - **Options** - Select this check box to cache the results of the trigger query.
 - **Data Source** - Select the data source for the trigger query.
 - **SQL Query** - Enter the query in the text area, or click **Query Builder** to use the utility to construct the SQL query, see [Use the SQL Query Builder](#).

You can include parameters in the trigger query. Define the parameter in the same data model as the trigger. Enter parameter values when you schedule the report job.

The schedule trigger queries don't support multi-select parameters. If your query expects a set of values, modify your query.

If the SQL query returns any results, the scheduled report job executes. The figure below shows a schedule trigger to test for inventory levels based on a parameter value that can be entered at runtime.

The screenshot displays the Oracle Data Model Editor interface. On the left, the 'Data Model' pane shows a tree view with 'Event Triggers' expanded, highlighting the 'Quantity' trigger. The main 'Event Triggers' pane shows a table with columns: Name, Type, Language, and Reorder. The 'Quantity' trigger is configured with Type 'Schedule' and Language 'SQL Query'. Below the table, the configuration for the 'Quantity' trigger is shown, including the 'Options' section with 'Cache Result' checked, the 'Data Source' set to 'demo', and the 'SQL Query' text area containing the following SQL:

```
select true
from "OE"."OC_INVENTORIES"."OC_INVENTORIES"
where "OC_INVENTORIES"."QUANTITY_ON_HAND" < :pQuantity
```

6

Add Flexfields

This topic describes the support for flexfields in data models.

Topics:

- [About Flexfields](#)
- [Add Key Flexfields](#)


About Flexfields

A flexfield is a data field that your organization can customize to your business needs without programming.

Oracle applications use two types of flexfields:

- key flexfields
A key flexfield is a field you can customize to enter multi-segment values such as part numbers, account numbers, and so on.
- descriptive flexfields
A descriptive flexfield is a field you customize to enter additional information for which your Oracle applications product hasn't provided a field.

If you are reporting on data from Oracle applications, use the Flexfield component of the data model to retrieve flexfield data.



Before including flexfields in your reports, you should understand flexfields in your applications.

Use Flexfields in Your Data Model

Use flexfields based on SQL SELECT statements in your data model.

To use flexfields in your SQL-based data model:

- Add the **Flexfield** component to the data model as described in this chapter.

- Define the SQL SELECT statement against the applications data tables.
- Within the SELECT statement, define each flexfield as a lexical. Use the &LEXICAL_TAG to embed flexfield related lexicals into the SELECT statement.

Add Key Flexfields

You can use key flexfield references to replace the clauses appearing after SELECT, FROM, WHERE, ORDER BY, or HAVING.

Use a flexfield reference when you want the parameter to replace multiple values at runtime. The data model editor supports the following flexfield types:

- **Where** - This type of lexical is used in the WHERE section of the statement. Use it to modify the WHERE clause such that the SELECT statement can filter based on key flexfield segment data.
- **Order by** - This type of lexical is used in the ORDER BY section of the statement. Use it to obtain a list of column expressions so that the resulting output can be sorted by the flex segment values.
- **Select** - This type of lexical is used in the SELECT section of the statement. Use it to retrieve and process key flexfield (kff) code combination related data based on the lexical definition.
- **Filter** - This type of lexical is used in the WHERE section of the statement. Use it to modify the WHERE clause such that the SELECT statement can filter based on Filter ID passed from Oracle Enterprise Scheduling Service.
- **Segment Metadata** - Use it to retrieve flexfield-related metadata. You don't have to write PL/SQL code to retrieve this metadata. Instead, define a dummy SELECT statement, then use this lexical to get the metadata. This lexical should return a constant string.

After you set up the flexfield components of your data model, create a flexfield lexical reference in the SQL query using the following syntax:

```
&LEXICAL_TAG ALIAS_NAME
```


for example:

```
&FLEX_GL_BALANCING alias_gl_balancing
```

After entering the SQL query, when you click **OK**

- Enter the following:
 - **Lexical Name** - Enter a name for the flexfield component.
 - **Flexfield Type** - Select **Key Flexfield..**
 - **Lexical Type** - Select the type from the list. Your selection here determines the additional fields required. See [Enter Flexfield Details](#).
 - **Application Short Name** - Enter the short name of the Oracle Application that owns this flexfield, for example, *GL*.
 - **Flexfield Code** - Enter the flexfield code defined for this flexfield. In Oracle E-Business Suite this code is defined in the Register Key Flexfield form, for example, *GL#*.

- **ID Flex Number** - Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, `:PARAM_STRUCT_NUM`.



Enter Flexfield Details

The Details region displays appropriate fields depending on the Lexical Type you chose.

Fields for Key Flexfield Type: Segment Metadata

The table describes the detail fields for segmented metadata.

| Field | Description |
|---------------------------|---|
| Structure Instance Number | Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, <code>:PARAM_STRUCT_NUM</code> . |
| Segments | (Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax. |
| Show Parent Segments | Select this box to automatically display the parent segments of dependent segments even if it's not displayed in the segments attribute. |
| Metadata Type | Select the type of metadata to return: Above Prompt of Segments — Above prompt of segment(s). Left Prompt of Segments — Left prompt of segment(s) |

Fields for Key Flexfield Type: Select

The table below shows the detail fields for the Select flexfield type.

| Field | Description |
|-------------------------------------|--|
| Enable Multiple Structure Instances | Indicates whether this lexical supports multiple structures. Checking this box indicates all structures are potentially used for data reporting. The data engine uses <code><code_combination_table_alias>.<set_defining_column_name></code> to retrieve the structure number. |
| Code Combination Table Alias | Specify the table alias to prefix to the column names. Use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join. |

| Field | Description |
|---------------------------|--|
| Structure Instance Number | Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM. |
| Segments | (Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax. |
| Show Parent Segments | Select this box to automatically display the parent segments of dependent segments even if it's not displayed in the segments attribute. |
| Output Type | Select from the following: <ul style="list-style-type: none"> • Value — Segment value as it's displayed to users. • Padded Value — Padded segment value as it's displayed to users. Number type values are padded from the left. String type values are padded on the right. • Description — Segment value's description up to the description size defined in the segment definition. • Full Description — Segment value's description (full size). • Security — Returns Y if the current combination is secured against the current user, N otherwise. |

Fields for Key Flexfield Type: Where

The table below shows the detail fields for the Where key flexfield type.

| Field | Description |
|------------------------------|---|
| Code Combination Table Alias | Specify the table alias to prefix to the column names. You use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join. |
| Structure Instance Number | Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, :PARAM_STRUCT_NUM. |
| Segments | (Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax. |
| Operator | Select the appropriate operator. |
| Operand1 | Enter the value to use on the right side of the conditional operator. |
| Operand2 | (Optional) High value for the BETWEEN operator. |

Fields for Key Flexfield Type: Order By

The table below shows the detail fields for the Order by flexfield type.

| Field | Description |
|-------------------------------------|---|
| Enable Multiple Structure Instances | Indicates whether this lexical supports multiple structures. Selecting this box indicates all structures are potentially used for data reporting. The data engine uses <code><code_combination_table_alias>.<set_defining_column_name></code> to retrieve the structure number. |
| Structure Instance Number | Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, <code>:PARAM_STRUCT_NUM</code> . |
| Code Combination Table Alias | Specify the table alias to prefix to the column names. You use <code>TABLEALIAS</code> if your <code>SELECT</code> joins to other flexfield tables or uses a self-join. |
| Segments | (Optional) Identifies for which segments this data is requested. Default value is "ALL". See <i>Oracle E-Business Suite Developer's Guide</i> for syntax. |
| Show Parent Segments | Select this box to automatically display the parent segments of dependent segments even if it's not displayed in the segments attribute. |

Fields for Key Flexfield Type: Filter

The table below shows the detail fields for the Filter flexfield type.

| Field | Description |
|------------------------------|---|
| Code Combination Table Alias | Specify the table alias to prefix to the column names. You use <code>TABLEALIAS</code> if your <code>SELECT</code> joins to other flexfield tables or uses a self-join. |
| Structure Instance Number | Enter the name of the source column or parameter that contains the flexfield structure information. For example: 101. To use a parameter, prefix the parameter name with a colon, for example, <code>:PARAM_STRUCT_NUM</code> . |

Add Descriptive Flexfields

Reporting on descriptive flexfields is supported only for Oracle Fusion Applications.

- Enter the basic flexfield information:
 - Name** - Enter a name for the flexfield component.
 - Flexfield Type** - Select **Descriptive Flexfield**.
 - Lexical Type** - Only **Select** is supported.
 - Application Short Name** - Enter the short name of the Oracle Application that owns this flexfield (for example, FND).
 - Flexfield Code** - Enter the flexfield code defined for this flexfield in the Register Descriptive Flexfield form, for example, FND_DFF1.

Flexfields
+ X

| Lexical Name | Flexfield Type | Lexical Type | Application Short Name | Flexfield Code | Reorder |
|--------------|-----------------------|--------------|------------------------|----------------|---------|
| OFF_SELECT | Descriptive Flexfield | Select | FND | FLEX_DFF1 | ▲▼ |

- Enter the flexfield details:
 - Table Alias** -Specify the table alias to prefix to the column names. Use TABLEALIAS if your SELECT joins to other flexfield tables or uses a self-join.
 - Flexfield Usage Code** - (Optional) Identifies for which segments this data is requested. Default value is "ALL".
- If your descriptive flexfield definition includes parameters, you can enter the parameters in the Parameters region.

To enter parameters, click + to add each parameter. Enter a **Label** and a **Value** for each parameter. The Label must match exactly the label in the descriptive flexfield definition.

GL_Flexfield: Type: Select

Table Alias

Flexfield Usage Code


Parameters
+ X

| *Label | *Value |
|--------------|--------|
| ALL SEGMENTS | 3 |


Include Descriptive Flexfield Reference in SQL Queries

When you create the SQL data set, you can include the descriptive flexfield using the ampersand symbol.

For example, the figure below shows &DFF_SELECT referencing of the descriptive flexfield.



When you click OK, the diagram of your data set shows the columns that are returned from your descriptive flexfield as shown below.



The columns that are returned from the key flexfield have the following limitations:

- Element properties are disabled
- In the data model Structure tab, you cannot edit the following fields: XML Tag Name, Value if Null, Display Name, Data Type
- Subgrouping of descriptive flexfield elements isn't supported
- Element linking isn't supported

7

Add Bursting Definitions

This topic describes the support for bursting reports and how to define a bursting definition in the data model to split and deliver your report to multiple recipients.

Topics:

- [About Bursting](#)
- [What is the Bursting Definition?](#)
- [Prerequisites for Adding Bursting Definition](#)
- [Use SQL Query to Add a Bursting Definition to Your Data Model](#)
- [Use a Visualized Data Set to Add a Bursting Definition to Your Data Model](#)
- [Define the Query for Delivery XML](#)
- [Pass a Parameter to the Bursting Query](#)
- [Define the Split By and Deliver By Elements for a CLOB/XML Data Set](#)
- [Configure a Report to Use a Bursting Definition](#)
- [Sample Bursting Query](#)
- [Create a Table to Use as a Delivery Data Source](#)

Prerequisites for Adding Bursting Definition

This topic lists the prerequisites for adding a bursting definition to the data model.

Before you define bursting and enable bursting in your report, make sure:

- You've defined a SQL query data set or a data set from Data Modeler for this data model.
- The data set is sorted or grouped by the element by which you want to split the data in your bursting definition.
- The delivery and formatting information is available to Publisher. You can provide the information at runtime to Publisher in one of the following ways:
 - The information is stored in a database table available to Publisher for a dynamic delivery definition.
 - The information is hard coded in the delivery SQL for a static delivery definition.
- The report definition for this data model has been created and includes the layouts to be applied to the report data.

Use a Visualized Data Set to Add a Bursting Definition to Your Data Model

You can use a visualized data set from Data Modeler to add a bursting definition to the data model, and then enable bursting in your report.

If you want to add the data sets that are created in Data Modeler to your bursting definition, make sure you create the correct query in Data Modeler, because you can't change the key and delivery channels after you add the data set to the bursting definition in Publisher. In Data Modeler, you can create data models from scratch, or use your business data previously modeled with Oracle Analytics Server.

To use a data set from Data Modeler to define bursting in the data model, and then enable bursting in your report:

1. On the component pane of the data model editor, click **Bursting** to create a bursting query.
2. On the Bursting definition table, click the **Create new Bursting** button.
3. Enter the following for this bursting definition:
 - Name** - Enter a name for the query. For example, *Burst to Email*.
 - Type** - Select **DV Data Sets** to use a data set defined in Data Modeler.
4. In the lower region, enter the following for this bursting definition:
 - Split By** - Select the element from the data set by which to split the data.
 - Deliver By** - Select the element from the data set by which to format and deliver the data.
 - Enable Consolidated Output** - Select the option to generate a single consolidated report.
 - Group Data by Split Key Values** - Select the option to group the data based on Split Key values.
 - Dataset Name** - Select the data set defined in Data Modeler.
5. In the Report Properties dialog, select **Enable Bursting** to enable bursting for a report.

If the *Split By* and *Deliver By* elements reside in an XML document stored as a CLOB in your database, you must enter the full XPATH in the *Split By* and *Delivery By* fields.

About Bursting

Bursting is a process of splitting data into blocks, generating documents for each block, and delivering the documents to one or more destinations.

The data for the report is generated by executing a query once and then splitting the data based on a *Key* value. For each block of the data, a separate document is generated and delivered.

Using Publisher bursting enables splitting a single report based on an element in the data model and deliver the report based on a second element in the data

model. Driven by the delivery element, you can apply a different template, output format, delivery method, and locale to each split segment of the report. Example implementations include:

- Invoice generation and delivery based on customer-specific layouts and delivery preference.
- Financial reporting to generate a master report of all cost centers, splitting out individual cost center reports to the appropriate manager.
- Generation of pay slips to all employees based on one extract and delivered through e-mail.

What is the Bursting Definition?

A bursting definition is a component of the data model. After you define the data sets for the data model, you can set up one or more bursting definitions.

When you set up a bursting definition, you define the following:

- The **Split By** element governs how the data is split. For example, to split a batch of invoices by each invoice, you may use an element called `CUSTOMER_ID`. The data set must be sorted or grouped by this element.
- The **Deliver By** governs how formatting and delivery options are applied. In the invoice example, it's likely that each invoice has delivery criteria determined by customer; therefore, the Deliver By element would also be `CUSTOMER_ID`.
- The **Delivery Query** is a SQL query that you define to construct the delivery XML data file. The query must return the formatting and delivery details.

Use SQL Query to Add a Bursting Definition to Your Data Model

In the Bursting definition table, create a new bursting definition by specifying its name, type, data source, and other properties.

To use a SQL query to add a bursting definition to the data model and enable bursting in your report:

1. On the component pane of the data model editor, click **Bursting** to create a bursting query.
2. On the Bursting definition table, click the **Create new Bursting** button.
3. Enter the following for this bursting definition:
 - Name** - Enter a name for the query. For example, *Burst to File*.
 - Type** - Select **SQL Query** .
 - Data Source** - Select the data source that contains the delivery information.
4. In the lower region, enter the following for this bursting definition:
 - Split By** - Select the element from the data set by which to split the data.
 - Deliver By** - Select the element from the data set by which to format and deliver the data.

Enable Consolidated Output - Select the option to generate a single consolidated report.

Group Data by Split Key Values - Select the option to group the data based on Split Key values.

SQL Query — Enter the query or click **QueryBuilder** to construct the bursting query.

Attachment — You can attach external PDF files to your bursted PDF output.

5. In the Report Properties dialog, select **Enable Bursting** to enable bursting for a report.

If the `Split By` and `Deliver By` elements reside in an XML document stored as a CLOB in your database, you must enter the full XPATH in the `Split By` and `Delivery By` fields.

Attach PDF to Reports using Bursting Engine

You may have a requirement to attach PDFs along with invoices for customers. You can now append these documents to the invoice while bursting.

Once a bursting query is defined, you can enter the attachment query in the **Attachment** tab. The attachment expects the repository source to be a WebCenter content, which can be defined as a data source by the Administrator.

1. Click the **Attachment** tab.
2. Select the content server name from the **Attachment Repository** LOV.
3. Define the SQL query for the attachment in the Content Server.
4. Click **Save** icon after you make changes to the data model.
5. Click the **View Data** button.
6. Click **View** to view the data.
7. Save the data by clicking **Save As Sample Data**.
8. To create a report based on the data model that you created, click **Create Report**.

Note that the PDF attachments are delivered to recipients along with the main report as a single PDF file. The attachment document isn't separately embedded, but appended to the report.

If you want to save the entire PDF report along with the attachments as a single consolidated file, then check the option **Enable Consolidated Output** under bursting query. The consolidated output contains the sequential merge of report and attachment of each burst. A user (with consumer role) who schedules the bursting report job and the Administrator will be able to view the consolidated output in the Job History Details page.

Define the Query for Delivery XML

The bursting query is a SQL query that you define to provide the required information to format and deliver the report.

Publisher uses the results from the bursting query to create the delivery XML.

The Publisher bursting engine uses the delivery XML as a mapping table for each Deliver By element. The structure of the delivery XML required by Publisher is as follows:

```
<ROWSET>
  <ROW>
    <KEY></KEY>
    <TEMPLATE></TEMPLATE>
    <LOCALE></LOCALE>
    <OUTPUT_FORMAT></OUTPUT_FORMAT>
    <DEL_CHANNEL></DEL_CHANNEL>
    <TIMEZONE></TIMEZONE>
    <CALENDAR></CALENDAR>
    <OUTPUT_NAME></OUTPUT_NAME>
    <SAVE_OUTPUT></SAVE_OUTPUT>
    <PARAMETER1></PARAMETER1>
    <PARAMETER2></PARAMETER2>
    <PARAMETER3></PARAMETER3>
    <PARAMETER4></PARAMETER4>
    <PARAMETER5></PARAMETER5>
    <PARAMETER6></PARAMETER6>
    <PARAMETER7></PARAMETER7>
    <PARAMETER8></PARAMETER8>
    <PARAMETER9></PARAMETER9>
    <PARAMETER10></PARAMETER10>
  </ROW>
</ROWSET>
```

- **KEY** — The Delivery key and must match the **Deliver By** element. The bursting engine uses the key to link delivery criteria to a specific section of the burst data. Ensure that you use double quotes around "KEY" in the select statement, for example:

```
select d.department_name as "KEY",
```
- **TEMPLATE** — The name of the Layout to apply. Note that the value is the Layout name (for example, 'Customer Invoice'), not the template file name (for example, invoice.rtf).
- **LOCALE** — The template locale, for example, 'en-US'.
- **OUTPUT_FORMAT** — The output format. The table below shows the valid values to enter for the bursting query.

| Output Format | Value to Enter in Bursting Query | Template Types That Can Generate This Output Format |
|---------------|----------------------------------|--|
| Interactive | N/A | Not supported for bursting |
| HTML | html | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| PDF | pdf | <ul style="list-style-type: none"> – Publisher – RTF – PDF – XSL Stylesheet (FO) |

| Output Format | Value to Enter in Bursting Query | Template Types That Can Generate This Output Format |
|---------------------|----------------------------------|--|
| RTF | rtf | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| Excel (mhtml) | excel | <ul style="list-style-type: none"> – Publisher – RTF – Excel – XSL Stylesheet (FO) |
| Excel (html) | excel2000 | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| Excel (*.xlsx) | xlsx | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| PowerPoint (mhtml) | ppt | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| PowerPoint (*.pptx) | pptx | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| MHTML | mhtml | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| PDF/A | pdfa | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| PDF/X | pdfx | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| Zipped PDFs | pdfz | <ul style="list-style-type: none"> – Publisher – RTF – PDF – XSL Stylesheet (FO) |
| FO Formatted XML | xslfo | <ul style="list-style-type: none"> – Publisher – RTF – XSL Stylesheet (FO) |
| Data (XML) | xml | <ul style="list-style-type: none"> – Publisher – RTF – PDF – Excel – XSL Stylesheet (FO) – XSL Stylesheet (HTML XML/Text) – Etext |

| Output Format | Value to Enter in Bursting Query | Template Types That Can Generate This Output Format |
|---------------|----------------------------------|--|
| Data (CSV) | csv | <ul style="list-style-type: none"> – Publisher – RTF – PDF – Excel – XSL Stylesheet (FO) – XSL Stylesheet (HTML XML/Text) – Etext |
| XML | txml | XSL Stylesheet (HTML XML/Text) |
| Text | text | <ul style="list-style-type: none"> – XSL Stylesheet (HTML XML/Text) – Etext |

- **SAVE_OUTPUT** — Indicates whether to save the output documents to Publisher history tables that the output can be viewed and downloaded from the Report Job History page.

Valid values are 'true' (default) and 'false'. If this property isn't set, the output is saved.

- **DEL_CHANNEL** — The delivery method. Valid values are:
 - EMAIL
 - FAX
 - FILE
 - FTP
 - PRINT
 - WEBDAV
 - WCC
 - CEC
- **TIMEZONE** — The time zone to use for the report. Values must be in the Java format, for example: 'America/Los_Angeles'. If time zone isn't provided, then the system default time zone is used to generate the report.
- **CALENDAR** — The calendar to use for the report. Valid values are:
 - GREGORIAN
 - ARABIC_HIJRAH
 - ENGLISH_HIJRAH
 - JAPANESE_IMPERIAL
 - THAI_BUDDHA
 - ROC_OFFICIAL (Taiwan)

If not provided, the value 'GREGORIAN' is used.

- **OUTPUT_NAME** — The name to assign to the output file in the report job history.
- **Delivery parameters by channel** — The values required for the parameters depend on the delivery method chosen. The parameter values mappings for each method are shown in the table below. Not all delivery channels use all the parameters.

| Delivery Channel | PARAMETER Values |
|------------------|--|
| Email | <p>PARAMETER1: Email address</p> <p>PARAMETER2: cc</p> <p>PARAMETER3: From</p> <p>PARAMETER4: Subject</p> <p>PARAMETER5: Message body</p> <p>PARAMETER6: Attachment value ('true' or 'false'). If your output format is PDF, you must set this parameter to "true" to attach the PDF to the e-mail.</p> <p>PARAMETER7: Reply-To</p> <p>PARAMETER8: Bcc (PARAMETER 9-10 are not used)</p> |
| Printer | <p>PARAMETER1: Printer group</p> <p>PARAMETER2: Printer name or for a printer on CUPS, the printer URI, for example: <code>ipp://myserver.com:631/printers/printer1</code></p> <p>PARAMETER3: Number of copies</p> <p>PARAMETER4: Sides. Valid values are:</p> <ul style="list-style-type: none"> • "d_single_sided" for single-sided • "d_double_sided_l" for duplex/long edge • "d_double_sided_s" for tumble/short edge <p>If the parameter isn't specified, single-sided is used.</p> <p>PARAMETER5: Tray. Valid values are:</p> <ul style="list-style-type: none"> • "t1" for "Tray 1" • "t2" for "Tray 2" • "t3" for "Tray 3" <p>If not specified, the printer default is used.</p> <p>PARAMETER6: Print range. For example "3" prints page 3 only, "2-5" prints pages 2-5, "1,3-5" prints pages 1 and 3-5 (PARAMETER 7-10 are not used)</p> |
| Fax | <p>PARAMETER1: Fax Server Name</p> <p>PARAMETER2: Fax number</p> <p>(PARAMETER 3-10 are not used)</p> |
| WebDAV | <p>PARAMETER1: Server Name</p> <p>PARAMETER2: Username</p> <p>PARAMETER3: Password</p> <p>PARAMETER4: Remote Directory</p> <p>PARAMETER5: Remote Filename</p> <p>PARAMETER6: Authorization type, values are 'basic' or 'digest'</p> <p>(PARAMETER 7-10 are not used)</p> |
| File | <p>PARAMETER1: Directory</p> <p>PARAMETER2: File Name</p> <p>(PARAMETER 3-10 are not used)</p> |

| Delivery Channel | PARAMETER Values |
|---|--|
| FTP and SFTP | PARAMETER1: Server Name PARAMETER2: Username PARAMETER3: Password PARAMETER4: Remote Directory PARAMETER5: Remote Filename PARAMETER6: Secure (set this value to 'true' to enable Secure FTP) (PARAMETER 7-10 are not used) |
| WCC | PARAMETER1: Server Name PARAMETER2: Security Group PARAMETER3: Author PARAMETER4: Account (Optional) PARAMETER5: Title PARAMETER6: Primary File (or File Name) PARAMETER7: Comments (Optional) PARAMETER8: Content ID (Optional. Content ID must be unique.) PARAMETER9: Custom Metadata |
| CEC (Oracle Content and Experience Cloud) | PARAMETER1: Server Name PARAMETER2: Folder Name PARAMETER3: File Name |

Pass a Parameter to the Bursting Query


You can pass the value for an element of your bursting XML using a parameter defined in the data model.

For example, if you want to be able to select the template at the time of submission, you can define a parameter in the data model and use the `:parameter_name` syntax in your query. The following example demonstrates this use case of a parameter in a bursting query.


Assume your report definition includes three layouts: `layout1`, `layout2`, and `layout3`. At submission time you want to select the layout (or `TEMPLATE`, as defined in the bursting query) to use.

To pass a parameter to the bursting query:

1. In your data model, define a list of values with the layout names.



2. Create a menu type parameter. Enter P1 as the name and select **List of Layouts** from **List of Values**.
3. In the bursting query, pass the parameter value to the TEMPLATE field using :P1 as shown in the following figure:



Define the Split By and Deliver By Elements for a CLOB/XML Data Set

If the `split-by` and `deliver-by` elements required for your bursting definition reside in a data set retrieved from a CLOB column in a database, Publisher can't parse the XML to list the elements in the **Split By** and **Deliver By** fields in the data model editor.

You therefore must manually enter the XPath to locate each element in the retrieved XML data set. To ensure that you enter the path correctly, use the data model editor's **Get XML Output** feature to view the XML that is generated by the data engine.

For example, the sample XML code, shown in the figure below, was stored in a CLOB column in the database called "XMLTEXT", and extracted as an XML data set:


```

<!--Generated by Oracle BI Publisher -->
-<DATA_DS>
  -<G_1>
    -<XMLTEXT>
      -<DATA_DS>
        -<G_1>
          <DEPARTMENT_ID>10</DEPARTMENT_ID>
          <DEPARTMENT_NAME>Administration</DEPARTMENT_NAME>
          <MANAGER_ID>200</MANAGER_ID>
          <LOCATION_ID>1700</LOCATION_ID>
        -<G_2>
          <EMPLOYEE_ID>200</EMPLOYEE_ID>
          <FIRST_NAME>Jennifer</FIRST_NAME>
          <LAST_NAME>Whalen</LAST_NAME>
          <EMAIL>JWHALEN</EMAIL>
          <PHONE_NUMBER>515.123.4444</PHONE_NUMBER>
          <HIRE_DATE>1987-09-17T00:00:00.000-07:00</HIRE_DATE>
          <JOB_ID>AD_ASST</JOB_ID>
          <SALARY>4400</SALARY>
          <MANAGER_ID_1>101</MANAGER_ID_1>
          <DEPARTMENT_ID_1>10</DEPARTMENT_ID_1>


```

For this example, you want to add a bursting definition with split by and deliver by element based on the `DEPARTMENT_ID`, which is an element within the CLOB/XML data set.

When you add the bursting definition, the Split By and Deliver By fields can't parse the structure beneath the `XMLTEXT` element. Therefore, the field doesn't display the elements available beneath the `XMLTEXT` node, as shown in the figure below.



To use the DEPARTMENT_ID element as the Split By element, manually type the XPath into the field as shown in the figure below.



Configure a Report to Use a Bursting Definition

Although you can define multiple bursting definitions for a single data model, you can enable only one for a report.

To configure a report to use a bursting definition:

1. Enable a report to use a bursting definition on the Report Properties dialog of the report editor.
2. Schedule a job for this report.
3. Choose to use the bursting definition to format and deliver the report.

You can choose not use the bursting definition and choose your own output and destination as a regular scheduled report.

Sample Bursting Query

This example of a bursting query is based on an invoice report. This report is to be delivered by CUSTOMER_ID to each customer's individual e-mail address

This example assumes that the delivery and formatting preferences for each customer are contained in a database table named "CUSTOMERS". The CUSTOMERS table includes the following columns that will be retrieved to create the delivery XML dynamically at runtime:

- CST_TEMPLATE
- CST_LOCALE
- CST_FORMAT
- CST_EMAIL_ADDRESS

The CUSTOMER_ID will be used as the KEY and also to define the output file name.

The SQL code to generate the delivery data set for this example is as follows:

```
select distinct
CUSTOMER_ID as "KEY",
CST_TEMPLATE TEMPLATE,
CST_LOCALE LOCALE,
CST_FORMAT OUTPUT_FORMAT,
CUSTOMER_ID OUTPUT_NAME,
'EMAIL' DEL_CHANNEL,
CST_EMAIL_ADDRESS PARAMETER1,
'accounts.receivable@example.com' PARAMETER2,
'bip-collections@example.com' PARAMETER3,
'Your Invoices' PARAMETER4,
'Hi'||CUST_FIRST_NAME||': '|| 'Please find attached your
invoices.' PARAMETER5,
'true' PARAMETER6,
'donotreply@mycompany.com' PARAMETER7
from CUSTOMERS
```

Create a Table to Use as a Delivery Data Source

If the delivery information isn't easily available in the existing data sources, then you can consider creating a table to use for the query to create the delivery XML.

Following is a sample:

```
CREATE TABLE "XXX"."DELIVERY_CONTROL"
( "KEY" NUMBER,
  "TEMPLATE" VARCHAR2(20 BYTE),
  "LOCALE" VARCHAR2(20 BYTE),
  "OUTPUT_FORMAT" VARCHAR2(20 BYTE),
  "DEL_CHANNEL" VARCHAR2(20 BYTE),
  "PARAMETER1" VARCHAR2(100 BYTE),
  "PARAMETER2" VARCHAR2(100 BYTE),
  "PARAMETER3" VARCHAR2(100 BYTE),
  "PARAMETER4" VARCHAR2(100 BYTE),
  "PARAMETER5" VARCHAR2(100 BYTE),
  "PARAMETER6" VARCHAR2(100 BYTE),
  "PARAMETER7" VARCHAR2(100 BYTE),
  "PARAMETER8" VARCHAR2(100 BYTE),
  "PARAMETER9" VARCHAR2(100 BYTE),
  "PARAMETER10" VARCHAR2(100 BYTE),
  "OUTPUT_NAME" VARCHAR2(100 BYTE),
  "SAVE_OUTPUT" VARCHAR2(4 BYTE),
  "TIMEZONE" VARCHAR2(300 BYTE),
  "CALENDAR" VARCHAR2(300 BYTE)
) PCTFREE 10 PCTUSED 40 INITRANS 1 MAXTRANS 255 NOCOMPRESS LOGGING
STORAGE(INITIAL 65536 NEXT 1048576 MINEXTENTS 1 MAXEXTENTS 2147483645
PCTINCREASE 0 FREELISTS 1 FREELIST GROUPS 1 BUFFER_POOL DEFAULT)
TABLESPACE "EXAMPLES";
```

If the JDBC driver that you use doesn't support column alias, when you define the bursting control table, the columns must match exactly the control XML tag

name. For example, the KEY column must be named *KEY*, upper case is required. PARAMETER1 must be named *PARAMETER1*, not *parameter1* nor *param1*, or any other non-matching name.

Tips for creating a creating bursting delivery table:

- If the split data set doesn't contain a *DELIVERY_KEY* value, then the document is neither delivered nor generated. For example, using the preceding example, if customer with ID 123 isn't defined in the bursting delivery table, this customer's document isn't generated.
- To enable a split data set to generate more than one document or deliver to more than one destination, duplicate the *DELIVERY_KEY* value and provide different sets of *OUTPUT_FORMAT*, *DEL_CHANNEL*, or other parameters. For example, customer with ID 456 wants his document delivered to two e-mail addresses. To achieve this, insert two rows in the table, both with 456 as the *DELIVERY_KEY* and each with its own e-mail address.

8

Add Custom Metadata for Oracle WebCenter Content Server

This topic describes how to use the data model editor to map fields from your data source to the custom metadata fields. When delivering reports to an Oracle WebCenter Content, Publisher can populate the custom metadata fields defined in your document profiles.

Topics:

- [About Custom Metadata Mapping](#)
- [Map Data Fields to Custom Metadata Fields](#)
- [Delete Unused Metadata Fields](#)

About Custom Metadata Mapping

The Custom Metadata component of the data model enables mapping data fields, for example, invoice number or customer name, from your data model to the metadata fields defined in document profile rules configured on your Oracle WebCenter Content Server.

When you run the report and select an Oracle WebCenter Content server as the delivery destination, Publisher generates and stores the document on the content server with the metadata.

Prerequisites

Certain requirements must be met to use this feature of the data model editor.

Prerequisites:


- The content server must be configured as a delivery destination with custom metadata enabled.
- To map the custom metadata fields to data fields from your data model data set, the data set must be of a type that the data model editor can retrieve the data structure, for example, SQL data sets and Excel data sets are supported; however, web service data sets aren't supported.

Map Data Fields to Custom Metadata Fields

You can start metadata under a document profile.

To map custom metadata:

1. In the data model editor task pane, click **Custom Metadata**.




- Oracle WebCenter Content Server stores metadata under a document profile. A document profile is further nested into rules. To retrieve the metadata fields for mapping, you first select the WebCenter server, then the Content Profile, then the Rules set.

On the Custom Metadata header region, select the Rules as follows:

- **Server** — Select the Web content server where the content profile is defined.
- **Content Profile** — Select the content profile that includes the rules that define custom metadata fields.
- **Rules** — Select the Rules set that specifies the metadata fields.


If you do not select a Rules set, then Publisher loads the metadata for all Rules under the Content Profile.

- Click **Load Metadata**. The lower pane displays the metadata fields defined in the **Rules** you selected.



- For each metadata field, map a data field from your data sets by selecting it from the **Data Mapping** list. The Data Mapping list displays all the data fields from your data sets.

If a metadata field is required a Y is displayed in the **Required** column.



- When you are done with mapping the metadata fields, click **Save**.

Delete Unused Metadata Fields

Publisher loads all the metadata fields defined for the Rules set that you select. You can delete unneeded custom metadata fields.

1. Select the metadata field, either by clicking the field name on the left pane or by clicking the selection column in the table.
2. Click the **Delete** button.

9

Performance Best Practices

This topic provides tips for creating efficient data models for better performance.

Topics:

- [Know Oracle WebLogic Server Default Time Out Setting](#)
- [Best Practices for SQL Data Sets](#)
- [Limit Lists of Values](#)
- [Work with Date Parameters](#)
- [Run Report Online/Offline \(Schedule\)](#)
- [Set Data Model Properties to Prevent Memory Errors](#)
- [Tune SQL Query](#)
- [Validate Data Models](#)

Know Oracle WebLogic Server Default Time Out Setting

WebLogic Server has a default time out of 600 seconds for each request thread.

When the time exceeds 600 seconds, Oracle WebLogic Server marks the thread as *Stuck*. When the number of Stuck threads reaches 25, the server shuts down.

To avoid this problem, verify that your SQL execution time doesn't exceed the WebLogic Server setting.

Best Practices for SQL Data Sets

Consider the following tips to help you create more efficient SQL data sets:

- [Only Return the Data You Need](#)
- [Use Column Aliases to Shorten XML File Length](#)
- [Avoid Using Group Filters by Enhancing Your Query](#)
- [Avoid PL/SQL Calls in WHERE Clauses](#)
- [Avoid Use of the System Dual Table](#)
- [Avoid PL/SQL Calls at the Element Level](#)
- [Avoid Including Multiple Data Sets](#)
- [Avoid Nested Data Sets](#)
- [Avoid In-Line Queries as Summary Columns](#)
- [Avoid Excessive Parameter Bind Values](#)
- [Tips for Multi-value Parameters](#)

- [Group Break and Sort Data](#)

Only Return the Data You Need

Ensure that your query returns only the data you need for your reports. Returning excessive data risks OutOfMemory exceptions.

For example, never simply return all columns as in:

```
SELECT * FROM EMPLOYEES;
```

Always avoid the use of *.

Two best practices for restricting the data returned are:

- Always select only the columns you need

For example:

```
SELECT DEPARTMENT_ID, DEPARTMENT_NAME FROM EMPLOYEES;
```

- Use a WHERE clause and bind parameters whenever possible to restrict the returned data more precisely.

This example selects only the columns needed and only those that match the value of the parameter:

```
SELECT DEPARTMENT_ID, DEPARTMENT_NAME  
FROM EMPLOYEES  
WHERE DEPARTMENT_ID IN (:P_DEPT_ID)
```

Use Column Aliases to Shorten XML File Length

The shorter the column name, the smaller the resulting XML file; the smaller the XML file the faster the system parses it.

Shorten your column names using aliases to shorten I/O processing time and enhance report efficiency.

In this example, DEPARTMENT_ID is shortened to "id" and DEPARTMENT_NAME is shortened to "name":

```
SELECT DEPARTMENT_ID id, DEPARTMENT_NAME name  
FROM EMPLOYEES  
WHERE DEPARTMENT_ID IN (:P_DEPT_ID)
```

Avoid Using Group Filters by Enhancing Your Query

Although the Data Model Group Filter feature enables you to remove records retrieved by your query, this process takes place in the middle tier, which is much less efficient than the database tier.

It's better to remove unneeded records through your query using WHERE clause conditions instead.

Avoid PL/SQL Calls in WHERE Clauses

PL/SQL function calls in the WHERE clause of the query can result in multiple executions.

These function calls execute for each row found in the database that matches. Moreover, this construction requires PL/SQL to SQL context switching, which is inefficient.

As a best practice, avoid PL/SQL calls in the WHERE clause; instead, join the base tables and add filters.

Avoid Use of the System DUAL Table

The use of the system DUAL table for returning the sysdate or other constants is inefficient. You should avoid using the system DUAL table when not required.

For example, instead of:

```
SELECT DEPARTMENT_ID ID, (SELECT SYSDATE FROM DUAL) TODAYS_DATE FROM
DEPARTMENTS WHERE DEPARTMENT_ID IN (:P_DEPT_ID)
```

Consider:

```
SELECT DEPARTMENT_ID ID, SYSDATE TODAYS_DATE FROM DEPARTMENTS WHERE
DEPARTMENT_ID IN (:P_DEPT_ID)
```

In the first example, DUAL isn't required. You can access SYSDATE directly.

Avoid PL/SQL Calls at the Element Level

Package function calls at the element, within the group or row level, are not allowed. You can include package function calls at the global element level because these functions are executed only once per data model execution request.

Example:

```
<dataStructure>
  <group name="G_order_short_text" dataType="xsd:string"
source="Q_ORDER_ATTACH">
  <element name="order_attach_desc" dataType="xsd:string"
value="ORDER_ATTACH_DESC"/>
  <element name="order_attach_pk" dataType="xsd:string"
value="ORDER_ATTACH_PK"/>
```

The following element is incorrect:

```
<element name="ORDER_TOTAL_FORMAT" dataType="xsd:string" value="
WSH_WSHRDPK_XMLP_PKG.ORDER_TOTAL_FORMAT "/>
```



```
<!-- This is wrong should not be called within group.-->
</group>

  <element name="S_BATCH_COUNT" function="sum" dataType="xsd:double"
value="G_mo_number.pick_slip_number"/>
</dataStructure>
```

Avoid Including Multiple Data Sets

It can seem desirable to create one data model with multiple data sets to serve multiple reports, but this practice results in very poor performance.

When a report runs, the data processor executes all data sets irrespective of whether the data is used in the final output.

For better report performance and memory efficiency, consider carefully before using a single data model to support multiple reports.

Avoid Nested Data Sets

The data model provides a mechanism to create parent-child hierarchy by linking elements from one data set to another.

At run time, the data processor executes the parent query and for each row in the parent executes the child query. When a data model has many nested parent-child relationships slow processing can result.

A better approach to avoid nested data sets is to combine multiple data set queries into a single query using the WITH clause.

Following are some general tips about when to combine multiple data sets into one data set:

- When the parent and child have a 1-to-1 relationship; that is, each parent row has exactly one child row, then merge the parent and child data sets into a single query.
- When the parent query has many more rows compared to the child query. For example, an invoice distribution table linked to an invoice table where the distribution table has millions of rows compared to the invoice table. Although the execution of each child query takes less than a second, executing the child query for each distribution can result in STUCK threads.

Example of when to use a WITH clause:

```
Query Q1:
SELECT DEPARTMENT_ID EDID,EMPLOYEE_ID EID,FIRST_NAME FNAME, LAST_NAME
LNAME,SALARY SAL,COMMISSION_PCT COMFROM EMPLOYEES
```

```
Query Q2:
SELECT DEPARTMENT_ID DID,DEPARTMENT_NAME DNAME,LOCATION_ID LOCFROM
DEPARTMENTS
```

Combine the these queries into one using WITH clause as follows:

```
WITH Q1 as (SELECT DEPARTMENT_ID DID,DEPARTMENT_NAME DNAME,LOCATION_ID
LOC
FROM DEPARTMENTS),
Q2 as (SELECT DEPARTMENT_ID EDID,EMPLOYEE_ID EID,FIRST_NAME
FNAME,LAST_NAME LNAME,SALARY SAL,COMMISSION_PCT COMM
FROM EMPLOYEES)
SELECT Q1.*, Q2.*
FROM Q1 LEFT JOIN Q2
ON Q1.DID=Q2.EDID
```

Avoid In-Line Queries as Summary Columns

In-line queries execute for each column for each row. For example, if a main query has 100 columns, and brings 1000 rows, then each column query executes 1000 times.

Avoid the following use of in-line queries. If this query returns only a few rows this approach may work satisfactorily. However, if the query returns 10000 rows, then each sub or in-line query executes 10000 times, which can result in Stuck threads.

```
SELECT
NATIONAL_IDENTIFIERS,NATIONAL_IDENTIFIER,
PERSON_NUMBER,
PERSON_ID,
STATE_CODE
FROM
(select pprd.person_id,(select REPLACE(national_identifier_number,'-')
from per_
national_identifiers pni where pni.person_id = pprd.person_id and
rownum<2)
national_identifiers,(select national_identifier_number from
per_national
identifiers pni where pni.person_id = pprd.person_id and rownum<2)
national_
identifier,(select person_number from per_all_people_f ppf
where ppf.person_id = pprd.person_id
and :p_effective_start_date between ppf.effective_start_date and
ppf.effective_
end_date) PERSON_NUMBER
(Select hg.geography_code from hz_geographies hg
where hg.GEOGRAPHY_NAME = paddr.region_2
and hg.geography_type = 'STATE') state_code
```

Avoid Excessive Parameter Bind Values

Oracle Database allows bind maximum of 1000 values per parameter.

Binding a large number of parameter values is inefficient. Avoid binding more than 100 values to a parameter.

When you create a Menu type parameter and your list of values contains many values, ensure that you enable both the *Multiple Selection* and *Can Select All* options, then also select *NULL* value passed to ensure that too many values are not passed.

New_Parameter_1: Type: Menu

Display Label

List of Values ▼

Number of Values to Display in List

Options Multiple Selection

Can select all

NULL Value Passed All Values Passed

Refresh other parameters on change

Tips for Multi-value Parameters

Report consumers often must run reports that support the certain conditions.

- If no parameter is selected (null), then return all.
- Allow selection of multiple parameter values

In these cases the use of NVL() doesn't work, you should therefore use

- COALESCE() for queries against Oracle Database
- CASE / WHEN for Oracle BI EE (logical) queries

Example:

```
SELECT EMPLOYEE_ID ID, FIRST_NAME FNAME, LAST_NAME LNAME FROM EMPLOYEES
WHERE DEPARTMENT_ID = NVL(:P_DEPT_ID, DEPARTMENT_ID)
```

The preceding query syntax is correct only when the value of P_DEPT_ID is a single value or null. This syntax doesn't work when you pass more than a single value.

To support multiple values, use the following syntax:

For Oracle Database:

```
SELECT EMPLOYEE_ID ID, FIRST_NAME FNAME, LAST_NAME LNAME FROM EMPLOYEES
WHERE (DEPARTMENT_ID IN (:P_DEPT_ID) OR COALESCE (:P_DEPT_ID, null) is
NULL)
```

For Oracle BI EE data source:

```
(CASE WHEN ('null') in (:P_YEAR) THEN 1 END =1 OR "Time"."Per Name
Year" in (:P_YEAR))
```

For Oracle BI EE the parameter data type must be string. Number and date data types are not supported.

Group Break and Sort Data

The data model provides a feature to group breaks and sort data.


Sorting is supported for parent group break columns only. For example, if a data set of employees is grouped by department and manager, you can sort the XML data by department. If you know how the data should be sorted in the final report or template, you specify sorting at data generation time to optimize document generation. The column order specified in the SELECT clause must exactly match the element orders in the data structure. Otherwise group break and sort may not work. Due to complexity, multiple grouping with multiple sorts at different group levels isn't allowed.

Example: In the example shown below, sort and group break are applied to the parent group only, that is, G_1. Notice the column order in the query, data set dialog, and data structure. The SQL column order must exactly match the data structure element field order; otherwise, it may result in data corruption.

Example:

```
SELECT d.DEPARTMENT_ID DEPT_ID, d.DEPARTMENT_NAME DNAME,  
       E.FIRST_NAME FNAME, E.LAST_NAME LNAME, E.JOB_ID JOB, E.MANAGER_ID  
FROM EMPLOYEES E, DEPARTMENTS D  
WHERE D.DEPARTMENT_ID = E.DEPARTMENT_ID  
ORDER BY d.DEPARTMENT_ID, d.DEPARTMENT_NAME
```

Once you define the query, you can use the data model designer to select data elements and create group breaks as shown below.



The Data Structure with breaks is:

```
<output rootName="DATA_DS" uniqueRowName="false">
<nodeList name="data-structure"> <dataStructure tagName="DATA_DS">
<group name="G_1" label="G_1" source="q1">
  <element name="DEPT_ID" value="DEPT_ID" label="DEPT_ID"
fieldOrder="1"/>fieldOrder="2"/>

```

Limit Lists of Values

Lists of values based on SQL queries must be limited to 1000 rows.

Adding blind runaway queries in a list of values can cause `OutOfMemory` exceptions. Consider that the number of rows returned by an LOV is stored in memory, therefore the higher the number of rows the more memory usage.

Work with Lexicals/Flexfields

Publisher supports lexical parameters for Oracle Fusion Applications and Oracle E-Business Suite. Lexical parameters enable you to create dynamic queries.

In Publisher, lexical parameters are defined as:

Lexical – PL/SQL packaged variable defined as a data model parameter.

Key Flexfield (KFF) – Lexical token in a data set query. KFF creates a "code" made up of meaningful segment values and stores a single value as a code combination id. Key Flexfields always return as a single column when used in `SELECT / SEGMENT METADATA` type or condition when used in `WHERE` clause. Key Flexfields execute at run time to extract the lexical definition and then are substituted in the SQL query.

Descriptive Flexfields (DFF) – Customizable expansion space to track additional information that is important and unique to the business. DFFs can be context sensitive, where the information stored in the application depends on the other values of the user input. Unlike Key Flexfields, Descriptive Flexfields can have multiple context-sensitive segments.

When you define any lexical, name the lexical to match the usage so that when the editor dialog pops up it will be easier to enter the default values for the SQL query. For example, if you are using a lexical in a `SELECT` clause, use `"_select"` as a suffix. The default values must be valid to get metadata.

The following example demonstrates the usage of a lexical:

Flexfields
+ X

| Lexical Name | Flexfield Type | Lexical Type | Application Short Name | Flexfield Code | Reorder |
|--------------|----------------|--------------|------------------------|----------------|---------|
| KFF_SELECT | Key Flexfield | Select | GL | GL# | ▲▼ |

KFF_SELECT: Type: Select

Enable Multiple Structure Instance

Code Combination Table Alias

Structure Instance Number

Segments

Show Parent Segments


Output Type

When you create the data set query for the select columns, specify column alias,

```
SELECT gcc.CODE_COMBINATION_ID,
GCC.ATTRIBUTE_CATEGORY,
gcc.segment1 seg1,
gcc.segment2 seg2,
gcc.segment3 seg3,
gcc.segment4 seg4,
gcc.segment5 seg5,
&KFF_SELECT account
FROM GL_CODE_COMBINATIONS GCC
WHERE gcc.CHART_OF_ACCOUNTS_ID = 101
AND &KFF_WHERE
```

When you save the query, a pop-up dialog prompts you for the default values. To get SQL metadata at design time you must specify the default values that can form a valid SQL query. For example,

- if the lexical usage is a SELECT clause then you could enter null
- if the lexical usage is a WHERE clause then you could enter 1 = 1 or 1 =2
- if the lexical usage is ORDER BY clause then you could enter 1



Please enter values for lexical references in SQL-Q1

*&KFF_SELECT flex field

*&KFF_WHERE flex field

OK Cancel

Work with Date Parameters

Publisher always binds date column or date parameter as a timestamp object.

To avoid timestamp conversion, define the parameter as a string and pass the value with formatting as 'MM-DD-YYYY' to match the RDBMS date format.

Run Report Online/Offline (Schedule)

Running reports in interactive/online mode uses in-memory processing.

Use the following guidelines for deciding when a report is appropriate for running online.

For Online / Interactive mode:

- When report output size is less than 50MB
Browsers do not scale when loading large volumes of data. Loading more than 50MB in the browser will slow down or possibly crash your session.
- Data model SQL Query time out is less than 500 seconds
Any SQL query execution that takes more than 500 seconds results in Stuck WebLogic Server threads. To avoid this condition, schedule long-running queries. The Scheduler process uses its own JVM threads instead of Weblogic server threads. It's more efficient to schedule reports than run reports online.
- Total number of elements in the data structure is less than 500
When the data model data structure contains many data elements, the data processor must maintain the element values in memory; which may result in OutOfMemory exceptions. To avoid this condition, schedule these reports. For scheduled reports, the data processor uses temporary file system to store and process data.
- No CLOB or BLOB columns
Online processing holds the entire CLOB or BLOB columns in memory. You should schedule reports that include CLOB or BLOB columns.

Set Data Model Properties to Prevent Memory Errors

You can use the data model properties to help prevent memory errors in your system.

You can set the **Query Time Out**, **Enable SQL Pruning**, and **Skip Unused Data Set Query** properties at the data model level.

Only an administrator can set the **Enable Data Model scalable mode** and **DB fetch size** runtime properties for all data models.

Query Time Out

The Query Time Out property specifies the time limit in seconds within which the database must execute SQL statements for scheduled reports.

The default value of SQL query timeout for scheduled reports is 600 seconds. You specify the time limit on the data model. By increasing the number of seconds, you risk getting stuck threads in the Oracle WebLogic Server. Don't raise the value unless all other optimizations and alternatives have been utilized.

Queries that can't execute in less than 600 seconds aren't well optimized. Ask your DBA or performance expert to analyze and fine-tune the query. Increase the number of seconds only after attempting optimizations of the query.

Enable SQL Pruning

The SQL pruning property specifies whether to fetch only the columns that are used in the report layout/template.

Set the **Enable SQL Pruning** property to **On** in the Data Model Properties page to enhance performance by allowing the system to fetch only the columns used in the report layout or template. The system won't fetch columns that are defined in the query but not used in the report. This property doesn't alter the WHERE clause but instead wraps the entire SQL query with the columns specified in the layout.

If you enabled SQL pruning, you can use the **Skip Unused Data Set Query** property to skip the execution of unused data sets in a layout.

DB Fetch Size

The DB Fetch Size runtime property specifies the number of rows of data that are fetched from the database at one time.

An administrator can set the **DB fetch size** runtime property for all data models. A large number reduces the number of calls to the database but consumes more memory for storing more rows of data. Set the **Enable Auto DB fetch size mode** property to true to allow the system to calculate the optimal fetch size at runtime.

Scalable Mode

The scalable mode property in data model specifies whether to use the temp file system to generate data.

Administrator can set the **Enable Data Model scalable mode** runtime property for all data models.

If you select **Enable Data Model scalable mode**, Publisher uses the temp file system to generate data, and the data processor uses the least amount of memory.

This scalable mode property can be set at the data model level and the instance level. The data model setting overrides the instance value. The instance value can be overridden by Data model setting shown here:

The following table details the expected results for the possible on/off settings at each level:

| Scalable Mode Instance Value | Scalable Mode Data Model Value | Expected Result |
|------------------------------|--------------------------------|-----------------|
| On | Instance | On |
| Off | Instance | Off |
| On | On | On |
| On | Off | Off |
| Off | On | On |
| Off | Off | Off |

Tune SQL Query

Query tuning is the most important step to improve performance of any report.

Explain plan, SQL Monitoring, SQL Trace facility with TKPROF are the most basic performance diagnostic tools that can help to tune SQL statements in applications running against the Oracle Database.

Publisher provides a mechanism to generate the explain plan and SQL monitoring reports and to enable SQL session trace. This functionality is applicable to SQL statements executing against Oracle Database only. Logical queries against any other type of database are not supported.

Generate Explain Plan

You can generate an Explain plan at the data set level for a single query or at the report level for all queries in a report.

For more information about interpreting the explain plan, see *Oracle Database SQL Tuning Guide*.

Explain Plan for a Single Query

From the SQL data set Edit dialog you can generate an explain plan before actually executing the query. This provides a best guess estimation of a plan. The query will be executed binding with null values.

Click **Generate Explain Plan** on the Edit SQL Query dialog. Open the generated document in a text editor like Notepad or WordPad.

Explain Plan for Reports

To generate an explain plan for a report, run the report through the Scheduler.

1. From the **New** menu, select **Report Job**.
2. Select the report to schedule then click the **Diagnostics** tab.
You must have BI Administrator or BI Data Model Developer privileges to access the **Diagnostics** tab.
3. Select Enable SQL Explain Plan and Enable Data Engine Diagnostic.
 - Enable SQL Explain Plan — Generates a diagnostic log with Explain plan/SQL monitor report information.
 - Enable Data Engine Diagnostic — Generates a data processor log.
 - Enable Report Processor Diagnostic — Generates FO (Formatting Options) and server related log information.
 - Enable Consolidated Job Diagnostic — Generates the entire log, which includes scheduler log, data processor log, FO and server log details.
4. Submit the report.
5. From the Home page, under **Browse/Manage**, select **Report Job History**.
6. Select the report to view the details. Under **Output & Delivery** click **Diagnostic Log** to download the explain plan output.

Sample Explain plan:

```

SQLQuery;EXPLAIN PLAN SET STATEMENT_ID = 'dm_plan_Q2_150622_0249' FOR
select /* QUERY_SRC('datamodel: _Users_riyengar_XPLAN_Test1_xdm,dataset:Q2') */ *
from departments
WHERE :DEPARTMENT_ID=DEPARTMENT_ID
SQL Query Timeout: 600
Number of SQL Executionst: 108
PLAN_TABLE_OUTPUT
-----
Plan hash value: 4024094692
-----
| Id | Operation | Name | Rows | Bytes | Cost (%CPU) | Time |
-----|-----|-----|-----|-----|-----|-----|-----|
| 0 | SELECT STATEMENT | | 1 | 7 | 1 (0) | 00:00:01 |
| 1 | TABLE ACCESS BY INDEX ROWID | DEPARTMENTS | 1 | 7 | 1 (0) | 00:00:01 |
|* 2 | INDEX UNIQUE SCAN | DEPT_ID_PK | 1 | | 0 (0) | 00:00:01 |
-----
Predicate Information (identified by operation id):
-----
2 - access("DEPARTMENT_ID"=:DEPARTMENT_ID)

```

Guidelines for Tuning Queries

Tune queries by following a set of guidelines.

- Analyze the explain plan and identify high impact SQL statements.
- Add required filter conditions and remove unwanted joins.
- Avoid and remove FTS (full table scans) on large tables. Note that in some cases, full table scans on small tables are faster and improve query fetch. Ensure that you use caching for small tables.
- Use SQL hints to force use of proper indexes.
- Avoid complex sub-queries and use Global Temporary Tables where necessary.
- Use Oracle SQL Analytical functions for multiple aggregation.
- Avoid too many sub-queries in where clauses if possible. Instead rewrite queries with outer joins.
- Avoid group functions like HAVING and IN / NOT IN where clause conditions.
- Use CASE statements and DECODE functions for complex aggregate functions.

Tips for Database Tuning

Follow best practices when tuning a database.

- Work with your Database Administrator to gather statistics on the tables.
- If the server is very slow, analyze network / IO / Disk issues and optimize the server parameters.
- In some scenarios when you cannot avoid a large data fetch you may encounter PGA Heap size errors in the database. To resolve these issues, increase PGA heap size as a last resort. Use the following statement to increase heap size:

```
alter session set events '10261 trace name context forever, level
2097152'
```

Validate Data Models

When you validate data models, the validation messages help you correct data models, optimize queries, reduce stuck threads, and enhance the reporting performance.

After you create or edit a data model that's created in the current or previous releases, if you click **Validate**, Publisher:

1. Checks the queries used for data sets, LOVs, and bursting definitions.
2. Generates the execution plan for SQL queries.
3. Displays a list of error and warning messages.

Take the required action based on the validation message. See [Data Model Validation Messages](#).

Note that if you have upgraded Publisher from a previous release, the existing data models are marked as not validated.

Data Model Validation Messages

This topic lists the data model validation messages for your reference.

Message Types

- **Error** – You must resolve the data model errors if you want to use the data model to run a report.
- **Warning** – Make the correction suggested in the warning message. Reporting performance might get affected if you choose to run the report ignoring the warning.

Message Reference

| Validation Type | Message Type | Message | Limit |
|-----------------|--------------|---|-------|
| Query | Warning | SQL query contains SELECT *. Use of '*' is restricted. Select the specific columns. | |
| Query | Warning | Data model contains nested BI JDBC queries. Linking logical queries is restricted. Use OTBI instead of Publisher reports or remove the link between OBIEE data sets. | |
| Query | Warning | SQL query execution plan contains merge cartesian joins. Generate the explain plan for the SQL query and identify the merge cartesian joins. Add the required filters in the SQL query. | |
| Runtime | Warning | Number of bind values per parameter more than the limit of {0} results in poor performance. Reduce the number of bind values. | 100 |

| Validation Type | Message Type | Message | Limit |
|-----------------|--------------|--|-------|
| Query | Warning | Number of columns in SELECT exceeds the limit of {0}. Select only the required columns and enable pruning. See Publisher Best Practices for SaaS Environments (Doc ID 2145444.1). | 30 |
| Query | Warning | Number of columns in SELECT exceeds the limit of {0}. Select only the required columns. | 100 |
| Query | Warning | SQL query contains non-equi joins. Intermediate row spawning can cause performance issues. Replace non-equi joins with equi join or outer join. | |
| Query | Warning | Selected column name length exceeds the limit of {0}. Length of the column name must not be more than 15 characters. Use short alias for column names. | 15 |
| Query | Warning | Number of inline or subquery exceeds the limit of {0}. Remove the additional in-line select queries. | 10 |
| Query | Warning | SQL query contains the FROM DUAL clause. SQL query contains too many DUAL tables. Avoid the usage of FROM DUAL clause. | |
| Query | Warning | Number of LOB columns in SELECT exceeds the limit of {0}. Select only the required columns. | 2 |
| Query | Error | Query contains DDL or DML keywords. Remove the DDL and DML keywords from the SQL query. | |
| Structure | Warning | Number of group breaks on single dataset exceeds the limit of {0}. Remove multiple groups from the dataset. | 2 |
| Structure | Warning | Data model contains group filters. Replace the group filters with the WHERE clause in the SQL query. | |
| Runtime | Error | Data model property is invalid or contains invalid values. Specify the correct data model property and check the property value. | |
| Query | Warning | SQL query execution plan contains full table scans. Provide the required filters on indexed columns in the SQL query. | |
| Query | Warning | SQL query execution plan contains high buffer reads. Buffer reads exceed the limit of 1GB. Add filters in the SQL query to reduce the data fetch volume. | |
| Query | Warning | SQL query execution plan contains high CPU cycles. Add the required filters in the SQL query to reduce the data fetch volume. | |

| Validation Type | Message Type | Message | Limit |
|-----------------|--------------|--|-------|
| Query | Warning | SQL query execution plan contains function calls on filter columns. Use of SQL function calls on index columns results in poor performance. Remove function calls on filter columns. | |
| Query | Warning | Detected function calls in the WHERE clause predicates. | |
| Query | Warning | Detected calls to PL/SQL functions in the SELECT list; such calls may affect performance significantly. | |
| Query | Warning | Scalar subqueries are subqueries in the SELECT list. They must return exactly one value. Using ROWNUM or DISTINCT to restrict the output indicates potential performance problem. | |
| Query | Warning | Too many values in the IN-LIST filter might prevent the optimizer from finding a more efficient plan. | |
| Runtime | Warning | Security predicate is wrapped inside a subquery causing unnecessary nesting. BI Server has generated too many joins between WITH sub-queries using unsupported SYS_OP_MAP_NONNULL function. | |
| Query | Warning | BI Server has generated too many joins between WITH sub-queries using unsupported SYS_OP_MAP_NONNULL function. | |
| Query | Warning | An inline view or table detected was OUTER-joined on optional side of the join, and has no data selected from it. | |
| Query | Warning | Scalar subqueries are subqueries in the SELECT list. Having a WITH clause in scalar subquery might create serious performance problems. | |
| Query | Warning | Tables that are listed in a query and joined to other tables, but never used in the SELECT FROM clause might be redundant. Check if this table is joined on the primary key column to the foreign key columns of other tables. | |
| Query | Warning | Column is defined as scalar correlated subquery and later used in a filter or join expression. This might cause serious performance degradation. | |
| Query | Warning | Predicates that use bind variables in a non-trivial way. For example, (:JCODE IS NULL OR mcd.JCODE LIKE :JCODE). | |
| Query | Warning | CASE Expression contains more than 10 complex WHEN ... THEN expressions. | |
| Query | Warning | Columns defined as constants (literals) in a View Object were referenced in join predicate(s) in a query. | |
| Query | Warning | The SQL statement has more than 10 UNION branches in one sub-query. | |

| Validation Type | Message Type | Message | Limit |
|------------------------|---------------------|---|--------------|
| Query | Warning | Remove unnecessary table reference as the same column is used in SELECT, JOIN and FILTER. | |
| Structure | Warning | Don't store data in CLOB and convert to XML. Store in XML for better performance. | |

Part II

Create Pixel-Perfect Reports and Layouts

This part describes how to create pixel-perfect reports and layouts.

Topics:

- [Introduction to Designing Reports](#)
- [Create and Edit Reports](#)
- [Create Publisher Layout Templates](#)
- [Create RTF Templates](#)
- [Create RTF Templates Using the Template Builder for Word](#)
- [Create Excel Templates](#)
- [Create PDF Templates](#)
- [Create eText Templates](#)
- [Set Report Processing and Output Document Properties](#)

10

Introduction to Designing Reports

This topic introduces the components that comprise a pixel-perfect report.

Topics:

- [Overview for Report Designers](#)
- [About the Layout Types](#)
- [About Setting Run-Time Properties](#)
- [About Translations](#)
- [About Style Templates](#)
- [About Sub Templates](#)

Overview for Report Designers

A report consists of a data model, a layout, and a set of properties.

Optionally, a report may also include a style template and a set of translations. A report designer performs the following tasks:

- Design the layout for the report. The layout can be created using a variety of tools. The output and design requirements of a particular report determine the best layout design tool. Options include the Layout Editor, which is a Web-based layout design tool and enables interactive output, Microsoft Word, Adobe Acrobat, Microsoft Excel, and Adobe Flexbuilder.
- Set runtime configuration properties for the report.
- Design style templates to enhance a consistent look and feel of reports in your enterprise.
- Create subtemplates to re-use common functionality across multiple templates.
- Enable translations for a report.

Define Summary Text for Tables

You can define a text summary to describe a table within a report.

To define summary table text:

1. Select a table.
2. On the **Properties** pane, expand **Misc**.
3. In the **Summary** property, enter the table summary text.

About the Layout Types

You have several options for designing layouts for reports.

The layout type determines the types of output documents supported. The following formats are supported.

- **Publisher layout (XPT)**
The Layout Editor is a Web-based design tool for creating layouts. Layouts created with the Layout Editor support interactive viewing as well as the full range of output types supported by RTF layouts.
- **Rich Text Format (RTF)**
A plug-in utility for Microsoft Word that automates layout design and enables you to connect to Publisher to access data and upload templates directly from a Microsoft Word session. The RTF format also supports advanced formatting commands providing the most flexible and powerful of the layout options. RTF templates support a variety of output types.
- **Portable Document Format (PDF)**
PDF templates are used primarily when you must use a predefined form as a layout for a report (for example, a form provided by a government agency). Because many PDF forms already contain form fields, using the PDF form as a template simply requires mapping data elements to the fields that exist on the form. You can also design PDF templates using Adobe Acrobat Professional. PDF templates support only PDF output.
- **Microsoft Excel (XLS)**
Excel templates enable you to map data and define calculations and formatting logic in an Excel workbook. Excel templates support Microsoft Excel (.xls) output only.
- **XSL Stylesheet**
Layouts can also be defined directly in XSL formatting language. Specify whether the layout is for Data (CSV), Data (XML), FO Formatted XML, HTML, Text, or XML transformation.
- **eText**
These are specialized RTF templates used for creating text output for Electronic Data Interchange (EDI) or Electronic Funds Transfer (EFT) transactions.

See [Create and Edit Reports](#).

About Setting Run-Time Properties

Publisher provides a variety of user-controlled settings that are specified using an easily accessible Properties dialog. These include security settings for individual PDF reports, HTML output display settings, font mapping, currency formatting, and other output-specific settings.

See [Set Report Processing and Output Document Properties](#). These settings are also configured at the system-level, but can be customized per report.

About Translations

Publisher provides the ability to create an XLIFF file from RTF templates. XLIFF is the XML Localization Interchange File Format, and is the standard format used by

localization providers. Using Publisher's XLIFF generation tool you can generate the standard translation file of an RTF template.

You can then translate this file (or send to a translation provider). Once translated, the file can be uploaded to the report definition under the appropriate locale setting so that at runtime the translated report runs automatically for users who select the corresponding locale.

See [Translation Support Overview and Concepts](#).

About Style Templates

A style template is an RTF template that contains style information that can be applied to layout templates. The style information in the style template is applied to report layout templates at runtime to achieve a consistent look and feel across your enterprise reports.

See [Create and Implement Style Templates](#).

About Sub Templates

A Sub Template is a piece of formatting functionality that can be defined once and used multiple times within a single layout template or across multiple layout template files.

This piece of formatting can be in an RTF file format or an XSL file format. RTF subtemplates are easy to design as you can use Microsoft Word native features. XSL subtemplates can be used for complex layout and data requirements.

See [Understand Subtemplates](#).

11

Create and Edit Reports

This topic describes how to create and edit pixel-perfect reports.

Topics:

- [About Report Components](#)
- [Create Reports: Process Overview](#)
- [Create Reports](#)
- [Create Reports Using a Direct Connection to a Subject Area](#)
- [Edit Reports](#)
- [Add Layouts to the Report Definition](#)
- [Configure Layouts Using the List View](#)
- [Configure Parameter Settings for the Report](#)
- [Configure Report Properties](#)
- [Access Reports via a URL](#)

About Report Components

The first step in creating a new report is to select the source of the data for the report. A Data Model defines data that is used by a report.

A report typically consists of the following components:

- Data Model
- Layout
- Properties
- Translations

A Data Model may contain multiple data sets and it defines how data fields are structured in relation to each other. It may also contain parameters with lists of values, bursting definitions and other structures or properties that determine how data is provided to a report.

Reports that use Oracle Analytics Server Subject Areas as the data source do not require a separate data model. See [Create Reports Using a Direct Connection to a Subject Area](#).

The next step is to design a layout for the report data. The layout defines how the data is presented in the report. A layout consists of a template file and a set of properties for rendering the template file. Publisher supports templates created from a variety of sources including Microsoft Word, Adobe Acrobat, Microsoft Excel, and Publisher's own layout editor. A report can include multiple layouts.

Next, configure the properties for the report. The report properties enable you to control many aspects of the report generation, formatting, and display.

Optionally, add translations for the report. Publisher's translation support enables you to include translations for individual layouts or for all translatable strings in the layout, data model, and the report metadata.

This topic describes the process of creating a report by selecting a data model, adding a layout, and configuring properties using the report editor.

| Topic | More Information |
|---|---|
| Creating a data model | Process Overview for Creating a Data Model |
| Selecting a layout type | About the Layout Types |
| Creating specific layout template types | Create Publisher Layout Templates Create RTF Templates Create RTF Templates Using the Template Builder for Word Create Excel Templates Create PDF Templates Create eText Templates |
| Translating reports | Translation Support Overview and Concepts |

Create Reports: Process Overview

The Create Report process guides you through the steps to create a basic report. After creating the basic report, use the report editor to configure the report and create additional layouts.

The Create Report process guides you through the following steps:

1. Launch the Create Report guide to select a data source, and create a basic report. You can create a simple layout using the guide or add the layout later.
2. Edit the simple report layout that you created using the Create Report guide, or create a new layout.
3. Configure the properties for the layout.
4. Configure parameters for the report.
5. Configure report properties.
6. Add translations for the layouts. Complete this step if the report requires support for multiple languages.

Create Reports

Use the Create Report guide to create reports.

If your user interface preference is set to a bidirectional language, the Create Report guide doesn't display all components in right-to-left orientation.

To create a report:

1. Launch the Create Report guide in one of these ways.
 - From the global header, click **New**, and then click **Report**.
 - From the Home page, under the **Create** region, click **Report**.
 - On the catalog toolbar, click **New**, and then click **Report**.
 - From the Data Model editor page, click **Create Report**.
2. Follow the guided steps to select data and layout for the report, and if required add charts and tables.
3. Save the report.

Select a Data Source

Building a report begins with selecting a data source.

Choose one of the following options to begin building your report:

- **Use Data Model**
Select an existing data model from the catalog.
Click **Next** to proceed to choose **Guide Me** or **Use Report Editor**.
- **Upload Spreadsheet**
Upload a Microsoft Excel file (file type.xls or .xlsx). If the uploaded spreadsheet contains multiple sheets, select the sheet to use as the data source. You can include data from only one sheet.

To use multiple sheets in a workbook, you first create a data model that includes each spreadsheet as a data set, and then use that data model as the data source for the report.
Click **Next** to proceed to choose **Guide Me** or **Use Report Editor**.
- **Use Subject Area**
Select a subject area from the repository. This option enables you to directly query the server and eliminates the need to create a data model in Publisher. The Create Report guide limits you to one subject area, however, you can create a report against multiple subject areas using the report editor.
Click **Next** to proceed to choose **Guide Me** or **Use Report Editor**.

Choose Guide Me or Use Report Editor

You can either choose guide or to use the report editor on the Create Report page.

The following table describes the options on the Create Report page.

| Option | Description |
|----------|--|
| Guide Me | <p>This option guides you through defining the layout of your data in common predefined report styles. Choose this option to:</p> <ul style="list-style-type: none"> • Create a report with simple components • Select a common report style with basic options • Quickly view the data in preview mode <p>Proceed to select the report layout.</p> |

| Option | Description |
|-------------------|--|
| Use Report Editor | This option prompts you to save the report and then opens the report editor. Choose this option to proceed to configure the report or to create a more complex layout. |

Select the Report Layout

When you choose Guide Me, you are prompted to select the report page options.

After you select the data source for the report, select the report page options and report layout to define how data is displayed in the report.

To select report layout:

1. Select report page options as follows:
 - Select the **Portrait** or **Landscape** page option to define the report page orientation.
 - Select the **Page Header** option to include the date in the report page header.
 - Select the **Page Footer** option to include the page number in the report page footer.
2. Select one of the following report layouts:
 - Table (default)
 - Chart
 - Pivot Table
 - Chart and Table
 - Chart and Pivot Table
 - Two Charts and Table
3. Click **Next** to proceed.

Choose Columns for Report Layouts

The layout that you select on the Select Layout page drives the remaining pages that you must complete to create the report.

For example, if you select the Table layout, Create Table is the next page displayed.

After you select a layout, select the data source columns to include in the report. As you select columns, sample data for the columns displays on the page. The selected columns display in the order selected.

Keep the following points in mind about sample data:

- For data models: The Create Report process uses the sample data that is saved to the data model. If sample data isn't attached to the data model, the selected column headings display without data.
- For uploaded spreadsheets: Sample data is displayed from the selected spreadsheet.

- For subject areas: Sample data is displayed directly from the columns in the subject area.

Table Layout

On the **Create Table** page you add columns to the layout by dragging and dropping them from the Data Source pane to the table area.

The columns are displayed in a simple tabular format and the column widths are automatically adjusted based on the number of selected columns as shown in the following illustration.

To remove a column from the table, hover your mouse over the upper-right hand corner of the column header and click **Delete**.

Create Report

Select Data Select Layout Create Chart Create 2nd Chart **Create Table** Save Report

Drag fields from the Data Source to create the table. Sample data is displayed.

Data Source

- ▲ A - Sample Sales
 - ▶ Time
 - ▶ Products
 - ▶ Offices
 - ▶ Sales Person
 - ▶ Customers
 - ▶ Orders
 - ▶ Other Objects
 - ▲ Facts
 - ▲ Base Facts
 - # 1- Revenue
 - # 2- Billed Quanti

| D4 Company | D3 Organization | D1 Office | 2- Billed Quantity |
|----------------|--------------------|-------------------|--------------------|
| Genmind Corp | Production Org. | Figueroa Office | 311012 |
| Genmind Corp | Production Org. | Guadalupe Office | 310911 |
| Genmind Corp | Production Org. | River Office | 274721 |
| Genmind Corp | Subcontracted Org. | Copper Office | 276642 |
| Genmind Corp | Subcontracted Org. | Morange Office | 287876 |
| Stockplus Inc. | Inbound Org. | Blue Bell Office | 279347 |
| Stockplus Inc. | Inbound Org. | Foster Office | 281633 |
| Stockplus Inc. | Inbound Org. | Glenn Office | 269829 |
| Stockplus Inc. | Inbound Org. | Montgomery Office | 272968 |
| Stockplus Inc. | Inbound Org. | Tellaro Office | 265217 |
| | | | 5657221 |

Show Grand Totals Row Preview Report

Previous Next Cancel Finish

The **Show Grand Totals Row** option is selected by default to automatically display an aggregated summary row for all columns. Deselect this option to remove the row from the table.

Click **Preview Report** to display the report in the report viewer.


Click **Next** to proceed to save the report.

Chart Layout

The Chart Layout page supports three types of charts. Choose the chart type by clicking its icon: Bar, Line, or Pie. Add columns to the chart by dragging and dropping them from the **Data Source** pane to the chart area.

The following figure shows the create chart layout. You can specify two values each to display for the chart Value, Series, and Label.

The layout editor supports a variety of more complex charts. To add more values to this chart or create another chart type, edit this layout in the layout editor after saving the report.



To remove a value from the chart, hover your mouse over the upper-right hand corner of the item label and click **Delete**.

Click **Preview Report** to display the report in the report viewer.

Click **Next** to proceed to save the report.

Chart and Table Layout

When you select the chart and table layout, you add columns to the Create Chart page first, click **Next**, and then the Create Table page displays with the columns that you previously selected for the chart.

You can also add additional columns and remove columns on this page.

Click **Next** to proceed to save the report.

Pivot Table Layout

When you select columns for the pivot table layout, the columns display on the Create Table page.

The figure below shows the columns displayed.

Drag fields from the Data Source to create the pivot table. Sample data is displayed.

| | | BizTech | FunPod | HomeView | Total |
|------|----------------|------------------------|------------------------|------------------------|------------|
| | | 1- Revenue | 1- Revenue | 1- Revenue | 1- Re |
| 2010 | Genmind Corp | 2154210.74 | 1980258.18 00000002 | 1993378.24 | 6127 01 |
| | Stockplus Inc. | 3209986.69 | 2671224.7 | 3210421.81 | 9091 01 |
| | Tescare Ltd. | 2913244.46 99999997 | 2584515.88 | 2782759.29 | 8280 |
| 2011 | Genmind Corp | 2167842.75 | 1967397.91 00000001 | 1818447.70 00000002 | 5953 |
| | | | 2743937.28 | | |

The **Show Row Grand Totals** option is selected by default. Deselect this option to hide the row in the table that includes the grand total for each column.

The **Show Column Grand Totals** option is selected by default. Deselect this option to hide the column in the table that includes the grand total for each row.

Click **Switch Rows and Columns** to flip the rows and columns axes.

Click **Preview Report** to display the report in the report viewer.

Click **Next** to proceed to save the report.

Chart and Pivot Table Layout

When you select the chart and pivot table layout, you add columns to the Create Chart page first, click **Next**, and then the Create Table page displays with the columns that you previously selected for the chart. You can also add additional columns and remove columns on this page.

Click **Next** to proceed to save the report.

Two Charts and Table Layout

When you select the two charts and table layout, you add columns to the Create Chart page first, click **Next**, and then **Create 2nd Chart**.


Once you add columns to the Create 2nd Chart page, click **Next** to display the Create Table page. The Create Table page displays with the columns that you already selected for the first chart. You can also add additional columns and remove columns on this page.

Click **Next** to proceed to save the report.

Save the Report

You can save the report layout and the columns you added.

Use the Save Report page as shown in the following illustration.



Select one of the following options:

- To run the report you just created, click **View Report** and then click **Finish**. The final page prompts you to save the report. After saving, Publisher runs and displays the report in the report viewer.

- To customize the report layout, click **Customize Report Layout** and then click **Finish**. The final page prompts you to save the report. After saving, the report opens in the layout editor.

Create Reports Using a Direct Connection to a Subject Area

Subject area reports contain queries that are issued directly to the Oracle BI Server, therefore the report doesn't use a Publisher data model.

When you run a report that uses a subject area as a data source, the Oracle BI Server optimizes and determines how many queries are actually issued to the database based on the columns selected for the report.

Keep the following points in mind when creating a subject area report:

- You must use the Create Report guide to create subject area reports.
- No data model is created for a subject area report. Publisher executes the subject area queries as defined in Oracle Analytics Server to retrieve the report data.
- In the Create Report guide, you can only select one subject area for a report. To create a report that uses multiple subject areas, first create a report against a single subject area using the Create Report guide and then edit the report in the report editor to add subject areas. See [Create a Report Against Multiple Subject Areas](#).
- For reports that use a subject area, Publisher calculates subtotals and totals based on the data received from the BI Server, which is already summarized. As Publisher isn't performing the summary calculations, certain functions that require access to the original column data, such as count distinct and average, may deliver different results in Publisher.
- Hierarchical columns that are available in Oracle Analytics Server are not available for use in subject area reports in Publisher.
- Be aware that if you link multiple fields from unrelated subject areas in a single report component such as a graph, table, or pivot table, the rendering of the component may fail because the data cannot be correlated correctly.

Create Subject Area Reports

You can create a subject area report by launching the create report guide.

To create a subject area report:

1. Launch the Create Report guide.
2. Select a subject area. Only one subject area can be selected.
To report against multiple subject areas, after selecting the first subject area, select the **Use Report Editor** option, and click **Finish** to save the report. Then, use the report editor to add the additional subject areas.
3. Follow the prompts to create your report layout as described in [Choose Columns for Report Layouts](#).

Add Parameters to Subject Area Reports

Parameters are usually defined in the data model for Publisher reports. Reports that run directly against a subject area do not use a data model, therefore, you must use the report editor to set up parameter definitions for subject area reports.


If you intend to use a subject area report in an Oracle Analytics Server dashboard and you need to use parameters.

Add parameters to subject area reports

1. Create and save the report as described in [Create Subject Area Reports](#).
2. In report editor, click **Parameters** to launch the Edit Parameters dialog as shown in the following figure.


| Show | Name | Display | Multiple | Label | Default Value | Row Placement | Edit |
|-------------------------------------|------------|-------------|----------|------------------|---------------|---------------|------|
| <input checked="" type="checkbox"/> | P3 LOB | Checkboxes | True | Line of Business | All | 1 | |
| <input checked="" type="checkbox"/> | D4 Company | Choice List | False | Company | Genmind Corp | 1 | |

3. Click **Add** to launch the Select a Column to Define Parameter dialog as shown in the following figure.



4. Select a parameter column and click **OK** to launch the Edit Parameter dialog as shown in the following figure.

The options displayed for selection in the Edit Parameter dialog are driven by the parameter column data type.




5. Enter the parameter label to be displayed in the report.
6. Select a parameter display option:
 - **Calendar** - Provides users with a field into which they can enter a specific date, as well as a calendar pop-up to select a date. This display option is only available for selection if the parameter has a date column type.
 - **Choice List** - Provides users with a collapsed list of all prompt values. This display option is useful for a long list of values where you want to provide the user with the ability to search for a specific value.
 - **Checkboxes** - Provides users with a visible list of all prompt values where a small, selectable box displays before each value item. This display option is suitable for a prompt that contains a smaller set of data.
 - **Radio Buttons** - Provides users with a visible list of all prompt values where a radio button is displayed before each prompt value. This display option is useful for short lists of values where the user is to select only one prompt value.
 - **Text** - Provides users with a field into which they can enter a specific prompt value. This display option cannot be used for multiple prompt values. Only the field and the field label are displayed for this option.
7. Select the parameter operator. The default value is set to **is equal to/is in**.
8. Click **OK**.

Create a Report Against Multiple Subject Areas

You can use the report editor to link a report to multiple subject areas.

To add multiple subject areas to a report:

1. Use the report editor to open the report. The upper left corner displays the subjects areas already linked to the report.
2. Click **Edit Subject Areas** to launch the Select Subject Areas dialog as shown in the following figure:




3. From the **Available** pane, select one or more subject areas.
4. Click **Add** to move the subject area(s) to the **Selected** pane.
5. Click **Finish**.

Edit Reports

Navigate to the report editor through the Create Report process flow or by clicking a report's **Edit** link in the catalog.

The report editor is shown in the following figure:



Use the report editor to:

- Add layouts
- Configure layouts
- Configure the parameters for this report
- Configure the report properties
- Update the data model associated with the report


This procedure addresses these options in the order listed.

Add Layouts to the Report Definition

You can add a layout to a report in three different ways:

- **Create Layout** - Select one of the basic or shared templates to launch the Layout Editor.
- **Upload Layout** - Upload a template file layout that you have designed in one of the supported file types.
- **Generate Layout** - Automatically generate a simple RTF layout.

To add a new layout, from the report editor, click **Add New Layout**. The Add Layout page is shown in the following figure.



Add a Layout Using the Layout Editor

Follow these steps to add a layout using the Layout Editor.

1. Under the **Create Layout** region, click one of the basic or shared templates to launch the Layout Editor. The shared templates are preformatted layouts with common report components already inserted.
2. Design the template.
3. When finished, click **Save**. In the Save Template dialog enter a name for this layout and select a locale. Click **Save**.
4. Click **Return** to return to the Report Editor.
5. Configure the settings for the layout.

Add a Layout by Uploading a Template File

Uploading a template file assumes that you've already created a template file.

To add a layout by uploading a template file:

1. Under the **Upload or Generate Layout** region, click the **Upload** icon.
2. In the Upload dialog, perform the following:
 - Enter a **Layout Name**.
 - Click **Browse** to locate the **Template File** in the local file system.
 - Select the **Template Type** from the list.
 - Select the **Template Locale** from the list.
 - Click **Upload**.

If you are connected to Publisher through the Template Builder, then you can upload the layout file directly from the client tool.

Add a Layout by Generating a Template File

Follow these steps to add a layout by generating a template file.


1. Under the Upload or Generate Layout region, click the Generate icon.
2. In the Autogenerate Layout dialog, perform the following:
 - Enter a **Template Name** for the layout.
 - Click **Generate**.

The autogenerate feature creates a simple table-based RTF layout that includes all the fields in the data model. The feature can only be used with data sets for which metadata is available. Therefore, this feature can't be used with data sets generated from stored XML files, HTTP feeds, web services, or migrated data templates.

Configure Layouts Using the List View

After creating or uploading the layouts for the report, you can configure settings for the layout from the **List View**.

The following figure shows the **List View**.



Apply a Style Template to the Layout

A style template contains style definitions that are applied to the paragraphs, headings, tables, and headers and footers of a report. A style template is optional and can only be applied to an RTF template file.

1. Click **Choose** to browse for and select the style template.
2. To apply the style template to an individual layout in the list, select the **Apply Style Template** box for that layout in the list of properties.

About the Layouts Toolbar

The table explains the actions that you can do with the layout toolbar buttons.

The Layout toolbar buttons are described in the following table.

| Toolbar Button | Description |
|-------------------|--|
| Create | Launches the add layout page to upload or create a new layout. |
| Edit | Launches the Layout Editor for the selected layout. This button is enabled for Publisher layouts (.xpt) only. |
| Properties | Launches the Properties page to enable the upload of localized templates and XLIFF files to associate with this layout. This button is enabled for RTF (.rtf) and Publisher layouts (.xpt) only. |
| Delete | Deletes the selected layout. |

Configure the Layout Settings Using the List View

Configure these layout settings using **List View**.

The settings are described in the following table:

| Setting | Description |
|-----------------------------|---|
| Name | Place the cursor in the text box to enter a new name for the layout. |
| Template File | Displays the name of the file that was saved to the report definition. Click the template file name to download it. |
| <i>Type</i> | Displays the template file type. |
| Output Formats | Select the output types to be enabled for this layout. By default, all valid output types for a layout are enabled. The layout type determines the output types available. See Select Output Formats for the complete list. |
| Default Format | Select the default output format for this layout when viewed or scheduled. |
| Default Layout | Select the layout that this report uses by default when viewed online or scheduled. Only one box in this column can be checked. |
| Apply Style Template | Select this box to apply the style template to this layout. Note that a style template can only be applied to RTF template files. See Apply a Style Template to the Layout . |
| Active | By default a layout is active. Clear this box when you want to keep the layout as part of the report definition, but no longer make it available. When a layout is inactive it doesn't display in the report viewer or the scheduler. |
| View Online | By default, a layout is available for report consumers who open the report in the Report Viewer. If this layout is for scheduled reports only, clear this box. |
| Locale (Read-only) | Displays the locale selected when the layout was uploaded. |

Select Output Formats

You can use a wide range of output formats.

Different layout types support different output types. The following table lists all possible output types.

| Output Format | Description |
|------------------|---|
| Data (CSV) | Enable this option to generate comma separated value output. |
| Data (XML) | Enable this option to generate XML output. |
| Excel (*.xlsx) | <p>Enable this option to generate the report in Excel.xlsx (Excel XML format). If your report consumers have Excel 2007 or later installed, this option provides the best preservation of layout and formatting.</p> <p>For this output format, Publisher doesn't apply any formatting for number and date. Publisher saves the formatting mask and the actual value (date or number) into the XLSX output file. The formatting is handled by Microsoft Excel. For example:</p> <ul style="list-style-type: none"> • If the Microsoft Windows Region and Language of the client computer is set to English (United States), then the numbers and dates are formatted in en-US locale in the Excel 2007 output file. • If the Microsoft Windows Region and Language of the client computer is set to French (France), then the numbers and dates in the same Excel 2007 output file are formatted in fr-FR locale. |
| FO Formatted XML | This option generates a XSL-FO (Extensible Stylesheet Language Formatting Objects) file. This output type is useful for debugging templates. |
| HTML | Enable HTML output for reports that require browser viewing. |

| Output Format | Description |
|---------------------|--|
| Interactive | This output is only available for layouts designed using Publisher's Layout Editor. Interactive output enables pop-up chart value displays, scrollable and filterable tables, and other interactive features for a report. |
| MHTML | Enable Mime Hyper Text Markup Language to allow the report consumer to save a Web page and its resources as a single MHTML file (.mht), in which all images and linked files are saved as a single entity. A report consumer would use this option to send or save HTML output and retain the embedded images and stylesheet formatting. |
| PDF | Portable Document Format is commonly required for reports that require printing or sharing. |
| PDF/A | Use for reports that require long-term preservation or archiving. PDF/A is a specialized subset of the PDF standard that prohibits elements that may interfere with the preservation of the file as a self-contained document. |
| PDF/X | Use for reports that require formatting for prepress graphics exchange. PDF/X is a specialized subset of the PDF standard that streamlines documents for high-quality print production output and restricts content that doesn't serve the print production, such as signatures, comments, and embedded multimedia. |
| PowerPoint (mhtml) | Enable this output type to generate a PowerPoint file compatible with Microsoft PowerPoint 2003. Note that Microsoft PowerPoint 2010 doesn't support this output type. Choose PowerPoint (*.pptx) instead. |
| PowerPoint (*.pptx) | Enable this output type to generate a Microsoft PowerPoint file in Microsoft Office Open XML format. This output type is supported for versions of Microsoft PowerPoint 2007 and later. |
| RTF | Rich Text Format. Enable this output for reports that must be opened for editing. |
| Text | This option generates text output for eText templates. Text output is available only for eText templates. |
| Word | Generates Microsoft Word .docx file. |
| Zipped PDFs | Publisher can generate a zip file containing the report PDF output and index files. This option is only available for layouts that have been designed to enable zipped PDF output. For information on designing a report to generate zipped PDF. |

The following table lists valid output formats for each layout type.

| Layout Type | Valid Output Types |
|--|--|
| Publisher template created using the layout editor (XPT) | Data (CSV), Data (XML), FO Formatted XML, HTML, Interactive, MHTML, PDF, PDF/A, PDF/X, PowerPoint (*.pptx), RTF, Word, Zipped PDFs Excel (html), Excel (mhtml), PowerPoint (mhtml) |
| RTF template (RTF) | Data (CSV), Data (XML), Excel (*.xlsx), FO Formatted XML, HTML, MHTML, PDF, PDF/A, PDF/X, PowerPoint (*.pptx), RTF, Word, Zipped PDFs Excel (html), Excel (mhtml), PowerPoint (mhtml) |
| PDF template (PDF) | Data (CSV), Data (XML), PDF, Zipped PDFs |
| Excel template (XLS) | Data (CSV), Data (XML), Excel (*.xls) |
| XSL Stylesheet (FO) (XSL) | Same outputs as RTF template |

| Layout Type | Valid Output Types |
|--------------------------------------|---|
| XSL Stylesheet (HTML XML/Text) (XSL) | Data (CSV), Data (XML), HTML, Text |
| eText template (RTF) | Data (CSV), Data (XML), Text |
| Analyzer template (XPA) | (Supported for backward compatibility only.) Analyzer templates can be uploaded from previous versions of Publisher. The Online Analyzer in current versions exports the online analysis to layout editor templates (.xpt). |

Data (CSV) and Data (XML) output formats are available for all layout types. However, when you select either of these formats, no layout formatting is applied and only data is included in the output.

Edit a Layout

Follow these steps to edit a Publisher layout and other template types.

To edit a Publisher layout (.xpt file type):

- Select the report from the list and click **Edit**.

To edit any other template type:

- Click the File name link to download the layout to a local computer for editing.

Configure Parameter Settings for the Report

Parameters are defined in the data model. The report editor enables you to configure the parameter settings specifically for each report that uses the data model.

To configure the parameters for this report:

1. On the Report Editor page, click **Parameters**. The Parameters dialog is displayed as shown in the following figure:

The screenshot shows a dialog box titled "Parameters" with a close button (X) and a help button (?). It contains the following sections:

Display Options

- Parameter Location: Vertical Region (dropdown)
- Parameter Label Location: Place label on top (dropdown)
- Show Apply Button: False (dropdown)

| Show | Name | Type | Multiple | Display Label | Default Value | Row Placement |
|-------------------------------------|-----------|-------------|----------|-------------------|---------------|---------------|
| <input checked="" type="checkbox"/> | P_YEAR | Radio Butto | False | Calendar Year | Default | 1 |
| <input checked="" type="checkbox"/> | P_COMPANY | Radio Butto | False | Company Name | Default | 1 |
| <input checked="" type="checkbox"/> | P_ORG | Radio Butto | False | Organization Name | Default | 1 |

At the bottom right, there are "OK" and "Cancel" buttons.

2. Customize the parameter settings for this report by making selections for the following display options:

Parameter Location - This property controls where the parameter region is displayed in the report viewer. The options are:

- Horizontal Region - displays the parameters horizontally across the top of the report viewer.
- Vertical Region - displays the parameters vertically along the left side of the report viewer.
- Full Page - displays the parameters on a separate page in the report viewer. After a user enters parameter values, the page is dismissed. To change parameter values, click the report viewer **Parameters** button to display the **Parameters** page again.
- Dialog - invokes a dialog box to display the parameters. After a user enters parameter values, the dialog is dismissed. To change parameter values, click the report viewer **Parameters** button to display the dialog again.

Parameter Label Location - This property controls where the parameter labels are displayed. The options are:

- Place label on side - places the parameter label to the left side of the entry box.
- Place label on top - places parameter label on top of the entry box.

Show Apply Button - This property controls the display of the **Apply** button in the report viewer.

When set to True, reports with parameter options display the **Apply** button in the report viewer. When a user changes the parameter values, he must click **Apply** to render the report with the new values.

When set to False, the report viewer doesn't display the **Apply** button. Instead, when a user enters a new parameter value, Publisher automatically renders the report after the new value is selected or entered without further action from the user.

This property is also set at the server level. To always use the server setting, choose the Default option.

When deciding whether to remove the **Apply** button, consider the ability of the underlying data sources to quickly return data. Lists of values that're based on static lists or very fast data sources are ideally suited to turning off the **Apply** button. If the underlying data sources for the lists of values queries are slow, or if there're many parameter values to set and refine before rendering the report, then retaining the **Apply** button is recommended.

Show - This property controls whether the parameter is displayed to the user. Disable the **Show** property if you don't want the user to see or change the parameter values that're passed to the data model.


Don't hide a parameter on which other parameters depend. If the value of a hidden parameter changes, then any parameters that dependent on that hidden parameter aren't updated. This lack of updating might cause report generation to fail with a message such as "Invalid Parameter Requested".

Type - This property is customizable for menu type parameters only. For menu type parameters, the following display options are available:

- **Check box** - If the parameter allows multiple selections, (Multiple = True) this option is available. The check box type displays all menu options in the parameter region of the report. Users can make multiple selections, as shown the following figure:



- **Radio button** - If the parameter allows only a single selection (Multiple = False), this option is available. The radio button type displays all menu options in the parameter region of the report. Users can make a single selection as shown in the following figure:



- The check box and radio button options are best suited for menus when the list of values is small. These options also display well when the **Parameter Location** is the vertical region.

Multiple - This property is display only; it indicates whether multiple values may be selected for a menu parameter.

Display Label - Use this property to edit the display labels shown for each parameter. The default values are defined in the data model.

Default Value - Use this property to configure the default value for the parameter specifically for this report. Choose *Default* to pass the default value defined in the data model.

Row Placement - Use this property to configure the number of rows for displaying the parameters and in which row to place each parameter. For example, if your report has six parameters, you can assign each parameter to a separate row, 1 - 6, with one being the top row; or, you can assign two parameters each to rows 1, 2, 3. By default, all parameters are assigned to row 1.

- When the **Parameter Location** property is set to Vertical Region, only one parameter displays per row. You can use the Row Placement property to order the rows vertically.

Configure Report Properties

In the report editor, click **Properties** and launch the Report Properties dialog to configure report properties.

The Report Properties dialog has the following option sets:

- **General** - Set general properties for the report.
- **Caching** - Specify caching options for this report.
- **Formatting** - Set the runtime configuration properties for the report.
- **Font Mapping** - Create font mappings for this report.
- **Currency Format** - Define currency formats for this report.

Set the General Properties

Set the properties on the General tab as follows:

Run Report Online

Disable this property if you don't want users to view this report in the online Report Viewer.

When disabled, users can Schedule the report only. For most reports you keep this enabled. Disable it for long-running, batch, or other reports for which online viewing isn't appropriate. When this property is enabled, you can also set the properties described in the following table.

| Property | Description | Default |
|-----------------------------------|--|-------------|
| Show controls | This property controls the display of the control region of the report. The Control region consists of the Template list, Output list, and Parameter lists. Disable this property if you don't want users to view and update these options. | Enabled |
| Allow Sharing Report Links | The Actions menu of the Report Viewer includes the option Share Report Link , which enables users to display the URL for the current report. Disable this property if you don't want users to see and copy the report link. | Enabled |
| Open Links in New Window | This property controls how links contained within a report are opened. By default links open in a new browser window. Disable this property to open links in the same browser window. | Enabled |
| Asynchronous Mode | Reports run in asynchronous mode use a unique thread to execute the report when run in the report viewer. This allows Publisher to cleanly terminate the thread if a user cancels the report execution. Note that there're performance implications when enabling this property. | Not Enabled |

| Property | Description | Default |
|-----------------|---|---------|
| Auto Run | When this property is enabled, the report automatically runs when the user selects the Open link for the report. When Auto Run is disabled, selecting the Open link for the report displays the online viewer but doesn't run the report. The user must select an output type from the View Report menu to run the report. | Enabled |

Advanced Options

You can set the advanced properties for a report.


The following table describes the advanced property options.

| Property | Description |
|---|---|
| Job Priority | Specifies the priority for the report. You can assign Critical, Normal, or Low priority for a report. By default, the priority of a report is Normal. Publisher sets the JMS Priority to sort the scheduled report jobs based on priority, and enables the high priority report jobs to run before the non-critical jobs. If all the reports have the same priority, Publisher processes the reports in First In First Out (FIFO) order. You can view the priority settings of jobs in the Report Job History page. |
| Enable Bursting | Select this option to enable bursting of the report output, and then select the appropriate bursting definition from the list. When a user schedules the report, the selected bursting definition will be enabled in the Scheduler. The bursting definition is a component of the data model. |
| Enable Chunking Chunk Size | Select this option to enable XML data chunking for a report job and specify the data size for each chunk. The layout processor outputs individual XML data chunks and merges them to generate a consolidated final report output. XML data chunking isn't available for online reports. XML data chunking in a report job supports RTF, XPT, and eText output formats, but you can't have multiple output formats. |
| Report is Controlled by External Application. Users cannot run or schedule report from catalog, can view history | Select this option when Publisher is integrated with another application that controls the generation of this report, and you do not want users to run and view this report directly from the catalog. Reports run by Publisher are stored in the Publisher history tables and users can view completed reports from the Report Job History page. |

Set the Caching Properties

Set these options for caching.

The following illustration shows the Caching tab.



The following table describes the properties on the Caching tab.

| Variable | Description | Default |
|-----------------------------------|---|-------------|
| Enable Data Caching | When this property is enabled, the data generated by the online submission of this report is stored in the cache. Subsequent requests to run this report with the same parameter selections display the report using the data from the cache. This setting enhances performance by using stored data to generate a report rather than regenerating the data from the source. The data remains in the cache according to the time limit that's specified in the Cache Duration property. You can control whether the cache for the report is shared by users by setting the User Level property. | Not Enabled |
| Caching Duration (Minutes) | Enter the time limit for a report data set or document to remain in cache. Once the time limit has expired, the next request for the same report generates a fresh data set. | 30 minutes |
| User Level | This property stores a separate cache for each user. The report data shown to each user comes only from the private cache. When enabled, this property ensures that each user can only see data that they're authorized to view. However, user-level cache has less efficient performance. If the report data isn't user sensitive, you can disable this property to enhance performance. | Enabled |
| Document Caching | Enable this property to cache the report document. With document cache enabled, when a user views the report online, the document (data plus layout) is placed in the cache. When any other user (unless User Level is enabled) uses the online viewer to view the exact same report (same layout, same output type, same parameter selections) the document is retrieved from the cache. The document remains in the cache according to the caching duration specified. Scheduled reports don't use document cache. | Enabled |

| Variable | Description | Default |
|-------------------------------------|--|-------------|
| User Can Refresh Report Data | When this property is enabled, the user can choose to refresh the data on demand. When the user clicks Refresh in the report viewer, Publisher generates a fresh data set for the report. | Not Enabled |

Set the Formatting Properties

The Formatting properties tab enables you to set runtime properties at the report level.

These same properties can also be set at the system level, from the Administration page. The Formatting properties tab displays both the system-level setting and the report-level setting for each property. If different values are set at each level, the report level takes precedence.

For a full description of each property, see [Set Report Processing and Output Document Properties](#).

Configure Font Mapping

You can map base fonts in RTF or PDF templates to target fonts to be used in the published document. Font mappings can be set at the report level or the system level. When you view the report properties Font Mapping tab, any system level settings are displayed. To change the settings for this report, edit the font mappings here.

1. Under RTF Templates or PDF Templates, select **Add Font Mapping**.
2. Enter the following on the Add Font Mapping page:
 - Base Font: Enter the font family to map to a new font. Example: Arial
 - Select the **Style**: Normal or Italic (Not applicable to PDF Template font mappings)
 - Select the **Weight**: Normal or Bold (Not applicable to PDF Template font mappings)
 - Select the **Target Font Type**: Type 1 or TrueType
 - Enter the **Target Font**.

If you selected TrueType, then you can enter a specific numbered font in the collection. Enter the **TrueType Collection (TTC) Number** of the desired font.

Configure Currency Formats

In the **Currency Format** tab, map a number format mask to a specific currency so that reports can display multiple currencies with their own corresponding formatting. Currency formatting is only supported for RTF and XSL-FO templates.

Currency formats can be set at the report level or the system level. The report properties display the system level settings in the **Currency Format** tab. You can edit the currency format and change the settings for the report.

To apply these currency formats in an RTF template, you must use the format-currency function.

1. Click the **Add** icon.
2. Enter the ISO currency code, for example: USD, JPY, EUR, GBP, INR.
3. Enter the format mask to apply for this currency.

The Format Mask must be in the Oracle number format. The Oracle number format uses the components "9", "0", "D", and "G" to compose the format, for example: 9G999D00

where


9 represents a displayed number only if present in data

G represents the group separator

D represents the decimal separator

0 represents an explicitly displayed number regardless of incoming data

The following figure shows sample currency formats:



Access Reports via a URL

You can call a report via a URL from another application.

Use the report URL format and specify the parameters for the report in the URL.

Report URL Format

You can call a Publisher report via a URL, for which you can build the URL.

The basic URL for a report is:

```
http://<server:port>/ui/xmlpserver/<ReportDirectory>/<ReportName>.xdo
```

or

```
http://<server:port>/xmlpserver/<ReportDirectory>/  
<ReportName>.xdo
```

where

`server:port` is the name of the server and port number where Publisher is running
`ui` is a static string for the user interface path

`xmlpserver` is a required static string (the name of the application)

`ReportDirectory` is the folder path to the report. When the report is under Shared Folders, do not include "Shared Folders" in the path. If the report is under My Folders, include the `~username` as the first node in the path. See the examples following.

`ReportName.xdo` is the name of the report with the `.xdo` extension. If the name contains spaces, replace the space with a "+" character.

Examples

The following examples render the complete report inside the report viewer with all the report controls.

The following URL launches the North America Sales report. The report resides in the catalog under Shared Folders/Samples/Sales. Note that Shared Folders isn't included in the path.

```
http://example.com:7001/xmlpserver/Samples/Sales/  
North+America+Sales.xdo
```

The following URL launches the North America Sales report that resides in the catalog under My Folders/Samples/Sales. Note that the user name in this case is `weblogic`, therefore the first node in the path is `~weblogic`.

```
http://example.com:7001/xmlpserver/~weblogic/Samples/Sales/  
North+America+Sales.xdo
```

Report URL Parameters

When you use a URL to call a report, you can specify parameters in the URL.

The default layout, default output format, and default parameters are used to render the report. You can add parameters to the URL to specify how the report renders.

When you construct the URL, note the following standard URL syntax:

- `?` denotes the first parameter
- `&` denotes each additional parameter

The following table describes the parameters you can add to the URL.

| Parameter | Definition | Example Usage |
|--|--|--|
| <code>_xpt</code> | <p>Specifies whether to render the report in the report viewer or export the document to a new window appropriate for the output type. For example, if the output type specified is html, the report document (only) will render in a browser window; if the output type is PDF you will be prompted to save or open the PDF document. When this parameter isn't specified, the report renders in the report viewer.</p> <p>Valid values are:</p> <ul style="list-style-type: none"> • 0 renders the report in the report viewer • 1 exports the document to appropriate application window | <code>_xpt=0</code> |
| <code>_xdo</code> | (Optional) Provides the path to the report. | <code>_xdo=%2FSamples%2FSalary+Report.xdo</code> |
| <code>_xt</code> | Specifies the layout to use. Enter the name of the layout as defined in the report definition. If an invalid name is entered, the default layout is used. | <code>_xt=Manager+Summary</code> |
| <code>_xf</code> | <p>Specifies the output format. If no value is specified, the default output format is used. If an invalid value is specified, or, if a value is specified that isn't enabled for the layout, the report doesn't render. Valid values are:</p> <ul style="list-style-type: none"> • <code>analyze</code> for Interactive output • <code>rtf</code> • <code>docx</code> • <code>pdf</code> • <code>html</code> • <code>pptx</code> for PowerPoint 2007 • <code>ppt</code> for PowerPoint • <code>xml</code> for data • <code>excel</code> for Excel • <code>excel2000</code> for Excel 2000 • <code>xslx</code> for Excel 2007 • <code>csv</code> | <code>_xf=pdf</code> |
| Report parameters as named in the data model | Specify name-value pairs for the parameters specific to the report. You must use the parameter name as defined in the data model. | <code>dept=10</code> |
| <code>_xmode</code> | <p>Specifies the report viewer mode. If not specified, defaults to view in the full report viewer. Valid values are:</p> <ul style="list-style-type: none"> • 0 to view in the full report viewer. • 1 to hide Publisher banner, hide parameters, can change layout, other actions: export only. • 2 to hide Publisher banner. (No Header) • 3 to hide Publisher banner and parameters. (No Parameters) • 4 to hide Publisher banner, parameters, other actions, and layouts. (Document Only) | <code>_xmode=1</code> |

Example:

```
http://example.com:7001/xmlpserver/Samples/Salary+Report.xdo?
_xpt=0&_xdo=%2FSamples%2FSalary%20Report.xdo&_xmode=4&dept=10&_x
t=Simple&_xf=html
```

This URL runs the "Salary Report" report located under Shared Folders/Samples. Note the following:

_xpt=0 renders the document in the report viewer

_xdo=%2FSamples%2FSalary%20Report.xdo defines the report path

_xmode=4 renders the document only


dept=10 sets the report-specific parameter "dept" to "10"

_xt=Simple uses the layout called "Simple"

_xf=html sets the output format to html

About the Layout Editor Interface

The illustrated figure shows the layout editor interface.



The **Layout Editor** interface comprises the following:

- The top of the **Layout Editor** contains two toolbars:
 - The **Static toolbar** is always available and contains common commands such as save and preview.
 - The **Tabbed toolbar** includes the **Insert** tab, the **Page Layout** tab, and a dynamic tab that shows the most commonly used actions and commands for the selected layout component. You can collapse this toolbar to make more room to view the design area. See [About the Tabbed Toolbar](#).
- The accordion pane on the left contains the following:
 - Use the **Data Source** pane to select the data fields to drag to the layout components.
 - Use the **Components** pane to select layout components and drag them to the design area. You can also use the **Insert** tab to insert components when this pane is collapsed.
 - Use the **Properties** pane to modify properties for the selected layout component.

You can expand and display each control by clicking the title of the control or the plus sign next to the title of the control. You can collapse the entire accordion pane to allow more room to view the layout.
- The lower right region is the design area for building the layout.


About the Data Source Pane

The **Data Source** pane displays the structure of the data model and the data elements that are available to insert into the layout.

To insert a data element, select and drag it from the **Data Source** pane to the component in the layout.

The data type for each field is represented by an appropriate icon: number, date, or text.

The following figure shows the data source pane. The icon beside each element indicates the data type.




The JOB_TITLE element is shown as text, the SALARY element is shown as a number, and the HIRE_DATE element is shown as a date data type.

Note that when you enter dates in the Layout Editor (such as a data comparison for a filter or for conditional formatting), use one of the following XSL date or time formats: YYYY-MM-DD or YYYY-MM-DDTHH:MM:SS.

About the Components Pane

The **Components** pane contains the layout components that you can insert into a report. These components include charts, pivot tables, and images. To insert a component, simply drag and drop it to the layout.

You can also use the **Insert** menu to add components to the layout.




About the Properties Pane

The **Properties** pane displays the properties for the selected component. The properties displayed are determined by the selected component. Some of the properties available in the **Properties** pane are also editable in the dynamic tab for the component.

Click a property value to edit it. The change is applied to the component when you move the cursor out of the field. Collapse or expand a property group by clicking the plus or minus signs beside the group name.

The properties available for each component are discussed in detail in the corresponding section for that component in this chapter. If a property field is blank, then the default is used.

The following figure shows a sample **Properties** pane for a table column header.



About the Tabbed Toolbar

The section defines the tabs and their functions in the Tabbed toolbar.

The Tabbed toolbar contains the following tabs:

- The **Insert** tab provides the components and page elements that can be placed on a layout. See [Insert Layout Components](#).
- The **Page Layout** tab provides common page-level tools and commands. See [Page Layout Tab](#).
- The component-specific tab provides the most commonly used commands and properties for the component that is selected in the layout. For example, when you select a chart, the **Chart** tab displays. See the section on a specific component for details on the commands.

To set or control more properties for the selected component, open the **Properties** pane in the accordion pane, as described in [About the Properties Pane](#).

Select and Delete Layout Objects


You can select layout objects to set the focus or remove the object entirely

Each of the component-specific tabs include the **Select** region.

- The **Select** tool enables you to control precisely which component on the layout has focus. This ability is particularly helpful when working with a complex layout where components overlap. For example, to select a table, it's sometimes difficult

to click the correct spot to select the table and not a column, or header cell. To avoid unnecessary clicking, use the Select tool to precisely select the Table component from the list.


The following illustration shows the **Select** tool.



- The **Delete** tool provides a similar function to the **Select** tool to enable you to precisely select the component to delete.

About the Insert Tab

Use the **Insert** tab to insert report components and page elements.



The **Components** group displays the report components that you can insert into the layout. To insert a component, select and drag the item to the desired location in the design area. For more information about each component, see its corresponding section in this chapter.

The **Page Elements** group contains page-level elements for the report. To insert a page break, the page number, or the total page number calculation, select and drag the component to the desired position in the layout. Note that **Page Elements** are intended for paginated output types, such as PDF and RTF. Using them in interactive or HTML output may have unexpected results.

12

Create Publisher Layout Templates

This topic describes creating layout templates using the layout editor.

Topics:

- [Overview of Publisher Layouts](#)
- [Launch the Layout Editor](#)
- [About the Layout Editor Interface](#)
- [Page Layout Tab](#)
- [Insert Layout Components](#)
- [Insert Layout Grids](#)
- [About Repeating Sections](#)
- [About Data Tables](#)
- [About Charts](#)
- [About Gauge Charts](#)
- [About Pivot Tables](#)
- [About Text Items](#)
- [About Images](#)
- [About Lists](#)
- [Set Predefined or Custom Formulas](#)
- [Save a Layout](#)


Overview of Publisher Layouts

Use the Publisher layout editor to create Publisher layout templates.

The Publisher layout template enables end users to:

- View Dynamic HTML output and perform lightweight interaction with their report data from within a browser
- Generate high fidelity, pixel-perfect reports to PDF, RTF, Excel, PowerPoint, and static HTML

The Publisher layout editor is a design tool that provides a WYSIWIG, drag and drop interface for creating pixel-perfect reports in PDF, RTF, Excel, Word, PowerPoint, and HTML. It also provides dynamic HTML output that supports lightweight interaction through a browser. This interactive output is featured in the following illustration.



Notice the following features:

- Pop-up chart details - Hover cursor over chart items to display details of data.
- Group filtering - Grouped regions can be filtered by the grouping element.
- Scrollable tables - Table data can be scrolled while maintaining display of the headers and totals.
- Table column sorting - Table data can be sorted by different columns from within the viewer.
- Table column filtering - Table data can be filtered by values in different columns from within the viewer.
- Automatic table totaling - Table data totals are automatically added to the layout.
- Propagated filtering - Filter other components by clicking on chart areas or by clicking on pivot table header, column, or elements.
- Collapse and expand areas of the document.

When to Use a Publisher Layout

Publisher layouts are best suited for reports of simple to medium complexity that don't require custom coding.

Because the dynamic HTML view is only available for Publisher layouts, always use a Publisher layout when report consumers need an interactive report (change sorting, apply filters, and so on).

Prerequisites, Recommendations, and Limitations

These tips will help you use Publisher more effectively.

- To use the layout editor, your account must be granted a role that includes the appropriate permissions for accessing report layout tools.
- You must attach sample data to the data model before you create a new layout.
- For optimum viewing, set your display resolution to 1024 x 768 or higher.
- Publisher can handle a large amount of data for interactive sorting and filtering and still provide fast response. It's best to summarize data in the Data Model to the level of interest for the consumer for optimal performance. Publisher layouts can generate static output such as PDF or RTF documents up to 50% faster than comparable RTF layouts depending on the data.
- The layout editor doesn't support namespaces or attributes in the XML data.

Launch the Layout Editor

The layout editor is available in several places.

Launch the layout editor in one of the following ways:

- [Create a New Report](#)
- [Edit a Report](#)
- [View a Report](#)

Create a New Report

You can use the Layout Editor to change the appearance of a report.

To launch the Layout Editor when creating a new report:

1. Select the data model for the new report.
The Report Editor displays the Add Layout page.
2. From the Create Layout region, click a predefined template to launch the Layout Editor.

Edit a Report

You can alter the layout of a report using the Layout Editor.

To launch the Layout Editor when editing a report:

1. In the Report Editor:
From the **Thumbnail** view, click **Add New Layout**.
or
From the **List** view, click the **Create** button on the layouts table toolbar.
2. From the **Create Layout** region, click a predefined template to use to launch the Layout Editor.

View a Report

You can change the layout of a report while viewing it.

To launch the Layout Editor when viewing a report:


- Click **Actions** and then click **Edit Layout**.

The layout must have been created in the layout editor.

Select a Predefined Layout

When you create a new layout, you are given the option of selecting a predefined layout to help you get started.

The following illustration shows the predefined layouts offered by the Basic and Shared Templates.



The Basic and Shared Templates offer common layout structures with specific components already added. Choosing one of the predefined layouts is optional, but can facilitate layout design. If your enterprise utilizes a common design that isn't available here, then you can add predefined layouts for your own use, or your Administrator can add more for all users.

Add Shared Templates for All Users

Follow the steps to add redefined layout files to the shared directory for all users to access.

1. Log in with Administrator privileges and navigate to the **Catalog**.
2. In the **Shared Folders** directory, open the **Components** folder.

3. Locate the **Boilerplates** report and click **Edit**.
4. Click **Add New Layout**.
5. Design or upload the layout.

To design the layout: Click an existing boilerplate (or blank) to launch the layout editor. Insert the components to the layout. When finished, click **Save** and give the boilerplate a name. This layout is now displayed to all users in the **Shared Templates** region.

To upload a layout: Click **Upload** to upload a predefined Publisher Template (.xpt file).

6. Save the report.

Any Publisher Templates (.xpt) added to this report are displayed to all users as a Shared Template.

Add Personal Predefined Layouts

Adding personal predefined layouts are available to your account user only. You can design the layout by launching the layout editor or you can upload a predefined template.

1. Navigate to My Folders.
2. Create a new report called *Boilerplate*. This report doesn't have a data model.
3. Click **Add New Layout**.
4. Design or upload the layout.

To design the layout: Click an existing boilerplate (or blank) to launch the layout editor. Insert the components to the layout. When finished, click **Save** and give the boilerplate a name.


To upload a layout: Click **Upload** to upload a predefined Publisher Template (.xpt file).

These layouts are presented in the **My Templates** region when you create a new layout.

Page Layout Tab

The Page Layout tab contains commands to set up the layout.

The figure below shows the Page Layout tab.



Paper Options

Paper options include Orientation and Paper Size.

| Option | Description |
|-------------|---|
| Orientation | Choose Portrait or Landscape . |
| Paper Size | Select from the following paper size options: Letter, Legal, A4, A3, Executive, B5, Com-10, Monarch DL, or C5. The paper size determines the dimensions of the layout area. |

Header/Footer Options

This table describes the header and footer options.

| Option | Description |
|---------------|--|
| Page Header | Click to insert a page header in the layout. By default, the page header appears on every page of a printed report, but can be configured to skip the first page. To remove the page header, click Page Header again. |
| Page Footer | Click to insert a page footer in the layout. By default, the page footer appears on every page of a printed report, but can be configured to skip the last page. To remove the page footer, click Page Footer again. |
| Report Header | Click to insert a report header to the layout. The report header appears only once at the beginning of the report. To remove the report header, click Report Header again. |
| Report Footer | Click to insert a report footer to the layout. The report footer appears only once at the end of the report. To remove the report footer, click Report Footer again. |

Set Properties for Headers and Footers

The Properties pane enables you to set the following properties for headers and footers.

To access the Properties pane, select the header or footer in the design region, then click **Properties** from the accordion pane on the left of the page.


For all report and page headers and footers:

- **Height** - Set the height of the header region in pixels, points, centimeters, or inches

For headers:

- **Show in the first page** - Select **True** to show the header in the first page. Select **False** to suppress the header from the first page.

This figure shows the Properties for a report header.



For footers:

- **Show in the last page** - Select **True** to show the footer in the last page. Select **False** to suppress the footer from the last page.

View Options

The following table describes view options.

| Option | Description |
|--------------|--|
| Grid | Click to insert gridlines in the layout design area. The grid unit size depends on the Display Unit selected. To remove the gridlines, click Grid again. |
| Ruler | Click to insert a display ruler across the top of the layout design area. The ruler units depend on the Display Unit . To remove the ruler, click Ruler again. |

Display Unit

Select the unit of measure to display. This unit is used for the ruler and grid view options, as well as for any other function that displays a measurement, such as setting border widths and sizing grid cells. Options are: inch, px (pixel), cm (centimeter), and point (pt).

Configure Events

The **Configure Events** option enables you to configure how components of the layout respond to events triggered by a user when viewing the report in interactive mode.


The two types of events are:

- **Filter** - If you click an element in a list, chart, or pivot table, that element is used to dynamically filter other components defined as targets in the report. The component being clicked doesn't change.
- **Show Selection Only** - If you click an element of a list, chart, or pivot table, the chart or pivot table (being clicked) shows the results for the selected element only. This action doesn't affect other components of the report.

Example of Filter Event Configuration

The illustration here shows an example of filter event configuration. The layout contains two charts and a table. The first chart shows salary totals by department in a pie chart. The second chart shows salary totals by manager in a bar chart. The table displays a list of employees and their salaries.

In this report, if a user clicks on a value in the Salary by Department chart, you want the Salary by Manager chart and the Employees table to automatically filter to show only the managers and employees in the selected department.




Configure Automatic Filtering

Follow these steps to know how to configure automatic filtering.

1. On the **Page Layout** tab, click **Event Configuration** to display the Configure Events dialog.

The following figure shows the Configure Events dialog.



2. In the **Components** column, click the layout component (lists, charts, and pivot tables are available to configure).
3. Select **Filter** to enable automatic filtering in other report components.
4. Select the report components in the **Targets** column to enable the automatic filtering based on interactive events in the selected component. To disable the automatic filtering for a target component, clear the box.


The preceding figure shows that the **Filter** event is enabled for Chart 1 in the layout. Chart 2 and Table 3 are selected as targets to enable automatic filtering when a selection event occurs in Chart 1.

The **Show Selection Only** option isn't enabled for Chart 1. That means that Chart 1 continues to display all values when one of its elements is selected.


Example: Show Selection Only

The Show Selection Only event displays only the value of the selected element within the chart or pivot table (being acted on).

In the example shown in the following figure, Chart 2 is configured with **Show Selection Only** enabled and **Filter** enabled with Table 3 as the Target.



This configuration results in the output shown in the following figure. When the user clicks on Chart 2, only the selected value is shown in Chart 2. Because the Filter event is enabled for Table 3, the selection is applied as a filter to Table 3.




Set Page Margins


You can set page margins for reports.

To set the page margins for the report:

1. Click anywhere in the design area outside of an inserted component.
2. Click the **Properties** pane in the lower left of the Layout Editor. The following illustration shows the Properties for the page.



3. Click the value shown for **Margin** to launch the Margin dialog. The following illustration shows the Margin dialog.



4. Select the desired size for the margin. Enter the value for the Top, Left, Right, and Bottom margins.

To automatically set the same value for all sides, select the box: **Use same value for all sides**. This action disables all but the Top margin entry. Enter the value in the Top to apply to all sides.


Set Maximum Connections for an Interactive Report

You can limit the connections from the browser to the server for the interactive viewer.


More connections are faster but increase server load. The default is six connections. Reduce the number to reduce the load on the server for large reports.

To set the maximum connections for this layout:

1. Click anywhere in the design area outside of an inserted component.
2. Click the Properties pane in the lower left of the Layout Editor. The following illustration shows the Properties for the page.



- Click the value shown for **Max. Connections** and select the desired value from the list, as shown in the following illustration.



Insert Layout Components

The layout editor supports components that are typically used in reports and other business documents.

The following components are described in these sections:

- [Insert Layout Grids](#)
- [About Repeating Sections](#)
- [About Data Tables](#)
- [About Charts](#)
- [About Gauge Charts](#)
- [About Pivot Tables](#)
- [About Text Items](#)
- [About Images](#)
- [About Lists](#)

Insert Layout Grids


The layout grid provides a way to divide a layout into sections.

It functions similarly to a table in HTML or Word documents to create forms or to provide sophisticated layouts. Use a layout grid to control the exact placement of all other components in the layout.


To insert a layout grid:

- Select and drag the **Layout Grid** component to the design area.

The following illustration shows the Create a Layout Grid dialog.



In the dialog, enter the number of rows and columns for the grid and click **OK** to insert the grid to the design area, as shown in the following illustration.



Note the following about a layout grid:

- The grid is created with equidistant columns, and the row size defaults to a minimum of one row of text.

- Although Font properties are not enabled for a layout grid cell (set font properties using the individual component properties), the background color and border properties are enabled.
- When you insert a component to a grid cell, it automatically resizes to accommodate the component.
- Adjust the column width and height by either positioning the mouse pointer over the border and dragging the blue bar, or by changing the grid column properties in the Properties pane.
- The grid supports merging of cells.
- You can insert a grid inside a grid.
- Similar to Microsoft Word, the grid uses a flow layout that is very convenient for designing business documents. Components that do not occupy a full paragraph or block are positioned top-down and left to right.

Add a Border or Background Color

By default, the gridlines are displayed in the design area only and are not shown during runtime. If you want to display the gridlines in the finished report, then select the grid cell and click the **Set Border** command button to launch the Border dialog.

- To add a background color to a cell, click the **Background Color** command button to launch the Color Picker.

About the Insert Options

When you insert a layout grid, you can add additional rows or columns.

Select the layout grid cell that is the focal point, then click the appropriate command button:

- Add a Row above
- Add a Column to the right
- Add a Row below
- Add a Column to the left

About the Join and Unjoin Options

You can join cells or remove joins on cells.


To join cells or remove joins on cells:

1. To join cells:
 - a. Select multiple adjacent cells by holding down the `Ctrl` key and clicking each grid cell.
 - b. Click the **Join** command button.
2. To remove joins on cells, select the joined cell, and click the **Unjoin** button.

Add Expand and Collapse Option

When viewing a report in interactive mode, you can expand and collapse a layout grid to toggle the display of the grid's contents. Expand and Collapse are supported at the grid level, (not the cell-level) therefore ensure to insert grids appropriately. For example, if the report contains a chart in the top portion of the layout and a table in the bottom and you want to collapse the chart display, you must insert one layout grid to contain the chart and a second layout grid beneath the first to contain the table. Do not insert one grid with two rows.

1. Select the layout grid.
2. Open the **Properties** pane.
3. Set the **Interactive: Expand/Collapse** property to True. The following figure shows this option on the **Properties** pane.



About Repeating Sections

Repeating sections repeat the components within the section of the layout based on the occurrence of an element in the data. Repeating sections are used to create classic banded reports, as well as repeating pages or sections for different data elements such as Group Above/Outline.

1. Drag and drop the repeating section component to the layout.
2. In the Repeating Section dialog, select one of the following:
 - **Element** - Specify the element for which the section repeats. For example, if the dataset contains sales information for several countries. If you select COUNTRY as the repeat-by element, then the section of the layout repeats for each unique country occurring in the dataset.
 - **Group Detail** - If you have nested sections, then select this option. To continue the previous example, assuming there're unique data rows for each city and grouping by country, then this option creates a section that repeats for each city.

The following figure shows a layout with a repeating section defined for the element **Department**. Within the repeating section are a chart that shows salaries by manager

and a table that shows all employee salaries. So for each occurrence of department in the dataset, the chart and table are repeated.

| Salary Details | | | |
|----------------------------------|-----------------|--------------------------------|---------------|
| Start Grouping - Department Name | | | |
| Manager | Full Name | Title | Annual Salary |
| Kevin Mourgos | Donald OConnell | Shipping Clerk | \$31,200 |
| | Douglas Grant | Shipping Clerk | \$31,200 |
| | Trenna Rajs | Stock Clerk | \$42,000 |
| | Curtis Davies | Stock Clerk | \$37,200 |
| | Randall Matos | Stock Clerk | \$31,200 |
| | Peter Vargas | Stock Clerk | \$30,000 |
| | Alana Walsh | Shipping Clerk | \$37,200 |
| | Kevin Feeney | Shipping Clerk | \$36,000 |
| Neena Kochhar | Jennifer Whalen | Administration Assistant | \$52,800 |
| | Susan Mavris | Human Resources Representative | \$78,000 |
| | | | \$7,924,800 |
| End Grouping - Department Name | | | |

Set Page Break Options for a Repeating Section

By default, for paginated output types, the page breaks automatically according to the amount of content that fits on a page.


You typically have the report break after each occurrence of the repeated content.

Using the preceding example, in the PDF output you typically want to break after each department.

To create a break in the report after each occurrence of the repeating section:

1. Select the repeating section component.
2. Open the Properties pane.
3. Set the **Page Break** property to **Page**.


The following illustration shows the Properties for a repeating section.




How Repeating Sections Display in Interactive Mode

In interactive mode, the values for the repeat by element are displayed as a list of values. This enables the report consumer to dynamically select and view the results.

The following figure shows the repeat by element Department displayed in a list of values:



By contrast, the below figure shows the same layout displayed in PDF. In this example the page break option is set so that each new department begins the repeating section on a new page.



Show All Values in a Repeating Section

You can view all the values in a repeating section.


In interactive mode, the values for the repeat by element are displayed as a list of values. By default, this list includes only the values present for the element in the data. Therefore, a report consumer can view results for only one item at a time.

To enable a report consumer to view the results in the repeating section for all values of the element, the Repeating Section component provides the property: Show All. When this property is set to true, the value "All" is added to the list to enable the display of results for all values.


To enable Show All:

1. Select the repeating section component.
2. Open the **Properties** pane.
3. Set the **Show All** property to **True**.

The following illustration shows the **Show All** setting in the **Properties** pane.



When you view the report, the option All is added to the menu of values, as shown in the following illustration.



About Data Tables

The data table is a standard table that is shown in many layouts. It contains a header, data columns, and a total row. The table supports "group left" functionality (outlines) that merges fields with the same values as well as subtotals, grand totals, custom calculations, and running totals.

Once inserted, you can edit the table properties using the dynamic tabs or the **Properties** pane. The following dynamic tabs are available for the table components:

- Table
- Table Column Header
- Column
- Total Cell

This section contains the following topics about working with tables:

- [Insert a Data Table](#)
- [Set Alternating Row Colors](#)
- [About the Table Tab](#)
- [About the Table Column Header Tab](#)
- [About the Column Tab](#)
- [About the Total Cell Tab](#)
- [Insert Dynamic Hyperlinks](#)


Insert a Data Table

Follow these steps to insert a data table and to add data columns to the table.

To insert a data table:

1. From the **Insert** tab, select and drag the **Data Table** component to the design area.

The following figure shows an example of an inserted, empty data table. Notice that the **Table** tab is now displayed.




- To add data columns to the table, select an element from the Data Source pane and drag it to the table in the layout.

Note:


You cannot include elements from multiple data models in report components unless the data models are linked.

The following figure shows the columns being added to the table. Notice that when you drop a column on the table the sample data is immediately displayed.



- Continue to drag the elements from the Data Source pane to form the columns of the table. If you must reposition a column that you've already added, then select it and drag it to the correct position.

The following figure shows a completed data table:



Notice the following default behavior:

- A total row is automatically inserted. By default it calculates the sum of the items in the column. You can remove this row or edit the display and calculation applied.
- Default date formatting is applied.
- Default number formatting and alignment is applied.

Set Alternating Row Colors


Some data tables are easier to read when the rows display alternating colors.

An example of alternating colors is shown in the following illustration.

| Last Name | Title | Manager | Department | Monthly_Salary | Annual_Salary |
|-----------|-------------------------------|------------------|------------|----------------|---------------|
| Kochhar | Administration Vice President | Steven King | Executive | 17000 | 204,000.00 |
| De Haan | Administration Vice President | Steven King | Executive | 17000 | 204,000.00 |
| Hunold | Programmer | Lex De Haan | IT | 9000 | 108,000.00 |
| Ernst | Programmer | Alexander Hunold | IT | 6000 | 72,000.00 |
| Austin | Programmer | Alexander Hunold | IT | 4800 | 57,600.00 |
| Pataballa | Programmer | Alexander Hunold | IT | 4800 | 57,600.00 |
| Lorentz | Programmer | Alexander Hunold | IT | 4200 | 50,400.00 |
| Greenberg | Finance Manager | Neena Kochhar | Finance | 12000 | 144,000.00 |
| Faviet | Accountant | Nancy Greenberg | Finance | 9000 | 108,000.00 |
| Chen | Accountant | Nancy Greenberg | Finance | 8200 | 98,400.00 |
| Sciarra | Accountant | Nancy Greenberg | Finance | 7700 | 92,400.00 |

To set an alternating row color:

1. Select the table.
2. Open the **Properties** pane.
3. Click the value shown for **Alternate Row Color** to launch the color picker. The following illustration shows the **Alternate Row Color** option.



4. Choose a color and click **OK**.


About the Table Tab

The **Table** tab defines the functions that you can perform to display a table in a customized manner.

The **Table** tab enables you to perform the following:

- Set the number of rows displayed
- Define filters for the data displayed in the table
- Define conditions and formats to apply to rows that meet the conditions
- Show or hide the total row for the table

The following figure shows the **Table** tab.



Set the Rows to Display Option

The **Rows to Display** property controls the number of rows of data displayed

The property is set as follows:

- When designing the layout, this property sets the number of rows that are displayed for the table within the layout editor.
- When viewing this layout in the report viewer in interactive mode, this property sets the size of the scrollable region for the table.

The default is 10 rows of data. You can select 10, 20, 30, 40, or All rows of data to be displayed. To set a custom value, open the **Properties** pane and enter the custom value for the **Rows to Display** property.

**Note:**

Displaying more rows of data can impact the performance of the Layout Editor.

About Filters

A filter refines the displayed items by a condition. This is a powerful feature that enables you to display only desired elements in the table in an interactive output without having to perform additional coding.

For example, you could add a filter to meet some of the following report conditions:

- Display only the top 10 salaries
- Display only the bottom 25 store sales
- Display only employees in the IT department
- Display only sales that are between \$10,000 and \$20,000 and in the Southern region

You can add multiple filters and manage the order in which they're applied to the table data.

Set Filters for a Table

You can use a filter to narrow table results.

To set a filter:


1. Click the **Filter** toolbar button.
2. Select a **Data Field** to filter by specific data elements. All elements are available regardless of whether they're included as table columns.
3. Select an **Operator** to filter by these operators: is equal to, is not equal to, is less than, is greater than, is less than or equal to, is greater than or equal to, is between, is in top, is in bottom.
4. Add a **Value** appropriate for the operator selected. The value can be either a text entry, or an element from the data.

Manage Filters

After you've added filters, use the Manage Filters feature to edit, delete, or change the order that the filters are applied.

To manage filters:

1. Click the **Manage Filters** toolbar button to launch the Manage Filters dialog, as shown in the following illustration.



2. Hover the cursor over the filter to display the actions toolbar. Use the toolbar buttons to edit the filter, move the filter up or down in the order of application, delete, or add another filter.

About Conditional Formats

A conditional format changes the formatting of an element in the table based on a condition.

This feature is extremely useful for highlighting target ranges of values in the table. For example, you could create a set of conditional formats for the table that display rows in different colors depending on threshold values.

Apply Conditional Formats to a Table

This table describes the different fields in the Highlight dialog.

To apply a conditional format:

1. Click the **Highlight** button. This launches the Highlight dialog, as shown in the following figure.

The screenshot shows a 'Highlight' dialog box with the following settings:

- Data Field:** Annual Salary
- Operator:** is greater than
- Value:** 100000 (selected), Name
- Font Family:** Tahoma
- Font Style:** Bold (B), Italic (I), Underline (U)
- Size:** 10pt
- Color:** Red
- Background Color:** White
- Text Indent:** 0 px
- Preview:** Value 123 (highlighted in red)

2. Select a **Data Field** to create a condition for a data field. All elements are available regardless of whether they're included as table columns. For example, you may want to highlight in red all employees with salaries greater than \$10,000, but not actually include the salary element in the table.
3. Select an **Operator** to create a conditional format by these operators: is equal to, is not equal to, is less than, is greater than, is less than or equal to, is greater than or equal to, is between, is in top, is in bottom.
4. Add a **Value** appropriate for the operator selected. The value can be either a text entry, or an element from the data.

 **Note:**

If entering a date value, use one of the following XSL date or time formats: YYYY-MM-DD or YYYY-MM-DDTHH:MM:SS.

5. Select a **Font Family** to apply to the row of data that meets the condition. You can also apply bold, italic, or underline emphasis.
6. Select the **Size** of the font to apply to the row of data that meets the condition.
7. Click **Color** to open the **Color Picker**. Choose one of the predefined colors or click **Custom Color** to define a color to apply to the font.

- Click **Background Color** to open the **Color Picker**. Choose one of the predefined colors or click **Custom Color** to define the background color to apply to the row.
The following figure shows the table in the layout with the condition applied.


| Name | Job Title | Manager | Annual Salary |
|-------------------|---------------------------------|-------------------|---------------|
| Donald O'Connell | Shipping Clerk | Kevin Mourgos | 31200 |
| Douglas Grant | Shipping Clerk | Kevin Mourgos | 31200 |
| Jennifer Whalen | Administration Assistant | Neena Kochhar | 52800 |
| Michael Hartstein | Marketing Manager | Steven King | 156000 |
| Pat Fay | Marketing Representative | Michael Hartstein | 72000 |
| Susan Mavris | Human Resources Representative | Neena Kochhar | 78000 |
| Hermann Baer | Public Relations Representative | Neena Kochhar | 120000 |
| Shelley Higgins | Accounting Manager | Neena Kochhar | 144000 |
| William Gietz | Public Accountant | Shelley Higgins | 99600 |
| Neena Kochhar | Administration Vice President | Steven King | 204000 |
| | | | 7924800 |

Manage Formats

After you've added conditional formats, use the **Manage Formats** command to edit or delete a format.

To manage formats:

- Click the **Manage Formats** button to launch the Manage Conditional Formats dialog, as shown in the following illustration.




2. Hover the cursor over an item to display the actions toolbar. Use the toolbar buttons to edit the format, move the format up or down in the order of application, delete, or add another format. The order of the conditions is important because only the first condition that is met is applied.

Control the Display of the Total Row

By default, the layout editor inserts a total row in a table that sums numeric columns. To remove the total row, click the **Show** menu and select the table view without the highlighted total row.

The following figure shows the **Show** menu options:




The total row can be further customized using the **Total Cell** tab and the **Properties** pane.

About the Table Column Header Tab

The **Table Column Header** tab defines the functions that you can perform.

The following figure shows the **Table Column Header** tab.



The **Table Column Header** tab enables you to perform the following:

- Edit the font properties of the table header column

- Edit the cell properties of the table header including border weight, style, and color and background fill color
- Set the vertical and horizontal alignment of the table header
- Apply grouping

About Grouping

"Grouping" groups together elements in the data of the same value. In a table, applying grouping can make the table easier to read.

The Grouping option enables you to choose between "Group Left" or "Group Above". Group left maintains the "group by" element within the table. The following figure shows a table that has been grouped by Manager using **Group Left**.

| Manager | Name | Job Title | Annual Salary |
|---------------|-----------------|--------------------------------|---------------|
| Kevin Mourgos | Donald OConnell | Shipping Clerk | 31200 |
| | Douglas Grant | Shipping Clerk | 31200 |
| | Trenna Rajs | Stock Clerk | 42000 |
| | Curtis Davies | Stock Clerk | 37200 |
| | Randall Matos | Stock Clerk | 31200 |
| | Peter Vargas | Stock Clerk | 30000 |
| | Alana Walsh | Shipping Clerk | 37200 |
| | Kevin Feeney | Shipping Clerk | 36000 |
| Neena Kochhar | Jennifer Whalen | Administration Assistant | 52800 |
| | Susan Mavris | Human Resources Representative | 78000 |
| | | | 7924800 |

Group above inserts a Repeating Section component, and extracts the grouping element from the table. The grouping element is instead displayed above the table and a separate table is displayed for each occurrence of the grouping element. The following figure shows a table that has been grouped by Manager using **Group Above**.

Manager Zlotkey

| Employee | Title | Hire Date | SALARY |
|------------|----------------------|--------------|-----------|
| Abel | Sales Representative | May 10, 1996 | 11,000.00 |
| Hutton | Sales Representative | Mar 18, 1997 | 8,800.00 |
| Johnson | Sales Representative | Jan 03, 2000 | 6,200.00 |
| Livingston | Sales Representative | Apr 22, 1998 | 8,400.00 |
| Taylor | Sales Representative | Mar 23, 1998 | 8,600.00 |
| | | Grand Total | 43,000.00 |

Manager Weiss

| Employee | Title | Hire Date | SALARY |
|-------------|----------------|--------------|-----------|
| Fleur | Shipping Clerk | Feb 22, 1998 | 3,100.00 |
| Geoni | Shipping Clerk | Feb 02, 2000 | 2,800.00 |
| Landry | Stock Clerk | Jan 13, 1999 | 2,400.00 |
| Markle | Stock Clerk | Mar 07, 2000 | 2,200.00 |
| Mikkilineni | Stock Clerk | Sep 27, 1998 | 2,700.00 |
| Nayer | Stock Clerk | Jul 15, 1997 | 3,200.00 |
| | | Grand Total | 22,100.00 |

Manager Vollman

| Employee | Title | Hire Date | SALARY |
|----------|----------------|--------------|----------|
| Bell | Shipping Clerk | Feb 03, 1996 | 4,000.00 |
| Everett | Shipping Clerk | Mar 02, 1997 | 3,900.00 |

Example: Group Left

The illustration here shows an example where the table data has been grouped by the elements of the first two columns, Manager and Title.

Notice that there's only one entry per manager name and one entry for each job title under that manager name. This organizes the data rows more cleanly in the table.

| Manager | Job Title | Name | Annual Salary |
|---------------|--------------------------------|-----------------|---------------|
| Kevin Mourgos | Shipping Clerk | Donald OConnell | 31200 |
| | | Douglas Grant | 31200 |
| | | Alana Walsh | 37200 |
| | | Kevin Feeney | 36000 |
| | Stock Clerk | Trenna Rajs | 42000 |
| | | Curtis Davies | 37200 |
| | | Randall Matos | 31200 |
| | | Peter Vargas | 30000 |
| Neena Kochhar | Administration Assistant | Jennifer Whalen | 52800 |
| | Human Resources Representative | Susan Mavris | 78000 |
| | | | 7924800 |

Apply Subtotals

To further enhance a table, you can add a subtotal row to display for each grouped occurrence of the element.

Example: Group Above

The illustration here shows an example where the table data has been grouped by Manager.

Notice that in the design pane, the Data Table component has been replaced with a Repeating Element component that contains the data table. The Manager element is inserted above the table with a label.

Start Grouping - Manager

| Job Title | Name | Annual Salary |
|----------------|------------------|---------------|
| Shipping Clerk | Donald OConnell | 31200 |
| | Douglas Grant | 31200 |
| | Winston Taylor | 38400 |
| | Jean Fleaur | 37200 |
| | Martha Sullivan | 30000 |
| | Girard Geoni | 33600 |
| | Nandita Sarchand | 50400 |
| | Alexis Bull | 49200 |
| | Julia Dellinger | 40800 |
| | Anthony Cabrio | 36000 |
| | | |

End Grouping - Manager

The label is a text item. Edit the text by double-clicking the item to select it, then single-clicking to edit.

When you run the report, a separate table is created for each occurrence of the grouping element. In Interactive output mode, the grouping element displayed at the top of the table is displayed as a filter. Select the value that you want to view from the list, as shown in the below figure:

Salary Report


| Manager | Adam Fripp | Manager | Adam Fripp |
|----------------|------------------|---------|------------|
| Job Title | Name | | |
| Stock Clerk | Laura Bissot | | |
| | Mozhe Atkinson | | |
| | James Marlow | | |
| | TJ Olson | | |
| Shipping Clerk | Nandita Sarchand | | |
| | Alexis Bull | | |
| | Julia Dellinger | | |
| | Anthony Cabrio | | |

Percentage Salary by Department

Manager Adam Fripp ▼
 Adam Fripp
 Alberto Errazuriz
 Alexander Hunold
 Den Raphaely
 Eleni Zlotkey
 Gerald Cambraut
 John Russell
 Karen Partners
 Kevin Mourgos
 Lex De Haan
 Matthew Weiss
 Michael Hartstein
 Nancy Greenberg
 Neena Kochhar
 Payam Kaufling
 Shanta Vollman
 Shelley Higgins
 Steven King

About the Column Tab

The **Column** tab is enabled when you select a specific column in a table. You can edit font and cell properties and apply them.



The **Column** tab allows you to perform the following actions:

- Edit the font properties of the column including style, size, and color
- Edit the cell properties of the column including border weight, style, and color and background fill color
- Set the vertical and horizontal alignment of the column contents
- Apply formatting to the column data (options depend on the data type)

- Apply grouping
- Apply a running total (or other formula) to the data
- Apply sorting and sort precedence
- Apply conditional formatting to the column

About the Data Formatting Options for Columns

The options available from the **Data Formatting** region of the tab depend on the data type of the column selected. The tab provides common options to choose from.


If an option isn't listed, you can enter a custom Oracle or Microsoft formatting mask in the **Properties** pane. You can also set a formatting mask dynamically by including the mask as an element in your data. These features are described in the following sections:

- [Apply Formatting to Numeric Data Columns](#)
- [Apply Formatting to Date Type Data Columns](#)
- [Custom and Dynamic Formatting Masks](#)

Apply Formatting to Numeric Data Columns

Follow these formatting options if the column contains numeric data.

- **Format** - Select one of the common number formats from the list. The format is applied immediately to the table column. The formats are categorized by Number, Percent, and Currency, as shown in the following figure:




- **Decimal position** - Click the **Move Left** or **Move Right** to increase or decrease the decimal positions displayed.
- **Show/Hide Grouping Separator** - Click this button to hide the grouping separator (for example, 1,234.00 displays as 1234.00). To show the grouping separator, click the button again.

Apply Formatting to Date Type Data Columns

Use these formatting options if the column contains dates.

- **Format** - Select one of the common date formats from the list. The format is applied immediately to the table column. The formats are categorized by Date and Time, as shown in the following figure:



Custom and Dynamic Formatting Masks


You can apply any Microsoft or Oracle (recommended) format mask to a report data field. You can manually enter the mask in the Formatting Mask property on the **Properties** pane.

To enter a custom data formatting mask:

1. Select the data column or field in the layout.
2. On the **Properties** pane, under the **Data Formatting** group select the **Formatting Style**. Supported styles are Oracle and Microsoft.
3. In the **Formatting Mask** field, manually enter the format mask to apply.

Formatting masks can also be applied dynamically by either including the mask in a data element of your report data, or as a parameter to the report. The mask is passed to the layout editor based on the value of the data element.

To enter a dynamic formatting mask, in the **Formatting Mask** field, choose the data element that defines the formatting mask. The following figure shows an example of setting a dynamic number format mask. For this example, a parameter called `NumberFormat` prompts the user to define a format mask when the report is submitted. The value is passed to the Formatting Mask property and applied to the data field in the layout.



If you use a parameter to pass the format mask ensure that you select the **Include Parameter Tags** option on the data model Properties page.

About the Formula Option

The options available from the **Formula** region of the **Column** tab depend on the data type of the column.

For more information about applying formulas, see [Set Predefined or Custom Formulas](#).

About the Sort Option

To sort the data in a column, select the column, then under the **Sort** group click **Ascending Order** or **Descending Order**.


To sort by more than one column, select the column, the sort order, and then assign a Priority to each column. The priority list is a list of values beneath the sort order commands.

For example, in the employee salary table shown in the following figure, assume you want to sort ascending first by **Title** then sort descending by **Annual Salary**:

| Name | Hire Date | Title | Annual Salary |
|------------------|-----------|-------------------------------|---------------|
| Neena Kochhar | 9/21/89 | Administration Vice President | \$204,000.00 |
| Lex De Haan | 1/13/93 | Administration Vice President | \$204,000.00 |
| Alexander Hunold | 1/3/90 | Programmer | \$108,000.00 |
| Bruce Ernst | 5/21/91 | Programmer | \$72,000.00 |
| David Austin | 6/25/97 | Programmer | \$57,600.00 |
| Valli Pataballa | 2/5/98 | Programmer | \$57,600.00 |
| Diana Lorentz | 2/7/99 | Programmer | \$50,400.00 |
| Nancy Greenberg | 8/17/94 | Finance Manager | \$144,000.00 |
| Daniel Faviet | 8/16/94 | Accountant | \$108,000.00 |
| John Chen | 9/28/97 | Accountant | \$98,400.00 |
| | | | 7,411,200.00 |

1. Select the **Title** column.
2. On the **Column** tab, under **Sort**, click the **Ascending Order** button.
3. From the **Priority** list, select 1.

The following figure shows the **Priority** list.



4. Next select the **Annual Salary** column.
5. On the **Column** tab, under **Sort**, click the **Descending Order** button.
6. From the **Priority** list, select 2.

Remove a Sort Order

You can remove the sorting applied to a column.


To remove a sort order applied to a column:

1. Select the column.
2. From the **Sort** region on the Column tab, click the appropriate button of the sort order that has been applied. For example, to deselect the ascending order, click the **Ascending Order** button to undo the sort.

About the Total Cell Tab

The Layout Editor automatically inserts a grand total row when you insert a data table to the layout. As shown in the section on grouping, you can also insert subtotal rows within the table based on a grouping element.

To edit the attributes of the cells in a grand total or subtotal row, select the cell and use the options in the **Total Cell** tab shown in the following figure.



The **Total Cell** tab enables you to perform the following:

- Edit the font properties of the total cell
- Edit the cell properties of the total cell including border weight, style, and color and background fill color
- Set the vertical and horizontal alignment of the table header
- Apply formatting to the cell data
- Apply a formula to the cell
- Apply conditional formatting to the cell

Apply Data Formatting to a Total Cell

The section talks about applying data formatting to a total cell.

See [About the Data Formatting Options for Columns](#).

Apply a Formula

By default, the formula applied to a Total Cell within a numeric column is a sum of the column items. The Formula option enables you to apply a different formula.

Not all options available from the **Formula** region of the column tab are applicable to a Total Cell.


For more information about applying formulas, see [Set Predefined or Custom Formulas](#).

Insert Dynamic Hyperlinks

The layout editor supports dynamic hyperlinks in tables.

To insert a dynamic hyperlink:

1. Select the table column.
2. Click **Properties**. The column properties include an option for URL, as shown in the following illustration.



- In the URL field, enter the static portion of the URL and embed the absolute path to the element that provides the dynamic portion of the URL within curly braces `{}`. For example:

```
http://example.com/show_page?id={/DATA/GROUP1/ELEMENT_NAME}
```

where `http://example.com/show_page?id=` is the static portion of the URL and `{/DATA/GROUP1/ELEMENT_NAME}` is the absolute path to the element in the data that supplies the dynamic portion.

For example, in the employee salary report, suppose each employee name should render as a hyperlink to the employee's person record. Assume the static portion of the URL to each person record is

```
https://people.hrserver.com/records/show_page?id=
```

The dynamic portion comes from the data element `EMPLOYEE_ID`. For this example, append the full path to the `EMPLOYEE_ID` element within curly braces and enter this in the URL field as follows:

```
https://people.hrserver.com/records/show_page?id={/ROWSET/ROW/EMPLOYEE_ID}
```

Apply Custom Data Formatting

Publisher supports the use of the Oracle and Microsoft format masks for custom data formatting. The results of the output depends on the selected locale.

See [Use the Microsoft Number Format Mask](#) and [Use the Oracle Format Mask](#).

- Select a data field or column.
- Click **Properties**. The Data Formatting options are displayed as shown in the following figure:

| Manager | Full Name | Annual Salary | Title |
|---------------|------------------|---------------|---------|
| Kevin Mourgos | Donald O'Connell | \$31,200 | Shipp |
| | Douglas Grant | \$31,200 | Shipp |
| | Trenna Rajs | \$42,000 | Stock i |
| | Curtis Davies | \$37,200 | Stock i |
| | Randall Matos | \$31,200 | Stock i |
| | Peter Vargas | \$30,000 | Stock i |
| | Alana Walsh | \$37,200 | Shipp |
| Neena Kochhar | Kevin Feeney | \$36,000 | Shipp |
| | Jennifer Whalen | \$52,800 | Admini |
| | Susan Mavris | \$78,000 | Humar |
| | | \$7,924,800 | |

3. From the **Formatting Style** drop-down list, select the Oracle or Microsoft formatting style. The Oracle formatting style is recommended.
4. In the **Formatting Mask** field, enter a formatting mask. For example, for a column that contains product totals, you can use the Oracle formatting style, and the 9G999D99 formatting mask to display total values with two zeros to the right of the decimal place.

About Charts

The layout editor supports a variety of chart types and styles to graphically present data in the layout.

Once inserted, you can edit the chart properties using the dynamic toolbars or the **Properties** pane. The **Properties** pane extends the options from the **Chart** tab and enables you to enter very specific custom settings for the following:

- Chart Effect
- Chart Legend
- Chart Plot Area
- Chart Title
- Chart Label

Note:

The following Chart Label properties apply to Scatter and Bubble chart types only: Title Font, Title Horizontal Align, Title Text, and Title Visible.

- Chart Values

**Note:**

Some font effects such as underline, italic, and bold might not render in PDF output.


Insert a Chart

Follow these steps to insert a chart.


To insert a chart:

1. From the **Insert** menu, select and drag the Chart component to the layout.


By default an empty vertical bar chart is inserted and the **Chart** dynamic tab is displayed, as shown in the following figure:



2. To change the chart type, click the **Chart Type** list to select a different type. In the following figure, the chart type is changed to Pie.




3. Select and drag the data fields from the Data Source pane to the appropriate areas in the chart. The chart immediately updates with the preview data, as shown in the following figure:



- To resize the chart, drag and drop the resize handler on the lower right corner of the chart, as shown in the figure below.

To preserve the aspect ratio when resizing a chart, press and hold the `Shift` key before starting to drag the corner.



About the Chart Tab

The **Chart** tab helps you to apply a different chart type, filter the data, manage multiple filters.

The **Chart** tab enables you to perform the following:

- Select a different **Chart** Type
- Apply a different **Chart** Style
- Enable 3-D effects
- Filter the data that is displayed in the chart
- Manage multiple filters
- Convert the chart to a pivot table or switch the series and dimensions values

Apply and Manage Filters

This section helps you to know how to apply and manage filters.

See [About Filters](#) for information on how to apply and manage filters.

Convert a Chart to a Pivot Table

Follow these steps to convert a chart to a pivot table.


1. Select the chart.
2. In the **Convert** group, click **Pivot Table**.

The layout editor converts the label, series, and value elements of the chart into the appropriate rows, columns, and data elements of a pivot table.

Change the Formula Applied to a Chart Measure Field

By default, the chart displays a sum of the values of the chart measure. You can change the formula applied to a chart measure field by selecting an option from the **Chart Measure Field** tab.

1. Select the measure field in the chart. This displays the **Chart Measure Field** tab, as shown in the following figure:



2. Select from the following options available from the **Formula** list:
 - Count
 - Sum
 - Running Total

Sort a Chart Field

Charts can be sorted by fields.

To sort a field in the chart:

1. Select the field to display the **Chart Field** tab.
2. On the **Chart Field** tab select **Sort Ascending** or **Sort Descending**.
3. To sort by multiple fields, apply a **Priority** to each sort field to apply the sort in the desired order.

Use Advanced Chart Features

Create more useful charts by altering their appearance.

The following features enable you to apply additional formatting to your charts:


- [Format Time Series Axis](#)
- [Hide Axis Option](#)
- [Format Independent Axis](#)
- [Scale Axis](#)
- [Format Pie Slice](#)

If you do not select a value for these format options above, the Publisher default system settings are applied.

Format Time Series Axis

When the x-axis of your line chart is a date field, Publisher applies a time series format based on the range of the data.

The following illustration shows the time series format options. You can customize the display of the time series in your chart, or turn it off.



To select time series date formatting options for a chart:

1. Expand the Time Series report properties category.
2. In **Day Format** field, select one of the following format options for days:
 - **None** to hide the day label.
 - **Day of Week** to display only the names of each day of the week.
 - **Day Single Letter** to display only the first letter of each day of the week.
 - **Day of Week Number** to display only the number assigned to each day of the week. For example, if Sunday is the first day of the week, it can be displayed as 1, Monday displayed as 2, etc.
 - **Day of Month** to display all days in a month by the actual date. For example, the first day of the month would be displayed as 1.
3. In **Month Format** field, select one of the following format options for months:
 - **None** to hide all month labels.
 - **Month Number** to display only a number for each month in the year. For example, if the first month of the year is January, it's displayed in the chart as 1.
 - **Month Single Letter** to display only the first letter of each month in the year.
 - **Month Short** to display only the short names for each month. For example, January can be displayed as Jan.
 - **Month Long** to display only the full name of each month.
4. In the **Time Format** field, select one of the following format options for time increments:

- **None** to hide all time labels.
 - **Hour** to display time in hours.
 - **Hour24** to display time in 24 hour increments.
 - **Hour24 Minute** to display minutes in 24 hour increments.
 - **Hour Minute** to display time in hours and minutes.
 - **Second** to display time in seconds.
5. In **Year Format** field, select one of the following format options for years:
 - **None** to hide all year labels.
 - **Year Short** to display only the short names for each year.
 - **Year Long** to display only the full name of each year.

Hide Axis Option

You can hide axis labels in reports for certain situations such as when you are working with small charts or visualizing data without values. This option is especially useful for creating reports that evaluate trends.

To hide an axis:

1. On the Properties pane, expand the Chart Label, Chart Value (1) or Chart Value (2) report properties category.
2. In Axis Visible, select **False**.

Format Independent Axis

You can format decimal digits and numbers for each Y axis in a multiple Y-axis report.

To format decimal digits and number types for an axis:

1. On the Properties pane, expand the Chart Value (1) or Chart Value (2) report category.
2. To format axis decimals, in the Axis Decimals field, enter the number of decimals to display for a data element per axis.
3. To format data decimals for an axis where the Data Visible property is set to True, enter the number of decimals to display on the axis.
4. To apply number formatting to an axis, in the Format field, select one of the following options: General, Percent, or Currency.
5. If you select Currency, in the Currency Symbol field, manually enter the currency symbol.

Scale Axis

You can set chart axis scaling as logarithmic or linear in reports.

1. On the **Properties** pane, expand the Chart Value (1) or Chart Value (2) report properties category.
2. In the **Axis Scaling** field, select one of the following options: Logarithmic or Linear.

Format Pie Slice

You can format pie slice charts to display percentages, total actual values, percentages, and labels.


To format pie slices:

1. On the Properties pane, expand the Plot Area report property category.
2. In the **Pie Slice Format** field, select one of the following options: Percent, Value, Label, or Label and Percent.

About Gauge Charts

A gauge chart is a useful way to illustrate progress or goals. The illustration shows a report with gauges.

For example, the following figure shows a report with three gauges to indicate the status of regional sales goals:



Insert a Gauge Chart

Follow these steps to insert a gauge chart.

To insert a gauge chart in the layout:

1. From the **Insert** menu, select and drag the **Gauge** component to the layout. This inserts an empty gauge chart.
2. Select and drag the data fields from the Data Source pane to the Label, Value, and Series areas of the chart. The chart immediately updates with the preview data.

Note the following:

- A separate gauge is created for each occurrence of the Label (that is, each REGION). One set of properties applies to each occurrence.

- By default, the **Value** field is a sum. You can change the expression applied to the value field.
- You can apply a sort to the other gauge chart fields.

Apply and Manage Filters

Follow this section to know how to apply and manage filters.

See [About Filters](#) for information on how to apply and manage filters.

About Pivot Tables

The pivot table provides views of multidimensional data in tabular form. It supports multiple measures and dimensions and subtotals at all levels.

The following figure shows a pivot table:


| | | Magicolor | | Subtotal | | Total | |
|-----------------|----------------------|-------------|-----------|-------------|-----------|-------------|-----------|
| | | PrevRevenue | Revenue | PrevRevenue | Revenue | PrevRevenue | Revenue |
| | | | | | | | |
| CENTRAL REGION | CHICAGO DISTRICT | 5,587.00 | 3,741.00 | 5,587.00 | 3,741.00 | 5,587.00 | 3,741.00 |
| | CINCINNATI DISTRICT | 9,875.00 | 38,054.00 | 9,875.00 | 38,054.00 | 9,875.00 | 38,054.00 |
| | DETROIT DISTRICT | 5,706.00 | 2,149.00 | 5,706.00 | 2,149.00 | 5,706.00 | 2,149.00 |
| | KANSAS CITY DISTRICT | 9,467.00 | 55,519.00 | 9,467.00 | 55,519.00 | 9,467.00 | 55,519.00 |
| | MINNEAPOLIS DISTRICT | 140.00 | 231.00 | 140.00 | 231.00 | 140.00 | 231.00 |
| Subtotal | | 30,775.00 | 99,694.00 | 30,775.00 | 99,694.00 | 30,775.00 | 99,694.00 |
| Total | | 30,775.00 | 99,694.00 | 30,775.00 | 99,694.00 | 30,775.00 | 99,694.00 |

Insert a Pivot Table

Follow the steps in the procedure to insert a pivot table.


To insert a pivot table:

1. From the **Insert** tab, select and drag the **Pivot Table** component to the layout. The following figure shows the empty pivot table structure.




2. Drag and drop data fields from the Data Source pane to the row, column, and data positions.

Drag multiple fields to the pivot table and place them precisely to structure the pivot table, as shown in the following figure:



3. By default the pivot table is inserted with no data formatting applied. To apply a format to the data, click the first column of data to enable the Pivot Table Data toolbar. On the Data Formatting group, select the appropriate format as shown in the following figure:



4. Optional: Resize the pivot table by clicking and dragging the handler in the lower right corner of the pivot table.

Customize a Pivot Table Menu


After you insert a pivot table customize the appearance and layout using these dynamic tabs.

- **Pivot Table** tab
- **Pivot Table Header** tab
- **Pivot Table Data** tab

About the Pivot Table Tab

You can customize the appearance of a pivot table using the **Pivot Table** tab.

The following figure shows the **Pivot Table** tab.



Apply Filters

This section describes filters and manage filters features.

See [About Filters](#) for a description of the **Filter** and **Manage Filters** features.

Customize the Display of Totals

The **Pivot Table** tab enables you to quickly customize the display of grand total and subtotal rows.

By default, the layout editor inserts the pivot table with the total and subtotal displays as shown in the tab:

- **Row Grand Total** - Inserted at the bottom of table
- **Row Subtotal** - Inserted at the top of each subgroup, with no row header
- **Column Grand Total** - Inserted at the far right
- **Column Subtotal** - Inserted to the left of each column subgroup, with no header


Change the positioning and display of totals and subtotals by clicking the appropriate group in the tab and selecting the desired layout pattern from the menu.

Convert a Pivot Table to a Chart

The **Convert Pivot Table to a Chart** command converts the pivot table to a default vertical bar chart.

After conversion, customize the table as described in [About Charts](#).

The following figure shows the pivot table created in the preceding step converted to a vertical bar chart.



Switch Rows and Columns

Use the Switch Rows and Columns command to see a different view of the same data.


The following illustration shows the pivot table created in the previous step with rows and columns switched.

| | CENTRAL REGION | | | EASTERN REGION | |
|-------|------------------|----------------------|----------------------|----------------|----------------|
| | CHICAGO DISTRICT | KANSAS CITY DISTRICT | MINNEAPOLIS DISTRICT | NEV DIS | |
| 2000 | 1,555,548.00 | 1,555,548.00 | | 1,701,664.00 | |
| 1998 | 4,006,702.00 | | 4,006,702.00 | 21,644,266.00 | |
| 1999 | 4,431,632.00 | | 1,897,554.00 | 2,534,078.00 | 109,795,216.00 |
| Total | 9,993,882.00 | 1,555,548.00 | 5,904,256.00 | 2,534,078.00 | 133,141,146.00 |

Customize the Pivot Table Headers

Use the **Pivot Table Header** tab to customize the fonts, colors, etc.

The **Pivot Table Header** tab is shown in the following figure:




Select the column or row header of the pivot table and use the **Pivot Table Header** tab to perform the following:

- Customize the fonts, colors, alignment and other display features of the header.
- Apply a sort order (for more information see [About the Sort Option](#)).
- Apply data formatting (if the data type is number or date).

Customize the Pivot Table Data

Select the data area of the pivot table and use the **Pivot Table Data** tab to perform these actions. The commands in the **Pivot Table Data** tab are the same as the corresponding commands in the table Column tab.

The **Pivot Table Data** tab is shown in the following figure:



See the references for more information on their use.

- Customize the fonts, colors, alignment and other display features of the data.
- Apply conditional formatting to the data for more information (see [About Conditional Formats](#)).
- Apply data formatting (see [About the Data Formatting Options for Columns](#)).
- Apply a formula (see [Apply a Formula](#)).

About Text Items


The text item component allows you to enter free-form text in the layout.

1. Drag and drop the text item component to the layout.
2. Double-click the text to enter text editor mode. Select parts of the text to apply different formatting to different parts.

Display a Data Field Side-by-Side with a Text Item


By default, the text item always spawns a complete paragraph. Inserting a data field next to the text field places the data field beneath the text field.

The data field beneath a text item is shown in the following figure:




To display the data field inline with the text item:

- Set the Display property to **Inline** in the **Properties** pane.




This setting enables the positioning of text items and data fields into a single line as shown in the following figure:



About the Text Toolbar

The **Text** tab defines all the functions that you can do with respect to font and alignment of text in a report.

The **Text** tab is shown in the following figure.



The **Text** tab enables you to perform the following:

- Set the font properties
- Set alignment of the text in the grid cell
- Insert predefined text items: page number, date, and time
- Insert a hyperlink

Edit Font Properties

Use the Font group of commands to set the style, size, emphasis, and color.



- Select a font style
- Select a font size
- Apply emphasis (bold, italic, or underline)
- Insert a border around the text item
- Apply a background color

- Apply a font color

Insert Page Numbers

Drag and drop the page number component to the design area.

The following illustration shows the Page # of *N* construction.

Page  of 

To create the Page # of *N* construction:

1. From the **Insert** tab drag and drop a **Text Item** to the design area where you want the page numbers to display.
2. Double-click the inserted text to select the text item for editing. Type "Page ".
3. From the **Text** dynamic tab, drag and drop the **Page Number** component.
4. Enter a space, and type "of ".
5. From the **Text** dynamic tab, drag and drop the **Page Total** component.

Insert the Date and Time

You can insert time and date variables in a report design.

To insert the date and time in a report:


1. From the tab drag and drop a **Text Item** to the design area where you want the date and time to display.
2. Double-click the inserted text to select the text item for editing.
3. Click the **Date** icon to insert the date icon in the text item. Click the **Time** icon to insert the time icon in the text item.



Note:

To display the items side-by-side, set the **Text Item** property to "Inline".

The following illustration shows the insertion of the date and time icons.



When this report is viewed, the date and time are displayed according to the server time zone if viewed online, or for scheduled reports, the time zone selected for the schedule job.

Insert a Hyperlink

Follow these steps to insert a hyperlink.

To insert a hyperlink in a report:

1. From the **Insert** tab drag and drop a **Text Item** to the design area where you want the date and time to display.
2. Double-click the inserted text to select the text item for editing. Enter the text which you want to convert to a link.
3. Select the text, then click the **Link** button.
4. In the dialog enter the URL.

About Images

The image component enables you to include a graphic in the layout.

Publisher supports the following methods for including an image:

- **Static image:** Upload a static image that is saved in the report file. An uploaded image file must be in one of the following graphic file formats: GIF, JPEG, PNG, or BMP. The image file cannot be larger than 500 KB.
- **Static URL:** Specify a static link to a URL where an image is stored.
- **Dynamic URL:** Include the image URL in an element of the data. The value of the element is evaluated at runtime enabling dynamic insertion of images.
- **Images from a Content Server:** Embed dynamic images from a Content Server (UCM) in RTF and XPT templates. The administrator has to create a connection to the Content Server where the images are stored. The data model should use the Content Server as the data source.

Limitations:


- XPT template supports dynamic images from a Content Server only in the repeating sections.

- XSLX output format doesn't support inclusion of images from a Content Server.
- Default size for rendering images from a Content Sever (UCM) is 1MB.

To include an image in a layout:

1. Drag and drop the image component to the layout.
2. In the Insert an Image dialog, specify one of the following sources for the image:
 - **Location:** Click **Browse** to specify the file name and directory of the image on a local or mapped drive to upload the image.
 - **URL:** Enter the URL where the image is stored.
 - **Field:**
 - Image URL:** Select the field from the data that contains a URL to an image.
 - Alternative Text:** If the data includes a field that contains alternative text for the image, then select that field to display alternative text when the report is viewed as HTML.

The following figure shows the Insert an Image dialog set up to retrieve an image URL dynamically from the "Image" data element. The value of the "Name" element is used as alternative text.



3. Optional: Resize the image in one of the following ways:
 - Drag the right bottom corner of the image. To preserve the aspect ratio when resizing an image, press and hold the `Shift` key before starting to drag the corner.
 - Modify the width and height in the **Properties** pane.

Add BLOB Image

You can add a Binary Large Object (BLOB) image in an RTF or XPT template. Usage of an RTF template is recommended for BLOB images.

To add a BLOB image in XPT layout:

1. Specify the data column type as Binary Large Object (BLOB).
2. Insert the image in the BLOB column, and then select the BLOB column data element to display as image.

To add multiple BLOB data rows in tabular format, use Repeating Group. Include a Layout Grid to create a tabular format, and add the BLOB column in the Layout grid.


3. In the column preceding the BLOB image, type `"data:image/jpeg;base64,"` along with the quotes.

About Lists

The list component displays all values of a data element in a vertical or horizontal list. When viewed in interactive mode, clicking an item in the list updates the results shown in the linked components of the report.

The following figure shows a report that displays multiple charts based on sales data. The list component displays each country with sales data. The list enables the report consumer to quickly see results for each country in the list by clicking the entry in the list.

Click item in list to update results shown in other layout components




Insert a List

Follow these steps to insert a list.

To insert a list:


1. From the **Insert** tab, select and drag the **List** component to the design area.

The following figure shows an inserted, empty list:



- To create the list, select an element from the Data Source pane and drag it to the empty list in the layout.

The following figure shows the list component after dragging the element Country Name to it.



- Customize the appearance of the list.

4. Configure linked components using the **Configure Events** command. By default, all other tables and charts in the layout are configured to filter their results based on the user selections in the list component.


Customize a List

The **List** tab helps you to edit the font attributes, define border for the list, set background color, etc.

Use the **List** tab to:

- Edit the font size, style, and color
- Define borders for the list
- Set the background color
- Edit the font color and background color for the display of selected items
- Set the orientation of the list
- Specify the sort order

The following figure shows the **List** tab:



Customize the Font Style and the Selected Font Style Commands

This figure illustrates default formats. The list on the left shows the default format of the list. The list on the right shows the **Selected Font** default format

| |
|--------------------------|
| Australia |
| Brazil |
| Canada |
| Denmark |
| France |
| Germany |
| Italy |
| Japan |
| Singapore |
| Spain |
| Turkey |
| United Kingdom |
| United States of America |

Default format of list with
no items selected

| |
|--------------------------|
| France |
| Australia |
| Brazil |
| Canada |
| Denmark |
| Germany |
| Italy |
| Japan |
| Singapore |
| Spain |
| Turkey |
| United Kingdom |
| United States of America |

Default format with item
selected

Edit the font settings by selecting a font family from the list and adjusting the point size.


By default, the list displays with one point black gridlines. Click the **Set Border** to adjust the default borders of the list. Use the **Background Color** and **Font Color** commands to customize the colors.

The **Selected Font** commands edit the appearance of the item in a list when it's selected. By default, the selected element is moved to the top of the list, and the background is changed to light blue. You can edit the font weight, background color, and font color that are displayed for selected items.

Customize Behavior of Selected Items

By default, the selected items move to the top of the list and the non-selected items are hidden by a gray fill. You also have the option of not applying this behavior by setting the property **Hide Excluded**.

This property is available from the **Properties** pane when the List component is selected. The **Hide Excluded** property is highlighted in the following figure:



The following figure shows the difference in the display depending on the setting of the property:

Display of selected item
when "Hide Excluded" set
to False



| |
|--------------------------|
| France |
| Australia |
| Brazil |
| Canada |
| Denmark |
| Germany |
| Italy |
| Japan |
| Singapore |
| Spain |
| Turkey |
| United Kingdom |
| United States of America |

Selected item moved to top
of list; other items grayed
out

Display of selected item
when "Hide Excluded" set
to True




| |
|--------------------------|
| Australia |
| Brazil |
| Canada |
| Denmark |
| France |
| Germany |
| Italy |
| Japan |
| Singapore |
| Spain |
| Turkey |
| United Kingdom |
| United States of America |

Selected item not moved;
other items unchanged

Set Predefined or Custom Formulas

You can set custom formulas using the Define Custom Formula icon.

The following illustration shows the Define Custom Formula icon.



The Formula group of commands is available from the following tabs:

- Column tab
- Total Cell tab
- Chart Measure Field tab
- Pivot Table Data tab

Note that not all options are applicable to each component type.

About the Predefined Formulas

The table provides definitions of predefined formulas.

The menu provides the predefined formulas that are described in the following table.

| Formula | Description |
|-----------------------|---|
| No Formula | Removes any mathematical formula from a numeric column. |
| Blank Text | Removes all data and inserts blank text. |
| Count | Returns the count of the number of occurrences of the element in the current group. |
| Count Distinct | Returns a count of the distinct values of an element in the current group. |
| Summation | Sums the values of the element in the current group. |
| Average | Displays the average of the values in the current group. |
| Maximum | Displays the highest value of all occurrences in the current group. |
| Minimum | Displays the lowest value of all occurrences in the current group. |


For non-numeric data, only the following formula options are supported:

- Blank Text
- Count
- Count Distinct

Apply a Custom Formula

Click **Define Custom Formula** to define your own formula for a component. The Function dialog enables you to define Basic Math, Context, and Statistical functions in the layout.


The following figure shows the Function dialog:



About the Basic Math Functions

When you click one of the basic math functions, you are prompted to define the appropriate parameters for the function. You can enter a constant value, select a field from the data, or create a nested function to supply the value.


In the **Function** dialog, clicking the **Multiplication** function displays prompts to enter the multiplicand and the multiplier. The example shows that the multiplicand is the value of the Amount Sold field. The multiplier is the constant value.



About the Statistical Math Functions

When you click one of the statistical math functions you are prompted to define the appropriate parameter for the function. You can select a field from the data, or create a nested function to supply the values.

In the following figure, clicking the **Average** function displays prompts for you to specify the source of the values for which to calculate the average.



Apply a Custom Formula: Examples

Follow these examples to understand custom formula.

Example 12-1 Example 1: Subtraction

The following figure shows data for Revenue and Cost for each Office:


| Office | Revenue | Cost |
|------------|-------------|------------|
| Whalen | \$4,400.00 | \$1,100.00 |
| Hartstein | \$13,000.00 | \$3,250.00 |
| Fay | \$6,000.00 | \$1,500.00 |
| Raphaely | \$11,000.00 | \$2,750.00 |
| Khoo | \$3,100.00 | \$775.00 |
| Baida | \$2,900.00 | \$725.00 |
| Tobias | \$2,800.00 | \$700.00 |
| Himuro | \$2,600.00 | \$650.00 |
| Colmenares | \$2,500.00 | \$625.00 |
| Mavris | \$6,500.00 | \$1,625.00 |

Using a custom formula, you can add a column to this table to calculate Profit (Revenue - Cost).


1. Add another numeric data column to the table. For example, drag another instance of Revenue to the table, as shown in the following figure:

| Office | Revenue | Cost | Revenue |
|------------|-------------|------------|-------------|
| Whalen | \$4,400.00 | \$1,100.00 | \$4,400.00 |
| Hartstein | \$13,000.00 | \$3,250.00 | \$13,000.00 |
| Fay | \$6,000.00 | \$1,500.00 | \$6,000.00 |
| Raphaely | \$11,000.00 | \$2,750.00 | \$11,000.00 |
| Khoo | \$3,100.00 | \$775.00 | \$3,100.00 |
| Baida | \$2,900.00 | \$725.00 | \$2,900.00 |
| Tobias | \$2,800.00 | \$700.00 | \$2,800.00 |
| Himuro | \$2,600.00 | \$650.00 | \$2,600.00 |
| Colmenares | \$2,500.00 | \$625.00 | \$2,500.00 |
| Mavris | \$6,500.00 | \$1,625.00 | \$6,500.00 |


2. With the table column selected, click **Define Custom Formula**.
3. In the Function dialog select **Subtraction** from the list, as shown in the following figure. Because the source data for the column is Revenue, by default the **Minuend** and the **Subtrahend** both show the Revenue element.



4. Select **Subtrahend**, then in the **Parameter** region, select **Field** and choose the **Cost** element, as shown in the following figure:



The dialog is updated to show that the formula is now Revenue minus Cost, as shown in the following figure:



5. Click **OK** to close the dialog.
6. The table column displays the custom formula. Edit the table column header title, and now the table has a Profit column, as shown in the following figure:

| Office | Revenue | Cost | Profit |
|------------|-------------|------------|------------|
| Whalen | \$4,400.00 | \$1,100.00 | \$3,300.00 |
| Hartstein | \$13,000.00 | \$3,250.00 | \$9,750.00 |
| Fay | \$6,000.00 | \$1,500.00 | \$4,500.00 |
| Raphaely | \$11,000.00 | \$2,750.00 | \$8,250.00 |
| Khoo | \$3,100.00 | \$775.00 | \$2,325.00 |
| Baida | \$2,900.00 | \$725.00 | \$2,175.00 |
| Tobias | \$2,800.00 | \$700.00 | \$2,100.00 |
| Himuro | \$2,600.00 | \$650.00 | \$1,950.00 |
| Colmenares | \$2,500.00 | \$625.00 | \$1,875.00 |
| Mavris | \$6,500.00 | \$1,625.00 | \$4,875.00 |


Example 12-2 Example 2: Nested Function

This example uses a nested function to create a column that shows Revenue less taxes.


1. Add another numeric data column to the table. For example, drag another instance of Revenue to the table, as shown in the following figure:

| Office | Revenue | Revenue |
|------------|-------------|-------------|
| Whalen | \$4,400.00 | \$4,400.00 |
| Hartstein | \$13,000.00 | \$13,000.00 |
| Fay | \$6,000.00 | \$6,000.00 |
| Raphaely | \$11,000.00 | \$11,000.00 |
| Khoo | \$3,100.00 | \$3,100.00 |
| Baida | \$2,900.00 | \$2,900.00 |
| Tobias | \$2,800.00 | \$2,800.00 |
| Himuro | \$2,600.00 | \$2,600.00 |
| Colmenares | \$2,500.00 | \$2,500.00 |
| Mavris | \$6,500.00 | \$6,500.00 |


2. With the table column selected, click **Define Custom Formula**.
3. In the Function dialog select **Subtraction** from the list. Because the source data for the column is Revenue, by default the **Minuend** and the **Subtrahend** both show the Revenue element, as shown in the following figure:




4. Select **Subtrahend**, then in the **Parameter** region, select **Nested Function** and click **Edit**, as shown in the following figure.



A second Function dialog is displayed to enable you to define the nested function. In this case the nested function is Revenue times a constant value (tax rate of .23), as shown in the following figure:



5. Click **OK** to close the dialog. The primary Function dialog now shows the nested function as the source of the subtrahend, as shown in the following figure:



6. Click **OK** to close the Function dialog. The table column displays the custom formula. Edit the table column header label, and now the table displays the custom function, as shown in the following figure:

| Office | Revenue | Revenue less tax (23%) |
|------------|------------|------------------------|
| Whalen | 4,400.00 | 3,388.00 |
| Hartstein | 13,000.00 | 10,010.00 |
| Fay | 6,000.00 | 4,620.00 |
| Raphaely | 11,000.00 | 8,470.00 |
| Khoo | 3,100.00 | 2,387.00 |
| Baida | 2,900.00 | 2,233.00 |
| Tobias | 2,800.00 | 2,156.00 |
| Himuro | 2,600.00 | 2,002.00 |
| Colmenares | 2,500.00 | 1,925.00 |
| Mavris | 6,500.00 | 5,005.00 |
| | 633,500.00 | 487,795.00 |

Save a Layout

You can save a report layout.

To save the layout to the report definition:

1. Click the **Save** or **Save As** toolbar button
2. Enter a unique name for this layout.
3. Select a **Locale**.

 **Note:**

After you save the layout, you can't update the Locale.

13

Create RTF Templates

This topic describes the concepts of associating XML data to layout elements in an RTF report template. It describes basic and advanced techniques for creating complex and highly conditionalized report formats.

Topics:

- [Get Started](#)
- [Associate the XML Data to the Template Layout](#)
- [Add Markup to the Template Layout](#)
- [Define Groups](#)
- [Define Headers and Footers](#)
- [Insert Images and Charts](#)
- [Add Drawings, Shapes, and Clip Art](#)
- [Supported Formatting Features of Microsoft Word](#)
- [Template Features](#)
- [Use Conditional Formatting](#)
- [Insert Page-Level Calculations](#)
- [Handle Data](#)
- [Set Variables, Parameters, and Properties](#)
- [Use Advanced Report Layouts](#)
- [Format Numbers, Dates, and Currencies](#)
- [Support Calendars and Time Zones](#)
- [Use External Fonts](#)
- [Control the Placement of Instructions Using the Context Commands](#)
- [Use XPath Commands](#)
- [Declare Namespaces](#)
- [Use FO Elements and XSL Elements](#)
- [Guidelines for Designing RTF Templates for Microsoft PowerPoint Output](#)
- [Guidelines for Designing RTF Templates for Microsoft Excel 2007 Output](#)
- [Render HTML Formatted Data in a Report](#)
- [Embed PCL Commands for Check Printing](#)
- [2D Barcode Functions](#)

Get Started

This chapter describes the concepts of associating XML data to layout elements in a report template. It describes basic techniques as well as advanced techniques for creating complex and highly conditionalized report formats.

If you are using Microsoft Word to create RTF templates, then see [Create RTF Templates Using the Template Builder for Word](#) before reading this chapter. The demos and samples provided in the Template Builder installation can help orient you to the process of creating templates in Microsoft Word.

You don't need Microsoft Word or the Template Builder to create RTF templates and this chapter describes how to add components without using the Template Builder. Many of the layout components described in this chapter can also be inserted in a template using the Template Builder.

This section covers the following topics:

- [What Are RTF Templates?](#)
- [Prerequisites for Designing Templates](#)
- [What is XSLT Compatibility?](#)
- [Key Concepts](#)
- [Design the Template Layout](#)
- [About Adding Publisher Code](#)

What Are RTF Templates?

Rich Text Format (RTF) is a specification used by common word processing applications, such as Microsoft Word.

When you save a document, RTF is a file type option.

Publisher converts documents saved as the RTF file type to XSL-FO enabling you to create report layouts using many standard word processor features.

During design time, you add data fields and other markup to the template using Publisher's simplified tags for XSL expressions. These tags associate the XML report data to the report layout and include other processing instructions.

In addition to the word processor's formatting features, Publisher supports other advanced reporting features such as conditional formatting, dynamic data columns, running totals, and charts.

If you are familiar with XSL and prefer not to use the simplified tags, Publisher also supports the use of pure XSL elements in the template. If you want to include code directly in the template, then you can include *any* XSL element, many FO elements, and a set of SQL expressions that Publisher extends.

Prerequisites for Designing Templates

You must perform these tasks before designing a template.

Before you design a template, you must:

- Know the business rules that apply to the data from the source report.
 - Generate sample data from the report data model.
- Be familiar with the formatting features of Microsoft Word.

What is XSLT Compatibility?

Publisher uses the XSLT processor provided by Oracle XDK 11.1.0.7.0, which supports the W3C XSL Transformations 1.0 recommendation.

The processor also implements the current working drafts of the XSLT and XPath 2.0 standards.

By default, Publisher is compatible with XSLT 1.0. If you want to use XSLT and XPath 2.0 features in the template, then you must disable XSLT 1.0 compatibility. This configuration is performed at the template level. The template-level setting overrides the server setting.

XSLT compatibility is set as a Build Option in the Template Builder for Word. See [Set UI Options](#).

Key Concepts

When you design the template layout, you must understand how to associate the XML input file to the layout.

This chapter presents a sample template layout with its input XML file to illustrate how to make the proper associations to add the markup tags to the template.

Design the Template Layout

Use the word processor's formatting features to create the design.

For example:

- Select the size, font, and alignment of text
- Insert bullets and numbering
- Draw borders around paragraphs
- Include a watermark
- Include images (jpg, gif, or png)
- Use table auto formatting features
- Insert a header and footer

About Adding Publisher Code

When you create an RTF template, you add Publisher code to the RTF document. Follow one of these methods to add code.

Publisher supports the following methods for adding code:

- Basic RTF Method

Use any word processor that supports RTF version 1.6 writer (or later) to design a template using Publisher's simplified syntax.

- Form Field Method

Using Microsoft Word's form field feature allows you to place the syntax in hidden form fields, rather than directly into the design of the template.

If you use XSL or XSL-FO code rather than the simplified syntax, then you must use the form field method.

This chapter describes how to create RTF templates using the preceding methods.

If you are using Microsoft Word, you can use the Publisher Template Builder for Word to facilitate inserting Publisher code fields.

Associate the XML Data to the Template Layout

The figure in this section shows a sample layout for a Payables Invoice Register.

ORACLE
E-Business Suite

Payables Invoice Register

Page 1 of 1
25 July 2003

Group: Suppliers Sort by: Supplier

Supplier: **Supplier 1**

| Invoice Num | Invoice Date | GL Date | Curr | Entered Amt | Accounted Amt |
|-------------------------------|--------------|------------|------|--------------|---------------|
| Group:Invoices 1234566 | 1-Jan-2004 | 1-Jan-2004 | USD | 1000.00 | 1000.00 |
| | | | | End:Invoices | |
| Total for Supplier: Supplier1 | | | | 1000.00 | 1000.00 |

End:Suppliers

Company Confidential

Note the following:

- The data fields that are defined on the template.
For example: Supplier, Invoice Number, and Invoice Date
- The elements of the template that are repeated when the report is run.
For example, all the fields on the template are repeated for each Supplier that is reported. Each row of the invoice table is repeated for each invoice that is reported.

Use an XML Input File

Following is the XML file that is used as input to the Payables Invoice Register report template.

To simplify the example, the XML output shown has been modified from the actual output from the Payables report.

```
<?xml version="1.0" encoding="WINDOWS-1252" ?>
- <VENDOR_REPORT>
- <LIST_G_VENDOR_NAME>
- <G_VENDOR_NAME>
  <VENDOR_NAME>COMPANY A</VENDOR_NAME>
- <LIST_G_INVOICE_NUM>
- <G_INVOICE_NUM>
  <SET_OF_BOOKS_ID>124</SET_OF_BOOKS_ID>
  <GL_DATE>10-NOV-03</GL_DATE>
  <INV_TYPE>Standard</INV_TYPE>
  <INVOICE_NUM>031110</INVOICE_NUM>
  <INVOICE_DATE>10-NOV-03</INVOICE_DATE>
  <INVOICE_CURRENCY_CODE>EUR</INVOICE_CURRENCY_CODE>
  <ENT_AMT>122</ENT_AMT>
  <ACCTD_AMT>122</ACCTD_AMT>
  <VAT_CODE>VAT22%</VAT_CODE>
  </G_INVOICE_NUM>
</LIST_G_INVOICE_NUM>
<ENT_SUM_VENDOR>1000.00</ENT_SUM_VENDOR>
<ACCTD_SUM_VENDOR>1000.00</ACCTD_SUM_VENDOR>
</G_VENDOR_NAME>
</LIST_G_VENDOR_NAME>
<ACCTD_SUM_REP>108763.68</ACCTD_SUM_REP>
<ENT_SUM_REP>122039</ENT_SUM_REP>
</VENDOR_REPORT>
```

XML files are composed of elements. Each tag set is an element. For example `<INVOICE_DATE> </INVOICE_DATE>` is the invoice date element. "INVOICE_DATE" is the tag name. The data between the tags is the value of the element. For example, the value of INVOICE_DATE is "10-NOV-03".

The elements of the XML file have a hierarchical structure. Another way of saying this is that the elements have parent-child relationships. In the XML sample, some elements are contained within the tags of another element. The containing element is the parent and the included elements are its children.

Every XML file has only one root element that contains all the other elements. In this example, VENDOR_REPORT is the root element. The elements LIST_G_VENDOR_NAME, ACCTD_SUM_REP, and ENT_SUM_REP are contained between the VENDOR_REPORT tags and are children of VENDOR_REPORT. Each child element can have child elements of its own.

Identify Placeholders and Groups

The template content and layout must correspond to the content and hierarchy of the input XML file. Each data field in the template must map to an element in the XML file. Each group of repeating elements in the template must correspond to a parent-child relationship in the XML file.

Define placeholders to map the data fields. Define groups to designate the repeating elements.

 **Note:**

Publisher supports regrouping of data if the report requires grouping that doesn't follow the hierarchy of the incoming XML data. For information on using this feature, see [Regroup the XML Data](#).

Use Placeholders

Each data field in the report template must correspond to an element in the XML file.

When you mark up the template design, you define placeholders for the XML elements. The placeholder maps the template report field to the XML element. At runtime the placeholder is replaced by the value of the element of the same name in the XML data file.

For example, the "Supplier" field from the sample report layout corresponds to the XML element `VENDOR_NAME`. When you mark up the template, you create a placeholder for `VENDOR_NAME` in the position of the Supplier field. At runtime, this placeholder is replaced by the value of the element from the XML file (the value in the sample file is **COMPANY A**).

Identify the Groups of Repeating Elements

The sample report lists suppliers and their invoices. There're fields that repeat for each supplier and invoice.

The report therefore consists of two groups of repeating fields:

- Fields that repeat for each supplier
- Fields that repeat for each invoice

The invoices group is nested inside the suppliers group. This can be represented as follows:

Suppliers

- Supplier Name
- Invoices
 - Invoice Num
 - Invoice Date
 - GL Date
 - Currency
 - Entered Amount
 - Accounted Amount
- Total Entered Amount
- Total Accounted Amount

Compare this structure to the hierarchy of the XML input file. The fields that belong to the Suppliers group shown above are children of the element `G_VENDOR_NAME`.

The fields that belong to the Invoices group are children of the element G_INVOICE_NUM.

By defining a group, you're notifying Publisher that *for each* occurrence of an element (parent), you want the included fields (children) displayed. At runtime, Publisher loops through the occurrences of the element and displays the fields each time.

Add Markup to the Template Layout

Publisher converts the formatting that you apply in the word processor to XSL-FO. You add markup to create the mapping between the layout and the XML file and to include features that cannot be represented directly in the format.

The most basic markup elements are placeholders, to define the XML data elements; and groups, to define the repeating elements.

Publisher provides tags to add markup to the template. For the XSL equivalents of the Publisher tags, see [XSL Equivalents](#).

Create Placeholders

The placeholder maps the template field to the XML element data field. At runtime the placeholder is replaced by the value of the element of the same name in the XML data file.

Enter placeholders in the document using the following syntax:

```
<?XML element tag name?>
```

The placeholder must match the XML element tag name exactly. It's case sensitive.

There're two ways to insert placeholders in the document:

- [Use the Basic RTF Method](#): Insert the placeholder syntax directly into the template document.
- [Use the Form Field Method](#): (Requires Microsoft Word) Insert the placeholder syntax in Microsoft Word's Text Form Field Options window. This method allows you to maintain the appearance of the template.

See [Insert a Field](#).

Use the Basic RTF Method

Enter the placeholder syntax in the document where you want the XML data value to appear.

Enter the element's XML tag name using the syntax:

```
<?XML element tag name?>
```

In the example, the template field "Supplier" maps to the XML element VENDOR_NAME. In the document, enter:

```
<?VENDOR_NAME?>
```

The entry in the template is shown in the following illustration.

Supplier: <?VENDOR_NAME?>

| Invoice Num | Invoice |
|-------------|---------|
| | |

Total for Supplier:

Use the Form Field Method

Placeholder tags can be added using the Form Field method.

To use Microsoft Word's Form Field method to insert the placeholder tags:

1. Enable the **Forms** toolbar in the Microsoft Word application.
2. Position the cursor in the location where you want to create a placeholder.
3. Select the **Text Form Field** toolbar icon. This action inserts a form field area in the document.
4. Double-click the form field area to invoke the **Text Form Field Options** dialog box.
5. Optional: Enter a description of the field in the **Default text** field. The entry in this field populates the placeholder's position on the template.

For the example, enter "Supplier 1".

6. Select the **Add Help Text** button.
7. In the help text entry field, enter the XML element's tag name using the syntax:


```
<?XML element tag name?>
```

You can enter multiple element tag names in the text entry field.

In the example, the report field "Supplier" maps to the XML element VENDOR_NAME. In the **Form Field Help Text** field enter:

```
<?VENDOR_NAME?>
```

The following illustration shows the Text Form Field Options dialog and the Form Field Help Text dialog with the appropriate entries for the Supplier field.




Tip:

For longer strings of Publisher syntax, use the Help Key (F1) tab instead of the Status Bar tab. The text entry field on the Help Key (F1) tab allows more characters.

8. Click **OK** to apply.

The **Default text** is displayed in the form field on the template.

The following illustration shows the Supplier field from the template with the added form field markup.




Complete the Example

This table shows the entries made to complete the example. The Template Field Name is the display name from the template. The Default Text Entry is the value entered in the Default Text field of the Text Form Field Options dialog box (form field method only). The Placeholder Entry is the XML element tag name entered either in the Form Field Help Text field (form field method) or directly on the template.

| Template Field Name | Default Text Entry (Form Field Method) | Placeholder Entry (XML Tag Name) |
|---------------------------------|--|----------------------------------|
| Invoice Num | 1234566 | <?INVOICE_NUM?> |
| Invoice Date | 1-Jan-2004 | <?INVOICE_DATE?> |
| GL Date | 1-Jan-2004 | <?GL_DATE?> |
| Curr | USD | <?INVOICE_CURRENCY_CODE?> |
| Entered Amt | 1000.00 | <?ENT_AMT?> |
| Accounted Amt | 1000.00 | <?ACCTD_AMT?> |
| (Total of Entered Amt column) | 1000.00 | <?ENT_SUM_VENDOR?> |
| (Total of Accounted Amt column) | 1000.00 | <?ACCTD_SUM_VENDOR?> |

This figure shows the Payables Invoice Register with the completed form field placeholder markup. See [Use the Basic RTF Method](#) for the completed basic RTF markup.

|  | | Payables Invoice Register | | <small>Page 1 of 1 25th January 2004</small> | |
|---|--------------|----------------------------------|------|---|----------------|
| Supplier: Supplier 1 | | | | | |
| Invoice Num | Invoice Date | GL Date | Curr | Entered Amt | Accounted Amt |
| 1234566 | 1-Jan-2004 | 1-Jan-2004 | USD | 1000.00 | 1000.00 |
| Total for Supplier: Supplier1 | | | | 1000.00 | 1000.00 |

Company Confidential

Define Groups

By defining a group, you notify Publisher that *for each* occurrence of an element, you want the included fields displayed. At runtime, Publisher loops through the occurrences of the element and displays the fields each time.

In the example, for each occurrence of G_VENDOR_NAME in the XML file, you want the template to display its child elements VENDOR_NAME (Supplier Name), G_INVOICE_NUM (the Invoices group), Total Entered Amount, and Total Accounted Amount. And, for each occurrence of G_INVOICE_NUM (Invoices group), you want the template to display Invoice Number, Invoice Date, GL Date, Currency, Entered Amount, and Accounted Amount.

To designate a group of repeating fields, insert the grouping tags around the elements to repeat.

Insert the following tag before the first element:

```
<?for-each:XML group element tag name?>
```

Insert the following tag after the final element:

```
<?end for-each?>
```

See [Insert a Repeating Group](#).

Group Scenarios

When grouping, note that the group element must be a parent of the repeating elements in the XML input file. These are some of the grouping scenarios.

- If you insert the grouping tags around text or formatting elements, then the text and formatting elements between the group tags are repeated.
- If you insert the tags around a table, then the table is repeated.
- If you insert the tags around text in a table cell, then the text in the table cell between the tags is repeated.
- If you insert the tags around two different table cells, but in the same table row, then the single row is repeated.
- If you insert the tags around two different table rows, then the rows between the tags are repeated (this doesn't include the row that contains the "end group" tag).

Use the Basic RTF Method

Enter the tags in the document to define the beginning and end of the repeating element group.


To create the Suppliers group in the example, insert the tag:

```
<?for-each:G_VENDOR_NAME?>
```

before the Supplier field that you previously created.

Insert `<?end for-each?>` in the document after the summary row.

The following illustration shows the Payables Invoice Register with the basic RTF grouping and placeholder markup.



Payables Invoice Register

Page 1 of 1
25th January 2004

`<?for-each: G_VENDOR_NAME?>` `<?sort:VENDOR_NAME?>`
 Supplier: `<?VENDOR_NAME?>`

| Invoice Num | Invoice Date | GL Date | Curr | Entered Amt | Accounted Amt |
|--|--|--------------------------------|---|--|---|
| <code><?for-each:</code> <code>G_INVOICE_NUM?></code> <code><?INVOICE_NUM?></code> | <code><?INVOICE_D</code> <code>ATE?></code> | <code><?GL_DATE?></code> | <code><?INV</code> <code>OICE</code> <code>_CUR</code> <code>REN</code> <code>CY_C</code> <code>ODE?></code> | <code><?ENT_AMT?></code> | <code><?ACCTD_AMT?></code> <code><?end for-each?></code> |
| Total for Supplier: <code><?VENDOR_NAME?></code> | | | | <code><?ENT_SUM_VEND</code> <code>OR?></code> | <code><?ACCTD_SUM_V</code> <code>ENDOR?></code> |

`<?end for-each?>`

Company Confidential

Use the Form Field Method

You can define a group using the Form Field method.

To use Microsoft Word's Form Field method to defining a group:

1. Insert a form field to designate the beginning of the group.

In the help text field enter:

```
<?for-each:group element tag name?>
```

To create the Suppliers group in the example, insert a form field before the Suppliers field that you previously created. In the help text field enter:

```
<?for-each:G_VENDOR_NAME?>
```

For the example, enter the Default text "Group: Suppliers" to designate the beginning of the group on the template. Default text is optional, but can make the template easier to read.

2. Insert a form field after the final placeholder element in the group. In the help text field enter `<?end for-each?>`.

For the example, enter the Default text "End: Suppliers" after the summary row to designate the end of the group on the template.

The following figure shows the template after the markup to designate the Suppliers group was added.

Group: Suppliers

Supplier: Supplier 1

| Invoice Num | Invoice |
|-------------|---------|
| 1234566 | 1-Jan- |
| | |

End:Suppliers

Complete the Example

The second group in the example is the invoices group. The repeating elements in this group are displayed in the table. For each invoice, the table row should repeat. Create a group within the table to contain these elements.

Note:

For each invoice, only the table *row* should repeat, not the entire table. Placing the grouping tags at the beginning and end of the table row repeats only the row. If you place the tags around the table, then for each new invoice the entire table with headings is repeated.

To mark up the example, insert the grouping tag `<?for-each:G_INVOICE_NUM?>` in the table cell before the Invoice Num placeholder. Enter the Default text `Group:Invoices` to designate the beginning of the group.

Insert the end tag inside the final table cell of the row after the Accounted Amt placeholder. Enter the Default text `End:Invoices` to designate the end of the group.

The following figure shows the completed example using the form field method.



Payables Invoice Register

Page 1 of 1
25 July 2003

Group: Suppliers Sort by: Supplier

Supplier: **Supplier 1**

| Invoice Num | Invoice Date | GL Date | Curr | Entered Amt | Accounted Amt |
|--------------------------------------|--------------|------------|------|----------------|----------------|
| Group:Invoices 1234566 | 1-Jan-2004 | 1-Jan-2004 | USD | 1000.00 | 1000.00 |
| | | | | | End:Invoices |
| Total for Supplier: Supplier1 | | | | 1000.00 | 1000.00 |

End:Suppliers

Company Confidential

Define Headers and Footers

You can define headers and footers as part of the template.

This section covers the following topics:

- [Native Support for Headers and Footers](#)
- [Insert Placeholders in the Headers and Footers](#)
- [Create Multiple or Complex Headers and Footers](#)
- [Define Different First Page and Different Odd and Even Pages](#)

Native Support for Headers and Footers

You can use native RTF header and footer in the report.

To create a header or footer, use the word processor's header and footer insertion tools. As an alternative, or if you have multiple headers and footers, you can use start:body and end body tags to distinguish the header and footer regions from the body of the report.

Insert Placeholders in the Headers and Footers

At the time of this writing, Microsoft Word doesn't support form fields in the header and footer.

You must therefore insert the placeholder syntax directly into the template (basic RTF method), or use the start body/end body syntax described in the next section.

Create Multiple or Complex Headers and Footers

If the template requires multiple headers and footers, then create them by using Publisher tags to define the body area of the report. You may also want to use this method if the header and footer contain complex objects that you want to place in form

fields. When you define the body area, the elements occurring before the beginning of the body area compose the header. The elements occurring after the body area compose the footer.

Use the following tags to enclose the body area of the report:

```
<?start:body?>
```

```
<?end body?>
```

Use the tags either directly in the template, or in form fields.

The Payables Invoice Register contains a simple header and footer and therefore doesn't require the start body/end body tags. However, if you wanted to add another header to the template, define the body area.


To define the body area:

1. Insert `<?start:body?>` before the Suppliers group tag:

```
<?for-each:G_VENDOR_NAME?>
```
2. Insert `<?end body?>` after the Suppliers group closing tag:

```
<?end for-each?>
```

The following figure shows the Payables Invoice Register with the start body/end body tags inserted:



Payables Invoice Register

Page 1 of 1
25th July 2003

`<?start:body?>`

Group: **Suppliers** Sort by: **Supplier**

Supplier: **Supplier 1**

| Invoice Num | Invoice Date | GL Date | Curr | Entered Amt | Accounted Amt |
|--------------------------------------|--------------|------------|------|----------------|----------------|
| Group:Invoices 1234566 | 1-Jan-2004 | 1-Jan-2004 | USD | 1000.00 | 1000.00 |
| | | | | | End:Invoices |
| Total for Supplier: Supplier1 | | | | 1000.00 | 1000.00 |

End:Suppliers
`<?end body?>`

Company Confidential

Define Different First Page and Different Odd and Even Pages

If the report requires a different header and footer on the first page of the report; or, if the report requires different headers and footers for odd and even pages, then you can define this behavior using Microsoft Word's Page Setup dialog.

 **Note:**

This feature is supported for PDF and RTF output only.

To define different page setups:

1. Select **Page Setup** from the **File** menu.
2. In the Page Setup dialog, select the **Layout** tab.
3. In the **Headers and footers** region of the dialog, select the appropriate check box:
Different odd and even
Different first page
4. Insert the headers and footers into the template as desired.

At runtime the generated report exhibits the defined header and footer behavior.

Insert Images and Charts

Publisher supports several methods for including images in the published document.

The following sections describe these options:

- [Directly Insert Images](#)
- [Insert Images with URL References](#)
- [Insert Images with an Element Reference from an XML File](#)
- [Render an Image Retrieved from BLOB Data](#)
- [Add Charts to Templates](#)

Directly Insert Images

Insert the jpg, gif, or png image directly in the template.

Note that if you insert an image to an RTF template, and set the **Wrap Text** property of the image to a value other than **In Line With Text**, the PowerPoint output won't contain the image.

Insert Images with URL References

Include an alternative text link for an image.

To insert images with URL references:

1. Insert a dummy image in the template.
2. In Microsoft Word's Format Picture dialog box select the **Web** tab. Enter the following syntax in the **Alternative text** region to reference the image URL:

```
url: {'http://<image location>'}
```

For example, enter:

```
url: {'http://www.example.com/images/ora_log.gif'}
```

Insert Images with an Element Reference from an XML File

Include a link to an XML file for an image.

To insert images with element references:

1. Insert a dummy image in the template.
2. In Microsoft Word's Format Picture dialog box select the **Web** tab. Enter the following syntax in the **Alternative text** region to reference the image URL:

```
url:{IMAGE_LOCATION}
```

where *IMAGE_LOCATION* is an element from the XML file that holds the full URL to the image.

You can also build a URL based on multiple elements at runtime. Just use the concat function to build the URL string. For example:

```
url:{concat(SERVER,'/',IMAGE_DIR,'/',IMAGE_FILE)}
```

where *SERVER*, *IMAGE_DIR*, and *IMAGE_FILE* are element names from the XML file that hold the values to construct the URL.

This method can also be used with the *OA_MEDIA* reference as follows:

```
url:{concat('${OA_MEDIA}','/',IMAGE_FILE)}
```

Render an Image Retrieved from BLOB Data

You can include an image stored as a BLOB in a form.

If results XML contains image data that had been stored as a BLOB in the database, then use the following syntax in a form field inserted in the template where you want the image to render at runtime:

```
<fo:instream-foreign-object content-type="image/jpg">  
<xsl:value-of select="IMAGE_ELEMENT"/>  
</fo:instream-foreign-object>
```

where

image/jpg is the MIME type of the image (other options might be: *image/gif* and *image/png*)

and

IMAGE_ELEMENT is the element name of the BLOB in the XML data.

Note that you can specify height and width attributes for the image to set its size in the published report. The image fits the box size that you define. For example, to set the size of the example above to three inches by four inches, enter the following:

```
<fo:instream-foreign-object content-type="image/jpg" height="3 in"  
width="4 in">  
<xsl:value-of select="IMAGE_ELEMENT"/>  
</fo:instream-foreign-object>
```


Specify in pixels as follows:

```
<fo:instream-foreign-object content-type="image/jpg" height="300 px"
width="4 px">
...
```

or in centimeters:

```
<fo:instream-foreign-object content-type="image/jpg" height="3 cm"
width="4 cm">
...
```

or as a percentage of the original dimensions:

```
<fo:instream-foreign-object content-type="image/jpg" height="300%"
width="300%">
...
```

Add Charts to Templates

Follow these steps to add a chart to the template.

The following list summarizes the steps to add a chart to the template. These steps are discussed in detail in this section with an example.

1. Insert a dummy image in the template to define the size and position of the chart.
2. Add the definition for the chart to the Alternative text box of the dummy image. The chart definition requires XSL commands.
3. At runtime Publisher calls the charting engine to render the image that is then inserted into the final output document.

Note that RTF output is limited to raster images. PDF and HTML output support raster and vector images.

Add a Sample Chart

Follow this illustration to add a sample chart.

Following is a piece of XML data showing total sales by company division.


```
<sales year=2004>
  <division>
    <name>Groceries</name>
    <totalsales>3810</totalsales>
    <costofsales>2100</costofsales>
  </division>
  <division>
    <name>Toys</name>
    <totalsales>2432</totalsales>
    <costofsales>1200</costofsales>
  </division>
  <division>
    <name>Cars</name>
```

```

<totalsales>6753</totalsales>
<costofsales>4100</costofsales>
</division>
<division>
  <name>Hardware</name>
  <totalsales>2543</totalsales>
  <costofsales>1400</costofsales>
</division>
<division>
  <name>Electronics</name>
  <totalsales>5965</totalsales>
  <costofsales>3560</costofsales>
</division>
</sales>

```

This example describes how to insert a chart into the template to display it as a vertical bar chart, as shown in the following bar chart.



Note the following attributes of this chart:

- The style is a vertical bar chart.
- The chart displays a background grid.
- The components are colored.
- Sales totals are shown as Y-axis labels.

- Divisions are shown as X-axis labels.
- The chart is titled.
- The chart displays a legend.

Each of these properties can be customized to suit individual report requirements.

Insert the Dummy Image


The first step is to add a dummy image to the template in the position you want the chart to appear.

The image size defines how large the chart image is in the final document.

Note:

You must insert the dummy image as a "Picture" and not any other kind of object.

The following illustration shows an example of a dummy image.




The image can be embedded inside a for-each loop like any other form field if you want the chart to be repeated in the output based on the repeating data. In this example, the chart is defined within the sales year group so that a chart is generated for each year of data present in the XML file.

Right-click the image to open the **Format Picture** palette and select the **Web** tab. Use the **Alternative text** entry box to enter the code to define the chart characteristics and data definition for the chart.

Add Code to the Alternative Text Box

An **Alternative text** box is a text field that contains code, the content of which is rendered as a chart in the final document.

The following figure shows an example of the Publisher code in the Format Picture Alternative text box.



The content of the **Alternative text** represents the chart that is rendered in the final document. For this chart, the text is as follows:

```
chart:
<Graph graphType = "BAR_VERT_CLUST">
  <Title text="Company Sales 2004" visible="true"
horizontalAlignment="CENTER"/>
  <Y1Title text="Sales in Thousands" visible="true"/>
  <O1Title text="Division" visible="true"/>
  <LocalGridData colCount="{count(//division)}" rowCount="1">
    <RowLabels>
      <Label>Total Sales $1000s</Label>
    </RowLabels>
    <ColLabels>
      <xsl:for-each select="//division">
        <Label>
          <xsl:value-of select="name"/>
        </Label>
      </xsl:for-each>
    </ColLabels>
```

```

<DataValues>
  <RowData>
    <xsl:for-each select="//division">
      <Cell>
        <xsl:value-of select="totalsales"/>
      </Cell>
    </xsl:for-each>
  </RowData>
</DataValues>
</LocalGridData>
</Graph>

```

The first element of the chart text must be the chart: element to inform the RTF parser that the following code describes a chart object.

Next is the opening <Graph> tag. Note that the whole of the code resides within the tags of the <Graph> element. This element has an attribute to define the chart type: graphType. If this attribute isn't declared, the default chart is a vertical bar chart. BI Beans supports many different chart types. Several more types are presented in this section. For a complete listing, see the BI Beans graph DTD documentation.

The following code section defines the chart type and attributes:

```

<Title text="Company Sales 2004" visible="true"
horizontalAlignment="CENTER"/>
  <Y1Title text="Sales in Thousands" visible="true"/>
  <O1Title text="Division" visible="true"/>

```

All of these values can be declared or you can substitute values from the XML data at runtime. For example, you can retrieve the chart title from an XML tag by using the following syntax:

```

<Title text="{CHARTTITLE}" visible="true" horizontalAlignment="CENTER"/>

```

where "CHARTTITLE" is the XML tag name that contains the chart title. Note that the tag name is enclosed in curly braces.

The next section defines the column and row labels:

```

<LocalGridData colCount="{count(//division)}" rowCount="1">
  <RowLabels>
    <Label>Total Sales $1000s</Label>
  </RowLabels>
  <ColLabels>
    <xsl:for-each select="//division">
      <Label>
        <xsl:value-of select="name"/>
      </Label>
    </xsl:for-each>
  </ColLabels>

```

The `LocalGridData` element has two attributes: `colCount` and `rowCount`. These define the number of columns and rows that are shown at runtime. In this example, a count function calculates the number of columns to render:

```
colCount="{count(//division)}"
```

The `rowCount` is hard-coded to 1. This value defines the number of sets of data to be charted. In this case it's 1.

Next the code defines the row and column labels. These can be declared, or a value from the XML data can be substituted at runtime. The row label is used in the chart legend (that is, "Total Sales \$1000s").

The column labels for this example are derived from the data: Groceries, Toys, Cars, and so on. This is done using a for-each loop:

```
<ColLabels>
  <xsl:for-each select="//division">
    <Label>
      <xsl:value-of select="name"/>
    </Label>
  </xsl:for-each>
</ColLabels>
```

This code loops through the `<division>` group and inserts the value of the `<name>` element into the `<Label>` tag. At runtime, this code generates the following XML:

```
<ColLabels>
  <Label>Groceries</Label>
  <Label>Toys</Label>
  <Label>Cars</Label>
  <Label>Hardware</Label>
  <Label>Electronics</Label>
</ColLabels>
```

The next section defines the actual data values to chart:

```
<DataValues>
  <RowData>
    <xsl:for-each select="//division">
      <Cell>
        <xsl:value-of select="totalsales"/>
      </Cell>
    </xsl:for-each>
  </RowData>
</DataValues>
```

Similar to the labels section, the code loops through the data to build the XML that is passed to the BI Beans rendering engine. This code generates the following XML:

```
<DataValues>
  <RowData>
    <Cell>3810</Cell>
```

```


    <Cell>2432</Cell>
    <Cell>6753</Cell>
    <Cell>2543</Cell>
    <Cell>5965</Cell>
  </RowData>
</DataValues>

```

Add Chart Samples

Follow the sample pie chart to understand how you can display the data in a pie chart.

You can also display this data in a pie chart as shown in the following figure.



The following is the code added to the template to render this chart at runtime:

```

chart:
<Graph graphType="PIE">
  <Title text="Company Sales 2004" visible="true"
    horizontalAlignment="CENTER"/>
  <LocalGridData rowCount="{count(//division)}" colCount="1">
    <RowLabels>
      <xsl:for-each select="//division">
        <Label>
          <xsl:value-of select="name"/>
        </Label>
      </xsl:for-each>
    </RowLabels>
    <DataValues>
      <xsl:for-each select="//division">

```


```

<RowData>
  <Cell>
    <xsl:value-of select="totalsales"/>
  </Cell>
</RowData>
</xsl:for-each>
</DataValues>
</LocalGridData>
</Graph>

```

Horizontal Bar Chart Sample

This example shows total sales and cost of sales charted in a horizontal bar format. This also adds the data from the cost of sales element (<costofsales>) to the chart.



The following code defines this chart in the template:

```

chart:
<Graph graphType = "BAR_HORIZ_CLUST">
  <Title text="Company Sales 2004" visible="true"
horizontalAlignment="CENTER"/>
  <LocalGridData colCount="{count(//division)}" rowCount="2">
  <RowLabels>
    <Label>Total Sales ('000s)</Label>
    <Label>Cost of Sales ('000s)</Label>
  </RowLabels>
  <ColLabels>
    <xsl:for-each select="//division">

```



```

    <Label><xsl:value-of select="name" /></Label>
  </xsl:for-each>
</ColLabels>
<DataValues>
  <RowData>
    <xsl:for-each select="//division">
      <Cell><xsl:value-of select="totalsales" /></Cell>
    </xsl:for-each>
  </RowData>
  <RowData>
    <xsl:for-each select="//division">
      <Cell><xsl:value-of select="costofsales" /></Cell>
    </xsl:for-each>
  </RowData>
</DataValues>
</LocalGridData>
</Graph>


```

To accommodate the second set of data, the `rowCount` attribute for the `LocalGridData` element is set to 2. Also note the `DataValues` section defines two sets of data: one for Total Sales and one for Cost of Sales.

Change the Appearance of the Chart

There're many attributes available from the BI Beans graph DTD that you can manipulate to change the look and feel of the chart.

For example, the previous chart can be changed to remove the grid, place a graduated background, and change the bar colors and fonts, as shown in the following figure:



The code to support this is as follows:

```
chart:
<Graph graphType = "BAR_HORIZ_CLUST">
<SeriesItems>
  <Series id="0" color="#ffcc00"/>
  <Series id="1" color="#ff6600"/>
</SeriesItems>
<O1MajorTick visible="false"/>
<X1MajorTick visible="false"/>
<Y1MajorTick visible="false"/>
<Y2MajorTick visible="false"/>
<MarkerText visible="true" markerTextPlace="MTP_CENTER"/>
<PlotArea borderTransparent="true">
  <SFX fillType="FT_GRADIENT" gradientDirection="GD_LEFT"
  gradientNumPins="300">
  <GradientPinStyle pinIndex="1" position="1"
  gradientPinLeftColor="#999999"
  gradientPinRightColor="#cc6600"/>
  </SFX>
</PlotArea>
<Title text="Company Sales 2004" visible="true">
  <GraphFont name="Tahoma" bold="false"/>
</Title>
. . .
</Graph>
```

The colors for the bars are defined in the SeriesItems section. The colors are defined in hexadecimal format as follows:

```
<SeriesItems>
  <Series id="0" color="#ffcc00"/>
  <Series id="1" color="#ff6600"/>
</SeriesItems>
```

The following code hides the chart grid:

```
<O1MajorTick visible="false"/>
  <X1MajorTick visible="false"/>
  <Y1MajorTick visible="false"/>
  <Y2MajorTick visible="false"/>
```

The MarkerText tag places the data values on the chart bars:

```
<MarkerText visible="true" markerTextPlace="MTP_CENTER"/>
```

The PlotArea section defines the background. The SFX element establishes the gradient and the borderTransparent attribute hides the plot border:

```
<PlotArea borderTransparent="true">
  <SFX fillType="FT_GRADIENT" gradientDirection="GD_LEFT"
  gradientNumPins="300">
```

```
<GradientPinStyle pinIndex="1" position="1"
  gradientPinLeftColor="#999999"
  gradientPinRightColor="#cc6600" />
</SFX>
</PlotArea>
```

The `Title` text tag has also been updated to specify a new font type and size:

```
<Title text="Company Sales 2004" visible="true">
  <GraphFont name="Tahoma" bold="false" />
</Title>
```

Add Drawings, Shapes, and Clip Art

Publisher supports Microsoft Word drawing, shape, and clip art features. You can add these objects to the template and they're rendered in the final PDF output or HTML output (not supported for other output types).

The following AutoShape categories are supported:

- Lines - Straight, arrows, connectors, curve, free form, and scribble.
- Connectors - Straight connectors only are supported. Curved connectors can be achieved by using a curved line and specifying the end styles to the line.
- Basic Shapes - All shapes are supported.
- Block arrows - All arrows are supported.
- Flowchart - All flowchart objects are supported.
- Stars and Banners - All objects are supported.
- Callouts - The "line" callouts are not supported.
- Clip Art - Add images to the templates using the Microsoft Clip Art libraries.

Add Freehand Drawings

The freehand drawing tool helps you create drawings to the final PDF.

Use the freehand drawing tool in Microsoft Word to create drawings in the template to be rendered in the final PDF output.

Add Hyperlinks


This section explains on how to add hyperlinks to shapes.

See [Insert Hyperlinks](#).

Layer Shapes

You can layer shapes on top of each other and use the transparency setting in Microsoft Word to allows shapes on lower layers to show through.

The following illustration shows an example of layered shapes.



Use 3-D Effects

Publisher doesn't support the 3-D option for shapes.

Add Microsoft Equations

Use the equation editor to generate equations in the output.


The following figure shows an example of an equation:

$$\sigma = \sqrt{\frac{1}{N} \sum_{i=1}^N \left(x_i - \bar{x} \right)^2}$$

Add Organization Charts

Use the organization chart functionality in the templates and the chart that is rendered in the output.

The following figure shows an example of an organization chart.



Add WordArt

You can use Microsoft Word's WordArt functionality in the templates.

The following figure shows a sample WordArt example.



Note:

Some Microsoft WordArt uses a bitmap operation that currently cannot be converted to SVG. To use the unsupported WordArt in the template, you can take a screenshot of the WordArt then save it as an image (gif, jpeg, or png) and replace the WordArt with the image.

Add Data-Driven Shapes

In addition to supporting the static shapes and features in the templates, Publisher supports the manipulation of shapes based on incoming data or parameters, as well.


The following manipulations are supported:

- Replicate
- Move
- Change size
- Add text
- Skew
- Rotate

These manipulations not only apply to single shapes, but you can use the group feature in Microsoft Word to combine shapes together and manipulate them as a group.

Include Manipulation Commands

Enter manipulation commands for a shape in the **Web** tab of the shape's properties dialog as shown in this figure.



Replicate Shapes

You can replicate a shape based on incoming XML data in the same way you replicate data elements in a for-each loop.

To replicate a shape, use a `for-each@shape` command in conjunction with a `shape-offset` declaration. For example, to replicate a shape down the page, use the following syntax:

```
<?for-each@shape:SHAPE_GROUP?>
  <?shape-offset-y:(position()-1)*100?>
<?end for-each?>
```

where

`for-each@shape` opens the for-each loop for the shape context

`SHAPE_GROUP` is the name of the repeating element from the XML file. For each occurrence of the element `SHAPE_GROUP` a new shape is created.

`shape-offset-y`: is the command to offset the shape along the y-axis.

`(position()-1)*100` sets the offset in pixels per occurrence. The XSL position command returns the record counter in the group (that is 1,2,3,4); one is subtracted from that number and the result is multiplied by 100. Therefore for the first occurrence the offset would be 0: $(1-1) * 100$. The offset for the second occurrence would be 100 pixels: $(2-1) * 100$. And for each subsequent occurrence the offset would be another 100 pixels down the page.

Add Text to Shapes

You can add text to a shape dynamically either from the incoming XML data or from a parameter value.

In the Property dialog enter the following syntax:

```
<?shape-text:SHAPETEXT?>
```

where SHAPETEXT is the element name in the XML data. At runtime the text is inserted into the shape.

Add Text Along a Path

You can add text along a line or curve from incoming XML data or a parameter.

After drawing the line, in the Property dialog enter:

```
<?shape-text-along-path:SHAPETEXT?>
```

where SHAPETEXT is the element from the XML data. At runtime the value of the element SHAPETEXT is inserted above and along the line.

Move a Shape

You can move a shape or transpose it along both the x and y-axes based on the XML data.

For example to move a shape 200 pixels along the y-axis and 300 along the x-axis, enter the following commands in the property dialog of the shape:

```
<?shape-offset-x:300?>  
<?shape-offset-y:200?>
```

Rotate a Shape

You can rotate a shape about a specified axis based on the incoming data.


Use the following command:

```
<?shape-rotate:ANGLE;'POSITION'?>
```

where

ANGLE is the number of degrees to rotate the shape. If the angle is positive, the rotation is clockwise; if negative, the rotation is counterclockwise.

POSITION is the point about which to carry out the rotation, for example, 'left/top'. Valid values are combinations of left, right, or center with center, top, or bottom. The default is left/top. The following illustration shows these valid values.



To rotate this rectangle shape about the bottom right corner, enter the following syntax:

```
<?shape-rotate:60,'right/bottom'?>
```

You can also specify an x,y coordinate within the shape itself about which to rotate.

Skew a Shape

You can skew a shape using the `skew` command.

You can skew a shape along its x or y axis using the following commands:

```
<?shape-skew-x:ANGLE;'POSITION'?>
<?shape-skew-y:ANGLE;'POSITION'?>
```

where

ANGLE is the number of degrees to skew the shape. If the angle is positive, the skew is to the right.

POSITION is the point about which to carry out the rotation, for example, 'left/top'. Valid values are combinations of left, right, or center with center, top, or bottom. See [Rotate a Shape](#). The default is 'left/top'.

For example, to skew a shape by 30 degrees about the bottom right hand corner, enter the following:

```
<?shape-skew-x:number(.)*30;'right/bottom'?>
```

Change the Size of Shapes

You can change the size of a shape using the appropriate commands either along a single axis or both axes.

To change a shape's size along both axes, use:

```
<?shape-size:RATIO?>
```

where `RATIO` is the numeric ratio to increase or decrease the size of the shape. Therefore a value of 2 would generate a shape twice the height and width of the original. A value of 0.5 would generate a shape half the size of the original.

To change a shape's size along the x or y axis, use:

```
<?shape-size-x:RATIO?>  
<?shape-size-y:RATIO?>
```

Changing only the x or y value has the effect of stretching or shrinking the shape along an axis. This can be data driven.


Combine Commands

You can also combine these commands to carry out multiple transformations on a shape at one time. For example, you can replicate a shape and for each replication, rotate it by some angle and change the size at the same time.

The following example shows how to replicate a shape, move it 50 pixels down the page, rotate it by five degrees about the center, stretch it along the x-axis and add the number of the shape as text:

```
<for-each@shape:SHAPE_GROUP?>  
  <?shape-text:position()?>  
  <?shape-offset-y:position()*50?>  
  <?shape-rotate:5;'center/center'?>  
  <?shape-size-x:position()+1?>  
<end for-each?>
```

These commands generate the output shown in the following shape transformation figure:



CD Ratings Example

This example demonstrates how to set up a template that generates a star-rating based on data from an incoming XML file.

Assume the following incoming XML data:

```
<CATALOG>
  <CD>
    <TITLE>Empire Burlesque</TITLE>
    <ARTIST>Bob Dylan</ARTIST>
    <COUNTRY>USA</COUNTRY>
    <COMPANY>Columbia</COMPANY>
    <PRICE>10.90</PRICE>
    <YEAR>1985</YEAR>
    <USER_RATING>4</USER_RATING>
  </CD>
  <CD>
    <TITLE>Hide Your Heart</TITLE>
    <ARTIST>Bonnie Tylor</ARTIST>
    <COUNTRY>UK</COUNTRY>
    <COMPANY>CBS Records</COMPANY>
    <PRICE>9.90</PRICE>
    <YEAR>1988</YEAR>
    <USER_RATING>3</USER_RATING>
  </CD>
  <CD>
    <TITLE>Still got the blues</TITLE>
    <ARTIST>Gary More</ARTIST>
    <COUNTRY>UK</COUNTRY>
    <COMPANY>Virgin Records</COMPANY>
    <PRICE>10.20</PRICE>
    <YEAR>1990</YEAR>
    <USER_RATING>5</USER_RATING>
  </CD>
```

```
<CD>
  <TITLE>This is US</TITLE>
  <ARTIST>Gary Lee</ARTIST>
  <COUNTRY>UK</COUNTRY>
  <COMPANY>Virgin Records</COMPANY>
  <PRICE>12.20</PRICE>
  <YEAR>1990</YEAR>
  <USER_RATING>2</USER_RATING>
</CD>
<CATALOG>
```

Notice the `USER_RATING` element for each CD. Using this data element and the shape manipulation commands, you can create a visual representation of the ratings so that the reader can compare them at a glance. A template to achieve this is shown in the following visual representation of ratings figure:

| Title | Artist | Rating |
|---------|--------|---|
| F TITLE | ARTIST | E  |

The values for the fields are shown in the following values for fields table:

| Field | Form Field Entry |
|--------------|--|
| F | <?for-each:CD?> |
| TITLE | <?TITLE?> |
| ARTIST | <?ARTIST?> |
| E | <?end for-each?> |
| (star shape) | Web Tab Entry: <?for- each@shape:xdoxslt:foreach_number(\$_XDOCTX,1,USER_RATI NG,1)?> <?shape-offset-x:(position()-1)*25?> <?end for-each?> |

The form fields hold the simple element values. The only difference with this template is the value for the star shape. The replication command is placed in the **Web** tab of the Format AutoShape dialog.

In the `for-each@shape` command you can use a command to create a "for...next loop" construct. Specify 1 as the starting number; the value of `USER_RATING` as the final number; and 1 as the step value. As the template loops through the CDs, it creates an inner loop to repeat a star shape for every `USER_RATING` value (that is, a value of 4 generates 4 stars). The output from this template and the XML sample is shown in the following figure:

| Title | Artist | Rating |
|---------------------|--------------|--------|
| Empire Burlesque | Bob Dylan | ★★★★ |
| Hide Your Heart | Bonnie Tylor | ★★★ |
| Still got the blues | Gary More | ★★★★★ |
| This is US | Gary Lee | ★★ |


Grouped Shape Example

This example shows how to combine shapes into a group and have them react to the incoming data both individually and as a group.

Assume the following XML data:

```
<SALES>
  <SALE>
    <REGION>Americas</REGION>
    <SOFTWARE>1200</SOFTWARE>
    <HARDWARE>850</HARDWARE>
    <SERVICES>2000</SERVICES>
  </SALE>
  <SALE>
    <REGION>EMEA</REGION>
    <SOFTWARE>1000</SOFTWARE>
    <HARDWARE>800</HARDWARE>
    <SERVICES>1100</SERVICES>
  </SALE>
  <SALE>
    <REGION>APAC</REGION>
    <SOFTWARE>900</SOFTWARE>
    <HARDWARE>1200</HARDWARE>
    <SERVICES>1500</SERVICES>
  </SALE>
</SALES>
```

You can create a visual representation of this data so that users can very quickly understand the sales data across all regions. Do this by first creating the composite shape in Microsoft Word that you want to manipulate. The following figure shows a composite shape comprising four components:



The shape consists of three cylinders: red, yellow, and blue. These represent the data elements software, hardware, and services. The combined object also contains a rectangle that is enabled to receive text from the incoming data.

The following commands are entered into the **Web** tab:

Red cylinder: `<?shape-size-y:SOFTWARE div 1000;'left/bottom'??>`

Yellow cylinder: `<?shape-size-y:HARDWARE div 1000;'left/bottom'??>`

Blue cylinder: `<?shape-size-y:SERVICES div 1000;'left/bottom'??>`

The shape-size command is used to stretch or shrink the cylinder based on the values of the elements SOFTWARE, HARDWARE, and SERVICES. The value is divided by 1000 to set the stretch or shrink factor. For example, if the value is 2000, divide that by 1000 to get a factor of 2. The shape generates as twice its current height.

The text-enabled rectangle contains the following command in its **Web** tab:

`<?shape-text:REGION??>`


At runtime the value of the REGION element is displayed in the rectangle.

All of these shapes were then grouped together and in the **Web** tab for the grouped object, the following syntax is added:

```
<?for-each@shape:SALE??>
<?shape-offset-x:(position()-1)*110??>
<?end for-each??>
```


In this set of commands, the `for-each@shape` loops over the SALE group. The `shape-offset` command moves the next shape in the loop to the right by a specific number of pixels. The expression `(position()-1)` sets the position of the object. The `position()` function returns a record counter while in the loop, so for the first shape, the offset would be $1-1*110$, or 0, which would place the first rendering of the object in the position defined in the template. Subsequent occurrences would be rendered at a 110 pixel offset along the x-axis (to the right).

At runtime three sets of shapes are rendered across the page, as shown in the following figure:



To make an even more visually representative report, these shapes can be superimposed onto a world map. Just use the Order dialog in Microsoft Word to layer the map behind the grouped shapes.

- Microsoft Word 2000 Users: After you add the background map and overlay the shape group, use the Grouping dialog to make the entire composition one group.
- Microsoft Word 2002/3 Users: These versions of Word have an option under Tools > Options, **General** tab to "Automatically generate drawing canvas when inserting autoshapes". Using this option removes the need to do the final grouping of the map and shapes. You can now generate a visually appealing output for the report as seen in the following figure:



Supported Formatting Features of Microsoft Word

Microsoft Word can simplify formatting output.

In addition to the features already listed, other supported features of Microsoft Word are described in the following sections:

- [General Features of Microsoft Word](#)
- [Align Objects](#)
- [Insert Tables](#)
- [Insert Date Fields](#)
- [Insert Multiple Columns on Pages](#)
- [Insert Backgrounds and Watermarks](#)
- [Microsoft Word Features That Are Not Supported](#)

General Features of Microsoft Word

The general features of Microsoft Word are large blocks of text, page breaks, page numbering, and hidden text.

- Large blocks of text
- Page breaks

(Not supported for HTML output) To insert a page break, press `Ctrl+Enter` right before the closing tag of a group. For example if you want the template to start a new page for every Supplier in the Payables Invoice Register:

1. Place the cursor just before the Supplier group's closing `<?end for-each?>` tag.
2. Press `Ctrl+Enter` to insert a page break.

At runtime each Supplier starts on a new page.

Using this Microsoft Word native feature causes a single blank page to print at the end of the report output. To avoid this single blank page, use Publisher's page break alias.

- Page numbering

Insert page numbers into the final report by using the page numbering methods of the word processor. For example, if you're using Microsoft Word:

1. From the **Insert** menu, select **Page Numbers...**
2. Select the **Position**, **Alignment**, and **Format** as desired.

At runtime the page numbers are displayed as selected.

Note that page numbering isn't supported for HTML output and has limited support in RTF output. After the RTF report is generated, press `F9` to reset the page numbers.

- Hidden text

You can format text as hidden in Microsoft Word and the hidden text is maintained in RTF output reports.

Align Objects

Use the word processor's alignment features to align text, graphics, objects, and tables. Bidirectional languages are handled automatically using the word processor's left/right alignment controls.

Note that Publisher output documents do not support right and left justification for symbol-based languages such as Chinese, Japanese, and Korean.

Insert Tables

Microsoft Word tables can be used to enhance your reports.

The following Microsoft Word features are supported in Publisher:

- Nested Tables
- Cell Alignment

You can align any object in the template using the word processor's alignment tools. This alignment is reflected in the final report output.

- Row spanning and column spanning

To span both columns and rows in the template:

1. Select the cells that you want to merge.
2. From the **Table** menu, select **Merge Cells**.
3. Align the data within the merged cell as you would normally.

At runtime the cells appear merged.

- Table Autoformatting

Publisher recognizes the table autoformats available in Microsoft Word.

To autoformat tables:

1. Select the table that you want to format.
2. From the **Table** menu, select **Autoformat**.
3. Select the desired table format.

At runtime, the table is formatted using your selection.

- Cell patterns and colors

To highlight cells or rows of a table with a pattern or color:

1. Select the cell(s) or table.
2. From the **Table** menu, select **Table Properties**.
3. From the **Table** tab, select the **Borders and Shading...** button.
4. Add borders and shading as desired.

- Repeating table headers

 **Note:**

This feature isn't supported for RTF output.

If the data is displayed in a table and you expect the table to extend across multiple pages, then you can define the header rows that you want to repeat at the start of each page.

To repeat header rows:

1. Select the row(s) that you want to repeat on each page.
 2. From the **Table** menu, select **Heading Rows Repeat**.
- Prevent rows from breaking across pages.

If you want to ensure that data within a row of a table is kept together on a page, you can set this as an option using Microsoft Word's **Table Properties**.

To keep a row's contents together on one page:

1. Select the row(s) that you want to ensure do not break across a page.
 2. From the **Table** menu, select **Table Properties**.
 3. From the **Row** tab, deselect the check box **Allow row to break across pages**.
- Fixed-width columns

To set the widths of table columns:

1. Select a column and then select **Table > Table Properties**.
2. In the Table Properties dialog, select the **Column** tab.
3. Enable the **Preferred width** checkbox and then enter the width as a **Percent** or in **Inches**.
4. Select the **Next Column** button to set the width of the next column.

Note that the total width of the columns must add up to the total width of the table.

- Text truncation

By default, if the text within a table cell doesn't fit within the cell, then the text is wrapped. To truncate the text instead, use the table properties dialog.

Note that table text truncation is supported for PDF and PPT outputs only.

To truncate the text within a table cell:

1. Place the cursor in the cell in which you want the text truncated.
2. Right-click and select **Table Properties...** from the menu, or navigate to **Table > Table Properties...**
3. From the Table Properties dialog, select the **Cell** tab, then select **Options...**
4. Deselect the **Wrap Text** check box.

An example of truncation is shown in the following figure.

| | |
|--|---------------------|
| Wrap Text checked | Wrap Text unchecked |
| The quick brown fox jumped over the lazy river. | The quick brown fox |

 **Note:**

When using multibyte characters (for example, simplified Chinese) in tables, ensure that the column widths are large enough to contain the width of the largest character plus the cell's left and right margins to avoid unexpected character display in your final output.

Insert Date Fields

Insert dates using the date feature of the word processor. Note that this date corresponds to the publishing date, not to the request run date.

Insert Multiple Columns on Pages

Publisher supports Microsoft Word's Columns function to enable you to publish the output in multiple columns on a page. (Note that this isn't supported for HTML output.)

Select **Format**, then **Columns** to display the Columns dialog to define the number of columns for the template.

To generate address labels in a two-column format:

1. Divide the page into two columns using the Columns command.
2. Define the repeatable group in the first column. Note that you define the repeatable group only in the first column, as shown in the following illustration.



F

| | |
|----------|-----------------|
| Name | CUSTOMER_NAME |
| Number | CUSTOMER_NUMBER |
| City | CITY |
| State | STATE |
| Zip Code | ZIP_CODE |

E



Tip:

To prevent the address block from breaking across pages or columns, embed the label block inside a single-celled table. Then specify in the Table Properties that the row shouldn't break across pages.

This template produces the multicolumn output that is shown in the following illustration.

| | | | |
|----------|--------------------|----------|----------------|
| Name | Nuts and Bolts Ltd | Name | Big Co |
| Number | 1220 | Number | 1221 |
| City | Espoo | City | Helsinki |
| State | FI | State | FI |
| Zip Code | llllllllllllll | Zip Code | llllllllllllll |
| Name | My Company | Name | Small Co |
| Number | 1220 | Number | 1221 |
| City | Espoo | City | Helsinki |
| State | FI | State | FI |
| Zip Code | llllllllllllll | Zip Code | llllllllllllll |

Insert Backgrounds and Watermarks

Publisher supports the *Background* feature in Microsoft Word. You can specify a single, graduated color or an image background for the template to be displayed in the PDF output.



Note:

This feature is supported for PDF output and PPT output only.

To add a background to the template, use the Format > Background menu option.

Add a Background Using Microsoft Word 2000

With the Background support feature in Microsoft Word you can select a color background and fill effects.

From the **Background** pop up menu, you can:

- Select a single color background from the color palette.
- Select **Fill Effects** to open the Fill Effects dialog.

From this dialog, select one of the following supported options:

- **Gradient:** This can be either one or two colors.

- **Texture:** Select one of the textures provided, or load your own.
- **Pattern:** Select a pattern and background/foreground colors.
- **Picture:** Load a picture to use as a background image.


Add a Text or Image Watermark Using Microsoft Word 2002 or later

These versions of Microsoft Word allow you to add either a text or image watermark. Note that the steps you take to add a watermark depend on which version of Microsoft Word you are using.

You can add the following types of watermarks to documents:

- **Picture Watermark** - Load an image and define how it should be scaled on the document.
- **Text Watermark** - Use the predefined text options or enter your own, then specify the font, size and how the text should be rendered.

The following figure shows an example of the Printed Watermark dialog completed to display a text watermark in Microsoft Word 2010:



Microsoft Word Features That Are Not Supported

Do not use soft returns in your RTF template to achieve specific text placement. Instead use hard carriage returns.

A soft return may have unexpected results in your generated output.

Template Features

Templates include several features that enhance their formatting and layout.

The template features are described in the following topics:

- [Insert Page Breaks](#)
- [Insert an Initial Page Number](#)
- [Specify Last Page Only Content](#)
- [End on Even or Odd Pages](#)
- [Skip Pages and Page Numbers](#)
- [Insert Hyperlinks](#)
- [Include a Table of Contents](#)
- [Generate Bookmarks in PDF Output](#)
- [Insert Check Boxes](#)
- [Insert Drop-Down Lists](#)
- [Repeat Row Headers After Page Break](#)

Insert Page Breaks

You can create a page break in a few ways.



Note:

Page breaks are supported for PDF, RTF, and PPT output. Page breaks are not supported for HTML output.

To create a page break after the occurrence of a specific element use the "split-by-page-break" alias. This causes the report output to insert a hard page break between every instance of a specific element.

To insert a page break between each occurrence of a group, insert the "split-by-page-break" form field within the group immediately before the `<?end for-each?>` tag that closes the group. In the Help Text of this form field enter the syntax:

```
<?split-by-page-break:??>
```

For the following XML, assume you want to create a page break for each new supplier:

```
<SUPPLIER>
  <NAME>My Supplier</NAME>
  <INVOICES>
    <INVOICE>
      <INVNUM>10001-1</INVNUM>
      <INVDATE>1-Jan-2005</INVDATE>
      <INVAMT>100</INVOICEAMT>
    </INVOICE>
    <INVOICE>
      <INVNUM>10001-2</INVNUM>
      <INVDATE>10-Jan-2005</INVDATE>
      <INVAMT>200</INVOICEAMT>
    </INVOICE>
  </INVOICES>
</SUPPLIER>
```

```

<SUPPLIER>
  <NAME>My Second Supplier</NAME>
  <INVOICES>
    <INVOICE>
      <INVNUM>10001-1</INVNUM>
      <INVDATE>11-Jan-2005</INVDATE>
      <INVAMT>150</INVOICEAMT>
    </INVOICE>
  ...

```

In the template sample shown in the following illustration, the field called PageBreak contains the split-by-page-break syntax:

FE
Supplier: Supplier 1

| Invoice Number | Invoice Date | Amount | Running Total |
|----------------|--------------|--------|---------------|
| FE10001-1 | 1-Jan-2005 | 100.00 | 100.00EFE |

PageBreak EFE

Place the PageBreak field with the `<?split-by-page-break:?>` syntax immediately before the `<?end for-each?>` field. The PageBreak field sits inside the end of the SUPPLIER loop. This ensures that a page break is inserted before the occurrence of each new supplier. This method avoids the ejection of an extra page at the end of the group when using the native Microsoft Word page break after the group.

An Excel output generated using a direct FO file created by analytics or by using an RTF template can have page breaks (`break-before="page"`) in the rows of nested tables. This enables you to export an analysis report with sections to an Excel file. For example, in a dashboard page with sections, if you have set the **Insert Page Break** section property to **Outermost Column**, when you export the dashboard page to an Excel file, the Excel file stores information of each section in separate tab.

Insert an Initial Page Number

Some reports require that the initial page number be set at a specified number. For example, monthly reports may be required to continue numbering from month to month. Publisher allows you to set the page number in the template to support this requirement.

Note:

Initial page number is supported for PDF and PPT output, but not for HTML or RTF output.

Use the following syntax in the template to set the initial page number:

```
<?initial-page-number:pagenumber?>
```

where *pagenumber* is the XML element or parameter that holds the numeric value.

Publisher also supports continuing the page number from a previous section. The default behavior of a new section in a document is to reset the page numbering. However, if the report requires that the page numbering continue into the next section, use the following command:

```
<?initial-page-number:'auto'?>
```

This command allows the continuation of the page numbering from the previous section.

Example 1 - Set page number from XML data element

If the XML data contains an element to carry the initial page number, for example:

```
<REPORT>  
  <PAGESTART>200<\PAGESTART>  
  . . . .  
</REPORT>
```

Enter the following in the template:

```
<?initial-page-number:PAGESTART?>
```

The initial page number is the value of the PAGESTART element, which in this case is 200.

Example 2 - Set page number by passing a parameter value

If you define a parameter called PAGESTART, then you can pass the initial value by calling the parameter.

Enter the following in the template:

```
<?initial-page-number:$PAGESTART?>
```



Note:

You must first declare the parameter in the template. See [Set Parameters](#).

Specify Last Page Only Content

Publisher supports the Microsoft Word functionality to specify a different page layout for the first page, odd pages, and even pages.



Note:

This feature is supported for PDF and PPT output only.

To implement these options, simply select **Page Setup** from the **File** menu, then select the **Layout** tab. Publisher recognizes the settings that you make in this dialog.

However, Microsoft Word doesn't provide settings for a different last page only. This is useful for documents such as checks, invoices, or purchase orders on which you may want the content such as the check or the summary in a specific place only on the last page. Publisher provides this ability.

To specify last page only content:

1. Create a section break in the template to ensure the content of the final page is separated from the rest of the report.
2. Insert the following syntax on the final page:

```
<?start@last-page:body?>
<?end body?>
```

Any content on the page that occurs above or below these two tags is displayed only on the last page of the report. Also, note that because this command explicitly specifies the content of the final page, any desired headers or footers previously defined for the report must be reinserted on the last page.

This example uses the last page only feature for a report that generates an invoice listing with a summary to appear at the bottom of the last page.

Assume the following XML:

```
<?xml version="1.0" encoding="WINDOWS-1252"?>
<INVOICELIST>
  <VENDOR>
    <VENDOR_NAME>Nuts and Bolts Limited</VENDOR_NAME>
    <ADDRESS>1 El Camino Real, Redwood City, CA 94065</ADDRESS>
    <INVOICE>
      <INV_TYPE>Standard</INV_TYPE>
      <INVOICE_NUM>981110</INVOICE_NUM>
      <INVOICE_DATE>10-NOV-04</INVOICE_DATE>
      <INVOICE_CURRENCY_CODE>EUR</INVOICE_CURRENCY_CODE>
      <ENT_AMT>122</ENT_AMT>
      <ACCTD_AMT>122</ACCTD_AMT>
      <VAT_CODE>VAT22%</VAT_CODE>
    </INVOICE>
    <INVOICE>
      <INV_TYPE>Standard</INV_TYPE>
      <INVOICE_NUM>100000</INVOICE_NUM>
      <INVOICE_DATE>28-MAY-04</INVOICE_DATE>
      <INVOICE_CURRENCY_CODE>FIM</INVOICE_CURRENCY_CODE>
      <ENT_AMT>122</ENT_AMT>
      <ACCTD_AMT>20.33</ACCTD_AMT>
      <VAT_CODE>VAT22%</VAT_CODE>
    </INVOICE>
  </VENDOR>
  <VENDOR>
    ...
  <INVOICE>
    ...
  </INVOICE>
```



```

</VENDOR>
<SUMMARY>
  <SUM_ENT_AMT>61435</SUM_ENT_AMT>
  <SUM_ACCTD_AMT>58264.68</SUM_ACCTD_AMT>
  <TAX_CODE>EU22%</TAX_CODE>
</SUMMARY>
</INVOICELIST>

```

The report should show each VENDOR and their INVOICE data with a SUMMARY section that appears only on the last page, placed at the bottom of the page. The template for this is shown in this figure.

F
 Vendor: **VENDOR_NAME**
 Address: **ADDRESS**

| Invoice Type | Invoice Num | Invoice Date | Invoice Currency | Entered Amount | Accounted Amount |
|------------------|-------------|--------------|------------------|----------------|------------------|
| F Invoice | 120000 | 01-Jan-2006 | USD | 100 | 100 E |

E

<<insert section break>

Insert a Microsoft Word section break (type: next page) on the first page of the template. For the final page, insert new line characters to position the summary table at the bottom of the page. The summary table is shown in the following illustration.

Last Page Placeholder

Tax Summary

| Tax Code | Entered Amount | Accounted Amount |
|-------------------|----------------|------------------|
| F VAT 18.5 | 100 | 100 E |

In this example:

- The F and E components contain the for-each grouping statements.
- The grayed report fields are placeholders for the XML elements.
- The "Last Page Placeholder" field contains the syntax:

```
<?start@last-page:body?> <?end body?>
```

to declare the last page layout. Any content above or below this statement is displayed on the last page only. The content above the statement is regarded as the header and the content below the statement is regarded as the footer.

If the reports contains headers and footers that you want to carry over onto the last page, you must reinsert them on the last page.

You must insert a section break (type: next page) into the document to specify the last page layout. This example is available in the samples folder of the Publisher Template Builder for Word installation.

Because the default behavior of a new section in a document is to reset the page numbering the page number on the last page is reset. To continue the page numbering from the previous section, use the following command:

```
<?initial-page-number:'auto'?>
```

This command allows the continuation of the page numbering from the previous section.

If the report is only one page in length, the first page layout is used. If the report requires that a single page report should default to the last page layout (such as in a check printing implementation), then you can use the following alternate syntax for the "Last Page Placeholder" on the last page:

```
<?start@last-page-first:body?> <?end body?>
```

Substituting this syntax results in the last page layout for reports that are only one page long.

End on Even or Odd Pages

If the report has different odd and even page layouts, then you might want to force the report to end specifically on an odd or even page by following these steps.

Note:

This feature is supported for PDF and PDF output, but not for RTF or HTML output.

For example, you may include the terms and conditions of a purchase order in the footer of the report using the different odd/even footer functionality and you want to ensure that the terms and conditions are printed on the final page.

Or, you may have binding requirements to have the report end on an even page, without specific layout.

To end on an even page with layout:

- Insert the following syntax in a form field in the template:

```
<?section:force-page-count;'end-on-even-layout'?>
```

To end on an odd page layout:

- Insert the following syntax in a form field in the template:

```
<?section:force-page-count;'end-on-odd-layout'??>
```

If you do not have layout requirements for the final page, but would like a blank page ejected to force the page count to the preferred odd or even, then use the following syntax:

```
<?section:force-page-count;'end-on-even'??>
```

or

```
<?section:force-page-count;'end-on-odd'??>
```

Skip Pages and Page Numbers

You can skip pages and page numbers in the first page, even pages, or odd pages of the report.

The `fo:page-sequence` object is used as a container for page output elements. The `xdofo:blank-on` attribute of `fo:page-sequence` can specify whether to:

- Leave the first page, even pages, or odd pages blank.
- Skip the page numbers in the first page, even pages, or odd pages.

If you specify to skip the page count, the page number counter isn't displayed when the page renders. The internal page number counter increments irrespective of the setting.

| Attribute Name | Values | Default |
|-----------------------------|--|---------|
| <code>xdofo:blank-on</code> | <ul style="list-style-type: none"> • none • even • odd • first • even-skip-page-count • odd-skip-page-count • first-skip-page-count | none |

The tags for RTF Template are:

```
<?section:xdofo:blank-on;'even'??>
<?section:xdofo:blank-on;'odd'??>
<?section:xdofo:blank-on;'first'??>
<?section:xdofo:blank-on;'even-skip-page-count'??>
<?section:xdofo:blank-on;'odd-skip-page-count'??>
<?section:xdofo:blank-on;'first-skip-page-count'??>
```

Examples

To leave the odd pages blank in a report, specify the following code in a form field at the beginning of the template:

```
<?section:xdofoblank-on;'odd'?'>
```

To skip the page count on the even pages of an order report, specify the following code in a form field at the beginning of the template:

```
<?section:xdofoblank-on;'even-skip-page-count'?'>
```

Insert Hyperlinks

Publisher supports several different types of hyperlinks.

Note:

Hyperlinks are supported for PDF, RTF, HTML, PPT, and Excel output.


The hyperlinks can be fixed or dynamic and can link to either internal or external destinations. Hyperlinks can also be added to shapes.

- To insert static hyperlinks to either text or a shape, use the word processor's insert hyperlink feature.

To insert a static hyperlink to a text or a shape:

- Select the text or shape.
- Use the right-mouse menu to select **Hyperlink**; or, select **Hyperlink** from the **Insert** menu.
- Enter the URL using any of the methods provided on the Insert Hyperlink dialog box.

The following illustration shows the insertion of a static hyperlink using Microsoft Word's Insert Hyperlink dialog.



- If the input XML data includes an element that contains a hyperlink or part of one, then you can create dynamic hyperlinks at runtime. In the **Type the file or Web page name** field of the Insert Hyperlink dialog, enter the following syntax:

```
{URL_LINK}
```

where *URL_LINK* is the incoming data element name.


If you have a fixed URL that you want to add elements from the XML data file to construct the URL, enter the following syntax:

```
http://www.example.com?product={PRODUCT_NAME}
```

where *PRODUCT_NAME* is the incoming data element name.

In both these cases, at runtime the dynamic URL is constructed.

The following illustration shows the insertion of a dynamic hyperlink using Microsoft Word's Insert Hyperlink dialog. The data element *SUPPLIER_URL* from the incoming XML file contains the hyperlink that is inserted into the report at runtime.



- You can also pass parameters at runtime to construct a dynamic URL. Enter the parameter and element names surrounded by braces to build up the URL as follows:

```
{$SERVER_URL}{$REPORT}/cstid={CUSTOMER_ID}
```

where *SERVER_URL* and *REPORT* are parameters passed to the template at runtime (note the \$ sign) and *CUSTOMER_ID* is an XML data element. This link may render as:

```
http://myserver.domain:8888/CustomerReport/cstid=1234
```

To add the target attribute to a URL, add the following to the URL string:

```
??target=_target_value
```

For example:

```
http://www.example.com??target=_top
```

Values for the target attribute are:

- `_top`
- `_blank`
- `_self`
- `_parent`
- `framename`

You can pass in the value of target dynamically, using the following syntax:

```
http://www.example.com/index.html??target={$myTarget}
```

where *myTarget* is the name of the parameter that holds the value.

Insert Internal Links

Internal links point to a section within a document.

Insert internal links into the template using Microsoft Word's Bookmark feature.

1. Position the cursor in the desired destination in the document.
2. From the **Insert** menu, select **Bookmark**.
3. In the Bookmark dialog, enter a name for this bookmark, and select **Add**.
4. Select the text or shape in the document that you want to link back to the Bookmark target.
5. Use the right-mouse menu to select **Hyperlink**; or select **Hyperlink** from the **Insert** menu.
6. On the Insert Hyperlink dialog, select **Bookmark**.
7. Select the bookmark that you created from the list.

At runtime, the link is maintained in the generated report.

Include a Table of Contents

Publisher supports the table of contents generation feature of the RTF specification. Follow the word processor's procedures for inserting a table of contents.

Note:

Table of contents feature is supported for PDF and PPT output. RTF support is limited: After report generation, the user must press F9 to reset the page numbers.

Publisher also provides the ability to create dynamic section headings in the document from the XML data. You can then incorporate these into a table of contents.

To create dynamic headings:

1. Enter a placeholder for the heading in the body of the document, and format it as a "Heading", using the word processor's style feature. You cannot use form fields for this functionality.

For example, you want the report to display a heading for each company reported. The XML data element tag name is <COMPANY_NAME>. In the template, enter <?COMPANY_NAME??> where you want the heading to appear. Now format the text as a Heading.

2. Create a table of contents using the word processor's table of contents feature.

At runtime, the TOC placeholders and heading text are substituted.

Generate Bookmarks in PDF Output

If you define a table of contents in the RTF template, then you can use the table of contents definition to generate links in the **Bookmarks** tab in the navigation pane of the output PDF.

The bookmarks can be either static or dynamically generated.

Note:

Bookmark support in RTF templates is limited to a single-point bookmark. This is to allow link (Goto) functionality within the document. Arrays in bookmarks are not supported.

- To create links for a static table of contents:

Enter the syntax:

```
<?copy-to-bookmark:??>
```

directly above the table of contents and

```
<?end copy-to-bookmark:??>
```

directly below the table of contents.

- To create links for a dynamic table of contents:

Enter the syntax:

```
<?convert-to-bookmark:??>
```

directly above the table of contents and

```
<?end convert-to-bookmark:??>
```

directly below the table of contents.

To control the initial state of the bookmark when the PDF file is opened, use the following command:

```
<?collapse-bookmark:state;level?>
```

where

the state can have the following values:

- hide - Collapses the table of contents entries
- show - Expands the table of contents entries

and

level sets the table of contents collapse level. For example: "1" collapses the first level of entries in the table of contents; "2" collapses the first and second level entries.

Use this command with `<?copy-to-bookmark:??>` and `<?convert-to-bookmark:??>` as shown in the following examples:

- To create a static table of contents that hides level 1 and level 2 of the table of contents entries, enter the following:

```
<?copy-to-bookmark:??>  
<?collapse-bookmark:hide;2?>
```

directly above the table of contents and

```
<?end copy-to-bookmark:??>
```

directly below the table of contents.

- To create links for a dynamic table of contents that shows levels 1 and 2 of the table of contents expanded, enter the following:

```
<?convert-to-bookmark:>  
<?collapse-bookmark:show;2?>
```

directly above the table of contents and

```
<?end convert-to-bookmark:??>
```

directly below the table of contents.

Insert Check Boxes


You can include a check box in the template that you can define to display as checked or unchecked based on a value from the incoming data.

 **Note:**

Check boxes are supported in PDF output only.

To define a check box in the template:

1. Position the cursor in the template where you want the check box to display, and select the **Check Box Form Field** from the **Forms** tool bar, as shown in the following figure:




2. Right-click the field to open the Check Box Form Field Options dialog.
3. Specify the **Default value** as either Checked or Not Checked.
4. In the Form Field Help Text dialog, enter the criteria for how the box should behave. This must be a boolean expression (that is, one that returns a true or false result).

For example, suppose the XML data contains an element called <population>. You want the check box to appear checked if the value of <population> is greater than 10,000. Enter the following in the help text field:

```
<?population>10000?>
```

The help text coding is shown in the following figure:



Note that you do not have to construct an "if" statement. The expression is treated as an "if" statement.

Insert Drop-Down Lists

Publisher allows you to use the drop-down form field to create a cross-reference in the template from the XML data to some other value that you define in the drop-down form field.

For example, suppose you've the following XML:

```
<countries>
<country>
  <name>Chad</name>
  <population>7360000</population>
  <continentIndex>5</continentIndex>
</country>
<country>
  <name>China</name>
  <population>1265530000</population>
  <continentIndex>1</continentIndex>
</country>
<country>
  <name>Chile</name>
  <population>14677000</population>
  <continentIndex>3</continentIndex>
</country>
```

```


. . .
</countries>

```

Notice that each `<country>` entry has a `<continentindex>` entry, which is a numeric value to represent the continent. Using the drop-down form field, you can create an index in the template that cross-references the `<continentindex>` value to the actual continent name. You can then display the name in the published report.

To create the index for the continent example:

1. Position the cursor in the template where you want the value from the drop-down list to display, and select the **Drop-Down Form Field** from the **Forms** tool bar, as shown in the figure below:




2. Right-click the field to display the Drop-Down Form Field Options dialog.
3. Add each value to the **Drop-down item** field and the click **Add** to add it to the **Items in drop-down list** group. The values are indexed starting from one for the first, and so on. For example, the list of continents is stored as:
 - 1 - Asia
 - 2 - North America
 - 2 - South America
 - 4 - Europe
 - 5 - Africa
 - 6 - Australia
4. Now use the Help Text box to enter the XML element name that holds the index for the drop-down field values.

For this example, enter

```
<?continentIndex?>
```

The following figure shows the Drop-Down Form Field Options dialogs for this example:



Using the check box and drop-down list features, you can create a report to display population data with check boxes to demonstrate figures that reach a certain limit. An example illustrating a report of population data with check boxes is shown in the following figure:

| Country | Population | more than 10M? | Continent |
|---------------|---------------|-------------------------------------|---------------|
| Chad | 7,360,000 | <input type="checkbox"/> | Africa |
| China | 1,265,530,000 | <input checked="" type="checkbox"/> | Asia |
| Chile | 14,677,000 | <input checked="" type="checkbox"/> | South America |
| Sweden | 8,887,000 | <input type="checkbox"/> | Europe |
| United States | 270,312,000 | <input checked="" type="checkbox"/> | North America |
| New Zealand | 3,625,000 | <input type="checkbox"/> | Australia |

The template to create this report is shown in the below figure and the fields have the values shown in the table below.

| Country | Population | more than 10M? | Continent |
|----------|------------|--------------------------|-----------|
| FE China | 1,000,000 | <input type="checkbox"/> | Asia EFE |

Description of the fields for drop-down list:

- FE - Form field entry: `<?for-each:country?>` - Begins the country repeating group.
- China - Form field entry: `<?name?>` - Placeholder for the name element.
- 1,000,000 - Form field entry: `<?population?>` - Placeholder for the population element.
- (check box) - Form field entry: `<?population>1000000?>` - Establishes the condition for the check box. If the value for the population element is greater than 1,000,000, the check box is displayed as checked.
- Asia - Form field entry: `<?continentIndex?>` - The drop-down form field for the continentIndex element. See the preceding description for its contents. At runtime,

the value of the XML element is replaced with the value it's cross-referenced to in the drop-down form field.

- EFE - Form field entry: `<?end for-each?>` - Ends the country group.

Repeat Row Headers After Page Break

If your report includes a row header that spans multiple rows, for example in a group-left construction, you can specify that the content in the initial cell repeats on the next page.

See the example shown in the following table.

| Date | Invoice | Amount |
|-----------|----------|-----------|
| 02-DEC-12 | 234 | 53.35 |
| 04-DEC-12 | 10020402 | 146776.07 |
| | 10020403 | 172482.45 |
| | 10020404 | 147740.25 |
| | 10020405 | 71577.42 |
| | 10020406 | 89344.81 |
| | 10020407 | 223563.03 |
| | 10020408 | 176353.55 |
| 05-DEC-12 | 10020487 | 112902.54 |
| 06-DEC-12 | 502444 | 19125 |
| | 502445 | 12375 |

In the preceding example, if the report breaks across the 04-Dec-12 group, you would most likely prefer that the cell contents "04-Dec-12" repeat on the next page. To specify that the cell contents repeat, insert the following code in a form field in the table data cell that is to repeat:

```
<?attribute@block:xdofo:rowspancell-repeat-nextpage;'true'?>
```

This feature is only useful when number-rows-spanned for the table-cell is greater than one.

Use Conditional Formatting

Conditional formatting occurs when a formatting element appears only when a certain condition is met.

Note:

For information about using the Template Builder to insert conditional regions and conditional formatting, see [Insert and Edit Conditional Regions](#) and [Insert Conditional Formatting](#).

Publisher supports the usage of simple "if" statements, as well as more complex "choose" expressions.

The conditional formatting that you specify can be XSL or XSL:FO code, or you can specify actual RTF objects such as a table or data. For example, you can specify that if reported numbers reach a certain threshold, they're displayed shaded in red. Or, you can use this feature to hide table columns or rows depending on the incoming XML data.

This section covers the following topics of conditional formatting:

- [Use If Statements](#)
- [Use If Statements in Boilerplate Text](#)
- [Use If-Then-Else Statements](#)
- [Insert Choose Statements](#)
- [Format Columns](#)
- [Format Rows](#)
- [Highlight Cells](#)

Use If Statements

Use an if statement to define a simple condition; for example, if a data field is a specific value.

To use an if statement:

1. Insert the following syntax to designate the beginning of the conditional area.

```
<?if:condition?>
```

2. Insert the following syntax at the end of the conditional area: `<?end if?>`.

For example, to set up the Payables Invoice Register to display invoices only when the Supplier name is "Company A", insert the syntax `<?if:VENDOR_NAME='COMPANY A'?>` before the Supplier field on the template.

Enter the `<?end if?>` tag after the invoices table.

This example is displayed in the following illustration. Note that you can insert the syntax in form fields, or directly into the template.

```

Group: Suppliers
<?if:VENDOR_NAME='Company A'?>
Supplier: Supplier 1

| Invoice Num            | Invoice Date |
|------------------------|--------------|
| Group:Invoices 1234566 | 1-Jan-2004   |


<?end if?>
End:Suppliers

```

Use If Statements in Boilerplate Text

You can use "if" statements to change messages presented to users.

Assume that you want to incorporate an "if" statement into the following free-form text:

The program was (not) successful.

You want the "not" to display only if the value of an XML tag called <SUCCESS> equals "N".

To achieve this requirement, use the Publisher context command to place the if statement into the inline sequence rather than into the block (the default placement).

See [Control the Placement of Instructions Using the Context Commands](#).

For example, if you construct the code as follows:

```
The program was <?if:SUCCESS='N'?>not<?end if?> successful.
```

The following undesirable result occurs:

```
The program was
not
successful.
```

Because Publisher applies the instructions to the block by default. To specify that the if statement should be inserted into the inline sequence, enter the following:

```
The program was <?if@inlines:SUCCESS='N'?>not<?end if?>
successful.
```

This construction results in the following display:

```
The program was successful.
```

```
If SUCCESS doesn't equal 'N';
```

```
or
```

```
The program was not successful.
```

```
If SUCCESS equals 'N'.
```

 **Note:**

If you use `@inlines` with `if` syntax, any other `if` syntax inside the statement must use the context command `@inline`. If you use `@inlines` with `FOR-EACH` syntax any other `if` or `FOR-EACH` syntax inside the statement must use the context command `@inline`.

Use If-Then-Else Statements

Publisher supports the common programming construct "if-then-else".

"if-then-else" is extremely useful when you must test a condition and conditionally show a result. For example:

```
IF X=0 THEN
  Y=2
ELSE
  Y=3
END IF
```

You can also nest these statements as follows:

```
IF X=0 THEN
  Y=2
ELSE
  IF X=1 THEN
    Y=10
  ELSE Y=100
END IF
```

Use the following syntax to construct an if-then-else statement in the RTF template:

```
<?xdofx:if element_condition then result1 else result2 end if?>
```


For example, the following statement tests the AMOUNT element value. If the value is greater than 1000, show the word "Higher"; if it's less than 1000, show the word "Lower"; if it's equal to 1000, show "Equal":

```
<?xdofx:if AMOUNT > 1000 then 'Higher'  
  else  
    if AMOUNT < 1000 then 'Lower'  
    else  
      'Equal'  
    end if?  
end if?>
```

Insert Choose Statements

Use the choose, when, and otherwise elements to express multiple conditional tests. If certain conditions are met in the incoming XML data, then specific sections of the template are rendered. This is a very powerful feature of the RTF template. In regular XSL programming, if a condition is met in the choose command then further XSL code is executed. In the template, however, you can actually use visual widgets in the conditional flow (in the following example, a table).

Use the following syntax for these elements:

```
<?choose:??>  
  
<?when:expression?>  
  
<?otherwise?>
```

Conditional Formatting Example

This example shows a choose expression in which the display of a row of data depends on the value of the fields EXEMPT_FLAG and POSTED_FLAG. When the EXEMPT_FLAG equals "^", the row of data renders light gray. When POSTED_FLAG equals "*" the row of data renders shaded dark gray. Otherwise, the row of data renders with no shading.

In the following figure, the form field default text is displayed. The form field help text entries are shown in the following table:

| | | | | | |
|-----------------------|--|--|--------------|--|-------------------------------------|
| Column Legend: | <table border="1"> <tr> <td style="background-color: #cccccc;"></td> <td>'Not Posted'</td> </tr> <tr> <td style="background-color: #808080;"></td> <td>'Reduces Available Exemption Limit'</td> </tr> </table> | | 'Not Posted' | | 'Reduces Available Exemption Limit' |
| | 'Not Posted' | | | | |
| | 'Reduces Available Exemption Limit' | | | | |

| Tax Code | Taxable Recoverable | Taxable Non-Recoverable | Recoverable Tax | Tax Non-Recoverable | Total |
|---------------------------------------|---------------------|-------------------------|-----------------|---------------------|-------|
| <code><Grp:VAT</code> | | | | | |
| <code><Choose</code> | | | | | |
| <code><When EXEMPT_FLAG='^'</code> | | | | | |
| VAT 15% | 1000 | 1000 | 1000 | 1000 | 1000 |
| <code>End When></code> | | | | | |
| <code><When POSTED_FLAG='*'</code> | | | | | |
| VAT 15% | 1000 | 1000 | 1000 | 1000 | 1000 |
| <code>End When></code> | | | | | |
| <code>Otherwise</code> | | | | | |
| VAT 15% | 1000 | 1000 | 1000 | 1000 | 1000 |
| <code>End Otherwise></code> | | | | | |
| <code>End Choose></code> | | | | | |
| <code>End VAT></code> | | | | | |

| Default Text Entry in Example Form Field | Help Text Entry in Form Field |
|--|--|
| <code><Grp:VAT</code> | <code><?for-each:G_VAT?></code> starts the G_VAT group |
| <code><Choose</code> | <code><?choose:?></code> opens the choose statement |
| <code><When EXEMPT_FLAG='^'</code> | <code><?when: EXEMPT_FLAG='^'?></code> tests the EXEMPT_FLAG element, if true, use the first table shown |
| <code>End When></code> | <code><?end when?></code> ends the EXEMPT_FLAG test |
| <code><When POSTED_FLAG='*'</code> | <code><?when:POSTED_FLAG='*'?></code> tests the POSTED_FLAG element, if true, use the table following |
| <code>End When></code> | <code><?end when?></code> ends the POSTED_FLAG test |
| <code>Otherwise</code> | <code><?otherwise:?></code> If none of above are true then use the following table |
| <code>End Otherwise></code> | <code><?end otherwise?></code> ends the otherwise statement |
| <code>End Choose></code> | <code><?end choose?></code> ends the choose statement |
| <code>End Vat></code> | <code><?end for-each?></code> ends the G_VAT group |

Format Columns

You can conditionally show and hide columns of data in the document output. This example demonstrates how to set up a table so that a column is only displayed based on the value of an element attribute.

This example shows a report of a price list, represented by the following XML:

```
<items type="PUBLIC"> <! - can be marked 'PRIVATE' - >
  <item>
    <name>Plasma TV</name>
    <quantity>10</quantity>
    <price>4000</price>
  </item>
```

```
<item>
  <name>DVD Player</name>
  <quantity>3</quantity>
  <price>300</price>
</item>
<item>
  <name>VCR</name>
  <quantity>20</quantity>
  <price>200</price>
</item>
<item>
  <name>Receiver</name>
  <quantity>22</quantity>
  <price>350</price>
</item>
</items>
```

Notice the "type" attribute associated with the items element. In this XML it's marked as "PUBLIC" meaning the list is a public list rather than a PRIVATE list. For the public version of the list, the quantity column shouldn't be shown in the output, but you want to develop only one template for both versions based on the list type.

The following figure contains a simple template that conditionally shows or hides the quantity column.

| Name | IFQuantityend-if | Price |
|-------------------|------------------|-----------------|
| grp:ItemPlasma TV | IF 20 end-if | 1,000.00end grp |

The following table shows the entries made in the template that is shown in the above figure:

| Default Text | Form Field Entry | Description |
|--------------|--|--|
| grp:Item | <?for-each:item?> | Holds the opening for-each loop for the item element. |
| Plasma TV | <?name?> | The placeholder for the name element from the XML file. |
| IF | <?if@column:/items/ @type="PRIVATE"?> | The opening of the if statement to test for the attribute value PRIVATE in the column header. Note that this syntax uses an XPath expression to navigate back to the items level of the XML to test the attribute. For more information about using XPath in templates, see Use XPath Commands . |
| Quantity | N/A | Boilerplate heading |
| end-if | <?end if?> | Ends the if statement. |
| IF | <?if@cell:/items/ @type="PRIVATE"?> | The opening of the if statement to test for the attribute value PRIVATE in the column data. |
| 20 | <?quantity?> | The placeholder for the quantity element. |

| Default Text | Form Field Entry | Description |
|--------------|------------------|--|
| end-if | <?end if?> | Ends the if statement. |
| 1,000.00 | <?price?> | The placeholder for the price element. |
| end grp | <?end for-each?> | Closing tag of the for-each loop. |

The conditional column syntax is the "if" statement syntax with the addition of the @column clause. It's the @column clause that instructs Publisher to hide or show the column based on the outcome of the if statement.

If you did not include the @column the data would not display in the report as a result of the if statement, but the column still would because you had drawn it in the template.

Note:

The @column clause is an example of a context command. For more information, see [Control the Placement of Instructions Using the Context Commands](#).

The example renders the output that is shown in the following figure:

| Name | Price |
|------------|----------|
| Plasma TV | 4,000.00 |
| DVD Player | 300.00 |
| VCR | 200.00 |
| Receiver | 350.00 |

If the same XML data contained the type attribute set to PRIVATE, then the output that is shown in the below figure is rendered from the same template.

| Name | Quantity | Price |
|------------|----------|----------|
| Plasma TV | 10 | 4,000.00 |
| DVD Player | 3 | 300.00 |
| VCR | 20 | 200.00 |
| Receiver | 22 | 350.00 |

Format Rows

Publisher allows you to specify formatting conditions as the row-level of a table.

Examples of row-level formatting are:

- Highlighting a row when the data meets a certain threshold.

- Alternating background colors of rows to ease readability of reports.
- Showing only rows that meet a specific condition.

Conditionally Display a Row

To display only rows that meet a certain condition, insert the `<?if:condition?>` `<?end if?>` tags at the beginning and end of the row, within the for-each tags for the group. These tags are demonstrated in the sample template that is shown in the following figure:

| Industry | Year | Month | Sales |
|--|------|-------|--|
| <code>for-each SALE if big</code> INDUSTRY | YEAR | MONTH | SALES <code>end if</code> <code>end SALE</code> |

The following table describes the fields from the template in the above figure:

| Default Text Entry | Form Field Help Text | Description |
|--------------------|---|--|
| for-each SALE | <code><?for-each:SALE?></code> | Opens the for-each loop to repeat the data belonging to the SALE group. |
| if big | <code><?if:SALES>5000?></code> | If statement to display the row only if the element SALES has a value greater than 5000. |
| INDUSTRY | <code><?INDUSTRY?></code> | Data field |
| YEAR | <code><?YEAR?></code> | Data field |
| MONTH | <code><?MONTH?></code> | Data field |
| SALES end if | <code><?end if?></code> | Closes the if statement. |
| end SALE | <code><?end for-each?></code> | Closes the SALE loop. |

Conditionally Highlight a Row

This example demonstrates how to set a background color on every other row. The template to create this effect is shown in the following figure:

| Industry | Year | Month | Sales |
|---|------|-------|-----------------------------|
| <code>for-each SALE format;</code> INDUSTRY | YEAR | MONTH | SALES <code>end SALE</code> |

The following table shows values of the form fields from the template in the above figure:

| Default Text Entry | Form Field Help Text | Description |
|--------------------|---|--|
| for-each SALE | <?for-each:SALE?> | Defines the opening of the for-each loop for the SALE group. |
| format; | <?if@row:position() mod 2=0?> <xsl:attribute name="background-color" xdofo:ctx="incontext">lightgray</xsl:attribute><?end if?> | For each alternate row, the background color attribute is set to gray for the row. |
| INDUSTRY | <?INDUSTRY?> | Data field |
| YEAR | <?YEAR?> | Data field |
| MONTH | <?MONTH?> | Data field |
| SALES | <?SALES?> | Data field |
| end SALE | <?end for-each?> | Closes the SALE for-each loop. |

In the above table, note the format; field. It contains an if statement with a "row" context (@row). This sets the context of the if statement to apply to the current row. If the condition is true, then the <xsl:attribute> for the background color of the row is set to light gray. This setting results in the output that is shown in the following figure:

| Industry | Year | Month | Sales |
|------------|------|-------|---------|
| Oil | 2000 | Jan | 100,000 |
| Automotive | 2000 | Jan | 200,000 |
| Groceries | 2000 | Jan | 50,000 |

See [Control the Placement of Instructions Using the Context Commands](#).

Highlight Cells

This example demonstrates how to conditionally highlight a cell based on a value in the XML file.

This example uses the following XML code:

```
<accounts>
  <account>
    <number>1-100-3333</number>
    <debit>100</debit>
    <credit>300</credit>
  </account>
  <account>
    <number>1-101-3533</number>
    <debit>220</debit>
    <credit>30</credit>
  </account>
  <account>
    <number>1-130-3343</number>
    <debit>240</debit>
```

```

    <credit>1100</credit>
  </account>
</account>
  <number>1-153-3033</number>
  <debit>3000</debit>
  <credit>300</credit>
</account>
</accounts>

```

The template lists the accounts and their credit and debit values. The final report will highlight in red any cell whose value is greater than 1000. The template for this is shown in the following figure:

| Account | Debit | Credit |
|-----------------------|------------|----------------|
| FE:Account 1-232-4444 | CH1 100.00 | CH2 100.00 EFE |

The field definitions for the template are shown in the following table:

| Default Text Entry | Form Field Entry | Description |
|--------------------|--|--|
| FE:Account | <?for-each:account?> | Opens the for each-loop for the element account. |
| 1-232-4444 | <?number?> | The placeholder for the number element from the XML file. |
| CH1 | <?if:debit>1000? ><xsl:attribute xdofo:ctx="block" name="background-color">red</ xsl:attribute><?end if?> | This field holds the code to highlight the cell red if the debit amount is greater than 1000. |
| 100.00 | <?debit?> | The placeholder for the debit element. |
| CH2 | <?if:credit>1000? ><xsl:attribute xdofo:ctx="block" name="background-color">red</ xsl:attribute><?end if?> | This field holds the code to highlight the cell red if the credit amount is greater than 1000. |
| 100.00 | <?credit?> | The placeholder for the credit element. |
| EFE | <?end for-each?> | Closes the for-each loop. |

! Important:

The <?debit?> element must reside in its own field.

The code to highlight the debit column as shown in the table is:

```

<?if:debit>1000?>
  <xsl:attribute
    xdofo:ctx="block" name="background-color">red

```

```
</xsl:attribute>
<?end if?>
```

The "if" statement tests whether the debit value is greater than 1000, and if so the next lines are invoked. Notice that the example embeds native XSL code inside the if statement.

The "attribute" element allows you to modify properties in the XSL.

The xdofo:ctx component is an Publisher feature that allows you to adjust XSL attributes at any level in the template. In this case, the background color attribute is changed to red.

To change the color attribute, you can use either the standard HTML names (for example, red, white, green) or you can use the hexadecimal color definition (for example, #FFFFFF).

This template results in the output that is shown in the following figure:

| Account | Debit | Credit |
|------------|---------|---------|
| 1-100-3333 | 100.00 | 300.00 |
| 1-101-3533 | 220.00 | 30.00 |
| 1-130-3343 | 240.00 | 1100.00 |
| 1-153-3033 | 3000.00 | 300.00 |

Insert Page-Level Calculations

Learn more about the supported page-level calculations for PDFs and PPTs.

Publisher supports the page-level calculations that are described in the following sections for PDF and PPT outputs only:

- [Display Page Totals](#)
- [Insert Brought Forward and Carried Forward Totals](#)
- [Insert Running Totals](#)

Display Page Totals

Publisher allows you to display calculated page totals in the report. Because the page isn't created until publishing time, the totaling function must be executed by the formatting engine.

Note:

Page totaling is performed in the PDF-formatting layer. Therefore this feature isn't available for other outputs types: HTML, RTF, Excel. This page totaling function works only if the source XML code has raw numeric values. The numbers shouldn't be preformatted.

Because the page total field doesn't exist in the XML input data, you must define a variable to hold the value. When you define the variable, you associate it with the element from the XML file that is to be totaled for the page. Once you define total fields, you can also perform additional functions on the data in those fields.

To declare the variable that is to hold the page total, insert the following syntax immediately following the placeholder for the element being totaled:

```
<?add-page-total:TotalFieldName;'element'??>
```

where

TotalFieldName is the name you assign to the total (to reference later) and

'element' is the XML element field to be totaled.

You can add this syntax to as many fields as you want to total.

Then when you want to display the total field, enter the following syntax:

```
<?show-page-total:TotalFieldName;'Oracle-number-format' number-  
separators="{$_XDONFSEPARATORS}"??>
```

where

TotalFieldName is the name you assigned to give the page total field above and

Oracle-number-format is the format you want to use to for the display, using the Oracle format mask (for example: 'C9G999D00'). For the list of Oracle format mask symbols, see [Oracle Abstract Format Masks](#).

number-separators="{\$_XDONFSEPARATORS}" is a required attribute to apply the grouping separator and decimal separator for the format mask you defined.

The following example shows how to set up page total fields in a template to display total credits and debits that have displayed on the page, and then calculate the net of the two fields.

This example uses the following XML code:

```
<balance_sheet>  
  <transaction>  
    <debit>100</debit>  
    <credit>90</credit>  
  </transaction>  
  <transaction>  
    <debit>110</debit>  
    <credit>80</credit>  
  </transaction>  
  ...  
</balance_sheet>
```

The following figure shows the table to insert in the template to hold the values:

| Debit | Credit |
|-----------|---------------|
| FE 100.00 | 90.00 Net EFE |

The following table shows the form field entries made in the template whose table is shown in the previous figure:

| Default Text Entry | Form Field Help Text Entry | Description |
|--------------------|---|---|
| FE | <?for-each:transaction?> | This field defines the opening "for-each" loop for the transaction group. |
| 100.00 | <?debit?><?add-page-total:dt;'debit'?> | This field is the placeholder for the debit element from the XML file. To total this field by page, the page total declaration syntax is added. The variable defined to hold the total for the debit element is dt. |
| 90.00 | <?credit?> <?add-page-total:ct;'credit'?> | This field is the placeholder for the credit element from the XML file. To total this field by page, the page total declaration syntax is added. The variable defined to hold the total for the credit element is ct. |
| Net | <add-page-total:net;'debit - credit'?> | Creates a net page total by subtracting the credit values from the debit values. |
| EFE | <?end for-each?> | Closes the for-each loop. |

Note that on the variable defined as "net" you perform a calculation on the values of the credit and debit elements.

Now that you've declared the page total fields, you can insert a field in the template where you want the page totals to appear. Reference the calculated variables using the names you supplied (in the example, ct and dt). The syntax to display the page totals is as follows:

For example, to display the debit page total, enter the following:

```
<?show-page-total:dt;'C9G990D00';'(C9G990D00)' number-separators="{$_XDONFSEPARATORS}"?>
```

Therefore to complete the example, place the following at the bottom of the template page, or in the footer:

```
Page Total Debit: <?show-page-total:dt;'C9G990D00';'(C9G990D00)' number-separators="{$_XDONFSEPARATORS}"?>
```

```
Page Total Credit: <?show-page-total:ct;'C9G990D00';'(C9G990D00)' number-separators="{$_XDONFSEPARATORS}"?>
```

```
Page Total Balance: <?show-page-total:net;'C9G990D00';'(C9G990D00)' number-separators="{$_XDONFSEPARATORS}"?>
```

The output for this report is shown in the following figure:

| | Debit | Credit |
|--|--------|--------|
| | 100.00 | 90.00 |
| | 110.00 | 80.00 |
| | 120.00 | 70.00 |
| | 130.00 | 60.00 |
| | 140.00 | 50.00 |
| | 150.00 | 40.00 |

Page 1
 Page Total Debit: 750.00
 Page Total Credit: 390.00
 Page Total Balance: 360.00

Insert Brought Forward and Carried Forward Totals

Many reports require that a page total be maintained throughout the report output and be displayed at the beginning and end of each page. These totals are known as "brought forward and carried forward" totals.



Note:

The totaling for the brought forward and carried forward fields is performed in the PDF-formatting layer. Therefore this feature isn't available for other outputs types such as HTML, RTF, or Excel.

An example of a report with forward totals is displayed in the following figure:

| Page 1 | | | Page 2 Brought Forward: 300 | | | Page 3 Brought Forward: 600 | | |
|----------------------|----------|--------|--------------------------------|----------|--------|--------------------------------|----------|--------|
| Inv | Date | Amount | Inv | Date | Amount | Inv | Date | Amount |
| 1001 | 1-Jan-05 | 100 | 1004 | 1-Jan-05 | 100 | 1007 | 1-Jan-05 | 100 |
| 1002 | 1-Jan-05 | 100 | 1005 | 1-Jan-05 | 100 | 1008 | 1-Jan-05 | 100 |
| 1003 | 1-Jan-05 | 100 | 1006 | 1-Jan-05 | 100 | 1009 | 1-Jan-05 | 100 |
| Carried Forward: 300 | | | Carried Forward: 600 | | | | | |

At the end of the first page, the page total for the Amount element is displayed as the **Carried Forward** total. At the top of the second page, this value is displayed as the **Brought Forward** total from the previous page. At the bottom of the second page, the brought forward value plus the total for that page is calculated and displayed as the new **Carried Forward** value, and this continues throughout the report.

This functionality is an extension of the [Display Page Totals](#) feature. The following example walks through the syntax and setup required to display the brought forward and carried forward totals in the published report.

Assume that you've the following XML code:

```
<?xml version="1.0" encoding="WINDOWS-1252"?>
<INVOICES>
  <INVOICE>
    <INVNUM>10001-1</INVNUM>
    <INVDATE>1-Jan-2005</INVDATE>
    <INVAMT>100</INVOICEAMT>
  </INVOICE>
  <INVOICE>
    <INVNUM>10001-2</INVNUM>
    <INVDATE>10-Jan-2005</INVDATE>
    <INVAMT>200</INVOICEAMT>
  </INVOICE>
  <INVOICE>
    <INVNUM>10001-1</INVNUM>
    <INVDATE>11-Jan-2005</INVDATE>
    <INVAMT>150</INVOICEAMT>
  </INVOICE>
  . . .
</INVOICES>
```

The sample template that is shown in the following figure creates the invoice table and declares a placeholder that holds the page total.

Init PTs

| Invoice | Date | Amount |
|-----------|-------------|--------------------|
| FE 132342 | 10-May-2005 | 1,000.00 InvAmt EG |

End PTs

The following table shows the fields in the template that is shown in the above figure.

| Field | Form Field Help Text Entry | Description |
|------------|-------------------------------------|---|
| Init PTs | <?init-page-total: InvAmt?> | Declares InvAmt as the placeholder that holds the page total. |
| FE | <?for-each: INVOICE?> | Begins the INVOICE group. |
| 10001-1 | <?INVNUM?> | Placeholder for the Invoice Number tag. |
| 1-Jan-2005 | <?INVDATE?> | Placeholder for the Invoice Date tag. |
| 100.00 | <?INVAMT?> | Placeholder for the Invoice Amount tag. |
| InvAmt | <?add-page-total: InvAmt ; INVAMT?> | Assigns the "InvAmt" page total object to the INVAMT element in the data. |
| EFE | <?end for-each?> | Closes the INVOICE group. |
| End PTs | <?end-page-total: InvAmt?> | Closes the "InvAmt" page total. |

To display the brought forward total at the top of each page (except the first), use the following syntax:

```
<xdofo:inline-total
  display-condition="exceptfirst"
  name="InvAmt">
  Brought Forward:
<xdofo:show-brought-forward
  name="InvAmt"
  format="99G999G999D00" number-separators="{$_XDONFSEPARATORS}"/>/>
</xdofo:inline-total>
```

The following list describes the elements that comprise the brought forward syntax:

- **inline-total** - This element has two properties:
 - name - Specifies the name of the variable you declared for the field.
 - display-condition - Sets the display condition. This is an optional property that takes one of the following values:
 - * first - Contents are displayed only on the first page.
 - * last - Contents are displayed only on the last page.
 - * exceptfirst - Contents are displayed on all pages except first.
 - * exceptlast - Contents are displayed on all pages except last.
 - * everytime - (Default) Contents are displayed on every page.

In this example, display-condition is set to "exceptfirst" to prevent the value from appearing on the first page where the value would be zero.
- **Brought Forward:** - This string is optional and is displayed as the field name on the report.
- **show-brought-forward** - Shows the value on the page. It has the following properties:
 - name - The name of the field to show. In this case, InvAmt. This property is mandatory.
 - format - The Oracle number format to apply to the value at runtime. This property is optional, but if you want to supply a format mask, you must use the Oracle format mask. See [Oracle Abstract Format Masks](#).
 - number-separators="{\$_XDONFSEPARATORS}" - This attribute is required to apply the grouping separator and number separator for the format mask you defined.

Insert the brought forward object at the top of the template where you want the brought forward total to display. If you place it in the body of the template, then you can insert the syntax in a form field.

If you want the brought forward total to display in the header, you must insert the full code string into the header because Microsoft Word doesn't support form fields in the header or footer regions. However, you can alternatively use the start body/end body syntax, which allows you to define what the body area of the report is. Publisher recognizes any content above the defined body area as header content, and any content below as the footer. This allows you to use form fields. See [Create Multiple or Complex Headers and Footers](#) for details.

Place the carried forward object at the bottom of the template where you want the total to display. The carried forward object for our example is as follows:

```
<xdofo:inline-total
  display-condition="exceptlast"
  name="InvAmt">
  Carried Forward:
<xdofo:show-carry-forward
  name="InvAmt"
  format="99G999G999D00" number-separators="{$_XDONFSEPARATORS}"/>
</xdofo:inline-total>
```

Note the following differences with the brought-forward object:

- The display-condition is set to exceptlast so that the carried forward total is displayed on every page except the last page.
- The display string is "Carried Forward".
- The show-carry-forward element is used to show the carried forward value. It has the same properties as brought-carried-forward, described above.

You are not limited to a single value in the template, you can create multiple brought forward/carried forward objects in the template pointing to various numeric elements in the data.

Note:

Ensure that you do not include the commands `<?init-page-total:invAmnt?>` and `<?end-page-total:InvAmt?>` as shown in the preceding example. The display-condition logic computation depends on these commands to function correctly.

Insert Running Totals

The variable functionality can be used to add a running total to the invoice listing report.

See [Set Variables](#) for more information. This example assumes the following XML structure:

```
<?xml version="1.0" encoding="WINDOWS-1252"?>
<INVOICES>
  <INVOICE>
    <INVNUM>10001-1</INVNUM>
    <INVDATE>1-Jan-2005</INVDATE>
    <INVAMT>100</INVOICEAMT>
  </INVOICE>
  <INVOICE>
    <INVNUM>10001-2</INVNUM>
    <INVDATE>10-Jan-2005</INVDATE>
    <INVAMT>200</INVOICEAMT>
  </INVOICE>
```

```

<INVOICE>
  <INVNUM>10001-1</INVNUM>
  <INVDATE>11-Jan-2005</INVDATE>
  <INVAMT>150</INVOICEAMT>
</INVOICE>
</INVOICES>

```

You can use this XML code to create a report that contains running totals as shown in the following illustration.

| Invoice Number | Invoice Date | Amount | Running Total |
|----------------|--------------|--------|---------------|
| 1000-1 | 1-Jan-2005 | 100.00 | 100.00 |
| 1000-2 | 10-Jan-2005 | 200.00 | 300.00 |
| 1000-3 | 11-Jan-2005 | 150.00 | 450.00 |

To create the Running Total field, define a variable to track the total and initialize it to 0. The template is shown in the following illustration.

| RTotalVar | | | |
|----------------|--------------|--------|---------------|
| Invoice Number | Invoice Date | Amount | Running Total |
| FE10001-1 | 1-Jan-2005 | 100.00 | 100.00EFE |

The values for the form fields in the template that is shown in the previous illustration are described in the next table.

| Form Field | Syntax | Description |
|------------|---|--|
| RtotalVar | <?xdoxslt:set_variable(\$_XDOCTX, 'RTotalVar', 0)?> | Declares the "RTotalVar" variable and initializes it to 0. |
| FE | <?for-each:INVOICE?> | Starts the Invoice group. |
| 10001-1 | <?INVNUM?> | Invoice Number tag |
| 1-Jan-2005 | <?INVDATE?> | Invoice Date tag |
| 100.00 | <?xdoxslt:set_variable(\$_XDOCTX, 'RTotalVar', xdoxslt:get_variable(\$_XDOCTX, 'RTotalVar') + INVAMT)?> <?xdoxslt:get_variable(\$_XDOCTX, 'RTotalVar')?> | Sets the value of RTotalVar to the current value plus the new Invoice Amount. Retrieves the RTotalVar value for display. |
| EFE | <?end for-each?> | Ends the INVOICE group. |

Handle Data

These sections describe methods for handling data in templates.

- [Sort Data](#)
- [Check for Null Values](#)
- [Regroup the XML Data](#)

Sort Data

You can sort a group by any element within the group. Insert the following syntax within the group tags:

```
<?sort:element name; order; data-type?>
```

where

element name is the name of the element you want the group sorted by

order is 'ascending' or 'descending'

data-type is the element data type. Valid values are: 'text' and 'number'.

If the order isn't specified, by default, the sort order is ascending. If the data type isn't specified, the type is assumed to be text.

For example, to sort a data set by an element named SALARY so that the highest salaries appear first, enter the following:

```
<?sort:SALARY;'descending';'number'?>
```

When you are sorting within a for-each group, enter the sort statement after the for-each statement. For example, to sort the Payables Invoice Register (shown at the beginning of this chapter) by Supplier (VENDOR_NAME), enter the following:

```
<?for-each:G_VENDOR_NAME?><?sort:VENDOR_NAME?>
```

To sort a group by multiple fields, just enter additional sort statements in the appropriate order. For example, to sort by Supplier and then by Invoice Number, enter the following

```
<?sort:VENDOR_NAME?> <?sort:INVOICE_NUM;'ascending';'number'?>
```

Check for Null Values

Within the XML data there're three possible scenarios for the value of an element.

Scenarios:

- The element is present in the XML data, and it has a value.
- The element is present in the XML data, but it doesn't have a value.
- The element is missing from the XML data, and therefore there's no value.

In the report layout, you may want to specify a different behavior depending on the presence of the element and its value. The following examples show how to check for each of these conditions using an "if" statement. The syntax can also be used in other conditional formatting constructs.

- To define behavior when the element is present and the value isn't null, use the following:

<?if:element_name!='?'> *desired behavior* <?end if?>

- To define behavior when the element is present, but is null, use the following:
<?if:element_name and element_name=""> *desired behavior* <?end if?>
- To define behavior when the element is missing, use the following:
<?if:not(element_name)?> *desired behavior* <?end if?>

Regroup the XML Data

The RTF template supports the XSL 2.0 for-each-group standard that allows you to regroup XML data into hierarchies that are not present in the original data.

With this feature, the template doesn't have to follow the hierarchy of the source XML file. You are therefore no longer limited by the structure of the data source.

XML Sample

This XML sample shows a set of data that uses the for-each-group standard.

To demonstrate the for-each-group standard, the following XML data sample of a CD catalog listing is regrouped in a template:

```
<CATALOG>
  <CD>
    <TITLE>Empire Burlesque</TITLE>
    <ARTIST>Bob Dylan</ARTIST>
    <COUNTRY>USA</COUNTRY>
    <COMPANY>Columbia</COMPANY>
    <PRICE>10.90</PRICE>
    <YEAR>1985</YEAR>
  </CD>
  <CD>
    <TITLE>Hide Your Heart</TITLE>
    <ARTIST>Bonnie Tylor</ARTIST>
    <COUNTRY>UK</COUNTRY>
    <COMPANY>CBS Records</COMPANY>
    <PRICE>9.90</PRICE>
    <YEAR>1988</YEAR>
  </CD>
  <CD>
    <TITLE>Still got the blues</TITLE>
    <ARTIST>Gary More</ARTIST>
    <COUNTRY>UK</COUNTRY>
    <COMPANY>Virgin Records</COMPANY>
    <PRICE>10.20</PRICE>
    <YEAR>1990</YEAR>
  </CD>
  <CD>
    <TITLE>This is US</TITLE>
    <ARTIST>Gary Lee</ARTIST>
    <COUNTRY>UK</COUNTRY>
    <COMPANY>Virgin Records</COMPANY>
    <PRICE>12.20</PRICE>
```

```
<YEAR>1990</YEAR>
</CD>
```

Using the regrouping syntax, you can create a report of this data that groups the CDs by country and then by year. You are not limited by the data structure presented.

Regroup Syntax

You can regroup data using the proper syntax

To regroup the data, use the following syntax:

```
<?for-each-group: BASE-GROUP; GROUPING-ELEMENT?>
```

For example, to regroup the CD listing by COUNTRY, enter the following in the template:

```
<?for-each-group: CD; COUNTRY?>
```

The elements that were at the same hierarchy level as COUNTRY are now children of COUNTRY. You can then refer to the elements of the group to display the values desired.

To establish nested groupings within the already defined group, use the following syntax:

```
<?for-each:current-group(); GROUPING-ELEMENT?>
```

For example, after declaring the CD grouping by COUNTRY, you can then further group by YEAR within COUNTRY as follows:

```
<?for-each:current-group(); YEAR?>
```

At runtime, Publisher loops through the occurrences of the new groupings, displaying the fields that you defined in the template.

Note:

This syntax is a simple XSL for-each-group syntax. If you choose not to use the simplified syntax above, you can use the XSL syntax as shown below. The XSL syntax can only be used within a form field of the template.

```
<xsl:for-each-group
  select=expression
  group-by="string expression"
  group-adjacent="string expression"
  group-starting-with=pattern>
  <!--Content: (xsl:sort*, content-constructor) -->
</xsl:for-each-group>
```

Template Example

You can see some features that can be used to enhance templates in this example.

The following illustration shows a template that displays the CDs by Country, then Year, and lists the details for each CD.

```

Group by Country
Country:USA

    Group by Year
    Year:2000

        Title      Artist      Price
        Group:DetailsMy CD  John Doe  1.00End Group

    End Group by Year
End Group by Country

```

The following table shows the Publisher syntax entries made in the form fields of the template shown in the previous illustration.

| Default Text Entry | Form Field Help Text Entry | Description |
|--------------------|---|--|
| Group by Country | <?for-each-group:CD;COUNTRY?> | The <?for-each-group:CD;COUNTRY?> tag declares the new group. It regroups the existing CD group by the COUNTRY element. |
| USA | <?COUNTRY?> | Placeholder to display the data value of the COUNTRY tag. |
| Group by Year | <?for-each-group:current-group();YEAR?> | The <?for-each-group:current-group();YEAR?> tag regroups the current group (that is, COUNTRY), by the YEAR element. |
| 2000 | <?YEAR?> | Placeholder to display the data value of the YEAR tag. |
| Group:Details | <?for-each:current-group()?> | Once the data is grouped by COUNTRY and then by YEAR, the <?for-each:current-group()?> command is used to loop through the elements of the current group (that is, YEAR) and render the data values (TITLE, ARTIST, and PRICE) in the table. |
| My CD | <?TITLE?> | Placeholder to display the data value of the TITLE tag. |
| John Doe | <?ARTIST?> | Placeholder to display the data value of the ARTIST tag. |
| 1.00 | <?PRICE?> | Placeholder to display the data value of the PRICE tag. |

| Default Text Entry | Form Field Help Text Entry | Description |
|----------------------|----------------------------|---|
| End Group | <?end for-each?> | Closes out the <?for-each:current-group()?> tag. |
| End Group by Year | <?end for-each-group?> | Closes out the <?for-each-group:current-group();YEAR?> tag. |
| End Group by Country | <?end for-each-group?> | Closes out the <?for-each-group:CD;COUNTRY?> tag. |

This template produces the report that is shown in the next illustration when merged with the XML file.

| Country:USA | | |
|---------------------|--------------|-------|
| Year:1985 | | |
| Title | Artist | Price |
| Empire Burlesque | Bob Dylan | 10.90 |
| Country:UK | | |
| Year:1988 | | |
| Title | Artist | Price |
| Hide your heart | Bonnie Tylor | 9.90 |
| Year:1990 | | |
| Title | Artist | Price |
| Still got the blues | Gary More | 10.20 |
| This is US | Gary Lee | 12.20 |

Regroup by an Expression

Regrouping by an expression allows you to apply a function or command to a data element, and then group the data by the returned result.

To use this feature, state the expression within the regrouping syntax as follows:

```
<?for-each:BASE-GROUP;GROUPING-EXPRESSION?>
```

To demonstrate this feature, an XML data sample that simply contains average temperatures per month is used as input to a template that calculates the number of months having an average temperature within a certain range.

The following XML code is composed of <temp> groups. Each <temp> group contains a <month> element and a <degree> element, which contains the average temperature for that month:

```
<temps>
  <temp>
    <month>Jan</month>
    <degree>11</degree>
  </temp>
  <temp>
    <month>Feb</month>
    <degree>14</degree>
  </temp>
  <temp>
    <month>Mar</month>
    <degree>16</degree>
  </temp>
  <temp>
    <month>Apr</month>
    <degree>20</degree>
  </temp>
  <temp>
    <month>May</month>
    <degree>31</degree>
  </temp>
  <temp>
    <month>Jun</month>
    <degree>34</degree>
  </temp>
  <temp>
    <month>Jul</month>
    <degree>39</degree>
  </temp>
  <temp>
    <month>Aug</month>
    <degree>38</degree>
  </temp>
  <temp>
    <month>Sep</month>
    <degree>24</degree>
  </temp>
  <temp>
    <month>Oct</month>
    <degree>28</degree>
  </temp>
  <temp>
    <month>Nov</month>
    <degree>18</degree>
  </temp>
  <temp>
    <month>Dec</month>
    <degree>8</degree>
  </temp>
</temps>
```

You want to display this data in a format showing temperature ranges and a count of the months that have an average temperature to satisfy those ranges, as shown in the following illustration.

Annual Temperature Summary

| Range | Number of Months |
|--------------|------------------|
| 0 F to 10 F | 1 Month(s) |
| 10 F to 20 F | 4 Month(s) |
| 20 F to 30 F | 3 Month(s) |
| 30 F to 40 F | 4 Month(s) |

Using the for-each-group command you can apply an expression to the <degree> element that enables you to group the temperatures by increments of 10 degrees. You can then display a count of the members of each grouping, which is the number of months having an average temperature that falls within each range.

The next illustration shows the template to create the report that is shown in the previous illustration.

Annual Temperature Summary

| Range | Number of Months |
|-----------------|---------------------------|
| Group by TmpRng | Months Month(s)End TmpRng |
| Range | |

The next table shows the form field entries made in the template that is shown in the previous illustration.

| Default Text Entry | Form Field Help Text Entry |
|--------------------|---|
| Group by TmpRng | <?for-each-group:temp;floor(degree div 10)?> > <?sort:floor(degree div 10)?> |
| Range | <?concat(floor(degree div 10)*10,' F to ',floor(degree div 10)*10+10, 'F')?> |
| Months | <?count(current-group())?> |
| End TmpRng | <?end for-each-group?> |

Note the following about the form field tags:

- The <?for-each-group:temp;floor(degree div 10)?> is the regrouping tag. It specifies that for the existing <temp> group, the elements are to be regrouped by the expression, floor(degree div 10). The floor function is an XSL function that returns the highest integer that's less than the argument (for example, 1.2 returns 1, 0.8 returns 0).

In this case, it returns the value of the <degree> element, which is then divided by 10. This generates the following values from the XML data: 1, 1, 1, 2, 3, 3, 3, 3, 2, 2, 1, and 0.

These are sorted, so that when processed, the following four groups are created: 0, 1, 2, and 3.

- The `<?concat(floor(degree div 10)*10,'F to ', floor(degree div 10)*10+10, 'F'?)>` displays the temperature ranges in the row header in increments of 10. The expression concatenates the value of the current group times 10 with the value of the current group times 10 plus 10.

Therefore, for the first group, 0, the row heading displays 0 to (0 +10), or "0 F to 10 F".

- The `<?count(current-group())?>` uses the count function to count the members of the current group (the number of temperatures that satisfy the range).
- The `<?end for-each-group?>` tag closes out the grouping.

Set Variables, Parameters, and Properties

Learn more about setting variables, parameters, and properties.

This section covers the following topics:

- [Set Variables](#)
- [Set Parameters](#)
- [Set Properties](#)

Set Variables

Updatable variables differ from standard XSL variables `<xsl:variable>` in that they're updatable during the template application to the XML data.

This allows you to create many new features in the templates that require updatable variables.

The variables use a "set and get" approach for assigning, updating, and retrieving values.

Use the following syntax to declare/set a variable value:

```
<?xdoxslt:set_variable($_XDOCTX, 'variable name', value)?>
```

Use the following syntax to retrieve a variable value:

```
<?xdoxslt:get_variable($_XDOCTX, 'variable name')?>
```

You can use this method to perform calculations. For example:

```
<?xdoxslt:set_variable($_XDOCTX, 'x', xdoxslt:get_variable($_XDOCTX, 'x' + 1)?>
```

This sets the value of variable 'x' to its original value plus 1, much like using "x = x + 1".

The `$_XDOCTX` specifies the global document context for the variables. In a multi-threaded environment there may be many transformations occurring at the same time, therefore the variable must be assigned to a single transformation.

See [Insert Running Totals](#) for an example of the usage of updatable variables.

Set Parameters

You can pass runtime parameter values into the template.

Parameters can be referenced throughout the template to support many functions. For example, you can filter data in the template, use a value in a conditional formatting block, or pass property values (such as security settings) into the final document.

All name-value parameter pairs are passed to the template. You must register the parameters that you want to utilize in the template using the syntax described below.

To use a parameter in a template:

1. Declare the parameter in the template.

Use the following syntax to declare the parameter:

```
<?param@begin:parameter_name;parameter_value?>
```

where

parameter_name is the name of the parameter

parameter_value is the default value for the parameter (the *parameter_value* is optional)

`param@begin`: is a required string to push the parameter declaration to the top of the template at runtime so that it can be referred to globally in the template.

The syntax must be declared in the Help Text field of a form field. The form field can be placed anywhere in the template.

2. Refer to the parameter in the template by prefixing the name with a "\$" character. For example, if you declare the parameter name to be "InvThresh", then reference the value using "\$InvThresh".
3. If you are not using BI Publisher Enterprise, but only the core libraries:

At runtime, pass the parameter to the BI Publisher engine programmatically.

Prior to calling the FOPProcessor API create a Properties class and assign a property to it for the parameter value as follows:

```
Properties prop = new Properties();  
prop.put("xslt.InvThresh", "1000");
```

Example 13-1 Example: Pass an invoice threshold parameter

This example illustrates how to declare a parameter in the template that filters the data based on the value of the parameter.

The following XML sample lists invoice data:

```
<INVOICES>
  <INVOICE>
    <INVOICE_NUM>981110</INVOICE_NUM>
    <AMOUNT>1100</AMOUNT>
  </INVOICE>
  <INVOICE>
    <INVOICE_NUM>981111</INVOICE_NUM>
    <AMOUNT>250</AMOUNT>
  </INVOICE>
  <INVOICE>
    <INVOICE_NUM>981112</INVOICE_NUM>
    <AMOUNT>8343</AMOUNT>
  </INVOICE>
  . . .
</INVOICES>
```

The following illustration shows a template that accepts a parameter value to limit the invoices displayed in the final document based on the parameter value.

InvThresh Declaration

| Invoice Number | Invoice Amount |
|----------------|-----------------|
| FE IF 13222-2 | \$100.00 EI EFE |

Fields for defining parameters as shown in the template in the previous illustration:

- InvThreshDeclaration - Form Field Help Text Entry: `<?param@begin:InvThresh?>` - Declares the parameter InvThresh.
- FE - Form Field Help Text Entry: `<?for-each:INVOICE?>` - Begins the repeating group for the INVOICE element.
- IF - Form Field Help Text Entry: `<?if:AMOUNT>$InvThresh?>` - Tests the value of the AMOUNT element to determine if it's greater than the value of InvThresh.
- 13222-2 - Form Field Help Text Entry: `<?INVOICE_NUM?>` - Placeholder for the INVOICE_NUM element.
- \$100.00 - Form Field Help Text Entry: `<?AMOUNT?>` - Placeholder for the AMOUNT element.
- EI - Form Field Help Text Entry: `<?end if?>` - Closing tag for the if statement.
- EFE - Form Field Help Text Entry: `<?end for-each?>` - Closing tag for the for-each loop.

In this template, only INVOICE elements with an AMOUNT greater than the InvThresh parameter value are displayed. If you pass in a parameter value of 1,000, then the report that is shown in the following illustration is produced.

| Invoice Number | Invoice Amount |
|----------------|----------------|
| 981110 | 1100 |
| 981112 | 8343 |

Notice the second invoice doesn't display because its amount was less than the parameter value.

Set Properties

The properties in the configuration file can alternatively be embedded into the RTF template.

The properties set in the template are resolved at runtime. You can either hard code the values in the template or embed the values in the incoming XML data. Embedding the properties in the template avoids the use of the configuration file.

For example, if you use a nonstandard font in the template, then rather than specify the font location in the configuration file, you can embed the font property inside the template. If you must secure the generated PDF output, then you can use the PDF security properties and obtain the password value from the incoming XML data.

To add a property to a template, use the Microsoft Word Properties dialog (available from the **File** menu), and enter the following information:

- **Name** - Enter the property name prefixed with "xdo-"
- **Type** - Select "Text"
- **Value** - Enter the property value. To reference an element from the incoming XML data, enter the path to the XML element enclosed by curly braces. For example: `{/root/password}`

Embed a Font Reference

For this example, suppose you want to use a font in the template called "XMLPScript". This font isn't available on the server; therefore you must define where to find the font at runtime by setting the "font" property. Assume the font is located in "/tmp/fonts", then you would enter the following in the Properties dialog:

- **Name** - xdo-font.XMLPScript.normal.normal
- **Type** - Text
- **Value** - truetype./tmp/fonts/XMLPScript.ttf

When the template is applied to the XML data on the server, the font is looked up in the /tmp/fonts directory. Note that if the template is deployed in multiple locations, then you must ensure that the path is valid for each location.

Secure a PDF Output

For this example, suppose you want to use a password from the XML data to secure the PDF output document. The XML data is as follows:

```
<PO>
  <security>true</security>
  <password>welcome</password>
  <PO_DETAILS>
  ..
</PO>
```

In the Properties dialog set two properties: pdf-security to set the security feature as enabled or not, and pdf-open-password to set the password. Enter the following in the Properties dialog:

- **Name:** xdo-pdf-security
- **Type:** Text
- **Value:** {/PO/security}
- **Name:** xdo-pdf-open-password
- **Type:** Text
- **Value:** {/PO/password}

Storing the password in the XML data isn't recommended if the XML persists in the system for any length of time. To avoid this potential security risk, you can use a template parameter value that's generated and passed into the template at runtime.

For example, you could set up the following parameters:

- PDFSec - To pass the value for the xdo-pdf-security property
- PDFPWD - To pass the value for the password

You would then enter the following in the Properties dialog:

- **Name** - xdo-pdf-security
- **Type** - Text
- **Value** - {\$PDFSec}
- **Name** - xdo-pdf-open-password
- **Type** - Text
- **Value** - {\$PDFPWD}

To set the template parameters, see [Set Parameters](#).

Use Advanced Report Layouts

Learn more about Advanced Report Layouts.

This section describes the following tasks for advanced report layouts:

- [Create Batch Reports](#)

- [Handle No Data Found Conditions](#)
- [Insert Pivot Tables](#)
- [Construct Dynamic Data Columns](#)

Create Batch Reports

It's a common requirement to print a batch of documents, such as invoices or purchase orders in a single PDF file. Because these documents are intended for different customers, each document requires that the page numbering be reset and that page totals are specific to the document. If the header and footer display fields from the data (such as customer name), then these must be reset as well.

Publisher supports this requirement through the use of a context command. This command allows you to define elements of the report to a specific section. When the section changes, these elements are reset.

The following example demonstrates how to reset the header and footer and page numbering within an output file:

The following XML code is a report that contains multiple invoices:

```
...
<LIST_G_INVOICE>
  <G_INVOICE>
    <BILL_CUST_NAME>Vision, Inc. </BILL_CUST_NAME>
    <TRX_NUMBER>2345678</TRX_NUMBER>
    ...
  </G_INVOICE>
  <G_INVOICE>
    <BILL_CUST_NAME>Oracle, Inc. </BILL_CUST_NAME>
    <TRX_NUMBER>2345685</TRX_NUMBER>
    ...
  </G_INVOICE>
  ...
</LIST_G_INVOICE>
...
```

Each G_INVOICE element contains an invoice for a potentially different customer. To instruct Publisher to start a new section for each occurrence of the G_INVOICE element, add the @section command to the opening for-each statement for the group, using the following syntax:

```
<?for-each@section:group_name?>
```

where *group_name* is the name of the element for which you want to begin a new section.

For example, the for-each grouping statement for this example is as follows:

```
<?for-each@section:G_INVOICE?>
```

The closing <?end for-each?> tag is not changed.

The following figure shows a sample template for batch reports:



Note:

The G_INVOICE group for-each declaration is still within the body of the report, even though the headers are reset by the command.

```

Invoice# <?TRX_NUMBER?>

for-each G_INVOICE
INVOICE
BILL_CUST_NAME
BILL_ADDRESS1
BILL_ADDRESS2
BILL_CITY, BILL_STATE BILL_POSTAL_CODE
end G_INVOICE

```

The following table describes the values of the form fields from the template in the previous figure (that shows a sample template for batch reports):

| Default Text Entry | Form Field Help Text | Description |
|--------------------|--------------------------------|---|
| for-each G_INVOICE | <?for-each@section:G_INVOICE?> | Begins the G_INVOICE group, and defines the element as a Section. For each occurrence of G_INVOICE, a new section is started. |
| <?TRX_NUMBER? > | N/A | Microsoft Word doesn't support form fields in the header, therefore the placeholder syntax for the TRX_NUMBER element is placed directly in the template. |
| end G_INVOICE | <?end for-each?> | Closes the G_INVOICE group. |

Now for each new occurrence of the G_INVOICE element, a new section begins. The page numbers restart, and if header or footer information is derived from the data, it's reset as well.

Handle No Data Found Conditions

When you use @section with the Publisher commands for-each or for-each-group (for example: <?for-each@section:ELEMENT_NAME?>), and the input data file has no data, then an empty or invalid PDF output document may be generated for that for-each loop. To prevent this from happening, edit the RTF template.

To handle no data found conditions:

1. At the end of the RTF template, add a section break.

2. On the last page (the new section page), add the command `<?if@section:not(ELEMENT_NAME)?>No Data Found<?end if?>`

where `ELEMENT_NAME` is the same data element that you are using in the `for-each@section` loop.

Now if no data exists for `ELEMENT_NAME`, a valid PDF is generated with the text "No Data Found".

Insert Pivot Tables

The columns of a pivot table are data dependent.

At design time you do not know how many columns are reported, or what the appropriate column headings are. Moreover, if the columns should break onto a second page, you must be able to define the row label columns to repeat onto subsequent pages. The following example shows how to design a simple pivot table report that supports these features. See [Insert a Pivot Table](#).

This example uses the following XML sample:

```
<ROWSET>
  <RESULTS>
    <INDUSTRY>Motor Vehicle Dealers</INDUSTRY>
    <YEAR>2005</YEAR>
    <QUARTER>Q1</QUARTER>
    <SALES>1000</SALES>
  </RESULTS>
  <RESULTS>
    <INDUSTRY>Motor Vehicle Dealers</INDUSTRY>
    <YEAR>2005</YEAR>
    <QUARTER>Q2</QUARTER>
    <SALES>2000</SALES>
  </RESULTS>
  <RESULTS>
    <INDUSTRY>Motor Vehicle Dealers</INDUSTRY>
    <YEAR>2004</YEAR>
    <QUARTER>Q1</QUARTER>
    <SALES>3000</SALES>
  </RESULTS>
  <RESULTS>
    <INDUSTRY>Motor Vehicle Dealers</INDUSTRY>
    <YEAR>2004</YEAR>
    <QUARTER>Q2</QUARTER>
    <SALES>3000</SALES>
  </RESULTS>
  <RESULTS>
    <INDUSTRY>Motor Vehicle Dealers</INDUSTRY>
    <YEAR>2003</YEAR>
    ...
  </RESULTS>
  <RESULTS>
    <INDUSTRY>Home Furnishings</INDUSTRY>
    ...
  </RESULTS>
</RESULTS>
```

```

        <INDUSTRY>Electronics</INDUSTRY>
        ...
    </RESULTS>
    <RESULTS>
        <INDUSTRY>Food and Beverage</INDUSTRY>
        ...
    </RESULTS>

</ROWSET>

```

From this XML code, a report is generated that shows each industry and totals the sales by year as shown in the following illustration.

| Industry | 2005 | 2004 | 2003 |
|-----------------------|------|------|------|
| Motor Vehicle Dealers | 3000 | 6000 | 1200 |
| Home Furnishings | 3200 | 7770 | 3300 |
| Electronics | 9000 | 9000 | 4300 |
| Food and Beverage | 1200 | 900 | 5600 |

The following illustration shows the template to generate the report that is shown in the previous illustration.

| | |
|-------------------------------|----------------------------|
| Industry header column | for: YEAR end |
| for: INDUSTRY | for: sum(SALES) end end |

The form fields in the template that is shown in the previous illustration have the values that are described in the following table.

| Default Text Entry | Form Field Help Text | Description |
|--------------------|--|--|
| header column | <?horizontal-break-table:1?> | Defines the first column as a header that should repeat if the table breaks across pages. See Define Columns to Repeat Across Pages . |
| for: | <?for-each-group@column:RESULTS;YEAR?> | Uses the regrouping syntax (see Regroup the XML Data) to group the data by YEAR; and the @column context command to create a table column for each group (YEAR). See Control the Placement of Instructions Using the Context Commands . |
| YEAR | <?YEAR?> | Placeholder for the YEAR element. |

| Default Text Entry | Form Field Help Text | Description |
|--------------------|--|---|
| end | <?end for-each-group?> | Closes the for-each-group loop. |
| for: | <?for-each-group:RESULTS;INDUSTRY?> | Begins the group to create a table row for each INDUSTRY. |
| INDUSTRY | <?INDUSTRY?> | Placeholder for the INDUSTRY element. |
| for: | <?for-each-group@cell:current-group();YEAR?> | Uses the regrouping syntax (see Regroup the XML Data) to group the data by YEAR; and the @cell context command to create a table cell for each group (YEAR). |
| sum(Sales) | <?sum(current-group()//SALES)?> | Sums the sales for the current group (YEAR). |
| end | <?end for-each-group?> | Closes the for-each-group statement. |
| end | <?end for-each-group?> | Closes the for-each-group statement. |

Note that only the first row uses the @column context to determine the number of columns for the table. All remaining rows must use the @cell context to create the table cells for the column. See [Control the Placement of Instructions Using the Context Commands](#).

Construct Dynamic Data Columns

The ability to construct dynamic data columns is a very powerful feature of the RTF template. Using this feature you can design a template that correctly renders a table when the number of columns that is required by the data is variable.

For example, you are designing a template to display columns of test scores within specific ranges. However, you do not how many ranges have data to report. You can define a dynamic data column to split into the correct number of columns at runtime.

Use the following tags to accommodate the dynamic formatting required to render the data correctly:

- Dynamic Column Header

```
<?split-column-header:group element name?>
```

Use this tag to define which group to split for the column headers of a table.

- Dynamic Column `<?split-column-data:group element name?>`

Use this tag to define which group to split for the column data of a table.

- Dynamic Column Width

```
<?split-column-width:name?> OR
```

```
<?split-column-width:@width?>
```

Use one of these tags to define the width of the column when the width is described in the XML data. The width can be described in two ways:

- An XML element stores the value of the width. In this case, use the syntax `<?split-column-width:name?>`, where *name* is the XML element tag name that contains the value for the width.

- If the element defined in the split-column-header tag, contains a width attribute, use the syntax `<?split-column-width:@width?>` to use the value of that attribute.
- Dynamic Column Width's unit value (in points) `<?split-column-width-unit:value?>`

Use this tag to define a multiplier for the column width. If the column widths are defined in character cells, then you must use the appropriate multiplier value to render the columns to the correct width in points. For example, if you are using 10 point courier font in the table, you would use a multiplier of 6, which is the approximate width of a character displayed in 10 point courier font. If the multiplier isn't defined, then the widths of the columns are calculated as a percentage of the total width of the table. The column width calculations are illustrated in the following table:

| Width Definition | Column 1 (Width = 10) | Column 2 (Width = 12) | Column 3 (Width = 14) |
|---------------------------------|-----------------------|-----------------------|-----------------------|
| Multiplier not present -% width | 10/10+12+14*100 28% | %Width = 33% | %Width =39% |
| Multiplier = 6 - width | 60 pts | 72 pts | 84 pts |

Define Columns to Repeat Across Pages

If the table columns expand horizontally across more than one page, you can define how many row heading columns you want to repeat on every page.

Use the following syntax to specify the number of columns to repeat:

```
<?horizontal-break-table:number?>
```

where number is the number of columns (starting from the left) to repeat.

Note:

This functionality is supported for PDF output only.

Example of Dynamic Data Columns

A template is required to display test score ranges for school exams. Logically, you want the report to be arranged as shown in the table here.

| Test Score | Test Score Range 1 | Test Score Range 2 | Test Score Range 3 | ...Test Score Range n |
|---------------|-----------------------|-----------------------|-----------------------|--------------------------|
| Test Category | # students in Range 1 | # students in Range 2 | # students in Range 3 | # of students in Range n |

However, you don't know how many Test Score Ranges are reported. The number of Test Score Range columns is dynamic, depending on the data.

The following XML data describes these test scores. The number of occurrences of the element `<TestScoreRange>` determine how many columns are required. In

this case there're five columns: 0-20, 21-40, 41-60, 61-80, and 81-100. For each column there's an amount element (<NumOfStudents>) and a column width attribute (<TestScore width="15">).

```
<?xml version="1.0" encoding="utf-8"?>
<TestScoreTable>
  <TestScores>
    <TestCategory>Mathematics</TestCategory>
    <TestScore width="15">
      <TestScoreRange>0-20</TestScoreRange>
      <NumofStudents>30</NumofStudents>
    </TestScore>
    <TestScore width="20">
      <TestScoreRange>21-40</TestScoreRange>
      <NumofStudents>45</NumofStudents>
    </TestScore>
    <TestScore width="15">
      <TestScoreRange>41-60</TestScoreRange>
      <NumofStudents>50</NumofStudents>
    </TestScore>
    <TestScore width="20">
      <TestScoreRange>61-80</TestScoreRange>
      <NumofStudents>102</NumofStudents>
    </TestScore>
    <TestScore width="15">
      <TestScoreRange>81-100</TestScoreRange>
      <NumofStudents>22</NumofStudents>
    </TestScore>
  </TestScores>
</TestScoreTable>
```

Using the dynamic column tags in form fields, set up the table in two columns as shown in the following figure. The first column, `Test Score` is static. The second column, `Column Header and Splitting` is the dynamic column. At runtime this column is split according to the data, and the header for each column is appropriately populated. The Default Text entry and Form Field Help entry for each field are listed in the following table.

| Test Score | Column Header and Splitting |
|--------------------------------|--------------------------------------|
| Group:TestScores Test Category | Content and Splitting end:TestScores |

| Default Text Entry | Form Field Help Text Entry |
|-----------------------------|---|
| Group:TestScores | <?for-each:TestScores?> |
| Test Category | <?TestCategory?> |
| Column Header and Splitting | <?split-column-header:TestScore?> <?split-column-width:@width?> <?TestScoreRange?>% |
| Content and Splitting | <?split-column-data:TestScore?> <?NumofStudents?> |

| Default Text Entry | Form Field Help Text Entry |
|--------------------|----------------------------|
| end:TestScores | <?end for-each?> |

- `Test Score` is the boilerplate column heading.
- `Test Category` is the placeholder for the `<TestCategory>` data element, that is, Mathematics, which is also the row heading.
- The second column is the one to be split dynamically. The width you specify is divided by the number of columns of data. In this case, there're 5 data columns.
- The second column contains the dynamic range data. The width of the column is divided according to the split column width. Because this example doesn't contain the unit value tag (`<?split-column-width-unit:value?>`), the column is split on a percentage basis. Wrapping of the data occurs if required.

If the tag (`<?split-column-width-unit:value?>`) were present, then the columns have a specific width in points. If the total column widths were wider than the allotted space on the page, then the table breaks onto another page.

The `horizontal-break-table` tag could then be used to specify how many columns to repeat on the subsequent page. For example, a value of 1 would repeat the column `Test Score` on the subsequent page, with the continuation of the columns that didn't fit on the first page.

The template renders the output that is shown in the following figure:

| Test Score | 0-20 | 21-40 | 41-60 | 61-80 | 81-100 |
|-------------|------|-------|-------|-------|--------|
| Mathematics | 30 | 45 | 50 | 102 | 22 |

Format Numbers, Dates, and Currencies

This section provides details for formatting numbers, dates, and currencies.

It contains the following topics:

- [Format Numbers](#)
- [Format Dates](#)
- [Format Currencies](#)

Format Numbers

Publisher supports two methods for specifying the number format.

- Oracle's format-number function (recommended).
- Microsoft Word's Native number format mask.

 **Note:**

You can also use the native XSL format-number function to format numbers. For information, see [Format Native XSL Numbers](#).

Use only one of these methods. If the number format mask is specified using both methods, then the data is formatted twice, causing unexpected behavior.

The group separator and the number separator are set at runtime based on the template locale. If you are working in a locale other than en-US, or the templates require translation, use the Oracle format masks.

Data Source Requirements

To use the Oracle format mask or the Microsoft format mask, the numbers in the data source must be in a raw format, with no formatting applied (for example: 1000.00). If the number has been formatted for European countries (for example: 1.000,00) then the format won't work.

The Publisher parser requires the Java BigDecimal string representation. This consists of an optional sign ("-") followed by a sequence of zero or more decimal digits (the integer), optionally followed by a fraction, and optionally followed by an exponent. For example: -123456.3455e-3.

Localization Considerations

If you are working in a locale other than en-US, or the templates require translation, then use the Oracle format masks.

The Microsoft format masks can generate unexpected results in templates run in different locale settings.

Do not include "%" in the format mask because this fixes the location of the percent sign in the number display, while the desired position could be at the beginning or the end of a number, depending on the locale.

Use the Microsoft Number Format Mask

To format numeric values, use Microsoft Word's field formatting features available from the Text Form Field Options dialog.

To apply a number format to a form field:

1. Open the Form Field Options dialog for the placeholder field.
2. Set the **Type** to Number.
3. Select the appropriate **Number format** from the list of options.

Supported Microsoft Format Mask Definitions

Several format mask definitions can be used to standardize output.

The following table lists the supported Microsoft format mask definitions.

| Symbol | Location | Meaning |
|--------|---------------------|--|
| 0 | Number | Digit. Each explicitly set 0 appears, if no other number occupies the position. Example: Format mask: 00.0000 Data: 1.234 Display: 01.2340 |
| # | Number | Digit. When set to #, only the incoming data is displayed. Example: Format mask: ##.#### Data: 1.234 Display: 1.234 |
| . | Number | Determines the position of the decimal separator. The decimal separator symbol used is determined at runtime based on template locale. Example: Format mask: #,##0.00 Data: 1234.56 Display for English locale: 1,234.56 Display for German locale: 1.234,56 |
| - | Number | Determines placement of minus sign for negative numbers. |
| , | Number | Determines the placement of the grouping separator. The grouping separator symbol used is determined at runtime based on template locale. Example: Format mask: #,##0.00 Data: 1234.56 Display for English locale: 1,234.56 Display for German locale: 1.234,56 |
| E | Number | Separates mantissa and exponent in a scientific notation. Example: 0.###E+0 plus sign always shown for positive numbers 0.###E-0 plus sign not shown for positive numbers |
| ; | Subpattern boundary | Separates positive and negative subpatterns. See the Note that follows the table. |
| % | Prefix or Suffix | Multiply by 100 and show as percentage |
| ' | Prefix or Suffix | Used to quote special characters in a prefix or suffix. |

 **Note:**

Subpattern boundary: A pattern contains a positive and negative subpattern, for example, "#,##0.00;(#,##0.00)". Each subpattern has a prefix, numeric part, and suffix. The negative subpattern is optional. If absent, the positive subpattern prefixed with the localized minus sign ("-") in most locales) is used as the negative subpattern. That is, "0.00" alone is equivalent to "0.00;-0.00". If there's an explicit negative subpattern, it serves only to specify the negative prefix and suffix. The number of digits, minimal digits, and other characteristics are all the same as the positive pattern. That means that "#,##0.0#;(#)" produces precisely the same behavior as "#,##0.0#;(#,##0.0#)".

Use the Oracle Format Mask

You can use the Oracle format mask in form fields.

To apply the Oracle format mask to a form field:

1. Open the Form Field Options dialog box for the placeholder field.
2. Set the **Type** to "Regular text".
3. In the Form Field Help Text field, enter the mask definition according to the following example:


```
<?format-number:fieldname;'999G999D99'?>
```

where

fieldname is the XML tag name of the data element you are formatting and

999G999D99 is the mask definition.

The following illustration shows an example Form Field Help Text dialog entry for the data element "empno".



Supported Oracle number format mask symbols and their definitions:

- 0 - Digit. Each explicitly set 0 appears, if no other number occupies the position. Example: Format mask: 00.0000 Data: 1.234 Display: 01.2340
- 9 - Digit. Returns value with the specified number of digits with a leading space if positive or a leading minus if negative. Leading zeros are blank, except for a zero value, which returns a zero for the integer part of the fixed-point number. Example: Format mask: 99.9999 Data: 1.234 Display: 1.234
- C - Returns the ISO currency symbol in the specified position.
- D - Determines the placement of the decimal separator. The decimal separator symbol used is determined at runtime based on template locale. For example: Format mask: 9G999D99 Data: 1234.56 Display for English locale: 1,234.56 Display for German locale: 1.234,56
- EEEE - Returns a value in scientific notation.
- G - Determines the placement of the grouping (thousands) separator. The grouping separator symbol used is determined at runtime based on template locale. For example: Format mask: 9G999D99 Data: 1234.56 Display for English locale: 1,234.56 Display for German locale: 1.234,56
- L - Returns the local currency symbol in the specified position.
- MI - Displays negative value with a trailing "-".
- PR - Displays negative value enclosed by <>.
- PT - Displays negative value enclosed by ().
- S (before number) - Displays positive value with a leading "+" and negative values with a leading "-".
- S (after number) - Displays positive value with a trailing "+" and negative value with a trailing "-".

Format Dates

Publisher supports three methods for specifying the date format.

- Specify an explicit date format mask using Microsoft Word's native date format mask.
- Specify an explicit date format mask using Oracle's format-date function.
- Specify an abstract date format mask using Oracle's abstract date format masks. (Recommended for multilingual templates.)

Use only one method. If both the Oracle and MS format masks are specified, the data is formatted twice, which causes unexpected behavior.

Data Source Requirements

To use the Microsoft format mask or the Oracle format mask, the date from the XML data source must be in canonical format.

This format is:

YYYY-MM-DDThh:mm:ss+HH:MM

where

- YYYY is the year
- MM is the month
- DD is the day
- T is the separator between the date and time component
- hh is the hour in 24-hour format
- mm is the minutes
- ss is the seconds
- +HH:MM is the time zone offset from Universal Time (UTC), or Greenwich Mean Time

An example of this construction is:

```
2005-01-01T09:30:10-07:00
```

The data after the "T" is optional, therefore the following date: 2005-01-01 can be formatted using either date formatting option.

 **Note:**

If the time component and time zone offset are not included in the XML source date, then Publisher assumes it represents 12:00 AM UTC (that is, yyyy-mm-ddT00:00:00-00:00).

Use the Microsoft Date Format Mask

To format date values, use Microsoft Word's field formatting features available from the Form Field Options dialog.

To apply a date format to a form field:

1. Open the Form Field Options dialog box for the placeholder field.
2. Set the **Type** to Date, Current Date, or Current Time.
3. Select the appropriate **Date format** from the list of options.

If you don't specify the mask in the **Date format** field, then the abstract format mask "MEDIUM" is used as default.

Supported Microsoft date format masks:

- d - The day of the month. Single-digit days don't have a leading zero.
- dd - The day of the month. Single-digit days have a leading zero.
- ddd - The abbreviated name of the day of the week, as defined in AbbreviatedDayNames.
- dddd - The full name of the day of the week, as defined in DayNames.
- M - The numeric month. Single-digit months don't have a leading zero.
- MM - The numeric month. Single-digit months have a leading zero.

- MMM - The abbreviated name of the month, as defined in AbbreviatedMonthNames.
- yy - The year without the century. If the year without the century is less than 10, the year is displayed with a leading zero.
- yyyy - The year in four digits.
- gg - The period or era. This pattern is ignored if the date to be formatted doesn't have an associated period or era string.
- h - The hour in a 12-hour clock. Single-digit hours don't have a leading zero.
- H - The hour in a 24-hour clock. Single-digit hours don't have a leading zero.
- HH - The hour in a 24-hour clock. Single-digit hours have a leading zero.
- m - The minute. Single-digit minutes don't have a leading zero.
- mm - The minute. Single-digit minutes have a leading zero.
- s - The second. Single-digit seconds don't have a leading zero.
- ss - The second. Single-digit seconds do have a leading zero.
- f - Displays seconds fractions represented in one digit.
- ff - Displays seconds fractions represented in two digits.
- fff - Displays seconds fractions represented in three digits.
- ffff - Displays seconds fractions represented in four digits.
- fffff - Displays seconds fractions represented in five digits.
- ffffff - Displays seconds fractions represented in six digits.
- ffffffff - Displays seconds fractions represented in seven digits.
- tt - The AM/PM designator defined in AMDesignator or PMDesignator, if any.
- z - Displays the time zone offset for the system's current time zone in whole hours only. (This element can be used for formatting only)
- zz - Displays the time zone offset for the system's current time zone in whole hours only. (This element can be used for formatting only)
- zzz - Displays the time zone offset for the system's current time zone in hours and minutes.
- : - The default time separator defined in TimeSeparator.
- / - The default date separator defined in DateSeparator.
- ' - Quoted string. Displays the literal value of any string between two ' characters.
- " - Quoted string. Displays the literal value of any string between two " characters.

Use the Oracle Format Mask

Use the Oracle format mask to specify how date and time displays.

To apply the Oracle format mask to a date field:

1. Open the **Form Field Options** dialog box for the placeholder field.
2. Set the **Type** to Regular Text.
3. Select the **Add Help Text...** button to open the **Form Field Help Text** dialog.

4. Insert the following syntax to specify the date format mask:

```
<?format-date:date_string; 'ABSTRACT_FORMAT_MASK'; 'TIMEZONE'?>
```

or

```
<?format-date-and-calendar:date_string;  
'ABSTRACT_FORMAT_MASK'; 'CALENDAR_NAME'; 'TIMEZONE'?>
```

where time zone is optional. The detailed usage of format mask, calendar and time zone is described below.

If no format mask is specified, then the abstract format mask "MEDIUM" is used as the default.

Example form field help text entry:

```
<?format-date:hiredate;'YYYY-MM-DD'?>
```

Supported Oracle format mask symbols:

Note:

Excel2007 output (.xlsx) doesn't support the following format masks: E, EE, W, WW, X, XX. If you use these in an RTF template and generate Excel2007 output, dates with any of these formats won't be viewable. Some combinations of these format masks may result in an error when the Excel2007 (.xlsx) output is opened.

- - / , . ; : "text" - Punctuation and quoted text are reproduced in the result.
- AD A.D. - AD indicator with or without periods.
- AM A.M. - Meridian indicator with or without periods.
- BC B.C. - BC indicator with or without periods.
- CC - Century. For example, 2002 returns 21; 2000 returns 20.
- DAY - Name of day, padded with blanks to length of 9 characters.
- D - Day of week (1-7).
- DD - Day of month (1-31).
- DDD - Day of year (1-366).
- DL - Returns a value in the long date format.
- DS - Returns a value in the short date format.
- DY - Abbreviated name of day.
- E - Abbreviated era name.
- EE - Full era name.
- FF[1..9] - Fractional seconds. Use the numbers 1 to 9 after FF to specify the number of digits in the fractional second portion of the datetime value returned. Example: 'HH:MI:SS.FF3'
- HH - Hour of day (1-12).
- HH12 - Hour of day (1-12).

- HH24 - Hour of day (0-23).
- MI - Minute (0-59).
- MM - Month (01-12; JAN = 01).
- MON - Abbreviated name of month.
- MONTH - Name of month, padded with blanks to length of 9 characters.
- PM P.M. - Meridian indicator with or without periods.
- RR - Lets you store 20th century dates in the 21st century using only two digits.
- RRRR - Round year. Accepts either 4-digit or 2-digit input. If 2-digit, provides the same return as RR. If you do not want this functionality, then simply enter the 4-digit year.
- SS - Seconds (0-59).
- TZD - Daylight savings information. The TZD value is an abbreviated time zone string with daylight savings information. It must correspond to the region specified in TZR. Example: PST (for Pacific Standard Time), PDT (for Pacific Daylight Time)
- TZH - Time zone hour. (See TZM format element.)
- TZM - Time zone minute. (See TZH format element.) Example: 'HH:MI:SS.FFTZH:TZM'
- TZR - Time zone region information. The value must be one of the time zone regions supported in the database. Example: PST (Pacific Standard Time)
- WW - Week of year (1-53) where week 1 starts on the first day of the year and continues to the seventh day of the year.
- W - Week of month (1-5) where week 1 starts on the first day of the month and ends on the seventh.
- X - Local radix character.
- YYYY - 4-digit year.
- YY Y - Last 2, or 1 digit(s) of year.

Default Format Mask

If you do not want to specify a format mask with either the MS method or the Oracle method, you can omit the mask definition and use the default format mask. The default format mask is the MEDIUM abstract format mask from Oracle.

To use the default option using the Microsoft method, set the **Type** to Date, but leave the **Date format** field blank in the Text Form Field Options dialog.

To use the default option using the Oracle method, do not supply a mask definition to the "format-date" function call. For example:

```
<?format-date:hiredate?>
```

Oracle Abstract Format Masks

The abstract date format masks reflect the default implementations of date/time formatting in the I18N library.

When you use one of these masks, the output generated depends on the locale that is associated with the report.

Specify the abstract mask using the following syntax:

```
<?format-date:fieldname;'MASK' ?>
```

where *fieldname* is the XML element tag and

MASK is the Oracle abstract format mask name

For example:

```
<?format-date:hiredate;'SHORT' ?>
<?format-date:hiredate;'LONG_TIME_TZ' ?>
<?format-date:xdoxslt:sysdate_as_xsdformat();'MEDIUM' ?>
```

The following table lists the abstract format masks and the sample output that would be generated for the US locale.

| Mask | Output for US Locale |
|----------------|---------------------------------------|
| SHORT | 2/31/99 |
| MEDIUM | Dec 31, 1999 |
| LONG | Friday, December 31, 1999 |
| SHORT_TIME | 12/31/99 6:15 PM |
| MEDIUM_TIME | Dec 31, 1999 6:15 PM |
| LONG_TIME | Friday, December 31, 1999 6:15 PM |
| SHORT_TIME_TZ | 12/31/99 6:15 PM GMT |
| MEDIUM_TIME_TZ | Dec 31, 1999 6:15 PM GMT |
| LONG_TIME_TZ | Friday, December 31, 1999 6:15 PM GMT |

Display the System Date (sysdate) in Reports

To correctly display the sysdate, use the function `xdoxslt:sysdate_as_xsdformat()` with the `<?format-date:??>` command.

For example:

```
<?format-date:xdoxslt:sysdate_as_xsdformat();'MEDIUM'?>
```

```
<?format-date:xdoxslt:sysdate_as_xsdformat();'LONG'?>
```

```
<?format-date:xdoxslt:sysdate_as_xsdformat();'LONG_TIME_TZ'?>
```

```
<?format-date-and-calendar:xdoxslt:sysdate_as_xsdformat();  
'LONG_TIME';'ROC_OFFICIAL';?>
```


Format Currencies

Publisher enables you to define specific currency format masks to apply to the published data at runtime.

To utilize currency formatting in the RTF template:

1. Set up the currency formats in the runtime configuration properties. The currency formats can be defined at the system level or at the report level.

When you set up the currency format property, you define the format to be used for a specified currency, using the International Standards Organization (ISO) currency code. A sample is shown in the following figure:



2. Enter the format-currency command in the RTF template to apply the format to the field at runtime.

Apply a Currency Format to a Field

Follow these steps to understand the parameters for the format-currency function and to apply a currency format to a field.

The parameters for the format-currency function are as follows:

```
<?format-currency:Amount_Field;CurrencyCode;displaySymbolOrNot?>
```

where

`Amount_Field` takes the tag name of the XML element that holds the amount value in the data.

`CurrencyCode` can either be set to a static value or it can be set dynamically. If the value is static for the report, then enter the ISO three-letter currency code in single quotes, for example, 'USD'.

To set the value dynamically, enter the tag name of the XML element that holds the ISO currency code. Note that an element that contains the currency code must be present in the data.

At runtime, the `Amount_Field` is formatted according to the format you set up for the currency code in the report properties.

`displaySymbolOrNot` takes one of the following values: `true` or `false`. When set to `true`, the currency symbol is displayed in the report based on the value for **CurrencyCode**. If you do not want the currency symbol to be displayed, then you can either enter `false` or simply do not specify the parameter.

Example: Display Multiple Currency Formats in a Report

The table here provides an example that assumes you've set up the various currency formats in the report properties.

| Currency Code | Format Mask |
|---------------|----------------|
| USD | 9G999D99 |
| INR | 9G99G99G999D99 |

In this example, you need not set the currency code dynamically. You've the following elements in the XML data:

```
<TOTAL_SALES>
  <US_SALES>8596526459.56</US_SALES>
  <INDIA_SALES>60000000</INDIA_SALES>
</TOTAL_SALES>
```

You want to display these two total fields in the template.

For `US_SALES`, the syntax in the Publisher properties field is as follows:

```
<?format-currency:US_SALES;'USD'?>
```

At runtime, the fields are displayed as shown in the following figure:

India Sales: 6,00,00,000.00
US Sales: 8,596,526,459.56

Example: Display Multiple Currency Codes in a Single Report

This simple XML code includes an element that contains the Amount (`Trans_amount`) and an element that contains the ISO currency code (`Cur_Code`).

```
<ROW>
  <Trans_Amount>123</Trans_Amount>
  <Cur_Code>USD</Cur_Code>
</ROW>
<ROW>
  <Trans_Amount>-456</Trans_Amount>
  <Cur_Code>GBP</Cur_Code>
</ROW>
<ROW>
  <Trans_Amount>748</Trans_Amount>
  <Cur_Code>EUR</Cur_Code>
</ROW>
<ROW>
  <Trans_Amount>-987</Trans_Amount>
  <Cur_Code>JPY</Cur_Code>
</ROW>
```

To display each of these amounts with the appropriate currency symbol, enter the following in the template for the field in which you want the amounts to display:

```
<?format-currency:Trans_Amount;Cur_Code;'true'?>
```

The following figure shows the multiple currency report that is generated:

| | |
|-------------|----------|
| USD Amount: | \$123.00 |
| GBP Amount: | -£456.00 |
| EUR Amount: | € 748.00 |
| JPY Amount: | -¥987 |

Support Calendars and Time Zones

This section describes support for calendars and time zones.

Calendar Specification

The term *calendar* refers to the calendar date displayed in the published report.

The following types are supported:

- GREGORIAN
- ARABIC_HIJRAH
- ENGLISH_HIJRAH
- JAPANESE_IMPERIAL
- THAI_BUDDHA
- ROC_OFFICIAL (Taiwan)

Use one of the following methods to set the calendar type:

- Call the `format-date-and-calendar` function and declare the calendar type.

For example: `<?format-date-and-calendar:hiredate;'LONG_TIME_TZ';'ROC_OFFICIAL';?>`

The following figure shows the output generated using this definition with locale set to zh-TW and time zone set to Asia/Taipei:

中華民國88年12月31日 星期五 下午 2:15 台北

- Set the calendar type using the profile option XDO: Calendar Type (XDO_CALENDAR_TYPE).

Note:

The calendar type that is specified in the template overrides the calendar type set in the profile option.

Specify Time Zone

You can specify a time zone using a Java time zone string.

There're two ways to specify time zone information:

- Call the `format-date` or `format-date-and-calendar` function with the Oracle format.
- Set the user profile option Client Timezone (CLIENT_TIMEZONE_ID) in Oracle Applications.

If no time zone is specified, then the report time zone is used.

In the template, the time zone must be specified as a Java time zone string, for example, America/Los Angeles. The following example shows the syntax to enter in the help text field of the template:

```
<?format-date:hiredate;'LONG_TIME_TZ';'Asia/Shanghai'??>
```

Specify No Time Zone Conversion

You can prevent a time zone from being converted to the user's local time zone.

To stop timezone conversion truncate the timezone component in the date-time XSD string. In reports that do not need timezone conversion, `<?format-date-nt: ...?>` is a convenient function to achieve no timezone conversion.

Use this RTF template command to prevent any time zone conversion on the date-time provided.

Syntax: `<?format-date-nt:<date_string>;'ABSTRACT_FORMAT_MASK'??>`

Examples:

```
<?format-date-nt:Hire_Date;'SHORT'??>
<?format-date-nt:xdxslt:sysdate_as_xsdformat();'MEDIUM'??>
<?format-date-nt:Hire_Date;'MEDIUM_TIME'??>
```

Use External Fonts


You can use external fonts in the output that are not normally available on the server.

External fonts are supported for PDF output only. To set up a new font for the report output, use the font to design the template on your client machine, then make it available on the server, and configure Publisher to access the font at runtime.

To use external fonts

1. Use the font in the template.
 - a. Copy the font to the `<WINDOWS_HOME>/fonts` directory.
 - b. Open Microsoft Word and build the template.
 - c. Insert the font in the template: Select the text or form field and then select the desired font from the font dialog box (Format > Font) or font drop down list.

The following illustration shows an example of the form field method and the text method.



2. Place the font in the `ORACLE_HOME/common/fonts` directory.

 **Note:**

The predefined fonts are located in: `ORACLE_HOME/common/fonts`. The font location is set by the `XDO_FONT_DIR` variable. If this variable isn't set in your environment, then the fonts are located in `$JAVA_HOME/jre/lib/fonts`.

3. Set the "font" property.

You can set the font property for the report in the Font Mappings page, or in the configuration file.

To set the property in the Font Mappings page:

- a. Open the report in the report editor.
- b. Click **Properties**, then click **Font Mappings**.
- c. Enter the font and then select the font to which you want to map it.

To set the property in the configuration file:

- a. Update the "fonts" section in the configuration file with the font name and its location on the server. For example, the new entry for a TrueType font is structured as follows:

```
<font family="MyFontName" style="normal" weight="normal">  
  <truetype path="\user\fonts\MyFontName.ttf"/>  
</font>
```

Administrator must set the properties in the configuration file.

Now you can run the report to use the font in the output as designed. For PDF output, the advanced font handling features embed the external font glyphs directly into the final document. The embedded font only contains the glyphs required for the document and not the complete font definition. Therefore the document is completely self-contained, eliminating the need to have external fonts installed on the printer.

Use the Barcode Fonts Shipped with Publisher

There're several fonts that output barcodes included with Publisher.

There're several fonts that output barcodes included with Publisher. Font files included with Publisher:

- 128R00.TTF - Supports code128a, code128b, and code128c algorithm.
- B39R00.TTF - Supports code39 and code39mod43 algorithm.
- UPCR00.TTF - supports upca and upce algorithm.

When you use one of these prepackaged fonts, Publisher executes the preprocessing on the data prior to applying the barcode font to the data in the output document. For example, to calculate checksum values or start and end bits for the data before formatting them.

At design time, you don't need to apply the barcode font to the field in Microsoft Word. Instead, you can map the font that you apply to the field using Publisher's font mapping. At runtime, Publisher applies the barcode font to any field using the base font you specified in the font mapping. Be sure to choose a font that isn't used elsewhere in the template.

If you want to use the font directly in Microsoft Word, then add the appropriate .TTF file to the `C:\WINDOWS\FONTS` directory. To use the Template Builder Preview function, map the font in the Template Builder configuration file.

To use the barcode fonts in the report output:

1. Insert a field in the template where the barcode is to display in the report output.
2. In the form field, enter the following command:

```
<?format-barcode:data;'barcode_type'??>
```

where

data is the element from the XML data source to be encoded. For example:
INVOICE_NO

barcode_type is one of the supported algorithms listed above.

Examples:

```
<?format-barcode:INVOICE_NO;'code128a'??>
```

```
<?format-barcode:INVOICE_NO;'code39mod43'??>
```

```
<?format-barcode:INVOICE_NO;'upca'??>
```

3. In Microsoft Word, apply the font to the field. If you haven't installed the barcode fonts on your client machine, then select a font that isn't used elsewhere in the template, for example, Bookman.
4. Configure the font in the Font Mapping page. For more information about the Font Mapping page.

Note the following:

- Microsoft Word may not render the barcode fonts properly even when they're installed on your client. To work around this issue, apply a different font to the field and map the font as described above.
- The `upca` algorithm accepts only UPC-A message string and encodes into UPC-A barcode.
- A string of 12 characters is treated as UPC-A message with a check digit, 11 is without a check digit.
- The `upce` algorithm accepts only UPC-E message strings and encodes into UPC-E barcode.
- A string of 8 characters is treated as a UPC-E message with both a front and end guard bar; a string of 6 characters is without guard bars.

Implement Custom Barcode Formats

If you choose to use a custom barcode instead, use this procedure to implement a custom barcode.

Publisher offers the ability to execute preprocessing on the data prior to applying a barcode font to the data in the output document. For example, you might need to calculate checksum values or start and end bits for the data before formatting them.

The solution requires that you register a barcode encoding class with Publisher that can then be instantiated at runtime to apply the formatting in the template.

To enable the formatting feature in the template, you must use two commands in the template. The first command registers the barcode encoding class with Publisher. This must be declared somewhere in the template prior to the encoding command. The second is the encoding command to identify the data to be formatted.

Register the Barcode Encoding Class

You can include barcodes in form fields.

Use the following syntax in a form field in the template to register the barcode encoding class:

```
<?register-barcode-vendor:java_class_name;barcode_vendor_id?>
```

This command requires a Java class name (this carries out the encoding) and a barcode vendor ID as defined by the class. This command must be placed in the template before the commands to encode the data in the template. For example:

```
<?register-barcode-  
vendor:'oracle.xdo.template.rtf.util.barcode.BarcodeUtil';'XMLPBarVendor'  
'?>
```

where

`oracle.xdo.template.rtf.util.barcode.BarcodeUtil` is the Java class and
`XMLPBarVendor` is the vendor ID that is defined by the class.

Encode the Data

Use this syntax in a form field in the template to format the data.

```
<?format-barcode:data;'barcode_type';'barcode_vendor_id'?>
```

where

the `data` is the element from the XML data source to be encoded. For example:
`LABEL_ID`

the `barcode_type` is the method in the encoding Java class used to format the data (for example: `Code128a`).

the `barcode_vendor_id` is the ID defined in the `register-barcode-vendor` field of the first command you used to register the encoding class.

For example:

```
<?format-barcode:LABEL_ID;'Code128a';'XMLPBarVendor'?>
```

At runtime, the `barcode_type` method is called to format the data value and the barcode font is then applied to the data in the final output.

Control the Placement of Instructions Using the Context Commands

The Publisher syntax is simplified XSL instructions. This syntax, along with any native XSL commands you may use in the template, is converted to XSL-FO at runtime. The placement of these instructions within the converted stylesheet determines the behavior of the template.

Publisher's RTF processor places these instructions within the XSL-FO stylesheet according to the most common context. However, sometimes you must define the context of the instructions differently to create a specific behavior. To support this requirement, Publisher provides a set of context commands that allow you to define the context (or placement) of the processing instructions. For example, using context commands, you can:

- Specify an `if` statement in a table to refer to a cell, a row, a column or the whole table.
- Specify a `for-each` loop to repeat either the current data or the complete section (to create new headers and footers and restart the page numbering)
- Define a variable in the current loop or at the beginning of the document.

You can specify a context for both processing commands using the Publisher syntax and those using native XSL.

- To specify a context for a processing command using the simplified Publisher syntax, simply add `@context` to the syntax instruction. For example:
 - `<?for-each@section:INVOICE?>` - Specifies that the group INVOICE should begin a new section for each occurrence. By adding the section context, you can reset the header and footer and page numbering.

If you do not want to restart the page numbering, then add the command: `<?initial-page-number:'auto'?>` after the `@section` command to continue the page numbering across sections.
 - `<?if@column:VAT?>` - Specifies that the `if` statement should apply to the VAT column only.
- To specify a context for an XSL command, add the `xdofo:ctx="context"` attribute to the tags to specify the context for the insertion of the instructions. The value of the context determines where the code is placed.

For example:

```
<xsl:for-each xdofo:ctx="section" select ="INVOICE">
<xsl:attribute xdofo:ctx="inblock" name="background-color">red</
xsl:attribute>
```

Publisher supports the context types that are described in the following table:

| Context | Description |
|-----------|---|
| section | The statement affects the whole section including the header and footer. For example, a <code>for-each@section</code> context command creates a new section for each occurrence - with restarted page numbering and header and footer. Note that you can retain continuous page numbering across sections by using the <code><?initial-page-number:'auto'?></code> command. See Create Batch Reports for an example of this usage. |
| column | The statement affects the whole column of a table. This context is typically used to show and hide table columns depending on the data. See Format Columns for an example. |
| cell | The statement affects the cell of a table. This is often used together with <code>@column</code> in pivot tables to create a dynamic number of columns. See Insert Pivot Tables for an example. |
| block | The statement affects multiple complete <code>fo:blocks</code> (RTF paragraphs). This context is typically used for <code>if</code> and <code>for-each</code> statements. It can also be used to apply formatting to a paragraph or a table cell. See Highlight Cells for an example. |
| inline | The context becomes the single statement inside an <code>fo:inline</code> block. This context is used for variables. |
| incontext | The statement is inserted immediately after the surrounding statement. This is the default for <code><?sort?></code> statements that must follow the surrounding <code>for-each</code> as the first element. |
| inblock | The statement becomes a single statement inside an <code>fo:block</code> (RTF paragraph). This is typically not useful for control statements (such as <code>if</code> and <code>for-each</code>) but is useful for statements that generate text, such as <code>call-template</code> . |
| inlines | The statement affects multiple complete inline sections. An inline section is text that uses the same formatting, such as a group of words rendered as bold. See Use If Statements in Boilerplate Text . If you use <code>@inlines</code> with <code>if</code> syntax, any other <code>if</code> syntax inside the statement must use the context command <code>@inline</code> . If you use <code>@inlines</code> with <code>FOR-EACH</code> syntax any other <code>if</code> or <code>FOR-EACH</code> syntax inside the statement must use the context command <code>@inline</code> . |
| begin | The statement is placed at the beginning of the XSL stylesheet. This is required for global variables. See Set Parameters . |
| end | The statement is placed at the end of the XSL stylesheet. |

The following table shows the default context for the Publisher commands:

| Command | Context |
|-----------------------------|---------|
| <code>apply-template</code> | inline |
| <code>attribute</code> | inline |
| <code>call-template</code> | inblock |
| <code>choose</code> | block |
| <code>for-each</code> | block |
| <code>if</code> | block |
| <code>import</code> | begin |

| Command | Context |
|----------|-----------|
| param | begin |
| sort | incontext |
| template | end |
| value-of | inline |
| variable | end |

Use XPath Commands

XPath is an industry standard developed by the World Wide Web Consortium (W3C).

It's the method used to navigate through an XML document. XPath is a set of syntax rules for addressing the individual pieces of an XML document. You might not know it, but you've already used XPath; RTF templates use XPath to navigate through the XML data at runtime.

This section contains a brief introduction to XPath principles. XPath follows the Document Object Model (DOM), which interprets an XML document as a tree of nodes. A node can be one of seven types:

- root
- element
- attribute
- text
- namespace
- processing instruction
- comment

Many of these elements are shown in the following sample XML, which contains a catalog of CDs:

```
<?xml version="1.0" encoding="UTF-8"?>
<!-- My CD Listing -->
<CATALOG>
  <CD cattype=Folk>
    <TITLE>Empire Burlesque</TITLE>
    <ARTIST>Bob Dylan</ARTIST>
    <COUNTRY>USA</COUNTRY>
    <PRICE>10.90</PRICE>
    <YEAR>1985</YEAR>
  </CD>
  <CD cattype=Rock>
    <TITLE>Hide Your Heart</TITLE>
    <ARTIST>Bonnie Tylor</ARTIST>
    <COUNTRY>UK</COUNTRY>
    <PRICE>9.90</PRICE>
    <YEAR>1988</YEAR>
```

```
</CD>  
</CATALOG>
```

The root node in this example is CATALOG. CD is an element, and it has an attribute cattype. The sample contains the comment My CD Listing. Text is contained within the XML document elements.

Locate Data

Locate information in an XML document using location-path expressions.

A node is the most common search element that you encounter. Nodes in the example CATALOG XML include CD, TITLE, and ARTIST. Use a path expression to locate nodes within an XML document. For example, the following path returns all CD elements:

```
//CATALOG/CD
```

where

the double slash (//) indicates that all elements in the XML document that match the search criteria are to be returned, regardless of the level within the document.

the slash (/) separates the child nodes. All elements matching the pattern are returned.

To retrieve the individual TITLE elements, use the following command:

```
/CATALOG/CD/TITLE
```

This example returns the following XML:

```
<CATALOG>  
  <CD cattype=Folk>  
    <TITLE>Empire Burlesque</TITLE>  
  </CD>  
  <CD cattype=Rock>  
    <TITLE>Hide Your Heart</TITLE>  
  </CD>  
</CATALOG>
```

Further limit the search by using square brackets. The brackets locate elements with certain child nodes or specified values. For example, the following expression locates all CDs recorded by Bob Dylan:

```
/CATALOG/CD[ARTIST="Bob Dylan"]
```

Or, if each CD element did not have an PRICE element, you could use the following expression to return only those CD elements that include a PRICE element:

```
/CATALOG/CD[PRICE]
```


Use the bracket notation to leverage the attribute value in the search. Use the @ symbol to indicate an attribute. For example, the following expression locates all Rock CDs (all CDs with the cattype attribute value Rock):

```
//CD[@cattype="Rock" ]
```

This returns the following data from the sample XML document:

```
<CD cattype=Rock>
  <TITLE>Hide Your Heart</TITLE>
  <ARTIST>Bonnie Tylor</ARTIST>
  <COUNTRY>UK</COUNTRY>
  <PRICE>9.90</PRICE>
  <YEAR>1988</YEAR>
</CD>
```

You can also use brackets to specify the item number to retrieve. For example, the first CD element is read from the XML document using the following XPath expression:

```
/CATALOG/CD[1]
```

The sample returns the first CD element:

```
<CD cattype=Folk>
  <TITLE>Empire Burlesque</TITLE>
  <ARTIST>Bob Dylan</ARTIST>
  <COUNTRY>USA</COUNTRY>
  <PRICE>10.90</PRICE>
  <YEAR>1985</YEAR>
</CD>
```

XPath also supports wildcards to retrieve every element contained within the specified node. For example, to retrieve all the CDs from the sample XML, use the following expression:

```
/CATALOG/*
```

You can combine statements with Boolean operators for more complex searches. The following expression retrieves all Folk and Rock CDs, thus all the elements from the sample:

```
//CD[@cattype="Folk" ] || //CD[@cattype="Rock" ]
```

The pipe (|) is equal to the logical OR operator. In addition, XPath recognizes the logical OR and AND, as well as the equality operators: <=, <, >, >=, ==, and !=. For example, you can find all CDs released in 1985 or later using the following expression:

```
/CATALOG/CD[YEAR >=1985]
```

Start Reference

The first character in an XPath expression determines the point at which it should start in the XML tree.

Statements beginning with a forward slash (/) are considered absolute. No slash indicates a relative reference. An example of a relative reference is:

```
CD/*
```

This statement begins the search at the current reference point. That means if the example occurred within a group of statements the reference point left by the previous statement would be utilized.

As noted earlier, double forward slashes (//) retrieve every matching element regardless of location in the document, therefore the use of double forward slashes (//) should be used only when necessary to improve performance.

Specify Context and Parents

To select current and parent elements, XPath recognizes the dot notation commonly used to navigate directories.

Use a single period (.) to select the current node and use double periods (..) to return the parent of the current node. For example, to retrieve all child nodes of the parent of the current node, use:

```
../*
```

Therefore, to access all CDs from the sample XML, use the following expression:

```
/CATALOG/CD/..
```

You could also access all the CD titles released in 1988 using the following:

```
/CATALOG/CD/TITLE[../YEAR=1988]
```

The two periods (..) are used to navigate up the tree of elements to find the YEAR element at the same level as the TITLE, where it's then tested for a match against "1988". You could also use // in this case, but if the element YEAR is used elsewhere in the XML document, then you might get erroneous results.

XPath is an extremely powerful standard when combined with RTF templates allowing you to use conditional formatting and filtering in the template.

Declare Namespaces

If the XML data contains namespaces, you must declare them in the template prior to referencing the namespace in a placeholder. Declare the namespace in the template using either the basic RTF method or in a form field.

Enter the following syntax:

```
<?namespace:namespace name= namespace url?>
```

For example:

```
<?namespace:fsg=http://www.example.com/fsg/2002-30-20/?>
```

Once declared, you can use the namespace in the placeholder markup, for example:

```
<?fsg:ReportName?>
```

Use FO Elements and XSL Elements

This section describes how to use FO elements and XSL elements.

Use FO Elements

You can use the native FO syntax inside the Microsoft Word form fields.

For more information on XSL-FO see the [W3C Website](#).

The full list of FO elements that Publisher supports is in [Supported XSL-FO Elements](#).

Use XSL Elements

You can use any XSL element in the template by inserting the XSL syntax into a form field.

If you are using the basic RTF method, you cannot insert XSL syntax directly into the template. Publisher has extended the following XSL elements for use in RTF templates.

To use these in a basic-method RTF template, you must use the Publisher Tag form of the XSL element. If you are using form fields, use either option.

Apply a Template Rule

Use this element to apply a template rule to the current element's child nodes.

XSL Syntax: `<xsl:apply-templates select="name">`

Publisher Tag: `<?apply:name?>`

This function applies to `<xsl:template-match="n">`, where *n* is the element name.

Copy the Current Node

Use this element to create a copy of the current node.

XSL Syntax: `<xsl:copy-of select="name">`

Publisher Tag: `<?copy-of:name?>`

Call a Named Template

Use this element to call a named template to be inserted into or applied to the current template.

For example, use this feature to render a table multiple times.

XSL Syntax: `<xsl:call-template name="name">`

Publisher Tag: `<?call-template:name?>`

Declare a Template

Use this element to apply a set of rules when a specified node is matched.

XSL Syntax: `<xsl:template name="name">`

Publisher Tag: `<?template:name?>`

Declare a Variable

Use this element to declare a local or global variable.

XSL Syntax: `<xsl:variable name="name">`

Publisher Tag: `<?variable:name?>`

Example:

```
<xsl:variable name="color" select="'red'"/>
```

Assigns the value *red* to the *color* variable. The variable can then be referenced in the template.

Import a Style Sheet

Use this element to import the contents of one style sheet into another.

 **Note:**

An imported style sheet has lower precedence than the importing style sheet.

XSL Syntax: `<xsl:import href="url">`

Publisher Tag: `<?import:url?>`

Define the Root Element of the Style Sheet

This and the `<xsl:stylesheet>` element are completely synonymous elements. Both are used to define the root element of the style sheet.



Note:

An included style sheet has the same precedence as the including style sheet.

XSL Syntax: `<xsl:stylesheet xmlns:x="url">`

Publisher Tag: `<?namespace:x=url?>`



Note:

The namespace must be declared in the template. See [Declare Namespaces](#).

Format Native XSL Numbers

The native XSL format-number function takes a basic format.

The basic format is:

`format-number(number, format, [decimalformat])`

The following list describes the parameters:

- number - Required. Specifies the number to be formatted.
- format - Required. Specifies the format pattern. Use the following characters to specify the pattern:
 - # (Denotes a digit. Example: #####).
 - 0 (Denotes leading and following zeros. Example: 0000.00).
 - . (The position of the decimal point Example: ###.##).
 - , (The group separator for thousands. Example: ###,###.##).
 - % (Displays the number as a percentage. Example: ##%).
 - ; (Pattern separator. The first pattern is used for positive numbers and the second for negative numbers).
- decimalformat - Optional. For more information on the decimal format, consult any basic XSLT manual.

Guidelines for Designing RTF Templates for Microsoft PowerPoint Output

Publisher can generate the RTF template as PowerPoint output enabling you to get report data into key business presentations. Currently, the PowerPoint document generated is a simple export of the formatted data and charts to PowerPoint.

Guidelines for Designing RTF Templates for Microsoft Excel 2007 Output

This section describes report features specific to designing RTF templates for Excel 2007 output (.xlsx).

It includes the following topics:

- [Create Multiple Sheets](#)
- [Specify a Sheet Name](#)
- [Specify Number and Date Formatting](#)

Create Multiple Sheets

By default, page breaks and section breaks specified in the RTF template create a new sheet in the output Excel workbook. You can control whether page breaks create a new sheet using the property `xlsx-page-break-as-new-sheet`. Set this property to *false* when you don't want page breaks in the RTF template to generate new sheets in the Excel workbook. A section break in the template will always create a new sheet in the Excel workbook output.

For information on setting properties in an RTF template, see [Set Properties](#).

Specify a Sheet Name

You can specify which sheet to use in an input data phrase.

To specify a sheet name, use the following command in the template:

```
<?spreadsheet-sheet-name: xpath-expression?>
```

where *xpath-expression* is an XPath expression or a string constant.

For example, assume your template uses input data as follows:

```
<?xml version="1.0" encoding="UTF-8" ?>
<ROWSET>
  <ROW>
    <CUSTOMER_NAME>Vgpsuwo Fjprpit</CUSTOMER_NAME>
    <CUSTOMER_NUMBER>7795</CUSTOMER_NUMBER>
    <YEAR>2005</YEAR>
    <BRAND>MSPKID</BRAND>
    <DIVISION>UWGLERXM</DIVISION>
    <STATE>LD</STATE>
    <INVOICE_DATE>2004-12-07T07:13:15.379-08:00</INVOICE_DATE>
    <INVOICE_NO>806356</INVOICE_NO>
    <INVOICE_AMOUNT>8181.704554734346</INVOICE_AMOUNT>
  </ROW>
  ...
</ROWSET>
```

To generate a sheet name that shows the YEAR and STATE from the data (for example, "2005 ID") enter the following in a Publisher field in your template:

```
<?spreadsheet-sheet-name: {concat(../YEAR, ' ', ../STATE)}?>
```

Ensure that your expression generates unique sheet names within the workbook.

Specify Number and Date Formatting

For Excel 2007 output format, Publisher doesn't apply any formatting for number and date.

Publisher saves the formatting mask and the actual value (date or number) into the XLSX output file. The formatting is handled by Microsoft Excel. For example:

- If the Microsoft Windows Region and Language of the client computer is set to English (United States), then the numbers and dates are formatted in en-US locale in the Excel 2007 output file.
- If the Microsoft Windows Region and Language of the client computer is set to French (France), then the numbers and dates in the same Excel 2007 output file are formatted in fr-FR locale.

Note also that Microsoft Excel 2007 output doesn't support some Oracle format masks. See [Use the Oracle Format Mask](#) for more information.

Render HTML Formatted Data in a Report

This section describes how to preserve HTML formatting from a data source in your final output report.

This section contains the following topics:

- [Supported HTML Features](#)
- [Data Model Requirements](#)
- [RTF Template Requirements](#)
- [Example](#)

Supported HTML Features

Using supported HTML features helps you format output for readability and consistency.

Supported HTML features are:

- Hyperlink
- List
 - Bulleted list
 - Ordered list
- Paragraph
- Font style (bold, italic, plain, underline, subscript, superscript, strike-through)
- Font size

- Font family
- Background color
- Foreground color
- Paragraph alignment (center, left, right, and justify)
- Paragraph indent

The following HTML features are not supported:

- Nested list (list with indent)
- Any HTML tags or attributes manually inserted by modifying the HTML source code; for example, inserted tables or images.

Data Model Requirements

The XML data used as input to the report must wrap the HTML portion of the data in a CDATA section.

You can retrieve data stored in the form of XHTML documents stored in a database CLOB column and render the markup in the generated report.

RTF Template Requirements

To render the HTML in your report, use the following tag in the RTF template.

The tag is:

```
<?html2fo: elementname?>
```

where *elementname* is the XML element name that contains the HTML data.

Example

This example uses the mentioned XML data with embedded HTML data.

```
<?xml version="1.0" encoding="UTF-8"?>
<RTECODE>
<![CDATA[
<p><font style="font-style: italic; font-weight: bold;" size="3">
<a href="http://www.oracle.com">oracle</a></font> </p>
<p><font size="6"><a href="http://docs.oracle.com/">Oracle
Documentation</a>
</font></p>
]]>
</RTECODE>
```

To render this sample as formatted HTML a report, enter the following in your RTF template:

```
<?html2fo: RTECODE?>
```


Embed PCL Commands for Check Printing

PCL (Printer Command Language) is a page description language. Like Postscript, it's widely supported in office printers. To support PCL printers, Publisher provides a PDF to PCL converter. In addition to translating the PDF document into a sequence of PCL commands, specific PCL commands can be embedded in an RTF template, so that when the report output is generated in PDF and then converted to PCL the commands are maintained in the PCL file. When the PCL printer receives the PCL file, it invokes the embedded commands.

Publisher supports PCL commands to enable font selection commands for secure check printing; for example, to invoke the MICR font used for the machine-readable account codes and the custom font used for the check signer's signature. The MICR font and the custom signature font are stored in hardware cartridges on the printer and are invoked using PCL escape sequences embedded in the PCL-formatted file.

To embed the PCL commands in the file that is printed, use the Publisher commands described in this section in your RTF template in the specific position on the page where you want the PCL commands to render.

To use this feature, an administrator must also define the PCL printer in the Publisher printer setup page to use the PDF to PCL filter.

Note:

This feature is provided to support commands for font selection as described in the chapter, *PCL Font Selection* of the *PCL5 Printer Language Technical Reference Manual*. If you include other PCL commands (such as tray switching) in the template, the report output may produce the results desired, although these commands are not strictly supported.

Procedure Overview

This overview discusses how to embed PCL commands in a template

To embed PCL commands in a template to be invoked by your PCL printer, perform the following:

1. Define the PCL printer in the Publisher **Administration Delivery** options.
2. Include the commands in the RTF template.
3. To generate the output, schedule or run the report selecting PDF as the output type. Select the PCL printer defined in step 1 as the destination.

Embed PCL Commands in RTF Templates

Publisher supports custom PCL command embedding, which means that in addition to translating PDF documents into a sequence of PCL commands, Publisher supports specifying exact PCL commands to be included at a specific position on a PCL page.

To use this feature, include the following syntax in a template or data at the position where you want to print out the text.

```
<pcl><control><esc/>(pcl command)</control>(text or data field)<sp/>(text or data field)</pcl>
```

where

`<pcl></pcl>`: indicates the start and end of the custom PCL command sequence and the text to print using the custom command. If any text data appears before `<pcl>` or after `</pcl>`, it's printed as regular text using the font and font size in effect.


`<control></control>`: indicates the start and end of the PCL sequence. The data inserted after `</control>` is considered text data. The PCL command included between `<control>` and `</control>` is applied to it. Inserting any data between `<pcl>` and `<control>` is invalid and the data is ignored.

`<esc/>`: include `<esc/>` between `<control>` and `</control>` to escape character (ASCII 0x1b) in the output.

`<sp/>`: inserts a space. Include `<sp/>` in the text section (after `</control>` and before `</pcl>`) to insert a space character in the output.

The entire command and text sequence between `<pcl></pcl>` must be entered as a single line of text rendered by a single text-showing (TJ) operator in PDF. To insert a space, you must use `<sp/>` because the inclusion of an actual space in the text or data would separate the sequence into multiple text sequences in the PDF.

The following figure shows a sample check template with the command sequence:



The PCL command sequence in the example is

```
<pcl><control><esc/>(70X</control>ROUTING<sp/>ACCOUNT</pcl>
```

Note that (70X is the font to substitute; ROUTING and ACCOUNT are form fields mapped to the input XML data and the `<sp/>` command is used to insert the space between the routing and account numbers.

This RTF template is merged with data and converted to PDF as shown in the following figure. The PCL command sequence is displayed as regular text.

Specifications and Restrictions

The PDF to PCL converter supports input of PDF files up to version 1.7 and output of PCL 5 (including HP/GL2 and P JL) and PCL 5c.

The converter supports basic text and vector/raster graphic features in PDF that are required for most business reporting and office printing.

Note the following limitations for documents processed by the PDF to PCL converter:

- SVG graphics, such as graphs, aren't supported.
- Embedded objects (such as Flash objects) and file attachments aren't supported.
- Use of Adobe core dingbats and symbol font isn't supported. Use TrueType fonts to print dingbats and symbols and embed the font when generating PDF.
- Supports printing of the generated output on any printer that supports PCL 5/PCL 5c standard. However, the display of the generated output using PCL viewer applications or any software that re-processes PCL for other than direct printing purposes isn't supported.
- The PDF to PCL converter supports, with limitations, the conversion of PDF documents generated by the FO processor. Other PDFs, such as PDF files processed with FormProcessor or PDF documents generated by external applications may produce the printed results desired, but aren't strictly supported.
- The PDF to PCL converter supports the conversion of PDF documents generated by the PDFBookBinder and PDFDocMerger utilities so far as all the PDF documents used for generating the output are originally generated by the FOProcessor and the documents don't include restricted features.

2D Barcode Functions

You can use the QR code or PDF417 2D barcode type in RTF templates. When you create an RTF template, use the `qrcode` or `pdf417` functions to specify the barcode type. These functions don't require external fonts.

qrcode Syntax

```
<?qrcode: <DATA>; <SIZE>[; <CHARSET>]??>
```

where

DATA – Data to be encoded in the QR code format.

SIZE – QR code size dimension in points(pt).

CHARSET – (Optional) Character set for encoding the data. Default is UTF8.

pdf417 Syntax

```
<?pdf417: <DATA>[; <XSCALE>[; <COLUMNS>[; <ROWS>[; <CHARSET>]]]??>
```

where

DATA – Data to be encoded in the PDF417 format.

XSCALE – Point(pt) per PDF417 module width. Default is 1 (1pt per module).

COLUMNS – The number of columns to be used in the generated PDF417 symbol. Default is -1.

ROWS – The number of rows to be used in the generated PDF417 symbol. Default is -1.

CHARSET – (Optional) Character set to be used to encode data with the Byte compaction mode. Specify *CHARSET* only if the data contains non-Latin-1(ISO-8859-1) characters.

14

Create RTF Templates Using the Template Builder for Word

This topic describes creating RTF templates using the Template Builder for Word add-in.

Topics:

- [Overview](#)
- [Get Started Using the Template Builder](#)
- [Access Data for Building Templates](#)
- [Insert Components to the Template](#)
- [Preview a Template](#)
- [Template Editing Tools](#)
- [Upload a Template to Publisher](#)
- [Use the Template Builder Translation Tools](#)
- [Set Options for the Template Builder](#)
- [Set Up a Configuration File](#)
- [Publisher Menu Reference](#)

Overview

The Template Builder is an add-in to Microsoft Word that simplifies the development of RTF templates.

Although you don't need Template Builder to create RTF templates, it provides many functions that increase productivity.

The Template Builder is tightly integrated with Microsoft Word and enables you to perform the following functions:

- Insert data fields
- Insert tables
- Insert forms
- Insert charts
- Preview the template with sample XML data
- Browse and update the content of form fields
- Extract boilerplate text into an XLIFF translation file and test translations

The Template Builder automates insertion of the most frequently used components of an RTF template. RTF templates also support much more complex formatting and processing.

Before You Get Started

The Template Builder installation provides samples and demo files to help you get started.

The demos can be accessed from the Windows Start menu as follows:

Select **Start, Programs, Oracle Analytics Publisher Desktop, and Demos**.

You can also access the demos from the Publisher Desktop\demos folder where you installed Oracle Analytics Publisher Desktop (for example: C:\Program Files\Oracle\Publisher\Publisher Desktop\demos).

The following demos are provided:

- **TemplateBuilderDemo.exe** - Demonstrates building a report layout using many key features of the Template Builder, including: connecting to the Publisher server, loading data for a report, inserting tables and charts, and defining conditional formatting.
- **TemplateBuilderInvoice.exe** - Demonstrates how to take a prepared layout and use the Template Builder to insert the required fields to fill the template with data at runtime.
- **LocalizationDemo.exe** - Demonstrates the localization capabilities of the Template Builder and shows you how to extract an XLIFF file from the base RTF template. The XLIFF file can then be translated and the translations previewed in the Template Builder.

The sample files are located in the Publisher Desktop\Samples folder. The Samples folder contains the subfolders:

- eText templates
- Excel templates
- PDF templates
- RTF templates

The eText, PDF, and Excel template samples can be used as references to create these types of templates. The Template Builder is only available for the RTF templates. The RTF templates folder contains eight subfolders to provide samples of different types of reports. Refer to the TrainingGuide.html located in the RTF templates folder for additional information on what is contained in each sample.

Prerequisites and Limitations

Certain prerequisites and limitations apply to this feature.

Prerequisites

- The report data model created and running successfully.
- Supported versions of Microsoft Word and Microsoft Windows are installed on the client.
- The Publisher Template Builder downloaded and installed on the client.

The Template Builder can be downloaded from the Home page.

Limitations

The Template Builder doesn't support bidirectional display of text in the user interface.

Get Started Using the Template Builder

This section describes how to get started with creating RTF templates using the Template Builder for Word.

It contains the following topics:

- [Features of the Publisher Template Builder for Word](#)
- [Build and Upload a Template](#)
- [Work in Connected Mode](#)

Features of the Publisher Template Builder for Word

When you open Microsoft Word after installing the Template Builder, you see the Publisher menu. Using this you can perform different tasks.

For Microsoft Word users, the Publisher commands are displayed in the ribbon format.

Use the menu (or toolbar) to perform the following:

- Insert data fields into age RTF templates
- Insert tables, forms, charts, and pivot tables
- Preview the template in multiple outputs
- Browse and update the content of form fields
- Validate the template
- Perform calculations on fields within the template
- Connect to the Publisher catalog to retrieve data to build the template
- Upload the template to the Publisher server
- Extract boilerplate text into an XLIFF translation file and test translations

Build and Upload a Template

You can build and upload the template using a direct connection with the Publisher server, or you can build and upload the template in disconnected mode.

Work in Connected Mode

Connected mode allows you to make changes directly on the Publisher server.

To work in connected mode:

1. Open Microsoft Word.
2. From the Publisher menu, select **Log On**.

3. Enter your Publisher credentials and the URL for the Publisher server, for example: `http://www.example.com:7001/xmlpserver`. (Contact your system administrator if you do not know the URL.)
4. The Open Template dialog presents the same folder structure as the Publisher catalog. Select the report or data model for which you want to build a template.
5. If you selected a data model:

Click **Create Report** to create a report for this data model in the Publisher catalog. This is the report that you upload the template to.

Enter a Report Name and select the folder in which to save it.

Click **Save**.

The sample data from the data model is loaded to the Template Builder.

If you selected a report:

Click **Open Report** to load the data to the Template Builder; or double-click **New** in the Layout Templates pane.

Any existing templates are listed in the **Layout Templates** pane.
6. Follow the guidelines in this chapter to insert data fields and design the template using features such as tables, charts, and graphics. Use Microsoft Word to apply formatting to fonts and other objects in the template.
7. To upload the template file to the Publisher server and add it to the report definition, select **Upload Template As** from the Publisher menu.

If you haven't saved the template, then you are prompted to save it in Rich Text Format.
8. Enter a name and select a locale in the **Upload as New** dialog. This is the name that is displayed under **Layouts** in the Report Editor. This is also the layout name that is displayed when a user runs this report.
9. Configure properties for this layout.

Navigate to the Publisher report editor to configure properties for this layout, such as output formats.

Work in Disconnected Mode

To work in disconnected mode, you must have a sample data file available in the local work environment.

To work in disconnected mode:

1. Save a sample data file to your local computer.
2. Open Microsoft Word with the Template Builder installed.
3. On the Publisher menu in the **Load Data** group select **Sample XML**. Locate the sample data file in the local directory and click **Open**. The Template Builder also supports using XML Schema to design an RTF template. However, because the schema contains no data, the preview of the report also contains no data.
4. Follow the guidelines in this chapter to insert data fields and design the template using features such as tables, charts, graphics, and other layout components. Use Microsoft Word to apply formatting to fonts and other objects in the template.
5. Upload the layout template file.

In the catalog, open the report in the Report Editor. Click **Add New Layout**.

Complete the fields in the dialog and then select **Upload**. The template now appears as a layout for the report.

6. Configure properties for this layout.

Access Data for Building Templates

The data model defines the XML format that is merged with the RTF template. The Template Builder requires sample data to build the template. You must load sample data to use most of the template builder functionality.

If you are not connected to Publisher, then use the procedure in [Load XML Data from a Local File](#). If you are connected, then use the procedure in [Load Data from the Publisher Catalog](#).

Load XML Data from a Local File

One method of loading data to the Template Builder is to save a sample of the report data to a local directory.

If you do not have access to the report data model, but you can access the report, then you can alternatively save sample data from the report viewer.

To save data from the report viewer:

1. In the Publisher catalog, navigate to the report.
2. Click **Open** to run the report in the report viewer.
3. Click the **Actions** icon, then click **Export**, then click **Data**. You are prompted to save the XML file.
4. Save the file to a local directory.
5. Use the **Load Sample XML** feature below to load the saved XML file to the Template Builder.

The **Load Data** group from the Publisher menu enables you to select and load the saved XML file to the Template Builder.

- **Sample XML** - Enables you to load a sample XML file that contains all fields that you want to insert into the template as a data source. If you are not connected to the Publisher, then use this method to load the data.
- **XML Schema** - Enables you to load an XML Schema file (.xsd) that contains the fields available in the report XML data. The XML schema has the advantage of being complete (a sample XML file might not contain all the fields from the data source). For the preview, the Template Builder can generate dummy sample data for an XML Schema. However, the preview works better if you also upload real sample data.

Load Data from the Publisher Catalog

You can connect directly to Publisher to load the Publisher report data to the Template Builder to use as sample data for designing layouts.

You can also download an existing template to modify it.

To connect to Publisher and load a data source:

1. Log in to Publisher: From the Publisher menu, select **Log On**.
2. After you area logged on, you can select **Open**. The Open Template dialog launches.
3. Navigate to the folder that contains the report or data model for which you want to create a template.

When you select a report, you can either select from the **Layout Templates** to open an existing template, select **Open Report** to load just the XML sample data to create a new layout, or double-click **<New>** to load the data to the Template Builder to build a new layout.

When you select a data model, you are prompted to create a report in the catalog.

Insert Components to the Template


This section includes topics that give more information on inserting components to the template.

- [Insert a Field](#)
- [Insert a Table Using the Table Wizard](#)
- [Insert a Table or Form Using the Insert Table/Form Dialog](#)
- [Insert a Chart](#)
- [Insert a Repeating Group](#)
- [Create Grouping Fields Around an Existing Block](#)
- [Insert a Pivot Table](#)
- [Manually Edit a Pivot Table](#)
- [Insert and Edit Conditional Regions](#)
- [Insert Conditional Formatting](#)

Insert a Field

This dialog enables you to select data elements from the data source and insert them into the template.

In the Insert group select **Field** to open the Field dialog. The dialog shows the structure of the loaded data source in a tree view, as shown in the following figure:



Select a field that represents a single data field (a leaf node of the tree) and select **Insert** (you can also insert the field by dragging and dropping it into the document, or by double-clicking the field). A text form field with hidden Publisher commands is inserted at the cursor position in the template. You may either select and insert additional data fields or close the dialog by clicking the **Close** button.

About the Insert Field Dialog

The fields in the Field dialog are explained in these sections.

The **Insert Field** dialog fields are described in the following sections:

Find

For an XML document with a large and complicated structure, use the find functionality to find a specific field. Enter a partial string of the field name you are searching into the **Find** field and click **Find Next**.

The next occurrence of a data element that includes the search expression is selected. Click the **Find Next** button again to see the next occurrence.

Example

When you select a field name in the tree view, an example value for this field is shown.

Force LTR (Left-to-Right) Direction

Force LTR Direction check box is only needed if you are using the template in a language that prints the characters from right to left, such as Arabic or Hebrew.

Use this feature to force left-to-right printing for fields such as phone numbers, addresses, postal codes, or bank account numbers.


Calculation

Calculation feature enables you to perform aggregation functions on data fields, such as sum, average, count, minimum, and maximum.

For example, if you select sum for a data field, then the field shows the sum of all occurring values for this data field, depending on the grouping.

It's important to understand the grouping context (marked by **G** and **E** form fields) to know exactly which fields are accumulated. If you insert a data field with an accumulation function into a repeating section (marked by **G** and **E** processing instruction form fields), you must select **On Grouping** to accumulate the data for the occurrences within the group. If you do not want the accumulation to be restricted to the group, you must place the accumulation field outside the group.

The following figure shows a grouping context example:



Also note that the data field must be a valid XSL number for the accumulation functions to work. Formatted numbers cannot be processed by Publisher (for example a number using a thousands separator: 10,000,000.00 cannot be processed).

For more information on groups in a template using the Template Builder, see [Insert a Repeating Group](#) and [Define Groups](#).

Insert a Table Using the Table Wizard

The **Insert Table Wizard** enables you to create standard reports. On the **Insert** menu select **Table Wizard** and complete these steps.

- [Step 1: Select Report Format](#)
- [Step 2: Select Table Data](#)
- [Step 3: Select Data Fields](#)
- [Step 4: Group the Table](#)
- [Step 5: Insert a Break for the Group](#)
- [Step 6: Sort the Table](#)
- [Step 7: Click Finish](#)
- [Step 8: Customize the Table Using Microsoft Word Functionality](#)

Step 1: Select Report Format

Start by selecting the basic report format.

Choose from **Table**, **Form**, or **Free Form**. The following illustration shows examples of each format.

| Table | <table border="1"><thead><tr><th>Last Name</th><th>First Name</th><th>Phone</th></tr></thead><tbody><tr><td>Doe</td><td>John</td><td>(123) 456-7890</td></tr></tbody></table> | Last Name | First Name | Phone | Doe | John | (123) 456-7890 |
|-----------|---|----------------|------------|-------|-----|-------|----------------|
| Last Name | First Name | Phone | | | | | |
| Doe | John | (123) 456-7890 | | | | | |
| Form | <table border="1"><tbody><tr><td>Last Name</td><td>John</td></tr><tr><td>First</td><td>Doe</td></tr><tr><td>Phone</td><td>(123) 456-7890</td></tr></tbody></table> | Last Name | John | First | Doe | Phone | (123) 456-7890 |
| Last Name | John | | | | | | |
| First | Doe | | | | | | |
| Phone | (123) 456-7890 | | | | | | |
| Freeform | John Doe (123) 456-7890 | | | | | | |

Step 2: Select Table Data

An XML document can include multiple grouped data sets.

For example, a purchase order XML document may contain header level information, lines, shipments and contacts.


In this step, select the data group that contains the data that is required for the table.

For example, in the Balance Letter sample RTF template (found in the Template Builder installed files under Oracle\Oracle Analytics Publisher\Oracle Analytics Publisher Desktop\samples\RTF Templates), the sample XML file contains three data groups as follows:

- ARXCOBLX/G_CUSTOMER
- ARXCOBLX/G_CUSTOMER/G_CURRENCY
- ARXCOBLX/G_CUSTOMER/G_CURRENCY/G_INVOICES

The Table Wizard presents a list of the available data groups in the XML data file. Select the group that contains the data fields for the table.

The following illustration shows the Table Wizard Step 2: Selecting Table Data.



To build a table to list the invoices contained in the data, select:


ARXCOBLX/G_CUSTOMER/G_CURRENCY/G_INVOICES

as the data set.

Step 3: Select Data Fields

The Table Wizard presents the data fields from the selected data set.

The following illustration shows the Table Wizard Step 3: Selecting Data Fields.



Use the shuttle buttons to select the data fields to show in the table. Use the up and down arrows to reorder the fields after selecting them.


Step 4: Group the Table

This step enables you to regroup the data by a particular field.

This is optional.

For example, if you are building a table of invoices, you may want to group all invoices of a particular type or date to be grouped together in the report.

The following illustration shows the Table Wizard Step 4: Grouping the Table.



There're two options for grouping: Group Left or Group Above. Group Left creates a nested table. The Group By field displays to the left in the outer table. Group Above creates a new table for each new value of the group by field, displaying the value of the group by field as a table title.

Examples follow:

Group Left groups the group by element occurrences together, as shown in the following illustration.

| Date | Invoice | Amount | Amount Remaining |
|-----------|----------|-----------|------------------|
| 02-DEC-07 | 234 | 53.35 | 53.35 |
| 04-DEC-07 | 10020402 | 146776.07 | 146776.07 |
| | 10020403 | 172482.45 | 172482.45 |
| | 10020404 | 147740.25 | 147740.25 |
| | 10020405 | 71577.42 | 71577.42 |
| | 10020406 | 89344.81 | 89344.81 |
| | 10020407 | 223563.03 | 223563.03 |
| | 10020408 | 176353.55 | 176353.55 |
| 05-DEC-07 | 10020487 | 112902.54 | 112902.54 |
| 06-DEC-07 | 502444 | 19125 | 19125 |
| | 502445 | 12375 | 12375 |

Group Above shows the result as a table with a header, as shown in the following illustration.

Grouping Field 1

| Header 1 | Header 2 | Header 3 | Header 4 | Header 5 |
|----------|----------|----------|----------|----------|
| Data 1 | Data 2 | Data 3 | Data 4 | Data 5 |

Example of Group Above:

02-DEC-03

| Invoice | Amount | Amount Remaining |
|---------|--------|------------------|
| 234 | 53.35 | 53.35 |

04-DEC-03

| Invoice | Amount | Amount Remaining |
|----------|-----------|------------------|
| 10020402 | 146776.07 | 146776.07 |
| 10020403 | 172482.45 | 172482.45 |
| 10020404 | 147740.25 | 147740.25 |
| 10020405 | 71577.42 | 71577.42 |
| 10020406 | 89344.81 | 89344.81 |
| 10020407 | 223563.03 | 223563.03 |
| 10020408 | 176353.55 | 176353.55 |

When you select an element to group by, Publisher sorts the data by the grouping element. If the data is already sorted by the grouping element, then select the **Data already sorted** check box. This selection improves performance.

Step 5: Insert a Break for the Group

Use the **Break** option to insert either a **Page** break or **Section** break after each occurrence of this group.

Note that a **Section** break can only be created on the top-level group. The subsequent grouping options only display the **Page** break option.


A page break starts the next group on a new page; a section break starts the next group on a new page, reset page numbering, reset headers and footers, and reset any running calculations for each occurrence of the group.

Step 6: Sort the Table

You can sort the data in the table by up to four different fields.

Select a field and then define the sorting order (ascending or descending), and select the correct data type for the field. For example, if text is selected, "12" comes before "2" (alphanumerical order). If number is selected, "2" comes before "12".

The following illustration shows the Table Wizard Step 6: Sorting the Table.



Step 7: Click Finish

Click **Finish** to create the table and insert it to the Microsoft Word document.

Step 8: Customize the Table Using Microsoft Word Functionality

Customize the table by changing fonts, colors, column sizing, borders, shading, and so on, using Microsoft Word formatting commands.

Insert a Table or Form Using the Insert Table/Form Dialog

The Insert Table/Form dialog is the most flexible tool of the template builder. It allows you to perform these tasks.

- Create a simple or nested table with a variable number of rows.
- Associate a group of data elements, such as a complete invoice or a purchase order line, with a form in the document that is repeated for each occurrence of the data element.
- Select and define a layout for all the data fields in the template.
- Group or re-group the data.

The Insert Table/Form dialog shows you two tree view panes. The left pane shows the data source structure, while the right pane shows the elements that are copied to the template when you click the **Insert** button.

Select Data Fields

First select the data fields to insert in the template and then define how to format them.

Drag an XML element from the left Data Source pane to the right Template pane. If the XML element has children, you see a pop-up menu with the following options:

- Drop Single Node
- Drop All Nodes
- Cancel

Select **Drop Single Node** if you want to move only the selected node or **Drop All Nodes** if you want to move the node and all its children.

If you drag an additional data field from the left Data Source pane to the right Template pane, it's either inserted at the same level (Same Level) or below the node (Child) where you release the node. The Insert Position box defines where the node is inserted.

If you use the left mouse button for drag and drop, then the node and all children are copied. However, if you use the right mouse button for dragging, a dialog is displayed when you release the mouse button. The dialog gives you the option to copy either only the selected node or the selected node and all children.

Define the Layout

When you select an element in the right Template pane, you see its properties as well as a preview of how the node is rendered.

There're two kinds of nodes:

- Data Fields

- **Data Groups**

Data Field nodes (leaf nodes) do not have any child nodes. They represent simple attributes such as the total amount for an invoice or the subtotal for a purchase order line.

Data Group nodes (parent nodes) are nodes that do have child nodes. Typically, they don't represent data attributes, but groups of data - such as an invoice, a purchase order, a purchase order line, or a shipment.

Data Field Properties

If a Data Field node is selected, its properties are shown in the **Properties** pane. Use these options to describe how the Template Builder should display the field.

- **Calculation**

You can select one of the aggregation functions for the data fields. These functions (besides count) only have an effect when there's more than one of the data fields in the context where you use the function.

- **Force LTR (Left-to-Right) Direction**

This option is only needed if you are using the template in a language that displays characters from right to left, such as Arabic or Hebrew. Use this option to force left-to-right printing for fields such as phone numbers, addresses, postal codes, or bank account numbers.

Data Group Properties

The order in which the data elements are shown reflects the order of the columns in the table. If you want to reorder the columns, change the Insert Position box from Child to Same Level. Then drag the elements into the correct order.

If a Data Group node is selected, its properties are shown in the **Properties** pane. Use these options to describe how the Template Builder should render the group:

- **Style**

To display the data as a horizontal table with a header, select Table. To display the fields below each other with labels in a table, use Form. If you want to insert the fields into a free-form text section that should be repeated for this element, select Free Form.

- **Grouping**

Grouping is an advanced operation that allows you to group the data by a specific element in the data. For example, you might want to group all invoices by customer. You can select a child element of the selected element as a grouping criterion. See [Group Nodes](#).

- **Show Grouping Value**

This property is shown only if you selected a node created by the Grouping functionality. By default, the field you've selected to group the data by is displayed in the report. If you don't want the grouping data field displayed, then select No.

- **Sort By**

Select an element by which the data groups are sorted.

- **Sort Order**

If you selected an element for Sort By you can select if the data should be sorted either ascending or descending.

- **Sort Data Type**

If you selected an element for Sort By the data is by default sorted as text. That means that 12 is shown after 111. If the data is numeric, select Number as the sort data type.

- **Break**

This property allows you to insert a page break or a section break between every data group. If you select New Page per Element, then a page break is inserted between each element after the first occurrence.

 **Tip:**

To insert a page break before the first occurrence of an element, use Microsoft Word's page break command.

If you select New Section per Element, then a section break is created for each data group. A section break has the following effects: it inserts page break, it resets the page numbers and new data can be displayed in the header and footer. You typically use this option to print multiple documents (for example invoices or purchase orders) to a single PDF file.

Insert Tables and Forms

Once you've dragged all data fields over and defined the layout, select the Insert button to place the tables and forms at the cursor position in the document.

Group Nodes

You can group any Data Group node by any of its child Data Field Nodes. For example if you've sales data for multiple quarters, you may want to show the sales data organized by quarter. In this case you would group the sales data rows by the quarter element.

Assume the following structure:

```
Sales Transaction
  Quarter
  Customer
  Amount
```

To group the child nodes of a node (Sales Transaction), you select one of the child nodes (Quarter) as the grouping property of the parent node (Sales Transaction). The Template Builder makes this node (e.g. quarter) the parent of the other child nodes (Customer and Amount).

The new structure looks like the following:

```
Sales Transaction
  Quarter
```

Customer
Amount

The grouping criterion (Quarter) now behaves like any other Data Group Node with children. That means that you can define the layout of its children using the Create As Table, Style, Label, Grouping, and Show Grouping Value properties.

Understand the Fields Inserted to the Template

There're distinct differences between the types of fields in templates.

The Insert Table/Form Dialog creates two kinds of form fields:

- Form fields representing data elements.
- Form fields with processing instructions for repeating table rows or document sections.

Form fields representing data elements are replaced with the data when the template is processed. Form fields indicating repeating sections are shown as **for-each** and **end for-each** in the document.

If you have selected the Abbreviated form field display option, then the for-each and end for-each form fields are displayed as **F** and **E**. The section of the document encapsulated by these two elements is repeated, if the associated data element is repeated in the data.

Insert a Chart

Use the Chart dialog to insert a chart into a template.

The following figure shows the Chart dialog.




Chart Type

Publisher supports a large variety of chart types. Expand the **Type** list to select the chart type for this template.

Values

Drag and drop the data value you want to measure to the Values field (for example, SALES).

You can select multiple Value elements (measures).

The **Values** field changes depending on the Chart Type that you select:

- Combination Graph - Enables three fields for the Value selections.
- Scatter Graph - Compares pairs of values. Drag and drop the X and Y data elements to compare.
- Bubble Graph - Compares sets of three values. Similar to the scatter graph, the third value is displayed as the size of the bubble.
- Stock Graph - Drag and drop the elements that represent the Open, High, Low, Close, and Volume values for the stock graph.

Aggregation

Use the **Aggregation** option in the **Properties** pane to do functions such as sum, count, and average.

You can choose to aggregate the Values data as a sum, a count, or an average.

Labels

Drag and drop the data element for which you want to see the Value charted (for example, Year).

Select Group Data to group the occurrences of the label element before rendering it in the chart. For example, if you are charting Sales by Year, then selecting Group Data accumulates the values for Year, so that only one occurrence of each year is displayed in the chart. If you do not select Group Data, then the value for every occurrence of Year in the data is plotted separately.

Color

If you want to add a series element to the chart, then drag and drop the element to display as a series. Each value is displayed as a new color in the graph.

Chart is Inside Group

Select this box if the chart is inside a grouping and you want the chart to display data only for the occurrences of the data elements within the group.

Style

Select a color scheme and style for the chart.

Properties

The properties region enables you to change value and label display names, select color, font, and other display options for the chart.

The properties list changes depending on the chart selection.

Preview

Click **Preview** to display the chart with the sample data.

Group Data

By default the data is grouped by the Value element and aggregated by sum.

If you deselect the **Group Data** check box, then each occurrence of the value element is charted and aggregation functions are not available.

Edit an Inserted Chart


To edit a chart that you've already inserted into the template, right-click the chart and select Publisher Chart from the menu. This invokes the chart dialog to enable you to edit the chart.

Insert a Repeating Group

Follow these steps to insert a repeating group.

To insert a repeating group:

1. Select the section of the template that contains the elements you want repeated.
2. On the Publisher menu, in the Insert group, click **Repeating Group**.
3. Enter the appropriate fields in the Publisher Properties dialog, as shown in the following figure:



For Each

Select the element that for each occurrence, you want the loop to repeat. When you select the For Each data field you are telling Publisher that for each occurrence of the selected field in the data you want the elements and processing instructions contained within the loop to be repeated.

For example, assume that the data contains invoice data for customers and you want to create a table with each customer's invoices. In this case, for each customer number you want the table to repeat. You would therefore select the customer number in the For Each field to create a new loop (or group) for each customer.

Note the following about creating repeating groups:

- For loops and groupings not inside another group (that is, outer groups or loops) you must select the repeating XML element to be used. For example if the data set is flat, the only repeatable element is `/DATA/ROWSET/ROW`. In cases with multiple data sources or hierarchical XML you can choose the data set.
- If you are creating nested groups (inserting a loop or group inside of another loop in the template), the **For Each** field isn't updatable because it's already

defined by the preexisting outer loop. The **For Each** field is displayed as Group Item to inform you that an outer group is already defined.

Absolute Path

Select this check box to use the Absolute Path to the element in the XML structure. This is important if the data contains the same element name grouped under different parent elements.

Group By

Select a field from the list by which you want to group the data. If you just want to create a simple loop, do not select a group by element. Selecting a group by element actually regroups the data into a new hierarchy based on the group by element.

Break

Use this option to create either a Page break or Section break if you want to insert a break after each occurrence of this group.

A Section break can only be created on outer groups that surround the whole document. If the selected field isn't an outer group, the Section break option isn't available.

Note also that when you insert a section break, the page numbering is reset, headers and footers are reset, and any running calculations are reset for each occurrence of the group.

4. To sort the grouped data, select the **Sorting** tab. You can select up to four sort-by fields. For each sort by field, select the following:

Sort order - Select Ascending or Descending.

Data Type - Select Number or Date/Text. It's important that you select the correct data type to achieve the expected sort order.

If you are sorting by four criteria and the XML data element names are long, then you might exceed the character length limitation (393 characters) of the Microsoft Word form field.


5. The **Advanced** tab enables you to edit the code directly and to enter **Text to display** for the field.

The Code region displays the code and processing instructions that the Template Builder has inserted for the field. You can edit this if you want to change the processing instructions for this field.

The **Text to display** field shows how this field displays in the template. You can choose to enter descriptive text to enable you to understand each field better when reading the template, or you can enter abbreviated text entries that are less intrusive to the look and feel of the template.

You can set the default display text as Descriptive or Abbreviated using the **Options** tab.

The following figure shows the **Advanced** tab of the Publisher Properties dialog.



- When you've completed the dialog options, click **OK**. This inserts the form fields in the template. By default, the beginning for-each form field displays the text "F" and is inserted at the beginning of the selected template section. At the end of the selection, an "E" form field is inserted to denote the end of the repeating group.

Create Grouping Fields Around an Existing Block

Follow these steps to create a group around an existing block of text or elements in a template.


- Select the block of text. For example, a table row.
If any preexisting Publisher tags are included in the block, then you must include the beginning and ending tags. For example, if the block contains any opening for-each, if, or for-each-group tags, then you must include the end for-each, end-if, and end for-each-group tags in the selection.
- On the Publisher menu, on the Insert group, click **Repeating Group**.
- In the Properties dialog, enter the fields to define the repeating group.
- Click **OK** to insert the grouping fields around the block. For example, if the block is a table row, then the begin field is inserted at the beginning of the first cell and the end field is inserted at the end of the last field.

Insert a Pivot Table


Follow these steps to insert a pivot table.

To insert a pivot table:


- On the Publisher menu on the **Insert** group, click **Pivot Table**. The Pivot Table dialog presents the data in the left pane with empty Layout panes on the right for you to drag and drop data elements. The following figure shows the Pivot Table dialog.



2. Drag and drop the elements from the Data pane to the Layout pane to build the pivot table structure. In the following figure, the layout shows Sales by Industry accumulated by Year and by Month:




3. Use the Properties pane to select **Aggregation**. You can choose Sum, Count, or Average. Then choose a number **Format**, as shown in the following figure:



- By default subtotals for rows and columns are displayed. You can choose not to display the subtotals by setting the properties to False.

The following figure shows the properties for setting totals and subtotals.



- Click **Preview** to see how the pivot table is displayed before you insert it into the template. Click **OK** to insert the pivot table into the template. The following figure shows how the pivot table is displayed in the template.

| CH | | G | Total |
|--------|---------|------------|---------|
| G YEAR | | INDUSTRIYE | |
| B | G MONTH | G 999.00E | 999.00E |
| | | G 999.00E | 999.00 |

At runtime, this pivot table is generated as shown in the following table:

| | | Building material & garden eq. & supplies dealers | Clothing & clothing accessories stores | Electronics & appliance stores | Food services & drinking places | Food & beverage stores | Furniture & home furnishings stores |
|------|----------|---|--|--------------------------------|---------------------------------|------------------------|-------------------------------------|
| 2006 | | 48,531.00 | 31,528.00 | 15,472.00 | 61,967.00 | 81,303.00 | 17,073.00 |
| | February | 23,146.00 | 15,611.00 | 7,710.00 | 30,803.00 | 40,449.00 | 8,418.00 |
| | March | 25,385.00 | 15,917.00 | 7,762.00 | 31,164.00 | 40,854.00 | 8,655.00 |
| 2007 | | 79,625.00 | 48,991.00 | 24,726.00 | 99,088.00 | 127,991.00 | 26,468.00 |
| | February | 26,369.00 | 16,497.00 | 8,320.00 | 33,239.00 | 42,723.00 | 8,859.00 |
| | January | 26,480.00 | 16,316.00 | 8,114.00 | 32,852.00 | 42,553.00 | 8,805.00 |
| | March | 26,776.00 | 16,178.00 | 8,292.00 | 32,997.00 | 42,715.00 | 8,804.00 |
| | | 128,156.00 | 80,519.00 | 40,198.00 | 161,055.00 | 209,294.00 | 43,541.00 |

Manually Edit a Pivot Table

This section describes the code inserted by the pivot table builder.

When the Template Builder inserts the pivot table, it inserts a Publisher command of the following structure:

```
<?crosstab: ctvarname; "data-element"; "rows"; "columns"; "measures"; "aggregation"?>
```

| Parameter | Description | Example |
|--------------|---|---------|
| Ctvarname | Crosstab variable name. This is automatically generated by the Add-in. | C123 |
| data-element | This is the XML data element that contains the data elements to include in the pivot table. If the pivot table is inside a repeating group, this field must be manually edited to achieve the expected results. See the table following this section. | "//ROW" |

| Parameter | Description | Example |
|-------------|--|--|
| rows | <p>This parameter defines the XML elements for row headers. The ordering information is specified within "{" and "}". The first attribute is the sort element. If not specified, the row header element is used as the sort element.</p> <p>Supported attributes are:</p> <ul style="list-style-type: none"> o - specifies the sort order. Valid values are "a" for ascending or "d" for descending. t - specifies the data type. Valid values are "t" for text or "n" for numeric. <p>You can specify more than one sort element, for example:</p> <pre>"emp-full-name {emp-lastname,o=a,t=n}{emp-firstname,o=a,t=n}"</pre> <p>sorts employee by last name and first name. Note that the sort element can be any element in the data set, and doesn't have to be included in the pivot table. In the preceding example, emp-lastname and emp-firstname don't have to be elements included in the pivot table.</p> | <pre>"REGION{,o=a,t=t}, DISTRICT{,o=a,t=t}"</pre> <p>In the example, the first row header is "REGION". It's sorted by "REGION", order is ascending, and type is text. The second row header is "DISTRICT". It's sorted by "DISTRICT", order is ascending, and type is text.</p> |
| columns | <p>This parameter defines the XML elements for column headers. The ordering information is specified within "{" and "}". The first attribute is the sort element. If not specified, the column header element is used as the sort element.</p> <p>Supported attributes are:</p> <ul style="list-style-type: none"> o - specifies the sort order. Valid values are "a" for ascending or "d" for descending. t - specifies the data type. Valid values are "t" for text or "n" for numeric. <p>You can specify more than one sort element, for example:</p> <pre>"emp-full-name {emp-lastname,o=a,t=n}{emp-firstname,o=a,t=n}"</pre> <p>sorts employee by last name and first name. Note that the sort element can be any element in the data set, and doesn't have to be included in the pivot table. In the preceding example, emp-lastname and emp-firstname don't have to be elements included in the pivot table.</p> | <pre>"ProductsBrand{,o=a,t=t}, PeriodYear{,o=a,t=t}"</pre> <p>In the example, the first column header is "ProductsBrand". It's sorted by "ProductsBrand"; the order is ascending, and type is text. The second column header is "PeriodYear". It's sorted by "PeriodYear"; the order is ascending, and type is text.</p> |
| measures | <p>This parameter defines the XML elements used as measures.</p> | <pre>"Revenue, PrevRevenue"</pre> |
| aggregation | <p>This parameter specifies the aggregation function. Currently, the only supported value is "sum".</p> | <pre>"sum"</pre> |

Example

This example uses the following XML data:


```

- <ROWSET>
- <ROW>
  <Productstype>COATINGS</Productstype>
  <Productsbrand>Enterprise</Productsbrand> <Region>CENTRAL REGION</
Region>
  <District>CHICAGO DISTRICT</District>
  <PeriodYear>1998</PeriodYear>
  <Revenue>1555548.0</Revenue>
  <PrevRevenue>125968</PrevRevenue>
  <Units>11</Units>
</ROW>
...
</ROWSET>

```

The full data set includes four values for ProductsBrand, four values for Region, and two values for PeriodYear to be displayed in the pivot table.

Using the Template Builder for Word and the sample XML file you can create a pivot table as shown in the following illustration.



The generated XDO command for this pivot tables is as follows:

```

<?crosstab:c4536;"/ /
ROW"; "Region{ ,o=a,t=t} ,District{ ,o=a,t=t}"; "PeriodYear{ ,o=a,t=t} ,Product
sBrand{ ,o=a,t=t}"; "Revenue ,PrevRevenue"; "sum"?>

```

Running the command on the given XML data files generates this XML file "cttree.xml". Each XPath in the "cttree.xml" is described in the following table. The information in the table is to help you understand how Publisher constructs the pivot table. The generated cttree.xml file isn't accessible for viewing or updating.

| Element | XPath | Count | Description |
|---------|---------------------|-------|---|
| C0 | /cttree/C0 | 1 | This contains elements which are related to column. |
| C1 | /cttree/C0/C1 | 4 | The first level column "ProductsBrand". There're four distinct values, shown in the label H element. |
| CS | /cttree/C0/C1/CS | 4 | The column-span value. It's used to format the pivot table. |
| H | /cttree/C0/C1/H | 4 | The column header label. There're four distinct values "Enterprise", "Magicolor", "McCloskey" and "Valspar". |
| T1 | /cttree/C0/C1/T1 | 4 | The sum for measure 1, which is Revenue. |
| T2 | /cttree/C0/C1/T2 | 4 | The sum for measure 2, which is PrevRevenue. |
| C2 | /cttree/C0/C1/C2 | 8 | The first level column "PeriodYear", which is the second group-by key. There're two distinct values "2001" and "2002". |
| H | /cttree/C0/C1/C2/H | 8 | The column header label. There're two distinct values "2001" and "2002". Because it's under C1, the total number of entries is $4 \times 2 = 8$. |
| T1 | /cttree/C0/C1/C2/T1 | 8 | The sum for measure 1 "Revenue". |
| T2 | /cttree/C0/C1/C2/T2 | 8 | The sum for measure 2 "PrevRevenue". |
| M0 | /cttree/M0 | 1 | This contains elements that are related to measures. |
| M1 | /cttree/M0/M1 | 1 | This contains summary for measure 1. |
| H | /cttree/M0/M1/H | 1 | The measure 1 label, which is "Revenue". |
| T | /cttree/M0/M1/T | 1 | The sum of measure 1 for the entire Xpath from "//ROW". |
| M2 | /cttree/M0/M2 | 1 | This contains summary for measure 2. |
| H | /cttree/M0/M2/H | 1 | The measure 2 label, which is "PrevRevenue". |
| T | /cttree/M0/M2/T | 1 | The sum of measure 2 for the entire Xpath from "//ROW". |
| R0 | /cttree/R0 | 1 | This contains elements that are related to row. |
| R1 | /cttree/R0/R1 | 4 | The first level row "Region". There're four distinct values, shown in the label H element. |
| H | /cttree/R0/R1/H | 4 | This is the row header label for "Region". There're four distinct values "CENTRAL REGION", "EASTERN REGION", "SOUTHERN REGION" and "WESTERN REGION". |
| RS | /cttree/R0/R1/RS | 4 | The row-span value. It's used to format the crosstab table. |
| T1 | /cttree/R0/R1/T1 | 4 | The sum of measure 1 "Revenue" for each distinct "Region" value. |
| T2 | /cttree/R0/R1/T2 | 4 | The sum of measure 1 "Revenue" for each distinct "Region" value. |
| R1C1 | /cttree/R0/R1/R1C1 | 16 | This contains elements from combining R1 and C1. There're 4 distinct values for "Region", and four distinct values for "ProductsBrand". Therefore, the combination is $4 \times 4 = 16$. |

| Element | XPath | Count | Description |
|---------|-------------------------------|-------|---|
| T1 | /cttree/R0/R1/R1C1/T1 | 16 | The sum of measure 1 "Revenue" for each combination of "Region" and "ProductsBrand". |
| T2 | /cttree/R0/R1/R1C1/T2 | 16 | The sum of measure 2 "PrevRevenue" for each combination of "Region" and "ProductsBrand". |
| R1C2 | cttree/R0/R1/R1C1/R1C2 | 32 | This contains elements from combining R1, C1 and C2. There're 4 distinct values for "Region", and four distinct values for "ProductsBrand", and two distinct values of "PeriodYear". Therefore, the combination is $4 \times 4 \times 2 = 32$. |
| T1 | /cttree/R0/R1/R1C1/R1C2/T1 | 32 | The sum of measure 1 "Revenue" for each combination of "Region", "ProductsBrand" and "PeriodYear". |
| T2 | /cttree/R0/R1/R1C1/R1C2/T2 | 32 | The sum of measure 2 "PrevRevenue" for each combination of "Region", "ProductsBrand" and "PeriodYear". |
| R2 | /cttree/R0/R1/R2 | 18 | This contains elements from combining R1 "Region" and R2 "District". Because the list of values in R2 has dependency on R1, the number of entries isn't just a simple multiplication. |
| H | /cttree/R0/R1/R2/H | 18 | The row header label for R2 "District". |
| R1N | /cttree/R0/R1/R2/R1N | 18 | The R2 position number within R1. This is used to check if it's the last row, and draw table border accordingly. |
| T1 | /cttree/R0/R1/R2/T1 | 18 | The sum of measure 1 "Revenue" for each combination "Region" and "District". |
| T2 | /cttree/R0/R1/R2/T2 | 18 | The sum of measure 2 "PrevRevenue" for each combination of "Region" and "District". |
| R2C1 | /cttree/R0/R1/R2/R2C1 | 72 | This contains elements from combining R1, R2 and C1. |
| T1 | /cttree/R0/R1/R2/R2C1/T1 | 72 | The sum of measure 1 "Revenue" for each combination of "Region", "District" and "ProductsBrand". |
| T2 | /cttree/R0/R1/R2/R2C1/T2 | 72 | The sum of measure 2 "PrevRevenue" for each combination of "Region", "District" and "ProductsBrand". |
| R2C2 | /cttree/R0/R1/R2/R2C1/R2C2 | 144 | This contains elements from combining R1, R2, C1 and C2, which gives the finest level of details. |
| M1 | /cttree/R0/R1/R2/R2C1/R2C2/M1 | 144 | The sum of measure 1 "Revenue". |
| M2 | /cttree/R0/R1/R2/R2C1/R2C2/M2 | 144 | The sum of measure 2 "PrevRevenue". |

Insert a Pivot Table in a Repeating Group

When you create a pivot table inside a repeating group you must manually edit the pivot table code so that the elements included in the pivot table respect the grouping context. The edit to the code depends on how you grouped the data.

Procedure When Using the Template Builder "Group by" Feature

If your data is flat and you used the Template Builder's Group By feature to group your data, then use this procedure. After inserting the pivot table, open the Publisher Properties dialog to view the `<?crosstab...?>` code. In the `crosstab` command, update the data-element component to `current-group()`.

For example, assume in the preceding example you created a repeating group around the pivot table that is grouped by the `<Region>` element.

To edit the pivot table code:

1. Select and right-click the inserted pivot table. From the menu, select **BI Publisher Properties** to view the `<?crosstab...?>` command. Alternatively, open the Template Builder **Field Browser** and select the `<?crosstab:...?>` command.
2. Replace the data-element component with `"current-group()"`. For example, in the sample, the data-element value is `"//ROW"`. Replace the value `"//ROW"` with `"current-group()"` as follows:

```
<?crosstab:c4536;"current-
group();" "Region{,o=a,t=t},District{,o=a,t=t}"; "PeriodYear{,o=a,t=t}
,ProductsBrand{,o=a,t=t}"; "Revenue,PrevRevenue"; "sum"??>
```

This applies the XDO `crosstab` command only across the current group to return the expected values in the pivot table.

Example 14-1 Procedure When the Data is Already Grouped

If the data input to the Template Builder is already grouped, then you must insert the appropriate XPath for the data-element component to ensure that the pivot table only includes the elements in the current group.

For example, assume the data for this report is structured as follows:

```
<ROWSET> <REGION>
  <RegionName>CENTRAL REGION</RegionName>
  <ProductList>
    <Product>
      <ProductsBrand>Enterprise</ProductsBrand>
      <District>CHICAGO DISTRICT</District>
      <PeriodYear>2001</PeriodYear>
      <Revenue>1555548.0</Revenue>
      <PrevRevenue>125968</PrevRevenue>
      <Units>11</Units>
    </Product>
```

In your template you insert a repeating group based on the `<REGION>` element. When you insert the pivot table within the repeating group, the code appears as

```
<?crosstab:c10959;"//
Product"; "District{,o=a,t=t},ProductsBrand{,o=a,t=t}"; "PeriodYear{,o=a,t
=t}"; "Revenue,PrevRevenue"; "sum"??>
```

In this case, to instruct Publisher to use only the elements under the current REGION grouping, edit the data-element to use the relative XPath as follows: `../Product`. The edited code is:


```
<?crosstab:c10959;" .//  
Product"; "District{ ,o=a,t=t},ProductsBrand{ ,o=a,t=t}"; "PeriodYear{ ,o=a,t  
=t}"; "Revenue,PrevRevenue"; "sum"?>
```

Insert and Edit Conditional Regions

A conditional region is an area that is surrounded by a conditional statement. If the statement tests true, the area is displayed in the report; if the condition tests false, the area is suppressed from the report.

For example, the data contains sales information. The report contains a table that displays sales by industry. You want this table in the report to display information for industries sales with sales amounts lower than 100,000. Using the insert conditional region functionality, you can select the region that contains the sales table and insert the condition that the sales element must be less than 100,000.

1. Select the region that you want to apply the condition to. For example, if you want to display a table only for a certain condition, then select the region that contains the table. Note that the region must be inside a loop.
2. On the Publisher menu, on the Insert group, click **Conditional Region**. The following figure shows the Publisher Properties dialog for a Conditional region.



3. Enter the following fields:

Data Field - Select the field to test for the condition. Select the data type of the field: Number or Date/Text.

(Condition 1) Data field - Select the comparison operator.

Select the value to meet the condition. Note that you can enter an integer, enter text, or select another data element to define a comparison based on the incoming values.

4. Click **OK**. The form fields that contain the conditional logic are inserted around the region. The beginning form field displays the text "C" and the form field closing the region displays the text "EC".

To edit the conditional region, double-click the inserted form field to launch the dialog for editing; or, right-click the form field and select **BI Publisher**, then **Properties**.

Insert Conditional Formatting

Using the Conditional Format feature you can insert simple conditional formats to apply to table rows or cells. The dialog provides several common options that you can select and the Template Builder inserts the code automatically. The Conditional Format dialog supports two conditions per field.

The Conditional Format dialog cannot be used inside of pivot tables. You must insert the conditional formatting logic directly to the appropriate form fields.

To insert a conditional format:

1. Place the cursor in the table cell of the data element for which you want to define the condition.
2. On the Publisher menu, on the Insert group, click **Conditional Format**.
3. Enter the following in the Conditional Format dialog

Data Field - Select the element to test for the condition and the data type of the element (Number or Date/Text).


Apply to Entire Table Row - If you want the format applied to the entire table row, not just the cell of the selected element, then select this box.

Condition 1) Data field - Select the comparison operator.

Select the value to meet the condition. You can enter an integer, enter text, or select another data element to define a comparison based on the incoming values.

4. Click **Format** to define the format you want to apply when the condition is met. Options are background color, font color, and font style (regular, bold, italic, bold italic). Select the box and format of each option you want to apply. After you select the format, the Preview region displays the format chosen.

The following figure shows the Format dialog.



5. Define a second condition if desired.
6. Click **OK**. The conditional format field is inserted as a form field with the display text "C".

To edit the conditional format, double-click the inserted form field to launch the dialog for editing; or, right-click the form field and select **Publisher**, then **Properties**.

Preview a Template

The Preview menu group enables you to preview the RTF template with sample XML data.

From the Preview group, select the output format. If you haven't saved the template as an RTF file, then you are prompted to do so. Ensure that you've loaded sample data to the Template Builder to preview the report.

- **PDF**

You must have Adobe Acrobat Reader version 5.0 or higher installed to preview documents in PDF format.

- **HTML**

Launches the default browser to display the report.

- **EXCEL**

To use this option, you must have Microsoft Excel 2003 or later. If you have Excel 2007, this option generates the document in .xlsx, the default Office Excel 2007 XML-based file format.

If you have Excel 2003 this option generates the document in MHTML and opens the document in Excel.

- **EXCEL 2000**

Generates HTML and launches Microsoft Excel to render it. Embedded images such as charts and logos are not supported in this output type. If you do not have Microsoft Excel 2003 or later, use this option.

- **RTF**

Generates the report in Rich Text Format.

- **PowerPoint**

Requires Microsoft PowerPoint 2003 or 2007.

Template Editing Tools

This section describes additional tools provided with the Template Builder to help you validate and edit the template.

This section includes:

- [Edit and View Field Properties](#)
- [Validate a Template](#)
- [Use the Field Browser](#)
- [Check Accessibility](#)

Edit and View Field Properties

Once you've inserted a data field, you can view or edit the field properties in the Publisher Properties dialog.

You can also insert a field.

To invoke the Publisher Properties dialog, perform one of the following:

- Double-click the field
- Right-click the field, from the menu select Publisher, then **Properties**

About the Properties Tab

Publisher **Properties** tab defines the different fields and options available in the **General**, **Formatting**, and **Data Aggregation** panes of the tab.

You can set the following properties for a data field:

Data Field - Select the data field from the list of available fields from the loaded data source.

Text to Display - Enter the display text for the form field in the template. This text is replaced at runtime by the value in the data.

Type - Select the type of data. Options are **Regular Text**, **Number**, **Date**, **Current Date**, and **Current Time**. The selection in this field determines the format options.

Format - For any data type except Regular Text, you can select from several number or date display formatting masks or enter your own.

Force LTR - (Force Left-to-Right) Use this check box when you are publishing the template in a language that prints the characters from right to left, such as Arabic or Hebrew. Use this option to force left-to-right printing for fields such as phone numbers, addresses, postal codes, or bank account numbers.

Function - This feature enables you to perform aggregation functions (Sum, Average, Count, Minimum, Maximum) on data fields. For example, if you select sum for a data field, then the field shows the sum of all occurring values for this data field depending on the scope.

Scope (informational only) - This field has two possible values:

- **Group Item** - Indicates that the data field is inside a group. If you choose to perform a function on the field, then only the occurrences of the field within the current group are included in the aggregation.
- **Normal** - Indicates that the field isn't inside a group. Aggregation functions are performed on all occurrences of the field in the data.

About the Advanced Tab

The **Advanced** tab displays the underlying code.

If the code pattern within the form field isn't recognized (for example, because you added commands manually to the field), then the Publisher Properties dialog displays this tab only.

Use this tab to edit or add code to the form field manually. Click **OK** to update the template.

About the Word Properties Button

The **Word Properties** button opens the Microsoft Word Text Form Field Options dialog. You can also use this dialog to set the data type and number format.

The underlying code used by Publisher is also available by clicking the **Add Help Text** button.

Validate a Template

The Template Builder provides a validation tool to check the template for incorrect use of Publisher commands and unsupported elements in the RTF file.

To validate the template:

- On the Publisher menu, on the Tools group, click **Validate Template**.

If there're no validation errors, then a "No Error found" message is returned. If an error is found, then an error message is displayed. You can use the Field Browser to help locate the error.


Use the Field Browser

The Field Browser dialog provides a fast way to review and update the Publisher instructions hidden in the Microsoft Word form fields.

This dialog is particularly useful to understand and modify existing templates.

On the Tools group, click **Field Browser**.

The following illustration shows the Field Browser dialog.



The Field Browser dialog shows a table with the display text of the form field in the Text column and the underlying code instructions in the second Code column. When you select a specific row in the dialog, the matching form field is selected in the Microsoft Word document.

If you select some part of the text before opening the Field Browser, then the dialog shows only the fields in the selection. If no text is selected, then the field browser shows all fields in the document.

The options in the Field Browser are described in the following table.

| Option | Description |
|----------|---|
| Edit | You can update processing instructions directly from the Field Browser dialog. Select a field in the Text table. The Edit box shows the processing instructions for the field. To change the instructions for the field modify the text in the Edit field and click Update . |
| Refresh | The Field Browser dialog isn't aware of any form fields that you've added or modified while the dialog is open. Click Refresh to show any changes to the document since the Field Browser dialog has been opened. |
| Show All | If you opened the browser with a part of the document selected, then you see only the form fields in the selected area. Click Show All to see all the form fields in the document. |
| Close | Click Close to close the field property browser. The only button doesn't automatically update any changes in the edit field, therefore ensure that you select Update if you want to save edits. |

Check Accessibility

The Template Builder provides an accessibility checker to check the template for features to enhance the accessibility of the report for report consumers who may need assistive technologies to view the report.

To check for the presence of accessibility features: On the Publisher tab, in the **Tools** group, click **Check Accessibility**. The tool generates a report that indicates areas of a template that do not include the following accessibility features:

- document title
- alternative text for images
- table summary for data tables
- column header for data tables
- row header for data tables

In some cases the accessibility checker cannot determine if the accessibility feature is present and generates a warning. The report designer can then verify that the accessibility features are present.

For information on how to add these features to the template, see [Design Accessible Reports](#).

Upload a Template to Publisher

If you used the Open Template dialog to connect to Publisher, and load the data to the Template Builder, or if you downloaded an existing template from the Publisher catalog, then you can upload the new or updated layout back to the report definition on the server.

See [Work in Connected Mode](#).

If you downloaded an existing template and want to upload the modifications to the template, then select **Upload Template** from the Publisher menu.

If this is a new template for the report definition, then use the **Upload Template As** option to upload the layout to the report definition on the server. Also use this option to upload modifications to an existing template under a different name.

Use the Template Builder Translation Tools

Translation is simplified by using Template Builder tools.

The Template Builder provides tools to help you create and test translations for templates.

About Translations

The section describes options for adding translated templates to a report.

There're two options for adding translated templates to a Publisher report definition:

- Create a separate RTF template that is translated (a localized template)

- Generate an XLIFF file from the original template (at runtime the original template is applied for the layout and the XLIFF file is applied for the translation)

Use the first option if the translated template requires a different layout from the original template.

If you only require translation of the text strings of the template layout, use the XLIFF option.

For detailed information, see [Translation Support Overview and Concepts](#).

To use the Template Builder translation tools to create templates for translations, see the following topics in this section:

- [Extracting Text to an XLIFF File for Translation](#)
- [Previewing a Translation](#)
- [Localizing a Template](#)

For a demo on Publisher's localization capabilities, see the LocalizationDemo.exe demo provided with the Template Builder installation (located in the Publisher\Oracle Analytics Publisher Desktop\demos folder where you installed Oracle Analytics Publisher Desktop).

Extract Text to an XLIFF File for Translation

This menu item allows you to create a standard XLIFF translation file that contains the boilerplate text from the template. XLIFF is a standard file format that is understood by many translation software packages. Since an XLIFF is an XML file, you can translate the text in a regular text editor.

A *translatable string* is any text in the template intended for display in the published report, such as table headers and field labels. Text supplied at runtime from the data isn't translatable, nor is any text that you supply in the Microsoft Word form fields.

To extract text to an XLIFF file for translation:

1. From the Publisher menu, select **Tools**, then **Translate Template**, then **Extract Text**.
2. You are prompted to save the extract file as an XML file type. Enter a name for the extract file and save to the desired location.
3. If you want to translate the template manually, open the .xlf file using a text editor and enter the translated strings in the file.
4. When done, you can preview the translation. Then upload the file to the Publisher report definition.

Preview the Template and Translation File

You can preview the translation of a template as a PDF file.

To preview the template with the translated XLIFF file applied:

1. From Publisher, in the Tools group, click **Translation**, then **Preview Translation**.
2. You are prompted to select the saved XLIFF file. Locate the file, and click **Open**.

The Template Builder merges the sample data, the translation file, and the RTF template to generate a PDF for preview.

Localize a Template

Localizing a template means that you are creating a template to be used for a specific language.

Because Publisher enables you to extract the boilerplate text strings from a template into an XLIFF file that can be translated and then applied at runtime, if the reports for additional languages only require the translation of these text strings, then you only need to supply translated XLIFF files to accompany the base template.

However, you would localize a template when the requirements for the report in the specific language go beyond the simple translation of the text in the layout.

To save a template as a localized template:

1. From the Publisher menu, in the Tools group, select **Translations**, then **Localize Template**. This invokes a warning message that localizing the template overwrites the template. Click **OK**.
2. You are prompted to select the XLIFF translation file. Locate the appropriate file and click **Open**.

The translated XLIFF file is applied to the template that you currently have open in Microsoft Word.

3. Save the localized template.
4. Upload the template file to the appropriate report definition in the catalog. Select the appropriate locale in the upload dialog.

Set Options for the Template Builder

Use the Options dialog to specify template settings.


Access the Options dialog as follows: In the **Options** group, click **Options**.

The Options dialog contains four tabs: UI, Preview, Build, and Connection, as described in the following sections.

Set UI Options

Use the Options dialog: UI tab to set options that influence the look and feel of the Template Builder.

The following illustration shows the Options dialog: UI tab.




The tree view that shows the data source can show either the correct XML tag names of the data source or they can show a slightly modified version that is easier to read. Select the option **Element Names for Report XML** to show the modified labels. These labels contain no <> characters, use "Title case" and use spaces (" ") instead of underscores ("_").

Set Preview Options

The Options dialog: Preview tab allows you to specify options that influence the Preview functionality of the Template Builder.

The following illustration shows the Options dialog: Preview tab.




The following table describes the options available from the Preview tab.

| Option | Description |
|----------------|---|
| Style Template | If you have a Publisher Style Template available locally, then you can specify it here. A style template is an RTF template that contains style information that can be applied to RTF layouts, similar to a style sheet. The style information in the style template is applied to RTF layouts at runtime to achieve a consistent look and feel across your enterprise reports. For more information, Create and Implement Style Templates . |
| Locale | You can choose the language and territory used for previewing the template. While this change doesn't automatically translate any files, it's important to set the correct locale for the preview to use the correct direction of the text (left-to-right or right-to-left), and to correctly set locale-specific date, number, and currency formats. |
| Java Home | The Preview (and export functionality) requires Java code. You can change the path to the JAVA HOME directory. If you don't specify this option, the Template Builder assumes that the Java virtual machine (java.exe) is accessible in the PATH specified in the environment variables of Windows. |
| Java Option | Specify the memory to reserve for the Template Builder to process the template. The default value is -Xmx256M. |

Set Build Options

Use the Options dialog: Build tab to specify options that influence how the Template Builder generates tables and forms.

The following illustration shows the Options dialog: Build tab.



The following table describes the options available from the Build tab.

| Option | Description |
|----------------------------|---|
| For-each form field | <p>Select how the Template Builder creates the form fields for processing instructions in the Insert Table/Form dialog.</p> <p>The Descriptive option (for example: for-each Invoice) renders a descriptive form field for the processing instructions. This option makes the layout template easier to understand. However, the longer fields may distract from the visual layout of the template. Note that the descriptive option doesn't apply to fields within table cells.</p> <p>The Abbreviated option (for example: F) provides a one letter abbreviation for each instruction.</p> <p>Select the Hidden box to generate the processing instruction form fields using Microsoft Word's hidden font effect. Hidden text is hidden in the Print Preview and you may display or hide the hidden text by changing the Hidden Text setting in the Display group of the Microsoft Word Options.</p> |

| Option | Description |
|---|--|
| Form Field Size | <p>Large - inserts the code to a document variable. The document variable field can accommodate approximately 48 kilobytes of code line.</p> <p>This setting affects only fields that are created or edited while this option is set. The form fields created with the Large setting cannot be understood by Publisher 10g. If the template is intended for use with the 10g version of Publisher, use the Backward Compatibility setting.</p> <p>Backward Compatible - in previous versions of the Template Builder the Publisher code was inserted to the Microsoft Word Form Field Help Text box. This limited the length of code that could be inserted for a single form field. By default, the Large option is used because it can accommodate much larger code strings. However, the Large option isn't compatible with Publisher10g.</p> |
| Table Header Color | When you insert a table using the Table Wizard or the Insert Table/Form dialog the Template Builder applies the Table Header Color specified here to the table header background. Customize the default color for the templates. |
| Generate XSLT 2.0 compliant code | <p>Publisher uses the XSLT processor provided by Oracle XDK 11.1.0.7.0, which supports the W3C XSL Transformations 1.0 recommendation. The processor also implements the current working drafts of the XSLT and XPath 2.0 standards.</p> <p>By default, Publisher is compatible with XSLT 1.0. If you want to use XSLT and XPath 2.0 features in the template, then enable this option. This configuration is performed at the template level. The template-level setting overrides the server setting.</p> |

Set Connection Options

Options on this tab are reserved for a future release.

Set Up a Configuration File

The Template Builder can be used with a Publisher configuration file.

The configuration file must be named xdoconfig.xml and must be stored in the config directory (example path: C:\Program Files\Oracle\BI Publisher Desktop\Template Builder for Word\config) under the Publisher directory.

Alternatively, you can use the file name xdo.cfg, which is used by the Publisher server. The configuration file allows you to:

- Define additional fonts such as Windings to test the templates
- Use security settings for PDF files

Publisher Menu Reference

After you install the Template Builder, the next time you open Microsoft Word, you see the Publisher menu.


If the Publisher menu isn't available after you install the Template Builder, modify the Add-In settings.

About the Online Group

The Online group of commands enable you to initiate interaction with the Publisher application.

For more information about working with the online commands, see [Work in Connected Mode](#).

The following figure shows the Online group of commands.



The following table describes the commands available for the Online group.


| Command | Description |
|---------------------------|---|
| Log on | Enables you to log in to Publisher. Enter your user name and password. Select or enter the URL for the Publisher Report Server (see your Administrator if you do not know the URL). When you log on, the Open Template dialog is displayed. You must log in directly to the Publisher server. For example: <code>http://www.example.com:7001/xmlpserver.</code> |
| Open | After you log on, this command becomes available to enable you to open a report in the Publisher catalog. |
| Upload Template | If you used the Open Template dialog to download a template from the Publisher catalog, use this option to upload the updated layout back to the report definition in the catalog. |
| Upload Template As | If you used the Open Template dialog to download a template or to open a report from the catalog, use this option to upload the layout to the report definition in the catalog. Also use this option to upload modifications to an existing template under a different name. |
| Save XML Data | If you are working in connected mode, then use this command to save the data to a local directory if you also need access to the data in disconnected mode. |

About the Load Data Group

The Load Data group of commands enables you to load a saved sample data file or sample schema to the Template Builder.

You must load data to use most of the Template Builder functionality. See [Access Data for Building Templates](#) for more options for loading data to the Template Builder.

The following figure shows the Load Data group of commands.



The Load Data Group options table below describes the commands available for the Load Data group.


| Command | Description |
|-------------------|--|
| Sample XML | This command enables you to load a previously saved sample XML file from the report data source. If you are not connected to the Publisher server, use this method to load the data. |
| XML Schema | This command enables you to load an XML Schema file (.xsd) that contains the fields available in the report XML data. The XML schema has the advantage of being complete (a sample xml file may not contain all the fields from the data source). For the preview, the Template Builder can generate dummy sample data for an XML Schema. However, the preview works better if you also upload real sample data. |

About the Insert Group

Use the Insert group of commands to insert the layout components to the template.

To insert components, see [Insert Components to the Template](#).

The following figure shows the Insert group of commands.



| Command | Description |
|---------------------|---|
| Table Wizard | This function provides a wizard that guides you through the creation of tables used in typical reports. |
| Pivot Table | The Pivot Table function enables you to drag and drop the data elements to a pivot table structure. |
| Chart | Publisher doesn't recognize native Microsoft Word charts. The Insert Chart function allows you to insert a chart that's understood by Publisher. |


| Command | Description |
|---------------------------|--|
| Field | This function allows you to select fields from the data source and insert them into the template. As a beginner, you should use Insert Fields only for data fields that are unique - none repeating - in the document. See Insert a Table Using the Table Wizard for additional information on how to insert repetitive fields. |
| Table/Form | Use this function to insert data fields to be organized as a simple or nested table or as a form that's repeated with different data. You may even organize all the data fields for the whole document before inserting them. |
| Repeating Group | Enables you to select or define a group of elements that you want repeated for each occurrence of an element in the data. |
| Conditional Format | Enables you to define simple conditional formats to apply to table rows or cells. |
| Conditional Region | Enables you to insert a conditional statement around a region of the template. |
| All Fields | This function inserts all fields found in the XML data into the document. It also inserts processing instructions into the document that repeats a section - such as a table row - when the associated XML element is repeated. XML documents often contain a large number of fields in a deeply nested hierarchy. For example, an Oracle Purchasing purchase order contains purchase order lines, which contain shipments, which contain distributions. The purchase order line alone contains more than 150 data fields. In these cases, you should use the Insert Table/Form function to have more control over which fields are inserted. |

About the Preview Group

The Preview group of commands enables you to preview the RTF template with the sample XML data. The preview menu offers PDF, HTML, RTF, PowerPoint, and Excel as output formats.

When you select any of these output formats, the Template Builder merges the data into the template and creates the output document.

The following figure shows the Preview group of commands.



 **Note:**


You must have Adobe Acrobat Reader version 5.0 or higher installed to preview documents in PDF format.

About the Tools Group

The section describes the commands available for a the **Tools** group.

For more information about using the commands in the **Tools** group refer to [Template Editing Tools](#) and [Use the Template Builder Translation Tools](#).

The following figure shows the **Tools** group of commands.



The table below describes the commands available for the **Tools** group.


| Command | Description |
|-------------------|---|
| Field Browser | The field browser is a tool for advanced users who must change the Publisher commands that are hidden in the form fields. It shows the commands behind each form field and allows you to change them. Use this tool to correct flawed RTF templates or to update multiple fields efficiently. |
| Validate Template | The validation function checks the template for incorrect use of Publisher commands and unsupported elements in the Word file. |
| Translation | Includes the following subcommands: <ul style="list-style-type: none"> • Extract Text - Enables you to create a standard XLIFF translation file that contains the boilerplate text from the template. XLIFF is a standard file format that is understood by many translation software packages. Because an XLIFF is an XML file, you can translate the text in a text editor. For more information on working with XLIFF files, see Work with Translation Files. • Preview Translation - Enables you to preview the template as a PDF file using a specified XLIFF translation file. This functionality enables you to test translation files. • Localize Template - Applies a translation file to an RTF template. This means that in the current RTF template all boilerplate text is translated. The main function of this feature is to create a language-specific version of a template. |

| Command | Description |
|---------|---|
| Export | <p>Includes the following functions:</p> <ul style="list-style-type: none">• XSL-FO Stylesheet - Allows you to convert the RTF template into an enhanced XSL-FO stylesheet. This function can be used to generate XSL-FO for debugging or further customization.• Formatted XML - Enables you to apply the XSL-FO stylesheet generated from the Word document to the sample data and save the intermediate FO format. This function is mainly for debugging.• PDF - Converts the Word document to PDF. |

About the Options Group

The Options group of commands allows you to define preferences and options for using Publisher and access online help.

The following figure shows the Options group of commands.



See [Set Options for the Template Builder](#).

15

Create Excel Templates

This topic describes creating report templates in Microsoft Excel using the Template Builder for Excel.

Topics:

- [Introduction to Excel Templates](#)
- [Understand the Mappings Between Template and Data](#)
- [Use the Template Builder for Excel](#)
- [Build a Basic Template Using the Template Builder](#)
- [Format Dates](#)
- [Understand Excel Template](#)
- [Use Advanced Publisher Functions](#)
- [Preprocess the Data Using an XSL Transformation \(XSLT\) File](#)

Introduction to Excel Templates

An Excel template is a report layout designed in Microsoft Excel for formatting your enterprise reporting data in Excel spreadsheets.

Excel templates provide a set of special features for mapping data to worksheets and for performing additional processing to control how the data is output to Excel workbooks.

This introduction includes the following topics:

- [Features of Excel Templates](#)
- [Limitations of Excel Templates](#)
- [Prerequisites](#)
- [Supported Output](#)
- [Desktop Tools for Excel Templates](#)
- [Sample Excel Templates](#)

Features of Excel Templates

With Excel templates you can format the data in different ways.

- Define the format for the data in Excel output.
- Split hierarchical data across multiple sheets and dynamically name the sheets.
- Create sheets of data that have master-detail relationships.
- Use native XSL functions in the data to manipulate it prior to rendering.

- Use native Excel functionality.

Limitations of Excel Templates

The following are limitations of Excel templates.

- For reports that split the data into multiple sheets, images aren't supported. If the template sheet includes images, when the data is split into multiple sheets, the images are displayed only on the first sheet.
- Publisher provides an add-in to Microsoft Excel to facilitate the insertion of fields and repeating groups. More complex designs require manual coding. Some features require the use of XSL and XSL Transformation (XSLT) specifications.
- The Excel template limits the maximum number of active cells to 100,000 in an Excel sheet.

Prerequisites

To design Excel templates, you must meet certain prerequisites.

- You must have Microsoft Excel 2003 or later installed. The template file must be saved as Excel 97-2003 Workbook binary format (*.xls). If you are using a version later than Excel 2003 to create your template and then save as Excel 97-2003, ensure that you don't use any features of the later version that are not supported in Excel 97-2003. For example, Excel 2003 allows only three conditional formatting rules per cell, but Excel 2007 allows more. If you apply more than three conditional formatting rules to a cell, only three are applied. Excel 2007 also provides color support not provided in Excel 2003.
- To use some of the advanced features, you must have knowledge of XSL.
- The data model must be created in Publisher with sample data available.

Supported Output

Excel templates generate Excel binary (.xls) output only.

Desktop Tools for Excel Templates

Publisher provides a downloadable add-in to Excel that provides these features.

- Connects directly to the Publisher server to load sample data and upload and download templates
- Inserts data field mappings to the template
- Inserts repeating group mappings to the template
- Provides a field browser to review all inserted code and to edit or delete mappings
- Previews the template using the sample data or live data when in connected mode

Install the Template Builder for Excel

The Template Builder for Excel is installed automatically when you install the Oracle Analytics Publisher Desktop tools.

The tools can be downloaded from the Home page of Oracle Analytics Publisher as follows:

Under the Get Started region, select the Oracle Analytics Publisher Desktop option (32bit Office or 64bit Office) appropriate for your version of Microsoft Office.

The Excel Template Builder isn't compatible with the (deprecated) Analyzer for Excel. If you have the Analyzer for Excel installed from a previous version, the Publisher Tools installer detects its presence and halts the installation. You must remove the Analyzer for Excel before installing the Oracle Analytics Publisher Desktop. The Excel Template Builder includes a feature to import Analyzer for Excel templates to the Excel template format.

Sample Excel Templates

The Template Builder installation includes sample Excel templates.

To access the samples from a Windows desktop:

- Click **Start, Programs**, Oracle Analytics Publisher Desktop, **Samples**, then **Excel**. This action launches the folder that contains the Excel sample templates.

Understand the Mappings Between Template and Data

When you design Excel templates use the Excel Template Builder for inserting fields and repeating groups to your template.


When the Template Builder inserts a field or repeating group it creates a mapping between the data and the spreadsheet and writes the mapping to a hidden sheet called the XDO_METADATA sheet. The Template Builder creates the hidden XDO_METADATA sheet the first time you insert a field or repeating group.

To view or update the XDO_METADATA sheet unhide the sheet. To add calculations or more advanced functions, enter the XSL functions directly in the XDO_METADATA sheet using the named mappings created by the Template Builder. For more information about template-data mappings, see [Understand Excel Template](#).

Use the Template Builder for Excel

The Excel Template Builder facilitates template design by automating the insertion of simple mappings, providing preview functionality, and enabling direct connection to the Publisher server from your Excel session.

The Publisher tab that displays when you install the Template Builder is shown in the following illustration.



You can use the Template Builder in connected mode or disconnected mode. In connected mode, log in to the Publisher server from Excel. The connection enables you to browse the Publisher catalog and load sample data from an existing report or data model. When your template is complete, you can upload it directly to the report definition in the Publisher catalog. In disconnected mode, you must download a sample data file from the data model to your local client.

This section includes the following topics about using the Template Builder for Excel:

- [Work in Connected Mode](#)
- [Work in Disconnected Mode](#)
- [Insert Fields](#)
- [Insert Repeating Groups](#)
- [Use the Field Browser to View, Edit, and Delete Fields](#)
- [Preview Templates](#)
- [Import Excel Analyzer Templates](#)

Work in Connected Mode

In connected mode you can interact directly with the Publisher server.

The process flow for creating or editing a template in connected mode is:

1. Open Excel with the Publisher Template Builder for Excel Add-in installed.
2. Log on to the Publisher server.
3. Select the report or data model for which you want to create a new layout; or, select an existing layout to modify.
4. Design your template in Excel.
5. Preview your template using the **View Report** or **Preview** command.
6. Use one of the upload template commands to upload your completed template to the Publisher catalog.

Log In Through the Template Builder

The Excel Template Builder enables a direct connection to Publisher from your desktop Excel session.


By logging in directly to Publisher, you can browse the catalog to choose the report to which to add the Excel template; or, if no report has been created, you can select the data model and create the report in the catalog from your Excel session.

To log in to Publisher from Excel:

1. In Excel, on the Publisher tab in the Online group, click **Log On**.
2. In the Login dialog, enter your Publisher username, password, and the URL.
Publisher URL format: `http://www.<host>:<port>/xmlpserver`.

Online Features of the Template Builder

After logging in, the following commands in the Online group become enabled.




- **Log Off** - ends the connection to Publisher.
- **Open** - enables interaction with the Publisher catalog.
- **View Report** - executes the data model on the server and returns live results to view in your template. If the data model includes parameters, you are prompted to enter values.
- **Upload Template/Upload Template As** - uploads the template to the Publisher catalog.

Access the Publisher Catalog from the Template Builder

The **Open** online command enables interaction with the Publisher catalog.

The **Open** command launches the Open Template dialog to enable access to the Publisher catalog.



Navigate the catalog folders to locate the report, data model, or existing layout template. From this dialog you can initiate one of the following actions:

- Modify an existing Excel template.
When you select a report in the **Reports** region, any existing Excel templates or Excel Analyzer templates (deprecated) are displayed in the lower **Layout Templates** region. To modify an existing template, select the template name and click **Open Layout Template**. The Template Builder loads the sample data from the report's data model and opens the existing template in Excel.
- Create a new template for an existing report.
Select the report name in the **Reports** region and click **Open Report**. The Template Builder loads the sample data for this report's data model.
- Select a data model to create a new report.
When you select a data model from the catalog, the **Create Report** button is enabled. Click **Create Report** and you are prompted to enter a report name and select the location in the catalog to save the new report.

Upload Templates from the Template Builder

A link to upload templates is provided if you are online with the server.

If you've maintained the connection during the design process, click one of the following to upload your completed template to the Publisher server:

- **Upload Template** uploads your edited template and replaces the existing template in the catalog. **Upload Template** is enabled only when you've opened an existing template from the Open Template dialog using the **Open Layout Template** button.
- **Upload Template As** prompts you to assign a **Template Name** and **Locale** to the template then uploads the file to the report in the Publisher catalog.

Work in Disconnected Mode

When direct connection to the Publisher server isn't possible or practical, you can use the Template Builder to design and preview templates in disconnected mode.

In disconnected mode the commands in the **Online** group are not enabled. The process flow for working in disconnected mode is:

1. Log in to the Publisher server and download sample data from the data model for which you want to design a template.
2. Open Excel with the Publisher Template Builder for Excel Add-in installed.
3. Load the sample data to the Template Builder.
4. Design your template in Excel.
5. Preview your template using the **Preview** command.
6. Log in to the Publisher server and use the report editor to upload your template.

Obtain Sample Data

The Template Builder requires sample data to insert the data field mappings to your template.

If you do not have access to the report data model, but you can access the report, then you can alternatively save sample data from the report viewer.

To save data from the report viewer:

1. In the Publisher catalog, navigate to the report.
2. Click **Open** to run the report in the report viewer.
3. Click the **Actions** menu, then click **Export**, then click **Data**. You are prompted to save the XML file.
4. Save the file to a local directory.

Load Sample Data in Disconnected Mode

You can load sample data into a local directory while offline.

Once you've saved the sample data from the report data model to a local directory, load it to the Template Builder.

1. Open Excel with the PublisherTemplate Builder for Excel Add-in installed.
2. On the Publisher tab, in the Load Data group, click **Sample XML**. You're prompted to locate and select the data from its saved location. A confirmation message confirms the data is loaded.

Upload Templates to the Report

You can upload report templates while offline.


When working in disconnected mode, upload the template to the report editor following the instructions in [Add a Layout by Uploading a Template File](#).

Insert Fields

The **Field** command in the **Insert** group maps data elements from the loaded sample data to the desired location in the spreadsheet.

To insert a field:


1. In Excel, select the cell to which to map the data element.
2. On the Publisher tab, in the **Insert** group, click **Field**. The Field dialog launches, displaying the data elements from your sample data.
3. On the Field dialog select the element to insert to the cell. Notice that as you select items in the data structure, sample data is displayed in the Example region as shown in the following illustration.




4. Click **Insert** to insert the data element to the cell in the spreadsheet. Sample data is inserted to the cell.

When you insert a field, the Template Builder creates a mapping between the data and the cell by assigning a unique Excel defined name to the cell and mapping the data element to that defined name. The mapping is written to the XDO_METADATA sheet as shown in the following illustration.

When the Template Builder inserts the field it assigns a defined name to the cell



and creates a mapping in the hidden XDO_METADATA sheet between the named cell and the element from your data.



Note that the XDO_METADATA sheet is hidden by default.

More Features of the Field Dialog

The Field dialog provides the following features.

Find

For an XML document with a large and complicated structure, use the find functionality to find a specific field. Enter all or part of the field name into the **Find** field and click **Find Next**.

Business View or XML Tag Name View

When working in connected mode, you can choose whether to view the data structure using the Business View names or the XML Tag Names as defined in the data model. Business View names are user-friendly names defined for the data elements in the data model editor. This option isn't available if sample data has been loaded from a locally stored file or when the data model doesn't include Business View names.

Insert Repeating Groups

You can insert repeating groups of cell elements.

To insert a repeating group:

1. Select the cells in the spreadsheet that contain the elements you want repeated.

2. On the Publisher menu, in the Insert group, click **Repeating Group**.
3. Enter the appropriate fields in the Publisher Properties dialog.
4. When you've completed the dialog options, click OK to insert the Publisher code to define the groupings. An Excel defined name is assigned to the cell range using the Publisher syntax `XDO_GROUP_?name?` and the code is written to the XDO_METADATA sheet as shown in the following illustration.

| | A | B | C |
|----|----------------------|---|-----------------------|
| 1 | Version | | |
| 2 | ARU-dbdv | | |
| 3 | Extractor Version | | |
| 4 | Template Code | | |
| 5 | Template Type | TYPE_EXCEL_TEMPLATE | |
| 6 | Preprocess XSLT File | | |
| 7 | Last Modified Date | | |
| 8 | Last Modified By | | |
| 9 | | | |
| 10 | Data Constraints: | | |
| 11 | XDO_GROUP_?XDOG1? | <xsl:for-each-group select="//DEPT" group-by="./DEPARTMENT_ID"> | </xsl:for-each-group> |
| 12 | | | |
| 13 | | | |

Use the Field Browser to View, Edit, and Delete Fields


The Field Browser enables you to view and edit the code inserted by the Template Builder and the code you inserted manually into the XDO_METADATA sheet.

When you select a line of code in the Field Browser, the corresponding cells in the template are highlighted, so you know which field you are editing, deleting, or viewing.

To edit or delete a field using the Field Browser:

1. On the Publisher menu, in the **Tools** group, click **Field Browser**.
2. The Field Browser displays the Publisher commands that are present in the template. Select the field or command to view. The code for the selected command displays in the lower **Edit** region. Notice that if the code has opening and ending tags (such as the opening and ending tags of a repeating group) the opening tag display in the upper code box and the closing tag displays in the lower code box.

When you select a command, the area of the template that corresponds to the code is highlighted. In the following illustration the repeating group is selected in the Field Browser and the corresponding fields are highlighted in the template.



3. To delete the code, click **Delete**. To edit the code, update the code displayed in the Edit and click **Update**.
4. When finished, click **Close** to close the Field Browser.

Preview Templates

Use the preview feature of the Template Builder to test your template before uploading it to the Publisher server.

To preview a template with the loaded sample data:

- On the Publisher tab in the Preview group, click **Excel**.

The sample data is applied to the template and the output document is opened in a new workbook.

If you're working in connected mode, you can test your template with live data from the report data model using **View Report**.

To view your template using live data:

- On the Publisher tab in the Online group, click **View Report**.

The Template Builder sends a request to execute the data model on the Publisher server and returns the data to apply to the template. If the data model requires parameters, you're prompted to enter values. The output document is opened in a new Excel workbook.

Import Excel Analyzer Templates

The Excel Analyzer feature of Publisher has been deprecated, but if you have Excel Analyzer templates from previous Publisher releases, you can use the Import command of the Excel Template Builder to import an Excel Analyzer template and convert it to an Excel template. The Import command supports only Excel Analyzer templates created using the Offline Mode.

To import an Excel Analyzer template:

1. Open the Excel Analyzer template. If you're working in connected mode, navigate to the report that contains the template you wish to convert. When you select the

report in the Open Template dialog, the Excel Analyzer template displays in the Layout Templates region as type "excel". Click **Open Layout Template** to open the Excel Analyzer template in Excel.

2. Click Import. A message notifies you: This feature will overwrite your template.
3. Click OK.

The Template Builder converts the Excel Analyzer template to an Excel template.

Build a Basic Template Using the Template Builder

This section demonstrates the concepts of Excel templates by describing the steps to create a simple Excel template using the Excel Template Builder.

This procedure follows these steps:

- Step 1: [Load Sample Data to the Template Builder](#)
- Step 2: [Design the Layout in Excel](#)
- Step 3: [Use the Template Builder to Insert Fields](#)
- Step 4: [Use the Template Builder to Insert Repeating Groups](#)
- Step 5: [Insert the Calculated Salary Field](#)
- Step 6: [Test the Template](#)

Step 1: Load Sample Data to the Template Builder

Loading sample data provides a properly formatted base from which to build a template.

The method you choose for loading sample data depends on whether you are working in connected or disconnected mode.

- To load data when working in connected mode, see [Access the Publisher Catalog from the Template Builder](#).
- To load data when working in disconnected mode, see [Load Sample Data in Disconnected Mode](#).

The sample data for this example is a list of employees by department. Note that employees are grouped and listed under the department.

```
<?xml version="1.0" encoding="UTF-8"?>
<!-- Generated by Oracle BI Publisher 11.1.1.4.0 -->
<DATA>
  <DEPT>
    <DEPARTMENT_ID>20</DEPARTMENT_ID>
    <DEPARTMENT_NAME>Marketing</DEPARTMENT_NAME>
    <EMPS>
      <EMPLOYEE_ID>201</EMPLOYEE_ID>
      <EMP_NAME>Michael Hartstein</EMP_NAME>
      <EMAIL>MHARTSTE</EMAIL>
      <PHONE_NUMBER>515.123.5555</PHONE_NUMBER>
      <HIRE_DATE>1996-02-17T00:00:00.000+00:00</HIRE_DATE>
      <SALARY>13000</SALARY>
    </EMPS>
  </DEPT>
  <DEPT>
    <EMPLOYEE_ID>202</EMPLOYEE_ID>
```

```

        <EMP_NAME>Pat Fay</EMP_NAME>
        <EMAIL>PFAY</EMAIL>
        <PHONE_NUMBER>603.123.6666</PHONE_NUMBER>
        <HIRE_DATE>1997-08-17T00:00:00.000+00:00</HIRE_DATE>
        <SALARY>6000</SALARY>
    </EMPS>
</DEPT>
<DEPT>
...
...
</DEPT>
</DATA>

```

To build the template described in this tutorial, use the sample data available in the Samples folder installed with BI Publisher Desktop. A very similar data set can be found in <Install Directory>\BI Publisher Desktop\Template Builder for Word\samples\Excel templates\Employee By Departments\EmpByDept Single Sheets\EmpbyDeptExcelData.xml

Step 2: Design the Layout in Excel

Use Excel to simplify a design layout.

In Excel, determine how you want to render the data and create a sample design, as shown in the following illustration.

| | A | B | C | D | E | F |
|----|---------------------------------------|----------------|---------|--------------|-----------|---|
| 1 | Employees by Department Report | | | | | |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| 5 | Department: | Administration | | | | |
| 6 | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Salary | |
| 8 | Jennifer Whalen | 200 | JWHALEN | 515-123-4444 | 10,000.00 | |
| 9 | | | | | 10,000.00 | |
| 10 | | | | | | |
| 11 | | | | | | |

The design shows a department name and a row for each employee within the department. You can apply Excel formatting to the design, such as font style, shading, and alignment. Note that this layout includes a total field. The value for this field isn't available in the data and requires a calculation.

Step 3: Use the Template Builder to Insert Fields


You can map data to data fields in the template.

In this layout design, the following fields must be mapped to the template from the data:

| Field in Layout | Element in Data |
|-----------------|-----------------|
| Department | DEPARTMENT_NAME |
| Employee Name | EMP_NAME |
| Employee ID | EMPLOYEE_ID |
| Email | EMAIL |
| Telephone | PHONE_NUMBER |
| Salary | SALARY |

To insert field mappings using the Template Builder:

1. Select the cell in the spreadsheet where the data field is to display. For example, to map the DEPARTMENT_NAME element, select cell B5.
2. On the Publisher tab, in the **Insert** group click **Field**. (Because this is the first field you are inserting, a message displays stating that the metadata sheet will be created.) The Field dialog displays showing the data structure, shown in the following illustration.



3. Select the element in the Field dialog and click **Insert**. Sample data is inserted to the cell in the template.
4. Repeat for the Employee Name, Employee ID, Email, Telephone, and Salary fields in the template.

Step 4: Use the Template Builder to Insert Repeating Groups

A group is a set of data that repeats for each occurrence of a particular element.

In the sample template design, there're two groups:

- For each occurrence of the <EMPS> element, the employee's data (name, e-mail, telephone, salary) is displayed in the worksheet.
- For each occurrence of the <DEPT> element, the department name and the list of employees belonging to that department are displayed.

In other words, the employees are "grouped" by department and each employee's data is "grouped" by the employee element. To achieve this in the final report, insert a repeating group around the cells that are to repeat for each grouping element.

Note that the data must be structured according to the groups that you want to create in the template. The structure of the data for this example

```
<DATA>
  <DEPT>
    <EMPS>
```

establishes the grouping desired for the report.

To insert the repeating group for Employees:

1. Select the cells that make up the group. In this example, the first group is the Employee data that makes up a row in the table, the cells are A8 - E8.
2. On the Publisher tab, in the **Insert** group, click **Repeating Group**.
3. In the Properties dialog, select the following:
 - From the **For Each** list, select EMPS.
 - From the **Group By** list, select EMPLOYEE_ID.

To insert the repeating group for Departments:

1. To define the department group, select the Department name cell and all the employee fields beneath it (A5-E9) as shown in the following illustration.

| | A | B | C | D | E |
|---|---------------------------------------|----------------|---------|--------------|-----------|
| 1 | Employees by Department Report | | | | |
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | Department: | Administration | | | |
| 6 | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Salary |
| 8 | Jennifer Whalen | 200 | JWHALEN | 515-123-4444 | 10,000.00 |
| 9 | | | | | 10,000.00 |

2. On the Publisher tab, in the **Insert** group, click **Repeating Group**. Notice that the total salary cell is included in the department group to ensure that it repeats at the department level.
3. In the Properties dialog, select the following:
 - From the **For Each** list, select DEPT.
 - From the **Group By** list, select DEPARTMENT_ID.

Step 5: Insert the Calculated Salary Field

Finally, insert the second Salary field that is to be an aggregated sum for each department.

To insert the calculated field:

1. Select the cell in the spreadsheet where the calculated salary is to display. In this example, the cell is E9.
2. On the Publisher tab, in the group, click **Field** to display the dialog.
3. Select the SALARY element and click **Insert** to insert the mapping in the template.
4. Open the XDO_METADATA sheet.

The Template Builder created a hidden XDO_METADATA sheet when you inserted the first field. Unhide the sheet in your workbook by right-clicking Sheet1 and selecting **Unhide** from the menu.

The following illustration shows the XDO_METADATA sheet for the sample template.

| | A | B | C | D | E |
|----|----------------------|--|---|---|---|
| 1 | Version | | | | |
| 2 | ARU-dbdv | | | | |
| 3 | Extractor Version | | | | |
| 4 | Template Code | | | | |
| 5 | Template Type | TYPE_EXCEL_TEMPLATE | | | |
| 6 | Preprocess XSLT File | | | | |
| 7 | Last Modified Date | | | | |
| 8 | Last Modified By | | | | |
| 9 | | | | | |
| 10 | Data Constraints: | | | | |
| 11 | XDO_?XDOFIELD1? | <?DEPARTMENT_NAME?> | | | |
| 12 | XDO_?XDOFIELD2? | <?EMP_NAME?> | | | |
| 13 | XDO_?XDOFIELD3? | <?EMPLOYEE_ID?> | | | |
| 14 | XDO_?XDOFIELD4? | <?EMAIL?> | | | |
| 15 | XDO_?XDOFIELD5? | <?PHONE_NUMBER?> | | | |
| 16 | XDO_?XDOFIELD6? | <?SALARY?> | | | |
| 17 | XDO_?XDOFIELD7? | <?SALARY?> | | | |
| 18 | XDO_GROUP_?XDOG1? | <xsl:for-each-group select="." </xsl:for-each-group> | | | |
| 19 | XDO_GROUP_?XDOG2? | <xsl:for-each-group select="." </xsl:for-each-group> | | | |
| 20 | | | | | |

The total salary field maps to the cell named XDO_?XDOFIELD7?.

- In Column B enter the calculation as an XPATH function. To calculate the sum of the SALARY element for all employees in the group, enter the following: `<?sum(../SALARY)?>`. The entry is shown in the following illustration.

| | A | B | C | D | E |
|----|----------------------|---|---|---|---|
| 1 | Version | | | | |
| 2 | ARU-dbdv | | | | |
| 3 | Extractor Version | | | | |
| 4 | Template Code | | | | |
| 5 | Template Type | TYPE_EXCEL_TEMPLATE | | | |
| 6 | Preprocess XSLT File | | | | |
| 7 | Last Modified Date | | | | |
| 8 | Last Modified By | | | | |
| 9 | | | | | |
| 10 | Data Constraints: | | | | |
| 11 | XDO_?XDOFIELD1? | <?DEPARTMENT_NAME?> | | | |
| 12 | XDO_?XDOFIELD2? | <?EMP_NAME?> | | | |
| 13 | XDO_?XDOFIELD3? | <?EMPLOYEE_ID?> | | | |
| 14 | XDO_?XDOFIELD4? | <?EMAIL?> | | | |
| 15 | XDO_?XDOFIELD5? | <?PHONE_NUMBER?> | | | |
| 16 | XDO_?XDOFIELD6? | <?SALARY?> | | | |
| 17 | XDO_?XDOFIELD7? | <?sum(../SALARY)?> | | | |
| 18 | XDO_GROUP_?XDOG1? | <xsl:for-each-group select="."/></xsl:for-each-group> | | | |
| 19 | XDO_GROUP_?XDOG2? | <xsl:for-each-group select="."/></xsl:for-each-group> | | | |
| 20 | | | | | |

Step 6: Test the Template

You can test a template using Preview.

To preview a template with the loaded sample data:

- On the Publisher tab in the group, click **Excel**.

The sample data is applied to the template and the output document is opened in a new workbook.

| 1 | Employees by Department Report | | | | |
|----|---------------------------------------|--------------------|--------------|------------------|---------------|
| 2 | | | | | |
| 3 | | | | | |
| 4 | | | | | |
| 5 | Department: | Marketing | | | |
| 6 | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Salary |
| 8 | Michael Hartstein | 201 | MHARTSTE | 515.123.5555 | 13,000.00 |
| 9 | Pat Fay | 202 | PFAY | 603.123.6666 | 6,000.00 |
| 10 | | | | | 19,000.00 |
| 11 | Department: | Purchasing | | | |
| 12 | | | | | |
| 13 | Employee Name | Employee ID | Email | Telephone | Salary |
| 14 | Den Raphaely | 114 | DRAPHEAL | 515.127.4561 | 11,000.00 |
| 15 | Alexander Khoo | 115 | AKHOO | 515.127.4562 | 3,100.00 |
| 16 | Shelli Baida | 116 | SBAIDA | 515.127.4563 | 2,900.00 |
| 17 | Sigal Tobias | 117 | STOBIAS | 515.127.4564 | 2,800.00 |
| 18 | Guy Himuro | 118 | GHIMURO | 515.127.4565 | 2,600.00 |
| 19 | Karen Colmenares | 119 | KCOLMENA | 515.127.4566 | 2,500.00 |
| 20 | | | | | 24,900.00 |
| 21 | Department: | Human Resources | | | |
| 22 | | | | | |
| 23 | Employee Name | Employee ID | Email | Telephone | Salary |
| 24 | Susan Mavris | 203 | SMAVRIS | 515.123.7777 | 6,500.00 |
| 25 | | | | | 6,500.00 |

Format Dates

Excel cannot recognize canonical date format. If the date format in the XML data is in canonical format, that is, YYYY-MM-DDThh:mm:ss+HH:MM, you must apply a function to display it properly.

One option to display a date is to use the Excel REPLACE and SUBSTITUTE functions. This option retains the full date and timestamp. If you only require the date portion in the data (YYY-MM-DD), then another option is to use the DATEVALUE function. The following example shows how to use both options.

Example: Formatting a Canonical Date in Excel

Using the Employee by Department template and data from the first example, this procedure adds the HIRE_DATE element to the layout and displays the date as shown in Column E of the following figure:

| | A | B | C | D | E | F |
|----|---------------------------------------|--------------------|-----------------|------------------|------------------|---------------|
| 1 | Employees by Department Report | | | | | |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| 5 | Department: Admin | | | | | |
| 6 | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary |
| 8 | John Thomas | 100001 | john@oracle.com | 111-333-3333 | 3-Feb-96 | 10,000 |
| 9 | | | | | | 10,000 |
| 10 | | | | | | |
| 11 | | | | | | |
| 12 | | | | | | |

To format the date:

1. Add a column to the table in your layout for HIRE_DATE.
2. In the table row where the data is to display, use the Template Builder to insert the HIRE_DATE field.

If you are not using the Template Builder, copy and paste a sample value for HIRE_DATE from the XML data into the cell that is to display the HIRE_DATE field. For example: Copy and paste 1996-02-03T00:00:00.000-07:00 into the E8 cell. Assign the cell the defined name XDO_?HIRE_DATE? to map it to the HIRE_DATE element in the data. The inserted field is shown in the following figure:

| | A | B | C | D | E | F |
|----|---------------------------------------|--------------------|-----------------|------------------|-------------------------|---------------|
| 1 | Employees by Department Report | | | | | |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| 5 | Department: Admin | | | | | |
| 6 | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary |
| 8 | John Thomas | 100001 | john@oracle.com | 111-333-3333 | 1996-02-03T00:00:00.000 | 10,000 |
| 9 | | | | | | 10,000 |
| 10 | | | | | | |

If you do nothing else, the HIRE_DATE value is displayed as shown. To format the date as "3-Feb-96", you must apply a function to that field and display the results in a new field.

3. Insert a new Hire Date column. This is now column F, as shown in the following figure:

| | A | B | C | D | E | F | G |
|----|---------------------------------------|--------------------|-----------------|------------------|-------------------------|------------------|---------------|
| 1 | Employees by Department Report | | | | | | |
| 2 | | | | | | | |
| 3 | | | | | | | |
| 4 | | | | | | | |
| 5 | Department: | Admin | | | | | |
| 6 | | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Hire Date | Salary |
| 8 | John Thomas | 100001 | john@oracle.com | 111-333-3333 | 1996-02-03T00:00:00.000 | | 10,000 |
| 9 | | | | | | | 10,000 |
| 10 | | | | | | | |

4. In the new Hire Date cell (F8), enter one of the following Excel functions:

- To retain the full date and timestamp, enter:

```
=--REPLACE(SUBSTITUTE(E8,"T"," "),LEN(E8)-6,6,"")
```

- To retain only the date portion (YYY-MM-DD), enter:

```
=DATEVALUE(LEFT(E8,10))
```


Notice that in both functions, "E8" refers to the cell that contains the value to convert.

After you enter the function, it populates the F8 cell as shown in the following figure:

| | A | B | C | D | E | F | G |
|----|---------------------------------------|--------------------|-----------------|------------------|-------------------------|------------------|---------------|
| 1 | Employees by Department Report | | | | | | |
| 2 | | | | | | | |
| 3 | | | | | | | |
| 4 | | | | | | | |
| 5 | Department: | Admin | | | | | |
| 6 | | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Hire Date | Salary |
| 8 | John Thomas | 100001 | john@oracle.com | 111-333-3333 | 1996-02-03T00:00:00.000 | 35098 | 10,000 |
| 9 | | | | | | | 10,000 |
| 10 | | | | | | | |

5. Apply formatting to the cell.

Right-click the F8 cell. From the menu, select **Format Cells**. In the Format Cells dialog, select **Date** and the desired format, as shown in the following figure.



The sample data in the F8 cell now displays as 3-Feb-96.

- Hide the E column, so that report consumers do not see the canonical date that is converted.

The following figure shows the template with column E hidden:

| | A | B | C | D | F | G | H |
|----|---------------------------------------|--------------------|-----------------|------------------|------------------|---------------|---|
| 1 | Employees by Department Report | | | | | | |
| 2 | | | | | | | |
| 3 | | | | | | | |
| 4 | | | | | | | |
| 5 | Department: | Admin | | | | | |
| 6 | | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary | |
| 8 | John Thomas | 100001 | john@oracle.com | 111-333-3333 | 3-Feb-96 | 10,000 | |
| 9 | | | | | | 10,000 | |
| 10 | | | | | | | |
| 11 | | | | | | | |
| 12 | | | | | | | |
| 13 | | | | | | | |

Understand Excel Template

Similar to RTF template design, Excel template design follows the paradigm of mapping fields from the XML data to positions in the Excel worksheet.

Excel templates make use of features of Excel in conjunction with special Publisher syntax to achieve this mapping. In addition to direct mapping of data elements, Excel templates support more complex formatting instructions by defining the cell ranges and the commands in a separate worksheet designated to contain these commands. This sheet is called the XDO_METADATA sheet.

Map Data Fields and Groups

Excel templates use named cells and groups of cells to enable Publisher to insert data elements.

Cells are named using Publisher syntax to establish the mapping back to the XML data. The cell names are also used to establish a mapping within the template between the named cell and calculations and formatting instructions defined on the XDO_METADATA sheet.

The template content and layout must correspond to the content and hierarchy of the XML data file used as input to the report. Each group of repeating elements in the template must correspond to a parent-child relationship in the XML file. If the data isn't structured to match the desired layout in Excel, you can regroup the data using XSLT preprocessing or the grouping functions. However, for the best performance and least complexity it's recommended that the data model be designed with the report layout in mind.

Use Excel Defined Names for Mapping

Publisher uses the Excel defined names feature to identify data fields and repeating elements.

A defined name in Excel is a name that represents a cell, range of cells, formula, or constant value.

The Template Builder for Excel automatically creates the defined names when you use it to insert fields and repeating groups. You can also insert the defined names manually. The defined names used in the Excel template must use the syntax described in this chapter and follow the Microsoft guidelines described in the Microsoft Excel help document. Note that Publisher defined names are within the scope of the template sheet.

When you create an Excel Template manually (that is, NOT using the Publisher Desktop Excel Template Builder), you must provide default values for all marked up cells XDO_?. The default values must match to the data type of the report data XML file. Without default values for the XDO_? cells, the output cells generated from those template cells may lose formatting and the result is unpredictable. If you use Publisher Desktop to create an Excel Template, the default values are automatically supplied with the first row of sample data in the report data file.

Use "XDO_" Prefix to Create Defined Names

The Publisher defined names are Excel defined names identified by the prefix "XDO_".

Creating the defined name with the Publisher code in the template creates the connection between the position of the code in the template and the XML data elements, and also maintains the ability to dynamically grow data ranges in the output reports, so that these data ranges can be referenced by other formula calculations, charts, and macros.

Use Native Excel Functions with the "XDO_" Defined Names

You can use the XDO_ defined names in Excel native formulas as long as the defined names are used in a simple table.

When a report is generated, Publisher automatically adjusts the region ranges for those named regions so that the formulas calculate correctly.

However, if you create nested groups in the template, then the cells generated in the final report within the grouping can no longer be properly associated to the correct name. In this case, the use of XDO_ defined names with native Excel functions cannot be supported.

About the XDO_METADATA Sheet

Each Excel template requires a sheet within the template workbook called "XDO_METADATA".

Publisher uses this sheet in the template in the following ways:

- To identify the template as an Excel template.
- To insert the code for the field and group mappings you create with the Template Builder.

As the template designer, you also use this sheet to specify more advanced calculations and processing instructions to perform on fields or groups in the template. Publisher provides a set of functions to provide specific report features. Other formatting and calculations can be expressed in XSLT.

Create the XDO_METADATA Sheet

When you begin the design of a new Excel template using the Template Builder, the first time you use one of the **Insert** functions the Template Builder automatically creates a hidden XDO_METADATA sheet. A message informs you that the sheet has been created.

Publisher creates the sheet as a hidden sheet. Use the Excel `Unhide` command to view and edit the XDO_METADATA sheet.

Format of the XDO_METADATA Sheet

The XDO_METADATA sheet is created with the format shown in this figure. The format consists of two sections: the header section and the data constraints section. Both sections are required.

| | A | B | C |
|----|-------------------------|---------------------|---|
| 1 | Version | | |
| 2 | ARU-dbdv | | |
| 3 | Extractor Version | | |
| 4 | Template Code | | |
| 5 | Template Type | TYPE_EXCEL_TEMPLATE | |
| 6 | Preprocess XSL Template | | |
| 7 | Last Modified Date | | |
| 8 | Last Modified By | | |
| 9 | | | |
| 10 | Data Constraints: | | |
| 11 | | | |
| 12 | | | |

In the header section, all the entries in column A must be listed, but a value is required for only one: Template Type, as shown. The entries in Column A are:

- Version
- ARU-dbdv
- Extractor Version
- Template Code
- Template Type
- Preprocess XSLT File
- Last Modified Date
- Last Modified By

The Data Constraints section is used to specify the data field mappings and other processing instructions. Details are provided in the following sections.

Hide the XDO_METADATA Sheet

Oracle recommends that you hide the XDO_METADATA sheet before uploading the completed template to the Publisher catalog to prevent its inclusion in the final report output. Use the `Excel Hide` command to hide the sheet before uploading the template to the server.

Enable Excel Template Scalability

Enable Excel template scalability to process large data to output reports in Excel format.

If you try to publish reports with large amounts of data as Excel spreadsheets, you might encounter memory issues because the limit of an Excel sheet is 65536 rows. If you enable an Excel template to scale, that template divides a large amount of data into multiple sheets, which helps to avoid memory issues. You can enable Excel template scalability at the system level, the report level, or the Excel template level. The template level setting overrides the report level setting, and the report level setting overrides the system level setting. To ensure backward compatibility, Excel template scalability is set to false by default.

An Excel template that's enabled to scale does the following to avoid memory issues:

- Flows data into multiple sheets when the data size is more than 65536 rows in a table.
- Flushes memory of every N rows after those N rows are processed for rendering the Excel report.

By default, the flush cell size = 3000 * 100 (rows * columns). $N = 3000 * 100 / \text{Actual_columns_in_your_Excel_template_sheet}$

You can override this flush cell size by specifying the flush cell size (XDO_FLUSH_CELL_SIZE_? *flush_cell_size*) below the "Data Constraints:" line in the XDO_METADATA sheet in the Excel template. An XDO_GROUP table might not work properly if the final report size of an XDO_GROUP table is greater than the flush cell size.

- Releases the memory used for each sheet after processing the data in the sheet.

Enable Excel Template Scalability at the Template Level

You can enable scalability in an Excel template to avoid running out of memory while publishing large amounts of data to an Excel spreadsheet.

To enable Excel template scalability at the template level:

1. Open the Excel template.
2. Select the XDO_METADATA sheet in the Excel template.
3. Below the "Data Constraints:" line, enter XDO_SCALABLE_? in Column A, and type true in column B.

Enable Excel Template Scalability at the System Level

As an administrator, you can set a runtime property to enable scalability for all Excel templates.

To enable Excel template scalability at the system level:

1. As an administrator, navigate to the Runtime Configuration page.
2. Scroll down to view the Excel template properties.
3. Set the **Enable Scalable Mode** property to true.

Enable Excel Template Scalability at the Report Level

As a report author, you can set a report level property to enable scalability for the Excel template used by the report.

To enable Excel template scalability at the report level:

1. Open the report for edit.
2. Click **Properties** to open the Report Properties dialog.
3. Click the **Formatting** tab and scroll down to view the Excel template properties.
4. Set the **Enable Scalable Mode** property to true.

Use Advanced Publisher Functions

Publisher provides a set of functions to achieve additional reporting functionality.

You define these functions in the Data Constraints region of the XDO_METADATA sheet.

The functions make use of Columns A, B, and C in the XDO_METADATA sheet as follows:

Use Column A to declare the function or to specify the defined name of the object to which to map the results of a calculation or XSL evaluation.

Use Column B to enter the special XDO-XSL syntax to describe how to control the data constraints for the XDO function, or the XSL syntax that describes the special constraint to apply to the XDO_ named elements.

Use Column C to specify additional instructions for a few functions.

The functions are described in the following sections:

- [Reporting Functions](#)
- [Format Functions That Rely on Specific Data Attribute Values](#)
- [Group Functions](#)

Reporting Functions

You can add functions to a template using the commands shown and a combination of Publisher syntax and XSL.

A summary list of the commands is shown in the following table. See the corresponding section for details on usage.

| Function | Commands |
|--|-----------------------------------|
| Split Data from Reports into Multiple Sheets | XDO_SHEET_? with XDO_SHEET_NAME_? |
| Declare and Pass Parameters | XDO_PARAM_?n? |
| Define a Link | XDO_LINK_?link object name? |
| Import and Call a Subtemplate | XDO_SUBTEMPLATE_?n? |
| Reference Java Extension Libraries | XDO_EXT_?n? |

Split Data from Reports into Multiple Sheets

You can define the logic to split the data from a report into multiple sheets.

You can't span images across multiple sheets. If the template sheet includes images, when the data splits into multiple sheets, the images are displayed only on the first sheet. Use this set of commands to split the report data into multiple sheets:

- XDO_SHEET_? command to define the logic to split the data onto a new sheet.
- XDO_SHEET_NAME_? command to specify the naming convention for each sheet.

In the XDO_METADATA sheet, you can specify multiple templates to create multiple sheets. For each template, define a pair of XDO_SHEET_? and XDO_SHEET_NAME_? commands. Make sure you define the same original template sheet name for each pair of XDO_SHEET_? and XDO_SHEET_NAME_? commands.

The following table describes the column entries.

| Column A Entry | Column B Entry | Column C Entry |
|------------------|--|--|
| XDO_SHEET_? | <p><?xsl_evaluation to split the data?></p> <p>Example:</p> <p><?./DEPT?></p> | <p><?original sheet name?></p> <p>Example:</p> <p><?Sheet2?></p> |
| XDO_SHEET_NAME_? | <p><?xsl_expression to name the sheet?></p> <p>Example:</p> <p><?concat(./DEPARTMENT_NAME, '-', count(./EMP_NAME))?></p> | <p><?original sheet name?></p> <p>Example:</p> <p><?Sheet2?></p> |

1. In column A, enter the XDO_SHEET_? and XDO_SHEET_NAME_? commands.
2. In column B:
 - The XDO_SHEET_? command must refer to an existing high-level node in the XML data. In the example, <?./DEPT?> creates a new sheet for each occurrence of <DEPT> in the data. If the data is flat, then you can't use this command unless you first preprocess the data to create the desired hierarchy. To preprocess the data, define the transformation in an XSLT file, then specify this file in the Preprocess XSLT File field of the header section of the XDO_METADATA sheet.
 - The XDO_SHEET_NAME_? command must define the name to apply to the sheets. Enter the XSL expression to derive the new sheet name. The expression can reference a value for an element or attribute in the XML data, or you can use the string operation on those elements to define the final sheet name. The following example names each sheet using the value of DEPARTMENT_NAME concatenated with "-" and the count of employees in the DEPT group.

```
<?concat(./DEPARTMENT_NAME, '-', count(./EMP_NAME))?>
```

3. In column C, specify the name of the original template sheet. For example, if you have a report that contains summary data in the first three worksheets and the burst data is in Sheet2 and Sheet3, specify <?Sheet2?> as the original template sheet name for the first pair of XDO_SHEET_? and XDO_SHEET_NAME_? commands and specify <?Sheet3?> for the second pair of commands. If you do not specify the template sheet name for either XDO_SHEET_? or XDO_SHEET_NAME_? commands, Publisher doesn't take any action for the definition pair.

Example: Splitting the data into multiple sheets

Using employee data, this example:

- Lists the employees of each department in separate sheets.

- Creates a new worksheet for each department.
- Names each worksheet the name of the department. For example, Marketing.
- Lists the first 100 employees in separate sheets for the departments of the first 100 employees.
 - Creates a new worksheet for each department to which the first 100 employees belong.
 - Names each worksheet the name of the department with the number of employees with employee ID less than 100 in that department. For example, Human Resources-3 if three employees in the Human Resources department have employee ID less than 100.

To split the data into sheets:

1. Enter the defined names for each cell of employee data and create the group for the repeating employee data, as shown in the following illustration. Do not create the grouping around the department because the data is split by department.
2. Enter the values in the Data Constraints section of the XDO_METADATA sheet.

The entries are shown in the following illustration.

| | A | B | C |
|----|--------------------------------|---|------------|
| 1 | Version | | |
| 2 | ARU-dbdrv | | |
| 3 | Extractor Version | | |
| 4 | Template Code | | |
| 5 | Template Type | TYPE_EXCEL_TEMPLATE | |
| 6 | Preprocess XSL Template | | |
| 7 | Last Modified Date | | |
| 8 | Last Modified By | | |
| 9 | | | |
| 10 | Data Constraints: | | |
| 11 | XDO_SHEET_? | <?//DEPT?> | <?Sheet2?> |
| 12 | XDO_SHEET_Name_? | <?//DEPARTMENT_NAME?> | <?Sheet2?> |
| 13 | XDO_?TOTAL_SALARY? | <?sum(//SALARY)?> | <?Sheet2?> |
| 14 | XDO_SHEET_? | <?//EMPID<=100?> | <?Sheet3?> |
| 15 | XDO_SHEET_Name_? | <?concat(//DEPARTMENT_NAME,'-',count(//EMP_NAME))?> | <?Sheet3?> |
| 16 | | | |
| 17 | | | |

The following illustration shows the generated report. The data for each department is displayed on its own sheet, which is named per the specified convention.

| | A | B | C | D | E | F |
|---------------|--------------------|------------|--------------|-----------|--------|--------------|
| 1 | | | | | | |
| 2 | | | | | | |
| 3 | Department: | Purchasing | | | | |
| 4 | | | | | | |
| Employee Name | Employee ID | Email | Telephone | Hire Date | Salary | |
| 6 | Sharon Dean | 118 SDEAN | 213-546-1449 | 1-Dec-93 | 4575 | |
| 7 | Tim Jones | 114 TJONES | 213-546-1436 | 5-Nov-93 | 3500 | |
| 8 | James Hardley | 99 JHARDL | 213-546-1438 | 7-Aug-93 | 3800 | |
| 9 | Mark Karen | 24 MKAREN | 213-546-1437 | 12-Feb-92 | 4500 | |
| 10 | Lily Alex | 106 LALEX | 213-546-1444 | 1-Oct-93 | 2700 | |
| 11 | Sandy Larry | 119 SLARRY | 213-546-1445 | 1-Dec-93 | 3950 | |
| 12 | | | | | | 23025 |
| 13 | | | | | | |
| 14 | | | | | | |
| 15 | | | | | | |

| | A | B | C | D | E | F |
|---------------|--------------------|-----------------|--------------|-----------|--------|---|
| 1 | | | | | | |
| 2 | | | | | | |
| 3 | Department: | Human Resources | | | | |
| 4 | | | | | | |
| Employee Name | Employee ID | Email | Telephone | Hire Date | Salary | |
| 6 | Lisa James | 96 LJAMES | 213-546-1456 | 5-Jul-93 | 2500 | |
| 7 | George Henry | 88 GHENRY | 213-546-1450 | 15-Jan-93 | 2800 | |
| 8 | Marina Lewis | 57 MLEWIS | 213-546-1455 | 24-Apr-92 | 3500 | |
| 9 | | | | | | |
| 10 | | | | | | |

Declare and Pass Parameters

To define a parameter, use the XDO_PARAM_?n? function to declare the parameter, then use the \$parameter_name syntax to pass a value to the parameter. A parameter must be defined in the data model.

Column A Entry

XDO_PARAM_?n?

where *n* is the unique identifier for the parameter

Column B Entry

<?param@begin:parameter_name;parameter_value?>

where *parameter_name* is the name of the parameter from the data model and *parameter_value* is the optional default value.

For example:

<?param@begin:Country;US?>

To use the value of the parameter directly in a cell, refer to the parameter as \$parameter_name in the definition for the XDO_ defined name, as described in the following table.

Column A Entry

XDO_PARAM_?parameter_name?

For example:

XDO_PARAM_?Country?

Column B Entry

<?\$parameter_name?>

For example:


<?\$Country?>

You can also refer to the parameter in other logic or calculations in the XDO_METADATA sheet using \$parameter_name.


Example 15-1 Example: Define and pass a parameter

To declare and reference a parameter named Country:

1. In the template sheet, mark the cell with a defined name. In the following figure, the cell has been marked with the defined name XDO_?Country?



2. In the hidden sheet assign that cell the parameter value, as shown in the following figure:



Define a Link

Use the XDO_LINK_? command to define a hyperlink for any data cell, as described in this table.

Example: Define a Link

| Column A Entry | Column B Entry |
|-----------------------------|--|
| XDO_LINK_?cell object name? | <xsl statement to build the dynamic URL> |
| For example: | For example: |
| XDO_LINK_?INVOICE_NO? | <xsl:value-of select="concat('https://server.company.com/ documents/invoice_print.show?c_rptno=', ../INVOICE_NO)"/> |

Assume your company generates customer invoices. The invoices are stored in a central location accessible by a Web server and can be identified by the invoice number (INVOICE_NO).

To generate a report that creates a dynamic link to each invoice:

1. In the template sheet, assign the cell that is to display the INVOICE_NO the XDO defined name: XDO_?INVOICE_NO?, as shown in the following figure:

| | A | B | C | D |
|---|---|----------|----------|----------------|
| 1 | | | | |
| 2 | | | | |
| 3 | | | | |
| 4 | | Customer | Priority | Invoice Number |
| 5 | | Smith | 2 | 1111 |
| 6 | | | | |
| 7 | | | | |
| 8 | | | | |

2. In the XDO_METADATA sheet, enter the appropriate values, as described:
 - Column A entry: XDO_LINK_?INVOICE_NO?
 - Column B entry: <xsl:value-of select="concat('https://server.company.com/documents/invoice_print.show?c_rptno=', ../INVOICE_NO)"/>

The entries in the Excel are shown in the following figure:

| | | |
|----|--------------------------|---|
| 10 | Data Constraints: | |
| 11 | XDO_LINK_?INVOICE_NO? | <xsl:value-of select="concat('https://server.company.com/documents/invoice_print.show?c_rptno=',./INVOICE_NO)"/> |
| 12 | | |

The report output is displayed as shown in the following figure. The logic that is defined in the XDO_METADATA sheet is applied to create a hyperlink for each INVOICE_NO entry.

| Customer | Priority | Invoice Number |
|-----------|----------|-------------------------|
| Aaron | 3 | 5952174 |
| Abner | 3 | 8280605 |
| Acheson | 2 | 7604618 |
| Addison | 3 | 9645172 |
| Aeschelle | 3 | 9616238 |
| Agers | 2 | 9685385 |
| Ahab | 3 | 9644915 |
| Aiden | 3 | 9663648 |
| Ajackal | 3 | 9685016 |
| Akkers | 3 | 9706403 |
| DZIMA | 3 | 9645249 |
| CGUO | 3 | 9706193 |

Import and Call a Subtemplate

Use these commands to declare XSL subtemplates that you can then call and reference in any of the XDO_ commands.

The Template Builder for Excel doesn't support preview for templates that import subtemplates. To import the subtemplate, enter the command shown in the following table:

| Column A Entry | Column B Entry |
|--|--|
| XDO_SUBTEMPLATE_?n? where n is a unique identifier. For example: XDO_SUBTEMPLATE_?1? | <xsl:import href="xdoxsl:///path to subtemplate.xsb"/> For example: <xsl:import href="xdoxsl:///Shared Folders/Financial Reports/SubTemplates/MySubTemplate.xsb"/> |

To call the subtemplate, declare the cell name for which the results should be returned in Column A, then enter the call-template syntax with any other XSL processing to be performed. The commands are shown in the following table:

| Column A Entry | Column B Entry |
|------------------------|---|
| XDO_?cell object name? | <xsl:call-template name="template_name"> </xsl:call-template> |


For more information on XSL subtemplates and creating the subtemplate object in the catalog, see [Design XSL Subtemplates](#).

Example: Importing and Calling a Subtemplate

Assume you have the following subtemplate uploaded to the Publisher catalog as PaymentsSummary-SubTemplate.xsb. This subtemplate evaluates the value of a parameter named pPayType and based on the value, return a string that indicates the payment type:

```
<?xml version="1.0" encoding="utf-8"?>
<xsl:stylesheet version="2.0"
  xmlns:xsl="http://www.w3.org/1999/XSL/Transform">
  <xsl:template match="/">
    </xsl:template>
    <xsl:template name="BRM_PAY_TYPES">
      <xsl:param name="pPayType" select="string('ALL')"/>
      <xsl:choose>
        <xsl:when test="$pPayType = '0'">UNDEFINED</xsl:when>
        <xsl:when test="$pPayType=string('10000')">PREPAID</
xsl:when>
        <xsl:when test="$pPayType=string('10001')">INVOICE</
xsl:when>
        <xsl:when test="$pPayType=string('10003')">CREDIT CARD</
xsl:when>
        <xsl:when test="$pPayType=string('10005')">DIRECT DEBIT</
xsl:when>
        <xsl:when test="$pPayType=string('10011')">CASH</xsl:when>
        <xsl:when test="$pPayType=string('10012')">CHECK</xsl:when>
        <xsl:when test="$pPayType=string('ALL')">ALL</xsl:when>
      </xsl:choose>
    </xsl:template>
  </xsl:stylesheet>
```

In the Excel template, you've defined a field with the XDO Defined Name XDO_?TYPE?, which is populated based on the string returned from code performed in the subtemplate, as shown in the following figure:



Enter the commands shown in the following table in the Data Constraints region.

| Column A Entry | Column B Entry |
|---------------------|---|
| XDO_SUBTEMPLATE_?1? | <xsl:import href="xdoxsl:///Shared Folders/Financial Reports/SubTemplates/PaymentsSummary-SubTemplate.xsb"/> |
| XDO_?TYPE? | <xsl:call-template name="BRM_PAY_TYPES"> <xsl:with-param name="pPayType" select="string('10000')"/> </xsl:call-template> |

The XDO_SUBTEMPLATE_?1? function imports the subtemplate from the Publisher catalog.

The XDO_?TYPE? cell entry maps the results of the subtemplate processing entered in Column B.

Reference Java Extension Libraries

You can include the reference to a Java extension library in the template and then call methods from this library to perform processing in the template.

Use the command shown in the following table to reference the Java extension libraries.

| Column A Entry | Column B Entry |
|--|---|
| XDO_EXT_?n? where <i>n</i> is a unique identifier. Example: XDO_EXT?1? | <?namespace:xmlns:bipext="extension library"? > Example: <?namespace:xmlns:bipext="http://www.example.com/XSL/Transform/java/example.com.xmlpublisher.reports.BIPEExtension"?> |

You can have multiple extension libraries defined in a single template file.

Example: Calling a Java Extension Library

Assume the extension library includes the following two methods that you want to call in the template:

- bipext:infTimeToStr()
- bipext:infStrToTimet()

After you've declared the library as shown above, specify the cell to which you want to apply the method by entering the XDO defined name in Column A and calling the function in Column B. The following table shows example commands.

| Column A Entry | Column B Entry |
|------------------------|--|
| XDO_?PARAM_START_DATE? | <xsl:value-of select="bipext:infTimeToStr(bipext:infStrToTimet((// PARAM_START_DATE)[1],2),3)" |

The entries in the XDO_METADATA sheet to declare and call the Java extension libraries are shown in the following illustration.

| | | |
|----|--------------------------|---|
| 10 | Data Constraints: | |
| 11 | XDO_EXT_?1? | <?namespace:xmlns:bipext="http://www.oracle.com/XSL/Transform/java/oracle.com.xmlpublisher.reports.BIPExtension"?> <xsl:value-of select="bipext:infTimetToStr(bipext:infStrToTimet((//PARAM_START_DATE)[1], 2), 3)" |
| 12 | XDO_?PARAM_START_DATE? | |
| 13 | | |

Format Functions That Rely on Specific Data Attribute Values

The commands in this table require that specific formatting attributes be present in the XML data file.

A summary list of the commands is shown in the following table. See the corresponding section for details on usage.

| Function | Command |
|--|--------------------------------|
| Define Border and Underline Styles | XDO_STYLE_n_?cell object name? |
| Skip a Row | XDO_SKIPROW_?cell object name? |

Define Border and Underline Styles

While you can define a consistent style in the template using Excel formatting, the XDO_STYLE command enables you to define a different style for any data cell dynamically based on the XML data.

With the XDO_STYLE command you specify the cell to which to apply the style, the logic to determine when to apply the style, and the style type to apply. The style value must be present in the XML data. The following table provides examples.

| Column A Entry | Column B Entry | Column C Entry |
|--------------------------------|---|-------------------|
| XDO_STYLE_n_?cell_object_name? | <xsl evaluation that returns a supported value> | Style type |
| For example: | | For example: |
| XDO_STYLE_1_?TOTAL_SALARY? | For example: <xsl:value-of select="..//TOTAL_SALARY/@borderStyle" /> | BottomBorderStyle |

Publisher supports the normal Excel style types and values as shown in the following table:

| Style Type | Supported Values (Must be in returned by evaluation in Column B) | Supported Types (Enter in Column C) |
|------------|--|---|
| Normal | BORDER_NONE BORDER_THIN BORDER_MEDIUM BORDER_DASHED BORDER_DOTTED BORDER_THICK BORDER_DOUBLE BORDER_HAIR BORDER_MEDIUM_DASHED BORDER_DASH_DOT BORDER_MEDIUM_DASH_DOT BORDER_DASH_DOT_DOT BORDER_MEDIUM_DASH_DOT_DOT BORDER_SLANTED_DASH_DOT | BottomBorderStyle TopBorderStyle LeftBorderStyle RightBorderStyle DiagonalLineStyle |

You can also set a color using one of the types shown in the following table:

| Style Type | Supported Value (Must be in returned by evaluation in Column B) | Supported Types (Enter in Column C) |
|------------|---|---|
| Normal | When you set Color Style, give the value in RRBBGG hex format, for example: borderColor="0000FF" | BottomBorderColor TopBorderColor LeftBorderColor RightBorderColor DiagonalLineColor |

Publisher also supports the underline type with the values shown in the following table:

| Style Type | Supported Values (Must be in returned by evaluation in Column B) | Supported Type (Enter in Column C) |
|------------|--|------------------------------------|
| Underline | UNDERLINE_NONE UNDERLINE_SINGLE UNDERLINE_DOUBLE UNDERLINE_SINGLE_ACCOUNTING UNDERLINE_DOUBLE_ACCOUNTING | UnderlineStyle |

You can have multiple underline styles defined for a single cell.

Example: Defining Styles

To apply a style in a template, the style value must be present in the data. In this example, a border style and an underline style are applied to the DEPT_TOTAL_SALARY field shown in the Excel template.

For this example, the following data is used. Note that the DEPT_TOTAL_SALARY element in the data has these attributes defined:

- borderStyle
- underLineStyle
- borderColor

The value of each of these attributes is used to apply the defined style based on logic defined in the template.

```
<?xml version="1.0" encoding="UTF-8"?>

<EMPLOYEES>
  <G_DEPT>
    <DEPARTMENT_ID>10</DEPARTMENT_ID>
    <DEPARTMENT_NAME>Administration</DEPARTMENT_NAME>
    <LIST_G_EMP>
      <G_EMP>
        <EMPLOYEE_ID>200</EMPLOYEE_ID>
        <EMP_NAME>Jennifer Whalen</EMP_NAME>
        <EMAIL>JWHALEN</EMAIL>
        <PHONE_NUMBER>515.123.4444</PHONE_NUMBER>
        <HIRE_DATE>1987-09-17T00:00:00.000-06:00</HIRE_DATE>
        <SALARY>4400</SALARY>
      </G_EMP>
    </LIST_G_EMP>

    <DEPT_TOTAL_SALARY borderStyle="BORDER_DOUBLE"
underLineStyle="UNDERLINE_DOUBLE_ACCOUNTING" borderColor="0000FF">4400</
DEPT_TOTAL_SALARY>
  </G_DEPT>
  <G_DEPT>
    <DEPARTMENT_ID>20</DEPARTMENT_ID>
    <DEPARTMENT_NAME>Marketing</DEPARTMENT_NAME>
    <LIST_G_EMP>
      <G_EMP>
        <EMPLOYEE_ID>201</EMPLOYEE_ID>
        <EMP_NAME>Michael Hartstein</EMP_NAME>
        <EMAIL>MHARTSTE</EMAIL>
        <PHONE_NUMBER>515.123.5555</PHONE_NUMBER>
        <HIRE_DATE>1996-02-17T00:00:00.000-07:00</HIRE_DATE>
        <SALARY>13000</SALARY>
      </G_EMP>
      <G_EMP>
        <EMPLOYEE_ID>202</EMPLOYEE_ID>
        <EMP_NAME>Pat Fay</EMP_NAME>
        <EMAIL>PFAY</EMAIL>
        <PHONE_NUMBER>603.123.6666</PHONE_NUMBER>
```

```
<HIRE_DATE>1997-08-17T00:00:00.000-06:00</HIRE_DATE>
<SALARY>6000</SALARY>
</G_EMP>
</LIST_G_EMP>
```

```
<DEPT_TOTAL_SALARY borderStyle="BORDER_DOUBLE"
underlineStyle="UNDERLINE_DOUBLE_ACCOUNTING"
borderColor="0000FF">19000</DEPT_TOTAL_SALARY>
</G_DEPT>
```

...

```
</EMPLOYEES>
```

To define a style:

1. In the Excel template, assign the defined name XDO_?DEPT_TOTAL_SALARY? to the field that is to display the DEPT_TOTAL_SALARY from the data, as shown in the following figure:

| | A | B | C | D | F | G |
|----|---------------------------------------|--------------------|-----------------|------------------|------------------|---------------|
| 1 | Employees by Department Report | | | | | |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| 5 | Department: Admin | | | | | |
| 6 | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary |
| 8 | John Thomas | 100001 | john@oracle.com | 111-333-3333 | 3-Feb-96 | 10,000 |
| 9 | | | | | | 10,000 |
| 10 | | | | | | |
| 11 | | | | | | |

2. In the XDO_METADATA sheet, enter the following:
 - To define the top border style, use these entries:
 - Column A entry: XDO_STYLE_1_?DEPT_TOTAL_SALARY?
 - Column B entry: `<xsl:value-of select="//DEPT_TOTAL_SALARY/@borderStyle"/>`
 - Column C entry: TopBorderStyle

The entry in Column A maps this style command to the cell assigned the name XDO_?DEPT_TOTAL_SALARY?

The entry in Column B retrieves the style value from the attribute borderStyle of the DEPT_TOTAL_SALARY element. Note from the sample data that the value for borderStyle is "BORDER_DOUBLE".

The entry in Column C tells Publisher to apply a TopBorderStyle to the cell.
 - To define the top border color, use these entries:

- Column A entry: XDO_STYLE_2_?DEPT_TOTAL_SALARY?
- Column B entry: <?.//DEPT_TOTAL_SALARY/@borderColor?>
- Column C entry: TopBorderColor

The entry in Column A maps this style command to the cell assigned the name XDO_?DEPT_TOTAL_SALARY?

The entry in Column B retrieves the style value from the attribute borderColor of the DEPT_TOTAL_SALARY element. Note from the sample data that the value for borderColor is 0000FF (blue).

The entry in Column C tells Publisher to apply a TopBorderColor to the cell.

- To define the underline style, use these entries:
 - Column A entry: XDO_STYLE_3_?DEPT_TOTAL_SALARY?
 - Column B entry: <?.//DEPT_TOTAL_SALARY/@underLineStyle?>
 - Column C entry: UnderLineStyle

The entry in Column A maps this style command to the cell assigned the name XDO_?DEPT_TOTAL_SALARY?

The entry in Column B retrieves the style value from the attribute underLineStyle of the DEPT_TOTAL_SALARY element. Note from the sample data that the value for underLineStyle is UNDERLINE_DOUBLE_ACCOUNTING.

The entry in Column C tells Publisher to apply the UnderLineStyle to the cell.

The following figure shows the three entries in the Data Constraints region:

| | | | |
|----|---------------------------------|--|----------------|
| 9 | | | |
| 10 | Data Constraints: | | |
| 11 | XDO_STYLE_1_?DEPT_TOTAL_SALARY? | <xsl:value-of select="..//DEPT_TOTAL_SALARY/@borderStyle"/> | TopBorderStyle |
| 12 | XDO_STYLE_2_?DEPT_TOTAL_SALARY? | <?.//DEPT_TOTAL_SALARY/@borderColor?> | TopBorderColor |
| 13 | XDO_STYLE_3_?DEPT_TOTAL_SALARY? | <?.//DEPT_TOTAL_SALARY/@underLineStyle?> | UnderLineStyle |
| 14 | | | |
| 15 | | | |

When you run the report, the style commands are applied to the XDO_?DEPT_TOTAL_SALARY? cell, as shown in the following figure:

| | A | B | C | D | F | G |
|----|---------------------------------------|--------------------|--------------|------------------|------------------|---------------|
| 1 | Employees by Department Report | | | | | |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| 5 | Department: | Administration | | | | |
| 6 | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary |
| 8 | Jennifer Whalen | 200 | JWHALEN | 515.123.4444 | 17-Sep-87 | 4,400 |
| 9 | | | | | | 4,400 |
| 10 | Department: | Marketing | | | | |
| 11 | | | | | | |
| 12 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary |
| 13 | Michael Hartstein | 201 | MHARTSTE | 515.123.5555 | 17-Feb-96 | 13,000 |
| 14 | Pat Fay | 202 | PFAY | 603.123.6666 | 17-Aug-97 | 6,000 |
| 15 | | | | | | 19,000 |
| 16 | Department: | Purchasing | | | | |
| 17 | | | | | | |
| 18 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary |
| 19 | Shelli Baida | 116 | SBAIDA | 515.127.4563 | 24-Dec-97 | 2,900 |
| 20 | Sigal Tobias | 117 | STOBIAS | 515.127.4564 | 24-Jul-97 | 2,800 |
| 21 | Karen Colmenare | 119 | KCOLMENA | 515.127.4566 | 10-Aug-99 | 2,500 |
| 22 | Alexander Khoo | 115 | AKHOO | 515.127.4562 | 18-May-95 | 3,100 |
| 23 | Guy Himuro | 118 | GHIMURO | 515.127.4565 | 15-Nov-98 | 2,600 |
| 24 | Den Raphaely | 114 | DRAPHEAL | 515.127.4561 | 7-Dec-94 | 11,000 |
| 25 | | | | | | 24,900 |
| 26 | Department: | Human Resources | | | | |

Skip a Row

Use the XDO_SKIPROW command to suppress the display of a row of data in a table when the results of an evaluation defined in Column B return the case insensitive string "True".

Example entries are shown in the following table.

| Column A Entry | Column B Entry |
|--------------------------------|---|
| XDO_SKIPROW_?cell_object_name? | <xsl evaluation that returns the string "True"/> |
| For example: | For example: |
| XDO_SKIPROW_?EMPLOYEE_ID? | <xsl:if test="string-length(/EMPLOYEE_ID/@MANAGER) != 0"> <xsl:value-of select="/EMPLOYEE_ID/@MANAGER"/> </xsl:if> |

Example: Skip a Row Based on Data Element Attribute

In this example, the Excel template suppresses the display of the row of employee data when the EMPLOYEE_ID element includes a "MANAGER" attribute with the value "True".

Assume data as shown below. Note that the EMPLOYEE_ID element for employee Michael Hartstein has the MANAGER attribute with the value "True". The other EMPLOYEE_ID elements in this set do not have the attribute.

```
<?xml version="1.0" encoding="UTF-8"?>

<EMPLOYEES>
  <G_DEPT>
    <DEPARTMENT_ID>20</DEPARTMENT_ID>
    <DEPARTMENT_NAME>Marketing</DEPARTMENT_NAME>
    <LIST_G_EMP>
      <G_EMP>
        <EMPLOYEE_ID MANAGER="TRUE">201</EMPLOYEE_ID>
        <EMP_NAME>Michael Hartstein</EMP_NAME>
        <EMAIL>MHARTSTE</EMAIL>
        <PHONE_NUMBER>515.123.5555</PHONE_NUMBER>
        <HIRE_DATE>1996-02-17T00:00:00.000-07:00</HIRE_DATE>
        <SALARY>13000</SALARY>
      </G_EMP>
      <G_EMP>
        <EMPLOYEE_ID>202</EMPLOYEE_ID>
        <EMP_NAME>Pat Fay</EMP_NAME>
        <EMAIL>PFAY</EMAIL>
        <PHONE_NUMBER>603.123.6666</PHONE_NUMBER>
        <HIRE_DATE>1997-08-17T00:00:00.000-06:00</HIRE_DATE>
        <SALARY>6000</SALARY>
      </G_EMP>
      <G_EMP>
        <EMPLOYEE_ID>652</EMPLOYEE_ID>
        <EMP_NAME>William Morgan</EMP_NAME>
        <EMAIL>WMORGAN</EMAIL>
        <PHONE_NUMBER>219.123.7776</PHONE_NUMBER>
        <HIRE_DATE>1994-10-17T00:00:00.000-06:00</HIRE_DATE>
        <SALARY>8000</SALARY>
      </G_EMP>
    </LIST_G_EMP>
  </G_DEPT>

  ...

</EMPLOYEES>
```

To suppress the display of the row of the employee data when the MANAGER attribute is set to "True", enter the entries shown in the following table in the Data Constraints section.

| Column A Entry | Column B Entry |
|---------------------------|---|
| XDO_SKIPROW_?EMPLOYEE_ID? | <xsl:if test="string-length(/EMPLOYEE_ID/@MANAGER) != 0"> <xsl:value-of select="/EMPLOYEE_ID/@MANAGER"/> </xsl:if> |

The output from this template is shown in the following illustration. Note that the employee Michael Hartstein isn't included in the report.

| | A | B | C | D | F | G |
|----|---------------------------------------|--------------------|--------------|------------------|------------------|---------------|
| 1 | Employees by Department Report | | | | | |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| 5 | Department: | Marketing | | | | |
| 6 | | | | | | |
| 7 | Employee Name | Employee ID | Email | Telephone | Hire Date | Salary |
| 8 | Pat Fay | 202 | PFAY | 603.123.6666 | 17-Aug-97 | 6,000 |
| 9 | William Morgan | 652 | WMORGAN | 219.123.7776 | 17-Oct-94 | 8,000 |
| 10 | | | | | | <u>14,000</u> |
| 11 | | | | | | |

Group Functions

Use the functions shown in this table to create groupings of data in the template.

| Function | Command |
|------------------|--|
| Group Data | <code>XDO_GROUP_?group element?</code> |
| Regroup the Data | <code>XDO_REGROUP_?</code> |

Group Data

Use the `XDO_GROUP` command to group flat data when the layout requires a specific data grouping, for example, to split the data across multiple sheets.

Example entries are shown in the following table:

| Column A Entry | Column B Entry | Column C Entry |
|--|--|--|
| <code>XDO_GROUP_?group element?</code> | <code><xsl beginning groupng logic/></code> | <code><xsl ending groupng tags/></code> |
| For example: | For example: | For example: |
| <code>XDO_GROUP_? STATE_GROUP?</code> | <code><xsl:for-each-group select="current-group()" group-by="./STATE"> <xsl:for-each-group select="current-group()" group-by="./RESOURCE_NAME"> <xsl:for-each select="current-group()"></code> | <code></xsl:for-each> <xsl:for-each-group> <xsl:for-each-group></code> |

Define the XSL statements to be placed at the beginning and ending of the section of the group definition marked up by `XDO_?cell object name?`. You can mark multiple groups nested in the template, giving each the definition appropriate to the corresponding group.

Handle the Generated XDO Define Names in Nested Groups

When `XDO_GROUP_?` is used in a nested group, the ranges of XDO define names in the final report become meaningless. In this case, don't refer to the define names in

formulas in the final report. You can disable the XDO markup activity in the final report using the command `XDO_MARKUP_?`.

The following table shows the usage of `XDO_MARKUP_?` in the `XDO_METADATA` sheet:

| Column A Entry | Column B Entry |
|---------------------------|--|
| <code>XDO_MARKUP_?</code> | "false" or "FALSE" (The cell must be formatted as Text in the Excel Format Cells dialog.) |

In addition, if your template includes a large number of defined names and these are used in multiple levels of nested groups, Excel may not be able to handle the number of generated defined names. In this case, use the `XDO_MARKUP_?` command to disable markup for the generated report.

When set to false, Publisher doesn't produce any defined names for any result produced by `XDO_GROUP_?`

Regroup the Data

The `XDO_REGROUP` regroups the data by declaring the structure using the defined names.

The `XDO_REGROUP` logic is a shortened form of the `XDO_GROUP` logic and doesn't require the XSLT coding requirements in the `XDO_METADATA` sheet. The definition must therefore be directly on `XDO_REGROUP_?` define names, or on any other definition on the `XDO_METADATA` sheet. Entries are shown in the following table.

| Column A Entry | Column B Entry |
|----------------------------|--|
| <code>XDO_REGROUP_?</code> | <code>XDO_REGROUP_?UniqueGroupID?levelName?groupByName?sortByName?sortByName?sortByName?</code> where <ul style="list-style-type: none"> • <code>UniqueGroupID</code> is the ID of the group. It can be the same as the <code>levelName</code> or you can assign it a unique name. • <code>levelName</code> is the XML level tag name in the XML data file or <code>XDO_CURRGRP_?</code> that represents the <code>current-group()</code> in the context of nested grouping. <code>XDO_CURRGRP_?</code> should be used for all inner groups when more than one nesting group exists in your template. • <code>groupByName</code> is the field name that you want to use for the <code>GroupBy</code> operation for the current group. This name can be empty if the <code>XDO_REGROUP_?</code> command is used for the most inner group. • <code>sortByName</code> is the field name that you want to sort the group by. You can have multiple <code>sortBy</code> fields. If no <code>sortByName</code> is declared, then the data from the XML file isn't sorted. |

The next three tables show an example of how to create three nested groupings.

| Column A Entry | Column B Entry |
|----------------|---|
| XDO_REGROUP_? | XDO_REGROUP_?PAYMENTSUMMARY_Q1? PAYMENTSUMMARY_Q1?PAY_TYPE_NAME? |

In the definition shown in the previous table, the most outer group is defined as PAYMENTSUMMARY_Q1, and it's grouped by PAY_TYPE_NAME

| Column A Entry | Column B Entry |
|----------------|---|
| XDO_REGROUP_? | XDO_REGROUP_?COUNTRYGRP? XDO_CURRGRP_?COUNTRY? |

The definition shown in the previous table creates a second outer group. The group is assigned the name COUNTRY_GRP and it's grouped by the element COUNTRY.

| Column A Entry | Column B Entry |
|----------------|---|
| XDO_REGROUP_? | XDO_REGROUP_?STATEGRP?XDO_CURRGRP_? STATE? |

The definition shown in the previous table creates the inner group STATEGRP and it includes a sortByName parameter: STATE.

Preprocess the Data Using an XSL Transformation (XSLT) File

For the best performance, design the data model to perform as much of the data processing as possible. When you can't get the required output from the data engine, you can preprocess the data using an XSLT file that contains the instructions to transform the data.

Some sample use cases include:

- To create groups to establish the necessary hierarchy to support the desired layout.
- To add style attributes to data elements.
- To perform complex data processing logic that may be impossible in the Excel Template or undesirable for performance reasons. The Template Builder for Excel doesn't support preview for templates that require XSLT preprocessing.

To use an XSLT preprocess file:

1. Create the file and save as .xsl.
2. Upload the file to the report definition in the Publisher catalog, as you would a template:
 - a. Navigate to the report in the catalog.
 - b. Click **Edit**.
 - c. Click **Add New Layout**.
 - d. Click **Upload**.

- e. Complete the fields in the Upload dialog and select **XSL Stylesheet (HTML/XML/Text)** as the template **Type**.
 - f. After upload, click **View a List**. Deselect **Active**, so that users do not see this template as an option when they view the report.

For testing purposes, you might want to maintain the XSL template as active to enable you to view the intermediate data when the template is applied to the data. After testing is complete, set the template to inactive.
 - g. Save the report definition.
3. In the Excel template, on the XDO_METADATA sheet, in the Header section, enter the file name for the **Preprocess XSLT File** parameter. For example: `splitByBrand.xsl`.

XSLT Preprocessing Examples: Split Flat Data into Multiple Sheets

This topic presents two examples of using an XSLT preprocess file to group flat data so that it can be split into multiple sheets in Excel.

The examples are:

- [Split the Data by a Specific Field](#)
- [Split the Data by Count of Rows](#)

Splitting the data by row count is an option when your report data exceeds the sheet row size of Excel 2003 (65,536 rows per sheet).

Both examples use the following XML data:

```
<ROWSET>
  <ROW>
    <Products.Type>COATINGS</Products.Type>
    <Products.Brand>Enterprise</Products.Brand>
    <Markets.Region>CENTRAL REGION</Markets.Region>
    <Markets.District>CHICAGO DISTRICT</Markets.District>
    <Periods.Year>2000</Periods.Year>
    <Measures.Dollars>1555548.0</Measures.Dollars>
  </ROW>
  <ROW>
    <Products.Type>COATINGS</Products.Type>
    <Products.Brand>Enterprise</Products.Brand>
    <Markets.Region>EASTERN REGION</Markets.Region>
    <Markets.District>NEW YORK DISTRICT</Markets.District>
    <Periods.Year>2000</Periods.Year>
    <Measures.Dollars>1409228.0</Measures.Dollars>
  </ROW>
  ...
</ROWSET>
```

Split the Data by a Specific Field

This example demonstrates how to use an XSLT preprocess file to create a grouping in the data that will enable the splitting of the data across multiple Excel sheets based on the grouping.

This example groups the sample data by the `Products.Brand` field.

1. Create an XSLT file to group the data.

The following sample XSLT file groups the data according to `<Products.Brand>` and creates a high level element `<BrandGroup>` for each of those groups.

```
<?xml version="1.0" encoding="utf-8" ?>
  <xsl:stylesheet version="2.0" xmlns:xsl="http://www.w3.org/
1999/XSL/Transform">
  <xsl:template match="/">
    <ROWSET>
      <xsl:for-each-group select="/ROWSET/ROW" group-by="./
Products.Brand">
        <xsl:variable name="var_brand" select="current-grouping-
key()" />
        <BrandGroup>
          <xsl:attribute name="name">
            <xsl:value-of select="$var_brand" />
          </xsl:attribute>
          <xsl:copy-of select="current-group()" />
        </BrandGroup>
      </xsl:for-each-group>
    </ROWSET>
  </xsl:template></xsl:stylesheet>
```

When applied to the data sample, this XSLT file generates intermediate data as follows:

```
<ROWSET>
  <BrandGroup name="Enterprise">
    <ROW>
      <Products.Type>COATINGS</Products.Type>
      <Products.Brand>Enterprise</Products.Brand>
      <Markets.Region>CENTRAL REGION</Markets.Region>
      <Markets.District>CHICAGO DISTRICT</Markets.District>
      <Periods.Year>2000</Periods.Year>
      <Measures.Dollars>1555548.0</Measures.Dollars>
    </ROW>
    ...
  </BrandGroup>
  ... <ROWSET>
```

2. Save the XSLT file as `splitByBrand.xml` and upload the file to the report definition in the catalog. Select "XSL Stylesheet (HTML/XML/Text)" as the template type.
3. In the Excel template file, in the `XDO_METADATA` sheet, enter the following:
 - For the **Preprocess XSLT File** parameter, enter "splitByBrand.xml"

- In the Data Constraints region, make the entries to split the data into multiple sheets based on the <BrandGroup> element created by the results of the XSLT preprocessing.
 - Column A entry: XDO_SHEET_?, Column B entry: <?//BrandGroup?>
 - Column A entry: XDO_SHEET_NAME_?, Column B entry: <?./@name?>

The sample entries in the XDO_METADATA sheet are shown in this figure.

| | A | B |
|----|--------------------------|---------------------|
| 1 | Version | |
| 2 | ARU-dbdrv | |
| 3 | Extractor Version | |
| 4 | Template Code | |
| 5 | Template Type | TYPE_EXCEL_TEMPLATE |
| 6 | Preprocess XSLT File | splitByBrand.xsl |
| 7 | Last Modified Date | |
| 8 | Last Modified By | |
| 9 | | |
| 10 | Data Constraints: | |
| 11 | XDO_SHEET_? | <?//BrandGroup?> |
| 12 | XDO_SHEET_NAME_? | <?./@name?> |
| 13 | | |

4. Hide the XDO_METADATA sheet if you do not want your users to see it. Upload the Excel template file to the report definition in the catalog.

Split the Data by Count of Rows

This example demonstrates how to use an XSLT preprocess file to group the sample XML data.

Group the sample XML data by the count of occurrences of /ROWSET/ROW, and then configure the Excel template to create a new sheet for each occurrence of the newly created group.

1. Create an XSLT file to create groups in the data according to a size specified in a variable.

The following sample XSLT file groups the occurrences of /ROWSET/ROW according to the value of \$var_size and creates a high level element <CountGroup> for each of those groups.

```
<?xml version="1.0" encoding="utf-8" ?> <xsl:stylesheet
version="2.0"
xmlns:xsl="http://www.w3.org/1999/XSL/Transform">
  <xsl:template match="/">
    <ROWSET>
      <xsl:variable name="var_size" select="3" />
      <xsl:for-each select="/ROWSET/ROW">
        <xsl:variable name="var_pos" select="position()" />
        <xsl:variable name="var_mod" select="$var_pos
mod($var_size)" />
        <xsl:if test="$var_mod = 1">
          <xsl:variable name="var_groupNum" select="($var_pos -
$var_mod) div number($var_size) + 1" />
```

```

        <xsl:element name="CountGroup">
          <xsl:attribute name="name">
            <xsl:value-of select="concat('Group', $var_groupNum)" />
          </xsl:attribute>
          <xsl:for-each select="/ROWSET/ROW[position() > ($var_pos -1)
and position() < ($var_pos + $var_size)]">
            <xsl:copy-of select="." />
          </xsl:for-each>
        </xsl:element>
      </xsl:if>
    </xsl:for-each>
  </ROWSET>
</xsl:template>
</xsl:stylesheet>

```

When applied to the data sample, this XSLT file generates intermediate data as follows:

```

<ROWSET>
  <CountGroup name="Group1">
    <ROW>
      <Products.Type>COATINGS</Products.Type>
      <Products.Brand>Enterprise</Products.Brand>
      <Markets.Region>CENTRAL REGION</Markets.Region>
      <Markets.District>CHICAGO DISTRICT</Markets.District>
      <Periods.Year>2000</Periods.Year>
      <Measures.Dollars>1555548.0</Measures.Dollars>
    </ROW>
    ...
  </CountGroup>
  ...
</ROWSET>

```

2. Save the XSLT file as `splitByCount.xsl` and upload the file to the report definition in the catalog. Select "XSL Stylesheet (HTML/XML/Text)" as the template type.
3. In the Excel template file, in the XDO_METADATA sheet, enter the following:
 - For the **Preprocess XSLT File** parameter, enter "splitByCount.xsl".
 - In the **Data Constraints** region, make these entries.
 - Column A entry: XDO_SHEET_?, Column B entry: <?//CountGroup?>
 - Column A entry: XDO_SHEET_NAME_?, Column B entry: <?./@name?>
4. Hide the XDO_METADATA sheet so that it doesn't display to report consumers.
5. Upload the Excel template file to the report definition in the catalog.

16

Create PDF Templates

This topic describes creating PDF templates for reports.

Topics:

- [Overview](#)
- [Requirements](#)
- [Design the Template](#)
- [Add Markup to the Template](#)
- [Create a Placeholder](#)
- [Define Groups of Repeating Fields](#)
- [Repeat a PDF Template by Using the document-repeat-elementname Form Field](#)
- [Add Page Numbers and Breaks](#)
- [Perform Calculations](#)
- [Completed PDF Layout Example](#)
- [Runtime Behavior](#)
- [Create a Layout from a Predefined PDF Form](#)
- [Add or Designate a Field for a Digital Signature](#)
- [PDF Template Limitations](#)

Overview

To create a PDF template, take an existing PDF document and apply the Publisher markup.

Because you can use a PDF from any source, you have multiple design options. For example:

- Design the template using any application that generates documents that can be converted to PDF, such as Microsoft Word
- Scan a paper document to use as a template
- Download a PDF document from a third-party website

Note:

The steps required to create a template from a third-party PDF depend on whether form fields have been added to the document. For more information, see [Create a Layout from a Predefined PDF Form](#).

If you are designing the template, then when you've converted to PDF, the template is treated like a set background. When you mark up the template, you draw fields on top of this background. To edit the template, you must edit the original document and then convert back to PDF.

For this reason, the PDF template isn't recommended for documents that require frequent updates. However, it's appropriate for forms that have a fixed template, such as invoices or purchase orders.

Requirements

To apply or edit form fields in a PDF document, you must have Adobe Acrobat Professional.

Publisher supports Adobe Acrobat 5.0 and later as a tool for updating the template.


Publisher generates the output PDF version based on the input PDF version as follows:

- PDF version 1.4 and earlier generates PDF 1.4
- PDF version 1.5 and later generates the same output version as the input version

Design the Template

To design the template you can use any desktop application that generates documents that can be converted to PDF. Or, scan in an original paper document to use as the background for the template.

The following figure shows a template for a sample purchase order. It was designed using Microsoft Word and converted to PDF using Adobe Acrobat Distiller.

|  | | Purchase Order | | | | | |
|---|-------------------------|------------------------|----------------------|------|--------------|-----------|----------------------|
| | | PURCHASE ORDER NO. | REVISION | | | | |
| VENDOR: | | SHIP TO: | | | | | |
| | | BILL TO: | | | | | |
| CUSTOMER ACCOUNT NO. | VENDOR NO. | DATE OF ORDER/BUYER | REVISED DATE/BUYER | | | | |
| PAYMENT TERMS | | SHIP VIA | JOB | | | | |
| FREIGHT TERMS | | REQUEST FOR DELIVER TO | CONFIRM TO TELEPHONE | | | | |
| ITEM | PART NUMBER/DESCRIPTION | DELIVERY | QUANTITY | UNIT | UNIT PRICE | EXTENSION | TAX |
| | | | | | Total | | |
| Oracle E-Business Suite | | | | | | | AUTHORIZED SIGNATURE |

The following is the XML data that is used as input to this template:

```
<?xml version="1.0"?>
<POXPRPOP2>
  <G_HEADERS>
    <POH_PO_NUM>1190-1</POH_PO_NUM>
    <POH_REVISION_NUM>0</POH_REVISION_NUM>
    <POH_SHIP_ADDRESS_LINE1>3455 108th Avenue</POH_SHIP_ADDRESS_LINE1>
    <POH_SHIP_ADDRESS_LINE2></POH_SHIP_ADDRESS_LINE2>
    <POH_SHIP_ADDRESS_LINE3></POH_SHIP_ADDRESS_LINE3>
    <POH_SHIP_ADR_INFO>Seattle, WA 98101</POH_SHIP_ADR_INFO>
    <POH_SHIP_COUNTRY>United States</POH_SHIP_COUNTRY>
    <POH_VENDOR_NAME>Allied Manufacturing</POH_VENDOR_NAME>
    <POH_VENDOR_ADDRESS_LINE1>1145 Brokaw Road</POH_VENDOR_ADDRESS_LINE1>
    <POH_VENDOR_ADR_INFO>San Jose, CA 95034</POH_VENDOR_ADR_INFO>
```



```

<POH_VENDOR_COUNTRY>United States</POH_VENDOR_COUNTRY>
<POH_BILL_ADDRESS_LINE1>90 Fifth Avenue</POH_BILL_ADDRESS_LINE1>
<POH_BILL_ADR_INFO>New York, NY 10022-3422</POH_BILL_ADR_INFO>
<POH_BILL_COUNTRY>United States</POH_BILL_COUNTRY>
<POH_BUYER>Smith, J</POH_BUYER>
<POH_PAYMENT_TERMS>45 Net (terms date + 45)</POH_PAYMENT_TERMS>
<POH_SHIP_VIA>UPS</POH_SHIP_VIA>
<POH_FREIGHT_TERMS>Due</POH_FREIGHT_TERMS>
<POH_CURRENCY_CODE>USD</POH_CURRENCY_CODE>
<POH_CURRENCY_CONVERSION_RATE></POH_CURRENCY_CONVERSION_RATE>
<LIST_G_LINES>
<G_LINES>
<POL_LINE_NUM>1</POL_LINE_NUM>
<POL_VENDOR_PRODUCT_NUM></POL_VENDOR_PRODUCT_NUM>
<POL_ITEM_DESCRIPTION>PCMCIA II Card Holder</POL_ITEM_DESCRIPTION>
<POL_QUANTITY_TO_PRINT></POL_QUANTITY_TO_PRINT>
<POL_UNIT_OF_MEASURE>Each</POL_UNIT_OF_MEASURE>
<POL_PRICE_TO_PRINT>15</POL_PRICE_TO_PRINT>
<C_FLEX_ITEM>CM16374</C_FLEX_ITEM>
<C_FLEX_ITEM_DISP>CM16374</C_FLEX_ITEM_DISP>
<PLL_QUANTITY_ORDERED>7500</PLL_QUANTITY_ORDERED>
<C_AMOUNT_PLL>112500</C_AMOUNT_PLL>
<C_AMOUNT_PLL_DISP> 112,500.00 </C_AMOUNT_PLL_DISP>
</G_LINES>
</LIST_G_LINES>
<C_AMT_POL_RELEASE_TOTAL_ROUND>312420</C_AMT_POL_RELEASE_TOTAL_ROUND>
</G_HEADERS>
</POXPRPOP2>

```

Add Markup to the Template

After you've converted a document to PDF, you define form fields that display the data from the XML input file. These form fields are placeholders for the data. The process of associating the XML data to the PDF template is the same as the process for the RTF template.

See [Associate the XML Data to the Template Layout](#).

When you draw the form fields in Adobe Acrobat, you're drawing them *on top* of the template that you designed. There isn't a relationship between the design elements on the template and the form fields. You therefore must place the fields exactly where you want the data to display on the template.

Create a Placeholder

You can define a placeholder as text, a check box, or a radio button, depending on how you want the data presented.

The steps for adding a form field depend on the version of Adobe Acrobat Professional that you are using. See the Adobe documentation for the version. If you are using Adobe Acrobat 9 Pro, then from the **Forms** menu, select **Add or Edit Fields**.

Name the Placeholder

The name of the placeholder must match the XML source field name.

Create a Text Placeholder

Follow these steps to create a text Form Field placeholder using Adobe Acrobat 9 Pro. If you are using a different version of Adobe Acrobat Professional, then refer to the documentation for details.

To create a text placeholder:

1. From the **Forms** menu, select **Add or Edit Fields**.
2. From the **Add New Field** list, choose **Text Field**. The cursor becomes a crosshair.
3. Place the crosshair in the form where you want the field to reside and click. The Field Name dialog pops up.
4. Enter the name. The name of the text field must match the name of the XML element from the data that is to populate this field at runtime.
5. To set more properties, click **Show All Properties**.
Use the Properties dialog box to set other attributes for the placeholder. For example, enforce maximum character size, set field data type, data type validation, visibility, and formatting.
6. If required, drag the field for exact placement and resize the field using the handles.

Supported Field Properties Options

Publisher supports the following options available from the Field Properties dialog box.

Note that these options are not available when you use repeating fields. For more information about these options, see the Adobe Acrobat documentation.

- **General**
 - Read Only
The setting of this check box in combination with a set of configuration properties controls the read-only/updatable state of the field in the output PDF. See [Set Fields as Updatable or Read Only](#).
 - Required
 - Visible/Hidden
 - Orientation (in degrees)
- **Appearance**
 - Border Settings: color, background, width, and style
 - Text Settings: color, font, size
 - Border Style
- **Options** tab

- Multi-line
- Scrolling Text
- **Format** tab - Number category options only
- **Calculate** tab - all calculation functions

Create a Check Box

A check box is used to present options from which more than one can be selected. Each check box represents a different data element. You define the value that causes the check box to display as *checked*.

For example, a form contains a check box listing of automobile options such as Power Steering, Power Windows, and Sunroof. Each of these represents a different element from the XML file (for example `<POWER_STEERING>`). If the XML file contains a value of `Y` for any of these fields, you want the check box to display as checked. All or none of these options may be selected.

The following describes how to create a check box field using Adobe Acrobat 9 Pro. If you are using a different version of Adobe Acrobat Professional, refer to the documentation for details.

To create a check box:

1. From the **Forms** menu, select **Add or Edit Fields**.
2. From the **Add New Field** list, choose **Check Box**. The cursor becomes a crosshair.
3. Place the crosshair in the form where you want the field to reside and click. The Field Name dialog pops up.
4. Enter the name. The name of the check box field must match the name of the XML element from the data that is to determine its state (checked or unchecked).
5. Click **Show All Properties**
6. Click the **Options** tab.
7. Select the **Check Box Style** type from the list.
8. In the **Export Value** field enter the value that the XML data field should match to enable the "checked" state.

For example, enter "Y" for each check box field.
9. Set other **Properties** as desired.

Create a Radio Button Group

A radio button group is used to display options from which only one can be selected.

For example, the XML data file contains a field called `<SHIPMENT_METHOD>`. The possible values for this field are "Standard" or "Overnight". You represent this field in the form with two radio buttons, one labeled "Standard" and one labeled "Overnight". Define both radio button fields as placeholders for the `<SHIPMENT_METHOD>` data field. For one field, define the *on* state when the value is Standard. For the other, define the *on* state when the value is Overnight.

The following describes how to create a radio button group using Adobe Acrobat 9 Pro. If you are using a different version of Adobe Acrobat Professional, then refer to the documentation for details.

To create a radio button group:

1. From the **Forms** menu, select **Add or Edit Fields**.
2. From the **Add New Field** list, choose **Radio Button**. The cursor becomes a crosshair.
3. Place the crosshair in the form where you want the radio button group to reside and click. The Radio Group Name dialog pops up.
4. Enter the name. The name of the radio group must match the name of the XML element from the data that is to determine its state (selected or unselected).
5. In the **Button Value** field enter the value that the XML data field should match to enable the *on* state.
For the example, enter Standard for the field labeled Standard.
6. To enter another radio button to the group, click **Add another button to group**. The name of the radio group defaults into the name field.
7. In the **Button Value** field enter the value that the XML data field should match to enable the *on* state for this button.
For example, enter Overnight for the field labeled Overnight.
8. If you want to change any of the properties, then click **Show All Properties**. To change the radio button style, click the **Options** tab.
9. Select **Radio Button** from the **Type** drop down list.
10. Set other **Properties** as desired.

Define Groups of Repeating Fields

In the PDF layout, you explicitly define the area on the page that contains the repeating fields. For example, on the purchase order layout, the repeating fields should display in the block of space between the Item header row and the Total field.

To define the area to contain the group of repeating fields:

1. Insert a Text Field at the beginning of the area that is to contain the group.
2. In the Field Name dialog, enter any unique name you choose. This field isn't mapped.
3. In the **Tooltip** field of the Text Field Properties dialog, enter the following syntax:

```
<?rep_field="BODY_START"?>
```
4. Define the end of the group area by inserting a Text Field at the end of the area the that is to contain the group.
5. In the Field Name dialog, enter any unique name you choose. This field isn't mapped. Note that the name you assign to this field must be different from the name you assigned to the **body start** field.
6. In the **Tooltip** field of the Text Field Properties dialog, enter the following syntax:

```
<?rep_field="BODY_END"?>
```

To define a group of repeating fields:

1. Insert a placeholder for the first element of the group. The placement of this field in relationship to the BODY_START tag defines the distance between the repeating rows for each occurrence.
2. For each element in the group, enter the following syntax in the **Tooltip** field:

```
<?rep_field="T1_Gn"?>
```

where n is the number of the element in the group.

For example, the group in the sample report is laid out in three rows.

- For the fields belonging to the row that begins with PO_LINE_NUM enter

```
<?rep_field="T1_G1"?>
```
- For the fields belonging to the row that begins with C_FLEX_ITEM_DISP enter

```
<?rep_field="T1_G2"?>
```
- For the fields belonging to the row that begins with C_SHIP_TO_ADDRESS enter

```
<?rep_field="T1_G3"?>
```

The following figure shows the entries for the **Short Description/Tooltip** field:

| FREIGHT TERMS | | REQUESTOR/DELIVER TO | | |
|-------------------|-------------------------|----------------------|----------|--|
| POH_FREIGHT_TERMS | | | | |
| ITEM | PART NUMBER/DESCRIPTION | DELIVERY | QUANTITY | |
| body_start | | | | |
| PO | IPOL_ITEM_DESCRIF | | | |
| | C_FLEX_ITEM_DISP | | | |
| | C_SHIPTO_ADDRESS | IPLL DUE | IPLL QU | |

Diagram illustrating the placement of the `<?rep_field="BODY_START"?>` and `<?rep_field="T1_G1"?>`, `<?rep_field="T1_G2"?>`, and `<?rep_field="T1_G3"?>` tags relative to the report structure.

Repeat a PDF Template by Using the document-repeat-elementname Form Field

The `document-repeat-elementname` form field in a PDF template enables repeating the entire template for a specified group of data elements.

When you want to use the same PDF template for a group of data elements, set the `document-repeat-elementname` PDF form field to the group name of the data elements to be used in the report.

Repeat a PDF Template in a Report


If the `document-repeat-elementname` PDF form field is set, when you run the report, the FormProcessor utility sends the PDF template and the associated XML data to the document repeat engine. The document repeat engine repeats the PDF template for each element of the group specified by `document-repeat-elementname`, and generates the report.

Example 16-1 Generate Monthly Payslips

To generate the monthly payslips for each employee in a department, set the `document-repeat-elementname` form field as shown below to the name of the group element associated with the data of employees in the department, and provide the XML data that contains the `employee_Data` element to the template. The report will iterate the same template for each employee payslip.

```
<?set-property: document-repeat-elementname; employee_Data?>
```

The following figure shows the `documents-repeat-elementname` field entry in the PDF template.



The following figure shows the report containing the payslips of the employees.

Payslip for the month of June 2015

| | | | |
|--------------------|---------------|---------------------|-------------|
| Employee No | 101 | Name | John Stuart |
| Bank | Deutsche Bank | Bank A/C No. | 10822334 |
| DOJ | Jan 23, 2010 | LOP Days | 0 |
| Department | Production | Designation | Supervisor |

| Earnings | Amount | Deductions | Amount |
|-----------------------|----------------|--------------------------|---------------|
| Basic | 30000 | Professional Tax | 200 |
| House Rent | 12000 | Income Tax | 17400 |
| FBP – Taxable portion | 6000 | Monthly Food Coupon Cost | 1650 |
| Education Allowance | 10000 | Club Deduction | 500 |
| Gross Earnings | 58000 | Gross Deduction | 19750 |
| | Net Pay | | 38250 |

Payslip for the month of June 2015

| | | | |
|--------------------|---------------|---------------------|-----------|
| Employee No | 102 | Name | Peter Pan |
| Bank | Deutsche Bank | Bank A/C No. | 145234 |
| DOJ | May 26, 2009 | LOP Days | 0 |
| Department | Production | Designation | Manager |

| Earnings | Amount | Deductions | Amount |
|-----------------------|----------------|--------------------------|---------------|
| Basic | 45000 | Professional Tax | 200 |
| House Rent | 18000 | Income Tax | 24600 |
| FBP – Taxable portion | 9000 | Monthly Food Coupon Cost | 1650 |
| Education Allowance | 10000 | Club Deduction | 500 |
| Gross Earnings | 82000 | Gross Deduction | 26950 |
| | Net Pay | | 55050 |

Add Page Numbers and Breaks

This section describes how to add the following page features to the PDF layout.

- [Add Page Numbers](#)
- [Add Page Breaks](#)

Add Page Numbers

To add page numbers, define a field in the layout where you want the page number to appear and enter an initial value in that field.

1. Decide the position on the layout where you want the page number to be displayed.
2. Create a placeholder field called @pagenum@.
3. Enter a starting value for the page number in the **Default** field (Text Field Properties > **Options** tab). If the XML data includes a value for this field, then the start value that is assigned in the layout is overridden. If no start value is assigned, then it defaults to 1.

Add Page Breaks

You can define a page break in the layout to occur after a repeatable field.

To insert a page break after the occurrence of a specific field, add the following to the syntax in the **Tooltip** field of the Text Field Properties dialog:

```
page_break="yes"
```

For example:

```
<?rep_field="T1_G3", page_break="yes"?>
```

The following example demonstrates inserting a page break in a layout. The XML sample contains salaries of employees by department:

```
<?xml version="1.0"?>
<ROOT>
  <LIST_G_DEPTNO>
    <G_DEPTNO>
      <DEPTNO>10</DEPTNO>
      <LIST_G_EMPNO>
        <G_EMPNO>
          <EMPNO>7782</EMPNO>
          <ENAME>CLARK</ENAME>
          <JOB>MANAGER</JOB>
          <SAL>2450</SAL>
        </G_EMPNO>
        <G_EMPNO>
          <EMPNO>7839</EMPNO>
          <ENAME>KING</ENAME>
          <JOB>PRESIDENT</JOB>
          <SAL>5000</SAL>
        </G_EMPNO>
        <G_EMPNO>
          <EMPNO>125</EMPNO>
          <ENAME>KANG</ENAME>
          <JOB>CLERK</JOB>
          <SAL>2000</SAL>
        </G_EMPNO>
        <G_EMPNO>
          <EMPNO>7934</EMPNO>
          <ENAME>MILLER</ENAME>
          <JOB>CLERK</JOB>
          <SAL>1300</SAL>
        </G_EMPNO>
        <G_EMPNO>
          <EMPNO>123</EMPNO>
          <ENAME>MARY</ENAME>
          <JOB>CLERK</JOB>
          <SAL>400</SAL>
        </G_EMPNO>
        <G_EMPNO>
          <EMPNO>124</EMPNO>
          <ENAME>TOM</ENAME>
```



```

        <JOB>CLERK</JOB>
        <SAL>3000</SAL>
    </G_EMPNO>
</LIST_G_EMPNO>
<SUMSALPERDEPTNO>9150</SUMSALPERDEPTNO>
</G_DEPTNO>

<G_DEPTNO>
  <DEPTNO>30</DEPTNO>
  <LIST_G_EMPNO>
    .
    .
    .
  </LIST_G_EMPNO>
  <SUMSALPERDEPTNO>9400</SUMSALPERDEPTNO>
</G_DEPTNO>
</LIST_G_DEPTNO>
<SUMSALPERREPORT>29425</SUMSALPERREPORT>
</ROOT>

```

Suppose the report requirement is to display the salary information for each employee by department as shown in the following figure:


Department Salary Summary

| body_start | Dept No. | Emp No | Emp Name | Job | Salary |
|------------|----------|--------|----------|-----|--------------|
| | DEPTNO | EMPNO | ENAME | JOB | SAL |
| | | | | | SUMSALPERDEP |

To insert a page break after each department, insert the page break syntax in the **Tooltip** field for the **SUMSALPERDEPTNO** field as follows:

```
<?rep_field="T1_G3", page_break="yes"?>
```

The Text Field Properties dialog for the field is shown in the following figure.



For a break to occur, the field must be populated with data from the XML file.

The sample report with data is shown in the following figure:

Department Salary Summary

| Dept No. | Emp No | Emp Name | Job | Salary |
|----------|--------|----------|-----------|--------|
| 10 | 7782 | CLARK | MANAGER | 2450 |
| | 7839 | KING | PRESIDENT | 5000 |
| | 125 | KANG | CLERK | 2000 |
| | 7934 | MILLER | CLERK | 1300 |
| | 123 | MARY | CLERK | 400 |
| | 124 | TOM | CLERK | 3000 |
| | | | | 9150 |

Department Salary Summary

| Dept No. | Emp No | Emp Name | Job | Salary |
|----------|--------|----------|---------|--------|
| 20 | 7369 | SMITH | CLERK | 800 |
| | 7876 | ADAMS | CLERK | 1100 |
| | 7902 | FORD | ANALYST | 3000 |
| | 7788 | SCOTT | ANALYST | 3000 |
| | 7566 | JONES | MANAGER | 2975 |
| | | | | |

The page breaks after each department.

Perform Calculations

Adobe Acrobat provides a calculation function in the Field Properties dialog box.

To create a field to display a calculated total on a report:

1. Create a text field to display the calculated total. Give the field any **Name** you choose.

2. In the **Field Properties** dialog box, select the Format tab.
3. Select **Number** from the **Category** list.
4. Select the Calculate tab.
5. Select the radio button next to "Value is the <List of operations> of the following fields:"
6. Select **sum (+)** from the list.
7. Click the **Pick...** button and select the fields to be totaled.

Completed PDF Layout Example

The figure gives an illustration of a completed PDF layout.

ORACLE
E-Business Suite

Purchase Order

| | | |
|--------------------|----------|------|
| PURCHASE ORDER NO. | REVISION | PAGE |
| IPOH PO NL | IPOH | |

SHIP TO:

| |
|---------------------|
| IPOH SHIP ADDRESS |
| IPOH SHIP ADR INFO1 |
| IPOH SHIP COUNTRY1 |

BILL TO:

| |
|---------------------|
| IPOH BILL ADDRESS |
| IPOH BILL ADR INFO1 |
| IPOH BILL COUNTRY1 |

VENDOR:

| |
|------------------------|
| IPOH VENDOR NAME |
| IPOH VENDOR ADDRESS LI |
| IPOH VENDOR ADR INFO1 |
| IPOH VENDOR COUNTRY |

| | | | |
|----------------------|----------------------|----------------------|---------------------|
| CUSTOMER ACCOUNT NO. | VENDOR NO. | DATE OF ORDER/BUYER | REVISION DATE/BUYER |
| IPOH CUST | IPOH VE | IPOH CR IPOH ARI | |
| PAYMENT TERMS | SHIP VIA | FOB | |
| IPOH PAYMENT TERMS | IPOH SHIP V | IPOH FOB | |
| FREIGHT TERMS | REQUESTOR/DELIVER TO | CONFIRM TO/TELEPHONE | |
| IPOH FREIGHT TERMS | | | |

| ITEM | ITEM NUMBER/DESCRIPTION | DELIVERY | QUANTITY | UNIT | UNIT PRICE | EXTENSION | TAX |
|------|---|----------|----------|------|------------|-----------|------|
| IPOL | IPOL ITEM DES IC FIX ITEM IC SHIPTO ADR | IPOL DI | IPOL Q | POL | IPOL | IC AMT | IPOL |

Total IC AMOUNT P

Oracle E-Business Suite

AUTHORIZED SIGNATURE

Runtime Behavior

The following sections describe runtime behavior of PDF templates:

- [Placement of Repeating Fields](#)
- [Set Fields as Updatable or Read Only](#)
- [Overflow Data](#)

Placement of Repeating Fields

The placement, spacing, and alignment of fields that you create on the layout are independent of the underlying form layout.

At runtime, according to calculations performed on the placement of the rows of fields that you created, Publisher places each repeating row of data as follows:

First occurrence:

The first row of repeating fields displays exactly where you placed them on the layout.

Second occurrence, single row:

To place the second occurrence of the group, Publisher calculates the distance between the BODY_START tag and the first field of the first occurrence. The first field of the second occurrence of the group is placed this calculated distance below the first occurrence.

Second occurrence, multiple rows:


If the first group contains multiple rows, then the second occurrence of the group is placed the calculated distance below the last row of the first occurrence.

The distance between the rows within the group is maintained as defined in the first occurrence.

Set Fields as Updatable or Read Only

You can make fields either read only or updatable.

When you define a field in the layout, you can set it to "Read Only", as shown in the following illustration:



Regardless of what you choose at design time for the Read-Only check box, the default behavior of the PDF processing engine is to set all fields to read-only for the output PDF. You can change this behavior using the following report properties:

- all-field-readonly
- all-fields-readonly-asis
- remove-pdf-fields

Note that in the first two options, you're setting a state for the field in the PDF output. The setting of individual fields can still be changed in the output using Adobe Acrobat Professional. Also note that because the fields are maintained, the data is still separate and can be extracted. In the third option, "remove-pdf-fields" the structure is flattened and no field/data separation is maintained.

To make all fields updatable:

Set the "all-field-readonly" property to "false". This sets the Read-Only state to false for all fields regardless of the individual field settings at design time.

To make all fields read only:

This is the default behavior. No settings are required.

To maintain the Read-Only check box selection for each field:

To maintain the setting of the Read Only check box on a field-by-field basis in the output PDF, set the property, all-fields-readonly-asis, to true. This property overrides the settings of all-field-readonly.

To remove all fields from the output PDF:

Set the property "remove-pdf-fields" to "true".

Overflow Data

When multiple pages are required to accommodate the occurrences of repeating rows of data, each page displays identically except for the defined repeating area, which displays the continuation of the repeating data.

For example, if the item rows of the purchase order extend past the area defined on the layout, succeeding pages displays all data from the purchase order form with the continuation of the item rows.

Create a Layout from a Predefined PDF Form

There're many PDF forms available online that you may want to use as layouts for the report data. For example, government forms that your company is required to submit. You can use these downloaded PDF files as the report layouts, supplying the XML data at runtime to fill in the report fields.

Some of these forms already have form fields defined, some don't. If the PDF form already has fields defined, then you can use one of the following methods to match the form field names to the data field names:

- Use Adobe Acrobat Professional to rename the fields in the document to match the names of the elements in the XML data file.
- Use BI Publisher's Data Model Editor to rename the XML element names in the data file to match the field names in the PDF form.

If the form fields are not already defined in the downloaded PDF, then you must create them.

Determine If a PDF Has Form Fields Defined

Follow these steps to determine if a PDF has form fields defined and to get a list of the field names.

1. Open the document in Adobe Acrobat Professional.
2. Click **Highlight Fields**. Form fields that exist in the document are highlighted.
3. From the **Form** menu, select **Add or Edit Fields**. The field names display in the document as well as in the **Fields** pane.


Use a Predefined PDF Form as a Layout by Renaming the Form Fields

You can use a PDF form as a template for another form.

To use a predefined PDF form as a layout:

1. Download or import the PDF file to the local system.
2. Open the file in Adobe Acrobat Professional.
3. From the **Form** menu, select **Add or Edit Fields**. This highlights text fields that have already been defined.

The following illustration shows a sample W-2 PDF form after selecting **Add or Edit Fields** to highlight the text fields.



To map the existing form fields to the data from the incoming XML file, rename the fields to match the element names in the XML file.

4. Open the form field **Text Field Properties** dialog by either double-clicking the field, or by selecting the field then selecting **Properties** from the right mouse menu.
5. In the **Name** field, enter the element name from the input XML file.
6. Repeat for all fields that you want populated by the data file.
7. When all fields have been updated, click **Close Form Editing**.
8. Save the layout.

Use the Comb of Characters Option

The comb of characters option for a PDF form field in Adobe Acrobat spreads the text evenly across the width of the text field.

Use this option when the form field requires the characters to be entered in specific positions, as the Routing number field shown in the following figure:

11a If line 9 is larger than line 10, subtract line 10 from line 9. This is your **refund**.
If Form 8888 is attached, check here


► b Routing number

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
|---|---|---|---|---|---|---|---|---|

 ► c Type: Checking Savings

To use this feature, perform the following:

1. In Adobe Acrobat Professional, add the form field as a text field. An example is shown in the following figure:




2. Open the Text Field Properties dialog and click the **Options** tab. Clear all check boxes and select the **Comb of characters** check box.

 **Note:**

The **Comb of characters** option is only enabled when all other options are cleared.

Enter the number of characters in the text field. For the routing number example, a value of 9 is entered in the **Comb of** field as shown in the following figure:



If your data may not contain the number of characters specified each time, you can set the **Alignment** option to specify whether the value will be aligned to the right, left, or center within the field.

When you run the report, the characters comprising the value for the routing field will be spread across the text field as shown in the following figure:

11a If line 9 is larger than line 10, subtract line 10 from line 9. This is your refund.
If Form 8888 is attached, check here

▶ b Routing number

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 5 | 4 | 2 | 3 | 9 | 7 | 3 | 2 | 5 |
|---|---|---|---|---|---|---|---|---|

 ▶ c Type: Checking Savings

The following figure shows how the data will display in the field when the data for the routing field doesn't contain the full nine characters and the **Alignment** option is set to left:

11a If line 9 is larger than line 10, subtract line 10 from line 9. This is your refund.
If Form 8888 is attached, check here

▶ b Routing number

| | | | | | | | | |
|---|---|---|---|---|---|---|--|--|
| 5 | 4 | 2 | 3 | 9 | 7 | 3 | | |
|---|---|---|---|---|---|---|--|--|

 ▶ c Type: Checking Savings

Add or Designate a Field for a Digital Signature

Publisher supports digital signatures on PDF output documents. Digital signatures enable you to verify the authenticity of the documents you send and receive. Publisher can access the digital ID file from a central, secure location and at runtime sign the PDF output with the digital ID. The digital signature verifies the signer's identity and ensures that the document hasn't been altered after it was signed.

Implementing digital signature requires several tasks across the Publisher product. This topic describes how to add a new field or configure an existing field in the PDF template for the digital signature.

About Signature Field Options

For PDF templates you've these options for designating a digital signature field for the output report.

- Add a signature field to the PDF layout.
Use this option if you want the digital signature to appear in a specific field and the PDF template doesn't include a signature field.
- Use an existing signature field in the PDF template.
Use this option if the PDF template already includes a signature field that you want to use. To designate an existing field for the digital signature, define the field in the Runtime Configuration page.
- Designate the position of the digital signature on the output report by setting x and y coordinates.


Use this option if you prefer to designate the x and y coordinates for the placement of the digital signature, rather than use a signature field. You set the position using the runtime digital signature properties.

All three options require setting configuration properties for the report in the Report Properties page after you've uploaded the template.

Add a Signature Field

Follow these steps to add a signature field.

1. Open the template in Adobe Acrobat Professional.
2. From the **Form** menu, select **Add or Edit Fields**. Then click **Add New Field**. Choose **Digital Signature** from the list of fields.
3. Draw the signature field in the desired location on the layout. When you release the mouse button, a dialog prompts you to enter a name for the field.
4. Enter a name for the signature field. The following figure shows an inserted digital signature field called "My_Signature."



5. Save the template.
6. Configure the report to insert the digital signature at runtime.

Configure the Report to Insert the Digital Signature at Runtime

After you've uploaded the PDF template to the report definition, you enable digital signature and specify the signature field in the Report Properties.

1. From the edit report page, click **Properties** and then click the **Formatting** tab.
2. Scroll to the **PDF Digital Signature** group of properties.
3. Set **Enable Digital Signature** to **True**.
4. For the property **Existing signature field name**, enter the field name from the PDF template.

No other properties are required for this method.

The following figure shows the **My_Signature** field name entered into the properties field.

The screenshot shows the 'Report Properties' dialog box with the 'Output' tab selected. The 'PDF Digital Signature' section is expanded, and the 'Existing signature field name' is set to 'My_Signature'. Other properties like 'Enable Digital Signature' are set to 'True', and 'Signature field X coordinate', 'Signature field Y coordinate', 'Signature field width', and 'Signature field height' are all set to '0'. The 'RTF Output' section is also expanded, with 'Enable change tracking' and 'Protect document for tracked changes' set to 'false', and 'Default font' set to 'Arial:12'.

| Properties | Report Value | Server Value |
|--|--------------------------|--------------|
| Use only one shared resources object for all pages | <input type="checkbox"/> | true |
| PDF Digital Signature | | |
| Enable Digital Signature | True | false |
| Existing signature field name | My_Signature | null |
| Signature field location | <input type="checkbox"/> | null |
| Signature field X coordinate | <input type="text"/> | 0 |
| Signature field Y coordinate | <input type="text"/> | 0 |
| Signature field width | <input type="text"/> | 0 |
| Signature field height | <input type="text"/> | 0 |
| RTF Output | | |
| Enable change tracking | <input type="checkbox"/> | false |
| Protect document for tracked changes | <input type="checkbox"/> | false |
| Default font | <input type="text"/> | Arial:12 |

5. Click **OK**.

The runtime properties that you set are at the report level and not the layout level. Therefore any layouts associated with the report now include the digital signature as specified in the Report Properties. When an **Existing signature field name** is specified, the template must contain the field for the signature to be applied.

PDF Template Limitations

The PDF template has a few limitations.

The PDF template doesn't support:

- The field properties mentioned in [Supported Field Properties Options](#) for repeating fields.
- Nested repeating fields.
- Section-wise repeat. The `document-repeat-elementname` field is used for repeating the entire template.
- Pixel control.
- Data alignment in fields.
- Large documents. You might experience performance issues when a document is larger than 250 MB.

To avoid these limitations, use an RTF template instead of a PDF template.

17

Create eText Templates

This topic describes creating the eText templates in Microsoft Word. Publisher uses eText templates to generate the flat files for EDI and EFT transactions.

Topics:

- [Overview](#)
- [Structure of eText Templates](#)
- [Construct the Data Tables](#)
- [Command Rows](#)
- [Structure of the Data Rows](#)
- [Set Up Command Tables](#)
- [Create a Filler Block](#)
- [Expressions, Control Structures, and Functions](#)
- [Identifiers, Operators, and Literals](#)

Overview

An eText template is an RTF-based template that is used to generate text output for Electronic Funds Transfer (EFT) and Electronic Data Interchange (EDI).

At runtime, Publisher applies this template to an input XML data file to create an output text file that can be transmitted to a bank or other customer. Because the output is intended for electronic communication, the eText templates must follow very specific format instructions for exact placement of data.

An EFT is an electronic transmission of financial data and payments to banks in a specific fixed-position format flat file (text).

EDI is similar to EFT except it's not limited to the transmission of payment information to banks. It's often used as a method of exchanging business documents, such as purchase orders and invoices, between companies. EDI data is delimiter-based, and also transmitted as a flat file (text).

Files in these formats are transmitted as flat files, rather than printed on paper. The length of a record is often several hundred characters and therefore difficult to layout on standard size paper.

To accommodate the record length, the EFT and EDI templates are designed using tables. Each record is represented by a table. Each row in a table corresponds to a field in a record. The columns of the table specify the position, length, and value of the field.

These formats can also require special handling of the data from the input XML file. This special handling can be on a global level (for example, character replacement and sequencing) or on a record level (for example, sorting). Commands to perform

Commands that apply globally, or commands that define program elements for the template, are "setup" commands. These must be specified in the initial tables of the template. Examples of setup commands are Template Type and Character Set.

In the data tables you provide the source XML data element name and the specific placement and formatting definitions required by the receiving bank or entity. You can also define functions to be performed on the data and conditional statements.

The data tables must always start with a command row that defines the "Level." The Level associates the table to an element from the XML data file, and establishes the hierarchy. The data fields that are then defined in the table for the Level correspond to the child elements of the XML element.

The following graphic illustrates the relationship between the XML data hierarchy and the template Level. The XML element "RequestHeader" is defined as the Level. The data elements defined in the table ("FileID" and "Encryption") are children of the RequestHeader element.

```
?xml version = "1.0" ?>
!DOCTYPE OutBoundPayments:BatchRequest SYSTEM "OutBoundPayments.dtd">
OutBoundPayments:BatchRequest>
  <PaymentsCommon:RequestHeader>
    <PaymentsCommon:Preamble>
      <PaymentsCommon:Version>1.0.11.5.7</PaymentsCommon:Version>
    </PaymentsCommon:Preamble>
    <PaymentsCommon:TrxnParties>
      <PaymentsCommon:RequesterParty>Oracle Germany</PaymentsCommon:Req
      <PaymentsCommon:FinancialInstitution>Citi Bank</PaymentsCommon:Fin
    </PaymentsCommon:TrxnParties>
    <PaymentsCommon:Encryption>N</PaymentsCommon:Encryption>
    <PaymentsCommon:FileID>10180300001</PaymentsCommon:FileID>
    <PaymentsCommon:BaseRecordCount>94457</PaymentsCommon:BaseRecordCount
  </PaymentsCommon:RequestHeader>
```

| <LEVEL> | <POSITION> | <LENGTH> | <FORMAT> | <PAD> | <DATA> |
|---------------|------------|----------|--------------|--------|---------------------------------|
| RequestHeader | 1 | 3 | Alpha | | FileID |
| RequestHeader | 8 | 1 | Alpha | R, ' ' | Encryption |
| RequestHeader | 9 | 6 | Date, YYMMDD | | SYSDATE |
| RequestHeader | 15 | 6 | Number | L, '0' | SEQUENCE NUMBER (AllRecordsSeq) |
| RequestHeader | 21 | 129 | Alpha | | |

The order of the tables in the template determines the print order of the records. At runtime the system loops through all the instances of the XML element corresponding to a table (Level) and prints the records belonging to the table. The system then moves on to the next table in the template. If tables are nested, the system generates the nested records of the child tables before moving on to the next parent instance.

Command Rows, Data Rows, and Data Column Header Rows

Command rows are used to specify commands in the template. Command rows always have two columns: command name and command parameter. Command rows don't have column headings. The commands control the overall setup and record structures of the template.

The following figure shows the placement of Command Rows, Data Rows, and Data Column Header Rows:

XDO file name:
APXNACHA.rtf

Mapping of Payment Format:
US NACHA Payments EFT Format

Format Setup:

Hint: Define formatting options...

| | |
|------------------------|----------------------|
| <TEMPLATE TYPE> | FIXED POSITION BASED |
| <CHARACTER SET> | iso-8859-1 |
| <NEW RECORD CHARACTER> | Carriage Return |

Sequences:

Hint: Define sequence generators...

| | |
|------------------------|-----------------|
| <DEFINE SEQUENCE> | PaymentsSeq |
| <RESET AT LEVEL> | PayerInstrument |
| <INCREMENT BASIS> | LEVEL |
| <END DEFINE SEQUENCE > | PaymentsSeq |

Format Data Records:

| <LEVEL> | <POSITION> | <LENGTH> | PayerInstrument <FORMAT> | <PAD> | <DATA> | <COMMENT> |
|--------------|---------------|----------|-----------------------------|--------|------------------------|----------------------|
| <NEW RECORD> | FileHeaderRec | | | | | |
| 1 | | 1 | Number | | 1 | Record Type |
| 2 | | 2 | Alpha | R, ' ' | '01' | Priority Code |
| 4 | | 1 | Alpha | R, ' ' | | Immediate D blank |
| 5 | | 9 | Alpha | R, ' ' | BankAccount/BankNumber | Immediate D |
| 14 | | 1 | Alpha | R, ' ' | '1' | Mutually Agri |
| 15 | | 9 | Alpha | R, ' ' | Payer/TaxIdentifier | Immediate O |
| 24 | | 6 | Date, | | SYSDATE | File Creation |

Blank rows can be inserted anywhere in a table to improve readability. Most often they're used in the setup table, between commands. Blank rows are ignored by Publisher when the template is parsed.

Data Column Header Rows

Data column headers specify the column headings for the data fields (such as Position, Length, Format, Padding, and Comments). A column header row usually follows the Level command in a table (or the sorting command, if one is used). The data column header row must come before any data rows in the table. Additional empty column header rows can be inserted at any position in a table to improve readability. The empty rows are ignored at runtime.

The required data column header rows vary depending on the template type. See [Structure of the Data Rows](#).

Data Rows

Data rows provide the values for the data column header attributes for each data field.

The content of the data rows varies depending on the template type. See [Structure of the Data Rows](#).

Construct the Data Tables

The data tables contain a combination of command rows and data field rows. Each data table must begin with a Level command row that specifies its XML element. Each record must begin with a New Record command that specifies the start of a new record, and the end of a previous record (if any).

The required columns for the data fields vary depending on the Template Type.

Command Rows

The command rows always have two columns: command name and command parameter.

The supported commands are:

- [Level Command](#)
- [New Record Command](#)
- [Sort Ascending and Sort Descending Commands](#)
- [Display Condition Command](#)

The usage for each of these commands is described in the following sections.

Level Command

The level command associates a table with an XML element. The parameter for the level command is an XML element. The level is printed once for each instance the XML element appears in the data input file.

The level commands define the hierarchy of the template. For example, Payment XML data extracts are hierarchical. A batch can have multiple child payments, and a payment can have multiple child invoices. This hierarchy is represented in XML as nested child elements within a parent element. By associating the tables with XML elements through the level command, the tables also have the same hierarchical structure.

Similar to the closing tag of an XML element, the level command has a companion end-level command. The child tables must be defined between the level and end-level commands of the table defined for the parent element.

An XML element can be associated with only one level. All the records belonging to a level must reside in the table of that level or within a nested table belonging to that level. The end-level command is specified at the end of the final table.

Following is a sample structure of an EFT file record layout:

- FileHeaderRecordA
 - BatchHeaderRecordA
 - BatchHeaderRecordB
 - PaymentRecordA
 - PaymentRecordB

- * InvoiceRecordA
 - Batch FooterRecordC
 - BatchFooterRecordD
- FileFooterRecordB

Following would be its table layout:

The table layout displays the command and its value:

```
<LEVEL> : RequestHeader
<NEW RECORD> : FileHeaderRecordA
Data rows for the FileHeaderRecordA
```

```
<LEVEL> : Batch
<NEW RECORD> : BatchHeaderRecordA
Data rows for the BatchHeaderRecordA
<NEW RECORD> : BatchHeaderRecordB
Data rows for the BatchHeaderRecordB
```

```
<LEVEL> : Payment
<NEW RECORD> : PaymentRecordA
Data rows for the PaymentRecordA
<NEW RECORD> : PaymentRecordB
Data rows for the PaymentRecordB
```

```
<LEVEL> : Invoice
<NEW RECORD> : InvoiceRecordA
Data rows for the InvoiceRecordA
<END LEVEL> : Invoice
```

```
<END LEVEL>: Payment
```

```
<LEVEL> : Batch
<NEW RECORD> : BatchFooterRecordC
Data rows for the BatchFooterRecordC
<NEW RECORD> : BatchFooterRecordD
Data rows for the BatchFooterRecordD
<END LEVEL> : Batch
```

```
<LEVEL> : RequestHeader
<NEW RECORD> : FileFooterRecordB
Data rows for the FileFooterRecordB
<END LEVEL> : RequestHeader
```

Multiple records for the same level can exist in the same table. However, each table can only have one level defined. In the example above, the BatchHeaderRecordA and BatchHeaderRecordB are both defined in the same table. However, note that the END LEVEL for the Payment must be defined in its own separate table after the child

element Invoice. The Payment END LEVEL cannot reside in the same table as the Invoice Level.

Note that you do not have to use all the levels from the data extract in the template. For example, if an extract contains the levels: RequestHeader > Batch > Payment > Invoice, you can use just the batch and invoice levels. However, the hierarchy of the levels must be maintained.

The table hierarchy determines the order that the records are printed. For each parent XML element, the records of the corresponding parent table are printed in the order they appear in the table. The system loops through the instances of the child XML elements corresponding to the child tables and prints the child records according to their specified order. The system then prints the records of the enclosing (end-level) parent table, if any.

For example, given the EFT template structure above, assume the input data file contains the following:

- Batch1
 - Payment1
 - * Invoice1
 - * Invoice2
 - Payment2
 - * Invoice1
- Batch2
 - Payment1
 - * Invoice1
 - * Invoice2
 - * Invoice3

| Record Order | Record Type | Description |
|--------------|--------------------|------------------------------------|
| 1 | FileHeaderRecordA | One header record for the EFT file |
| 2 | BatchHeaderRecordA | For Batch1 |
| 3 | BatchHeaderRecordB | For Batch1 |
| 4 | PaymentRecordA | For Batch1, Payment1 |
| 5 | PaymentRecordB | For Batch1, Payment1 |
| 6 | InvoiceRecordA | For Batch1, Payment1, Invoice1 |
| 7 | InvoiceRecordA | For Batch1, Payment1, Invoice2 |
| 8 | PaymentRecordA | For Batch1, Payment2 |
| 9 | PaymentRecordB | For Batch1, Payment2 |
| 10 | InvoiceRecordA | For Batch1, Payment2, Invoice1 |
| 11 | BatchFooterRecordC | For Batch1 |
| 12 | BatchFooterRecordD | For Batch1 |
| 13 | BatchHeaderRecordA | For Batch2 |
| 14 | BatchHeaderRecordB | For Batch2 |

| Record Order | Record Type | Description |
|--------------|--------------------|------------------------------------|
| 15 | PaymentRecordA | For Batch2, Payment1 |
| 16 | PaymentRecordB | For Batch2, Payment1 |
| 17 | InvoiceRecordA | For Batch2, Payment1, Invoice1 |
| 18 | InvoiceRecordA | For Batch2, Payment1, Invoice2 |
| 19 | InvoiceRecordA | For Batch2, Payment1, Invoice3 |
| 20 | BatchFooterRecordC | For Batch2 |
| 21 | BatchFooterRecordD | For Batch2 |
| 22 | FileFooterRecordB | One footer record for the EFT file |

New Record Command

The new record command signifies the start of a record and the end of the previous one, if any.

Every record in a template must start with the new record command. The record continues until the next new record command, or until the end of the table or the end of the level command.

A record is a construct for the organization of the elements belonging to a level. The record name is not associated with the XML input file.

A table can contain multiple records, and therefore multiple new record commands. All the records in a table are at the same hierarchy level. They're printed in the order in which they're specified in the table.

The new record command can have a name as its parameter. This name becomes the name for the record. The record name is also referred to as the record type. The name can be used in the COUNT function for counting the generated instances of the record. See the COUNT function [Functions](#) for more information.

Consecutive new record commands (or empty records) aren't allowed.

Sort Ascending and Sort Descending Commands

Use the sort ascending and sort descending commands to sort the instances of a level.

Enter the elements that you want to sort by in a comma-separated list. This is an optional command. When used, it must come right after the (first) level command and it applies to all records of the level, even if the records are specified in multiple tables.

Display Condition Command

The display condition command specifies when the enclosed record or data field group should be displayed. The command parameter is a boolean expression. When it evaluates to true, the record or data field group is displayed. Otherwise the record or data field group is skipped.

The display condition command can be used with either a record or a group of data fields. When used with a record, the display condition command must follow the new record command. When used with a group of data fields, the display condition command must follow a data field row. In this case, the display condition applies to the rest of the fields through the end of the record.

Consecutive display condition commands are merged as AND conditions. The merged display conditions apply to the same enclosed record or data field group.

Structure of the Data Rows

The output record data fields are represented in the template by table rows.

In `FIXED_POSITION_BASED` templates, each row has the following attributes (or columns):

- Position
- Length/Maximum Length
- Format Column
- Pad
- Data
- Comments

The first five columns are required and must appear in the order listed.

For `DELIMITER_BASED` templates, each data row has the following attributes (columns):

- Length/Maximum Length
- Format Column
- Data
- Tag
- Comments

The first three columns are required and must be declared in the order stated.

In both template types, the Comments column is optional and ignored by the system. You can insert additional information columns, because all columns after the required ones are ignored.

The usage rules for these columns are as follows:

Position

Specifies the starting position of the field in the record. The unit is in number of characters.

This column is only used with `FIXED_POSITION_BASED` templates.

Length/Maximum Length

Specifies the length of the field.

The unit is in number of characters. For `FIXED_POSITION_BASED` templates, all the fields are fixed length. If the data is less than the specified length, it's padded. If the data is longer, it's truncated. The truncation always occurs on the right.

For `DELIMITER_BASED` templates, this value specifies the maximum length of the field. If the data exceeds the maximum length, it's truncated. Data less than the maximum length isn't padded.

Format Column

Format Column specifies the data type and format setting.

There're three accepted data types:

- Alpha
- Number
- Date

Refer to [Field-Level Key Words](#) for their usage.

Number Data Type

Numeric data has three optional format settings: Integer, Decimal, or you can define a format mask.

Specify the optional settings with the Number data type as follows:

- Number, Integer
- Number, Decimal
- Number, <format mask>

For example:

```
Number, ###,###.00
```

The Integer format uses only the whole number portion of a numeric value and discards the decimal. The Decimal format uses only the decimal portion of the numeric value and discards the integer portion.

The following table shows examples of how to set a format mask. When specifying the mask, # represents that a digit is to be displayed when present in the data; 0 represents that the digit placeholder is to be displayed whether data is present or not.

When specifying the format mask, the group separator must always be "," and the decimal separator must always be "." To alter these in the actual output, you must use the Setup Commands `NUMBER THOUSANDS SEPARATOR` and `NUMBER DECIMAL SEPARATOR`. See [Set Up Command Tables](#) for details on these commands.

The following table shows sample Data, Format Specifier, and Output. The Output assumes the default group and decimal separators.

| Data | Format Specifier | Output |
|-------------|------------------|----------------|
| 123456789 | ###,###.00 | 123,456,789.00 |
| 123456789.2 | ###.00 | 123456789.20 |

| Data | Format Specifier | Output |
|-------------|------------------|-------------|
| 1234.56789 | ###.000 | 1234.568 |
| 123456789.2 | # | 123456789 |
| 123456789.2 | ### | 123456789.2 |
| 123456789 | ### | 123456789 |

Date Data Type

The Date data type format setting must always be explicitly stated. The format setting follows the SQL date styles, such as MMDDYY.

Map EDI Delimiter-Based Data Types to eText Data Types

Some EDI (DELIMITER_BASED) formats use more descriptive data types.

These are mapped to the three template data types as shown in the following table.

| ASC X12 Data Type | Format Template Data Type |
|-----------------------------|---------------------------|
| A - Alphanumeric | Alpha |
| AN -Alphanumeric | Alpha |
| B - Binary | Number |
| CD - Composite data element | N/A |
| CH - Character | Alpha |
| DT - Date | Date |
| FS - Fixed-length string | Alpha |
| ID - Identifier | Alpha |
| IV - Incrementing Value | Number |
| Nn - Numeric | Number |
| PW - Password | Alpha |
| R - Decimal number | Number |
| TM - Time | Date |

Assume the setup commands shown in the following table.

| Name | Command |
|----------------------------|---------|
| NUMBER THOUSANDS SEPARATOR | . |
| NUMBER DECIMAL SEPARATOR | , |

The following table shows the Data, Format Specifier, and Output for this case. Note that the Format Specifier requires the use of the default separators, regardless of the setup command entries.

| Data | Format Specifier | Output |
|-------------|------------------|----------------|
| 123456789 | ###,###.00 | 123.456.789,00 |
| 123456789.2 | ###.00 | 123456789,20 |
| 1234.56789 | ###.000 | 1234,568 |
| 123456789.2 | # | 123456789 |
| 123456789.2 | ### | 123456789,2 |
| 123456789 | ### | 123456789 |

Pad

Pad applies to FIXED_POSITION_BASED templates only. Specify the padding side (L = left or R = right) and the character. Both numeric and alphanumeric fields can be padded. If this field isn't specified, numeric fields are left-padded with "0" and alpha fields are right-padded with spaces.

Example usage:

- To pad a field on the left with a "0", enter the following in the Pad column field:
L, '0'
- To pad a field on the right with a space, enter the following the Pad column field:
R, ' '

Data

Specifies the XML element from the data extract that is to populate the field. The data column can simply contain the XML tag name, or it can contain expressions and functions.

For more information, see [Expressions, Control Structures, and Functions](#).

Tag

Acts as a comment column for DELIMITER_BASED templates.

It specifies the reference tag in EDIFACT formats, and the reference IDs in ASC X12.

Comments

Use this column to note any free form comments to the template. Usually this column is used to note the business requirement and usage of the data field.

Set Up Command Tables

A template always begins with a table that specifies the setup commands.

The setup commands define global attributes, such as template type and output character set and program elements, such as sequencing and concatenation.

The setup commands are:

- [TEMPLATE TYPE Command](#)
- OUTPUT CHARACTER SET
- [Output Length Mode](#)
- NEW RECORD CHARACTER
- INVALID CHARACTERS
- REPLACE CHARACTERS
- NUMBER THOUSANDS SEPARATOR
- NUMBER DECIMAL SEPARATOR
- DEFINE LEVEL
- DEFINE SEQUENCE
- DEFINE CONCATENATION
- CASE CONVERSION

An example setup table is shown in the following figure:

XDO file name:
XINT-01.rtf

Mapping of Payment Format:
International Payments EFT Format

Format Setup:

Hint: Define formatting options...

| | |
|--------------------------|----------------------|
| <TEMPLATE TYPE> | FIXED_POSITION_BASED |
| <OUTPUT CHARACTER SET> | iso-8859-1 |
| <NEW RECORD CHARACTER> | Carriage Return |
| <INVALID CHARACTERS> | ¿ |
| <REPLACE CHARACTERS> | |
| A | AO |
| E | EO |
| I | IO |
| O | OO |
| U | UO |
| <END REPLACE CHARACTERS> | |

Format Data Levels:

Hint: Define data levels that are needed in the format which do not exist in data extract...

| | |
|---------------------|-----------------------------------|
| <DEFINE LEVEL> | PaymentsByPayDatePayee |
| <BASE LEVEL> | Payment |
| <GROUPING CRITERIA> | `PaymentDate, PayeeName' |
| <END DEFINE LEVEL> | PaymentsByPayDatePayee |
| <DEFINE LEVEL> | InvoicesByReportingCat&and&Attrib |
| <BASE LEVEL> | Invoice |

Here is another example setup table:

| | |
|---------------------|--|
| <GROUPING CRITERIA> | <pre> InvoiceTrxnReportingCat', (IF InvoiceTrxnReportingCat = 'V' THEN InvoiceDEVTransitGoods' END IF), (IF InvoiceTrxnReportingCat = 'V' THEN InvoiceDEVGoodsIndexNum' END IF), (IF InvoiceTrxnReportingCat = 'V' THEN InvoiceDEVPassingTrade' END IF) </pre> |
| <END DEFINE LEVEL> | InvoicesByReportingCatAndAttrib |

Sequences :

Hint: Define sequence generators...

| | |
|------------------------|---------------------|
| <DEFINE SEQUENCE> | AllRecordsSeq |
| <RESET AT LEVEL> | PERIODIC SEQUENCE |
| <INCREMENT BASIS> | RECORD |
| <START AT> | BaseRecordCount + 1 |
| <MAXIMUM> | 999999 |
| <END DEFINE SEQUENCE > | AllRecordsSeq |

| | |
|------------------------|-------------|
| <DEFINE SEQUENCE> | PaymentsSeq |
| <RESET AT LEVEL> | Batch |
| <INCREMENT BASIS> | LEVEL |
| <END DEFINE SEQUENCE > | PaymentsSeq |

Concatenated Records :

Hint: Define fields that are composed of concatenated records...

| | |
|----------------------------|-------------------------|
| <DEFINE CONCATENATION> | ConcatenatedInvoiceInfo |
| <BASE LEVEL> | Invoice |
| <ELEMENT> | InvoiceNum |
| <DELIMITER> | ',' |
| <END DEFINE CONCATENATION> | ConcatenatedInvoiceInfo |

TEMPLATE TYPE Command

This command specifies the type of template.

There're two types: FIXED_POSITION_BASED and DELIMITER_BASED.

Use the FIXED_POSITION_BASED templates for fixed-length record formats, such as EFTs. In these formats, all fields in a record are a fixed length. If data is shorter than the specified length, then it's padded. If longer, it's truncated. The system specifies the default behavior for data padding and truncation. Examples of fixed position based formats are EFTs in Europe, and NACHA ACH file in the U.S.

In a DELIMITER_BASED template, data is never padded and only truncated when it reaches a maximum field length. Empty fields are allowed (when the data is null). Designated delimiters are used to separate the data fields. If a field is empty, two delimiters are displayed next to each other. Examples of delimited-based templates are EDI formats such as ASC X12 820 and UN EDIFACT formats - PAYMUL, DIRDEB, and CREMUL.

In EDI formats, a record is sometimes referred to as a segment. An EDI segment is treated the same as a record. Start each segment with a new record command and give it a record name. You should have a data field specifying the segment name as part of the output data immediately following the new record command.

For DELIMITER_BASED templates, you insert the appropriate data field delimiters in separate rows between the data fields. After every data field row, you insert a delimiter row. You can insert a placeholder for an empty field by defining two consecutive delimiter rows.

Empty fields are often used for syntax reasons: you must insert placeholders for empty fields so that the fields that follow can be properly identified.

There're different delimiters to signify data fields, composite data fields, and end of record. Some formats allow you to choose the delimiter characters. In all cases you should use the same delimiter consistently for the same purpose to avoid syntax errors.

In DELIMITER_BASED templates, the <POSITION> and <PAD> columns do not apply. They're omitted from the data tables.

Some DELIMITER_BASED templates have minimum and maximum length specifications. In those cases Oracle Payments validates the length.

DEFINE LEVEL Command

Some formats require specific additional data levels that are not in the data extract. For example, some formats require that payments be grouped by payment date. Using the Define Level command, a payment date group can be defined and referenced as a level in the template, even though it isn't in the input extract file.

When you use the Define Level command you declare a base level that exists in the extract. The Define Level command inserts a new level, one level higher than the base level of the extract. The new level functions as a grouping of the instances of the base level.

The Define Level command is a setup command, therefore it must be defined in the setup table. It has three subcommands:

- **BASE LEVEL** command - defines the level (XML element) from the extract that the new level is based on. The Define Level command must always have one and only one base level subcommand.
- **GROUPING CRITERIA** - defines the XML extract elements that are used to group the instances of the base level to form the instances of the new level. The parameter of the grouping criteria command is a comma-separated list of elements that specify the grouping conditions.

The order of the elements determines the hierarchy of the grouping. The instances of the base level are first divided into groups according to the values of the first criterion, then each of these groups is subdivided into groups according to the second criterion, and so on. Each of the final subgroups is considered as an instance of the new level.

- **GROUP SORT ASCENDING** or **GROUP SORT DESCENDING** - defines the sorting order of the group. Insert the <GROUP SORT ASCENDING> or <GROUP SORT DESCENDING> command row anywhere between the <DEFINE LEVEL> and <END DEFINE LEVEL> commands. The parameter of the sort command is a comma-separated list of elements by which to sort the group.
- **GROUP SORT ASCENDING NUMBER** or **GROUP SORT DESCENDING NUMBER** - defines the sorting order of the numeric group. Insert the <GROUP SORT ASCENDING NUMBER> or <GROUP SORT DESCENDING NUMBER> command row

anywhere between the <DEFINE LEVEL> and <END DEFINE LEVEL> commands. The parameter of the sort command is a comma-separated list of elements for sorting.

For example, the following table shows five payments under a batch.

| Payment Instance | PaymentDate (grouping criterion 1) | PayeeName (grouping criterion 2) |
|------------------|------------------------------------|----------------------------------|
| Payment1 | PaymentDate1 | PayeeName1 |
| Payment2 | PaymentDate2 | PayeeName1 |
| Payment3 | PaymentDate1 | PayeeName2 |
| Payment4 | PaymentDate1 | PayeeName1 |
| Payment5 | PaymentDate1 | PayeeName3 |

In the template, construct the setup table as follows to create a level called PaymentsByPayDatePayee from the base level "Payment" grouped according to Payment Date and Payee Name. Add the Group Sort Ascending command to sort each group by PaymentDate and PayeeName:

| Payment Group | Level |
|------------------------|------------------------|
| <DEFINE LEVEL> | PaymentsByPayDatePayee |
| <BASE LEVEL> | Payment |
| <GROUPING CRITERIA> | PaymentDate, PayeeName |
| <GROUP SORT ASCENDING> | PaymentDate, PayeeName |
| <END DEFINE LEVEL> | PaymentsByPayDatePayee |

The five payments generate the four groups (instances) shown in the following table for the new level:

| Payment Group Instance | Group Criteria | Payments in Group |
|------------------------|--------------------------|--------------------|
| Group1 | PaymentDate1, PayeeName1 | Payment1, Payment4 |
| Group2 | PaymentDate1, PayeeName2 | Payment3 |
| Group3 | PaymentDate1, PayeeName3 | Payment5 |
| Group4 | PaymentDate2, PayeeName1 | Payment2 |

The order of the new instances is the order in which the records print. When evaluating the multiple grouping criteria to form the instances of the new level, the criteria can be thought of as forming a hierarchy. The first criterion is at the top of the hierarchy, the last criterion is at the bottom of the hierarchy.

Generally there're two kinds of format-specific data grouping scenarios in EFT formats. Some formats print the group records only; others print the groups with the individual element records nested inside groups. The following tables are two examples for these scenarios based on the five payments and grouping conditions previously illustrated and show the generated output:

Scenario 1: Group Records Only

EFT File Structure:

- BatchRec

- PaymentGroupHeaderRec
- PaymentGroupFooterRec

| Record Sequence | Record Type | Description |
|-----------------|-----------------------|--|
| 1 | BatchRec | NA |
| 2 | PaymentGroupHeaderRec | For group 1 (PaymentDate1, PayeeName1) |
| 3 | PaymentGroupFooterRec | For group 1 (PaymentDate1, PayeeName1) |
| 4 | PaymentGroupHeaderRec | For group 2 (PaymentDate1, PayeeName2) |
| 5 | PaymentGroupFooterRec | For group 2 (PaymentDate1, PayeeName2) |
| 6 | PaymentGroupHeaderRec | For group 3 (PaymentDate1, PayeeName3) |
| 7 | PaymentGroupFooterRec | For group 3 (PaymentDate1, PayeeName3) |
| 8 | PaymentGroupHeaderRec | For group 4 (PaymentDate2, PayeeName1) |
| 9 | PaymentGroupFooterRec | For group 4 (PaymentDate2, PayeeName1) |

Scenario 2: Group Records and Individual Records

EFT File Structure:

BatchRec

- PaymentGroupHeaderRec
 - PaymentRec
- PaymentGroupFooterRec

| Record Sequence | Record Type | Description |
|-----------------|-----------------------|--|
| 1 | BatchRec | NA |
| 2 | PaymentGroupHeaderRec | For group 1 (PaymentDate1, PayeeName1) |
| 3 | PaymentRec | For Payment1 |
| 4 | PaymentRec | For Payment4 |
| 5 | PaymentGroupFooterRec | For group 1 (PaymentDate1, PayeeName1) |
| 6 | PaymentGroupHeaderRec | For group 2 (PaymentDate1, PayeeName2) |
| 7 | PaymentRec | For Payment3 |
| 8 | PaymentGroupFooterRec | For group 2 (PaymentDate1, PayeeName2) |

| Record Sequence | Record Type | Description |
|-----------------|-----------------------|--|
| 9 | PaymentGroupHeaderRec | For group 3 (PaymentDate1, PayeeName3) |
| 10 | PaymentRec | For Payment5 |
| 11 | PaymentGroupFooterRec | For group 3 (PaymentDate1, PayeeName3) |
| 12 | PaymentGroupHeaderRec | For group 4 (PaymentDate2, PayeeName1) |
| 13 | PaymentRec | For Payment2 |
| 14 | PaymentGroupFooterRec | For group 4 (PaymentDate2, PayeeName1) |

Once defined with the Define Level command, the new level can be used in the template in the same manner as a level occurring in the extract. However, the records of the new level can only reference the base level fields that are defined in its grouping criteria. They cannot reference other base level fields other than in summary functions.

For example, the PaymentGroupHeaderRec can reference the PaymentDate and PayeeName in its fields. It can also reference the PaymentAmount (a payment level field) in a SUM function. However, it cannot reference other payment level fields, such as PaymentDocName or PaymentDocNum.

The DEFINE LEVEL command must always have one and only one grouping criteria subcommand. The DEFINE LEVEL command has a companion END DEFINE LEVEL command. The subcommands must be specified between the DEFINE LEVEL and END DEFINE LEVEL commands. They can be declared in any order.

DEFINE SEQUENCE Command

The DEFINE SEQUENCE command defines a sequence that can be used in conjunction with the SEQUENCE_NUMBER function to index either the generated EFT records or the extract instances (the database records). The EFT records are the physical records defined in the template. The database records are the records from the extract. To avoid confusion, the term *record* always refers to the EFT record. The database record is referred to as an extract element instance or level.

The DEFINE SEQUENCE command has four subcommands: RESET AT LEVEL, INCREMENT BASIS, START AT, MINIMUM, and MAXIMUM:

RESET AT LEVEL

The RESET AT LEVEL subcommand defines where the sequence resets its starting number.

RESET AT LEVE is a mandatory subcommand. For example, to number the payments in a batch, define RESET AT LEVEL as Batch. To continue numbering across batches, define RESET AT LEVEL as RequestHeader.

In some cases the sequence is reset outside the template. For example, a periodic sequence may be defined to reset by date. In these cases, the PERIODIC_SEQUENCE keyword is used for the RESET AT LEVEL. The system saves the last sequence number used for a payment file to the database. Outside

events control resetting the sequence in the database. For the next payment file run, the sequence number is extracted from the database for the start at number (see start at subcommand).

INCREMENT BASIS

The INCREMENT BASIS subcommand specifies if the sequence should be incremented based on record or extract instances. The allowed parameters for this subcommand are RECORD and LEVEL.

Enter RECORD to increment the sequence for every record.

Enter LEVEL to increment the sequence for every new instance of a level.

Note that for levels with multiple records, if you use the level-based increment, then all the records in the level have the same sequence number. The record-based increment assigns each record in the level a new sequence number.

For level-based increments, the sequence number can be used in the fields of one level only. For example, suppose an extract has a hierarchy of batch > payment > invoice and you define the INCREMENT BASIS by level sequence, with reset at the batch level. You can use the sequence in either the payment or invoice level fields, but not both. You cannot have sequential numbering across hierarchical levels.

However, this rule doesn't apply to increment basis by record sequences. Records can be sequenced across levels.

For both increment basis by level and by record sequences, the level of the sequence is implicit based on where the sequence is defined.

MINIMUM

Specifies the minimum sequence number.

If MINIMUM isn't declared, the minimum sequence number is set as 1 by default.

Specify this value when you want the minimum sequence number to be a value other than 1.

Define Concatenation Command

Use the define concatenation command to concatenate child-level extract elements for use in parent-level fields.

For example, use this command to concatenate invoice number and due date for all the invoices belonging to a payment for use in a payment-level field.

The define concatenation command has three subcommands: base level, element, and delimiter.

Base Level Subcommand

The base level subcommand specifies the child level for the operation.

For each parent-level instance, the concatenation operation loops through the child-level instances to generate the concatenated string.

Element Subcommand

The element subcommand specifies the operation used to generate each element. An element is a child-level expression that is concatenated to generate the concatenation string.

Delimiter Subcommand

The delimiter subcommand specifies the delimiter to separate the concatenated items in the string.

Use the SUBSTR Function

Use the SUBSTR function to break down concatenated strings into smaller strings that can be placed into different fields.

For example, the following table shows five invoices in a payment.

| Invoice | InvoiceNum |
|---------|-------------------|
| 1 | car_parts_inv0001 |
| 2 | car_parts_inv0002 |
| 3 | car_parts_inv0003 |
| 4 | car_parts_inv0004 |
| 5 | car_parts_inv0005 |

Using the concatenation definition shown in the following table:

| Level | Definition |
|----------------------------|-------------------------|
| <DEFINE CONCATENATION> | ConcatenatedInvoiceInfo |
| <BASE LEVEL> | Invoice |
| <ELEMENT> | InvoiceNum |
| <DELIMITER> | ',' |
| <END DEFINE CONCATENATION> | ConcatenatedInvoiceInfo |

You can reference ConcatenatedInvoiceInfo in a payment level field. The string is as follows:

```
car_parts_inv0001,car_parts_inv0002,car_parts_inv0003,car_parts_inv0004,car_parts_inv0005
```

If you want to use only the first forty characters of the concatenated invoice information, then use either TRUNCATE function or the SUBSTR function as follows:

```
TRUNCATE(ConcatenatedInvoiceInfo, 40)
```

```
SUBSTR(ConctenatedInvoiceInfo, 1, 40)
```

Either of these statements result in:

```
car_parts_inv0001,car_parts_inv0002,car_
```


To isolate the next forty characters, use the SUBSTR function:

```
SUBSTR(ConcatenatedInvoiceInfo, 41, 40)
```

to get the following string:

```
parts_inv0003,car_parts_inv0004,car_par
```

Invalid Characters and Replacement Characters Commands

Some formats require a different character set than the one that was used to enter the data in Oracle Applications. For example, some German formats require the output file in ASCII, but the data was entered in German. If there's a mismatch between the original and target character sets you can define an ASCII equivalent to replace the original. For example, you would replace the German umlauted "a" with "ao".

Some formats don't allow certain characters. To ensure that known invalid characters are not transmitted in the output file, use the invalid characters command to flag occurrences of specific characters.

To use the replacement characters command, specify the source characters in the left column and the replacement characters in the right column. You must enter the source characters in the original character set. This is the only case in a format template in which you use a character set not intended for output. Enter the replacement characters in the required output character set.

For DELIMITER_BASED formats, if there're delimiters in the data, you can use the escape character "?" to retain their meaning. For example,

First name?+Last name equates to First name+Last name

Which source?? equates to Which source?

Note that the escape character itself must be escaped if it's used in data.

The replacement characters command can be used to support the escape character requirement. Specify the delimiter as the source and the escape character plus the delimiter as the target. For example, the command entry for the preceding examples is as follows:

```
<REPLACEMENT CHARACTERS>
+   ?+
?   ??
<END REPLACEMENT CHARACTERS>
```

The invalid character command has a single parameter that is a string of invalid characters that causes the system to error out.

The replacement character process is performed before or during the character set conversion. The character set conversion is performed on the XML extract directly, before the formatting. After the character set conversion, the invalid characters are checked in terms of the output character set. If no invalid characters are found, then the system proceeds to formatting.

Output Character Set and New Record Character Commands

Use the new record character command to specify the character(s) to delimit the explicit and implicit record breaks at runtime.

Each new record command represents an explicit record break. Each end of table represents an implicit record break. The parameter is a list of constant character names separated by commas.

Some formats contain no record breaks. The generated output is a single line of data. In this case, leave the new record character command parameter field empty.

If you do not define a "new record character" field in the template, then the system sets "\n" as default new record character.

Output Length Mode

Output Length Mode can be set to "character" or "byte".

When OUTPUT LENGTH MODE is set to "character", the output record length for each field is based on character length. When OUTPUT LENGTH MODE is set to "byte", the output record length for each field is based on byte length.

If no OUTPUT LENGTH MODE is setting is provided, "character" is used.

Number Thousands Separator and Number Decimal Separator

The default thousands (or group) separator is a comma (",") and the default decimal separator is a period ("."). Use the Number Thousands Separator command and the Number Decimal Separator command to specify separators other than the defaults.

For example, to define "." as the group separator and "," as the decimal separator, enter the commands as follows:

```
<NUMBER THOUSANDS SEPARATOR> .  
<NUMBER DECIMAL SEPARATOR> ,
```

Note that when you set "NUMBER DECIMAL SEPARATOR", you must also set "NUMBER THOUSANDS SEPARATOR". Ensure to set the appropriate format mask for the field to be displayed. For more information on formatting numbers, see [Format Column](#).

CASE CONVERSION

Use CASE CONVERSION to convert strings from lowercase to uppercase for fields with format type ALPHA. This command is used with FIXED_POSITION_BASED templates.

Valid values are "UPPER" and "LOWER". Enter the command as follows:

```
<CASE CONVERSION> : UPPER
```

Create a Filler Block

For `FIXED_POSITION_BASED` templates, you can use a filler block to define a specific block size for the eText output. When the actual data doesn't fill the specified block size, the remainder of the block is filled with a specified filler character.

For example, if you define a `BLOCK SIZE` of 9, and the eText output generated is only three lines of text, then the remaining six lines are filled with the specified `FILLER CHARACTER`.

The commands used are:

- `<BEGIN FILLER BLOCK>` - this signifies the beginning of the block. Enter a name for this block.
- `<FILLER CHARACTER>` - enter a character or string to use to "fill" the remainder of the block when the data doesn't fill it.

Example entries for `<FILLER CHARACTER>` are:

To fill the block with the `?` character, enter the `FILLER CHARACTER` command as shown:

```
<FILLER CHARACTER> : ?
```

To fill the block with the string `abc`, enter the `FILLER CHARACTER` command as shown:

```
<FILLER CHARACTER> : abc
```

To fill the block with empty spaces, enter the `FILLER CHARACTER` command as shown:

```
<FILLER CHARACTER> :
```

- `<BLOCK SIZE>` - enter an integer to specify the size of the block in lines of text.

These commands must be used before the template definition starts.

Enter the following command at the end of the block:

- `<END FILLER BLOCK>` - signifies the end of the block. Enter the name already specified for this block in the `<BEGIN FILLER BLOCK>` command.

The following figure shows an example of filler block usage:

| | |
|---|----------------------------|
| <code><BEGIN FILLER BLOCK></code> | <code>PaymentsBlock</code> |
| <code><FILLER CHARACTER></code> | <code>?</code> |
| <code><BLOCK SIZE></code> | <code>5</code> |

and ELSE clauses are optional, and there can be as many ELSIF clauses as necessary. The control structure can be nested.

The IN predicate is supported in the IF-THEN-ELSE control structure. For example:

```
IF PaymentAmount/Currency/Code IN ('USD', 'EUR', 'AON', 'AZM')
THEN
    PayeeAccount/FundsCaptureOrder/OrderAmount/Value * 100
ELSIF PaymentAmount/Currency/Code IN ('BHD', 'IQD', 'KWD') THEN
    PayeeAccount/FundsCaptureOrder/OrderAmount/Value * 1000
ELSE
    PayeeAccount/FundsCaptureOrder/OrderAmount/Value
END IF;
```

Functions

Here is the list of supported functions.

- **SEQUENCE_NUMBER** - Is a record element index. It's used in conjunction with the Define Sequence command. It has one parameter, which is the sequence defined by the Define Sequence command. At runtime it increases its sequence value by one each time it's referenced in a record.
- **COUNT** - Counts the child level extract instances or child level records of a specific type. Declare the COUNT function on a level above the entity to be counted. The function has one argument. If the argument is a level, then the function counts all the instances of the (child) level belonging to the current (parent) level instance.

Example: If the level to be counted is Payment and the current level is Batch, then the COUNT returns the total number of payments in the batch. However, if the current level is RequestHeader, the COUNT returns the total number of payments in the file across all batches. If the argument is a record type, the count function counts all the generated records of the (child level) record type belonging to the current level instance.

- **INTEGER_PART, DECIMAL_PART** - Returns the integer or decimal portion of a numeric value. This is used in nested expressions and in commands (display condition and group by). For the final formatting of a numeric field in the data column, use the Integer/Decimal format.
- **IS_NUMERIC** - Boolean test whether the argument is numeric. Used only with the "IF" control structure.
- **TRUNCATE** - Truncates the first argument - a string to the length of the second argument. If the first argument is shorter than the length specified by the second argument, the first argument is returned unchanged. This is a user-friendly version for a subset of the SQL substr() functionality.
- **SUM** - Sums all the child instance of the XML extract field argument. The field must be a numeric value. The field to be summed must always be at a lower level than the level on which the SUM function was declared.
- **MIN, MAX** - Finds the minimum or maximum of all the child instances of the XML extract field argument. The field must be a numeric value. The field to be operated on must always be at a lower level than the level on which the function was declared.

- **FORMAT_DATE** - Formats a date string to any desirable date format. For example:
`FORMAT_DATE("1900-01-01T18:19:20", "YYYY/MM/DD HH24:MI:SS")`
produces the following output:
1900/01/01 18:19:20
- **FORMAT_NUMBER** - Formats a number to display in desired format. For example:
`FORMAT_NUMBER("1234567890.0987654321", "999,999.99")`
produces the following output:
1,234,567,890.10
- **MESSAGE_LENGTH** - Returns the length of the message in the EFT message.
- **RECORD_LENGTH** - Returns the length of the record in the EFT message.
- **INSTR** - Returns the numeric position of a named character within a text field.
- **SYSDATE, DATE** - Gets Current Date and Time.
- **POSITION** - Returns the position of a node in the XML document tree structure.
- **REPLACE** - Replaces a string with another string.
- **CONVERT_CASE** - Converts a string or a character to UPPER or LOWER case.
- **CHR** - Gets the character representation of an argument, which is an ASCII value.
- **LPAD, RPAD** - Generates left or right padding for string values.
- **AND, OR, NOT** - Operator functions on elements.
- **AddToVar** - Adds the specified value to the current value of the variable, and returns the value added to the variable. If the assignment is unsuccessful, the function returns 0. If the variable doesn't exist, the function creates a new variable and assigns the specified value.
Usage: `AddToVar(var-name,value-to-be-added)`
Example:
`AddToVar('MyVAR', 10)` - if MyVar=0, assigns 10 to MyVar, and returns 10.
`AddToVar('MyVAR', 20)` - if MyVar=10, adds 20 to MyVar, assigns 30 to MyVar, and returns 20.
- **GetVar** - Returns the value of the specified variable. Returns 0 if the variable doesn't exist.
Usage: `GetVar(var-name)`
Example: `GetVar('MyVAR')`
- **ResetVar** - Resets the value of the variable to 0.
Usage: `ResetVar(var-name)`
Example: `ResetVar('MyVAR')`
- **SetVar** - Assigns the specified value to the variable, and returns the assigned value.
Usage: `SetVar(var-name, value-to-be-assigned)`
Example: `SetVar('MyVAR', 1200)`

- **DISTINCT_VALUES** - Returns a sequence in which all but one of a set of duplicate values, based on value equality, have been deleted. Equivalent to the XPATH function **DISTINCT-VALUES**. Usage: `distinct_values(fieldname)`.
- **INCREASE_DATE** - Increments a date by the number of days specified.
Usage:
`increase_date(//date, 2)`
returns a date value two days after the value of `//date`
- **DECREASE_DATE** - Decreases a date by the number of days specified.
Usage:
`decrease_date(//date, 2)`
returns a date value two before the value of `//date`
- **XPATH** - Allows direct injection of pure XPath language to generate the XSL template.
Example:
`XPATH('sum(..//PRE_TAX_DEDUCTIONS/PAYMENT)[position() >= 9]')`
`XPATH('sum(..//PRE_TAX_DEDUCTIONS/PAYMENT)[NAME = 'NULL']')`
- Other SQL functions include the following. Use the syntax corresponding to the SQL function.
 - **TO_DATE**
 - **LOWER**
 - **UPPER**
 - **LENGTH**
 - **GREATEST**
 - **LEAST**
 - **DECODE**
 - **CEIL**
 - **ABS**
 - **FLOOR**
 - **ROUND**
 - **CHR**
 - **TO_CHAR**
 - **SUBSTR**
 - **LTRIM**
 - **RTRIM**
 - **TRIM**
 - **IN**
 - **TRANSLATE**

Identifiers, Operators, and Literals

This section lists the reserved key word and phrases and their usage. The supported operators are defined and the rules for referencing XML extract fields and using literals.

Key Words

There're several categories of key words and key word phrases:

- Command and column header key words
- Command parameter and function parameter key words
- Field-level key words
- Expression key words

Command and Column Header Key Words

The command and column header key words must be used in the format shown: enclosed in <>s and in all capital letters with a bold font.

- **<LEVEL>** - the first entry of a data table. Associates the table with an XML element and specifies the hierarchy of the table.
- **<END LEVEL>** - declares the end of the current level. Can be used at the end of a table or in a standalone table.
- **<POSITION>** - column header for the first column of data field rows, which specifies the starting position of the data field in a record.
- **<LENGTH>** - column header for the second column of data field rows, which specifies the length of the data field.
- **<FORMAT>** - column header for the third column of data field rows, which specifies the data type and format setting.
- **<PAD>** - column header for the fourth column of data field rows, which specifies the padding style and padding character.
- **<DATA>** - column header for the fifth column of data field rows, which specifies the data source.
- **<COMMENT>** - column header for the sixth column of data field rows, which allows for free form comments.
- **<NEW RECORD>** - specifies a new record.
- **<DISPLAY CONDITION>** - specifies the condition when a record should be printed.
- **<TEMPLATE TYPE>** - specifies the type of the template, either `FIXED_POSITION_BASED` or `DELIMITER_BASED`.
- **<OUTPUT CHARACTER SET>** - specifies the character set to be used when generating the output.
- **<NEW RECORD CHARACTER>** - specifies the character(s) to use to signify the explicit and implicit new records at runtime.

- **<DEFINE LEVEL>** - defines a format-specific level in the template.
- **<BASE LEVEL>** - subcommand for the define level and define concatenation commands.
- **<GROUPING CRITERIA>** - subcommand for the define level command.
- **<END DEFINE LEVEL>** - signifies the end of a level.
- **<DEFINE SEQUENCE>** - defines a record or extract element based sequence for use in the template fields.
- **<RESET AT LEVEL>** - subcommand for the define sequence command.
- **<INCREMENT BASIS>** - subcommand for the define sequence command.
- **<START AT>** - subcommand for the define sequence command.
- **<MAXIMUM>** - subcommand for the define sequence command.
- **<MINIMUM>** - subcommand for the define sequence command.
- **<MAXIMUM LENGTH>** - column header for the first column of data field rows, which specifies the maximum length of the data field. For DELIMITER_BASED templates only.
- **<END DEFINE SEQUENCE>** - signifies the end of the sequence command.
- **<DEFINE CONCATENATION>** - defines a concatenation of child level elements that can be referenced as a string in the parent level fields.
- **<ELEMENT>** - subcommand for the define concatenation command.
- **<DELIMITER>** - subcommand for the define concatenation command.
- **<END DEFINE CONCATENATION>** - signifies the end of the define concatenation command.
- **<SORT ASCENDING>** - format-specific sorting for the instances of a level.
- **<SORT DESCENDING>** - format-specific sorting for the instances of a level.
- **<SORT ASCENDING NUMBER>** - numeric sorting for the instances of a level.
- **<SORT DESCENDING NUMBER>** - numeric sorting for the instances of a level.

Command Parameter and Function Parameter Key Words

The command parameter and function parameter key words must be entered in all capital letters, non-bold fonts.

- PERIODIC_SEQUENCE - used in the reset at level subcommand of the define sequence command. It denotes that the sequence number is to be reset outside the template.
- FIXED_POSITION_BASED, DELIMITER_BASED - used in the template type command, specifies the type of template.
- RECORD, LEVEL - used in the increment basis subcommand of the define sequence command. RECORD increments the sequence each time it's used in a new record. LEVEL increments the sequence only for a new instance of the level.

Field-Level Key Words

This section gives a list of key words and specifies the data type for each.

- **Alpha** - in the <FORMAT> column, specifies the data type is alphanumeric.
- **Number** - in the <FORMAT> column, specifies the data type is numeric.
- **Integer** - in the <FORMAT> column, used with the Number key word. Takes the integer part of the number. This has the same functionality as the INTEGER function, except the INTEGER function is used in expressions, while the Integer key word is used in the <FORMAT> column only.
- **Decimal** - in the <FORMAT> column, used with the Number key word. Takes the decimal part of the number. This has the same functionality as the DECIMAL function, except the DECIMAL function is used in expressions, while the Decimal key word is used in the <FORMAT> column only.
- **Date** - in the <FORMAT> column, specifies the data type is date.
- **L, R** - in the <PAD> column, specifies the side of the padding (Left or Right).

Expression Key Words

Key words and phrases used in expressions must be in capital letters and bold fonts.

- **IF THEN ELSE IF THEN ELSE END IF** - these key words are always used as a group. They specify the "IF" control structure expressions.
- **IS NULL, IS NOT NULL** - these phrases are used in the IF control structure. They form part of boolean predicates to test if an expression is NULL or not NULL.

Operators

There're two groups of operators: the boolean test operators and the expression operators.

The boolean test operators include: "=", "<>", "<", ">", ">=", and "<=". They can be used only with the IF control structure. The expression operators include: "()", "||", "+", "-", and "*". They can be used in any expression.

The following table lists the operators and describes their usage.

| Symbol | Usage |
|--------|--|
| = | Equal to test. Used in the IF control structure only. |
| <> | Not equal to test. Used in the IF control structure only. |
| > | Greater than test. Used in the IF control structure only. |
| < | Less than test. Used in the IF control structure only. |
| >= | Greater than or equal to test. Used in the IF control structure only. |
| <= | Less than or equal to test. Used in the IF control structure only. |
| () | Function argument and expression group delimiter. The expression group inside "()" is always be evaluated first. "()" can be nested. |
| | Union operator to be used in the <LEVEL> element. |

| Symbol | Usage |
|--------|---|
| | String concatenation operator. |
| + | Addition operator. Implicit type conversion may be performed if any of the operands aren't numbers. |
| - | Subtraction operator. Implicit type conversion may be performed if any of the operands aren't numbers. |
| * | Multiplication operator. Implicit type conversion may be performed if any of the operands aren't numbers. |
| DIV | Division operand. Implicit type conversion may be performed if any of the operands are not numbers. Note that "/" isn't used because it's part of the XPATH syntax. |
| IN | Equal-to-any-member-of test. |
| NOT IN | Negates the IN operator. Not-Equal-to-any-member-of test. |

Reference to XML Extract Fields and XPATH Syntax

XML elements can be used in any expression.

At runtime XML elements are replaced with the corresponding field values. The field names are case-sensitive.

When the XML extract fields are used in the template, they must follow the XPATH syntax. This is required so that the Publisher engine can correctly interpret the XML elements.

There's always an extract element considered as the context element during the Publisher formatting process. When Publisher processes the data rows in a table, the level element of the table is the context element. For example, when Publisher processes the data rows in the Payment table, Payment is the context element. The relative XPATH you use to reference the extract elements are specified in terms of the context element.

For example to refer to the PayeeName element in a Payment data table, specify the following relative path:

```
Payee/PayeeInfo/PayeeName
```

Each layer of the XML element hierarchy is separated by a backslash "/". You use this notation for any nested elements. The relative path for the immediate child element of the level is just the element name itself. For example, you can use TransactionID element name as is in the Payment table.

To reference a parent level element in a child level table, you can use the "../" notation. For example, in the Payment table if you must reference the BatchName element, you can specify ../BatchName. The "../" provides Batch as the context; in that context you can use the BatchName element name directly as BatchName is an immediate child of Batch. This notation goes up to any level for the parent elements. For example if you must reference the RequesterParty element (in the RequestHeader) in a Payment data table, you can specify the following:

```
../../../../TrxnParties/RequesterParty
```

You can always use the absolute path to reference any extract element anywhere in the template. The absolute path starts with a backslash "/". For the PayeeName in the

Payment table example above, you have the following absolute path: /BatchRequest/ Batch/Payment/Payee/PayeeInfo/PayeeName

The absolute path syntax provides better performance.

The identifiers defined by the setup commands such as define level, define sequence and define concatenation are considered to be global. They can be used anywhere in the template. No absolute or relative path is required. The base level and reset at level for the setup commands can also be specified. Publisher can find the correct context for them.

If you use relative path syntax, then you should specify it relative to the base levels in the following commands:

- The element subcommand of the define concatenation command
- The grouping criteria subcommand of the define level command

The extract field reference in the start at subcommand of the define sequence command should be specified with an absolute path.

The rule to reference an extract element for the level command is the same as the rule for data fields. For example, if you have a Batch level table and a nested Payment level table, then you can specify the Payment element name as-is for the Payment table. Because the context for evaluating the Level command of the Payment table is the Batch.

However, if you skip the Payment level and you have an Invoice level table directly under the Batch table, then you must specify Payment/Invoice as the level element for the Invoice table.

The XPATH syntax required by the template is very similar to UNIX/LINUX directory syntax. The context element is equivalent to the current directory. You can specify a file relative to the current directory or you can use the absolute path which starts with a "/".

Finally, the extract field reference as the result of the grouping criteria sub-command of the define level command must be specified in single quotes. This tells the Publisher engine to use the extract fields as the grouping criteria, not their values.

Notes on Viewing eText Output from a Browser

If the report data contains Simplified Chinese characters and the <OUTPUT CHARACTER SET> is set to GBK, then the Chinese characters do not display properly in Internet Explorer 7 with gbk2312 encoding.

This issue may also occur in other non-English encodings as well, such as native Japanese and Korean. The output renders appropriately with Firefox 3.5, when setting the character set to be GBK in the eText template and setting the browser encoding to be GBK or GB2312. You can work around this issue by setting <OUTPUT CHARACTER SET> to utf-8. Note that this is a browser display issue only. The text file is generated correctly.

18

Set Report Processing and Output Document Properties

This topic describes how to configure report processing and output document properties.

Topics:

- [Overview](#)
- [PDF Output Properties](#)
- [PDF Digital Signature Properties](#)
- [PDF Accessibility Properties](#)
- [PDF/A Output Properties](#)
- [PDF/X Output Properties](#)
- [DOCX Output Properties](#)
- [RTF Output Properties](#)
- [PPTX Output Properties](#)
- [HTML Output Properties](#)
- [FO Processing Properties](#)
- [RTF Template Properties](#)
- [XPT Template Properties](#)
- [PDF Template Properties](#)
- [Excel Template Properties](#)
- [CSV Output Properties](#)
- [Excel Output Properties](#)
- [EText Output Properties](#)
- [All Outputs Properties](#)
- [Define Font Mappings](#)

Overview

The **Formatting** tab of the Report Properties dialog enables you to set runtime formatting properties at the report level.

These properties are also set at the system level. If conflicting values are set for a property at each level, the report level takes precedence.


To set a property at the report level:

1. Open the report in the Report Editor. and then

2. Click **Properties** to display the Report Properties dialog.
3. Click the **Formatting** tab to display the formatting properties.

For each property, **Report Value** is updatable and the **Server Value** is shown for reference.

The Formatting tab of the Report Properties dialog is shown in the following illustration.



PDF Output Properties

Generate the type of PDF files you want by setting available output properties.

| Property Name | Description | Default | Configuration Name |
|-----------------------------|--|---------|--------------------|
| Compress PDF output | Specify "true" or "false" to control compression of the output PDF file. | true | pdf-compression |
| Hide PDF viewer's menu bars | Specify "true" to hide the viewer application's menu bar when the document is active. The menu bar option is only effective when using the Export button, which displays the output in a standalone Acrobat Reader application outside of the browser. | false | pdf-hide-menubar |

| Property Name | Description | Default | Configuration Name |
|--|--|---------|--|
| Hide PDF viewer's tool bars | Specify "true" to hide the viewer application's toolbar when the document is active. | false | pdf-hide-toolbar |
| Replace smart quotes | Specify "false" if you don't want curly quotes replaced with straight quotes in the PDF output. | true | pdf-replace-smartquotes |
| Disable opacity and gradient shading for DVT chart | Specify "true" if you don't want opacity and gradient shading for the PDF output. This reduces the size of the PostScript file. | false | pdf-dvt-no-opacity-no-gradient-shading |
| Enable PDF Security | Specify "true" if you want to encrypt the PDF output. You can then also specify the following properties: <ul style="list-style-type: none"> • Open document password • Modify permissions password • Encryption Level | false | pdf-security |
| Open document password | This password is required for opening the document. It enables users to open the document only. This property is enabled only when "Enable PDF Security" is set to "true". Note that Adobe's password restrictions apply. The password must contain only Latin-1 characters and must be no more than 32 bytes long. | N/A | pdf-open-password |
| Modify permissions password | This password enables users to override the security setting. This property is effective only when "Enable PDF Security" is set to "true". Note that Adobe's password restrictions apply. The password must contain only Latin-1 characters and must be no more than 32 bytes long. If you set a password in the pdf-open-password property without setting a password in the pdf-permissions-password property, or if you set the same password in both the pdf-open-password and pdf-permissions-password properties, the user gets full access to the document and its features, and permission settings such as "Disable printing" are bypassed or ignored. | N/A | pdf-permissions-password |

| Property Name | Description | Default | Configuration Name |
|--|---|----------|------------------------------|
| Encryption level | <p>Specify the encryption level for the output PDF file. The possible values are:</p> <ul style="list-style-type: none"> 0: Low (40-bit RC4, Acrobat 3.0 or later) 1: Medium (128-bit RC4, Acrobat 5.0 or later) 2: High (128-bit AES, Acrobat 7.0 or later) <p>This property is effective only when "Enable PDF Security" is set to "true". When Encryption level is set to 0, you can also set the following properties:</p> <ul style="list-style-type: none"> Disable printing Disable document modification Disable context copying, extraction, and accessibility Disable adding or changing comments and form fields <p>When Encryption level is set to 1 or higher, the following properties are available:</p> <ul style="list-style-type: none"> Enable text access for screen readers Enable copying of text, images, and other content Allowed change level Allowed printing level | 2 - high | pdf-encryption-level |
| Disable document modification | Permission available when "Encryption level" is set to 0. When set to "true", the PDF file cannot be edited. | false | pdf-no-changing-the-document |
| Disable printing | Permission available when "Encryption level" is set to 0. When set to "true", printing is disabled for the PDF file. | false | pdf-no-printing |
| Disable adding or changing comments and form fields | Permission available when "Encryption level" is set to 0. When set to "true", the ability to add or change comments and form fields is disabled. | false | pdf-no-accff |
| Disable context copying, extraction, and accessibility | Permission available when "Encryption level" is set to 0. When set to "true", the context copying, extraction, and accessibility features are disabled. | false | pdf-no-cceda |

| Property Name | Description | Default | Configuration Name |
|---|--|---------|--------------------------|
| Enable text access for screen readers | Permission available when "Encryption level" is set to 1 or higher. When set to "true", text access for screen reader devices is enabled. | true | pdf-enable-accessibility |
| Enable copying of text, images, and other content | Permission available when "Encryption level" is set to 1 or higher. When set to "true", copying of text, images, and other content is enabled. | false | pdf-enable-copying |
| Allowed change level | Permission available when "Encryption level" is set to 1 or higher. Valid Values are: <ul style="list-style-type: none">• 0: none• 1: Allows inserting, deleting, and rotating pages• 2: Allows filling in form fields and signing• 3: Allows commenting, filling in form fields, and signing• 4: Allows all changes except extracting pages | 0 | pdf-changes-allowed |
| Allowed printing level | Permission available when "Encryption level" is set to 1 or higher. Valid values are: <ul style="list-style-type: none">• 0: None• 1: Low resolution (150 dpi)• 2: High resolution | 0 | pdf-printing-allowed |

| Property Name | Description | Default | Configuration Name |
|--|--|----------------|-----------------------|
| Use only one shared resources object for all pages | <p>The default mode of Publisher creates one shared resources object for all pages in a PDF file. This mode has the advantage of creating an overall smaller file size. However, the disadvantages are the following:</p> <ul style="list-style-type: none"> Viewing may take longer for a large file with many SVG objects If you choose to break up the file by using Adobe Acrobat to extract or delete portions, then the edited PDF files are larger because the single shared resource object (that contains all of the SVG objects for the entire file) is included with each extracted portion. <p>Setting this property to "false" creates a resource object for each page. The file size is larger, but the PDF viewing is faster and the PDF can be broken up into smaller files more easily.</p> | true | pdf-use-one-resources |
| PDF Navigation Panel Initial View | <p>Controls the navigation panel view presented when a user first opens a PDF report. The following options are supported:</p> <ul style="list-style-type: none"> Panels Collapsed - displays the PDF document with the navigation panel collapsed. Bookmarks Open (default) - displays the bookmark links for easy navigation. Pages Open - displays a clickable thumbnail view of each page of the PDF. | Bookmarks Open | pdf-pagemode |

PDF Digital Signature Properties

You set properties at the report level to enable digital signature for a report and to define the placement of the signature in the output PDF document.

Note that to implement digital signature for a report based on a PDF layout template or an RTF layout template, you must set the property **Enable Digital Signature** to "True" for the report.

You also must set the appropriate properties to place the digital signature in the desired location on your output report. Your choices for placement of the digital signature depend on the template type. The choices are as follows:

- (PDF only) Place the digital signature in a specific field by setting the **Existing signature field name** property.
- (RTF and PDF) Place the digital signature in a general location of the page (top left, top center, or top right) by setting the **Signature field location** property.
- (RTF and PDF) Place the digital signature in a specific location designated by x and y coordinates by setting the **Signature field x coordinate** and **Signature field y coordinate** properties.

If you choose this option, you can also set **Signature field width** and **Signature field height** to define the size of the field in your document.

| Property Name | Description | Default | Configuration Name |
|-------------------------------|---|---------|--------------------------|
| Enable Digital Signature | Set this to "true" to enable digital signature for the report. | false | signature-enable |
| Existing signature field name | This property applies to PDF layout templates only. If the report is based on a PDF template, then you can enter a field from the PDF template in which to place the digital signature. | N/A | signature-field-name |
| Signature field location | This property can apply to RTF or PDF layout templates. This property provides a list that contains the following values: Top Left, Top Center, Top Right. Choose one of these general locations and Publisher inserts the digital signature to the output document, sized and positioned appropriately. If you choose to set this property, do not enter X and Y coordinates or width and height properties. | N/A | signature-field-location |
| Signature field X coordinate | This property can apply to RTF or PDF layout templates. Using the left edge of the document as the zero point of the X axis, enter the position in points that you want the digital signature to be placed from the left. For example, if you want the digital signature to be placed horizontally in the middle of an 8.5 inch by 11 inch document (that is, 612 points in width and 792 points in height), enter 306. | 0 | signature-field-pos-x |

| Property Name | Description | Default | Configuration Name |
|------------------------------|---|---------|------------------------|
| Signature field Y coordinate | This property can apply to RTF or PDF layout templates. Using the bottom edge of the document as the zero point of the Y axis, enter the position in points that you want the digital signature to be placed from the bottom. For example, if you want the digital signature to be placed vertically in the middle of an 8.5 inch by 11 inch document (that is, 612 points in width and 792 points in height), enter 396. | 0 | signature-field-pos-y |
| Signature field width | Enter in points (72 points equal one inch) the desired width of the inserted digital signature field. This applies only if you're also setting the Signature field x coordinate and Signature field Y coordinate properties.. | 0 | signature-field-width |
| Signature field height | Enter in points (72 points equal one inch) the desired height of the inserted digital signature field. This applies only if you're also setting the Signature field x coordinate and Signature field Y coordinate properties. | 0 | signature-field-height |

PDF Accessibility Properties

Set the properties described in the table below to configure PDF accessibility.

| Property Name | Description | Default |
|---|---|---------|
| Make PDF output accessible | Set to "true" to make the PDF outputs accessible. Accessible PDF output contains the document title and PDF tags. | False |
| Use PDF/UA format for accessible PDF output | Set to "true" to use the PDF/UA format for the accessible PDF outputs. | False |

PDF/A Output Properties

Set properties to configure PDF/A output.

PDF/A output properties are described in the following table. See [Generate PDF/A Output](#).

| Property Name | Description | Default | Internal Name |
|-------------------------------|--|---|-----------------------|
| PDF/A version | Select one of the PDF/A standards. The value is set in the xmpMM:Version field of the metadata dictionary. PDF/A-1B preserves the visual appearance and structure of the document. PDF/A-2B supports the PDF/A-1B features, preserves transparency, and uses compressed objects and XRef streams to make the PDF file size smaller. | PDF/A-1B | pdfa-version |
| PDF/A ICC profile data | The name of the ICC profile data file, for example: CoatedFOGRA27.icc The ICC (International Color Consortium) profile is a binary file describing the color characteristics of the environment where this PDF/A file is intended to be displayed. The ICC profile that you select must have a major version below 4. To use a specific profile data file other than the default settings in the JVM, obtain the file and place it under <code><publisher repository>/Admin/Configuration</code> . When you set this property, you must also set a value for PDF/A ICC Profile Info (pdfa-icc-profile-info). | Default profile data provided by JVM | pdfa-icc-profile-data |
| PDF/A ICC profile info | ICC profile information (required when pdfa-icc-profile-data is specified) | sRGB IEC61966-2.1 | pdfa-icc-profile-info |
| PDF/A file identifier | One or more valid file identifiers set in the xmpMM:Identifier field of the metadata dictionary. To specify more than one identifier, separate values with a comma (,). | Automatically generated file identifier | pdfa-file-identifier |
| PDF/A document ID | Valid document ID. The value is set in the xmpMM:DocumentID field of the metadata dictionary. | None | pdfa-document-id |
| PDF/A version ID | Valid version ID. The value is set in the xmpMM:VersionID field of the metadata dictionary. | None | pdfa-version-id |
| PDF/A rendition class | Valid rendition class. The value is set in the xmpMM:RenditionClass field of the metadata dictionary. | None | pdfa-rendition-class |

PDF/X Output Properties

Set properties to configure PDF/X output.

PDF/X output properties are described in the table below. The values that you set for these properties will depend on the printing device. Note the following restrictions on other PDF properties:

- pdf-version - value above 1.4 isn't allowed for PDF/X-1a output

- pdf-security - must be set to False
- pdf-encryption-level - must be set to 0
- pdf-font-embedding - must be set to true

See [Generate PDF/X output](#).

| Property Name | Description | Default | Internal Name |
|-----------------------------------|---|---------|----------------------------------|
| PDF/X ICC Profile Data | <p>(Required) The name of the ICC profile data file, for example: CoatedFOGRA27.icc.</p> <p>The ICC (International Color Consortium) profile is a binary file describing the color characteristics of the intended output device. For production environments, the color profile may be provided by your print vendor or by the printing company that prints the generated PDF/X file. The file must be placed under <bi publisher repository>/Admin/Configuration.</p> | None | pdfx-dest-output-profile-data |
| PDF/X output condition identifier | <p>(Required) The name of one of the standard printing conditions registered with ICC (International Color Consortium). The list of standard CMYK printing conditions to use with PDF/X-1a is provided on the following ICC website: http://www.color.org/chardata/drsection1.xalter.</p> <p>The value that you enter for this property is a valid "Reference name," for example: FOGRA43.</p> <p>Choose the appropriate value for the intended printing environment. This name is often used to guide automatic processing of the file by the consumer of the PDF/X document, or to inform the default settings in interactive applications.</p> | None | pdfx-output-condition-identifier |
| PDF/X output condition | <p>A string describing the intended printing condition in a form that will be meaningful to a human operator at the site receiving the exchanged file. The value is set in OutputCondition field of OutputIntents dictionary.</p> | None | pdfx-output-condition |

| Property Name | Description | Default | Internal Name |
|---------------------|--|----------------------|--------------------|
| PDF/X registry name | A registry name. Set this property when the pdfx-output-condition-identifier is set to a characterization name that is registered in a registry other than the ICC registry. | http://www.color.org | pdfx-registry-name |
| PDF/X version | The PDF/X version set in GTS_PDFXVersion and GTS_PDFXConformance fields of Info dictionary. PDF/X-1a:2003 is the only value currently supported. | PDF/X-1a:2003 | pdfx-version |

DOCX Output Properties

The table below describes the properties that control DOCX output files.

| Property Name | Description | Default | Configuration Name |
|--------------------------------------|--|----------|---|
| Enable change tracking | Set to "true" to enable change tracking in the output document. | false | docx-track-changes |
| Protect document for tracked changes | Set to "true" to protect the document for tracked changes. | false | docx-protect-document-for-tracked-changes |
| Default font | Use this property to define the font style and size in the output when no other font has been defined. This is particularly useful to control the sizing of empty table cells in generated reports. Enter the font name and size in the following format <FontName>:<size> for example: Arial:12. Note that the font you choose must be available to the processing engine at runtime. | Arial:12 | docx-output-default-font |
| Open password | Use this property to specify the password that report users must provide to open any DOCX report. | NA | docx-open-password |

RTF Output Properties

You can configure RTF output with a number of predetermined properties.

Set the properties described in the table below to configure RTF output.

| Property Name | Description | Default | Internal Name |
|--------------------------------------|--|----------|--|
| Enable change tracking | Set to "true" to enable change tracking in the output RTF document. | false | rtf-track-changes |
| Protect document for tracked changes | Set to "true" to protect the document for tracked changes. | false | rtf-protect-document-for-tracked-changes |
| Default font | Use this property to define the font style and size in RTF output when no other font has been defined. This is particularly useful to control the sizing of empty table cells in generated reports. Enter the font name and size in the following format <FontName>:<size> for example: Arial:12. Note that the font you choose must be available to the Publisher processing engine at runtime. | Arial:12 | rtf-output-default-font |
| Enable widow orphan | Set to "true" to ensure that there're no hanging paragraphs in the document. If the last para in a page contains an orphaned line and the remaining lines of the paragraph continue in the next page, the starting line of the paragraph is moved to the next page to keep the lines of the paragraph together for better readability. | false | rtf-enable-widow-orphan |

PPTX Output Properties

The table below describes the properties that control PPTX output files.

| Property Name | Description | Default | Configuration Name |
|---------------|---|---------|--------------------|
| Open password | Use this property to specify the password that report users must provide to open any PPTX report. | NA | pptx-open-password |

HTML Output Properties

The table below describes the properties that control HTML output files.

| Property Name | Description | Default | Configuration Name |
|--|--|---------|---------------------------------|
| Show header | Set to "false" to suppress the template header in HTML output. | true | html-show-header |
| Show footer | Set to "false" to suppress the template footer in HTML output. | true | html-show-footer |
| Replace smart quotes | Set to "false" if you don't want curly quotes replaced with straight quotes in the HTML output. | true | html-replace-smartquotes |
| Character set | Specify the output HTML character set. | UTF-8 | html-output-character set |
| Make HTML output accessible | Set to "true" to make the HTML output accessible. | false | make-accessible |
| Use percentage width for table columns | Set to "true" to display table columns according to a percentage value of the total width of the table rather than as a value in points. This property is especially useful if the browser display tables with extremely wide columns. Setting this property to true improves the readability of the tables. | true | html-output-width-in-percentage |
| View Paginated | <p>When you set this property to true, HTML output will render in the report viewer with pagination features. These features include:</p> <ul style="list-style-type: none">• Generated table of contents• Navigation links at the top and bottom of the page• Ability to skip to a specific page within the HTML document• Search for strings within the HTML document using the browser's search capability• Zoom in and out on the HTML document using the browser's zoom capability <p>Note that these features are supported for online viewing through the report viewer only.</p> | false | |
| Reduce Padding in Table-cell | When you set this property to true, cells in HTML tables are displayed without padding, which maximizes the page space available for text. | false | html-reduce-padding |

| Property Name | Description | Default | Configuration Name |
|--|---|---------|--|
| Embed images and charts in HTML for offline viewing | When you set this property to true, charts and images are embedded in the HTML output, which is suitable for viewing offline. | true | html-use-data-uri |
| Use SVG for charts | When you set this property to true, charts display as a SVG (Scalable Vector Graphic) to provide a higher resolution in the HTML output. When you set this property to false, charts display as a raster image. | true | html-use-svg |
| Keep original table width | When you set this property to true, if a column in a table is deleted, the original width of the table is maintained. | true | html-keep-original-table-width |
| Enable horizontal scrollbar automatically for html table | When you set this property to true, a horizontal scroll bar is added to a table that doesn't fit within the current size of the browser window. | false | html-enable-horiz-table-scroll |
| Enable html table column size auto adjust | When you set this property to true, the column widths in a table are automatically adjusted to the size of the browser window. | false | html-enable-table-col-size-auto-adjust |
| Set zero height for empty paragraph | When you set this property to true and the output is HTML, the height of an empty paragraph (that is, a paragraph without text) is set to zero points. | true | html-set-empty-paragraph-zero-height |

FO Processing Properties

The table below describes the properties that control FO processing.

| Property Name | Description | Default | Configuration Name |
|---|--|---------|--------------------|
| Use BI Publisher's XSLT processor | Controls the use of parser. If set to false, then XSLT isn't parsed. | true | xslt-xdoparser |
| Enable scalable feature of XSLT processor | Controls the scalable feature of the XDO parser. The property "Use BI Publisher's XSLT processor" must be set to "true" for this property to be effective. | false | xslt-scalable |

| Property Name | Description | Default | Configuration Name |
|---------------------------------------|--|----------|----------------------------|
| Enable XSLT runtime optimization | When set to "true", the overall performance of the FO processor is increased and the size of the temporary FO files generated in the temp directory is significantly decreased. Note that for small reports (for example 1-2 pages) the increase in performance isn't as marked. To further enhance performance when you set this property to true, set the Extract attribute sets property to "false". | true | xslt-runtime-optimization |
| Enable XPath Optimization | When set to "true", the XML data file is analyzed for element frequency. The information is then used to optimize XPath in XSL. | false | xslt-xpath-optimization |
| Pages cached during processing | This property is enabled only when you specify a Temporary Directory (under General properties). During table of contents generation, the FO Processor caches the pages until the number of pages exceeds the value specified for this property. It then writes the pages to a file in the Temporary Directory. | 50 | system-cache-page-size |
| Bidi language digit substitution type | Valid values are "None" and "National". When set to "None", Eastern European numbers are used. When set to "National", Hindi format (Arabic-Indic digits) is used. This setting is effective only when the locale is Arabic, otherwise it's ignored. | National | digit-substitution |
| Disable variable header support | When set to true, prevents variable header support. Variable header support automatically extends the size of the header to accommodate the contents. | false | fo-prevent-variable-header |
| Enable multithreading | If you have a multiprocessor machine or a machine with a dual-core single processor, you might achieve faster document generation by setting this option to True. | false | fo-multi-threads |

| Property Name | Description | Default | Configuration Name |
|---|--|---------|--------------------------|
| Disable external references | When set to true, disallows importing of secondary files such as subtemplates or other XML documents during XSL processing and XML parsing. This increases the security of the system. Set this to "false" if the report or template calls external files. | true | xdk-secure-io-mode |
| FO Parsing Buffer Size | Specifies the size of the buffer for the FO Processor. When the buffer is full, the elements from the buffer are rendered in the report. Reports with large tables or pivot tables that require complex formatting and calculations may require a larger buffer to properly render those objects in the report. Increase the size of the buffer at the report level for these reports. Note that increasing this value affects the memory consumption of the system. | 1000000 | fo-chunk-size |
| FO extended linebreaking | When set to true, punctuation, hyphenation, and international text are handled properly when line breaking is necessary. | true | fo-extended-linebreaking |
| Enable XSLT runtime optimization for sub-template | Provides an option to perform XSL import in FOProcessor before passing only one XSL to XDK for further processing. This allows xslt-optimization to be applied to the entire main XSL template which already includes all its subtemplates. The default is true. If you call the FOProcessor directly, the default is false. | true | xslt-do-import |
| Report Timezone | Valid values: User or JVM. When set to User, Publisher uses the User-level Report Time Zone setting for reports. The User Report Time Zone is set in the user's Account Settings. When set to JVM, Publisher uses the server JVM timezone setting for all users' reports. All reports therefore display the same time regardless of individual user settings. This setting can be overridden at the report level. | User | fo-report-timezone |

| Property Name | Description | Default | Configuration Name |
|--------------------------|--|---------|--------------------------|
| PDF Bidi Unicode Version | Specifies the Unicode version (3.0 or 4.1) used to display the BIDI strings in the PDF output. | 4.1 | pdf-bidi-unicode-version |

RTF Template Properties

You configure RTF templates with various settings.

The properties described in the following table can be set to govern RTF templates.

| Property Name | Description | Default | Internal Name |
|------------------------|---|---------|----------------------------|
| Extract attribute sets | <p>The RTF processor automatically extracts attribute sets within the generated XSL-FO. The extracted sets are placed in an extra FO block, which can be referenced. This improves processing performance and reduces file size. Valid values are:</p> <ul style="list-style-type: none"> • Enable - extract attribute sets for all templates and subtemplates • Auto - extract attribute sets for templates, but not subtemplates • Disable - do not extract attribute sets | Auto | rtf-extract-attribute-sets |
| Enable XPath rewriting | When converting an RTF template to XSL-FO, the RTF processor automatically rewrites the XML tag names to represent the full XPath notations. Set this property to "false" to disable this feature. | true | rtf-rewrite-path |

| Property Name | Description | Default | Internal Name |
|------------------------------|--|----------------------------|--------------------|
| Characters used for checkbox | <p>The default PDF output font doesn't include a glyph to represent a checkbox. If the template contains a checkbox, use this property to define a Unicode font for the representation of checkboxes in the PDF output. You must define the Unicode font number for the "checked" state and the Unicode font number for the "unchecked" state using the following syntax:</p> <pre>fontname;<unicode font number for true value's glyph >;<unicode font number for false value's glyph></pre> <p>Example: Albany WT J;9746;9747/A Note that the font that you specify must be made available at runtime.</p> | Albany WT J;9746;9747/A | rtf-checkbox-glyph |

XPT Template Properties

Configure XPT templates by setting the properties described in the table below.

| Property Name | Description | Default |
|---|--|---------|
| XPT Scalable Mode | <p>When you set this property to true, the scheduled reports that use the XPT template and include a large amount of data run without memory issues. The first 100,000 rows of data in the report are stored in memory and the remaining rows are stored in the file system.</p> <p>When you set this property to false, the scheduled reports that use XPT template are processed in-memory. Set this property to false for reports that contain less data.</p> | False |
| Enable Asynchronous Mode for Interactive Output | <p>When you set this property to true, interactive reports that use the XPT template make asynchronous calls to Oracle WebLogic Server.</p> <p>When you set this property to false, interactive reports that use the XPT template make synchronous calls to Oracle WebLogic Server. Oracle WebLogic Server limits the number of synchronous calls. Any calls that are stuck expire in 600 seconds.</p> | True |

PDF Template Properties

The properties described in the table below can be set to govern PDF templates.

| Property Name | Description | Default | Internal Name |
|---|---|---------|--------------------------|
| Remove PDF fields from output | Specify "true" to remove PDF fields from the output. When PDF fields are removed, data entered in the fields cannot be extracted. For repeating fields, the value of this property is set to true by default and cannot be changed to false. See Set Fields as Updatable or Read Only. | false | remove-pdf-fields |
| Set all fields as read only in output | By default, Publisher sets all fields in the output PDF of a PDF template to be read only. If you want to set all fields to be updatable, set this property to "false". For more information, see Set Fields as Updatable or Read Only. | true | all-field-readonly |
| Maintain each field's read only setting | Set this property to "true" if you want to maintain the "Read Only" setting of each field as defined in the PDF template. This property overrides the settings of "Set all fields as read only in output." For more information, see Set Fields as Updatable or Read Only. | false | all-fields-readonly-asis |

Excel Template Properties

Configure Excel templates by setting the properties described in the table below.

| Property Name | Description | Default |
|----------------------|--|---------|
| Enable Scalable Mode | When set to true, large reports that use Excel template run without out of memory issues. Data overflows automatically into multiple sheets if a group of data in a sheet exceeds 65000 rows. This overcomes the Microsoft Excel limitation of 65000 rows per sheet. When set to false, large reports that use Excel template can cause out of memory issues. | false |

CSV Output Properties

Use the properties described in this table to control comma-separated value output.

| Property Name | Description | Default |
|---|--|---------|
| CSV delimiter | Specifies the character used to delimit the data in comma-separated value output. Other options are: Semicolon (;), Tab (\t) and Pipe (). | |
| Remove leading and trailing white space | Specify "True" to remove leading and trailing white space between data elements and the delimiter. | false |

Excel Output Properties

You can set specific properties to control Excel output.

| Property Name | Description | Default |
|---------------------------|---|--------------------------|
| Show grid lines | Set to true to show the Excel table grid lines in the report output. | false |
| Page break as a new sheet | When set to "True" a page break specified in the report template generates a new sheet in the Excel workbook. | true |
| Minimum column width | When the column width is less than the specified minimum and it contains no data, the column is merged with the preceding column. The value must be set in points. The valid range for this property is 0.5 to 20 points. | 3 (in points, 0.04 inch) |
| Minimum row height | When the row height is less than the specified minimum and it contains no data, the row is removed. The value must be set in points. The valid range for this property is 0.001 to 5 points. | 1 (in points, 0.01 inch) |

| Property Name | Description | Default |
|--|--|---------|
| Keep values in same column | Set this property to True to minimize column merging. Column width is set based on column contents using the values supplied in the Table Auto Layout property. Output may not appear as neatly laid out as when using the original layout algorithm. | False |
| Table Auto Layout | <p>Specify a conversion ratio in points and a maximum length in points, for example 6.5,150. See example.</p> <p>For this property to take effect, the property "Keep values in same column" must be set to True.</p> <p>This property expands the table column width to fit the contents. The column width is expanded based on the character count and conversion ratio up to the maximum specification.</p> <p>Example: Assume a report with two columns of Excel data -- Column 1 contains a text string that's 18 characters and Column 2 is 30 characters long. When the value of this property is set to 6.5,150, the following calculations are performed:</p> <p>Column 1 is 18 characters: Apply the calculation: $18 * 6.5\text{pts} = 117\text{pts}$ The column in the Excel output will be 117 pts wide.</p> <p>Column 2 is 30 characters: Apply the calculation: $30 * 6.5\text{pts} = 195\text{pts}$ Because 195 pts is greater than the specified maximum of 150, Column 2 will be 150 pts wide in the Excel output.</p> | N/A |
| Maximum allowable nested table row count | <p>Specify the maximum allowable row count for a nested table. Allowed values are 15000 to 999,999.</p> <p>During report processing, nested inner table rows cannot be flushed to the XLSX writer, therefore they stay in-memory, increasing memory consumption. Set this limit to avoid out-of-memory exceptions. When this limit is reached for the size of the inner table, generation is terminated. The incomplete XLSX output file is returned.</p> | 20,000 |
| Open password | <p>Use this property to specify the password that report users must provide to open any XLSX output file.</p> <p>Configuration name: <code>xlsx-open-password</code></p> | NA |

EText Output Properties

The table below describes the properties that control EText output files.

| Property Name | Description | Default |
|-------------------------|--|---------|
| Add UTF-8 BOM Signature | When set to true, the Etext output is in UTF-8 Unicode with BOM format. | false |
| Enable bigdecimal | When set to true, you enable high-precision numeric calculation of the Etext output. | false |

All Outputs Properties

The properties in the table below apply to all outputs.

| Property Name | Description | Default |
|---------------------------------|--|---------|
| Use 11.1.1.5 compatibility mode | Reserved. Do not update unless instructed by Oracle. | false |

Define Font Mappings

You can map base fonts in RTF or PDF templates to the target fonts to be used in the published document. Font mapping is performed only for PDF PowerPoint output.

There're two types of font mappings:

- RTF Templates - for mapping fonts from RTF templates and XSL-FO templates to PDF and PowerPoint output fonts
- PDF Templates - for mapping fonts from PDF templates to different PDF output fonts.

Make Fonts Available to Publisher

Publisher provides a set of Type1 fonts and a set of TrueType fonts.

You can select any of the predefined fonts as a target font with no additional setup required.

The predefined fonts are located in `<oracle_home>/oracle_common/internal/fonts`. If you want to map to another font, then you must place the font in this directory to make it available to Publisher at runtime. If the environment is clustered, then you must place the font on every server.

Set Font Mapping at the Site Level or Report Level

A font mapping can be defined at the site level or the report level.

Use the following settings to set the font mapping:

- To set a mapping at the site level, select the **Font Mappings** link from the Admin page.
- To set a mapping at the report level, select the **Configuration** link for the report, then select the Font Mappings tab. These settings apply to the selected report only.

The report-level settings take precedence over the site-level settings.

Create a Font Mapping

From the Admin page, under **Runtime Configuration**, select **Font Mappings**.

To create a Font Mapping:

1. Under RTF Templates or PDF Templates, select **Add Font Mapping**.
2. Enter the following on the Add Font Mapping page:
 - Base Font - enter the font family that is mapped to a new font. Example: Arial
 - Select the **Style**: Normal or Italic (Not applicable to PDF Template font mappings)
 - Select the **Weight**: Normal or Bold (Not applicable to PDF Template font mappings)
 - Select the **Target Font Type**: Type 1 or TrueType
 - Enter the Target Font

If you selected TrueType, then you can enter a specific numbered font in the collection. Enter the TrueType Collection (TTC) Number of the desired font.

For a list of the predefined fonts, see [Publisher's Predefined Fonts](#).

Publisher's Predefined Fonts

These Type1 fonts are built-in to Adobe Acrobat and Publisher provides a mapping for these fonts by default. You can select any of these fonts as a target font with no additional setup required.

The Type1 fonts are listed in the following table:

| Number | Font Family | Style | Weight | Font Name |
|--------|-------------|--------|--------|-----------------------|
| 1 | serif | normal | normal | Time-Roman |
| 1 | serif | normal | bold | Times-Bold |
| 1 | serif | italic | normal | Times-Italic |
| 1 | serif | italic | bold | Times-BoldItalic |
| 2 | sans-serif | normal | normal | Helvetica |
| 2 | sans-serif | normal | bold | Helvetica-Bold |
| 2 | sans-serif | italic | normal | Helvetica-Oblique |
| 2 | sans-serif | italic | bold | Helvetica-BoldOblique |
| 3 | monospace | normal | normal | Courier |

| Number | Font Family | Style | Weight | Font Name |
|--------|--------------|--------|--------|-----------------------|
| 3 | monospace | normal | bold | Courier-Bold |
| 3 | monospace | italic | normal | Courier-Oblique |
| 3 | monospace | italic | bold | Courier-BoldOblique |
| 4 | Courier | normal | normal | Courier |
| 4 | Courier | normal | bold | Courier-Bold |
| 4 | Courier | italic | normal | Courier-Oblique |
| 4 | Courier | italic | bold | Courier-BoldOblique |
| 5 | Helvetica | normal | normal | Helvetica |
| 5 | Helvetica | normal | bold | Helvetica-Bold |
| 5 | Helvetica | italic | normal | Helvetica-Oblique |
| 5 | Helvetica | italic | bold | Helvetica-BoldOblique |
| 6 | Times | normal | normal | Times |
| 6 | Times | normal | bold | Times-Bold |
| 6 | Times | italic | normal | Times-Italic |
| 6 | Times | italic | bold | Times-BoldItalic |
| 7 | Symbol | normal | normal | Symbol |
| 8 | ZapfDingbats | normal | normal | ZapfDingbats |

The TrueType fonts are listed in the following table. All TrueType fonts are embedded into the PDF.

| Number | Font Family Name | Style | Weight | Actual Font | Actual Font Type |
|--------|----------------------|--------|--------|--------------|---|
| 1 | Albany WT | normal | normal | ALBANYWT.ttf | TrueType (Latin1 only) |
| 2 | Albany WT J | normal | normal | ALBANWTJ.ttf | TrueType (Japanese flavor) |
| 3 | Albany WT K | normal | normal | ALBANWTK.ttf | TrueType (Korean flavor) |
| 4 | Albany WT SC | normal | normal | ALBANWTS.ttf | TrueType (Simplified Chinese flavor) |
| 5 | Albany WT TC | normal | normal | ALBANWTT.ttf | TrueType (Traditional Chinese flavor) |
| 6 | Andale Duospace WT | normal | normal | ADUO.ttf | TrueType (Latin1 only, Fixed width) |
| 6 | Andale Duospace WT | bold | bold | ADUOB.ttf | TrueType (Latin1 only, Fixed width) |
| 7 | Andale Duospace WT J | normal | normal | ADUOJ.ttf | TrueType (Japanese flavor, Fixed width) |
| 7 | Andale Duospace WT J | bold | bold | ADUOJB.ttf | TrueType (Japanese flavor, Fixed width) |
| 8 | Andale Duospace WT K | normal | normal | ADUOK.ttf | TrueType (Korean flavor, Fixed width) |
| 8 | Andale Duospace WT K | bold | bold | ADUOKB.ttf | TrueType (Korean flavor, Fixed width) |

| Number | Font Family Name | Style | Weight | Actual Font | Actual Font Type |
|--------|-----------------------|--------|--------|-------------|--|
| 9 | Andale Duospace WT SC | normal | normal | ADUOSC.ttf | TrueType (Simplified Chinese flavor, Fixed width) |
| 9 | Andale Duospace WT SC | bold | bold | ADUOSCB.ttf | TrueType (Simplified Chinese flavor, Fixed width) |
| 10 | Andale Duospace WT TC | normal | normal | ADUOTC.ttf | TrueType (Traditional Chinese flavor, Fixed width) |
| 10 | Andale Duospace WT TC | bold | bold | ADUOTCB.ttf | TrueType (Traditional Chinese flavor, Fixed width) |

Included Barcode Fonts

The table lists the barcode fonts included in Publisher.

| Font File | Supported Algorithm |
|------------|----------------------------------|
| 128R00.TTF | code128a, code128b, and code128c |
| B39R00.TTF | code39, code39mod43 |
| UPCR00.TTF | upca, upce |

Part III

Create Style Templates and Subtemplates

This part describes how to create and implement style templates and subtemplates.

Topics:

- [Create and Implement Style Templates](#)
- [Understand Subtemplates](#)
- [Design RTF Subtemplates](#)
- [Design XSL Subtemplates](#)

19

Create and Implement Style Templates

This topic describes how to create and implement style templates. A style template is an RTF template that contains style information that can be applied to other RTF layouts to achieve a consistent look and feel across your enterprise reports.

Topics:

- [Understand Style Templates](#)
- [Create a Style Template RTF File](#)
- [Upload a Style Template File to the Catalog](#)
- [Assign a Style Template to a Report Layout](#)
- [Update a Style Template](#)
- [Add Translations to a Style Template Definition](#)

Understand Style Templates

A style template is an RTF template that contains style information that can be applied to RTF layouts.

The style information in the style template is applied to RTF layouts at runtime to achieve a consistent look and feel across your enterprise reports. You associate a style template to a report layout in the report definition. Using a style template has the following benefits:

- Enables the same look and feel across your enterprise reports
- Enables same header and footer content, such as company logos, headings, and page numbering
- Simplifies changing the elements and styles across all reports

About Styles Defined in the Style Template

Use style template to define paragraph and heading styles, table styles, and header and footer content.

The styles of the following elements can be defined in the style template:

- Paragraph and Heading Styles
You can create a paragraph style in a style template. When this same named style is used in a report layout, the report layout inherits the following from the style template definition: font family, font size, font weight (normal, bold), font style (normal, italic), font color, and text decoration (underline, overline, or strike through).
- Table Styles

Following are some of the style elements inherited from the table style definition: font style, border style, gridline definition, shading, and text alignment.

- **Header and Footer Content**

The header and footer regions of the style template are applied to the report layout. This includes images, dates, page numbers, and any other text-based content. If the report layout also includes header and footer content, then it's overwritten.

Style Template Process

Following this process for creating style templates helps ensure consistency across documents.

Design Time

For the Style Template:

1. Open Microsoft Word.
2. Define named styles for paragraphs, tables, headings, and static header and footer content. This is the style template.
3. Save this document as a .rtf file.
4. To ensure that you do not lose custom styles in Microsoft Word, also save the document as a Word Template file (.dot) or save the styles to the Normal.dot file. This file can be shared with other report designers.
5. Upload the RTF style template file to the catalog.

For the layout template using the style template:

1. In the RTF template, use the same named styles for paragraph and table elements that you want to be inherited from the style template.
2. Open the report in BI Publisher's Report Editor and select the style template to associate to the report. Then enable the style template for the specific report layout.

Runtime

When you run the report with the selected layout, Publisher applies the styles, header, and footer from the style template.

Create a Style Template RTF File

These sections describe how to define the style types in the Microsoft Word document.

For more complete information see the Microsoft Word documentation.

Define Styles for Paragraphs and Headings

Use a paragraph style to define formatting such as font type, size, color, text positioning and spacing. A paragraph style can be applied to one or more paragraphs. Use a paragraph style to format headings and titles in the report as well.

To define a paragraph style type:

1. In the Microsoft Word document, from the **Format** menu, select **Styles and Formatting**.
2. From the Styles and Formatting task pane, select **New Style**.
3. In the New Style dialog, enter a name for the style. Select style type: **Paragraph**. Format the style using the options presented in the dialog. To see additional paragraph options (such as font color and text effects), click **Format**.
4. When finished, click **OK** and the new style is displayed in the list of available formats in the Styles and Formatting task pane.
5. Select the new style and make an entry in the style template to display the style.

To apply the paragraph style type in the document:

1. Position the cursor within the paragraph (or text) to which you want to apply the style.
2. Select the style from the list of available formats in the Styles and Formatting task pane. The style is applied to the paragraph.

To modify an existing style type:

1. In the Microsoft Word document, from the **Format** menu, select **Styles and Formatting**.
2. From the Styles and Formatting task pane, select and right-click the style to modify.
3. From the menu, select **Modify**.

To apply heading styles in the document:

1. Position the cursor on the text to which you want to apply the heading style.
2. Select the heading style from the list of available formats in the Styles and Formatting task pane. The selected heading styles are applied to the report output. For example, in the HTML report, Heading 1 through Heading 6 styles use H1, H2, H3, H4, H5, and H6 tags respectively.

Define Styles for Tables

Follow these steps to define styles for tables.

To define a table style type:

1. In the Microsoft Word document, from the **Format** menu, select **Styles and Formatting**.
2. From the Styles and Formatting task pane, select **New Style**.
3. In the New Style dialog, enter a name for the style. Choose style type: **Table**. Format the style using the options presented in the dialog. To see additional table options (such as Table Properties and Borders and Shading), click **Format**.
4. When finished, click **OK** and the new style is displayed in the list of available formats in the Styles and Formatting task pane.
5. Choose the new style and make an entry in the style template to display the style.

To apply the table style type in the document:

1. Position the cursor within the table to which you want to apply the style.

2. Select the table style from list of available formats in the Styles and Formatting task pane. The style is applied to the table.

Define a Header and Footer

You can define a header and footer in the style template. The contents and sizing of the header and footer in the style template are applied to the report layouts.

If a header and footer have been defined in the report layout, then they're overwritten. The header and footer from the style template are applied.

To define a header and footer:

1. In the Microsoft Word document, from the **View** menu, select **Header and Footer**.
2. Enter header and footer content. This can include a logo or image file, static text, current date and time stamps, page numbers, or other content supported by Microsoft Word.


Upload a Style Template File to the Catalog

You can place a style template in any folder in the catalog to which you have access.

Your organization may have a designated folder for style templates.

To upload a style template file:

1. On the global header click **New** and then click **Style Template**. This launches an untitled Style Template properties page.
2. From the **Templates** region, click the **Upload** toolbar button.
3. In the **Upload Template File** dialog, click **Browse** to select the Template File. Select **rtf** as the **Type**, and select the appropriate **Locale**.



Sales Style Template - Style Template

Description

▲ **Templates**

Click the Upload icon to upload a template file. Only one template file can be uploaded for each locale.

| Default | Locale |
|-------------------------------------|-------------------------|
| <input checked="" type="checkbox"/> | English (United States) |

▲ **Translations**

Click Extract Translation to generate an XLIFF file type from the selected Base Template file.

Base Template

| Locale |
|---------------------------|
| No Translations available |

The style template file is displayed in the Templates region as the locale name that you selected (for example: English-United States).

4. Click **Save**.
5. In the Save As dialog choose the catalog folder in which to save the style template. Enter the **Name** and click **Save**.

You may only upload one RTF file per locale to a Style Template definition. If you upload additional template files to this Style Template, each file is automatically named as the locale regardless of the name that you give the file before upload.

6. If you are uploading multiple localized files, then select the file that is to be used as the default.

Assign a Style Template to a Report Layout

Follow these steps to assign a style template to a report layout.

1. Navigate to the report in the catalog and click **Edit** to open the report editor.
2. From the default thumbnail view, select **View a List**. In the Layout region, click the **Choose** icon to search for and select the style template from the Publisher catalog.
3. For the layout templates that you want to use the style template, select the **Apply Style Template** box for the template. Note that the box is only enabled for RTF templates.

The following figure highlights the actions required to enable a style template in the Report Editor.

The screenshot shows the 'Company Sales Report' interface. In the 'Layout' section, there is a table of style templates. The 'Apply Style Template' column for the 'Product Sales Details' row is highlighted with a red box, and a mouse cursor is clicking the checkbox.

| Name | Template File | Type | Output Formats | Default Format | Default Layout | Apply Style Template | Active | View Online | Locale |
|-----------------------|-------------------|------|--------------------|----------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------|
| Sales by Company Org. | Company Sales.xpt | xpt | Interactive;HTML;P | Interactive | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | English (United States) |
| Sales by Office | Office Sales.xpt | xpt | Interactive;HTML;P | Interactive | <input type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | English (United States) |
| Product Sales Details | Product Sales.rtf | rtf | HTML;PDF;RTF;Ex | PDF | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | English (United States) |

Update a Style Template

You can alter a style template after it has been saved.

To update or edit a saved style template:

1. Navigate to the file in the catalog.
2. Click **Edit** to open the Style Template properties page.
3. Delete the existing file.
4. Upload the edited file, choosing the same locale.

Add Translations to a Style Template Definition

Style templates offer the same support for translations as RTF template files.

You can upload multiple translated RTF files under a single Style Template definition and assign the appropriate locale.



Or you can generate an XLIFF (.xlf) file of the translatable strings, translate the strings, and upload the translated file. These are displayed in the **Translations** region, as shown in the following figure:

Oracle Styles Template - Style Template

Description

▲ **Templates**

Click the Upload icon to upload a template file. Only one template file can be uploaded for each locale.



 

| Default | Locale |
|-------------------------------------|-------------------------|
| <input checked="" type="checkbox"/> | English (United States) |
| <input type="checkbox"/> | Greek (Greece) |

▲ **Translations**

Click Extract Translation to generate an XLIFF file type from the selected Base Template file.

Base Template

| Locale |
|------------------|
| French (France) |
| German (Germany) |

At runtime, the appropriate style template is applied based on the user's account **Preference** setting for Report Locale for reports viewed online; or, for scheduled reports, based on the user's selection for Report Locale for the scheduled report.

The XLIFF files for style templates can be generated individually, then translated, and uploaded individually. Or, if you perform a catalog translation that includes the style template folders, the strings from the style template files are extracted and included in the larger catalog translation file. When the catalog translation file is uploaded to Publisher, the appropriate translations from the catalog file are displayed in the **Translations** region of the Style Template definition.

For more information on translations, see [Translation Support Overview and Concepts](#).

Understand Subtemplates

This topic describes concepts for using subtemplates. A subtemplate is a piece of formatting functionality that can be defined once and used multiple times within a single layout template or across multiple layout template files.

Topics:

- [What is a Subtemplate?](#)
- [Supported Locations for Subtemplates](#)
- [Test Subtemplates from the Desktop](#)
- [Upload a Subtemplate](#)
- [Call a Subtemplate from an External Source](#)

For information on designing an RTF subtemplate, see [Design RTF Subtemplates](#). For information on designing an XSL subtemplate, see [Design XSL Subtemplates](#).

What is a Subtemplate?

A subtemplate is a piece of formatting functionality that can be defined once and used multiple times within a single layout template or across multiple layout template files.

This piece of formatting can be in an RTF file format or an XSL file format. RTF subtemplates are easy to design as you can use Microsoft Word native features. XSL subtemplates can be used for complex layout and data requirements.

Some common uses for subtemplates include:

- Reusing a common layout or component (such as a header, footer, or address block)
- Handling parameterized layouts
- Handling dynamic or conditional layouts
- Handling lengthy calculations or reusing formulae

About RTF Subtemplates

An RTF subtemplate is an RTF file that consists of one or more `<?template:??>` definitions, each containing a block of formatting or commands.

This RTF file, when uploaded to Publisher as a subtemplate object in the Catalog, can be called from within another RTF Template.

About XSL Subtemplates

An XSL subtemplate is an XSL file that contains formatting or processing commands in XSL for the Publisher formatting engine to execute. Use an XSL template to include complex calculations or formatting instructions not supported by the RTF standard.

This XSL file, when uploaded to Publisher as a Subtemplate object in the **Catalog**, can be called from within an RTF Template.

Supported Locations for Subtemplates

It's recommended that you upload subtemplates to the Publisher catalog.

The catalog is the most secure location.

For compatibility with older versions of Publisher, you can also call a subtemplate that resides in a file on the local server, or on a different server (that can be accessed by HTTP protocol). Using one of these methods requires specific import syntax and server settings to allow the communication.

Test Subtemplates from the Desktop

If you have the Publisher Template Builder installed, you can preview the template and subtemplate combination before uploading them to the Publisher catalog.

To test from your local environment, you must alter the import template syntax to enable the Publisher processor to locate the subtemplate file on a local directory. To test, enter the import template syntax as follows:

```
<?import:file:{local_template_path}?>
```

For example:

```
<?import:file:C:///Template_Directory/subtemplate_file.rtf?>
```

or for an XSL subtemplate file:

```
<?import:file:C:///Template_Directory/subtemplate_file.xsl?>
```

You can then select the **Preview** option in the Template Builder and the Publisher processor can locate the subtemplate and render it from your local environment.

Note that before you upload the primary template to the Publisher catalog, you must change the import syntax to point to the appropriate location in the catalog.

Upload a Subtemplate

You can upload one or more sub templates for use with Publisher.

To upload a subtemplate file:

1. On the global header click **New** and then click **Sub Template**. This launches an untitled Sub Template page.
2. In the **Templates** region, click **Upload**.
3. In the Upload Template File dialog, select the subtemplate file for upload.
 - **Type**: Select rtf for RTF subtemplate files or xsl for XSL subtemplate files.
 - **Locale**: Select the appropriate locale for the subtemplate file.
4. Click **Upload**.

The subtemplate file is displayed in the **Templates** region as the locale name that you selected (for example: English).

5. Click **Save**. In the Save As dialog choose the catalog folder in which to save the Sub Template. Enter the **Name** and click **Save**.
6. (RTF Sub Templates only) If you are uploading multiple localized files, then select the file that is to be used as the default. For more information on localization of template files, see [Add Translations to an RTF Subtemplate](#).

You may upload only one RTF file per locale to a Sub Template definition. If you upload additional template files to this Sub Template, each file is automatically named as the locale regardless of the name that you give the file before upload.

Translations are not supported for XSL Sub Templates.

Note that the Sub Template object is saved with the extension ".xsb". You use the Name that you choose here with the .xsb extension when you import the Sub Template object (for example: MySubtemplate.xsb).

Call a Subtemplate from an External Source

This section describes how to call a subtemplate that resides outside the catalog.

Note:

These instructions are provided for backward compatibility only. It's recommended that you place subtemplates in the catalog.

Note that localization isn't supported for subtemplates that are maintained outside the catalog.

Import a Subtemplate Outside the Catalog over HTTP or FTP

Use a standard protocol, such as http or ftp and enter the import statement as shown here.

```
<?import:http://myhost:8080/subtemplate.rtf?>
```

Import Subtemplates Outside the Catalog on the Same Server

If the subtemplate is located on the server, but not in the Publisher catalog, then enter this.

```
<?import:file://{template_path}?>
```

where

template_path is the path to the subtemplate file on the server

For example:

```
<?import:file://c:/Folder/mySubtemplate.rtf?>
```

Required Settings To Run Sub Templates Stored Outside the Catalog

To run sub templates outside the catalog you must configure the disable external references property.

Using sub templates requires the following FO processing configuration property setting for the report:

Disable external references: Must be set to False

21

Design RTF Subtemplates

This topic describes how to use RTF subtemplates to create and reuse functionality across multiple reports.

Topics:


- [Understand RTF Subtemplates](#)
- [Process Overview for Creating and Implementing RTF Sub Templates](#)
- [Create an RTF Subtemplate File](#)
- [Call a Subtemplate from a Main Template](#)
- [When to Use RTF Subtemplates](#)
- [Add Translations to an RTF Subtemplate](#)

Understand RTF Subtemplates

An RTF subtemplate is an RTF file that consists of one or more `<?template:?>` definitions, each containing a block of formatting or commands.

This RTF file, when uploaded to Publisher as a Sub Template object in the Catalog, can be called from other RTF templates.

The following graphic illustrates the composition of an RTF Sub Template.



Process Overview for Creating and Implementing RTF Sub Templates

You must follow this process to work with RTF sub templates.

Using a sub template consists of the following steps (described in the following sections):

1. Create the RTF file that contains the common components or processing instructions that you want to include in other templates.
2. Create the calling or "main" layout and include the following two commands:
 - import - to import the sub template file to the main layout template.
 - call-template - to execute or render the sub template contents in the main layout.
3. Test the template and sub template.

 **Tip:**

You can use the Publisher Desktop Template Viewer to test the main layout plus sub template before loading them to the catalog. To do so, you must alter the import template syntax to point to the location of the sub template in the local environment. See [Test Subtemplates from the Desktop](#).

4. Upload the main template to the report definition and create the Sub Template object in the catalog. See [Upload a Subtemplate](#).

Create an RTF Subtemplate File

You can create an RTF subtemplate file.

To create an RTF subtemplate file:


1. Enter the components or instructions in an RTF file.
2. Define the instructions as a subtemplate by enclosing the contents in the tags as shown below.

```
<?template:template_name?>  
    ..subtemplate contents...  
<?end template?>
```

where `template_name` is the name you choose for the subtemplate. In a single RTF file, you can have multiple entries, to mark different subtemplates or segments to include in other files.

```
<?template:template_name?>  
<?end template?>
```

For example, the following figure shows a sample RTF file that contains two subtemplates, one named commonHeader and one named commonFooter.

| | | |
|--|--|-----------------------------|
| <?template:commonHeader?>  | | Report Date: 17 August 2009 |
| <?end template?> | | |
| <?template:commonFooter?> Oracle Corporation 600 Oracle Parkway Redwood Shores CA 94065 | | Page 1 of 1 |
| <?end template?> | | |

Call a Subtemplate from a Main Template

There're two entries that you must make to call a subtemplate from a main template.

To implement the subtemplate in a main template, you must make two entries in the main template:

First, import the subtemplate file to the main template. The import syntax tells the Publisher engine where to find the Sub Template in the catalog.

Second, enter a call command to render the contents of the subtemplate at the position desired.

Import the Subtemplate to the Main Template

Enter the import command anywhere in the main template prior to the call template command.

If you do not require a locale, enter the following:

```
<?import:xdoxsl:///path to subtemplate.xsb?>
```

where

path to subtemplate.xsb is the path to the subtemplate .xsb object in the catalog.

For example:

```
<?import:xdoxsl:///Executive/HR_Reports/mySubtemplate.xsb?>
```

If the subtemplate resides in a personal folder under My Folders, the command to import the subtemplate is:

```
<?import:xdoxsl:///~username/path to subtemplate.xsb?>
```

where *username* is your user name.

For example, if user *myuser* uploads a subtemplate called *Template1* to a folder called *Subtemplates* under *My Folders*, the correct import statement is:

```
<?import:xdoxsl:///~myuser/Subtemplates/Template1.xsb?>
```

Call the Subtemplate to Render Its Contents

You can also enter a call command to render the contents of the subtemplate at the position that you desire.


- In the position in the main template where you want the subtemplate to render, enter the call-template command, as follows:

```
<?call-template:template_name?>
```

where

template_name is the name you assigned to the contents in the template declaration statement within the subtemplate file (that is, the `<?template:template_name?>` statement).

The following figure illustrates the entries required in a main template:



Import a Localized Subtemplate

To designate the locale of the imported subtemplate, append the locale to the import statement as shown here.

```
<?import:xdoxsl:///{path to subtemplate.xsb}?loc={locale_name}?>
```

where

path to subtemplate.xsb is the path to the subtemplate .xsb object in the catalog

and

locale_name is the language-territory combination which comprises the locale. The locale designation is optional.

For example:

```
<?import:xdoxsl:///Executive/HR_Reports/mySubtemplate.xsb?loc=en-US?>
```

Note that you can also use `$_XDOLOCALE` to import a localized subtemplate based on the runtime user locale. For example:

```
<?import:xdoxsl:///Executive/HR_Reports/mySubtemplate.xsb?loc=${_XDOLOCALE}?>
```

Example

In this example, your company address is a fixed string that is displayed in all your templates. Rather than reproduce the string in all the templates, you can place it in one subtemplate and reference it from all the others.

To place the string in a subtemplate and reference it:

1. In an RTF file enter the following template declaration:

```
<?template:MyAddress?>
My Company
500 Main Street
Any City, CA 98765
<?end template?>
```

2. Create a Sub Template in the catalog in the following location: Customer Reports/ Templates.
3. Upload this file to the Sub Template and save it as "Common Components" (Publisher assigns the object the .xsb extension).
4. In the main template, enter the following import statement in a form field or directly in the template:

```
<?import:xdoxsl:///Customer Reports/Templates/Common Components.xsb?>
```

5. In the main template, in the location you want the address to appear, enter:

```
<?call-template:MyAddress?>
```

At runtime the contents of the MyAddress subtemplate are fetched and rendered in the layout of the main template.

This functionality isn't limited to just strings, you can insert any valid RTF template functionality in a subtemplate, and even pass parameters from one to the other. For examples, see [When to Use RTF Subtemplates](#).

When to Use RTF Subtemplates

RTF subtemplates can be used in various scenarios.

Following are several common use-cases for RTF subtemplates.

Reuse a Common Layout

Frequently multiple reports require the same header and footer content.

By using an RTF subtemplate to contain this content, any global changes are simplified and require updating only the subtemplate instead of each individual layout.

Conditionally Display a Layout Based on a Value in the Data

Subtemplates can also be used to apply conditional layouts based on a value in the report data.

By using the RTF template "choose" command, you can instruct Publisher to apply a different `<?template?>` defined in the subtemplate file.

You cannot conditionalize the import statement for the subtemplate file. Instead, you import one subtemplate file and conditionalize the call statement. You define the multiple `<?template?>` options in the single subtemplate file.

Example

Assume you have a report that is sent to customers in India and the United States. You must apply a different address layout depending on the country code (COUNTRY_CODE) supplied in the data. This example uses the RTF templates `if` statement functionality to call the subtemplate with the appropriate address format.

The subtemplate file may look as follows:

```
<?template:US_Address?>
  <?US_Address_Field1?>
  <?US_Address_Field2?>
  <?US_Address_Field3?>
<?end template?>

<?template:IN_Address?>
  <?IN_Address_Field1?>
  <?IN_Address_Field2?>
  <?IN_Address_Field3?>
<?end template?>
```

To call the sub template with the appropriate address format:

1. Create a Sub Template in the catalog in the following location:
Customers/Invoice Reports
Upload the RTF file and save the Sub Template as Addresses.
2. In the main template enter the following to import the Sub Template:

```
<?import:xdoxsl:///Customers/Invoice Reports/Addresses.xsb?>
```


3. In the location where you want the address to display, enter the following:

```
<?if:COUNTRY_CODE='USA'?>
    <?call:US_Address?>
<?end if?>
<?if:COUNTRY_CODE='IN'?>
    <?call:IN_Address?>
<?end if?>
```

When the report is run, the address format is properly applied, depending on the value of COUNTRY_CODE in the data.

Conditionally Display a Layout Based on a Parameter Value

This example illustrates how to display a different layout based on a user parameter value or a selection from a list of values. The parameter can be passed to the RTF template and used to call a different `<?template?>` within the subtemplate file based on the value.

You cannot conditionalize the import statement for the subtemplate file.

Example

Assume in the report data model that you've defined a parameter named DeptName. Set up this parameter as type Menu and associate it to a list of values, enabling your user to make a selection from the list when he views the report in the Report Viewer (or when he schedules the report).

In the RTF main layout template, enter the following command to capture the value chosen by the user:

```
<?param@begin:DeptName?>
```

To display the layout based on this user selection, you can use an IF statement or a CHOOSE statement to evaluate the parameter value and call the associated subtemplate.

Use the CHOOSE statement when there're many conditional tests and a default action is expected for the rest of the values. For example, the Accounting, Sales, and Marketing departments each require a different layout. All other departments can use a default layout.

To display the layout:

1. Create an RTF file and include the following template declarations:

```
<?template:tAccounting?>
    - - - Specific Accounting Layout here - - -
<?end template?>

<?template:tSales?>
    - - - Specific Sales Layout here - - -
<?end template?>

<?template:tMark?>
```

```

    - - - Specific Marketing Layout here - -
<?end template?>

<?template:tDefault?>
    - - - Default Layout here - - -
<?end template?>

```

2. Create a Sub Template in the catalog in the following location:

Shared Folders/Executive/Department Expenses

Upload the RTF file and save the Sub Template as DeptSubtemps.

3. In the main RTF template, include the following commands:

```

<?import:xdoxsl:///Executive/Department Expenses/DeptSubtemps.xsb?
loc=en-US?>

<?param@begin:DeptName?>

<?choose:??>
    <?when:$DeptName='Accounting'?>
        <?call:tAccounting?>
    <?end when?>
    <?when:$DeptName='Sales'?>
        <?call:tSales?>
    <?end when?>
    <?when:$DeptName='Marketing'?>
        <?call:tMark?>
    <?end when?>
    <?otherwise:$>
        <?call:tDefault?>
    <?end otherwise?>
<?end choose:??>

```

When the user runs the report, the layout applied is determined based on the value of DeptName. For more information on CHOOSE statements in RTF templates, see [Insert Choose Statements](#).

Handle Simple Calculations or Repeating Formulae

Simple calculations can also be handled using an RTF subtemplate. More complex formulae should be handled with an XSL subtemplate.

Example

This example illustrates setting up a subtemplate to contain a formula to calculate interest.

The subtemplate performs the interest calculation on the data in this report and passes the result back to the main template. The sub template accommodates the possibility that multiple reports that call this functionality might have different tag names for the components of the formula.

Assume that you've the following XML data:

```
<LOAN_DATA>
  <LOAN_AMOUNT>6000000</LOAN_AMOUNT>
  <INTEREST_RATE>.053</INTEREST_RATE>
  <NO_OF_YEARS>30</NO_OF_YEARS>
</LOAN_DATA>
```

To set up a sub template to contain a formula for calculating interest:

1. In an RTF file, create a template declaration called calcInterest. In this sub template define a parameter for each of the elements (principal, interest rate, and years) in the formula. Note that you must set the default value for each parameter.

```
<?template:calcInterest?>
  <?param:principal;0?>
  <?param:intRate;0?>
  <?param:years;0?>
  <?number($principal) * number($intRate) * number($years)?>
<?end template?>
```

2. Create a Sub Template in the catalog in the following location:

Shared Folders/Subtemplates

Upload the RTF file and save the Sub Template as calculations.

3. In the main template, enter the following to import the sub template:

```
<?import:xdoxsl:///Subtemplates/calculations.xsb?>
```

4. In the location where you want the results of the calculation to display, enter the following in a Publisher field:

```
<?call@inlines:calcInterest?>
  <?with-param:principal;./LOAN_AMOUNT?>
  <?with-param:intRate;./INTEREST_RATE?>
  <?with-param:years;./NO_OF_YEARS?>
<?end call?>
```

Note the use of the @inlines command here. This is optional. The @inlines command forces the results to be rendered inline at the location in the template where the call to the sub template is made. Use this feature, for example, if you want to keep the results on the same line as a string of text that precedes the call.

Add Translations to an RTF Subtemplate

RTF subtemplates offer the same support for translations as RTF template files.

You can upload multiple translated RTF files under a single Subtemplate definition and assign the appropriate locale. These are displayed in the **Templates** region, as shown in the following figure.

Or you can generate an XLIFF (.xlf) file of the translatable strings, translate the strings, and upload the translated file. These are displayed in the **Translations** region.

At runtime, the appropriate subtemplate localization is applied based on the user's account **Preference** setting for Report Locale for reports viewed online; or, for scheduled reports, based on the user's selection for Report Locale for the scheduled report.

The XLIFF files for subtemplates can be generated individually, then translated, and uploaded individually. Or, if you perform a catalog translation that includes the Sub Template folders, the strings from the subtemplate files are extracted and included in the larger catalog translation file. When the catalog translation file is uploaded to Publisher, the appropriate translations from the catalog file are displayed in the **Translations** region of the Sub Template definition.

Design XSL Subtemplates

This topic describes how to create XSL subtemplates to create reusable advanced functionality for your RTF templates.

Topics:

- [Understand XSL Subtemplates](#)
- [Process Overview for Creating and Implementing XSL Sub Templates](#)
- [Create an XSL Subtemplate File](#)
- [Call an XSL Subtemplate from the Main Template](#)
- [Create the Sub Template Object in the Catalog](#)
- [Example Uses of XSL Subtemplates](#)

Understand XSL Subtemplates

An XSL subtemplate is an XSL file that consists of one or more `<xsl:template>` definitions, each containing a block of formatting or processing commands.

When uploaded to Publisher as a Sub Template object in the Catalog, this XSL file can be called from other RTF templates to execute the formatting or processing commands.

XSL subtemplates can handle complex data and layout requirements. Use XSL subtemplates to transform the data structure for a section of a report (for example, for a chart) or to create a style sheet to manage a complex layout.

Where to Put XSL Code in the RTF Main Template

When you call the XSL subtemplate within a main RTF subtemplate, you use XSL commands.

You must put this code inside a Publisher field (or Microsoft Word form field). You cannot enter XSL code directly in the body of the RTF template.

For more information on inserting form fields in an RTF template see [Insert a Field](#).

Process Overview for Creating and Implementing XSL Sub Templates

You must follow this process when working with XSL sub templates.

Creating and implementing an XSL sub template consists of the following steps:

1. Create the XSL file that contains the common components or processing instructions to include in other templates.

An XSL sub template consists of one or more XSL template definitions. These templates contain rules to apply when a specified node is matched.

2. Create the calling or "main" layout that includes a command to "import" the sub template to the main template and a command to apply the XSL sub template to the appropriate data element.
3. Upload the main template to the report definition and create the Sub Template object in the catalog.

Create an XSL Subtemplate File

Enter the instructions in an editor that enables you to save the file as type ".xml". An XSL subtemplate consists of one or more XSL template definitions. These templates contain rules to apply when a specified node is matched.

The syntax of the subtemplate definition is as follows:

```
<xsl:template
  name="name"
  match="pattern"
  mode="mode"
  priority="number">
<!--Content:( <xsl:param>*,template) -->
</xsl:template>
```

The following table describes the components of the template declaration.

| Component | Description |
|-------------------|--|
| xsl:template | The xsl:template element is used to define a template that can be applied to a node to produce a desired output display. |
| name="name" | Optional. Specifies a name for the template. If this attribute is omitted, a match attribute is required. |
| match="pattern" | Optional. The match pattern for the template. If this attribute is omitted, a name attribute is required. |
| priority="number" | Optional. A number which indicates the numeric priority of the template. More than one template can be applied to a node. The highest priority value template is always chosen. The value ranges from -9.0 to 9.0. |

Example:

```
<xsl:template match="P|p">
  <fo:block white-space-collapse="false" padding-bottom="3pt" linefeed-
  treatment="preserve">
    <xsl:apply-templates select="text()|*|@"/*"/>
  </fo:block>
</xsl:template>

<xsl:template match="STRONG|B|b">
  <fo:inline font-weight="bold">
    <xsl:apply-templates/>
  </fo:inline>
</xsl:template>
```

```
</fo:inline>  
</xsl:template>
```

Call an XSL Subtemplate from the Main Template

To implement the subtemplate in the main template, make two entries in the main template.

First, import the subtemplate file to the main template. The import syntax tells the Publisher engine where to find the Sub Template in the catalog.

Second, enter a call command to render the contents of the subtemplate at the position desired.

Import the Subtemplate

Enter the import command anywhere in the main template prior to the call template command as shown here.

```
<?import:xdoxsl:///{path to subtemplate.xsb}?>
```

where

path to subtemplate.xsb is the path to the subtemplate .xsb object in the catalog.

For example:

```
<?import:xdoxsl:///Executive/Financial Reports/mySubtemplate.xsb?>
```

Call the Subtemplate

The template statements that you defined within the XSL subtemplate file are applied to data elements. There are two ways you can call a template defined in the imported XSL subtemplate.

- By matching the data content with the match criteria:

```
<xsl:apply-templates select="data_element"/>
```

This method applies all the templates that are defined in the XSL subtemplate to the `data_element` specified. Based on the data content of `data_element`, appropriate functions in those templates are applied. See the following use case for a detailed example: [Handle XML Data with HTML Formatting](#).

- By calling a template by name:

```
<xsl:call-template name="templateName"/>
```

This method calls the template by name and the template executes, similar to a function call. Here also parameters can be passed to the template call, similarly to an RTF subtemplate. See [Pass Parameters to an XSL Subtemplate](#).

See the following use case for a detailed example: [Dynamically Apply Formatting to a Portion of Data](#).

Pass Parameters to an XSL Subtemplate

Declare the parameter in the <xsl:template> definition.

To pass parameters to the XSL subtemplate:

1. Declare the parameter in the <xsl:template> definition, as follows:

```
<xsl:template name="templateName" match="/">
  <xsl:param name="name" />
</xsl:template>
```

2. Then call this template using the following syntax:

```
<xsl:call-template name="templateName">
  <xsl:with-param name="name" select="expression">
    <!-- Content:template -->
  </xsl:with-param>
</xsl:call-template>
```

Create the Sub Template Object in the Catalog

Follow these steps to upload the sub template file.

To upload the sub template file:

1. On the global header click **New** and then click **Sub Template**. This launches an untitled Sub Template page.
2. In the **Templates** region, click **Upload** to launch the Upload Template File dialog.
3. Browse for and select the sub template file.
 - **Type:** Select xsl for an XSL sub template file.
 - **Locale:** Select the appropriate locale for the sub template file.
4. Click **Upload**.

The sub template file is displayed in the **Templates** region as the locale name that you selected (for example: en_US).

5. Click **Save**. In the Save As dialog choose the catalog folder in which to save the Sub Template. Enter the **Name** and click **Save**.

The Sub Template object is saved with the extension ".xsb". Use the Name that you choose here with the .xsb extension when you import the Sub Template to the report (for example: MySubtemplate.xsb).

Translations are not supported for XSL Sub Templates.

Example Uses of XSL Subtemplates

These are examples of formatting that can be achieved in a report by using XSL subtemplates.

- [Handle XML Data with HTML Formatting](#)
- [Dynamically Apply Formatting to a Portion of Data](#)

Handle XML Data with HTML Formatting

If you have XML data that already contains HTML formatting and you want to preserve that formatting in the report, then you can preserve that formatting by using an XSL subtemplate to map the HTML formatting commands to XSL equivalents that can be handled by Publisher.

Note that the HTML must be in XHTML format. This means that all HTML tags must have start and end tags in the data. For example, if the data uses a simple `
` for a break, then you must add the closing `</BR>` before you can use this solution.

Following is some sample data with HTML formatting:

```
<DATA>
  <ROW>
    <PROJECT_NAME>Project Management</PROJECT_NAME>
    <PROJECT_SCOPE>
      <p>Develop an application to produce <i>executive-level
summaries</i> and detailed project reports. The application will allow
users to: </p>
      <p>Import existing MS Project files </p>
      <p>Allow the user to map file-specific resources to a central
database entities (i.e., people) and projects; </p>
      <p>Provide structured output that can be viewed by staff and
executives. </p>
    </PROJECT_SCOPE>
    <PROJECT_DEFINITION><b>Information about current projects is not
readily available to executives.</b> Providing this information creates
a reporting burden for IT staff, who may already maintain this
information in Microsoft Project files. </PROJECT_DEFINITION>
  </ROW>
</DATA>
```

Assume a report requirement to display this to retain the formatting supplied by these tags as shown in the following figure:

| | |
|---------------------------|---|
| Project Name | Project Management |
| Project Scope | Develop an application to produce <i>executive-level summaries</i> and detailed project reports. The application will allow users to: Import existing MS Project files Allow the user to map file-specific resources to a central database entities (i.e., people) and projects; Provide structured output that can be viewed by staff and executives. |
| Project Definition | Information about current projects is not readily available to executives. Providing this information creates a reporting burden for IT staff, who may already maintain this information in Microsoft Project files. |

The following subtemplate uses XSL syntax to match the three HTML tags in the XML data. The template then replaces the matched HTML string with its XSLFO equivalent.

```
<xsl:template match="P|p">
  <fo:block white-space-collapse="false" padding-bottom="3pt" linefeed-
treatment="preserve">
  <xsl:apply-templates select="text()|*|@*" />
  </fo:block>
</xsl:template>

<xsl:template match="STRONG|B|b">
  <fo:inline font-weight="bold">
    <xsl:apply-templates />
  </fo:inline>
</xsl:template>

<xsl:template match="EM|I|i">
  <fo:inline font-style="italic">
    <xsl:apply-templates />
  </fo:inline>
</xsl:template>
```

To use an XSL syntax:

1. Upload the XSL subtemplate file to the Publisher catalog location: Shared Folders/Projects. Save this subtemplate file as `htmlmarkup.xsb`.
2. In the main template enter the following to import the subtemplate file:
`<?import:xdoxsl:///Projects/htmlmarkup.xsb?>`
3. For each field that has HTML markup, call the `xsl apply-template` command. In this example, there're two fields:

```
<xsl:apply-templates select="PROJECT_SCOPE" />
<xsl:apply-templates select="PROJECT_DEFINITION" />
```

The command tells the processor to apply all templates to the value of the element `PROJECT_SCOPE` and `PROJECT_DEFINITION`. It then cycles through the subtemplate functions looking for a match.

Dynamically Apply Formatting to a Portion of Data

This application of subtemplates is useful for documents that require chemical formulae, mathematical calculations, or superscripts and subscripts.

For example, in the sample XML data below `CO2` is expected to display as CO_2 and `H2O` is expected to display as H_2O .

```
<ROWSET>
  <ROW>
    <FORMULA>CO2</FORMULA>
  </ROW>
  <ROW>
    <FORMULA>H2O</FORMULA>
```

```
</ROW>
</ROWSET>
```

This can be achieved by using an XSL subtemplate. Using XSL syntax you can define a template with any name, for example, "chemical_formatter" that accepts the FORMULA field as a parameter, and then reads one character at a time. It compares the character with 0 - 9 digits, and if there's a match, then that character is subscripted using the following XSL FO syntax:

```
<fo:inline baseline-shift="sub" font-size="75%">
```

Here is sample code for the XSL template statement:

```
<xsl:template name="chemical_formatter">
  <!-- accepts a parameter e.g. H2O -->
  <xsl:param name="formula"/>
  <!-- Takes the first character of the string and tests it to see if it
  is a number between 0-9 --> <xsl:variable name="each_char"
  select="substring($formula,1,1)"/>
  <xsl:choose>
    <xsl:when test="$each_char='1' or $each_char='2'
    or $each_char='3' or $each_char='4' or $each_char='5'
    or $each_char='6' or $each_char='7' or $each_char='8'
    or $each_char='9' or $each_char='0'">
      <!-- if it is numeric it sets the FO subscripting properties -->
      <fo:inline baseline-shift="sub" font-size="75%">
        <xsl:value-of select="$each_char"/>
      </fo:inline>
    </xsl:when>
    <xsl:otherwise>
      <!-- otherwise the character is left as is -->
      <fo:inline baseline-shift="normal">
        <xsl:value-of select="$each_char"/>
      </fo:inline>
    </xsl:otherwise>
  </xsl:choose>
  <!-- test if there are other chars in the string, if so the recall
  the template -->
  <xsl:if test="substring-after($formula,$each_char) != ''">
    <xsl:call-template name="chemical_formatter">
      <xsl:with-param name="formula">
        <xsl:value-of select="substring-
after($formula,$each_char)"/>
      </xsl:with-param>
    </xsl:call-template>
  </xsl:if>
</xsl:template>
```

To use this XSL template statement:

1. Save this file as chemical.xsl.

2. Follow the instructions in [Upload a Subtemplate](#). Assume that you name the Sub Template "Chemical" (it's saved as Chemical.xsb) and place it in the following location: Shared Folders/Subtemplates.
3. In the main RTF template enter the import syntax:

```
<?import:xdoxsl:///Subtemplates/Chemical.xsb?>
```

4. To render the XSL code in the report, create a loop over the data and in the VALUE field use:

```
<xsl:call-template name="chemical_formatter">  
<xsl:with-param name="formula" select="VALUE"/> </xsl:call-template>
```

This calls the formatting template with the FORMULA value that is, H₂O. Once rendered, the formulae are shown as expected: H₂O.

Part IV

Translate Objects in Pixel-Perfect Reports

This part provides information about translating reports and catalog objects.

Topics:

- [Translation Support Overview and Concepts](#)
- [Translate Individual Templates](#)
- [Translate Catalog Objects, Data Models, and Templates](#)

Translation Support Overview and Concepts

This topic provides an overview of concepts related to report and catalog translation in Publisher.

Topics:

- [Translation Support Overview](#)
- [Work with Translation Files](#)
- [Locale Selection Logic](#)

Translation Support Overview

You can translate reports and catalogs in Publisher.

Publisher supports translation in two ways, as described in the following sections:

- [What Is Catalog Translation?](#)
- [What Is Template Translation?](#)
- [About Supported Languages](#)

What Is Catalog Translation?

Catalog translation is a feature of Publisher that enables you to extract the translatable strings from all objects contained in a selected catalog folder into a separate file.

If Publisher is integrated with Oracle Business Intelligence Enterprise Edition, Publisher catalog translation (folder and report, data model, style template and sub template names) is ignored. The Oracle BI Enterprise Edition catalog translation mechanism is applied instead.

The separate string file can be translated and uploaded back to Publisher and assigned the appropriate language code.

Catalog translation extracts not only translatable strings from the report layouts, but also the user interface strings that are displayed to users, such as catalog object descriptions, report parameter names, and data display names.

Users viewing the catalog see the item translations that are appropriate for the user interface language that they selected in their My Account preferences. Users see report translations that are appropriate for the Report Locale that they selected in their My Account preferences.

What Is Template Translation?

Template translation enables you to extract the translatable strings from a single RTF-based template (including sub templates and style templates) or a single Publisher layout template (.xpt file).

Use this option when you need only the final report documents translated. For example, you must generate translated invoices to send to German and Japanese customers.

About Supported Languages

Publisher supports any language that is supported by Unicode and doesn't require a special algorithm to render.

Examples of languages that require a special algorithm to render are Hindi and Farsi. It's the user's responsibility to prepare an appropriate font if the language isn't supported by Albany fonts.

Publisher does support Arabic and Hebrew.

Work with Translation Files

When you extract the translatable strings for a catalog or template translation, Publisher creates an XLIFF file that contains the strings.

You can translate these strings within your organization or send the file to a localization provider. You then upload the translated XLIFF file back to the catalog or the individual layout and assign it the appropriate locale.

This section describes how to work with an XLIFF file. It contains the following topics:

- [What Is an XLIFF?](#)
- [Structure of the XLIFF File](#)

What Is an XLIFF?

XLIFF is the XML Localization Interchange File Format.

It's the standard format used by localization providers. For more information about the XLIFF specification, see <http://www.oasis-open.org/committees/xliff/documents/xliff-specification.htm>

Structure of the XLIFF File

XLIFF files must follow a specific structure

The generated XLIFF file has the following structure:

```
<xliff>
  <file>
    <header>
    <body>
```

```

<trans-unit>
  <source>
  <target>
  <note>

```

The following illustration shows an excerpt from an untranslated XLIFF file.

```

<?xml version = '1.0' encoding = 'utf-8' ?>
<xliff version="1.0">
  <file source-language="en-US" target-language="en-US" datatype="XDO" original="orpher
  <header/>
  <body>
    <trans-unit id="d678c24b" maxbytes="4000" maxwidth="90" size-unit="char" transl
    <source>Italian Purchase VAT Register - [&1]</source>
    <target>Italian Purchase VAT Register - [&1]</target>
    <note>Text located: header/table, token &1:anonymous placeholder(s)</not
  </trans-unit>
    <trans-unit id="4d3eb24" maxbytes="4000" maxwidth="15" size-unit="char" transl
    <source>Total</source>
    <target>Total</target>
    <note>Text located: body/table</note>
  </trans-unit>
    <trans-unit id="aeccc17e" maxbytes="4000" maxwidth="37" size-unit="char" transl
    <source>Non-Recoverable</source>
    <target>Non-Recoverable</target>
    <note>Text located: body/table</note>
  </trans-unit>
  .
  .
  </body>
</file>
</xliff>

```

Source-language and target-language Attributes

The `<file>` element includes the attributes `source-language` and `target-language`.

The valid value for `source-language` and `target-language` is a combination of the language code and country code as follows:

- the two-letter ISO 639 language code
- the two-letter ISO 3166 country code

Note:

For more information on the International Organization for Standardization (ISO) and the code lists, see the International Organization for Standardization Web site at <http://www.iso.org/iso/home.html>

For example, the value for English-United States is "en-US". This combination is also referred to as a *locale*.

When you edit the exported XLIFF file you must change the `target-language` attribute to the appropriate locale value of the target language. The following table shows examples of `source-language` and `target-language` attribute values appropriate for the given translations.

| Translation (Language/Territory) | source-language value | target-language value |
|--------------------------------------|-----------------------|-----------------------|
| From English/US To English/Canada | en-US | en-CA |
| From English/US To Chinese/China | en-US | zh-CN |
| From Japanese/Japan To French/France | ja-JP | fr-FR |

Embedded Data Fields

Some templates contain placeholders for data fields embedded in the text display strings of the report. To identify the embedded data fields use this token.

For example, the title of the sample report is: Italian Purchase VAT Register - (year)

where (year) is a placeholder in the RTF template that is populated at runtime by data from an XML element. These fields are not translatable, because the value comes from the data at runtime.

To identify embedded data fields, the following token is used in the XLIFF file:

[&#n]

where *n* represents the numbered occurrence of a data field in the template.

For example, in the preceding XLIFF sample, the first translatable string is:

```
<source>Italian Purchase VAT Register - [&#1]</source>
```



Note:

Do not edit or delete the embedded data field tokens or you affect the merging of the XML data with the template.

<source> and <target> Elements

Each <source> element contains a translatable string from the template in the source language of the template. Refer to the illustration for information to create a translation for a source element string.

For example,


```
<source>Total</source>
```

When you initially export the XLIFF file for translation, the source and target elements are all identical. To create the translation for this template, enter the appropriate translation for each source element string in its corresponding <target> element.

Therefore if you were translating the sample template into German, you would enter the following for the Total string:

```
<source>Total</source>
<target>Gesamtbetrag</target>
```

The following figure shows the sample XLIFF file from the previous figure updated with the Chinese translation:



Locale Selection Logic

Publisher applies a translation based on the user's selected Report Locale.

Publisher first tries to match an RTF template named for the locale, then an XLIFF file named for the locale. If an exact match on language-territory isn't found, then Publisher tries to match on language only.

For example, if you have a report for which the base template is called EmployeeTemplate.rtf and the locale selected is French (France), then Publisher selects the translation to apply according to the following hierarchy:

EmployeeTemplate.rtf (fr_FR)

EmployeeTemplate.xlf (fr_FR)

EmployeeTemplate.rtf (fr)

EmployeeTemplate.xlf (fr)

EmployeeTemplate.rtf (default)

With the same set of translations, if the locale selected is French (Switzerland), then the EmployeeTemplate.rtf (fr) is applied. Now if the available translations are limited to the following set:

EmployeeTemplate.rtf (fr_FR)

EmployeeTemplate.xlf (fr_FR)

EmployeeTemplate.rtf (default)

and the locale selected is French (Switzerland), then the EmployeeTemplate.rtf (default) is applied. Even though there's a language match, Publisher doesn't match the different locales.

Therefore, to ensure that a French language translation is used when French is the selected language, regardless of the selected locale, you must include either an rtf or xlf file named for the language only (that is, EmployeeTemplate_fr.rtf or EmployeeTemplate_fr.xlf).

Translate Individual Templates

This topic describes how to create and upload translated template files to provide translations for specific templates.

Topics:

- [Overview](#)
- [Types of Translations](#)
- [Use the XLIFF Option](#)
- [Use the Localized Template Option](#)

Overview

This chapter describes how to create and upload translated template files when you want to provide translations only for specific templates.

The following template types can be translated individually:

- RTF layout files
- style templates
- subtemplates
- Publisher layouts (.xpt)

Types of Translations

You can add different types of translations to templates.

There're two options for adding translations for templates:

- Create a separate RTF template that is translated (a localized template). This option is available for RTF templates only.
- Generate an XLIFF from the original template. At runtime the original template is applied for the layout and the XLIFF is applied for the translation.


Use the first option if the translated template requires a different layout from the original template.

If you require only translation of the text strings of the template layout, then use the XLIFF option.

The diagrams in the following graphic illustrate the translation concepts.


Localized Template Option

Use this option when you want a specific translation to have a different layout.



XLIFF File Option

Use this option when you want to use the same layout and apply specific translations.



Use the XLIFF Option

The XLIFF option is used to translate files.

The following sections describe using the XLIFF option:

- [Generate the XLIFF from a Template](#)
- [Translate the XLIFF](#)
- [Upload the Translated XLIFF to Publisher](#)

Generate the XLIFF from a Template

These sections describe the two methods for generating an XLIFF for a single template file.

- [Generate the XLIFF from the Template Builder](#) (not supported for XPT templates)
- [Generate the XLIFF from the Layout Properties Page](#)

Generate the XLIFF from the Template Builder

Follow these steps to generate the XLIFF from the template builder.

This procedure assumes that you've installed the Publisher Template Builder for Microsoft Word.

To generate an XLIFF from the Template Builder:

1. Open the template in Microsoft Word with the Template Builder for Word installed.
2. On the **Template Builder** tab, in the Tools group, click **Translation**, and then click **Extract Text**.

Publisher extracts the translatable strings from the template and exports them to an XLIFF (.xlf file).

3. Save the XLIFF to a local directory.

Generate the XLIFF from the Layout Properties Page

You can generate the XLIFF file for report layout templates or for style templates and subtemplates.

To generate the XLIFF file for report layout templates:

1. Navigate to the report in the catalog and click **Edit** to open it for editing.
2. From the thumbnail view of the report layouts, click the **Properties** link of the layout (RTF or XPT) to open the Layout Properties page.
3. In the Translations region, click **Extract Translation**.

Publisher extracts the translatable strings from the template and exports them to an XLIFF (.xlf) file.

4. Save the XLIFF file to a local directory.

To generate the XLIFF file for style templates and subtemplates:

1. Navigate to the style template or sub template in the catalog and click **Edit** to open the Template Manager.
2. In the Translations region, click **Extract Translation**.

Publisher extracts the translatable strings from the template and exports them to an XLIFF (.xlf) file.

3. Save the XLIFF file to a local directory.

Translate the XLIFF

When you've downloaded the XLIFF file, it can be sent to a translation provider, or using a text editor, you can enter the translation for each string.

A "translatable string" is any text in the template that is intended for display in the published report, such as table headers and field labels. Text supplied at runtime from the data isn't translatable, nor is any text that you supply in the Microsoft Word form fields.

You can translate the template XLIFF file into as many languages as desired and associate these translations to the original template. Ensure that when you save your translated file, you save it with UTF-8 encoding.

Upload the Translated XLIFF to Publisher

After a XLIFF file is translated, upload the XLIFF file to Publisher.

To upload the translated XLIFF:

1. Navigate to the report, subtemplate, or style template in the catalog and click **Edit** to open it for editing.

For reports only:

From the thumbnail view of the report layouts, click the **Properties** link of the layout to open the Template Manager.

2. In the **Translations** region, click the **Upload** toolbar button.
3. In the **Upload Translation File** dialog, locate the file in a local directory and select the **Locale** for this translation.
4. Click **OK** to upload the file and view it in the **Translations** table.

Use the Localized Template Option

If you must design a different layout for the reports that you present for different localizations, then you can create a new RTF file that is designed and translated for the locale and upload this file to the Template Manager.

The localized template option isn't supported for XPT templates. The following sections describe using the localized template option:

- [Design the Localized Template File](#)
- [Upload the Localized Template to Publisher](#)

Design the Localized Template File

Use the same tools that you used to create the base template file, translating the strings and customizing the layout as desired for the locale.

Upload the Localized Template to Publisher

You can upload several types of templates to Publisher.

To upload the localized template:

1. Navigate to the report, subtemplate, or style template in the catalog and click **Edit** to open it for editing.

For reports only:

From the thumbnail view of the report layouts, click the **Properties** link of the layout to open the Template Manager.

2. In the **Templates** region, click the **Upload** toolbar button.
3. In the Upload Template File dialog, locate the file in a local directory, select rtf as the **Template Type** and select the **Locale** for this template file.
4. Click **OK** to upload the file and view it in the **Templates** table.

Translate Catalog Objects, Data Models, and Templates

This topic describes translating the catalog objects, data models, and templates using the Export XLIFF function that is available at the catalog level.

Topics:

- [Overview](#)
- [What Can Be Translated?](#)
- [Export the XLIFF File](#)
- [Identify and Update the Object Tags](#)
- [Import the XLIFF File](#)

Overview

This chapter describes how to use the Export XLIFF function that is available at the catalog level.

When you select a folder and choose this option, a single XLIFF file is generated that contains the translatable strings from the catalog objects contained in the folder; and the RTF and XPT templates contained in the folder. See the following section for the detailed list of what is translatable.

The target strings in the generated XLIFF file can be translated into the desired language. The XLIFF can then be uploaded back to the Publisher repository and assigned the appropriate locale. The translated strings from the XLIFF are displayed when a user selects the target language as their UI language (for catalog object strings) or selects the target language as their Report Locale (for report template strings).

If Publisher is integrated with Oracle Business Intelligence Enterprise Edition, then Publisher catalog object string translation (folder and report, data model, style template and sub template names) is ignored. The Oracle BI Enterprise Edition catalog translation mechanism is applied instead.

What Can Be Translated?

Specific strings can be translated into different languages.

The following table shows what strings can be translated.

| Object | What Can Be Translated | Preference That Determines Translation Displayed |
|--------|------------------------|--|
| Folder | Name Description | UI Language (applies to all) |

| Object | What Can Be Translated | Preference That Determines Translation Displayed |
|--------------------------|---|--|
| Data Model | Name Description Data Display Name | UI Language (applies to all) |
| Report | Name Description Layout Names Data Model Reference Parameter Name | UI Language (applies to all) |
| Style Template | Name Static text in the template | UI Language Report Locale |
| Sub Template | Name Static text in the template | UI Language Report Locale |
| Publisher Layouts (.xpt) | Static text in the layout | Report Locale |
| RTF Layouts | Static text in the layout | Report Locale |

About Source Language Limitations

Translation of Publisher catalog objects using the Export XLIFF function is available at the catalog level.

For catalog translation, the source language is limited to "en". You must create catalog and data model objects in English locale to be able to translate them.

Export the XLIFF File

Follow these steps to export an XLIFF file for a catalog folder.

1. Select the folder in the catalog.
2. Click the **Translation** toolbar button and then click **Export XLIFF**.

Publisher extracts the translatable strings from the template and exports them to an XLIFF (.xlf file).

3. Save the XLIFF file to a local directory.

Identify and Update the Object Tags

In the XLIFF file generated for a catalog object, the source-language and target-language attributes contain values for the two-letter language code only as shown in this figure.

For information on how to manually update the XLIFF files with translation strings, see [What Is an XLIFF?](#)

```
<?xml version = '1.0' encoding = 'utf-8'?>
<xliff version="1.0">
  <file source-language="en" target-language="en" datatype="xml" product-version="11.1.1.3.0" pr
    <body>
      <trans-unit id="xdo#%2F%7Eadministrator%2FMy+Folder%2FReport.xdo#tmp_Salary.xpt">
        <source>Salary</source>
        <target>Salary</target>
      </trans-unit>
```

Import the XLIFF File

When the target tags have been translated you are ready to import the XLIFF file back to Publisher.

To import an XLIFF file:

1. Navigate to the folder from which the XLIFF file was generated.
2. From the toolbar, click the **Translation** button and select **Import XLIFF**.
3. In the Upload dialog click **Browse** to locate the translated file and then select the appropriate locale from the list.
4. Click **Upload**.

Part V

Reference Information

This part provides reference information for pixel-perfect reports.

Topics:

- [Techniques for Handling Large Output Files](#)
- [Extended Function Support in RTF Templates](#)
- [Design Accessible Reports](#)
- [Supported XSL-FO Elements](#)
- [Generate PDF/A and PDF/X Output](#)
- [Generate Accessible PDF Output](#)
- [Generate CSV Output](#)
- [PDF Version Support](#)
- [Test Templates with Template Viewer](#)

Techniques for Handling Large Output Files

This topic describes techniques that are available to improve performance when the report generates very large PDF output files.

Topics:

- [Reuse Static Content](#)
- [Generate Zipped PDF Output](#)
- [Implement PDF Splitting for an RTF Template](#)
- [Implement PDF Splitting for a PDF Template](#)

Reuse Static Content

This section describes how to reuse static, repeating content in a PDF report output to reduce the overall PDF file size.


This section contains the following topics:

- [What Is Static Content Reuse?](#)
- [Limitations of this Feature](#)
- [Define Reusable Content in an RTF Template](#)
- [Example](#)

What Is Static Content Reuse?

If the report contains static content and the placement of that content in the report is also fixed (for example, a set of instructions on the back of a Federal W-2 form), then you can use this feature to reduce the size of the generated PDF file.

Using the W-2 form as an example, the report has the expected output shown in the following illustration.



For each employee, specific content is rendered, but the back (or second) page of each contains an identical set of instructions.

This set of instructions can be defined as reusable static content. When content is identified as reusable static content, the PDF document includes the static content only once and references it in other places when needed, thereby reducing the overall output file size.

Limitations of this Feature

This feature has the following limitations.

- The static content to be reused in the generated report must fit onto one page of the generated PDF output.
- The contents of the report before the static content must have a fixed height. For example, the W-2 form has a fixed set of fields that occur before the static content is to be rendered. The reusable static contents are placed in the same position from the page origin for each occurrence.
- This feature can only be used with RTF templates generating PDF output.

Define Reusable Content in an RTF Template

To define the static content to be reused, use these tags around the content in the template.

```
<?reusable-static-content:??>
```

... static content here ...

<?end reusable-static-content?>

Inserting these tags around the static content signals Publisher to include this content only once in the generated file and then reference it in the same position for each occurrence.

Example

This example illustrates an implementation of this feature. The sample report generates one occurrence per employee. The generated report has employee-specific information on the front page of each occurrence, and static instructions that print on the back of each occurrence. A section break occurs after each employee to reset page numbering.

The following figure illustrates the template structure:

<?for-each@section:employee?>

| | | |
|-----------------|------------------|-----------------|
| Lastname | Firstname | MI |
| Address | City | State |
| Year | Employer | Earnings |

.....Page Break.....

<?reusable-static-content: ?>

Notice to Employee

Refund. Even if you do not have to file a tax return, you should file to get a refund if box 2 shows federal income tax withheld or if you can take the earned income credit. Earned income credit (EIC). You must file a tax return if any amount is shown in box 9. You may be able to take the EIC for 2009 if (a) you do not have a qualifying child and you earned less than \$13,440 (\$16,560 if married filing jointly), (b) you have one qualifying child and you earned less than \$35,463 (\$38,583 if married filing

or (c) you have one than one Qualifying child and you earned less than \$40,295 (\$43,415 if married filing jointly). You and any qualifying children must have valid social security numbers (SSNs). You cannot take the EIC if your investment income is more than \$3,100. Any EIC that is more than your tax liability is refunded to you, but only if you file a tax return. If you have at least one qualifying child, you may get as much as \$1,826 of the EIC in advance by completing Form W-5, Earned Income Credit Advance Payment Certificate, and giving it to your employer

<?end reusable-static-content?>

<?end for-each?>

Generate Zipped PDF Output

When generating PDF output, Publisher doesn't limit the size of the output file. However, when the size of the file approaches 2 GB, Adobe Acrobat Reader may no longer be able to open or handle the file. Publisher provides a feature to split a large PDF output file into smaller, more manageable files, while still maintaining the integrity of the report as one logical unit.

When PDF output splitting is enabled for a report, the report is split into multiple files generated in one zip file. The output type is PDFZ. For easy access to the component files, Publisher also generates an index file that specifies from and to elements contained in each component PDF file.

To enable this feature, the report designer must set up the report using the methods described in this section.

Limitations and Prerequisites

Perform these steps before using this feature, and be aware of its functional limitations.

- This feature is supported only for PDF output that is generated from an RTF template or a PDF template.
- Data set input to the report must be flat XML data (that is, ROWSET/ROW). The data set cannot be hierarchical or concatenated.
- The data set must be sorted by the element designated as the "repeat" element (as described below).

Design Time Considerations


To enable report splitting, the report designer must determine these steps.

- Select a *repeat* element to serve as the counter.
- Determine how many instances of the repeat element occur per PDF file.
- Select which data elements to include in the generated index file.


Select the Output Type

After uploading the template to the report definition, enable Zipped PDFs as an output type.

The output type menu is shown in the following illustration.



When scheduling the report, select PDFZ as the output type, as shown in the following illustration.



Implement PDF Splitting for an RTF Template

This section describes how to enable PDF splitting for reports generated from RTF templates.

This section includes the following topics:

- [Enter the Commands in an RTF Template](#)
- [Example - split by each department](#)

Enter the Commands in an RTF Template

When you design a template to use this feature, you must add commands to specify these queries.

- What element in the data is repeated (using the simple for-each command)
- How many occurrences of the element are included in each PDF file
- What information (data elements) to include in the index file

To achieve this, the following two commands must be entered in the template within the for-each loop of the element by which you want the document to split:

- `<?catalog-index-info:name;element_name?>`

where

name is the name that you choose that is used in the index file to identify the from and to records included in each document.

element_name is the XML tag name of the element that provides the value for name that you identify above.

The catalog-index-info command defines the construction of the index file that is created.

- `<?if:position() mod n = 0?><?document-split:?><?end if?>`

where

n is the number of records you want included per PDF file.

This command must be placed within the for-each loop of the element being counted. This command instructs Publisher to split the document after the next page break when the number of records equals the *n* value.

Each time the document-split is performed, the name-value pairs defined in the catalog-index-info command are written to the index files.

Example - split by each department

This example is based on the XML data given here.

This example is based on the following XML data:

```
<DATA_DS>
  <G_EMP>
    <DEPARTMENT_NAME>Sales</DEPARTMENT_NAME>
    <FIRST_NAME>Ellen</FIRST_NAME>
    <LAST_NAME>Abel</LAST_NAME>
    <HIRE_DATE>1996-05-11T00:00:00.000-07:00</HIRE_DATE>
    <SALARY>11000</SALARY>
  </G_EMP>
  <G_EMP>
    <DEPARTMENT_NAME>Sales</DEPARTMENT_NAME>
    <FIRST_NAME>Sundar</FIRST_NAME>
    <LAST_NAME>Ande</LAST_NAME>
    <HIRE_DATE>2000-03-24T00:00:00.000-08:00</HIRE_DATE>
    <SALARY>6400</SALARY>
  </G_EMP>
  <G_EMP>
    <DEPARTMENT_NAME>Shipping</DEPARTMENT_NAME>
    <FIRST_NAME>Mozhe</FIRST_NAME>
    <LAST_NAME>Atkinson</LAST_NAME>
    <HIRE_DATE>1997-10-30T00:00:00.000-08:00</HIRE_DATE>
    <SALARY>2800</SALARY>
  </G_EMP>
  <G_EMP>
    <DEPARTMENT_NAME>IT</DEPARTMENT_NAME>
    <FIRST_NAME>David</FIRST_NAME>
    <LAST_NAME>Austin</LAST_NAME>
    <HIRE_DATE>1997-06-25T00:00:00.000-07:00</HIRE_DATE>
    <SALARY>4800</SALARY>
  </G_EMP>
  ...
</DATA_DS>
```

In this example, the output PDF report includes a document for each employee. You want a new PDF file generated for each department. You want the index to list the FIRST_NAME and LAST_NAME from each record that is included in the PDF file.

To achieve this output, enter the following in the template:

```
<?for-each-group:ROW; ./DEPARTMENT_NAME?>
  <?for-each:current-group()?>
    <?catalog-index-info:'First Name';FIRST_NAME?>
    <?catalog-index-info:'Last Name';LAST_NAME?>
    ...
  <?end for-each?>
```

```
<?document-split:?>  
<?end for-each-group?>
```

Implement PDF Splitting for a PDF Template

This section describes the commands required in a PDF template to split the output into multiple PDF files.

Enter the Commands in the PDF Template

To enable this feature for a PDF template, enter the three form fields listed in this table here in the template with the specified commands in the **Tooltip** field.

| Form Field Name | Tooltip Command |
|--------------------|---|
| REPEAT-ELEMENT | <code><?repeat-element:element_name?></code> , where <code>element_name</code> is the XML tag name of the repeating element that is counted. Example: <code><?repeat-element:emp_id?></code> |
| CATALOG-INDEX-INFO | <code><?catalog-index-info:'Name';element_name?></code> , where <code>Name</code> is the label that appears in the index file for the <code>element_name</code> that you specify. The index generates a <i>From</i> and <i>To</i> listing for each file in the zipped set. Example: <code><?catalog-index-info:'Last Name';LAST_NAME?></code> You can include multiple occurrences of the <code>catalog-index-info</code> command to include multiple data elements in the index file. |
| SPLIT-COUNT | <code><?split-count:n?></code> , where <code>n</code> is the number of occurrences of the <code>repeat-element</code> that triggers the creation of a new file. Example: <code><?split-count:10000?></code> |

Extended Function Support in RTF Templates

This topic describes SQL and XSL functions extended by Publisher for use in RTF templates.

Topics:

- [Extended SQL and XSL Functions](#)
- [XSL Equivalents](#)
- [Use FO Elements](#)

Extended SQL and XSL Functions

Publisher has extended a set of SQL and XSL functions for use in RTF templates.

The syntax for these extended functions is

```
<?xdofx:expression?>
```

for extended SQL functions or

```
<?xdoxslt:expression?>
```

for extended XSL functions.

You can't mix `xdofx` statements with XSL expressions in the same context. For example, assume that you had two elements, `FIRST_NAME` and `LAST_NAME` to concatenate into a 30-character field and right pad the field with the character "x". You couldn't use the following:

```
<?xdofx:rpad(concat(FIRST_NAME, LAST_NAME), 30, 'x')?>
```

because `concat` is an XSL expression. Instead, you could use the following:

```
<?xdofx:rpad(FIRST_NAME || LAST_NAME), 30, 'x')?>
```

The supported functions are shown in the following table:

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------|-------------------|----------------|
| 2+3 | <?xdofx:2+3?> | Addition |
| 2-3 | <?xdofx:2-3?> | Subtraction |
| 2*3 | <?xdofx:2*3?> | Multiplication |
| 2 div 3 | <?xdofx:2 div 3?> | Division |

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------|--|--|
| 2**3 | <?xdofx:2**3?> | Exponential |
| 3 2 | <?xdofx:3 2?> | Concatenation |
| sdiv() | <?xdoxslt:sdiv(num1,num2, string)?> | Safe divide function returns a specified value if the result of the function is not a number (NaN). In the syntax shown, num1 is the dividend; num2 is the divisor and string is the value to be returned if NaN is returned. Examples: <?xdoxslt:sdiv(10,0, '0')?> would yield '0' <?xdoxslt:sdiv(10,0, 'None')?> would yield 'None'. |
| lpad('aaa',10,'.') | <?xdofx:lpad('aaa',10,'.')?> | The lpad function pads the left side of a string with a specific set of characters. The syntax for the lpad function is: lpad(string1,padded_length,[pad_string])string1 is the string to pad characters to (the left-hand side).padded_length is the number of characters to return.pad_string is the string that is padded to the left-hand side of string1 . |
| rpad('aaa',10,'.') | <?xdofx:rpad('aaa',10,'.')?> | The rpad function pads the right side of a string with a specific set of characters. The syntax for the rpad function is: rpad(string1,padded_length,[pad_string]).string1 is the string to pad characters to (the right-hand side).padded_length is the number of characters to return.pad_string is the string that is padded to the right-hand side of string1 |
| trim() | <?xdoxslt:trim(' a ')?> | Removes spaces in a string. Enter the text to be trimmed, the function returns the trimmed text. |
| ltrim() | <?xdoxslt:ltrim(' a ')?> | Removes the leading white spaces in a string. |
| rtrim() | <?xdoxslt:rtrim(' a ')?> | Removes the trailing white spaces in a string. |
| truncate | <?xdoxslt:truncate (number [, integer])?> | The truncate function returns number truncated to integer places right of the decimal point. If integer is omitted, then number is truncated to the whole integer value. integer can be negative to truncate values left of the decimal point. integer must be an integer. Example: <?xdoxslt:truncate(-2.3333)?> returns -2 Example: <?xdoxslt:truncate(2.7777, 2)?> returns 2.77 Example: <?xdoxslt:truncate(27.7777, -1)?> returns 20 |
| replicate | <?xdoxslt:replicate('string', integer)?> | The replicate function replicates the specified string the specified number of times. Example: <?xdoxslt:replicate('oracle', 3)?> returns oracleoracleoracle |

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------------|--|--|
| decode('xxx','bbb','ccc','xxx','ddd') | <?xdoxfx:decode('xxx','bbb','ccc','xxx','ddd')?> | The decode function has the functionality of an IF-THEN-ELSE statement. The syntax for the decode function is: decode(expression, search, result [,search, result]...[, default]) <i>expression</i> is the value to compare. <i>search</i> is the value that is compared against <i>expression</i> . <i>result</i> is the value returned, if <i>expression</i> is equal to <i>search</i> . <i>default</i> is returned if no matches are found. |
| Instr('abcabcabc','a',2) | <?xdoxfx:Instr('abcabcabc','a',2)?> | The <i>instr</i> function returns the location of a substring in a string. The syntax for the <i>instr</i> function is: instr(string1,string2,[start_position],[nth_appearance]) <i>string1</i> is the string to search. <i>string2</i> is the substring to search for in <i>string1</i> . <i>start_position</i> is the position in <i>string1</i> where the search starts. The first position in the string is 1. If the <i>start_position</i> is negative, the function counts back <i>start_position</i> number of characters from the end of <i>string1</i> and then searches towards the beginning of <i>string1</i> . <i>nth_appearance</i> is the <i>nth</i> appearance of <i>string2</i> . |
| substr('abcdefg',2,3) | <?xdoxfx:substr('abcdefg',2,3)?> | The substr function allows you to extract a substring from a string. The syntax for the substr function is: substr(string, start_position, length) <i>string</i> is the source string. <i>start_position</i> is the position for extraction. The first position in the string is always 1. <i>length</i> is the number of characters to extract. |
| left | <?xdoxslt:left('abcdefg', 3)?> | Enables you to extract the specified number of characters from a string, starting from the left. The syntax is left(string, Numchars) For example, <?xdoxslt:left('abcdefg', 3)?> returns abc |
| right | <?xdoxslt:right('abcdefg', 3)?> | Enables you to extract the specified number of characters from a string, starting from the right. The syntax is right(string, Numchars) For example, <?xdoxslt:right('abcdefg', 3)?> returns efg |
| replace(name,'John','Jon') | <?xdoxfx:replace(name,'John','Jon')?> | The replace function replaces a sequence of characters in a string with another set of characters. The syntax for the replace function is: replace(string1,string_to_replace,[replacement_string]) <i>string1</i> is the string to replace a sequence of characters with another set of characters. <i>string_to_replace</i> is the string that is searched for in <i>string1</i> . <i>replacement_string</i> is optional. All occurrences of <i>string_to_replace</i> are replaced with <i>replacement_string</i> in <i>string1</i> . |
| to_number('12345') | <?xdoxfx:to_number('12345')?> | Function <i>to_number</i> converts char, a value of CHAR, VARCHAR2, NCHAR, or NVARCHAR2 datatype that contains a number in the format that is specified by the optional format model <i>fmt</i> , to a value of NUMBER datatype. |

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------|---|--|
| format_number | <code><?xdoxslt:format_number(12345, n, \$_XDOLOCALE)?></code> | Converts a number to a string and formats the number according to the locale specified in <code>\$_XDOLOCALE</code> and to the number of decimal positions specified in <code>n</code> using Java's default symbols. For example: <code><?xdoxslt:format_number(-12345, 2, 'fr-FR')?></code> returns -12 345,00 |
| format_number | <code><?xdoxslt:format_number(12345, n, s1, s2,\$_XDOLOCALE)?></code> | Converts a number to a string and uses the specified separators: <code>s1</code> for the thousand separator and <code>s2</code> for the decimal separator. For example: <code><?xdoxslt:format_number(12345, 2, 'g', 'd', \$_XDOLOCALE)?></code> returns 12g345d00 |
| pat_format_number | <code><?xdoxslt:pat_format_number(12345, '##,##0.00', \$_XDOLOCALE)?></code> | Returns a number formatted with the specified pattern. For example: <code><?xdoxslt:pat_format_number(12345, '##,##0.00', \$_XDOLOCALE)?></code> returns 12,345.00 |
| to_char(12345) | <code><?xdoxfx:to_char('12345')?></code> | Use the TO_CHAR function to translate a value of NUMBER datatype to VARCHAR2 datatype. |
| to_date | <code><?xdoxfx:to_date (char [, fmt [, 'nlsparam']])></code> | TO_DATE converts char of CHAR, VARCHAR2, NCHAR, or NVARCHAR2 datatype to a value of DATE datatype. The <code>fmt</code> is a date format specifying the format of <code>char</code> . If you omit <code>fmt</code> , then <code>char</code> must be in the default date format. If <code>fmt</code> is 'J', for Julian, then <code>char</code> must be an integer. |
| format_date() | <code><?xdoxslt:format_date(./ AnyDate, 'yyyy-MM-dd', 'MM/dd/yyyy', \$_XDOLOCALE, \$_XDOTIMEZONE)?></code> | Reads date in one format and creates in another format. |
| sysdate() | <code><?xdoxfx:sysdate()?></code> | SYSDATE returns the current date and time in XML canonical date format (for example: 1997-07-16T19:20:30.45+01:00). The datatype of the returned value is DATE. The function requires no arguments. See Display the System Date (sysdate) in Reports for information on properly formatting the sysdate in report output. |
| current_date() | <code><?xdoxslt:current_date(\$_XDOLOCALE, \$_XDOTIMEZONE)?></code> Example: <code><?xdoxslt:current_date('ja-JP', 'Asia/Tokyo')?></code> | Returns the current date in yyyy-MM-dd format in the given locale and timezone. This function supports only the Gregorian calendar. |
| current_time() | <code><?xdoxslt:current_time(\$_XDOLOCALE, \$_XDOTIMEZONE)?></code> Example: <code><?xdoxslt:current_time('ja-JP', 'Asia/Tokyo')?></code> | Returns the current time in the given locale and timezone. This function supports only the Gregorian calendar. |
| minimum | <code><?xdoxslt:minimum(ELEMENT_NAME)?></code> | Returns the minimum value of the element in the set. |

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------|---|---|
| date_diff | <code><?xdoxslt:date_diff('y', 'YYYY-MM-DD', 'YYYY-MM-DD', \$_XDOLocale, \$_XDOTIMEZONE)?></code> | <p>This function provides a method to get the difference between two dates in the given locale. The dates must be in "yyyy-MM-dd" format. This function supports only the Gregorian calendar. The syntax is as follows: <code><?xdoxslt:date_diff('format', 'YYYY-MM-DD', 'YYYY-MM-DD', \$_XDOLocale, \$_XDOTIMEZONE)?></code> where format is the time value for which the difference is to be calculated. Valid values are:</p> <ul style="list-style-type: none"> • y - for year • m - for month • w - for week • d - for day • h - for hour • mi - for minute • s - for seconds • ms - for milliseconds <p>Example: <code><?xdoxslt:date_diff('y', '2000-04-08', '2001-05-01', \$_XDOLocale, \$_XDOTIMEZONE)?></code> returns 1</p> <p>Example: <code><?xdoxslt:date_diff('m', '2001-04-08', '2000-02-01', \$_XDOLocale, \$_XDOTIMEZONE)?></code> returns -14</p> <p>Example: <code><?xdoxslt:date_diff('d', '2006-04-08', '2006-04-01', \$_XDOLocale, 'America/Los_Angeles')?></code> returns -7</p> |
| sec_diff | <code><?xdoxslt:sec_diff('2000-04-08T20:00:00', '2000-04-08T21:00:00', \$_XDOLocale, \$_XDOTIMEZONE)?></code> | <p>This function provides a method to get the difference between two dates in seconds in the given locale. The dates must be in "yyyy-MM-dd'T'HH:mm:ss". This function supports only Gregorian calendar. Example: <code><?xdoxslt:sec_diff('2000-04-08T20:00:00', '2000-04-08T21:00:00', \$_XDOLocale, \$_XDOTIMEZONE)?></code> returns 3600</p> |
| get_day | <code><?xdoxslt:get_day('2000-04-08', \$_XDOLocale)?></code> | <p>This function provides a method to get the day value of a date in yyyy-MM-dd format in the given locale. This function supports only the Gregorian calendar. Example: <code><?xdoxslt:get_day('2000-04-08', \$_XDOLocale)?></code> returns 8</p> |

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------|---|---|
| get_month | <? xdoxslt:get_month('2000-04-08', \$_XDOLOCALE)?> | This function provides a method to get the month value of a date in yyyy-MM-dd format in the given locale. This function supports only the Gregorian calendar. Example: <? xdoxslt:get_month('2000-04-08', \$_XDOLOCALE)?> returns 4 |
| get_year | <? xdoxslt:get_year('2000-04-08', \$_XDOLOCALE)?> | This function provides a method to get the year value of a date in yyyy-MM-dd format in the given locale. This function supports only the Gregorian calendar. Example: <? xdoxslt:get_year('2000-04-08', \$_XDOLOCALE)?> returns 2000 |
| month_name | <?xdoxslt:month_name(1, 0, \$_XDOLOCALE)?> | This function provides a method to get the name of the month in the given locale. This function supports only the Gregorian calendar. The syntax for this function is: <?xdoxslt:month_name(<i>month</i> , [<i>abbreviate?</i>], \$_XDOLOCALE)?> where <i>month</i> is the numeric value of the month (January = 1) and [<i>abbreviate?</i>] is the value 0 for do not abbreviate or 1 for abbreviate. Example: <?xdoxslt:month_name(12, 1, 'fr-FR')?> returns dec. Example" <? xdoxslt:month_name(1, 0, \$_XDOLOCALE)?> returns January |
| maximum | <? xdoxslt:maximum(ELEMENT_NAME)?> | Returns the maximum value of the element in the set. |
| abs | <?xdoxslt:abs(-123.45)?> | Returns the absolute value of the number entered. Example: <?xdoxslt:abs(-123.45)?> Returns: 123.45 |
| chr | <?xdoxf:chr(<i>n</i>)?> | CHR returns the character having the binary equivalent to <i>n</i> in either the database character set or the national character set. |
| ceil | <?xdoxf:ceil(<i>n</i>)?> | CEIL returns smallest integer greater than or equal to <i>n</i> . |
| floor | <?xdoxf:floor(<i>n</i>)?> | FLOOR returns largest integer equal to or less than <i>n</i> . |
| round (SQL function) | <?xdoxf:round (<i>number</i> [, <i>integer</i>])?> | ROUND returns <i>number</i> rounded to <i>integer</i> places right of the decimal point. If <i>integer</i> is omitted, then <i>number</i> is rounded to 0 places. <i>integer</i> can be negative to round off digits left of the decimal point. <i>integer</i> must be an integer. Example: <? xdoxf:round (2.777)?> returns 3 Example: <? xdoxf:round (2.777, 2)?> returns 2.78 |

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------|---|--|
| round (XSLT function) | <code><?xdoxslt:round (number [, integer])?></code> | ROUND returns <i>number</i> rounded to <i>integer</i> places right of the decimal point. If <i>integer</i> is omitted, then <i>number</i> is rounded to 0 places. <i>integer</i> can be negative to round off digits left of the decimal point. <i>integer</i> must be an integer. Example: <code><?xdoxslt:round (2.777)?></code> returns 3 Example: <code><?xdoxslt:round (2.777, 2)?></code> returns 2.78 |
| lower | <code><?xdofx:lower (char)?></code> | LOWER returns <i>char</i> , with all letters lowercase. <i>char</i> can be any of the datatypes CHAR, VARCHAR2, NCHAR, NVARCHAR2, CLOB, or NCLOB. The return value is the same datatype as <i>char</i> . |
| upper | <code><?xdofx:upper (char)?></code> | UPPER returns <i>char</i> , with all letters uppercase. <i>char</i> can be any of the datatypes CHAR, VARCHAR2, NCHAR, NVARCHAR2, CLOB, or NCLOB. The return value is the same datatype as <i>char</i> . |
| length | <code><?xdofx:length(char)?></code> | The "length" function returns the length of <i>char</i> . LENGTH calculates length using characters as defined by the input character set. |
| greatest | <code><?xdofx:greatest (expr [, expr]...)?></code> | GREATEST returns the greatest of the list of <i>exprs</i> . All <i>exprs</i> after the first are implicitly converted to the datatype of the first <i>expr</i> before the comparison. |
| least | <code><?xdofx:least (expr [, expr]...)?></code> | LEAST returns the least of the list of <i>exprs</i> . All <i>exprs</i> after the first are implicitly converted to the datatype of the first <i>expr</i> before the comparison. |
| next_element | <code><?xdoxslt:next_element(current-group(),., '<element-name>')?></code> | Method to get the next element in the current group. Returns the element that occurs after the element named. For example: <code><?xdoxslt:next_element(current-group(),., 'employee')?></code> returns the element that occurs in the current group after "employee". |
| prev_element | <code><?xdoxslt:prev_element(current-group(),., '<element-name>')?></code> | Method to get the previous element in the current group. Returns the element that occurs before the element named. For example: <code><?xdoxslt:prev_element(current-group(),., 'employee')?></code> returns the element that occurs in the current group before "employee". |
| set_array | <code><?xdoxslt:set_array(\$_XDOCTX, '<name of hash table>', n, '<value>')?></code> | Sets a value in a hash table. Syntax is <code><?xdoxslt:set_array(\$_XDOCTX, '<name of hash table>', n, '<value>')?></code> where <code>\$_XDOCTX</code> is required to set the context, <code><name of hash table></code> is the name that you supply for your table <code>n</code> is the index of the hash table <code><value></code> is the value to set in the hash table. For example: <code><?xdoxslt:set_array(\$_XDOCTX, 'Employee', 2, 'Jones')?></code> See <code>get_array</code> below. |

| SQL Statement or XSL Expression | Usage | Description |
|---------------------------------|--|--|
| get_array | <code><?xdoxslt:get_array(\$_XDOCTX, '<name of hash table>', n)?></code> | Returns the value at the specified index of the hash table. Syntax is <code><?xdoxslt:get_array(\$_XDOCTX, '<name of hash table>', n)?></code> where <code>\$_XDOCTX</code> is required to set the context, <code><name of hash table></code> is the name you supplied for your table in <code>set_array</code> <code>n</code> is the index value of the element you want returned. For example, used in conjunction with the <code>set_array</code> example above, <code><?xdoxslt:get_array(\$_XDOCTX, 'Employee', 2)?></code> returns Jones |

The following table shows supported combination functions.

| SQL Statement | Usage |
|--|--|
| <code>(2+3/4-6*7)/8</code> | <code><?xdofx:(2+3/4-6*7)/8?></code> |
| <code>lpad(substr('1234567890',5,3),10,'^')</code> | <code><?xdofx:lpad(substr('1234567890',5,3),10,'^')?></code> |
| <code>decode('a','b','c','d','e','1') instr('321',1,1)</code> | <code><?xdofx:decode('a','b','c','d','e','1') instr('321',1,1)?></code> |

Number-To-Word Conversion

This function enables the conversion of numbers to words for RTF template output.

This is a common requirement for check printing.

The new function is "to_check_number". The syntax of this function is

```
<?xdofx:to_check_number(amount, precisionOrCurrency, caseType, decimalStyle)?>
```

The following table describes the function attributes.

| Attribute | Description | Valid Value |
|---------------------|---|---|
| amount | The number to be transformed. | Any number |
| precisionOrCurrency | For this attribute you can specify either the precision, which is the number of digits after the decimal point; or the currency code, which governs the number of digits after the decimal point. The currency code doesn't generate a currency symbol in the output. | An integer, such as 2; or a currency code, such as 'USD'. |
| caseType | The case type of the output. | Valid values are: 'CASE_UPPER', 'CASE_LOWER', 'CASE_INIT_CAP' |

| Attribute | Description | Valid Value |
|--------------|---|---|
| decimalStyle | Output type of the decimal fraction area. | Valid values are: 'DECIMAL_STYLE_FRACTION1', 'DECIMAL_STYLE_FRACTION2', 'DECIMAL_STYLE_WORD' |

The following table displays the example function as entered in an RTF template and the returned output.

| RTF Template Entry | Returned Output |
|---|--|
| <?xdofx:to_check_number(12345.67, 2)?> | Twelve thousand three hundred forty-five and 67/100 |
| <?xdofx:to_check_number(12345.67, 'USD')?> | Twelve thousand three hundred forty-five and 67/100 |
| <?xdofx:to_check_number(12345, 'JPY', 'CASE_UPPER')?> | TWELVE THOUSAND THREE HUNDRED FORTY-FIVE |
| <?xdofx:to_check_number(12345.67, 'EUR', 'CASE_LOWER', 'DECIMAL_STYLE_WORDS')?> | twelve thousand three hundred forty-five and sixty-seven |

XSL Equivalents

Publisher provides syntax equivalent with XSL.

The following table lists the Publisher simplified syntax with the XSL equivalents.

| Supported XSL Elements | Description | Publisher Syntax |
|-------------------------------------|---|---------------------|
| <xsl:value-of select="name"> | Placeholder syntax | <?name?> |
| <xsl:apply-templates select="name"> | Applies a template rule to the current element's child nodes. | <?apply:name?> |
| <xsl:copy-of select="name"> | Creates a copy of the current node. | <?copy-of:name?> |
| <xsl:call-template name="name"> | Calls a named template to be inserted into/applied to the current template. | <?call:name?> |
| <xsl:sort select="name"> | Sorts a group of data based on an element in the dataset. | <?sort:name?> |
| <xsl:for-each select="name"> | Loops through the rows of data of a group, used to generate tabular output. | <?for-each:name?> |
| <xsl:choose> | Used in conjunction with when and otherwise to express multiple conditional tests. | <?choose?> |
| <xsl:when test="exp"> | Used in conjunction with choose and otherwise to express multiple conditional tests | <?when:expression?> |
| <xsl:otherwise> | Used in conjunction with choose and when to express multiple conditional tests | <?otherwise?> |

| Supported XSL Elements | Description | Publisher Syntax |
|---|--|--|
| <code><xsl:if test="exp"></code> | Used for conditional formatting. | <code><?if:expression?></code> |
| <code><xsl:template name="name"></code> | Template declaration | <code><?template:name?></code> |
| <code><xsl:variable name="name"></code> | Local or global variable declaration | <code><?variable:name?></code> |
| <code><xsl:import href="url"></code> | Import the contents of one stylesheet into another | <code><?import:url?></code> |
| <code><xsl:include href="url"></code> | Include one stylesheet in another | <code><?include:url?></code> |
| <code><xsl:stylesheet xmlns:x="url"></code> | Define the root element of a stylesheet | <code><?namespace:x=url?></code> |

Use FO Elements

You can use most FO elements in an RTF template inside the Microsoft Word form fields.

The FO elements listed in the following table have been extended for use with Publisher RTF templates. The Publisher syntax can be used with either RTF template method.

The full list of FO elements supported by Publisher can be found in the [Supported XSL-FO Elements](#).

| FO Element | Publisher Syntax |
|--|--|
| <code><fo:page-number-citation ref-id="id"></code> | <code><?fo:page-number-citation:id?></code> |
| <code><fo:page-number></code> | <code><?fo:page-number?></code> |
| <code><fo:ANY NAME WITHOUT ATTRIBUTE></code> | <code><?fo:ANY NAME WITHOUT ATTRIBUTE?></code> |

Design Accessible Reports

This topic describes techniques for designing reports to increase accessibility of report output for users with disabilities.

Topics:

- [Design for Accessibility](#)
- [Design Accessible Reports Using RTF Templates](#)
- [Design Accessible Reports Using Publisher Layouts](#)

Design for Accessibility

When creating content for consumption by a wide variety of users, you must plan to provide support for users with various disabilities. Such support is a legal requirement in many locations throughout the world.

You can follow several general guidelines when designing content for consumption by a variety of people with differing abilities. These guidelines apply to any content that you create for Publisher or other applications. You must also be aware of features that are specific to Publisher that ensure that the content that you provide supports accessibility requirements.

This section contains the following topics on designing for accessibility:

- [Obtain General Information](#)
- [Avoid Common Misconceptions](#)
- [Follow General Guidelines for Accessible Content](#)
- [Use the Template Builder to Verify Report Accessibility](#)

Obtain General Information

You can locate information about accessibility across the Information Technology industry in numerous published books.

This guide doesn't intend to duplicate those works. Various standards and legislation are documented, especially as part of the World Wide Web Consortium (W3C) and Section 508 of the United States Rehabilitation Act.

Avoid Common Misconceptions

Many designers make assumptions about technology and accessibility. Some of the more common misconceptions are listed in this section.

- HTML content automatically equals accessible content.
- Accessible tools automatically create accessible content.

- Automated testing tools can reliably determine accessibility.

None of these assumptions is correct. Developers can create non-accessible content using HTML. A tool that can produce accessible content might not do so by default, or might allow a developer to select options that turn off the accessible features within existing accessible content. Automated testing tools do not always interact with content the same way that end users do. As a result, the tools can erroneously report accessible elements as non-accessible. Therefore, accessibility is ultimately the responsibility of the content designer. When creating content, designers must be aware of certain common practices to ensure the content is accessible to all users.

Follow General Guidelines for Accessible Content

Always consider the fact that multiple disabilities exist and that multiple disabilities might manifest in the same individual. You must also remember that there're varying degrees of certain disabilities (such as the various types of color vision deficiency). Your designs must take all these possibilities into account.

This section contains guidelines on the following general areas of design:

- ["Color Selection"](#)
- ["Color Contrast"](#)
- ["Font Selection"](#)

Color Selection

Many different types of color vision deficiency exist, from an inability to see the difference between one common color pair such as red-green (the most common deficiency), all the way to full color blindness where a person can see only varying shades of gray and black. Using only color to convey critical information means that certain users are not fully aware of all the pertinent information about a subject. And, of course, a blind user needs any information conveyed by color to also be present in an alternate textual format.

As a developer, you must not create any content that provides key information by color alone. One example of a non-accessible design is to denote negative numbers solely by coloring the text red. Another example is a typical "stoplight" indicator where the only context information comes from its color — green for good and red for bad.

Use Color with Text

You can use color in designs if you also include another indication of the same information.

For example, you can include a minus sign or parentheses to denote negative numbers in tables and pivots. For stoplight displays, you can add descriptive text or different shaped icons in addition to the color. You can include text such as "Status: good." You can include green circles for "good," yellow triangles for "warning," and red octagons for "bad."

Color Contrast

Because color vision deficiency can also manifest as an inability to distinguish between subtle shades of similar colors, overall color design of all screen elements must provide a large amount of contrast. You should strive to achieve a minimum

of a 4.5:1 color luminosity contrast ratio. For example, use black text on a white background instead of dark gray text on a light gray background.

You can check the following web sites for assistance:

- This site offers a tool that can test for the proper level of contrast:
<http://www.paciellogroup.com/resources/contrast-analyser.html>
- This site offers a tool for viewing how a web site is displayed for individuals with various types of color vision deficiency:
<http://colorfilter.wickline.org/>

Font Selection

Users with low visual acuity often use screen magnification software to make the screen easier to read. The fonts that you use should be readable even when magnified by accessibility tools by as much as 20 times.

Some fonts do not display well when magnified, while others do. For example, the Tahoma font magnifies well.

Use the Template Builder to Verify Report Accessibility

You use the Template Builder for Word to create RTF templates that can generate reports with accessibility features.

The Template Builder also provides an accessibility checker to review the template for features that enhance the accessibility of the report for report consumers who may need assistive technologies to view the report.

For more information, see [Check Accessibility](#).

Design Accessible Reports Using RTF Templates

This section describes the following techniques for designing reports using RTF templates.

- [Avoid Nested Tables or Separated Tables](#)
- [Define a Document Title](#)
- [Define Alternative Text for an Image](#)
- [Define a Table Summary](#)
- [Define a Table Column Header](#)
- [Define a Table Row Header](#)
- [Define a Layout Table](#)
- [Sample Supported Tables](#)
- [Convert Charts to Tables](#)

Avoid Nested Tables or Separated Tables

Avoid using nested tables in a report. For a complex report, try breaking down complex tables into several simple, straightforward tables.

The following figure shows a simple table.

| Header1 | Header2 | Header3 |
|---------|---------|---------|
| | | |
| | | |

The following figure shows an example of a nested table: A table is inserted inside a table-cell.

| Column Header1 | Column Header2 | Column Header3 | | | | |
|----------------|---|----------------|--------------|--|--|--|
| | Cell with inserted table | | | | | |
| | <table border="1"> <tr> <td colspan="2">Nested table</td> </tr> <tr> <td></td> <td></td> </tr> </table> | | Nested table | | | |
| Nested table | | | | | | |
| | | | | | | |
| | | | | | | |

Examples

These are examples of table structures that Publisher does and doesn't support for accessibility.

Nested Tables

Publisher doesn't support accessibility when nested tables are used in a report.

In the following illustration, Publisher can't tell to which column data "C1R1data" belongs.

| | Column header 1 | Column Header2 |
|-------------|-----------------|----------------|
| Row Header1 | C1R1data | C2R1data |
| | C1R2data | C2R2data |

Remove the nested table as shown in the following illustration.

| | Column header 1 | Column Header2 |
|-------------|-----------------|----------------|
| Row Header1 | C1R1data | C2R1data |
| | C1R2data | C2R2data |

Table Headers Must Not Be Separated from the Table Body

To ensure accessibility, table headers must be part of the table they belong to.

The example shown in the following illustration isn't supported because the header, table body and accessibility fields exist in three different tables.

| | | | |
|-----|-----------------|-----------------|-----------------|
| | Column Header 1 | Column Header 2 | Column Header 3 |
| UC1 | Row Header 1 | C1R1Data | C2R1Data |
| | Row Header 2 | C1R2Data | C2R2Data |
| UC2 | Subtotal | Total 1 | Total 2 |

These three tables should be joined into one to support accessibility, as shown in the following illustration.

| | | | |
|-----|-----------------|-----------------|-----------------|
| ACC | Column Header 1 | Column Header 2 | Column Header 3 |
| UC1 | Row Header 1 | C1R1Data | C2R1Data |
| | Row Header 2 | C1R2Data | C2R2Data |
| | Subtotal | Total 1 | Total 2 |

Define a Document Title

You can define a document title. The procedure differs slightly depending on the version of Microsoft Word.

To define a document title in Microsoft Word 2007:

1. Click **Office** and click **Prepare**.
2. Click **Properties** and define the title.

Define Alternative Text for an Image

You can define alternative text for an image in the template.

To define alternative text for an image:

1. Right-click the image.
2. On the menu, click **Format Picture**.
3. On the **Alt Text** tab, enter `alt:` followed by the alternative text and end with a semicolon.

For example,

```
alt:flower picture;
```

Define a Table Summary

Add a table summary to a table by inserting this command.

```
<?table-summary: 'My Table Test '?>
```

in the first column and first row position of the table.

Define a Table Column Header

You can define a table column header. The procedure differs slightly depending on the version of Microsoft Word.

To define a table column header:

1. Select the heading row or rows. The selection must include the first row of the table.
2. On the **Design** tab, in the **Table Style Options** group, select **Header Row**.
3. Right-click the table and select **Table Properties**.
4. In the Table Properties dialog, click the **Row** tab and then select Repeat as Header row at the top of each page.

Define a Table Row Header

To define multiple row headers, use the Publisher command.

```
<?acc-row-header:col_index?>
```

Example Usage:

```
<?acc-row-header:'1,2,4'?> ==> column 1, 2 and 4 will be row-headers.
```

```
<?acc-row-header:'1,4'?> ==> column 1 and 4 will be row-headers.
```

In the following figure, the code behind the ACC field is:

```
ACC Field=<?table-summary:'My Table Test '?><?acc-row-header:'1,2'?>
```

which defines the first two columns as row headers.

| | | | | |
|---------------|---------------|------------------|------------------|------------------|
| ACC | | Column header 1a | Column header 1b | |
| | | Column header 2a | Column header 2b | Column Header 2c |
| Row header 1a | Row header 2a | Data col 1 row 1 | Data col 2 row 1 | Data col 3 row 1 |
| Row header 1b | Row header 2b | Data col 1 row 2 | Data col 2 row 2 | Data col 3 row 2 |
| | Row header 2c | Data col 1 row 3 | Data col 2 row 3 | Data col 3 row 3 |

Sample Supported Tables

The following illustrations display sample tables for which accessibility is supported.

| | | | | |
|---------------|---------------|------------------|------------------|------------------|
| ACC | | Column header 1a | Column header 1b | |
| | | Column header 2a | Column header 2b | Column Header 2c |
| Row header 1a | Row header 2a | Data col 1 row 1 | Data col 2 row 1 | Data col 3 row 1 |
| Row header 1b | Row header 2b | Data col 1 row 2 | Data col 2 row 2 | Data col 3 row 2 |
| | Row header 2c | Data col 1 row 3 | Data col 2 row 3 | Data col 3 row 3 |

| | | | | | |
|---------------|-------------------|------------------|------------------|------------------|------------------|
| ACC | | Column header 1a | Column header 1b | Column header 1c | Column Header 1d |
| | | Column header 2a | Column header 2b | Column header 2c | Column Header 2d |
| Row header 1a | Row header 2a | Data col 1 row 1 | Data col 2 row 1 | Data col 3 row 1 | Data col 4 row 1 |
| | Row header 2b | Data col 1 row 2 | Data col 2 row 2 | Data col 3 row 2 | Data col 4 row 2 |
| | Row header 2c | Data col 1 row 3 | Data col 2 row 3 | Data col 3 row 3 | Data col 4 row 3 |
| | Summary Sub-Total | | | Total 1a | Total 2a |
| Row header 1b | Row header 2d | Data col 1 row 1 | Data col 2 row 1 | Data col 3 row 1 | Data col 4 row 1 |
| | Row header 2e | Data col 1 row 2 | Data col 2 row 2 | Data col 3 row 2 | Data col 4 row 2 |
| | Summary Sub-Total | | | Total 1b | Total 2b |
| Grant Total | | | | Grand-total | Grand-total |


| | | | |
|----------------------|------------------|----|------------------|
| ACC Paramaters Table | | | |
| Row header 1a | Data col 1 row 1 | HA | Data col 3 row 1 |
| Row header 1b | Data col 1 row 2 | HB | Data col 3 row 2 |
| Row header 1c | Data col 1 row 3 | HC | Data col 3 row 3 |

| ACC Paramaters Table | Column header 1a | | Column Header 1c |
|----------------------|------------------|----|------------------|
| Row header 1a | Data col 1 row 1 | HA | Data col 3 row 1 |
| Row header 1b | Data col 1 row 2 | HB | Data col 3 row 2 |
| Row header 1c | Data col 1 row 3 | HC | Data col 3 row 3 |

Convert Charts to Tables

Charts and gauges aren't readable by the visually impaired. In order to make report output accessible for visually impaired users, create a table or cross tab that summarizes the data in the table.

The following figure shows the summarized data in the table. Avoid providing a large table of detail data that isn't summarized appropriately.



Design Accessible Reports Using Publisher Layouts

This section describes the following techniques for designing accessible reports using the Publisher layout editor.

- Define Document Titles
- Define Alternative Text for Images
- Define Summary Text for Tables
- Define Table Row Headers
- Define Text Header Levels

Define Document Titles

You define the title of a report at the same time as you save the report layout. You can also rename the report at a later time.

Define Alternative Text for Images

You can define alternative text for images so that they're describable in accessibility mode.

To define alternative text for an image:

1. Select an image such as a chart.
2. On the **Properties** pane, expand **Misc**.
3. In the **Alternative Text** property, enter the alternative text for the image.

Define Summary Text for Tables

You can define a text summary to describe a table within a report.

To define summary table text:

1. Select a table.
2. On the **Properties** pane, expand **Misc**.
3. In the **Summary** property, enter the table summary text.

Define Table Row Headers

Table row headers summarize each row in a table. The layout editor automatically includes table row headers on all inserted tables. No further action is required.

Define Text Header Levels

You can define text header levels to specify structures within a report.

To define text header levels:

1. Select a text item.
2. On the **Properties** pane, expand **Misc**.
3. In the **Header Level** property, select a value 1 to 6.

Define a Layout Table

You can use layout tables to present information in columns and rows and arrange content without using headers and a table summary.

Use a layout table when you don't need column headers, row headers, IDs, table summary, and other semantics used by a data table. When you've enabled accessibility mode, if you leave the value of the summary property empty or if you

set `<?table-summary:?>` in a table, Publisher sets `role="presentation"` for that table, and specifies that table as a layout table in the HTML output.

To define a layout table:

1. Select a table.
2. On the **Properties** pane, expand **Misc**.
3. In the **Summary** property, make sure the value is empty.

29

Supported XSL-FO Elements

This topic lists the XSL-FO elements that are supported by Publisher in RTF templates.

- [Supported XSL-FO Elements](#)

Supported XSL-FO Elements

The following table lists the XSL-FO elements supported in this release.

For each element the supported content elements and attributes are listed. If elements have shared supported attributes, these are noted as a group and are listed in the subsequent table, Property Groups. For example, several elements share the content element "inline." Rather than list the inline properties each time, each entry notes that "inline-properties" are supported. The list of inline-properties can then be found in the Property Groups table.

| Element | Supported Content Elements | Supported Attributes |
|---------------|--|---|
| basic-link | external-graphic inline leader page-number page-number-citation basic-link block block-container table list-block wrapper marker retrieve-marker | inline-properties external-destination internal-destination |
| bidi-override | bidi-override external-graphic instream-foreign-object inline leader page-number page-number-citation basic-link | inline-properties |

| Element | Supported Content Elements | Supported Attributes |
|-----------------------------------|---|--|
| block | external-graphic inline page-number page-number-citation basic-link block block-container table list-block wrapper | block-properties |
| block-container | block block-container table list-block wrapper | block-properties |
| bookmark-tree | bookmark | N/A |
| bookmark | bookmark bookmark-title | external-destination internal-destination starting-state |
| bookmark-title | N/A | color font-style font-weight |
| conditional-page-master-reference | N/A | master-reference page-position <ul style="list-style-type: none"> • first • last • rest • any • inherit odd-or-even <ul style="list-style-type: none"> • odd • even • any • inherit blank-or-not-blank <ul style="list-style-type: none"> • blank • not-blank • any • inherit |
| external-graphic | N/A | graphic-properties src |

| Element | Supported Content Elements | Supported Attributes |
|-------------------------|---|-----------------------------------|
| flow | block block-container table list-block wrapper | flow-properties |
| inline | external-graphic inline leader page-number page-number-citation basic-link block block-container table wrapper | inline-properties |
| instream-foreign-object | N/A | graphic-properties |
| layout-master-set | page-sequence-master simple-page-master simple-page-master page-sequence-master | N/A |
| leader | N/A | inline-properties |
| list-block | list-item | block-properties |
| list-item | list-item-label list-item-body | block-properties |
| list-item-body | block block-container table list-block wrapper | block-properties |
| list-item-label | block block-container table list-block wrapper | block-properties |
| page-number | N/A | empty-inline-properties |
| page-number-citation | N/A | empty-inline-properties ref-id |

| Element | Supported Content Elements | Supported Attributes |
|-------------------------------------|---|---|
| page-sequence | static-content flow | inheritable-properties id master-reference initial-page-number <ul style="list-style-type: none"> • auto • <page-number> force-page-count <ul style="list-style-type: none"> • auto • end-on-even • end-on-odd • end-on-even-layout • end-on-odd-layout • no-force • inherit format |
| page-sequence-master | single-page-master-reference repeatable-page-master-reference repeatable-page-master-alternatives | master-name |
| region-after | N/A | side-region-properties |
| region-before | N/A | side-region-properties |
| region-body | N/A | region-properties margin-properties-CSS column-count |
| region-end | N/A | side-region-properties |
| region-start | N/A | side-region-properties |
| repeatable-page-master-alternatives | conditional-page-master-reference | maximum-repeats |
| repeatable-page-master-reference | N/A | master-reference maximum-repeats |
| root | bookmark-tree layout-master-set page-sequence | inheritable-properties |

| Element | Supported Content Elements | Supported Attributes |
|------------------------------|--|--|
| simple-page-master | region-body region-before region-after region-start region-end | margin-properties-CSS master-name page-height page-width reference-orientation <ul style="list-style-type: none"> • 0 • 90 • 180 • 270 • -90 • -180 • -270 • 0deg • 90deg • 180deg • 270deg • -90deg • -180deg • -270deg • inherit writing-mode <ul style="list-style-type: none"> • lr-tb |
| single-page-master-reference | N/A | master-reference |
| static-content | block block-container table wrapper | flow-properties |
| table | table-column table-header table-footer table-body | block-properties |
| table-body | table-row | inheritable-properties id |
| table-cell | block block-container table list-block wrapper | block-properties number-columns-spanned number-rows-spanned |
| table-column | N/A | inheritable-properties column-number column-width number-columns-repeated |
| table-footer | table-row | inheritable-properties id |

| Element | Supported Content Elements | Supported Attributes |
|--------------|---|------------------------------|
| table-header | table-row | inheritable-properties id |
| table-row | table-cell | inheritable-properties id |
| wrapper | inline page-number page-number-citation basic-link block block-container table wrapper | inheritable-properties id |

Property Groups Table

These properties support XSL-FO elements.

The following table lists the supported properties belonging to the attribute groups defined in [Supported XSL-FO Elements](#).

| Property Group | Properties |
|------------------|---|
| area-properties | clip overflow (visible, hidden) reference-orientation <ul style="list-style-type: none"> • 0 • 90 • 180 • 270 • -90 • -180 • -270 • 0deg • 90deg • 180deg • 270deg • -90deg • -180deg • -270deg • inherit writing-mode (lr-tb, rl-tb, lr, rl) baseline-shift (baseline, sub, super) vertical-align |
| block-properties | inheritable-properties id |

| Property Group | Properties |
|--|---|
| border-padding- background-properties | background-color background-image background-position-vertical background-position-horizontal border border-after-color border-after-style (none, dotted, dashed, solid, double) border-after-width border-before-color border-before-style (none, solid) border-before-width border-bottom border-bottom-color border-bottom-style (none, dotted, dashed, solid, double) border-bottom-width border-color border-end-color border-end-style (none, dotted, dashed, solid, double) border-end-width border-left border-left-color border-left-style (none, dotted, dashed, solid, double) border-left-width border-right border-right-color border-right-style (none, dotted, dashed, solid, double) border-right-width border-start-color border-start-style (none, dotted, dashed, solid, double) border-start-width border-top border-top-color border-top-style (none, dotted, dashed, solid, double) border-top-width border-width padding padding-after padding-before padding-bottom padding-end padding-left padding-right padding-start padding-top |

| Property Group | Properties |
|------------------------------------|---|
| box-size-properties | height width |
| character-properties | font-properties text-decoration |
| empty-inline-properties | character-properties border-padding-background-properties id color |
| flow-properties | inheritable-properties id flow-name |
| font-properties | font-family font-size font-style (normal, italic, oblique) font-weight (normal, bold) table-omit-header-at-break (TRUE, FALSE, inherit) table-omit-footer-at-break (TRUE, FALSE, inherit) |
| graphic-properties | border-padding-background-properties margin-properties-inline box-size-properties font-properties keeps-and-breaks-properties-atomic id |
| inheritable-properties | border-padding-background-properties box-size-properties margin-properties-inline area-properties character-properties line-related-properties leader-properties keeps-and-breaks-properties-block color absolute-position <ul style="list-style-type: none"> • auto • absolute • fixed • inherit |
| inline-properties | inheritable-properties id |
| keeps-and-breaks-properties-atomic | break-after (auto, column, page) break-before (auto,column) keep-with-next keep-with-next.within-page |
| keeps-and-breaks-properties-block | keeps-and-breaks-properties-inline |

| Property Group | Properties |
|------------------------------------|--|
| keeps-and-breaks-properties-inline | keeps-and-breaks-properties-atomic keep-together keep-together.within-line keep-together.within-column keep-together.within-page |
| leader-properties | leader-pattern (rule, dots) leader-length leader-length.optimum (dotted, dashed, solid, double) rule-thickness |
| line-related-properties | text-align (start, center, end, justify, left, right, inherit) text-align-last (start, center, end, justify, left, right, inherit) text-indent linefeed-treatment (ignore, preserve, treat-as-space, treat-as-zero-width-space, inherit) white-space-treatment (ignore, preserve, ignore-if-before-linefeed, ignore-if-after-linefeed, ignore-if-surrounding-linefeed, inherit) white-space-collapse (FALSE, TRUE, inherit) wrap-option (no-wrap, wrap, inherit) direction (ltr) |
| margin-properties-block | margin-properties-CSS space-after space-after.optimum space-before space-before.optimum start-indent end-indent |
| margin-properties-CSS | margin margin-bottom margin-left margin-right margin-top |
| margin-properties-inline | margin-properties-block space-start space-start.optimum space-end space-end.optimum position <ul style="list-style-type: none"> • static • relative • absolute • fixed • inherit top left |

| Property Group | Properties |
|------------------------|--|
| region-properties | border-padding-background-properties area-properties region-name |
| side-region-properties | region-properties extent |

Generate PDF/A and PDF/X Output

This topic describes how to generate PDF/A and PDF/X output from Publisher.

Topics:

- [Generate PDF/A Output](#)
- [Generate PDF/X output](#)

Generate PDF/A Output

PDF/A is a variation of PDF file format designed for the long-term archiving of electronic documents. Some governments and standards organizations require PDF/A to ensure preservation of documents. A PDF/A file is a PDF file viewable by PDF viewers such as Adobe Reader, but the PDF/A file must follow additional requirements specified in the ISO standard. These requirements specify both required objects and features not supported for long-term archiving. You can generate the PDF/A-1A, PDF/A-1B, PDF/A-2A, or PDF/A-2B variation of the PDF/A standard.

Requirements and Limitations

PDF/A output has specified requirements and limitations.

Limitations and requirements for generating PDF/A output:

- **Supported template types:** RTF, FO, XPT, and XSL.
- **Font requirements:** By default, all fonts in the template are replaced with Albany fonts in the output. To use a different font in the output, specify the font mappings in the report configuration. If Albany fonts aren't available in the JVM font directory, and you haven't specified a font mapping, the output won't be a valid PDF/A file. In this case, Helvetica font is used.
- **PDF features not supported in PDF/A documents:**
 - All audio and video content, including Flash embedding
 - Transparency (transparent colors render as opaque). Use PDF/A-2B to support transparency.
 - Encryption
- **Reprocessing by utilities isn't supported:** Reprocessing PDF/A file using the PDFBookBinder, PDFDocMerger, or PDFSignature (digital signature) utilities isn't supported. The reprocessed PDF file may lose conformance to the PDF/A standard.
- **Required report configuration properties:** The report run-time properties must be set as shown in the following table.

| Property | Required Setting |
|--|----------------------------|
| pdf-version | Must be no higher than 1.4 |
| Enable PDF Security (pdf-security) | Must be set to false |
| Encryption Level (pdf-encryption-level) | Must be set to 0 |
| pdf-font-embedding | Must be set to true |

Formatting properties specific to PDF/A output can be set in the Report Properties dialog. For more information, see [PDF/A Output Properties](#).

Additional Resources

For more information about the PDF/A standard, refer to the Adobe website. Refer also to the iso.org website for articles 'Use of PDF 1.4 (PDF/A-1)' and 'Addendum Cor 1:2007'.

Generate PDF/X output

PDF/X is a collection of ISO standards that defines methods for the exchange of digital graphic data using PDF to ensure predictable and consistent printing in a professional print environment.

A PDF/X document is a PDF file viewable by PDF readers such as Adobe Reader, but it follows an additional set of rules defined by the ISO specifications. These rules specify both required objects and features not supported for graphics exchange. The PDF/X standard follows strict rules in color management. Publisher supports the PDF/X-1a:2003 variation of the PDF/X standard.

Prerequisites

The generation of PDF/X output requires that you obtain the International Color Consortium (ICC) profile data file and place it under `<bi publisher repository>/Admin/Configuration`.

The ICC profile is a binary file describing the color characteristics of the intended output device. For production environments, the color profile may be provided by your print vendor or by the printing company that prints the generated PDF/X file. An example of an ICC profile data file is: CoatedFOGRA27.icc.

Profile data is also available from Adobe (<http://www.adobe.com/support>) or colormangement.org (<http://www.colormangement.org/>).

Requirements and Limitations

PDF/X output has specified requirements and limitations.

The following lists limitations of and requirements for generating PDF/X output:

- Supported template types: The following template types support the generation of PDF/X: RTF, FO, XPT, and XSL. There're no additional template requirements to generate PDF/X.

- Color requirements: The color data in the template (text color, images, and SVG) is stored as RGB data, but at the time the PDF/X file is generated, the color data is converted to CMYK using an ICC profile that you must provide to Publisher. Specify the ICC profile using the PDF/X ICC Profile Data property. See the following table.
- PDF features not supported in PDF/X documents:
 - Transparency (transparent colors render as opaque)
 - Encryption
- Font requirements: By default, all fonts are replaced with Albany fonts. To use a different font in the output, specify the font mappings in the report configuration. If Albany fonts aren't available in the JVM font directory and you haven't specified a font mapping (that is, there isn't an embeddable font available), the output won't become a valid PDF/X file. In this case, Helvetica font is used.
- Reprocessing by Publisher utilities isn't supported: Reprocessing of the PDF/X file using the Publisher utilities PDFBookBinder, PDFDocMerger, or PDFSignature isn't supported. The reprocessed file becomes a regular PDF file and may lose conformance to the PDF/X standard.
- Required report configuration properties: The report run-time properties must be set as shown in the following table.

| Property | Required Setting |
|--|-----------------------------|
| pdf-version | Must be no higher than 1.4. |
| Enable PDF Security (pdf-security) | Must be set to false. |
| Encryption Level (pdf-encryption-level) | Must be set to 0. |
| pdf-font-embedding | Must be set to true. |

Formatting properties specific to PDF/X output can be set in the Report Properties dialog. Of the formatting properties, the following two are required:

| Property | Description | Valid Values |
|-----------------------------------|---|--|
| PDF/X ICC Profile Data | The name of the ICC profile data file placed under <Publisherrepository>/Admin/Configuration. | ICC profile data file name, for example: CoatedFOGRA27.icc |
| PDF/X output condition identifier | The name of one of the standard printing conditions registered with ICC. The list of standard CMYK printing conditions to use with PDF/X-1a is provided on the following ICC website: http://www.color.org/chardata/drsection1.xalter . | A valid "Reference name," for example: FOGRA43 |

For more information, see [PDF/X Output Properties](#).

Additional Resources

For more information about the PDF/X standard, see these resources.

- [Application Notes for PDF/X Standards](#)
- [ISO 15930-4:2003](#) Graphic technology -- Prepress digital data exchange using PDF -- Part 4: Complete exchange of CMYK and spot color printing data using PDF 1.4 (PDF/X-1a)

31

Generate Accessible PDF Output

An accessible PDF output is a structured document that includes a document title and the PDF tags. The paragraph, link, image, table, and list elements are tagged in accessible PDF documents.

Prerequisites

Set the property for generating accessible PDF output at the report-level for specific reports or at the global level for all PDF outputs. See [Configure Accessible PDF Output for Reports](#).

Requirements and Limitations

| Element | Requirements | Limitations |
|-------------------|--|--|
| Text | Format the text using heading styles such as heading1, heading2, and heading3. | Don't justify text because screen readers might not correctly find the spaces between words when the line is justified. |
| Table | Tables must have headers. The PDF/UA standard recommends adding the headers. Adobe Acrobat reports a table without header as an error. If you add a table summary, the summary will be added as a table attribute in PDF documents. However, the PDF/UA format doesn't require a summary. | Don't use a table for layout purpose. Whether a table is used as a data table or as a layout table, all tables are tagged as tables. Don't use colspan or rowspan. The PDF/UA format allows spans, but Acrobat reports tables with spans as an error (irregular table). |
| Image | Add alternate text to every image. | NA |
| Document | Create bookmarks when you expect the output to contain more than 21 pages. The PDF/UA format doesn't require bookmarks, but Acrobat reports a large document without bookmarks as an error. Add the document title. You can add a title in the template, or you can set the title using the pdf-document-title runtime parameter. | NA |
| Header and footer | Use headers and footers only for providing the pagination information. | Don't include any information apart from the page numbers in the header/footer section. The headers and footers are marked as "Artifacts" and these artifacts aren't read by the screen readers as per the ISO 14289 7.4 standard. |

| Element | Requirements | Limitations |
|----------------|--|--|
| Static content | NA | Don't include a table, list, or link element in the static content. The entire static content area will be tagged as a single paragraph. |
| Graphics | NA | Don't use the Word Shape feature of RTF in the RTF template. Some of the Word Shape objects marked as artifacts instead of figures can't be read by the screen readers. |
| Font | Map the Symbol font to a TrueType font to avoid the usage of the Adobe core symbol font in the output. | Don't use the Dingbat font because there's no equivalent TrueType font. The Adobe accessibility checker displays a warning message when you use fonts that don't have encoding parameters. |

PDF/UA-1 (ISO 14289-1:2014) is a standard for universal accessibility. The PDF/UA format requires all the fonts used in the output to be embedded in the document. Hence, the PDF/UA formatted report output might look different from the original report and the file size of the PDF/UA formatted output might be more than the original report.

Configure Accessible PDF Output for Reports

You can configure all reports or specific reports to generate accessible PDF output.

To configure accessible PDF output for reports, choose one of these methods:

- Configure the report property to make the PDF output of a report accessible.
 1. Navigate to the report in the catalog.
 2. Click **Edit** to launch the Report Editor.
 3. Click **Properties** to open the Report Properties dialog.
 4. Click the **Formatting** tab and scroll down.
 5. Set the **Make PDF output accessible** property to `true`.
- Configure the output format to make the PDF output of a report accessible.
 1. Navigate to the report in the catalog.
 2. Click **Edit** to launch the Report Editor.
 3. Click **View a List** and select **PDF/UA** from the **Output Formats** list.

You can select PDF/UA output format when you view the report in Online viewer or when you schedule a report.
- Make the PDF outputs of all online reports and scheduled reports accessible.
 1. On the Administration page, under Runtime Configuration, select **Properties**.
 2. Set the **Make PDF output accessible** property to `true`.

Generate CSV Output

This topic describes how to generate a CSV output for large reports.

To output a report that includes millions of rows, select to output the report only in CSV format. When you select only CSV format for the output of a large report, the data processor directly generates the CSV output without generating an XML file, which reduces the likelihood of out-of-memory issues.

Requirements

To generate the CSV output for a large volume of data, make sure you:

- Create a data set using SQL query.
- Set the **Enable CSV Output** property in the Data Model Properties page.
- Select only the **Data (CSV)** output format for the report.
- Deselect the **Auto Run** and **Run Report Online** options for the report.
- Deselect the **Save Data for Republishing** option in the Output tab, if you are scheduling the report.

Limitations

The data engine cannot generate a CSV output when:

- The SQL query contains the CLOB/BLOB columns
When a query includes CLOB columns, the data processor cannot generate the CSV output because the LOB might be XML data or non-structured data. Converting the LOB columns to flatten a CSV format doesn't scale. This type of conversion requires complex code changes that are similar to embedding a formatting engine inside the data engine.
- Data model has a complex parent-child data set hierarchy with multiple groups
When a data model has multiple data sets with complex parent - child links, the data engine cannot generate CSV output.
- The SQL query contains the DFF/EFF columns
When a query includes DFF (Descriptive Flexfield) or EFF (Extensible Flexfield) columns, the data processor cannot generate a CSV output. Each DFF or EFF column is treated as a nested sub-group in the query, which results in nested XML data. You can't directly flatten nested XML data to a CSV file.
- The data model has both SQL and Non-SQL data sets
When a data model contains a mix of SQL and Non-SQL data sets (Non-Standard data sets such as web service, HTTP, and XML), the data processor cannot generate a CSV output.
- The data model has a non-standard SQL query
When a data model has a non-standard query such as a procedure or a function that returns a reference, the data processor cannot directly generate a CSV

output. The non-standard queries returning nested XML structure cannot be handled inside the data engine.

- The scheduled report has multiple output formats

If you select multiple output formats for the scheduled report, the data processor doesn't generate the CSV output.

- The scheduled report uses bursting

Splitting and delivering data requires raw XML data. The data engine cannot generate the CSV format for bursting reports.

Extract a Large Volume of Data

You can use Publisher reports to extract a large volume of data.

To extract a large volume of data and generate a CSV output:

1. Create a data model with a single SQL Query type data set.
 - a. If you have multiple queries, combine all the queries into a single query using the WITH clause.

For example. If you have these Q1, Q2, and Q3 data sets:

```
Q1 data set : SELECT DEPARTMENT_ID, DEPARTMENT_NAME, LOCATION FROM
DEPARTMENTS
```

```
Q2 data set: SELECT EMPLOYEE_ID, FIRST_NAME, LAST_NAME, JOB, SALARY FROM
EMPLOYEES Q3-dataset: SELECT JOB_ID, MAX_SALARY, MIN_SALARY FROM JOBS
```

```
Q3 data set: SELECT JOB_ID, MAX_SALARY, MIN_SALARY FROM JOBS
```

Instead of linking the Q1, Q2, and Q3 data sets to form a parent-child hierarchy, create a single data set combining the queries of Q1, Q2, and Q3 data sets as shown below:

```
WITH Q1 AS(SELECT DEPARTMENT_ID, DEPARTMENT_NAME, LOCATION FROM
DEPARTMENTS) ,
Q2 AS (SELECT EMPLOYEE_ID, FIRST_NAME, JOB_ID AS EMP_JOB_ID, SALARY
FROM EMPLOYEES) ,
Q3 AS(SELECT JOB_ID, MAX_SALARY, MIN_SALARY FROM JOBS)
SELECT Q1.*, Q2.*, Q3.* FROM Q1, Q2, Q3
```

- b. Click **View Data**.
 - c. Click **Save As Sample Data**.
2. Edit the data model properties to select the **Enable CSV Output** option.
 3. Save the data model.
 4. Create a report based on the data model.
 5. Edit the report properties and deselect the **Auto Run** and **Run Report Online** options.

If you run the report online, you might encounter performance issues while the large volume of data is processed.

6. Click **List View** and select only the **Data (CSV)** output format for the report..

7. Save the report.
8. Schedule the report.

Make sure you deselect the **Save Data for Republishing** option in the Output tab.

9. Submit the job to extract data.
10. After the report job completes successfully, download the output from the **Report Job History** page.

PDF Version Support

This topic describes BI Publisher's support for PDF specification 1.7 in its processing utilities.

Topics:

- [About PDF Version Support](#)
- [Supported Utilities](#)
- [Limitations](#)

About PDF Version Support

The output PDF version is based on the input PDF version.

The input PDF version defines the output PDF version as follows:

- PDF version 1.4 and earlier generates PDF 1.4
- PDF version 1.5 and later generates the same output version as the input version

Supported Utilities

Several utilities support PDF documents and templates.

The utilities that support PDF 1.7 are:

- **FormProcessor** – merges a PDF template with XML data to produce PDF document output.
- **PDFDocMerger** – provides optional processing of PDF files to merge documents, add page numbering, and set watermarks.
- **PDFSignature** – creates signed PDF documents by processing unsigned PDF documents with a signature field name and a password-protected Personal Information Exchange (PFX) file.

Limitations

This section describes the limitations of Publisher's support for the PDF 1.7 standard.

It includes the following topics:

- [Limitations That Apply to All PDF Utilities](#)
- [FormProcessor Limitations](#)
- [PDFDocMerger and PDFBookBinder Limitations](#)
- [PDFSignature Limitations](#)

Limitations That Apply to All PDF Utilities

PDF utilities have limited functionality in Publisher.

Limitations that apply to all the Publisher PDF utilities are:

- Secured PDF documents can't be used as input to any Publisher PDF utility.
- PDF documents generated by Publisher do not support most accessibility features.
- Unicode passwords are not supported.
- PDF utilities may not work properly with input PDFs that contain 3-D artwork and input PDF documents formatted as a presentation (slideshow).

FormProcessor Limitations

Limitations that apply to the FormProcessor utility are listed in this section.

- XFA Forms (Adobe's XML Forms Architecture) isn't supported.
- Portable collection (portfolio) isn't supported.
- Tagged PDF documents will lose tags after processing.

PDFDocMerger and PDFBookBinder Limitations

Limitations apply to the PDFDocMerger and PDFBookBinder utilities.

Limitations include:

- The output PDF document version is determined based on the first input PDF document.
- XFA Forms (Adobe's XML Forms Architecture) isn't supported.
- Portable collection (portfolio) isn't supported.
- Tagged PDF documents will lose tags after merging.
- The following objects are preserved in the output, but the navigation panel shows only objects contained in the first input PDF document.
 - Bookmark
 - Attachment
 - Layer
 - Print characteristics (such as paper selection, handling, page range, copies, and scaling)

PDFSignature Limitations

Limitations apply to the PDFSignature utility.

Limitations include:

- Object signature isn't supported.
- Selective encryption of embedded files isn't supported.

- AES (Advanced Encryption Standard) isn't supported.
- PDFSignature may not work correctly with the digital signature constraints and certificate constraints described in Section 1.2.5 of the PDF 1.7 specification. For more information about the PDF 1.7 specification, see the Adobe website at http://www.adobe.com/devnet/pdf/pdf_reference.html

Test Templates with Template Viewer

This topic describes how to use the Template Viewer tool.

Topics:

- [About Template Viewer](#)
- [Debug Templates](#)
- [Monitor Memory Usage](#)
- [Profile XSLT](#)
- [Validate XML Documents](#)
- [Test Fonts](#)


About Template Viewer

Template Viewer is a Publisher desktop tool for testing templates.

You can download the Publisher desktop tools from the Oracle Analytics Server Home page or from the Publisher Home page. Use the Start menu to launch the Template Viewer installed on your Windows machine.

With Template Viewer desktop tool, you can:

- Debug templates and sub-templates. See [Debug Templates](#).
- Monitor memory used when a template is applied to a data file. See [Monitor Memory Usage](#).
- Profile XSLT to view the time consumed by an XSL code. See [Profile XSLT](#).
- Test the fonts used in a template. See [Test Fonts](#).
- Test translation of a template by selecting the XLIFF file related to the template.
- Export the output files to a selected location by using the **Export** option.
- Run the XSLT processor to validate XML documents. See [Validate XML Documents](#).



Debug Templates

If you don't see the expected results in the template preview window, you can use Template Viewer to enable trace settings and view the debug messages to solve the problem.

You can also save and view the intermediate XSL file generated after the sample data and template are merged in the XSL-FO processor. If you already use XSL, you'll quickly learn the debugging features in Template Viewer.

To preview template with Template Viewer and view log messages:

1. Open Template Viewer:
From the Windows desktop, click **Start**, then **Programs**, then **Oracle BI Publisher Desktop**, then **Template Viewer**.
2. Click **Browse** to locate the working directory that contains the sample data file and template file. The data file and template file must reside in the same folder.
3. In the **Files** tab, select the appropriate option. For example, if you're testing a .xsl template, select **Excel Templates**. The **Data** and **Template** regions display the data files and template files present in the directory
4. Click the appropriate data and template files to select them.
5. Select the log (debug) level.
6. If you want to test a sub-template, browse and specify the sub-template in the **Style Template File** field.
7. If required, set the report parameters in the **Setting (Default)** tab.

8. From the **Output Format** list, select the output format. For example, Excel.
9. Click **Start Processing**.

The Template Viewer merges the selected data with the selected master template and sub-template and opens the appropriate viewer. View the log messages in the message box.

10. To view the generated XSL:
 - a. Select the data and template files and choose Excel output.
 - b. Select **Tools**, then **Generate XSL file from**, then **Excel Template**.
 - c. At the prompt, save the generated XSL file.
 - d. Navigate to the saved location and open the XSL file in an appropriate viewer.

Generate Reports in PDF/A, PDF/X, and PDF/UA Formats

You can generate reports in PDF/A, PDF/X, and PDF/UA formats in Template Viewer.

To generate reports in PDF/A, PDF/X, and PDF/UA formats in Template Viewer:

1. Set the font directory to embed fonts in the document.
2. Configure the PDF/A output by setting the properties. Add the key and value pairs for PDF/A output.
3. Add the optional property settings for PDF/A and PDF/X outputs.

Set the Font Directory

You must set the font directory for Template Viewer.

To set the font directory for Template Viewer:

1. Navigate to the c:\Program Files\Oracle\BI Publisher\BI Publisher Desktop\TemplateViewer directory.
2. Run the following command:

```
java -jar -DXDO_FONT_DIR="..\Template Builder for Word\fonts"
tmplviewer.jar
```

Add Key and Value Pairs for PDF/A Output

Add the key and value pairs for PDF/A output

To add the key and value pairs for PDF/A output:

1. Open Template Viewer.
2. From the Windows desktop, click **Start, Programs**, Oracle Analytics Publisher Desktop, and then **Template Viewer**.
3. Navigate to the **Setting (Default)** tab.
4. Optional: Load the xdo.cfg configuration file containing the font mapping.
If you don't specify the font mapping, the default font is TrueType.
5. Add the following key and value pairs:

- `pdfx-dest-output-profile-data`: *File path of the ICC profile data file*
For PDF/X, ICC profile data file must be CMYK. For example, Coated Fogra 39.
- `pdfx-output-condition-identifier`: *Name of one of the standard printing conditions registered with ICC*
For example, FOGRA39.

Add the Optional Property Settings for PDF/A and PDF/X Outputs

Add the optional property settings for PDF/A and PDF/X outputs.

To add the optional property settings for PDF/A and PDF/X outputs:

1. Open Template Viewer.
2. From the Windows desktop, click **Start, Programs, Oracle BI Publisher Desktop**, and then **Template Viewer**.
3. Navigate to the **Setting (Default)** tab.
4. Optional: Load the `xdo.cfg` configuration file containing the font mapping.

If you don't specify the font mapping, the default font is TrueType.

5. For a PDF/A output, add the required optional property settings.

Add the key and value pairs for the PDF/A properties you want to set. For the key, use the internal names of the PDF/A properties mentioned in the documentation for configuring the runtime property for PDF/A output.

6. For a PDF/X output, add the required optional property settings.

Add the key and value pairs for the PDF/X properties you want to set. For the key, use the internal names of the PDF/X properties mentioned in the documentation for configuring the runtime property for PDF/X output.

Monitor Memory Usage

In Template Viewer, you can track the memory used when a template is applied to a data file.

To monitor the memory used by a template:

1. Select the data file and template.
2. Select the **Monitor Memory Usage** option.
3. Select the output format from the **Output Format** list.
4. Click **Start Processing**.

In the directory that you selected, Template Viewer generates a `.csv` file with a name that starts with `MemMonLong`. This log file stores information about the memory used before and after garbage collection. Memory is monitored in regular time intervals that are measured in seconds.

Profile XSLT

You can use Template Viewer to profile XSLT. The XSL template includes time-logging commands that enable time measurements and act as a profiling tool. When you run a template, the log.csv file is generated to record the time for the running of the XSL code.

To profile XSLT in Template Viewer:

1. Open Template Viewer.
From the Windows desktop, click **Start**, then **Programs**, then **Oracle BI Publisher Desktop**, then **Template Viewer**.
2. Browse and select the working directory.
3. Select the XML data file and RTF template file to generate XSL.
4. Select **Tools**, then **Generate XSL file from**, then **Inject Profiling into XSL**.
5. Select **RTF Template** to generate XSL.
6. Select Excel from the **Output Format** list.
7. Click **Start Processing**.
8. Open the file using Excel.
9. Note the three areas that consume the most time.

Validate XML Documents

You can validate an XML document to ensure that it includes the proper code.

To validate an XML document by using an XSL template:

1. Open Template Viewer.
From the Windows desktop, click **Start**, then **Programs**, then **Oracle BI Publisher Desktop**, then **Template Viewer**.
2. Browse and select the working directory.
3. Select the XML data file.
4. Select an XSL template for testing the XML document.
5. Select **Run XSLT** from the **Output Format** list.

Test Fonts

You can test fonts to ensure that your reports are displayed correctly.

You must ensure that the required fonts are mapped correctly, to avoid issues such as Roman alphabet characters not being displayed. You must ensure that the font family name in the font mapping exactly matches the name that is used in the template.

1. Open Template Viewer.
From the Windows desktop, click **Start**, then **Programs**, then **Oracle BI Publisher Desktop**, then **Template Viewer**.

2. Navigate to the **Setting (Default)** tab.
3. Load the xdo.cfg configuration file containing the font mapping.

For example, the Arial font is set in the xdo.cfg file as follows:

```
<font family="Arial" style="italic" weight="bold">  
  <truetype path="D:\fonts\arialbi.ttf" />  
</font>
```

4. Reload the xdo.cfg configuration file if you make any changes to it.
5. Run the report.
 - a. In the **Files** tab, select the data file and template for testing the fonts.
 - b. From the **Output Format** list, select the output format.
 - c. Click **Start Processing**
 - d. View the report to verify if the fonts display correctly.