Oracle® Banking Branch

Teller User Guide



14.8.0.0.0
G35656-01
April 2025

Oracle Banking Branch Teller User Guide, 14.8.0.0.0

G35656-01

Copyright © 2021, 2025, Oracle and/or its affiliates.

This software and related documentation are provided under a license agreement containing restrictions on use and disclosure and are protected by intellectual property laws. Except as expressly permitted in your license agreement or allowed by law, you may not use, copy, reproduce, translate, broadcast, modify, license, transmit, distribute, exhibit, perform, publish, or display any part, in any form, or by any means. Reverse engineering, disassembly, or decompilation of this software, unless required by law for interoperability, is prohibited.

The information contained herein is subject to change without notice and is not warranted to be error-free. If you find any errors, please report them to us in writing.

If this is software, software documentation, data (as defined in the Federal Acquisition Regulation), or related documentation that is delivered to the U.S. Government or anyone licensing it on behalf of the U.S. Government, then the following notice is applicable:

U.S. GOVERNMENT END USERS: Oracle programs (including any operating system, integrated software, any programs embedded, installed, or activated on delivered hardware, and modifications of such programs) and Oracle computer documentation or other Oracle data delivered to or accessed by U.S. Government end users are "commercial computer software," "commercial computer software documentation," or "limited rights data" pursuant to the applicable Federal Acquisition Regulation and agency-specific supplemental regulations. As such, the use, reproduction, duplication, release, display, disclosure, modification, preparation of derivative works, and/or adaptation of i) Oracle programs (including any operating system, integrated software, any programs embedded, installed, or activated on delivered hardware, and modifications of such programs), ii) Oracle computer documentation and/or iii) other Oracle data, is subject to the rights and limitations specified in the license contained in the applicable contract. The terms governing the U.S. Government's use of Oracle cloud services are defined by the applicable contract for such services. No other rights are granted to the U.S. Government.

This software or hardware is developed for general use in a variety of information management applications. It is not developed or intended for use in any inherently dangerous applications, including applications that may create a risk of personal injury. If you use this software or hardware in dangerous applications, then you shall be responsible to take all appropriate fail-safe, backup, redundancy, and other measures to ensure its safe use. Oracle Corporation and its affiliates disclaim any liability for any damages caused by use of this software or hardware in dangerous applications.

Oracle®, Java, MySQL, and NetSuite are registered trademarks of Oracle and/or its affiliates. Other names may be trademarks of their respective owners.

Intel and Intel Inside are trademarks or registered trademarks of Intel Corporation. All SPARC trademarks are used under license and are trademarks or registered trademarks of SPARC International, Inc. AMD, Epyc, and the AMD logo are trademarks or registered trademarks of Advanced Micro Devices. UNIX is a registered trademark of The Open Group.

This software or hardware and documentation may provide access to or information about content, products, and services from third parties. Oracle Corporation and its affiliates are not responsible for and expressly disclaim all warranties of any kind with respect to third-party content, products, and services unless otherwise set forth in an applicable agreement between you and Oracle. Oracle Corporation and its affiliates will not be responsible for any loss, costs, or damages incurred due to your access to or use of third-party content, products, or services, except as set forth in an applicable agreement between you and Oracle.

Contents

1 Overview of Oracle Banking Branch

1.1 Prerequisites 1
1.2 About Main Menu 3
1.3 Application Layout 6
1.3.1 Customer Search 6
1.3.2 About Transaction Area 7
1.4 Salient Features 10
1.4.1 About Machine Learning 16
1.4.2 About Virtual Identifier 18
1.4.3 About Oracle Digital Assistant 19
1.4.4 About Amount-Based Signature Verification 22
1.4.5 Advice Generation for Teller Transactions 25
1.4.6 Keyboard Navigation for Transaction Screens 25
1.4.7 About Business Process Codes 26

2 Branch Operations

2.1 TC Denomination Enquiry 2
2.2 Open Branch Batch 3
2.3 Open Vault Batch 4
2.4 Open Teller Batch 6
2.5 Current Open Tills 8
2.6 Branch Breach Limits 10
2.7 Till Vault Position 11
2.8 Branch Total Position 13
2.9 Close Teller Batch 14
2.10 Close Vault Batch 16
2.11 Close Branch Batch 19
2.12 Book Shortage 20
2.12.1 Add Denomination Details 21
2.13 Book Overage 23
2.14 Book Vault Shortage 25
2.15 Book Vault Overage 26
2.16 Teller Session 27

Copyright © 2021, 2025, Oracle and/or its affiliates.

2.16.1 Start Teller Session 28
2.16.2 Stop Teller Session 30

3 Till-Vault Operations

3.1 Buy TC from Agent 2
3.1.1 Add TC Denominations to Buy TC 3
3.2 Buy TC from Head Office 4
3.3 Buy TC from Vault 6
3.4 Return TC to Vault 8
3.4.1 Add TC Denominations to Return TC 10
3.5 Return TC to HO 11
3.6 Buy Cash from Currency Chest 12
3.7 Sell Cash to Currency Chest 14
3.8 Buy Cash from Vault 15
3.9 Sell Cash to Vault 17
3.10 Buy Cash from Till 18
3.11 Sell Cash to Till 20
3.12 Denomination Exchange 21
3.13 Vault Denomination Exchange 22
3.14 Inter Branch Transactions 24
3.14.1 Inter Branch Transaction Request 25
3.14.2 Inter Branch Transaction Input 27
3.14.3 Inter Branch Transaction Liquidation 29

4 Customer Transactions

4.1 Cash Deposit 2
4.1.1 Charge Details 5
4.2 Cash Withdrawal 7
4.3 Cheque Withdrawal 10
4.4 FX Sale Against Account 14
4.5 FX Sale Against Walk-in 17
4.6 FX Purchase Against Account 20
4.7 FX Purchase Against Walk-in 24
4.8 Close Out Withdrawal 27
4.9 Close Out Withdrawal by Multi-Mode 33
4.10 Safe Deposit Rental By Cash 36
4.11 Recurring Deposit Payment by Cash 38
4.12 F23C Tax Payment by Cash 40
4.13 F24C Tax Payment By Cash 44
4.13.1 Add Standard Details 46

Copyright © 2021, 2025, Oracle and/or its affiliates.

4.13.1.1 Add Tax Details 48
4.13.1.2 Add INPS Details 49
4.13.1.3 Add Region Details 50
4.13.1.4 Add IMU and Other Local Taxes 51
4.13.1.5 Add Insurance Details 52
4.13.1.6 Add Other Bodies 53
4.13.1.7 Add Excise Details 54
4.13.2 Add Simplified Details 55
4.13.3 Add Element Identification Details 57
4.13.4 Add Predefined Details 58
4.14 F23 Tax Payment by Account 60
4.15 F24 Tax Payment By Account 65
4.15.1 Add Standard Details 69
4.15.2 Add Simplified Details 71
4.15.3 Add Element Identification Details 73
4.15.4 Add Predefined Details 74

5 Miscellaneous Transactions

5.1 Miscellaneous Customer Debit 1
5.2 Miscellaneous Customer Credit 4
5.3 Miscellaneous GL Debit 7
5.4 Miscellaneous GL Credit 10
5.5 Miscellaneous GL Transfer 12
5.6 Miscellaneous Transfer 15

6 Transfers

6.1 Account to Account Transfer 1
6.2 In-House Cheque Deposit 4
6.3 Domestic Transfer Against Account 6
6.3.1 Add Payment Details for Domestic Transfer 9
6.4 Domestic Transfer Against Walk-in 11
6.5 International Transfer Against Account 12
6.5.1 Add Payment Details for International Transfer 15
6.6 International Transfer Against Walk-in 19

7 Clearing Transactions

7.1 Cheque Deposit 1
7.1.1 Cheque Deposit Against Account 1
7.1.2 Cheque Deposit Against GL 5

Copyright © 2021, 2025, Oracle and/or its affiliates.

7.2 Cheque Return 8
7.3 Inward Clearing Data Entry 9
7.4 Outward Clearing Data Entry 12

8 Remittances

8.1 Banker's Cheque 1
8.1.1 BC Issue Against Account 2
8.1.2 BC Issue Against Walk-in 6
8.1.3 BC Issue Against GL 9
8.1.4 BC Print and Reprint 12
8.1.5 BC Operations 14
8.1.5.1 BC Inquiry 15
8.1.5.2 BC Revalidation 17
8.1.5.3 BC Duplicate Issue 19
8.1.5.4 BC Payment by Account 20
8.1.5.5 BC Payment by Cash 23
8.1.5.6 BC Payment by GL 25
8.1.5.7 BC Refund by Account 27
8.1.5.8 BC Refund by Cash 29
8.1.5.9 BC Refund by GL 31
8.1.5.10 Cancel BC by Account 33
8.1.5.11 Cancel BC by Cash 35
8.1.5.12 Cancel BC by GL 37
8.1.6 Multi BC Issuance 40
8.1.6.1 Multi BC Issuance Against Account 40
8.1.6.2 Multi BC Issuance Against Cash 43
8.2 Demand Drafts 46
8.2.1 DD Issue Against Account 46
8.2.2 DD Issue Against Walk-in 50
8.2.3 DD Issue Against GL 54
8.2.4 DD Print and Reprint 57
8.2.5 DD Operations 58
8.2.5.1 DD Inquiry 59
8.2.5.2 DD Revalidation 61
8.2.5.3 DD Duplicate Issue 63
8.2.5.4 DD Payment by Account 65
8.2.5.5 DD Payment by Cash 68
8.2.5.6 DD Payment by GL 70
8.2.5.7 DD Refund by Account 72
8.2.5.8 DD Refund by Cash 74
8.2.5.9 DD Refund by GL 77

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.2.5.10 Cancel DD by Account 79
8.2.5.11 Cancel DD by Cash 81
8.2.5.12 Cancel DD by GL 84
8.3 Cash Remittance 86
8.3.1 Cash Remittance Issue 86
8.3.1.1 Cash Remittance Issue Against Account 87
8.3.1.2 Cash Remittance Issue Against Cash 91
8.3.1.3 Cash Remittance Issue Against GL 94
8.3.2 Cash Remittance Operations 96
8.3.2.1 Cash Remittance Inquiry 97
8.3.2.2 Cash Remittance Payment by Account 100
8.3.2.3 Cash Remittance Payment by Cash 102
8.3.2.4 Cash Remittance Payment by GL 105
8.3.2.5 Cash Remittance Refund by Account 108
8.3.2.6 Cash Remittance Refund by Cash 111
8.3.2.7 Cash Remittance Refund by GL 113
8.3.2.8 Cancel Cash Remittance by Account 116
8.3.2.9 Cancel Cash Remittance by Cash 119
8.3.2.10 Cancel Cash Remittance by GL 121
8.3.3 Inward Remittance Registration 124
8.4 Travellers Cheque 127
8.4.1 TC Sale by Other Modes 127
8.4.1.1 Add TC Denominations to Sell TC 131
8.4.2 TC Sale Against Walk-in 132
8.4.3 TC Purchase Against Account 135
8.4.3.1 Add TC Denominations to Purchase TC 138
8.4.4 TC Purchase Against Walk-in 140
8.5 Instrument Status Update 143
8.6 Instrument Details Inquiry 144
8.7 Inventory Integration 146

9 Term Deposit Transactions

9.1 TD Account Opening 1
9.1.1 Add Funding Details 4
9.1.2 Add Joint Holders Details 7
9.1.3 Add Payout Details 8
9.1.4 Add Interest Details 10
9.1.5 Add Rollover Details 11
9.2 TD Redemption Against Cash 13
9.3 TD Redemption Against Account 16
9.4 TD Top-Up Against Account 18

Copyright © 2021, 2025, Oracle and/or its affiliates.

9.5 TD Top-Up Against Cash 20

10 Credit Card Transactions

10.1 Credit Card Advance by Cash 1
10.2 Credit Card Advance by Transfer 4
10.3 Credit Card Payment by Cash 6
10.4 Credit Card Payment by Non-Cash Modes 8
10.4.1 Credit Card Payment by Account 9
10.4.2 Credit Card Payment by Clearing Cheque 11
10.5 Stop Card Request 14

11 Loan Transactions

11.1 Loan Disbursement by Cash 1
11.2 Loan Repayment by Cash 3

12 Islamic Transactions

12.1 Murabaha Payment by Cash 1
12.2 Islamic Down Payment by Cash 3
12.3 Islamic TD Account Opening 5
12.3.1 Add Funding Details for Islamic TD 8
12.3.2 Add Joint Holders for Islamic TD 10
12.3.3 Add Payout Details for Islamic TD 11
12.3.4 Add Rollover Details for Islamic TD 12

13 Bill Payments

13.1 Bill Payment by Cash 1
13.2 Bill Payments by Other Modes 3
13.2.1 Bill Payment by Account 3
13.2.2 Bill Payment by Clearing Cheque 6

14 Session Teller Transactions

14.1 Cash Deposit 1
14.2 Cash Withdrawal 2
14.3 FX Sale Against Walk-in 3
14.4 FX Purchase Against Walk-in 7
14.5 Loan Repayment by Cash 8

Copyright © 2021, 2025, Oracle and/or its affiliates.

15 Journal Log

15.1 About Electronic and Servicing Journals 1
15.2 Electronic Journal 4
15.3 Servicing Journal 10
15.4 Types of Transaction Status 16
15.5 Reassign Transactions 16
15.6 Natural Electronic Journal 19

16 Prediction

16.1 Teller Service Counters Prediction 1
16.2 Cash Prediction 2
16.3 Large Language Model Training 4

17 Customer Service

17.1 Cheque Status Inquiry 2
17.2 Stop Cheque Request 3
17.3 Cheque Book Request 4
17.4 Passbook Issue 6
17.5 Passbook Update 8
17.6 Passbook Status Change 9
17.7 Passbook Reprint 11
17.8 Account Balance Inquiry 13
17.9 Account Statement Request 16
17.10 Customer Address Update 17
17.11 Account Address Update 18
17.12 Customer Contact Update 19
17.13 Cheque Book Status Change 21

18 Branch Dashboard

19 Branch Maintenance

19.1 Common Actions for Branch Maintenance 3
19.2 Teller Branch Parameters 4
19.3 Branch Role Limits 6
19.4 Branch User Preferences 7
19.5 Denominations 9
19.6 Charge Definitions 12

Copyright © 2021, 2025, Oracle and/or its affiliates.

19.7 Function Code Definitions 14
19.8 Function Code Preferences 18
19.9 Default Authorizer 24
19.10 Accounting and Settlements 26
19.11 Instrument Numbers 29
19.12 Inter Branch Transit Account 31
19.13 External System 33
19.14 Channel Limits 35
19.15 Account Group 37
19.16 Branch Group 39
19.17 Customer Group 40
19.18 Create Charge Pricing 42
19.19 View Charge Pricing 43
19.20 Charge Condition Group 44
19.20.1 Additional Information on Parameters 46
19.21 Charge Decisions 47
19.22 Charge Decision Enquiry 51
19.23 Reject Codes 52
19.24 Clearing Network Codes 53
19.25 Denomination Variations 55
19.26 External Bank Codes 56
19.27 Issuer Codes 58
19.28 Utility Providers 59
19.29 Account Entitlement Restriction 61
19.30 GST Rule Maintenance 62
19.30.1 Create GST Rule Maintenance 63
19.30.2 View GST Rule Maintenance 64
19.31 GST Branch Parameters 64
19.31.1 Create GST Branch Parameters 64
19.31.2 View GST Branch Parameters 65
19.32 Customer Account GST Parameters 66
19.32.1 Create Customer Account GST Parameters 66
19.32.2 View Customer Account GST Parameters 67

A List of Functional Activity Codes

B Error Codes and Messages

Copyright © 2021, 2025, Oracle and/or its affiliates.

C List of Function Codes

D Advices

E Order of Replacing Parameters with Wild Card Entries

F Static Maintenance Parameters

Index

Copyright © 2021, 2025, Oracle and/or its affiliates.

Preface

- Purpose
- Audience
- Documentation Accessibility
- Critical Patches
- Diversity and Inclusion
- Conventions
- Related Resources
- Screenshot Disclaimer
- Acronyms and Abbreviations
- Basic Actions
- Symbols and Icons

Purpose

This guide helps you to familiarize yourself with the Oracle Banking Branch application. It gives an overview of the module and explains all the maintenances required for its smooth functioning. It also takes you through the different types of transactions that can be handled through this module.

Audience

This guide is intended for the Branch Tellers, Vault Operators, and Branch Supervisors to provide quick and efficient service to customers and prospects of your bank.

Documentation Accessibility

For information about Oracle's commitment to accessibility, visit the Oracle Accessibility Program website at http://www.oracle.com/pls/topic/lookup?ctx=acc&id=docacc.

Access to Oracle Support

Oracle customer access to and use of Oracle support services will be pursuant to the terms and conditions specified in their Oracle order for the applicable services.

Critical Patches

Oracle advises customers to get all their security vulnerability information from the Oracle Critical Patch Update Advisory, which is available at Critical Patches, Security Alerts and Bulletins. All critical patches should be applied in a timely manner to ensure effective security, as strongly recommended by Oracle Software Security Assurance.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Diversity and Inclusion

Oracle is fully committed to diversity and inclusion. Oracle respects and values having a diverse workforce that increases thought leadership and innovation. As part of our initiative to build a more inclusive culture that positively impacts our employees, customers, and partners, we are working to remove insensitive terms from our products and documentation. We are also mindful of the necessity to maintain compatibility with our customers' existing technologies and the need to ensure continuity of service as Oracle's offerings and industry standards evolve. Because of these technical constraints, our effort to remove insensitive terms is ongoing and will take time and external cooperation.

Conventions

The following text conventions are used in this document:

Convention	Meaning
boldface	Boldface type indicates graphical user interface elements associated with an action, or terms defined in text or the glossary.
italic	Italic type indicates book titles, emphasis, or placeholder variables for which you supply particular values.
`monospace`	Monospace type indicates commands within a paragraph, URLs, code in examples, text that appears on the screen, or text that you enter.

Related Resources

The related documents are as follows:

- *Getting Started User Guide*
- *Current Account and Savings Account User Guide*
- *Servicing Configurations User Guide*

Screenshot Disclaimer

Personal information used in the interface or documents is dummy and does not exist in the real world. It is only for reference purposes.

Acronyms and Abbreviations

The following acronyms and abbreviations are used in this guide:

Table Acronyms and Abbreviations

Acronym/ Abbreviation	Description
ARC	Account, Rate, and Charge
BC	Bankers Cheque
CASA	Current Account and Saving Account

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table (Cont.) Acronyms and Abbreviations

Acronym/ Abbreviation	Description
CCY	Currency
CIF	Customer Information File
DD	Demand Draft
EJ	Electronic Journal
FCY	Foreign Currency
FX	Foreign Exchange
GL	General Ledger
HO	Head Office
LCY	Local Currency
LOV	List of Values
MIS	Management Information System
ML	Machine Learning
RD	Recurring Deposit
SD	Safe Deposits
System	Unless specified, it shall always refer to Oracle Banking Branch.
TC	Travellers Cheque
TD	Term Deposit
UDF	User Defined Fields
VAT	Value Added Tax

Basic Actions

Most of the screens contain icons to perform all or a few of the basic actions. The actions which are called here are generic, and it varies based on the usage and the applicability. The table below gives a snapshot of them:

Table Common Icons and its Definitions

Icon	Description
Submit	Click **Submit** to complete the transaction after you specify all the input parameters for a particular transaction.
Cancel	Click **Cancel** to cancel the transaction input midway without saving any data.
Clear	Click **Clear** to clear the transaction input data. The system displays a pop-up screen with confirmation to clear data. You can click **OK** to confirm or click ✕ icon to retain the data.
Query	On completion of input of necessary parameters, click **Query** to fetch and display the details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table (Cont.) Common Icons and its Definitions

Icon	Description
Save	Click **Save** to save the details specified on the screen.
Exit	Click **Exit** to close the screen and go to the Homepage.
OK	Click **OK** to confirm the details on the pop-up screen.

Symbols and Icons

The following are the symbols you are likely to find in this guide:

Table Symbols

Symbol	Function
	Add icon
	Add a row
	Edit icon
	Delete icon
	Calendar icon
	Close icon
	Delete a row
	Grid view
	Increase/Decrease value
	List view
	Maximize
	Minimize
	Navigate to the first page
	Navigate to the last page
	Navigate to the next page
	Navigate to the previous page

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table (Cont.) Symbols

Symbol	Function
	Open a list
	Perform search
	Refresh

The following shortcut keys can be used only for the screens which have the icons specified in the Function column:

Table Shortcut Keys

Shortcut Key	Function
Tab	Used to shift focus from one input field to the other. **Note** The last field of the last accordion will shift focus to **Submit**/**Cancel** button.
Alt + S	Used to select **Submit** button.
Alt + C	Used to select **Clear** button.
Alt + X	Used to select **Cancel** button.
Alt + A	Used to select **Charge Details** data segment.
Alt + Y	Used to select **Denominations** data segment.
Alt + T	Short cut for launching Customer 360. This is applicable when customer widget is already populated based on the Function ID parameters.
Alt + Z	Short cut to **Zoom in** and **Zoom out** on the Signature from the Signature Panel. The image can further be zoomed in or out or clicked 100% to view accordingly.
Alt + R	To launch customer search **Dialogue**.
Alt + N	This shortcut key will minimize all open screens in wizard and navigate to the menu search.
Electronic Journal/ Servicing Journal operations	The available options are: • **Alt + A**: Approve • **Alt + R**: Reject • **Alt + S**: Resubmit • **Alt + D**: Discard • **Alt + V**: Reverse • **Alt + G**: Generate Advice

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table (Cont.) Shortcut Keys

Shortcut Key	Function
Alt + number	Alt + number at which button is placed will also work for respective button in detail view. In Tile View, user can fetch single record by the Shortcut key as below : Alt + number at which button is placed. For example, 1st button: **Alt + 1**, second button: **Alt + 2** etc Multiple records: Select record: **Alt + number** at which record is placed. For example, 1st record: **Alt + 1**, 10th record: **Alt + 0**
Esc	**Esc** key can be used to go back to original records.

Copyright © 2021, 2025, Oracle and/or its affiliates.

1

Overview of Oracle Banking Branch

Oracle Banking Branch is a retail banking application that gives a 360-degree view of the customer and financial transactions to the Teller of the bank.

As a Teller in Oracle Banking Branch you provide customer-focused services while also cross-selling and up-selling the bank's products and services. A typical transaction in a branch is classified into the following stages:

Table 1-1 Transaction Stages

Stage	Description
Teller Request	In this stage, the Teller captures the transaction request and transaction enrichment.
Authorization	In this stage, the Supervisor authorizes the request.
Teller Resubmission	The Resubmission stage is applicable only for certain transactions.

This topic contains the following subtopics:

- Prerequisites
  Before you begin performing transactions, you need to log in to the Oracle Banking Branch Homepage.
- About Main Menu
  The Teller Main Menu is a Mega Menu that makes all the menu items visible at once. It is a large panel divided into groups of menu items, which simplifies the navigation.
- Application Layout
  The general layout of the Oracle Banking Branch application consists of the main menu, customer search, transaction area including customer summary, and additional widgets available to display the `Current Till Position` and frequently used transaction icons.
- Salient Features
  Learn about the salient features of the Oracle Banking Branch application.

1.1 Prerequisites

Before you begin performing transactions, you need to log in to the Oracle Banking Branch Homepage.

For information on how to log in, refer to the *Getting Started User Guide*. You can also launch the Oracle Banking Branch application through the FLEXCUBE Universal Banking.

To launch Oracle Banking Branch through FLEXCUBE Universal Banking:

1. Log in to the FLEXCUBE Universal Banking Homepage. For information on how to log in, refer to the *Procedures User Guide* in the FLEXCUBE Universal Banking Documentation Library.


   The FLEXCUBE Universal Banking Homepage is displayed.
2. Specify `CSDNGUIM` in the top right corner text box, and click **Next**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **Next Gen UI Products Maintenance** screen is displayed.

> **Note**
>
> Make sure that the user has roles for the screen.

Figure 1-1 Next Gen UI Products Maintenance




3. On the **Next Gen UI Products Maintenance** screen, update the Next Generation UI **Product URL**.

> **Note**
>
> For example, `NEW TELLER` can be used as the Function id, with the description as `Teller Next Generation Product`. It is released as Static Data and ensures the user roles are maintained for the same in FLEXCUBE Universal Banking.

4. Once the roles are maintained in FLEXCUBE Universal Banking, click **Next Generation UI** on the toolbar.

   The **Next Gen UI Dashboard** is displayed with the list of products.

Figure 1-2 Next Gen UI Dashboard



5. Click **NEW TELLER**.

   The **Next Generation – Homepage** is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> Make sure that the same user id is maintained in FLEXCUBE Universal Banking. In addition, make sure that the **Next Generation UI** is maintained and has the necessary roles. For example, if the user ID is Jones, the same needs to be present in the SMS systems of FLEXCUBE Universal Banking and **Next Generation UI**.

6. Do the **Next Generation UI** changes. The *SECURITY_CONFIG* table in *PLATO_SECURITY* schema must have the following entries:


Table 1-2 Next Generation UI Changes

Configuration	Value
INTEGRATION_ENABLED {id}	`true`
INTEGRATION_CALLBACK_URL {id}	`https://10.00.00.00:1010/FCJNeoWeb/ValidationService/FCNonceValidation/validate`

> **Note**
>
> The IP and port number of the FLEXCUBE Universal Banking server must be updated.

The Oracle Banking Branch Homepage is displayed.

Figure 1-3 Homepage



1.2 About Main Menu

The Teller Main Menu is a Mega Menu that makes all the menu items visible at once. It is a large panel divided into groups of menu items, which simplifies the navigation.

The menu items are grouped based on the type of operation performed. In addition, the **Menu Item Search** can be used to search and select a specific screen from any of the main menu

Copyright © 2021, 2025, Oracle and/or its affiliates.

items. Menu Item Search also supports fast path for Branch Screens, which allows user to key in function code and launch the screen. For more information on menus, refer to Figure 1-4 and Table 1-3.

Figure 1-4 Mega Menu Teller



Table 1-3 Menu Items – Description

Menu	Description
Branch Operations	Branch Manager, Vault Teller, or Teller can use **Branch Operations** to cover the internal activities done at the branch where the Customer is not involved. This facilitates branch, vault, Till opening, or closing for the day and monitoring the transactions done during the day, and Cash Balancing.
Till-Vault Operations	Vault Teller or Teller can use **Till-Vault Operations** to monitor the cash and currency boxes for the day and to perform cash transfers from or to the Vault or Till as and when required.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-3 (Cont.) Menu Items – Description

Menu	Description
Customer Transactions	Teller can use **Customer Transactions** to perform financial transactions for Customer accounts, which includes, Cash Deposits, Cash Withdrawals, Cheque Withdrawals, Forex Transactions, and Account Closure.
Miscellaneous Transactions	Teller can use **Miscellaneous Transactions** to perform General Ledger transactions such as miscellaneous debit and credit transactions against a Customer's CASA account and GL account.
Transfers	Teller can use **Transfers** to perform inter-bank transfers, intra-bank transfers, and cross-border transactions.
Clearing	Teller can use **Clearing** to capture the Inward Clearing Data Entry, Outward Clearing Data Entry, Cheque Return, and Cheque Deposit transactions.
Remittances	Teller can use **Remittances** to issue remittances such as demand drafts and banker's cheques, perform payment or cancellation of the issued remittances, and perform further operations on the issued remittances.
Term Deposits	Teller can use **Term Deposits** to initiate Term Deposit account opening and perform a redemption, top-up on the existing term deposit accounts.
Credit Card Transactions	Tellers can use **Credit Card Transactions** to perform credit card advance and payment transactions.
Loan Transactions	Teller can use **Loan Transactions** to perform loan disbursement and loan repayment transactions.
Islamic Transactions	Teller can use to **Islamic Transactions** perform various Islamic transactions.
Bill Payments	Teller can use **Bill Payments** to perform various bill payment transactions.
Session Teller Transactions	Teller can use **Session Teller Transactions** to perform financial transactions for Customer accounts in the Teller Session.
Journal Log	Teller or Supervisor can use **Journal Log** to view the status of transactions performed by them. Also, it allows to resubmit or reject an incomplete transaction, or to reverse a completed transaction.
Prediction	The Supervisor can use **Prediction** to predict the number of service counters required for a specific period.
Customer Service	Teller or Operations Executive can use **Customer Service** to maintain customer accounts and ancillary services and to enquire about customer account balance.
Branch Dashboard	Teller can use the **Branch Dashboard** to view the cash position, transaction status, alerts, to access the frequently used transaction screens, and to view the alerts and notifications.
Branch Maintenance	**Branch Maintenance** covers a set of definitions maintained to perform the branch-based operations, transactions, and services.
Customer/Account Search	Used to query for a specific Customer ID or Customer Account Number.

You can select an operation using any of the following methods:

- From the Homepage, navigate to the left menu and then click the necessary operation.
- Click the **Frequent Operations** widget placed at the right side of the transaction area.

Copyright © 2021, 2025, Oracle and/or its affiliates.

1.3 Application Layout

The general layout of the Oracle Banking Branch application consists of the main menu, customer search, transaction area including customer summary, and additional widgets available to display the `Current Till Position` and frequently used transaction icons.

This topic contains the following subtopics:

- Customer Search
  The **Customer Search** is located in the **Branch Dashboard** and **Teller Transaction** screens. It is used to query and find a specific customer account.
- About Transaction Area
  The transaction area consists of a transaction panel, a **Customer Information** widget, and additional widgets within the **Teller Transaction** screens.

1.3.1 Customer Search

The **Customer Search** is located in the **Branch Dashboard** and **Teller Transaction** screens. It is used to query and find a specific customer account.

You can use **Customer Search** to query and find a specific customer account with one of the following information:

- Customer ID
- Customer Name
- Account Number


To find a specific customer account:

1. On the Homepage or the transaction screen, in the Customer Search widget, click the  icon.

   The **Customer Search** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 1-5 Customer Search



2. On the **Customer Search** screen, query the details. For more information on fields, refer to the field description table.

Table 1-4 Customer Search - Field Description

Field	Description
Customer ID	Specify the customer ID which the details need to be queried.
Customer Name	Specify the name of the customer for which the details need to be queried.
Account Number	Specify the account number for which the details need to be queried.
Search	Click **Search** to get the results for the specified **Customer ID**, **Customer Name**, or **Account Number**.
Reset	Click **Reset** to clear the search results.
Customer Results	Displays the customer search results.
Customer ID	Displays the customer ID.
Customer Name	Displays the customer's name.
Account Details	Displays the account search results.
Account Number	Displays the account number.
Account Name	Displays the description of the account.
Account Currency	Displays the currency of the account.


1.3.2 About Transaction Area

The transaction area consists of a transaction panel, a **Customer Information** widget, and additional widgets within the **Teller Transaction** screens.

A sample of the transaction area is shown below:

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 1-6 Transaction Area



> **Note**
>
> Users can also input amounts in short formats on the transaction screens. The system converts short transaction amount formats to the full amount when users tab out. The system supports short amount formats such as T for Thousand, M for Million, and B for Billion. When the user inputs 1B in the **Transaction Amount** field, the system defaults it to "1,000,000,000" upon tabbing it out.

Transaction Header

The transaction header is specific to each transaction screen. The following details are provided in the transaction header:

Table 1-5 Transaction Header

Item	Description
Transaction Screen Name	Displays the name of the selected transaction screen.
Customer Search	For information on the **Customer Search**, refer to Customer Search.
Transaction Reference	Displays the reference number of the transaction.
Branch Date	Displays the current branch date.

Transaction Panel

The transaction panel consists of the data segments with the necessary input fields and action buttons. Users need to specify the details in the fields to perform the transactions.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Customer Information

The **Customer Information** widget provides the details about the customer that are validated during transaction submission. For information on the amount-based signature verification, refer to About Amount-Based Signature Verification.

Table 1-6 Customer Information

Field	Description
Display Option	The **Customer Information** widget is displayed only if this option is selected. **Note** The display option is based on the **Y/N** static maintenance maintained in the function code indicator table. You need to enable it in the **SRV_TM_BC_FUNCTION_INDICATOR** table.
Customer's Image	Displays the image of the customer.
Customer's ID	Displays the ID number of the customer.
Customer's Name	Displays the name of the customer.
KYC Status	Displays the KYC status of the customer.
Signature	Displays the signature of the customer.
Account Details	Displays the details of the customer account.
Address Details	Displays the address details of the customer.
Contact Details	Displays the contact details of the customer.

Additional Widgets

The additional widgets are located at the right side of the transaction area in the **Teller Transaction** screens. The additional widgets include the following:

Table 1-7 Additional Widgets

Widget	Description
Current Till Position	Displays the cash position in the branch currency for the logged-in Teller Id.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-7 (Cont.) Additional Widgets

Widget	Description
Memo Alerts	Displays the instructions maintained in FLEXCUBE Universal Banking for the specified account number. **Note** To enable memo alerts, in transaction schema the memo_enabled flag should be set to **Y** in **SRV_TM_BC_PARAM_DTLS** and Universal Banking entries should be maintained.
Alerts	Displays the alerts/notifications specific to the Customer.
Frequent Customer Operations	Displays some frequently used transaction icons. Users can open the frequently used transaction screens through this widget. **Note** The system displays an error message stating that the User does not have rights to access this screen if the user is trying to access the restricted screen in the widget.

1.4 Salient Features

Learn about the salient features of the Oracle Banking Branch application.

The salient features are as follows:

Table 1-8 Salient Features

Feature	Description
Generation of Teller Sequence Number	The system generates a unique Teller Sequence Number and displays an information message `Teller Sequence Number nnn` indicating the generated number after submission of each teller transaction. The generated sequence number is also displayed at the following levels: • Completion • Authorization Submission • Re-submission • Reversal • Rejection
Advice Generation for Teller Transactions	The system generates the transaction advice if it is enabled in Function Code Definition Maintenance screen for the given Function Code. The advice includes the currency and amount values involved in the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-8 (Cont.) Salient Features

Feature	Description
Transaction Approval	When you perform a transaction for an amount greater than the allowed limit, it needs approval from the Supervisor. Based on the **Assignment Mode** in **Function Code Preferences** screen, the following conditions apply: • **Manual** – The system will show a list of approval if the request status is **Approval**. • **Auto** – The transaction is automatically assigned to the default authorizer if the request status is **Approval**. The transaction approval flow consists of the following steps: • Initiation • Pending Approval • Approved (Sent Back) • Completed For more information on transaction approval flow, refer to .Table 1-9.
Transaction Reversal with Approval	A transaction can be reversed with auto-approval or approval from the Supervisor. Based on the **Assignment Mode** in **Function Code Preferences** screen, the following conditions apply: • **Manual** – The system will show a list of approval if the request status is **Approval**. • **Auto** – The transaction is automatically assigned to the default authorizer if the request status is **Approval**. The transaction approval flow consists of the following steps: • Completed • Pending Approval • Approved (Sent Back) • Completed • Reversed For more information on transaction flow for reversal with approval, refer to Table 1-10.
Transaction Reversal	A transaction can be manually reversed only when it is authorized and completed from the **Journal Log**. When you reverse a transaction, the data remains in the system with the status **Reversed** and the accounting entries are reversed. Also, this will update the Till Balance for the currencies (for cash transactions), wherever applicable. You can select the transaction to be reversed from the transaction screen. If the reversal is applicable for the function code, the **Reversal** icon will be enabled. When you click this icon, the reversal request will be initiated. If cash transactions are reversed, the system validates the following: • the Till used for the reversal is the same as that used in the original transaction • the denominations are input • a batch is open

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-8 (Cont.) Salient Features

Feature	Description
Transaction Rejection	You can manually reject the authorized customer transactions from the Teller **Journal Log**. **Note** When you reject a transaction, the data remains in the system with the contract status **Discarded** and no further action is allowed on the transaction.
External API	External APIs will be processed only if called by an external system, which is maintained in Oracle Banking Branch. The external system can be maintained using the **External System Maintenance** screen. For more information on the **External System Maintenance** screen, refer to *External System Maintenance*. External APIs are supported for the following transactions: • Cash Deposit • Cash Withdrawal • Account Balance Inquiry • Account Transfer • Misc Customer Credit • Misc GL Debit • Cash Deposit and Cash Withdrawal Reversal **Note** These transactions will work only if OAuth is enabled.
Machine Learning	For information on machine learning, refer to About Machine Learning.
Oracle Digital Assistant (ODA)	For information on ODA, refer to About Oracle Digital Assistant.
Virtual Identifier	For information on the virtual identifier, refer to About Virtual Identifier.
Amount-Based Signature Verification	For information on amount-based signature verification, refer to About Amount-Based Signature Verification.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-9 Transaction Approval Flow

Stage	Description
Initiation to Pending Approval	If the transaction amount exceeds the limit defined in Branch User Limits and on click of **Submit**, the system shows a popup message `Amount exceeds limit for this transaction`, and request status is shown as **Approval**. If assignment mode is manual and on click of **Confirm**, the system shows a list of approval based on branch code, transaction amount, currency, and function code. The user can give a narrative and click **Submit for Approval** button.
Pending Approval to Sent Back	The Approver needs to log in and fetch the transaction from **Journal Log** with transaction status as **Pending Approval**. The Supervisor can approve the pending transaction by clicking **Approve** with the supervisor comment. **Note** The approver remarks are mandatory during the rejection of a transaction.
Sent Back to Completed	The user needs to fetch the transaction from **Journal Log** with transaction status as **Sent Back** and click **Submit**.
Override Flow (Initiation to Completed)	Based on the branch maintenance setup at certain levels like Function Code, Function Code Preferences, Branch User Limits, and Branch role limits, if the transaction is validated with any warning override, the system shows a pop-up message with request status as **Warning**. Once the user confirms, the transaction status will be shown as **Completed**.

Table 1-10 Transaction Reversal with Approval Flow

Stage	Description
Completed to Pending Approval	The completed transaction can be selected from the **Journal Log** screen. Once you click **Reverse**, the system shows a pop-up message `Authorization required for Reversal` and requests for a confirmation. If assignment mode is manual and on click of **Confirm**, the system shows a list of approvers based on branch code, transaction amount, currency, and function code. The user can give a narrative and click **Submit for Approval** button.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-10 (Cont.) Transaction Reversal with Approval Flow

Stage	Description
Pending Approval to Sent Back	The Approver needs to log in and fetch the transaction from **Journal Log** with transaction status as **Pending Approval**. The Supervisor can approve the pending transaction by clicking **Approve** with the supervisor comment. **Note** The approver remarks are mandatory during the rejection of a transaction and the transaction will be restored to the **Completed** status.
Sent Back to Reversed	The user needs to fetch the transaction from **Journal Log** with transaction status as **Sent Back** and click **Submit**.
Override Flow (Sent Back to Reversed)	The user needs to select the completed transaction in the **Electronic Journal** screen and click **Reverse**. If the **Reversal Requires Authorization** is enabled in the **Function Code Definition** screen, the system displays an information message to select the Approver based on Manual or Auto assignment mode. After selecting the approver internally, reversal override will be called and request status will be updated as **Approval**.

Transaction Approval Flow with Account Overrides

When the Account Overrides are enabled (IS_ACC_OVD) and the Transaction Account is a CASA, then below is the Approval flow for Transaction Reversal.

Note:

If Account override is enabled, then ite is mandtory to enable Two Step Auth flow (FINISHTXN_ON_APP, TWO_STEP_SYNC) And Auto Processing (AUTO_PROCESSING).

Table 1-11 Transaction Approval Flow with Account Overrides

Stage	Description
Initiation to Pending Approval	If Account overrides are received , the same will be clubbed along with the Branch raised overrides and displayed on a popup message, on click of Submit. Maker has an options to Confirm the Overrides and Submit for Approval or Discard and Exit. If assignment mode is **Manual** and on click of Confirm, the system shows a list of approval based on Maintenances in Function Code Preferences. The user can give a narrative and click **Submit** for Approval button. If assignment mode is **Auto** and on click of Confirm, the system assigns to the ROLE based on Maintenances in Function Code Preferences. The user can give a narrative and click **Submit** for Approval button. If the Maker selects Discard and Exit, then the transaction will move to the Discarded queue of the Maker.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-11 (Cont.) Transaction Approval Flow with Account Overrides

Stage	Description
Pending Approval to Completed	The Approver needs to log in and fetch the transaction from Journal Log with transaction status as Pending Approval. The Supervisor can view the Overrides raised and Approve or Reject the Transaction. If the Supervisor Approves the pending transaction by clicking Approve along with the supervisor comment, then the Transaction is moved to Completed. **Note:** The approver remarks are mandatory during the rejection of a transaction.

Transaction Reversal with Approval Flow and Account Overrides

When the Account Overrides are enabled (IS_ACC_OVD) and the Transaction Account is a CASA, then below is the Approval flow for Transaction Reversal.

Note:

If Account override is enabled, then ite is mandtory to enable Two Step Auth flow (`FINISHTXN_ON_APP, TWO_STEP_SYNC`) And Auto Processing (`AUTO_PROCESSING`).

Table 1-12 Transaction Reversal with Approval Flow and Account Overrides

Stage	Description
Completed to Pending Approval	Transaction can be reversed by selecting the record from the completed transaction queue in the Journal Log screen. Once you click **Reverse**, If Account overrides are received , the same will be clubbed along with the Branch raised overrides and displayed on a popup message and requests for confirmation. Maker has an options to Confirm the Overrides and Submit the reversal request for Approval or Discard and Exit. If assignment mode is **Manual** and on click of Confirm, the system shows a list of approval based on Maintenances in Function Code Preferences. The user can give a narrative and click **Submit** for Approval button. If assignment mode is **Auto** then on click of Confirm, the system assigns to the ROLE based on Maintenances in Function Code Preferences. The user can give a narrative and click **Submit** for Approval button. If assignment mode is manual and on click of Confirm, the system shows a list of approvers based on branch code, transaction amount, currency, and function code. The user can give a narrative and click **Submit** for Approval button.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-12 (Cont.) Transaction Reversal with Approval Flow and Account Overrides

Stage	Description
Pending Approval to Reversed	The Approver needs to log in and fetch the transaction from Journal Log with transaction status as Pending Approval. The Supervisor can view the Overrides raised and Approve or Reject the Transaction. If the Supervisor Approves the pending transaction by clicking Approve along with the supervisor comment, then the Transaction is moved to Reversed . The Supervisor can approve the pending transaction by clicking Approve with the supervisor comment. **Note:** The approver remarks are mandatory during the rejection of a transaction and the transaction will be restored to the Completed status.

This topic contains the following subtopics:

- About Machine Learning
  Oracle Banking Branch uses machine learning to process an email request from a customer automatically.
- About Virtual Identifier
  The virtual identifier is used to validate the specified account number of the customer.
- About Oracle Digital Assistant
  The Oracle Digital Assistant (ODA) helps the Teller to reduce the time taken to access the transaction screens through automatic text/voice processing.
- About Amount-Based Signature Verification
  The Teller can use the "Amount-Based Signature Verification" feature to verify the signature displayed in the Customer Information widget while performing the transactions.
- Advice Generation for Teller Transactions
  This **Advice Generation** for teller helps to select the language for printing the transactions.
- Keyboard Navigation for Transaction Screens
  The keyboard navigation can be used as an alternative method to navigate through interactive elements on a screen – fields, buttons, data segments, tables, etc. It can be used to navigate through the application, input the necessary values, and perform the transactions.
- About Business Process Codes
  Business Process Code defines the various stages for servicing transactions.


1.4.1 About Machine Learning

Oracle Banking Branch uses machine learning to process an email request from a customer automatically.

When a customer sends an email request, the requirement is understood using machine learning, and the transaction is processed. A sample email request is shown in Figure 1-7. Based on pre-defined machine learning in **External System Maintenance**, the transaction is processed automatically.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 1-7 Sample Email Request



The following conditions apply to the machine learning use case for cheque book requests:

- If sufficient details are provided in the email request, the transaction will be processed until completion.
- If details are insufficient in the email request to process a transaction, it will be assigned in the **Servicing Journal** for user correction. After the assigned user does the correction, the transaction will be processed.

Figure 1-8 ML Correction Assistance – Extracted Information





Figure 1-9 ML Correction Assistance – Enriched Data



View Request

In the **Electronic Journal**, you can view the details of the **Cheque Book Request** initiated through the email request. The **View Request** button will be enabled for the transactions that are submitted or completed. You can view the details of the email request by clicking the **View Request**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 1-10 View Request (Completed Transaction)





Figure 1-11 View Request (Submitted Transaction)



If sufficient details are provided in the email request for card block, the transaction will be processed until completion.

1.4.2 About Virtual Identifier

The virtual identifier is used to validate the specified account number of the customer.

The virtual identifier is supported for the following screens:

- Cash Deposit
- Miscellaneous Customer Credit
- Account Transfer
- In-House Cheque Deposit


Copyright © 2021, 2025, Oracle and/or its affiliates.

Validations

If Virtual Identifier is enabled, the validation is performed as follows:

- After you specify the account number, and on tab out, the system will validate the specified account number.
- If the account number is invalid, the system prompts an information message to input the currency and amount.
- Once the currency and amount are entered, the virtual identifier service will be invoked to validate if it is a valid virtual account or not.

Figure 1-12 Virtual Identifier – Information Message




1.4.3 About Oracle Digital Assistant

The Oracle Digital Assistant (ODA) helps the Teller to reduce the time taken to access the transaction screens through automatic text/voice processing.

The ODA can be enabled by navigating to the user menu and selecting **Virtual Assistant** option.

Figure 1-13 Virtual Assistant




The virtual assistant supports the following use cases:

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-13 ODA Use Cases

Use Case	Description
Teller can either type/say, **Cash Withdrawal Account Number**, **Do Cash Withdrawal Account Number** in ODA Chatbot.	Based on the input provided, the **Cash Withdrawal** screen will be opened automatically with the specified account number. For example, refer to Figure 1-14. **Note** Teller needs to type/say the specific account number while giving the input text/voice.
Teller can either type/say, **Cash Deposit Account Number**, **Do Cash Deposit Account Number** in ODA Chatbot.	Based on the input provided, the **Cash Deposit** screen will be opened with the specified account number. For example, refer to Figure 1-14.
Teller can type/say the name of the operation like **Open Teller Batch** or **Open My Batch**.	If the Teller batch is closed, then it will open the teller batch. In case the Teller batch is already open, a response message (**Teller batch already open**) will be displayed. For example, refer to Figure 1-15.
Teller can type/say the name of the operation like **Check Batch Status**, **What is my Batch Status**, or **Check Batch**.	Based on the input, the following conditions apply: • If the Teller batch is open, the ODA will show the message **Your Teller Batch is Open**. • If the Teller batch is closed, the ODA will show the message **Your Teller Batch is Closed** and prompts **Do you want to open your Batch** with the options (**Yes** – select to open the Teller batch or **No** – select if it is not required to open the Teller batch). For example, refer to Figure 1-16

Figure 1-14 Use Case to launch Cash Deposit with Account Number



Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 1-15 Use Case to initiate Open Teller Batch





Figure 1-16 Use Case to Check Batch Status




ODA Voice Submit

Facilitate tellers in completing transactions solely through voice interactions. This speeds up the execution of common transactions, enhances the teller experience, and improves overall customer satisfaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 1-17 Voice Submit



The voice submit supports the following:

Table 1-14 Voice Submit

Use case	Description
Cash Deposit	1. Voice Command: Do a **Cash Deposit** for account 1006000000000135 with 120 GBP. 2. Provide the Denomination : Example 100 1, 10 2.
Cash Withdrawal	Voice Command: Do a Cash Withdrawal for account 1006000000000135 with 100 GBP.
Cheque Withdrawal	Voice Command: Do a Cheque Withdrawal for account 1006000000000135 with 100 GBP for cheque 0103.

> **Note**
>
> The denomination for Withdrawal will be auto-filled based on the till balance when the DEF_DEN_FR_WTDWL parameter is turned on.

1.4.4 About Amount-Based Signature Verification

The Teller can use the "Amount-Based Signature Verification" feature to verify the signature displayed in the Customer Information widget while performing the transactions.

To enable/disable this feature, configure the value as `Y` or `N` in the `AMOUNT_BASED_SV` flag. This flag is present in the *srv_tm_bc_param_dtls* table in the transaction domain.

The following use cases are applicable to this feature:


Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-15 Amount-Based Signature Verification

Use Case	Description
Amount-based signature verification is disabled	When the user specifies the **Account Number** in a transaction screen and presses the **Tab** key, the system displays the signature in the **Customer Information** widget.
Amount-based signature verification is enabled	When the user specifies the **Account Number** and **Amount** in a transaction screen and presses the **Tab** key, the system displays the following details of signature in the **Customer Information** widget: • Signature • Signature Type • Group ID • Number of Signatories

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 1-18 Amount-based Signature Verification Disabled




Copyright © 2021, 2025, Oracle and/or its affiliates.

1.4.5 Advice Generation for Teller Transactions

This **Advice Generation** for teller helps to select the language for printing the transactions.

Users can select the language for printing the advice during **Advice Generation** from the list of supported languages. user can specify the language under **Locale** to print the transactions.

Figure 1-19 Advice Generation



1.4.6 Keyboard Navigation for Transaction Screens

The keyboard navigation can be used as an alternative method to navigate through interactive elements on a screen – fields, buttons, data segments, tables, etc. It can be used to navigate through the application, input the necessary values, and perform the transactions.

The keyboard navigation for various operations and their descriptions are as follows:

Table 1-16 Keyboard Navigation

Operation	Description of Navigation
Input Values in Fields	After you launch the transaction screen, press the **Tab** key to navigate to the desired field, and specify the value.
Select Date	To select the appropriate date, perform the following steps: 1. Press **Tab**/**Shift** + **Tab** keys to navigate to the desired calendar icon. 2. Use **Arrow** keys to navigate to the desired date. 3. Press **Enter** key or **Spacebar** to select the date.
Select from Drop-down Lists	To select a value from the drop-down list, perform the following steps: 1. Press **Tab**/**Shift** + **Tab** keys to navigate to the desired drop-down list. 2. Use **Arrow** keys to navigate to the desired value. 3. Press **Enter** key to select the value.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 1-16 (Cont.) Keyboard Navigation

Operation	Description of Navigation
Select from List of Values	To select a value from the list of values, perform the following steps: 1. Press **Tab**/**Shift** + **Tab** keys to navigate to the desired list of values. 2. Press **Enter** key or **Spacebar** to enter into the list of values. 3. If the exact value is known, specify the value in the search field, and press the **Tab** key to navigate to the **Fetch** button. Press Enter key to select the **Fetch** button. The results will be fetched based on the input value. 4. Press the **Tab** key to navigate to the results. 5. Use **Arrow** keys to navigate to the desired value. 6. Press **Spacebar** to select the value.
Navigating through Tables	To specify/select value in the fields/cells of a table, perform the following steps: 1. Press **Tab**/**Shift** + **Tab** keys to navigate to the desired data segment, and navigate to the desired table row. 2. Press **Enter** key to enter into the data fields/cells. 3. Specify the necessary value in the fields. 4. If there are more cells in the row, use the **Tab** key to navigate to the other cells and specify the values. 5. After you specify the values in the cells, press the **Esc** key to change the selection from cell to row. 6. Press the **Tab** key to navigate to the other tables/data segments/ fields/buttons.
Select Option Buttons/ Icons	To select option buttons, perform the following steps: 1. Press **Tab**/**Shift** + **Tab** keys to navigate to the desired option button. 2. Press **Enter** key or **Spacebar** to select the desired option button.
Perform Transaction	To specify/select the necessary values and submit a transaction using keyboard navigation, perform the following steps: 1. Use the appropriate shortcut keys to navigate to the fields, buttons, data segments, tables, etc., and specify/select the necessary values. 2. After you specify the necessary values, use appropriate shortcut keys to select **Submit** button to complete a transaction.

1.4.7 About Business Process Codes

Business Process Code defines the various stages for servicing transactions.

The screens available in the Oracle Banking Branch application use the conductor flow. As a part of Oracle Banking Branch releases, a set of default process codes are factory-shipped for the following customer servicing transactions:

- **Customer Address Update**

Copyright © 2021, 2025, Oracle and/or its affiliates.

- **Account Address Update**
- **Customer Contact Details Update**

> **Note**
>
> For more information on the business process, refer to the *Servicing Configurations User Guide*.

Copyright © 2021, 2025, Oracle and/or its affiliates.

2

Branch Operations

The Branch Manager, Vault Teller, or Teller can use branch operations to perform the internal activities done at the branch where the customer is not involved.

This topic contains the following subtopics:

- TC Denomination Enquiry
  The **TC Denomination Enquiry** screen is used to enquire the currency-wise details of the TCs in the branch vault.
- Open Branch Batch
  The **Open Branch Batch** screen is used to initiate the branch operations for the posting date. The Supervisor or Branch Manager with necessary access can open this screen.
- Open Vault Batch
  The Vault Teller can use **Open Vault Batch** screen to open a vault batch on a specified date.
- Open Teller Batch
  The **Open Teller Batch** screen is used to open a teller batch on a specified date.
- Current Open Tills
  The **Current Open Tills** screen is used to view the open tills or vault for the branch during the day or before performing the end-of-day activity.
- Branch Breach Limits
  The **Branch Breach Limits** screen helps to view the details of Till or Vault, which is breaching the currency limits along with the current balance position.
- Till Vault Position
  The **Till Vault Position** screen is used to view the cash position of all the currencies at any time for the *Teller ID* or *Vault ID*, which is logged in for the current posting date. It also shows the denomination details.
- Branch Total Position
  The supervisor can use this screen to view the currency-wise cash position of all the Tellers and Vault Teller on the posting date for the logged-in branch.
- Close Teller Batch
  The **Close Teller Batch** screen is used to close the teller batch for the given posting date.
- Close Vault Batch
  The **Close Vault Batch** screen is used to close the vault batch for a specific date.
- Close Branch Batch
  The **Close Branch Batch** screen is used to close the branch batch after confirming that all the branch transactions have been accounted for in the account books.
- Book Shortage
  The Teller can use the **Book Shortage** screen to book the shortage if the actual or physical cash present is less than the system cash.
- Book Overage
  The Teller can use this screen to book the physical cash held in a particular currency, which exceeds the cash in that currency shown in the system.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Book Vault Shortage
  The Vault Teller can use the **Book Vault Shortage** screen to book the shortage if the actual or physical cash present is less than the system cash.
- Book Vault Overage
  The Vault Teller can use this screen to book the physical cash held in a vault particular currency, which exceeds the cash in that currency shown in the system.
- Teller Session
  The teller can perform several specific transactions for a customer in a single session. All the transactions done by the customer are grouped under a single session. At the end of the session, the teller accepts the net amount (of all the transactions done in the session) from the customer.

2.1 TC Denomination Enquiry

The **TC Denomination Enquiry** screen is used to enquire the currency-wise details of the TCs in the branch vault.

The currency-wise details include:


- Denomination
- Count
- Series
- Serial Number
- Amount

To enquire the TC denomination:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **TC Denomination Enquiry** or specify **TC Denomination Enquiry** in the search icon bar and select the screen.

   The **TC Denomination Enquiry** screen is displayed.

Figure 2-1 TC Denomination Enquiry



2. On the **TC Denomination Enquiry** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-1 TC Denomination Enquiry - Field Description

Field	Description
Branch Code	Displays the logged-in branch code.
Posting Date	Displays the current posting date of the branch.
Till Vault Indicator	Select the Till Vault Indicator from the drop-down values (`Till` or `Vault`).
Till ID	Displays the Till ID.
TC Currency	Click the search icon, and select the TC currency from the list of values.
Issuer Code	Click the search icon, and select the issuer code from the list of values.
Refresh	After you specify the **TC Currency** and **Issuer Code** fields, click **Refresh** to fetch and display the details of the TC.
Denomination Code	Displays the denomination code of the TC.
Description	Displays the description of the denomination code.
System Count	Displays the system count.
Series	Displays the series.
Start Number	Displays the start number.
End Number	Displays the end number.
Amount	Displays the amount.

2.2 Open Branch Batch

The **Open Branch Batch** screen is used to initiate the branch operations for the posting date. The Supervisor or Branch Manager with necessary access can open this screen.

The Teller or Vault Teller can perform the branch operations only after the branch batch is submitted for the posting date. When a branch batch is closed for the day, the system derives the next working day automatically, based on the branch calendar.


To open a branch batch:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Open Branch Batch** or specify **Open Branch Batch** in the search icon bar and select the screen.

   The **Open Branch Batch** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 2-2 Open Branch Batch



2. On the **Open Branch Batch** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-2 Open Branch Batch - Field Description

Field	Description
Posting Date	Indicates the date on which the branch batch needs to be opened. **Note** By default, the system displays the current date.

3. Click **Submit**.

   The branch batch is opened for the specified posting date.

Note

- Opening branch batch indicates to the head office that the branch is open for business operations on the specified posting date. You can open a Teller batch for the posting date only after the branch batch is opened.
- On submit , system will compare the Branch Date with the Common Core Date, and a warning will be shown if the current date is beyond the Next working date of Common Core.

2.3 Open Vault Batch

The Vault Teller can use **Open Vault Batch** screen to open a vault batch on a specified date.

On the specified posting date, the Vault Teller can open only one vault batch. To open another vault batch, the vault batch which is opened previously needs to be closed. All the tellers buy additional cash and sell their excess cash to the Vault Teller. When this screen is launched, the system will default the cash balances.


To open a vault batch:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Open Vault Batch** or specify **Open Vault Batch** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **Open Vault Batch** screen is displayed.

Figure 2-3 Open Vault Batch



2. On the **Open Vault Batch** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-3 Open Vault Batch - Field Description

Field	Description
Posting Date	Indicates the date on which the vault batch needs to be opened. **Note** By default, the system displays the current date.
Populate Denominations	Click this button to automatically populate total units using data from the previous closing balance. If it is not selected, the users must manually input the total units to proceed.
Currency	Displays the currency code.
Total Cash	Specify the total cash for a particular currency, physically present in the bank vault, at the beginning of the current posting date.
Cash Available	Displays the system calculated cash for a particular currency, which is available in the vault at the beginning of the current posting date. **Note** The amount shown in this column depends on the cash transactions that were carried out by the vault until the last posting date.
Shortage/Overage Amount	Displays the difference between the total cash and the cash available in the Vault, at the end of the current posting date.
Currency	Displays the currency code.
Denomination	Displays the denomination code.
Demon Type	Displays the demon type. Values: Note or Coin

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-3 (Cont.) Open Vault Batch - Field Description

Field	Description
Total Units	Specify the total units available while closing the batch.
Total Value	Displays the total value based on the total units.
System Units	Displays the units available in the system.
System Total	Displays the total value available in the system.
Shortage/Overage Units	Displays the shortage/overage units.
Shortage/Overage Amount	Displays the shortage/overage amount.
Total Cash Amount	Displays the total cash amount.
Denomination Total	Displays the total denomination value with the currency.
Validate Denominations	Click this button to calculate and display the **Total Cash** and **Shortage/Overage Amount** fields based on the currency selected.

3. Click **Submit**.

   The vault batch is opened for the specified posting date.

> **Note**
>
> During the vault batch opening, the system will internally transfer the available balance from the Primary vault of the branch to the current open Vault ID. The Vault Teller can perform the relevant vault operations for the posting date. The system does not allow to open the vault batch if the physical cash entered is not the same as the system cash.

2.4 Open Teller Batch

The **Open Teller Batch** screen is used to open a teller batch on a specified date.

A Teller can initiate the teller batch with the current cash position that has been retained from the previous day or start with zero cash and subsequently buy cash from the vault. The system will default the cash balances on opening a teller batch.


To open a teller batch:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Open Teller Batch** or specify **Open Teller Batch** in the search icon bar and select the screen.

   The **Open Teller Batch** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 2-4 Open Teller Batch



2. On the **Open Teller Batch** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-4 Open Teller Batch - Field Description

Field	Description
Posting Date	Indicates the date on which the vault batch needs to be opened. **Note** By default, the system displays the current date.
Populate Denominations	Click this button to automatically populate total units using data from the previous closing balance. If it is not selected, the users must manually input the total units to proceed.
Currency	Displays the currency code.
Total Cash	Specify the total cash for a particular currency, physically present in the bank teller, at the beginning of the current posting date.
Cash Available	Displays the system calculated cash for a particular currency, which is available in the vault at the beginning of the current posting date. **Note** The amount shown in this column depends on the cash transactions that were carried out by the vault until the last posting date.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-4 (Cont.) Open Teller Batch - Field Description

Field	Description
Shortage/ Overage Amount	Displays the difference between the total cash and the cash available with the Teller, at the end of the current posting date. Based on this difference, the overage or the shortage amount is displayed. **Note** An overage indicates that the physical cash with the Teller is more than the available cash as calculated by the system. A shortage indicates that the available cash calculated by the system is more than the physical cash present with the Teller.
Currency	Displays the currency code.
Denomination	Displays the denomination code.
Demon Type	Displays the demon type. Values: Note or Coin
Total Units	Specify the total units available while closing the batch.
Total Value	Displays the total value based on the total units.
System Units	Displays the units available in the system.
System Total	Displays the total value available in the system.
Shortage/Overage Units	Displays the shortage/overage units.
Shortage/Overage Amount	Displays the shortage/overage amount.
Total Cash Amount	Displays the total cash amount.
Denomination Total	Displays the total denomination value with the currency.
Validate Denominations	Click this button to calculate and display the **Total Cash** and **Shortage/Overage Amount** fields based on the currency selected.

3. Click **Submit**.

The teller batch is opened for the specified posting date.

Note

The Teller can perform the relevant teller operations for the posting date. The system does not allow to open the vault batch if the physical cash entered is not the same as the system cash. The system also allows to re-open the Teller batch for the current system date.

2.5 Current Open Tills

The **Current Open Tills** screen is used to view the open tills or vault for the branch during the day or before performing the end-of-day activity.

The branch user can use this screen to view the list of logged-in Tellers and to view the following transactions under each Teller or Vault Teller's ID:

Copyright © 2021, 2025, Oracle and/or its affiliates.


- Pending
- Assigned

To view the open tills or vault:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Current Open Tills** or specify **Current Open Tills** in the search icon bar and select the screen.

   The **Current Open Tills** screen is displayed.

Figure 2-5 Current Open Tills



2. On the **Current Open Tills** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-5 Current Open Tills - Field Description

Field	Description
Branch Code	Displays the logged-in branch.
Posting Date	Indicates the date on which the current open tills need to be enquired. **Note** By default, the system displays the current date.
Refresh	Click **Refresh** to refresh the details.
User ID	Displays the list of Tellers or Vault Tellers of the branch.
User Name	Displays the name of the user.
Till/Vault Indicator	Identification of the User as a Teller, Vault Teller or Both Values: `T, V or B`
User Working	Current Logged in Status of the User Values : `Y/N` **Note** If the Till/Vault Indicator is `B` and either the teller batch or Vault batch is open, the User Working Indicator will be set to `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-5 (Cont.) Current Open Tills - Field Description

Field	Description
Pending Transactions	Total count of pending transactions for the User in the **Sent Back** and **Sent for Approval** queues.
Assigned Transactions	Total count of transactions that are manually assigned to this user for Approval from the **Pending Approval** Queue and are not yet Approved.

2.6 Branch Breach Limits

The **Branch Breach Limits** screen helps to view the details of Till or Vault, which is breaching the currency limits along with the current balance position.


In addition, the branch supervisor can view the branch's total cash position and its breaching limits for the posting date.

To view the branch breaching limits:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Branch Breach Limits** or specify **Branch Breach Limits** in the search icon bar and select the screen.

   The **Branch Breach Limits** screen is displayed.

Figure 2-6 Branch Breach Limits



2. On the **Branch Breach Limits** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-6 Branch Breach Limits - Field Description

Field	Description
Branch Code	Displays the logged-in branch.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-6 (Cont.) Branch Breach Limits - Field Description

Field	Description
Posting Date	Indicates the date on which the branch breaching limits needs to be enquired. **Note** By default, the system displays the current date.
Refresh	Click this icon to refresh the details.
Tills Breaching Limit	Specify the fields under this section.
User ID	Displays the list of Tellers/Vault Tellers of the branch.
Vault User	Displays the checkbox if the **User ID** is a Vault Teller.
Currency	Displays the list of currencies in which the **User ID** has performed the transactions.
Minimum Limit	Displays the minimum till balance that needs to be maintained for the **User ID** and currency combination.
Maximum Limit	Displays the maximum till balance that needs to be maintained for the **User ID** and currency combination.
Current Till Balance	Displays the current till balance based on the till cash position for the specified currency.
Branch Breaching Limit	Displays the values under this section.
Branch Code	Displays the code of the logged-in branch.
Currency	Displays the currency code.
Minimum Limit	Displays the minimum limit that needs to be maintained for the branch.
Maximum Limit	Displays the maximum limit that needs to be maintained for the branch.
Current Total Balance	Displays the branch total cash position, currency-wise.

2.7 Till Vault Position

The **Till Vault Position** screen is used to view the cash position of all the currencies at any time for the *Teller ID* or *Vault ID*, which is logged in for the current posting date. It also shows the denomination details.


To view the cash position of all the currencies:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Till Vault Position** or specify **Till Vault Position** in the search icon bar and select the screen.

   The **Till Vault Position** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 2-7 Till Vault Position



2. On the **Till Vault Position** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-7 Till Vault Position - Field Description

Field	Description
Branch Code	Displays the logged-in branch.
Branch Posting Date	Displays the date on which the Till/Vault batch is opened.
Teller/Vault ID	Displays the logged-in Teller ID or Vault Teller ID.
Currency Details	Specify the fields under this section.
Currency	Displays the currency code.
Opening Balance	Displays the opening balance of the till or vault.
Incoming Cash Amount	Displays the incoming cash in the till or vault for the current posting date.
Outgoing Cash Amount	Displays the outgoing cash in the till or vault for the current posting date.
Total Cash	Displays the total cash available in the till or vault.
Till Vault Indicator	Displays whether the currency details apply to Till or Vault. (**T** or **V**)
Denomination Details	Displays the denomination details under this section.
Denomination Code	Displays the denomination code maintained for the currency.
Denomination Value	Displays the denominations maintained for the currency.
Opening Balance	Displays the opening balance in the Till or vault in terms of denominations.
Incoming Cash Amount	Displays the incoming cash in the Till or vault in terms of denominations.
Outgoing Cash Amount	Displays the outgoing cash in the Till or vault in terms of denominations.
Total Cash	Displays the total cash currently available in the Till or vault for the day in terms of denominations.
Units	Displays the total units available for the specific denomination code.

Copyright © 2021, 2025, Oracle and/or its affiliates.

2.8 Branch Total Position


The supervisor can use this screen to view the currency-wise cash position of all the Tellers and Vault Teller on the posting date for the logged-in branch.

To view the currency wise cash position:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Branch Total Position** or specify **Branch Total Position** in the search icon bar and select the screen.

   The **Branch Total Position** screen is displayed.

Figure 2-8 Branch Total Position



2. On the **Branch Total Position** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-8 Branch Total Position - Field Description

Field	Description
Branch Code	Displays the logged-in branch.
Posting Date	Indicates the date on which the teller totals position need to be enquired. **Note** By default, the system displays the current date.
Currency	Displays the currency code for which the teller totals details needs to be displayed.
Teller ID	Displays the logged-in teller ID from the LOV.
All Till	Select this radio button to display all the open Teller Till details of the day.
All Vault	Select this radio button to display all the open Vault details of the day.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-8 (Cont.) Branch Total Position - Field Description

Field	Description
All Till and Vault	Select this radio button to display all the open Till and open Vault details of the day.
Query	Displays the details if you click this icon.
Latest Posting Date	This will be the date when the Teller / Vault batch was last opened. **Note** Balances for unopened tills or vaults will be fetched from the last recorded entry, following the number of days configured in BRN_TOT_POSITION_DAYS parameter.
Currency	Displays the currency code for which the cash position is shown.
Teller ID	Displays the Teller ID for which the cash position is shown.
Carryover Balance	Displays the opening balance of the Teller ID for the specific currency.
Incoming Cash	Displays the total incoming cash received in the Till.
Outgoing Cash	Displays the outgoing cash moved out of the Till.
Closing Balance	Displays the total amount pending in the Till.
Till/Vault Indicator	Displays the details of Till/Vault.
Branch Total Currency Position	Display the total balance in the branch currency wise.
Currency	This indicates the currency for which the Branch Total Position will be displayed.
Total Balance	This reflects the combined till and vault position for the given currency.

2.9 Close Teller Batch

The **Close Teller Batch** screen is used to close the teller batch for the given posting date.

The system allows closing the teller batch only when the below conditions are met:

- Verify that all the transactions are successfully processed to a logical end. If there are any pending transactions, the system prompts to either complete or reject the transaction.
- Verify that there is a difference between the physical cash and the cash calculated by the system. You need to book the overage or shortage accordingly, and then each Teller can close the teller batch for that day.
- Verify that the teller cash position retains the minimum limit for every currency as maintained in the User limits. If you breach the minimum limit, the system prompts the error to maintain the required minimum balance.
- Verify that all the Servicing transactions are successfully processed to a logical end. If there are any pending transactions, the system prompts to complete the transaction.
- Pending branch servicing transactions that must be finished on the same day can be verified during the closing of the teller batch. For more information, refer Tasks User Guide.


To close the teller batch:

Copyright © 2021, 2025, Oracle and/or its affiliates.

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Close Teller Batch** or specify **Close Teller Batch** in the search icon bar and select the screen.

   The **Close Teller Batch** screen is displayed.

Figure 2-9 Close Teller Batch



2. On the **Close Teller Batch** screen, specify the details. For more information on fields, refer to the field description table.

Table 2-9 Close Teller Batch - Field Description

Field	Description
Posting Date	Indicates the date on which the teller batch needs to be closed. **Note** By default, the system displays the current date.
Currency	Displays the currency code in which the Teller deals.
Total Cash	Specify the total cash for a particular currency, physically present in the bank Teller, at the end of the current posting date.
Cash Available	Displays the system calculated cash for a particular currency, which is available in the teller at the end of the current posting date. **Note** The amount displayed in this column depends on the cash transactions that were carried out by the Teller until the last posting date.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-9 (Cont.) Close Teller Batch - Field Description

Field	Description
Shortage/ Overage Amount	Displays the difference between the **Total Cash** and the **Cash Available**. Based on this difference, the overage or the shortage amount is displayed. **Note** An overage indicates that the physical cash with the Teller is more than the available cash as calculated by the system. A shortage indicates that the available cash calculated by the system is more than the physical cash present with the Teller.
Currency	Displays the currency code.
Denomination	Displays the denomination code.
Demon type	Displays the demon type. Values: Note or Coin
Total Units	Specify the total units available while closing the batch.
Total Value	Displays the total value based on the total units.
System Units	Displays the units available in the system.
System Total	Displays the total value available in the system.
Shortage/Overage Units	Displays the shortage/overage units.
Shortage/Overage Amount	Displays the shortage/overage amount.
Total Cash Amount	Displays the total cash amount.
Denomination Total	Displays the total denomination value with the currency.

3. Specify the TC denomination details. For information on the fields, refer to the **Add TC Denomination Details** section in the **TC Denomination Details** data segment.
4. Click **Submit**.

   The cash balance is updated, and the teller batch is closed for the posting date.

> **Note**
>
> If there is any overage or shortage, the system displays an error message stating that the cash/TC is not balanced for the Teller ID. Also, if any of the conditions mentioned above fail, the system displays an appropriate error message on submit.

2.10 Close Vault Batch

The **Close Vault Batch** screen is used to close the vault batch for a specific date.

The Vault Teller can log in and close the vault batch only if the below conditions are met:

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Verify if there is a difference in the physical cash and that calculated by the system, the overage or shortage has to be booked accordingly. After the overage or shortage is booked, the Vault Teller can close the vault batch for that day.
- Verify that the cash position of the Vault Teller retains the minimum limit for every currency as maintained in the User limits. If the minimum limit is breached, the system prompts the error to maintain the required minimum balance.


> **Note**
>
> The Vault Teller can close the vault batch even if the Tills are open. When the Vault Batch is closed, the user will not be able to post transactions like **Buy Cash from Vault** that involve Vault.

To close the vault batch:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Close Vault Batch** or specify **Close Vault Batch** in the search icon bar and select the screen.

   The **Close Vault Batch** screen is displayed.

Figure 2-10 Close Vault Batch



2. On the **Close Vault Batch** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-10 Close Vault Batch - Field Description

Field	Description
Posting Date	Indicates the date on which the vault batch needs to be closed. **Note** By default, the system displays the current date.
Currency	Displays the currency code in which the Vault Teller deals.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-10 (Cont.) Close Vault Batch - Field Description

Field	Description
Total Cash	Specify the total cash for a particular currency, physically present in the bank Vault Teller, at the end of the current posting date.
Cash Available	Displays the system calculated cash for a particular currency, which is available in the Vault Teller at the end of the current posting date. **Note** The amount displayed in this column depends on the cash transactions that were carried out by the Teller until the last posting date.
Shortage/Overage Amount	Displays the difference between the total cash and the cash available in the Vault, at the end of the current posting date.
Currency	Displays the currency code.
Denomination	Displays the denomination code.
Demon type	Displays the demon type. Values: Note or Coin
Total Units	Specify the total units available while closing the batch.
Total Value	Displays the total value based on the total units.
System Units	Displays the units available in the system.
System Total	Displays the total value available in the system.
Shortage/Overage Units	Displays the shortage/overage units.
Shortage/Overage Amount	Displays the shortage/overage amount.
Total Cash Amount	Displays the total cash amount.
Denomination Total	Displays the total denomination value with the currency.

3. Specify the denomination details for the Traveller's Cheque. For information on the fields, refer to the **Add TC Denomination Details** section in the **TC Denomination Details** data segment.
4. Click **Submit**.

   The cash balance is updated and the vault batch is closed for the posting date.

Note

During vault batch closure, the system will internally transfer the closing balance from the current open Vault ID to the Primary vault of the branch. If there is any overage or shortage, the system displays an error message stating that the cash is not balanced for the Teller ID. Also, if any of the conditions mentioned above fail, the system displays an appropriate error on submit.

Copyright © 2021, 2025, Oracle and/or its affiliates.

2.11 Close Branch Batch

The **Close Branch Batch** screen is used to close the branch batch after confirming that all the branch transactions have been accounted for in the account books.


The posting date for closing a branch batch must be the same date on which the respective branch batch was opened. You need to close all the teller batches and the vault batch of the branch before closing the branch batch for that posting date. Archiving is done as a part of **Close Branch Batch** as per the archival days set up for the branch.

To close the branch batch:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Close Branch Batch** or specify **Close Branch Batch** in the search icon bar and select the screen.

   The **Close Branch Batch** screen is displayed.

Figure 2-11 Close Branch Batch



2. On the **Close Branch Batch** screen, specify the fields. For more information on fields, refer to the field description table.

Table 2-11 Close Branch Batch - Field Description

Field	Description
Posting Date	Indicates the date on which the branch batch needs to be closed. **Note** By default, the system displays the current date.

3. Click **Submit**.

   The branch batch is closed for the specified posting date.

Copyright © 2021, 2025, Oracle and/or its affiliates.

2.12 Book Shortage

The Teller can use the **Book Shortage** screen to book the shortage if the actual or physical cash present is less than the system cash.


While booking the shortage, the system lowers the cash balance to bring it in sync with the physical cash balance of the Teller by sending the difference to a cash shortage GL. Once the system cash and the physical cash are synchronized, the Teller can perform the cash balancing and close the Teller batch for the posting date.

To book the shortage:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Book Shortage** or specify **Book Shortage** in the search icon bar and select the screen.

   The **Book Shortage** screen is displayed.

Figure 2-12 Book Shortage



2. On the **Book Shortage** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-12 Book Shortage - Field Description

Field	Description
Transaction Amount	Displays the local currency of the branch. Specify the amount that needs to be booked for the shortage. **Note** The user can select another currency from the drop-down values in which the shortage amount is to be booked.
Narrative	Displays the default narrative `Book Shortage` and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the system reduces the cash balance by this transaction amount to synchronize with physical cash held with Teller.

- Add Denomination Details
  The **Denomination** segment is used to view the denominations maintained for the transaction currency and enter the denomination units.

2.12.1 Add Denomination Details

The **Denomination** segment is used to view the denominations maintained for the transaction currency and enter the denomination units.

Make sure that the main transaction details are added to the transaction screen.


The denomination details for the withdrawal transactions (when cash is disbursed to the customer) will be populated automatically based on the cash availability in the Teller's Till.

Note

By default, the denomination details will be auto populated. If the `DEF_DEN_FR_WTDWL` value is set to **N** in the **SRV_TM_BC_PARAM_DTLS** table, the auto population of denomination details will be disabled.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 2-13 Denomination Details



Validate the denomination details. For more information on fields, refer to the field description table.

Table 2-13 Denomination Details - Field Description

Field	Description
Denom Code	Displays the unique denomination codes for each currency.
Units	Indicates the number of units for the specified denomination. **Note** By default, the till contents are incremented for inflow transactions such as cash deposits and decremented for outflow transactions such as cash withdrawal. To reverse the transaction, you can specify units in negative.
Value	Displays the system-computed face value of the denomination based on the number of units. **Note** For example, if the denomination code represents USD 100 and the unit is specified as 3, the value will be displayed as 300.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-13 (Cont.) Denomination Details - Field Description

Field	Description
Denomination Amount	Displays the system-computed value of the denomination by multiplying the denomination value with the number of units. **Note** For example, if the denomination code represents USD 100 and the number of units is 10, the denomination amount will be 1000.
Total Cash Amount	Displays the total cash amount. **Note** The system computes the Denomination Amount and validates the amount if it is equal to the Total Cash Amount. It also prompts an error during saving if there is any difference.

2.13 Book Overage

The Teller can use this screen to book the physical cash held in a particular currency, which exceeds the cash in that currency shown in the system.

While booking a cash overage, the system passes the difference to a cash overage liability GL and increases the cash balance, and brings it to synchronize with the physical balance with the Teller. Once the system cash and the physical cash are synchronized, the Teller can perform cash balancing and close the Teller batch for the posting date.


To book the overage:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Book Overage** or specify **Book Overage** in the search icon bar and select the screen.

   The **Book Overage** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 2-14 Book Overage



2. On the **Book Overage** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 2-14 Book Overage - Field Description

Field	Description
Transaction Amount	Displays the local currency of the branch. Specify the amount that needs to be booked for the overage. **Note** The user can select another currency from the drop-down values in which the shortage amount is to be booked.
Narrative	Displays the default narrative `Book Overage` and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the system increases the cash balance by this transaction amount to synchronize with physical cash held with Teller.

Copyright © 2021, 2025, Oracle and/or its affiliates.

2.14 Book Vault Shortage

The Vault Teller can use the **Book Vault Shortage** screen to book the shortage if the actual or physical cash present is less than the system cash.


While booking the shortage, the system lowers the cash balance to bring it in sync with the physical cash balance of the Teller by sending the difference to a cash shortage GL. Once the system cash and the physical cash are synchronized, the Vault Teller can perform the cash balancing and close the Vault Teller batch for the posting date.

To book the shortage:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Book Vault Shortage** or specify **Book Vault Shortage** in the search icon bar and select the screen.

   The **Book Vault Shortage** screen is displayed.

Figure 2-15 Book Vault Shortage



2. On the **Book Vault Shortage** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 2-15 Book Vault Shortage - Field Description

Field	Description
Transaction Amount	Displays the local currency of the branch. Specify the amount that needs to be booked for the shortage. **Note** The user can select another currency from the drop-down values in which the shortage amount is to be booked.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-15 (Cont.) Book Vault Shortage - Field Description

Field	Description
Narrative	Displays the default narrative `Book Vault Shortage` and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the system reduces the cash balance by this transaction amount to synchronize with physical cash held with Vault Teller.

2.15 Book Vault Overage

The Vault Teller can use this screen to book the physical cash held in a vault particular currency, which exceeds the cash in that currency shown in the system.


While booking a cash overage, the system passes the difference to a cash overage liability GL and increases the cash balance, and brings it to synchronize with the physical balance with the Teller. Once the system cash and the physical cash are synchronized, the Vault Teller can perform cash balancing and close the Vault Teller batch for the posting date.

To book the overage

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Book Vault Overage** or specify **Book Vault Overage** in the search icon bar and select the screen.

   The **Book Vault Overage** screen is displayed.

Figure 2-16 Book Vault Overage



2. On the **Book Vault Overage** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 2-16 Book Vault Overage - Field Description

Field	Description
Transaction Amount	Displays the local currency of the branch. Specify the amount that needs to be booked for the overage. **Note** The user can select another currency from the drop-down values in which the shortage amount is to be booked.
Narrative	Displays the default narrative `Book Vault Overage` and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the system increases the cash balance by this transaction amount to synchronize with physical cash held with Vault Teller.

2.16 Teller Session

The teller can perform several specific transactions for a customer in a single session. All the transactions done by the customer are grouped under a single session. At the end of the session, the teller accepts the net amount (of all the transactions done in the session) from the customer.

This topic contains the following subtopics:

- Start Teller Session
  The Teller can use the **Start Teller Session** screen to start the teller session for a customer.
- Stop Teller Session
  The Teller can use the **Stop Teller Session** screen to stop the teller session for a customer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

2.16.1 Start Teller Session


The Teller can use the **Start Teller Session** screen to start the teller session for a customer.

To start a teller session:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Start Teller Session** or specify **Start Teller Session** in the search icon bar and select the screen.

   The **Start Teller Session** screen is displayed.

Figure 2-17 Start Teller Session



2. On the **Start Teller Session** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 2-17 Start Teller Session - Field Description

Field	Description
Customer Number	Specify the customer number. **Note** You can also select from the list of values, which displays all the open and authorized CIF IDs maintained in the system.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 2-17 (Cont.) Start Teller Session - Field Description

Field	Description
Operation Type	Select the operation types of the customer from the drop-down list. The drop-down list shows the following values: • **Transaction** • **Account/Contract** • **Both** **Note** By default, the **Transaction** value is selected.
Incoming Cash Amount	Specify the cash amount at the start of the teller session.
Remarks	Enter remarks for the transaction.

3. On the **Start Teller Session** screen, click on the **CIF Details** data segment.

   The **CIF Details** data segment is displayed with the fields.

Figure 2-18 CIF Details



4. Specify the CIF details. For more information on fields, refer to the field description table.

Table 2-18 CIF Details - Field Description

Field	Description
Executor CIF Number	When you press the **Tab** key, the system defaults the value which can be modified.
Executor CIF Name	Displays the executor CIF.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 2-18 (Cont.) CIF Details - Field Description

Field	Description
Beneficial Owner CIF Number	Select the desired value from the option list, which displays all the open and authorized CIF IDs maintained in the system.
Beneficial Owner CIF Number	Displays the beneficial owner's CIF number.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

2.16.2 Stop Teller Session


The Teller can use the **Stop Teller Session** screen to stop the teller session for a customer.

To stop a teller session:

1. On the Homepage, from **Teller** mega menu, under **Branch Operations**, click **Stop Teller Session** or specify **Stop Teller Session** in the search icon bar and select the screen.

   The **Stop Teller Session** screen is displayed.

Figure 2-19 Stop Teller Session



2. On the **Stop Teller Session** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 2-19 Stop Teller Session - Field Description

Field	Description
Customer Number	Displays the customer number associated with the selected session ID. **Note** When you launch the **Stop Teller Session**, its corresponding customer number will be populated in this field.
Session ID	The system defaults the session ID started.
Incoming Cash Amount	Displays the incoming cash amount that was entered at the start of the teller session.
Difference Amount	Displays the difference amount by which the total transaction amount in the session exceeds the incoming cash amount or is less than the incoming cash amount.
Cash In/ Out	Displays in/out based on the difference amount value as **IN** or **OUT**.

3. On the **Stop Teller Session** screen, click on the **Teller Transaction Details** data segment.

   The **Teller Transaction Details** data segment is displayed.

Figure 2-20 Teller Transaction Details



4. On the **Teller Transaction Details** segment, specify the fields. For more information on fields, refer to the field description table.

Table 2-20 Teller Transaction Details - Field Description

Field	Description
Transaction Reference No	Displays the reference number of the transactions completed within the teller session.
Function Id	Displays the Function ID of the transactions that occurred within the teller session.
Teller Sequence Number	Displays the unique sequence number generated for the teller to check the transaction in EJ Log.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 2-20 (Cont.) Teller Transaction Details - Field Description

Field	Description
Transaction Amount	Displays the Total Transaction Amount for the particular Transaction Reference No.
Total Charge Amount	Displays the Total Charge Amount for the specified **Transaction Reference No**. Click on the eye button to view the individual charges maintained for the transaction.

5. On the **Stop Teller Session** screen, click on the **Teller Session Denomination Details** data segment.

   The **Teller Session Denomination Details** data segment is displayed.

Figure 2-21 Teller Session Denomination Details



6. On the **Teller Session Denomination Details** segment, specify the fields. For more information on fields, refer to the field description table.

Table 2-21 Teller Session Denomination Details - Field Description

Field	Description
Transaction Currency	Displays the currency for the **Total Transaction Amount**.
Total Transaction Amount	Displays the total transaction amount for a particular currency within the teller session.
Cash In/Out	Displays the cash in/out value for the **Total Transaction Amount**.
Add Denomination	Click **Add** to view the denominations maintained for the transaction currency and to enter the denomination units. For more information on this segment, refer to Add Denomination Details.

7. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3

Till-Vault Operations

The Vault Teller or Teller can use Till-Vault operations to monitor the cash and currency boxes for the day. It is also used to perform cash transfers from or to the Vault/Till.

This topic contains the following subtopics:

- Buy TC from Agent
  The **Buy TC from Agent** screen is used to buy TC from agents into the branch's vault. Only a Vault user can access this screen.
- Buy TC from Head Office
  The **Buy TC from HO** screen is used to buy TC from head office into branch's vault. Only a Vault user can access this screen.
- Buy TC from Vault
  The **Buy TC from Vault** screen is used to buy TC from the vault to transfer TCs into logged-in Teller's Till. Only a Teller can access this screen.
- Return TC to Vault
  The Teller can use the **Return TC to Vault** screen to return TC to the branch's vault.
- Return TC to HO
  The **Return TC to HO** screen is used to sell TC to the HO, and only a Vault Teller can access this screen.
- Buy Cash from Currency Chest
  The Vault Teller can use this screen to get cash from the currency chest after opening the vault batch and deposit it into the vault. Once the cash is transferred from the currency chest, the system updates the cash position.
- Sell Cash to Currency Chest
  The Vault Teller can use this screen to sell cash to the Central Bank from the vault after all the Tellers have sold the additional cash to the Vault Teller.
- Buy Cash from Vault
  The Teller can use the **Buy Cash from Vault** screen to get cash from the vault.
- Sell Cash to Vault
  The Teller can use the **Sell Cash to Vault** screen to sell cash to the vault. It is used only when the *cash held* exceeds the limit set at the template level for any currency.
- Buy Cash from Till
  The Teller can use this screen to transfer cash from another Teller in case of insufficient funds available in the till to perform the customer cash transactions.
- Sell Cash to Till
  The Teller can use the **Sell Cash to Till** screen to transfer cash to another Teller's Till in case of excess funds available in the Till.
- Denomination Exchange
  The Teller can use the **Denomination Exchange** screen to exchange the currency denominations.
- Vault Denomination Exchange
  The Vault Teller can use the **Vault Denomination Exchange** screen to exchange the currency denominations by vault users.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Inter Branch Transactions
  The interbranch transactions are used to send a request from a bank branch to the central cash depository, for pickup or delivery of cash.

3.1 Buy TC from Agent


The **Buy TC from Agent** screen is used to buy TC from agents into the branch's vault. Only a Vault user can access this screen.

To buy TC from agents:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Buy TC from Agent** or specify **Buy TC from Agent** in the search icon bar and select the screen.

   The **Buy TC from Agent** screen is displayed.

Figure 3-1 Buy TC from Agent



2. On the **Buy TC from Agent** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-1 Buy TC from Agent - Field Description

Field	Description
TC Amount	Select the currency from the drop-down values, and specify the TC Amount.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-1 (Cont.) Buy TC from Agent - Field Description

Field	Description
Issuer Code	Click the search icon, and select the issuer code from the list of values. **Note** The list of values provides the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified issuer code.
Narrative	Displays the narrative as **Buy TC From Agent**, and it can be modified.

3. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Buy TC.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the TC position (TC Inflow) is updated to the branch vault (vault ID that is opened) for the combination of Issuer code, TC Currency, TC Denom Code, and Series.
>
> In addition, during transaction completion, the system creates individual TC records for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number with TC status as Null.


- Add TC Denominations to Buy TC
  You can add the denomination details for the TC in the **TC Denominations** data segment.

3.1.1 Add TC Denominations to Buy TC

You can add the denomination details for the TC in the **TC Denominations** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 3-2 TC Denominations



Copyright © 2021, 2025, Oracle and/or its affiliates.

To add the denomination details:

On the **TC Denominations** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 3-2 TC Denominations - Field Description

Field	Description
Denom Code	Specify the TC denomination code from the list of values.
Currency	Displays the default TC Currency.
Series	Specify the series of TC denomination code that needs to be purchased from the agent. **Note** This field accepts alphanumeric values.
Count	Specify the units.
Start Number	Specify the start number of the series.
End Number	Displays the end number, which is the sum of the start number and the count.
TC Amount	Displays the TC Amount, which is the product of the denomination and the count.
Total TC Amount	Displays the total TC amount along with the currency.
Denomination Amount	Displays the denomination amount along with the currency.

3.2 Buy TC from Head Office

The **Buy TC from HO** screen is used to buy TC from head office into branch's vault. Only a Vault user can access this screen.


To buy TC from head office:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Buy TC from HO** or specify **Buy TC from HO** in the search icon bar and select the screen.

   The **Buy TC from HO** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 3-3 Buy TC from HO



2. On the **Buy TC from HO** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-3 Buy TC from HO - Field Description

Field	Description
TC Amount	Select the currency from the drop-down values, and specify the TC Amount.
Issuer Code	Click the search icon and select the issuer code from the list of values. **Note** The list of values provides the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified issuer code.
Narrative	Displays the narrative as **Buy TC From HO**, and it can be modified.

3. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Buy TC.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the TC position (TC Inflow) is updated to the branch vault (vault ID that is opened) for the combination of Issuer code, TC Currency, TC Denom Code, and Series.
>
> In addition, during transaction completion, the system creates individual TC records for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number with TC status as Null.

3.3 Buy TC from Vault


The **Buy TC from Vault** screen is used to buy TC from the vault to transfer TCs into logged-in Teller's Till. Only a Teller can access this screen.

To buy TC from the vault:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Buy TC from Vault** or specify **Buy TC from Vault** in the search icon bar and select the screen.

   The **Buy TC from Vault** screen is displayed.

Figure 3-4 Buy TC from Vault



2. On the **Buy TC from Vault** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-4 Buy TC from Vault - Field Description

Field	Description
TC Amount	Select the currency from the drop-down values, and specify the TC Amount.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 3-4 (Cont.) Buy TC from Vault - Field Description

Field	Description
Issuer Code	Click the search icon and select the issuer code from the list of values. **Note** The list of values provides the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified issuer code.
Narrative	Displays the narrative as **Buy TC From Vault**, and it can be modified.

3. Click on the **TC Denominations** segment.

   The **TC Denominations** segment is displayed.

Figure 3-5 TC Denominations



4. In the **TC Denominations** segment, specify the fields. For more information on fields, refer to the field description table.

Table 3-5 TC Denominations - Field Description

Field	Description
Denom Code	Specify the TC denomination code from the list of values.
Currency	Displays the default TC Currency.
Series	Specify the series of the TC denomination code that needs to be purchased from the Vault. **Note** The list of values contains the valid TC series that are available with Vault. On click of LOV, the search criterion field will have **Series**, and the result criterion will display the **Series** and **Start Number**.
Count	Specify the count of the TC.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-5 (Cont.) TC Denominations - Field Description

Field	Description
Start Number	Displays the starting number of the series. **Note** Based on the series selected, the system will populate the start number available for the combination of **Currency**, **TC Denom Code**, and **Series**.
End Number	Displays the end number, which is the sum of the start number and the count.
TC Amount	Displays the TC Amount, which is the product of the denomination and the count.
Total TC Amount	Displays the total TC amount along with the currency.
Denomination Amount	Displays the denomination amount along with the currency.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the TC position (TC Outflow) is updated to the branch vault, and TC Inflow is updated to the logged-in Teller for the combination of Issuer Code, TC Currency, TC denom Code, and Series to the extent of TC denomination units being purchased.

In addition, during transaction completion, the system updates the TC status as **Unused** for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number.

3.4 Return TC to Vault

The Teller can use the **Return TC to Vault** screen to return TC to the branch's vault.


To sell TC to the branch's vault:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Return TC to Vault** or specify **Return TC to Vault** in the search icon bar and select the screen.

   The **Return TC to Vault** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 3-6 Return TC to Vault



2. On the **Return TC to Vault** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-6 Return TC to Vault - Field Description

Field	Description
TC Amount	Select the TC currency from the drop-down values, and specify the TC Amount.
Issuer Code	Click the search icon and select the issuer code from the list of values. **Note** The list of values provides the HO code of the logged-in branch and the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified **Issuer Code**.
Narrative	Displays the narrative as **Sell TC to Vault**, and it can be modified.

3. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Return TC.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

On transaction submission, the TC position (TC outflow) is decreased for logged-in Teller ID, and the TC Position (TC Inflow) is incremented for Vault ID of the branch. It is performed for the combination of Issuer Code, TC Currency, TC Denom code, and Series to the extent of TC denomination units being purchased.

In addition, during transaction completion, the system updates the TC Status as **Null** for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number.


- Add TC Denominations to Return TC
  You can add the denomination details for the TC in the **TC Denominations** data segment.

3.4.1 Add TC Denominations to Return TC

You can add the denomination details for the TC in the **TC Denominations** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 3-7 TC Denominations



To add the denomination details:

On the **TC Denominations** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 3-7 TC Denominations - Field Description

Field	Description
Denom Code	Specify the TC denomination code from the list of values.
Currency	Displays the default TC currency.
Series	Specify the series of the TC Denom Code that is being purchased from the agent.
Count	Specify the count of the TC that needs to be sold.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-7 (Cont.) TC Denominations - Field Description

Field	Description
Start Number	Display the starting number of the series. **Note** Based on the series selected, the system will populate the **Start Number** available for the combination of **Currency**, **TC Denom Code**, and **Series**.
End Number	Displays the end number, which is the sum of start number and the count.
TC Amount	Displays the TC Amount, which is the product of the denomination and the count.
Total TC Amount	Displays the total TC amount along with the currency.
Denomination Amount	Displays the denomination amount along with the currency.

3.5 Return TC to HO


The **Return TC to HO** screen is used to sell TC to the HO, and only a Vault Teller can access this screen.

To sell TC to the HO:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Return TC to HO** or specify **Return TC to HO** in the search icon bar and select the screen.

   The **Sale TC to HO** screen is displayed.

Figure 3-8 Sale TC to HO



2. On the **Sale TC to HO** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-8 Sale TC to HO - Field Description

Field	Description
TC Amount	Select the TC currency from the drop-down values, and specify the TC Amount.
Issuer Code	Click the search icon and select the issuer code from the list of values. **Note** The list of values provides the HO code of the logged-in branch and the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified **Issuer Code**.
Narrative	Displays the narrative as **Return TC to HO**, and it can be modified.

3. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Return TC.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the TC position (TC outflow) is decreased for the Vault ID for the combination of Issuer Code, TC Currency, TC Denom code, and Series to the extent of TC denomination units being purchased.

3.6 Buy Cash from Currency Chest

The Vault Teller can use this screen to get cash from the currency chest after opening the vault batch and deposit it into the vault. Once the cash is transferred from the currency chest, the system updates the cash position.


To buy cash from the currency chest:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Buy Cash from Ccy Chest**.

   The **Buy Cash from Currency Chest** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 3-9 Buy Cash from Currency Chest



2. On the **Buy Cash from Currency Chest** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-9 Buy Cash from Currency Chest - Field Description

Field	Description
Total Required Cash	Specify the total cash that you need to buy from Currency Chest. **Note** By default, the system displays the local currency of the branch. You can select another currency from the drop-down values in which cash needs to be bought from the currency chest.
Narrative	Displays the default narrative `Buy Cash from Currency Chest`, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the cash balance of the Vault Teller is updated successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3.7 Sell Cash to Currency Chest

The Vault Teller can use this screen to sell cash to the Central Bank from the vault after all the Tellers have sold the additional cash to the Vault Teller.


The Vault Teller can close the batch only if the excess cash is not available at the end of the day.

To sell cash to currency chest:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Sell Cash to Ccy Chest** or specify **Sell Cash to Ccy Chest** in the search icon bar and select the screen.

   The **Sell Cash to Currency Chest** screen is displayed.

Figure 3-10 Sell Cash to Currency Chest



2. On the **Sell Cash to Currency Chest** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-10 Sell Cash to Currency Chest - Field Description

Field	Description
Total Required Cash	Specify the total cash that you need to sell to the Currency Chest. **Note** By default, the system displays the local currency of the branch. The user can select another currency from the drop-down values in which cash needs to be sold to the currency chest.
Narrative	Displays the default narrative `Sell Cash to Currency Chest`, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the cash balance of the Vault Teller is updated successfully.

3.8 Buy Cash from Vault

The Teller can use the **Buy Cash from Vault** screen to get cash from the vault.


To get cash from the vault:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Buy Cash from Vault** or specify **Buy Cash from Vault** in the search icon bar and select the screen.

   The **Buy Cash from Vault** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 3-11 Buy Cash from Vault



2. On the **Buy Cash from Vault** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-11 Buy Cash from Vault - Field Description

Field	Description
Total Required Cash	Specify the total cash that you need to transfer from the vault to the till of the logged-in Teller. **Note** By default, the system displays the local currency of the branch. The user can select another currency from the drop-down values in which cash needs to be transferred from the vault.
Narrative	Displays the default narrative as **Transfer Cash from Vault**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the accounting entries (for example, Dr Teller Cash GL & Cr Vault Cash GL) for the transaction will be handed off to FCUBS based on the settlement definition maintained for the function code. Also, the cash positions of the Teller are increased and the Vault Teller is decreased successfully.
>
> If the cash position of the Vault Teller is less than the total cash requested by the Teller:
>
> - The system displays an error message
> - The Teller needs to perform this transaction after the vault is replenished sufficiently

3.9 Sell Cash to Vault

The Teller can use the **Sell Cash to Vault** screen to sell cash to the vault. It is used only when the *cash held* exceeds the limit set at the template level for any currency.


For transferring cash to the vault, the Teller batch and the Vault batch need to be opened for the posting date.

To sell cash to the vault:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Sell Cash to Vault** or specify **Sell Cash to Vault** in the search icon bar and select the screen.

   The **Sell Cash to Vault** screen is displayed.

Figure 3-12 Sell Cash to Vault



2. On the **Sell Cash to Vault** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-12 Sell Cash to Vault - Field Description

Field	Description
Total Required Cash	Specify the total cash that you need to transfer to the vault from the till of the logged-in Teller. **Note** By default, the system displays the local currency of the branch. The user can select another currency from the drop-down values in which cash needs to be transferred to the vault.
Narrative	Displays the default narrative as **Transfer Cash to Vault**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the accounting entries (for example, Dr Vault Cash GL & Cr Teller Cash GL) for the transaction will be handed off to FCUBS based on the settlement definition maintained for the function code. Also, the cash balance of the Teller is decreased and the Vault Teller is increased successfully.

3.10 Buy Cash from Till

The Teller can use this screen to transfer cash from another Teller in case of insufficient funds available in the till to perform the customer cash transactions.

Teller can request the required cash in a specific currency, and on completing this transaction, the system updates the cash position of both the Tellers to the extent of the transaction amount.


To transfer cash from another Teller's till:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Buy Cash from Till** or specify **Buy Cash from Till** in the search icon bar and select the screen.

   The **Buy Cash from Till** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 3-13 Buy Cash from Till



2. On the **Buy Cash from Till** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-13 Buy Cash from Till - Field Description

Field	Description
Teller ID	Displays the Teller ID from where the cash needs to be transferred.
Total Required Cash	Specify the total cash that you need to transfer from the specified **Teller ID** to the till of logged-in Teller. **Note** By default, the system displays the local currency of the branch. You can select another currency from the drop-down values in which cash needs to be transferred.
Narrative	Displays the default narrative as **Transfer Cash from Till**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the cash balance of both the Tellers is updated successfully.

3.11 Sell Cash to Till

The Teller can use the **Sell Cash to Till** screen to transfer cash to another Teller's Till in case of excess funds available in the Till.


In addition, the Teller can request to transfer from the Till in a specific currency. Once the transaction is completed, the system updates the cash position of both the Tellers to the extent of the transaction amount.

To sell cash to the Till:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Sell Cash to Till** or specify **Sell Cash to Till** in the search icon bar and select the screen.

   The **Sell Cash to Till** screen is displayed.

Figure 3-14 Sell Cash to Till



2. On the **Sell Cash to Till** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-14 Sell Cash to Till - Field Description

Field	Description
Teller ID	Displays the **Teller ID** from which the cash needs to be transferred.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-14 (Cont.) Sell Cash to Till - Field Description

Field	Description
Total Required Cash	Specify the total cash that you need to transfer to the specified **Teller ID** from the till of the logged-in Teller. **Note** By default, the system displays the local currency of the branch. The user can select another currency from the drop-down values in which the cash needs to be transferred.
Narrative	Displays the default narrative as **Transfer Cash to Till**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the cash balance of both the Tellers is updated successfully.

3.12 Denomination Exchange

The Teller can use the **Denomination Exchange** screen to exchange the currency denominations.

The exchange can be performed for the internal purpose of the bank or based on the customer's request. The outgoing cash needs to be entered as negative in the denomination details segment. This transaction involves only denomination exchange from the Till. The total value in the Till remains the same, and accounting entries are not posted for this exchange. However, the denomination count in the Till changes, and hence it needs to be updated.


To exchange the currency denominations:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Denomination Exchange** or specify **Denomination Exchange** in the search icon bar and select the screen.

   The **Denomination Exchange** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 3-15 Denomination Exchange



2. On the **Denomination Exchange** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-15 Denomination Exchange - Field Description

Field	Description
Branch Code	Displays the logged-in branch code.
Transaction Currency	Specify the currency for which the denominations are to be exchanged.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the cash balance of the Teller is updated successfully.

3.13 Vault Denomination Exchange

The Vault Teller can use the **Vault Denomination Exchange** screen to exchange the currency denominations by vault users.

The bank can perform the exchange for its internal purposes or based on the customer's request and the denomination details segment, you must enter outgoing cash as a negative number. The Vault Teller initiates this transaction with only a denomination exchange. The total

Copyright © 2021, 2025, Oracle and/or its affiliates.


value inthe Vault remains unchanged, and no accounting entries are posted for this exchange. The Vaultchanges require updating as the denomination counts change.

To exchange the currency denominations by vault users:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Vault Denomination Exchange** or specify **Vault Denomination Exchange** in the search icon bar and select the screen.

   The **Vault Denomination Exchange** screen is displayed.

Figure 3-16 Vault Denomination Exchange



2. On the **Vault Denomination Exchange** screen, you can specify the fields. For more information on what each field represents, consult the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-16 Vault Denomination Exchange - Field Description

Field	Description
Branch Code	Displays the logged-in branch code.
Transaction Currency	Specify the currency for which the denominations are to be exchanged.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> If no approval warning is raised when saving a transaction, it will be moved to authorization. On transaction completion, the cash balance of the vault is updated successfully.

3.14 Inter Branch Transactions

The interbranch transactions are used to send a request from a bank branch to the central cash depository, for pickup or delivery of cash.

A branch can request delivery of cash when it is having a shortage of cash and request for pickup of cash when it has excess cash. The process steps to request cash delivery and pickup are explained below.

The process steps for cash delivery are as follows:

1. The requesting branch sends a request for delivery of cash using the 1409 screen.
2. The remitting branch queries for the requests and accepts the request using the 1409 screen.
3. On the delivery date, the remitting branch books a transaction using the 1410 screen with the denominations being sent and generated.
4. On the delivery date, the remitting branch books a transaction input using the 1410 screen, generates advice, and sends money to the requesting branch.
5. On receiving money and advice, the requesting branch uses the 1411 screen to verify the denominations and save the liquidation.

The process steps for cash pickup are as follows:

1. The requesting branch sends a request for the pickup of cash using the 1409 screen.
2. The receiving branch queries for the requests and accepts the request using the 1409 screen.
3. On the date of cash pickup, the receiving branch generates advice and sends it to requesting branch.
4. The requesting branch receives the advice and books the transaction using the 1410 screen.
5. The requesting branch generates the advice and sends money and advice to the receiving branch.
6. The receiving branch receives the money and advice and verifies and liquidates the request using the 1411 screen.

> **Note**
>
> Accounting entries are not passed for the 1409 screen.

Inter branch Transaction

The process for completion of Inter branch Transaction in two steps is as follows:

1. The requesting branch initiates transfer using the 1410 screen by clicking on **New**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

2. The requesting branch generates the advice and sends money and advice to the receiving branch.
3. The receiving branch receives the money and advice and verifies and liquidates the request using the 1411 screen.

Inter Branch Transaction Input

Branch can also initiate Inter branch transfer directly from this screen for two step completion of Transfer.

This topic contains the following subtopics:

- Inter Branch Transaction Request
  The **Inter Branch Transaction Request** screen is used to create the inter-branch cash pickup or cash delivery requests.
- Inter Branch Transaction Input
  The **Inter Branch Transaction Input** screen is used for a branch to act as a remitting branch to book an input transaction for cash delivery.
- Inter Branch Transaction Liquidation
  The receiving branch can use the **Inter Branch Transaction Liquidation** screen to receive the cash, verify the advice with denomination units, and liquidate the request.

3.14.1 Inter Branch Transaction Request


The **Inter Branch Transaction Request** screen is used to create the inter-branch cash pickup or cash delivery requests.

To create the inter-branch transaction request:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Inter Branch Txn Req** or specify **Inter Branch Txn Req** in the search icon bar and select the screen.

   The **Inter Branch Transaction Request** screen is displayed.

Figure 3-17 Inter Branch Transaction Request



Copyright © 2021, 2025, Oracle and/or its affiliates.

2. On the **Inter Branch Transaction Request** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-17 Inter Branch Transaction Request - Field Description

Field	Description
New	Click this button to create a new inter branch transaction and generate the inter branch request reference number.
Query	Click **Query** to enable the field **Inter Branch Request Reference**.
Inter Branch Request Reference	The following conditions apply to this field: • If you click **New**, the request reference number for the inter branch transaction is displayed. • If you click **Query**, select the inter branch request reference from the list of values. The list of values fetches only the reference numbers that are saved and not submitted.
Transaction Amount	Select the transaction currency from the option list. Specify the amount that needs to be transferred.
Requesting Branch	Displays the branch code of requesting branch.
Requesting Branch Description	Displays the name of the branch code specified.
To Branch	Select the branch code to which the request is being made.
To Branch Description	Displays the name of the specified **To Branch**.
Request Type	Select from the following request types: • `Cash Delivery` - when the branch is in short of cash. • `Cash Pickup` - when the branch has excess cash.
Request Date	Displays the current date as the request date.
Cash Delivery/Pickup Date	Specify the date of cash delivery/pickup. **Note** By default, the current system date is displayed, and it can be modified.
Request Status	Select the status of the request. The drop-down list shows the following options: • `Request` - to create a new request. • `Accept` - to accept a request received. • `Pending` - system-defined status indicating that the request has been sent but not accepted. • `Initiated` - system-defined status indicating that the request has been accepted and initiated. • `Liquidated` - system-defined status indicating that the request has been processed and liquidated.
Narrative	Specify the remarks, if any.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   The request is sent to the receiving/remitting branch for further processing.

> **Note**
>
> The destination branch can access the same screen to accept or reject the request.

3.14.2 Inter Branch Transaction Input

The **Inter Branch Transaction Input** screen is used for a branch to act as a remitting branch to book an input transaction for cash delivery.


It is also used for the branch to act as a receiving branch to generate the advice and send it to the requesting branch. This option is allowed only after the destination branch has accepted the inter-branch transaction request.

To book an inter-branch transaction input:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Inter Branch Txn Input** or specify **Inter Branch Txn Input** in the search icon bar and select the screen.

   The **Inter Branch Transaction Input** screen is displayed.

Figure 3-18 Inter Branch Transaction Input



2. On the **Inter Branch Transaction Input** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-18 Inter Branch Transaction Input - Field Description

Field	Description
Inter Branch Request Reference	Select the request reference from the list of values.
New	If branch wants to initiate Inter branch transfer directly from this screen then click on **New** and transaction reference is populated to Inter branch request reference field.
Query	Click **Query** to fetch and populate the request details.
From Branch	Displays the branch code of **From Branch**. The following values are applied based on the request type in the **Inter Branch Transaction Request** screen: • For `Cash Delivery`, the **To Branch** in the **Inter Branch Transaction Request** screen is populated in this field. • For `Cash Pickup`, the **Requesting Branch** in the **Inter Branch Transaction Request** screen is populated in this field.
From Branch Description	Displays the description of the **From Branch**.
From Vault ID	Displays the Vault user of the specified **From Branch**.
To Branch	Displays the branch code of **To Branch**. The following values are applied based on the request type in the **Inter Branch Transaction Request** screen: • For `Cash Delivery`, the **Requesting Branch** in the **Inter Branch Transaction Request** screen is populated in this field. • For `Cash Pickup`, the **To Branch** in **Inter Branch Transaction Request** screen is populated in this field.
To Branch Description	Displays the description of specified **To Branch**.
To Vault ID	Displays the Vault user of **To Branch**.
Transaction Amount	Displays the transaction currency and transaction amount based on the request reference.
Requested Date	Displays the date on which the transaction is requested.
Narrative	Specify the remarks, if any.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   The request is sent to the requesting branch for further processing.

> **Note**
>
> - The request status in the **Inter Branch Transaction Request** screen will be internally updated to `Initiated` for the related request reference number. In addition, the system will post the accounting entries (for example, Dr Sending Branch Inter Branch Transit GL & Cr Sending Branch Vault GL) for the Inter Branch Input transaction as per the settlement definition maintained for the function code, and advice will be generated on transaction completion.
> - When saving a transaction without raising an approval warning, it is moved to authorization.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3.14.3 Inter Branch Transaction Liquidation

The receiving branch can use the **Inter Branch Transaction Liquidation** screen to receive the cash, verify the advice with denomination units, and liquidate the request.

This screen can be accessed by:


- The requesting branch for cash delivery
- The receiving branch for cash pickup

To perform the inter-branch transaction liquidation:

1. On the Homepage, from **Teller** mega menu, under **Till-Vault Operations**, click **Inter Branch Txn Liq** or specify **Inter Branch Txn Liq** in the search icon bar and select the screen.

   The **Inter Branch Transaction Liquidation** screen is displayed.

Figure 3-19 Inter Branch Transaction Liquidation



2. On the **Inter Branch Transaction Liquidation** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 3-19 Inter Branch Transaction Liquidation - Field Description

Field	Description
Inter Branch Request Reference	Select the request reference from the list of values.
Query	Click **Query** to fetch and populate the request details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 3-19 (Cont.) Inter Branch Transaction Liquidation - Field Description

Field	Description
From Branch	Displays the branch code of **From Branch**.
From Branch Description	Displays the description of the **From Branch**.
From Vault ID	Displays the Vault user of the specified **From Branch**.
To Branch	Displays the branch code of **To Branch**.
To Branch Description	Displays the description of specified To Branch.
To Vault ID	Displays the Vault user of To Branch.
Transaction Amount	Displays the transaction currency and transaction amount based on the request reference.
Requested Date	Displays the date on which the transaction is requested.
Narrative	Specify the remarks, if any.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   The system updates the request reference as **Liquidated** in the **Inter Branch Transaction Request** screen for the related request reference.

> **Note**
>
> - The system will post the accounting entries (for example, Dr Receiving Branch Vault Transit GL & Cr Sending Branch Inter Branch Transit GL) for the Inter Branch Input transaction as per the settlement definition maintained for the function code.
>   As the liquidation transaction accounting involves two different branches, the corresponding IB position entries will be processed by FCUBS accordingly.
> - When saving a transaction without raising an approval warning, it is moved to authorization.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4

Customer Transactions

The Teller can use Customer Transactions to perform financial transactions for customer accounts.

This topic contains the following subtopics:

- Cash Deposit
  The **Cash Deposit** screen is used to deposit the cash in a CASA. Cash can be deposited in either account currency or any foreign currency that is allowed.
- Cash Withdrawal
  The **Cash Withdrawal** screen is used to withdraw funds from the CASA account of the customer.
- Cheque Withdrawal
  The **Cheque Withdrawal** screen is used to withdraw cash from the CASA account of the customer against the in-house cheque.
- FX Sale Against Account
  The Foreign Exchange **(FX) Sale Against Account** screen is used to sell the foreign currency from the branch through the CASA account.
- FX Sale Against Walk-in
  The **FX Sale Against Walk-in** screen is used to sell a foreign currency to a walk-in customer in return for the equivalent amount received in the local currency.
- FX Purchase Against Account
  The **FX Purchase Against Account** screen is used to purchase foreign currency from the branch through the CASA account.
- FX Purchase Against Walk-in
  The **FX Purchase Against Walk-in** screen is used to buy a foreign currency from a walk-in customer in return for the equivalent amount in the local currency.
- Close Out Withdrawal
  The **Close Out Withdrawal** screen to initiate an account closure and close the CASA account by either dispersing the cash to the customer or by account transfer or by issuing Bankers Cheque.
- Close Out Withdrawal by Multi-Mode
  The **Close Out Withdrawal by Multi Mode** screen is used to close the CASA account by multi-mode payout options, which include cash, account transfer, and BC. This screen can be used only when the closeout withdrawal needs to be done in multiple payout modes.
- Safe Deposit Rental By Cash
  The Teller can use the **Safe Deposit Rental By Cash** screen to make payment by cash for the safe deposit locker of the customer.
- Recurring Deposit Payment by Cash
  The **Recurring Deposit Payment by Cash** screen is used to make payment for the Recurring Deposit (RD) account of the customer by cash.
- F23C Tax Payment by Cash
  The **F23C Tax Payment By Cash** screen is used to capture data related to the F23C tax document for a customer and collect the corresponding tax by cash from the customer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- F24C Tax Payment By Cash
  The **F24C Payment Details** screen is used to capture data related to the F24C tax document for a customer and collect the corresponding tax by cash from the customer.
- F23 Tax Payment by Account
  The **F23 Tax Payment by Account** screen is used to capture data related to the F23 tax document for a customer and collect the corresponding tax by cash from the customer.
- F24 Tax Payment By Account
  The **F24 Tax Payment By Account** screen is used to capture data related to the F24 tax document for a customer and collect the corresponding tax by account from the customer.

4.1 Cash Deposit

The **Cash Deposit** screen is used to deposit the cash in a CASA. Cash can be deposited in either account currency or any foreign currency that is allowed.


Whenever any transaction in foreign currency is posted to the account, it is converted to the account currency based on the maintained exchange rate for the transaction.

To deposit cash:

1. On the Homepage, click **Teller**. On the Teller Mega Menu, under **Customer Transaction**, click **Cash Deposit** or specify the **Cash Deposit** in the search icon bar.

   The **Cash Deposit** screen is displayed.

Figure 4-1 Cash Deposit



2. On the **Cash Deposit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-1 Cash Deposit - Field Description

Field	Description
Account Number	Specify a valid account number for the customer. When you press the **Tab** key, the corresponding account information will be displayed in the **Customer Information** widget. **Note** In addition, you can use Oracle Banking Virtual Accounts. These Virtual Accounts are used as a routing account to credit the underlying physical account. The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Transaction Amount	Displays the local currency of the branch. You can also select other transaction currencies from the drop-down values. Specify the transaction amount that needs to be credited to the customer account.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-1 (Cont.) Cash Deposit - Field Description

Field	Description
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated cost rate and transaction rate.
Account Amount	Displays the transaction amount converted in terms of account amount based on the exchange rate. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Deposit**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   Once you submit the transaction, the system validates the following:

   - Mandatory fields
   - Allowed minimum/maximum limit amount for the user ID
   - Allowed currency for Teller user ID
   - Till balance and branch breaching limit
   - Function code preferences

Copyright © 2021, 2025, Oracle and/or its affiliates.

If any of the validation fails, the system will prompt appropriate information, warning, or error message. For more information, refer to the following steps:

- If an information message is prompted, click **OK** to confirm and complete the transaction.
- If a warning message is prompted, the system will move the transaction for authorization. Once approved, the transaction is moved to Teller **Electronic Journal** for completion. Refer to authorization procedures to know more about authorization processing.
- If any validation error is prompted, you need to update the details to fix the error and re-submit the transaction.
- If any other error message is prompted, the transaction is discarded and does not get saved.
- If you click **Close** or **Cancel** after specifying the transaction details, then the data will not persist.

When the Teller completes the transaction, the corresponding Teller's cash position is updated.

The `Transaction Completed Successfully` information message is displayed.

- Charge Details
  The **Charge Details** segment is used to view the computed charge details based on the charge maintenance defined for the function code.


4.1.1 Charge Details

The **Charge Details** segment is used to view the computed charge details based on the charge maintenance defined for the function code.

Make sure that the charge details data segment are added to the transaction screen.

This segment is applicable for all Financial Customer transactions. If no charge is maintained for the combination, then the transaction is saved without any charges.

Figure 4-2 Charge Details



You can view or waive the computed charges. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-2 Charge Details - Field Description

Field	Description
Total Charges	Displays the total charges in transaction currency (TCY) and branch local currency (LCY).
Detailed View	Displays the following charge details of each charge code: • Charge Code • Currency • Charge Amount • Waiver • Charge By Cash • Charge TCY • Charge LCY • Basis • Min Charge • Max Charge • Price Rule Id • Credit Account • Debit Account
Charge Code	The system defaults the charge components applicable to the transaction.
Currency	Displays the currency in which the charge has to be deducted.
Charge Amount	Displays the charge amount that needs to be deducted for the corresponding charge component. **Note** The charge amount can be modified only if the field is enabled in the **Function Code Preferences** screen. The modified charge amount will be validated against the minimum and maximum charge amount that can be configured at the **Charge Maintenance** screen. When an individual charge amount is modified, the system will recalculate all the dependent charges.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-2 (Cont.) Charge Details - Field Description

Field	Description
Waiver	If necessary, check this box against the charge component to waive a certain charge for the customer. **Note** When the **Waiver** is enabled, the value under **Charge Amount** will be waived and no charge accounting entries will be passed. The charge waiver can be enabled at individual charge level without impacting other linked charges. The minimum charge amount configured at the charge maintenance level, will not be validated when the charge is waived.
Charge By Cash	Indicates whether the charges are to be collected by cash.

4.2 Cash Withdrawal

The **Cash Withdrawal** screen is used to withdraw funds from the CASA account of the customer.

The withdrawal is subject to the availability of a sufficient balance or available credit limit. When the transaction is performed, it updates the available balance in the CASA account immediately.


To withdraw cash:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **Cash Withdrawal** or specify **Cash Withdrawal** in the search icon bar and select the screen.

   The **Cash Withdrawal** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-3 Cash Withdrawal



2. On the **Cash Withdrawal** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-3 Cash Withdrawal - Field Description

Field	Description
Account Number	Specify a valid customer account number. **Note** When you press the **Tab** key, the corresponding account information will be displayed in the **Customer Information** widget. The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Transaction Amount	Displays the local currency of the branch. You can also select another currency from the drop-down values. Specify the transaction amount that needs to be debited from the customer account.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-3 (Cont.) Cash Withdrawal - Field Description

Field	Description
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as `Y`.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Account Amount	Displays the transaction amount converted in terms of account amount based on the exchange rate. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-3 (Cont.) Cash Withdrawal - Field Description

Field	Description
Total Charge Amount	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Withdrawal**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the cash is withdrawn successfully from the customer account. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

4.3 Cheque Withdrawal

The **Cheque Withdrawal** screen is used to withdraw cash from the CASA account of the customer against the in-house cheque.

The withdrawal is subject to the availability of a sufficient balance or available credit limit. To verify the signature for the transactions, you can click **Verify** button in the **Customer Information Widget**. The signature verification is applicable for the transactions, which have the `Signature Verification Required` option selected as `Y` at the Function Code Preference level.


To withdraw cash through the in-house cheque:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **Cheque Withdrawal** or specify **Cheque Withdrawal** in the search icon bar and select the screen.

   The **Cheque Withdrawal** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-4 Cheque Withdrawal



2. On the **Cheque Withdrawal** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-4 Cheque Withdrawal - Field Description

Field	Description
Account Number	Specify a valid account number for the customer. **Note** When you press the **Tab** key, the corresponding account information will be displayed in the **Customer Information** widget. The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Transaction Amount	Displays the local currency of the branch. You can also select another currency from the drop-down list. Specify the transaction amount that needs to be debited from the customer account.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-4 (Cont.) Cheque Withdrawal - Field Description

Field	Description
Cheque Number	Specify the cheque number of the customer account as provided by the Customer. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Select the date on which the cheque has been issued from the calendar option.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-4 (Cont.) Cheque Withdrawal - Field Description

Field	Description
Reject Code	Select the reject code from the list of values, which are maintained in the **Reject Code Maintenance** screen. **Note** If the cheque withdrawal transaction needs to be rejected, you can reject it by specifying the appropriate reject code in this field. The transaction can be rejected for one of the following reasons: • Insufficient funds • Signature mismatch • Stale cheque
Reject Code Description	Displays the description of the specified reject code.
Account Amount	Displays the transaction amount converted in terms of account amount based on the exchange rate. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cheque Withdrawal**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the cash is withdrawn successfully against the customer cheque. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4.4 FX Sale Against Account

The Foreign Exchange **(FX) Sale Against Account** screen is used to sell the foreign currency from the branch through the CASA account.


This transaction is performed by debiting the corresponding account currency from the CASA account.

To sell the foreign currency against CASA account:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **FX Sale - Account** or specify **FX Sale - Account** in the search icon bar and select the screen.

   The **FX Sale Against Account** screen is displayed.

Figure 4-5 FX Sale Against Account



2. On the **FX Sale Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-5 FX Sale Against Account - Field Description

Field	Description
Account Number	Specify the CASA account to be debited for the foreign currency sale from the adjacent option list. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Amount Sold	Specify the currency and amount sold against the CASA account. You can select the appropriate code from the adjoining option list that displays all the currency codes maintained in the system. The system also displays the amount that is being sold.
Allow Denom Variance	Select if the denomination-wise variance needs to be applied for the transaction. **Note** If the parameter at the function code indicator is set as Y, this option will be selected by default and it can be modified. If the parameter at the function code indicator is set as N, then this option will be disabled.
Beneficiary Name	Displays the name of the beneficiary customer based on the account number selected.
Address Line 1 to **Address Line 4**	Displays the address of the beneficiary.
Identification Type	Select the type of identification provided by the customer from the drop-down list.
Identification Number	Specify the identification number provided by the customer.
Exchange Rate	Displays the exchange rate used to convert the transaction (sale) currency into account currency and it can be modified. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-5 (Cont.) FX Sale Against Account - Field Description

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Amount Received	Displays the amount received and currency from the CASA account. **Note** The currency of the amount received defaults from the CASA account currency. The amount received will be calculated based on the **Amount Sold** and the **Exchange Rate**. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Total Charges	Displays the total charge amount which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **FX Sale Against Account**, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the FX Out Denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the foreign currency cash is withdrawn and the equivalent account amount is debited. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

4.5 FX Sale Against Walk-in


The **FX Sale Against Walk-in** screen is used to sell a foreign currency to a walk-in customer in return for the equivalent amount received in the local currency.

To sell a foreign currency to the walk-in customer:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **FX Sale - Walk-in** or specify **FX Sale - Walk-in** in the search icon bar and select the screen.

   The **FX Sale Against Walk-in** screen is displayed.

Figure 4-6 FX Sale Against Walk-in



2. On the **FX Sale Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-6 FX Sale Against Walk-in - Field Description

Field	Description
Amount Sold	Select the applicable currency from the drop-down list and specify the amount that needs to be sold to the walk-in customer.
Currency Received	Select the currency that you have received from the customer in return for the currency sold. You can select the appropriate code from the adjoining option list that displays all the currency codes maintained in the system.
Allow Denom Variance	Select if the denomination-wise variance needs to be applied for the transaction. **Note** If the parameter at function code indicator is set as Y, this option will be selected by default, and it can be modified. If the parameter at the function code indicator is set as N, then this option will be disabled.
Beneficiary Name	Specify the name of the beneficiary customer.
Beneficiary Address 1 to **Beneficiary Address 4**	Specify the address of the beneficiary.
Identification Type	Select the type of identification provided by the customer from the drop-down list.
Identification Number	Specify the identification number provided by the customer.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency, and it can be modified. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-6 (Cont.) FX Sale Against Walk-in - Field Description

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as `Y`.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Amount Received	Displays the amount received and currency from the customer. **Note** The currency of the amount received will be defaulted from **Currency Received**. The amount received will be calculated based on the **Amount Sold** and the **Exchange Rate**. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **FX Sale (Walk-in)**, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the FX In Denomination details. For information on the fields in the **FX In Denomination Details** segment, refer to Add Denomination Details.
5. Specify the FX Out Denomination details. For information on the fields in the **FX Out Denomination Details** segment, refer to Add Denomination Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the teller cash position to the equivalent of "Sold currency" is deducted, and "Received currency" is incremented. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

4.6 FX Purchase Against Account

The **FX Purchase Against Account** screen is used to purchase foreign currency from the branch through the CASA account.

This transaction is performed by crediting the corresponding amount to the CASA account.


To purchase foreign currency against the CASA account:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **FX Purchase - Account** or specify **FX Purchase - Account** in the search icon bar and select the screen.

   The **FX Purchase Against Account** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-7 FX Purchase Against Account



2. On the **FX Purchase Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-7 FX Purchase Against Account - Field Description

Field	Description
Account Number	Specify the CASA account number to be credited for the foreign currency purchase. **Note** In addition, you can use Oracle Banking Virtual Accounts. These Virtual Accounts are used as a routing account to credit the underlying physical account. The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Amount Bought	Select the applicable currency from the drop-down list, and specify the amount that needs to be bought from the customer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-7 (Cont.) FX Purchase Against Account - Field Description

Field	Description
Allow Denom Variance	Select if the denomination-wise variance needs to be applied for the transaction. **Note** If the parameter at the function code indicator is set as Y, this option will be selected by default, and it can be modified. If the parameter at function code indicator is set as N, then this option will be disabled.
Beneficiary Name	Displays the name of the beneficiary customer based on the account number provided.
Beneficiary Address 1 to **Beneficiary Address 4**	Displays the address of the beneficiary.
Identification Type	Select the type of identification provided by the customer from the drop-down list.
Identification Number	Specify the identification number provided by the customer.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency, and it can be modified. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-7 (Cont.) FX Purchase Against Account - Field Description

Field	Description
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Amount Paid	Displays the amount paid and currency to the CASA account. **Note** The currency of the amount paid is defaulted from the account currency. The **Amount Paid** will be calculated based on the **Amount Bought** and the **Exchange Rate**. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **FX Purchase Against Account**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the FX In Denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the teller's cash position gets incremented based on the amount bought.
>
> In addition, the corresponding foreign currency cash is deposited for an equivalent amount of credit in the customer's account. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

4.7 FX Purchase Against Walk-in


The **FX Purchase Against Walk-in** screen is used to buy a foreign currency from a walk-in customer in return for the equivalent amount in the local currency.

To buy a foreign currency from a walk-in customer:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **FX Purchase - Walk-in** or specify **FX Purchase - Walk-in** in the search icon bar and select the screen.

   The **FX Purchase Against Walk-in** screen is displayed.

Figure 4-8 FX Purchase Against Walk-in



2. On the **FX Purchase Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-8 FX Purchase Against Walk-in

Field	Description
Amount Bought	Select the applicable currency from the drop-down list, and specify the amount bought from the walk-in customer.
Currency Paid	Select the currency that you have paid to the walk-in customer. **Note** You can select the appropriate code from the list of values that displays all the currency codes maintained in the system.
Allow Denom Variance	Select if the denomination-wise variance needs to be applied for the transaction. **Note** If the parameter at function code indicator is set as Y, this option will be selected by default, and it can be modified. If the parameter at the function code indicator is set as N, then this option will be disabled.
Beneficiary Name	Specify the name of the beneficiary walk-in customer.
Beneficiary Address 1 to **Beneficiary Address 4**	Specify the address of the beneficiary walk-in customer.
Identification Type	Select the type of identification provided by the walk-in customer from the drop-down list.
Identification Number	Specify the identification number provided by the walk-in customer.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency, and it can be modified. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-8 (Cont.) FX Purchase Against Walk-in

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Amount Paid	Displays the amount paid and currency to the customer. **Note** The currency of the amount paid is defaulted from the received currency. The **Amount Paid** will be calculated based on the **Amount Bought** and the **Exchange Rate**. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Total Charges	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **FX Purchase (Walk-in)**, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the FX In Denomination details. For information on the fields in the **FX In Denomination Details** segment, refer to Add Denomination Details.
5. Specify the FX Out Denomination details. For information on the fields in the **FX Out Denomination Details** segment, refer to Add Denomination Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the teller cash position is updated based on the currency of the **Amount Bought** and the **Amount Paid** fields. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

4.8 Close Out Withdrawal

The **Close Out Withdrawal** screen to initiate an account closure and close the CASA account by either dispersing the cash to the customer or by account transfer or by issuing Bankers Cheque.

The balance amount displayed is only the available balance from FLEXCUBE Universal Banking and Oracle Banking Branch does not consider the closeout withdrawal charges configured in FLEXCUBE Universal Banking. In case charges are required to be displayed in Oracle Banking Branch, Oracle Banking Branch also supports charges which can be configured.


To close the CASA account by either dispersing the cash to the customer or by account transfer or by issuing Bankers Cheque:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **Close Out Withdrawal** or specify **Close Out Withdrawal** in the search icon bar and select the screen.

   The **Close Out Withdrawal** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-9 Close Out Withdrawal - New



2. On the **Close Out Withdrawal** screen, specify fields. For more information on fields, refer to the field description table.

Table 4-9 Close Out Withdrawal - New

Field	Description
Customer Account	Specify the account number for which the account closure to be requested. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Account Name	Displays the name of the specified account number.
IC Liquidate	Click this button to liquidate interest on accounts online before proceeding with account closure process. **Note** The system will prompt an error if **Submit** button is clicked before liquidating the interest.
Account Amount	Displays the account balance in account currency post liquidating the interest on account.
Narrative	Displays the default narrative **Close Out Withdrawal** and it can be modified.

3. Click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.


Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, it will verify if IC liquidation is completed for the account. Once the IC liquidation is done, the transaction details are handed off to the CASA module in the FLEXCUBE Universal Banking for the account closure process. During account closure process, the closure amount will be parked in the intermediary suspense GL specified during transaction request handoff.
>
> Maintain Close mode as CASH and linked product as ZRCD in Account Closing Maintenance (STDCLSMD) in FCUBS. This maintenance will ensure the funds are parked to the respective suspense GL during the account closure process at FCUBS.

4. Click **Query**.

   The **Close Out Withdrawal - Query** screen is displayed.

Figure 4-10 Close Out Withdrawal - Query Transaction



5. On the **Close Out Withdrawal** screen, specify fields. For more information on fields, refer to the field description table.

Table 4-10 Close Out Withdrawal

Field	Description
Transaction Reference Number	Specify the transaction reference number for which the closure is initiated.
Customer Account	Displays the customer account number.
Account Amount	Displays the account balance in account currency.
Close Mode	Select the close mode from the following drop-down values: • `Account` • `Cash` • `Bankers Cheque`
Narrative	Displays the default narrative **Close Out Withdrawal** and it can be modified.

On the **Close Out Withdrawal by Account** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-11 Close Out Withdrawal by Account Transfer - Field Description

Field	Description
Transaction Reference Number	Displays the transaction reference number for which the closure is initiated.
Close Account	Displays the customer account number. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Account Amount	Displays the account balance in account currency.
Close Mode	Displays the close mode as **By Account**.
Credit Account	Specify the account number to which the funds need to be transferred during the account closure.
Credit Account Branch	Displays the branch code of the offset account.
Credit Account Name	Displays the name of the offset account.
Credit Account Amount	Displays the offset account amount along with account currency.
Exchange Rate	Displays the exchange rate based on the Account Currency and Offset Account Currency, and it can be modified. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Close Out Withdrawal**, and it can be modified.

On the **Close Out Withdrawal by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

Table 4-12 Close Out Withdrawal by Cash - Field Description

Field	Description
Transaction Reference Number	Displays the transaction reference number for which the closure is initiated.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 4-12 (Cont.) Close Out Withdrawal by Cash - Field Description

Field	Description
Customer Account	Displays the account number for which the account closure is to be requested. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Account Amount	Displays the account balance in account currency.
Close Mode	Displays the close mode as **By Cash**.
Transaction Amount	Specify the currency in which the customer requested the cash. The system displays the derived transaction amount based on the exchange rate fetched using account currency and transaction currency. The transaction amount is the account amount deducted with total charges. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Exchange Rate	Displays the exchange rate based on the account currency and offset account currency. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Close Out Withdrawal**, and it can be modified.

Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-11 Close Out Withdrawal - Bankers Cheque



On the **Close Out Withdrawal by Bankers Cheque** screen, specify the fields. For more information on fields, refer to the field description table.

Table 4-13 Close Out Withdrawal by Bankers Cheque - Field Description

Field	Description
Transaction Reference Number	Displays the transaction reference number for which the closure is initiated. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Account Number	Displays the account number for which the account closure is to be requested.
Account Amount	Displays the account balance in account currency.
Close Mode	Displays the close mode as **By Bankers Cheque**.
Issue Branch	Displays the issuing branch of the banker's cheque.
BC Amount	Displays the account currency and account balance. You can also modify the account currency.
Instrument Number	Specify the instrument number.
MICR Number	Specify the MICR number.
Payee Name	Specify the payee name.
Address Line 1 to **Address Line 4**	Specify the address of the payee.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-13 (Cont.) Close Out Withdrawal by Bankers Cheque - Field Description

Field	Description
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency, and it can be modified. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Close Out Withdrawal**, and it can be modified.

Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.

6. Click **Submit**.

   The **Transaction Completed Successfully** information message is displayed.

Note

The transaction is moved to (Electronic Journal for Cash Mode and to Servicing Journal for Account and Bankers Cheque) authorization in case of any approval warning raised when the transaction saves. On transaction submission, the accounting details are handed off to Flexcube Universal Banking by debiting the amount parked in Intermediary suspense GL and credited to Cash GL/ Account/ISB GL based on the close mode specified.

4.9 Close Out Withdrawal by Multi-Mode

The **Close Out Withdrawal by Multi Mode** screen is used to close the CASA account by multi-mode payout options, which include cash, account transfer, and BC. This screen can be used only when the closeout withdrawal needs to be done in multiple payout modes.

The balance amount displayed is only the available balance from FLEXCUBE Universal Banking and Oracle Banking Branch does not consider the closeout withdrawal charges configured in FLEXCUBE Universal Banking. In case charges are required to be displayed in Oracle Banking Branch, Oracle Banking Branch also supports charges which can be configured.


To close the CASA account by multi-mode payout options:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **Close Out Withdrawal by Multi Mode** or specify **Close Out Withdrawal by Multi Mode** in the search icon bar and select the screen.

   The **Close Out Withdrawal by Multi Mode** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-12 Close Out Withdrawal by Multi Mode



2. On the **Close Out Withdrawal by Multi Mode** screen, specify the fields. For more information on fields, refer to the field description table.

Table 4-14 Close Out Withdrawal by Multi Mode - Field Description

Field	Description
Close Account	Specify the account number, which needs to be closed. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Fetch Balance	Click **Fetch Balance** to fetch and display the account amount.
Account Amount	Displays the account amount.
Payout Type	Select the payout type from the following drop-down values: • `Account` – If this option is selected, the user needs to specify the **Offset Account**, to which the transfer is to be made. Based on the specified offset account number, the system will default the **Offset Branch** and **Offset Currency** fields. • `Cash` – If this option is selected, the user needs to disburse the cash in the account currency. • `Bankers Cheque` - If this option is selected, either the field **Instrument Number** is populated or the teller can input the value. On submission, the system will validate the instrument number if inputted or derive the instrument number in case of a null value. In addition, the user needs to capture the BC-related details in the **Bankers Cheque Details** data segment. This data segment is mandatory only if the **Payout Type** is selected as **Bankers Cheque**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-14 (Cont.) Close Out Withdrawal by Multi Mode - Field Description

Field	Description
Percentage	Specify the amount of redemption for the payout type selected. **Note** Based on the percentage input, the system will derive the amount to be paid out.
Amount	Specify the amount that needs to be withdrawn in the payout type selected.
Instrument Number	Specify the BC number. **Note** This field is applicable only if the **Payout Type** is selected as `Bankers Cheque`.
Issuing Branch	Displays the branch code of the specified account number.
Offset Account	Specify the account number to which the payout amount needs to be transferred. **Note** This field is applicable only if the **Payout Type** is selected as `Account`.
Offset Branch	Displays the branch of the specified offset account number. **Note** This field is applicable only if the **Payout Type** is selected as `Account`.
Offset Currency	Displays the currency of the specified offset account number. **Note** This field is applicable only if the **Payout Type** is selected as `Account`.
Narrative	Displays the default narrative as **Close Out Withdrawal by Multimode**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the transaction details are handed off to the CASA module in the FLEXCUBE Universal Banking for the account closure process.
>
> If the account balance is credited to an intermediary bridge GL, the transaction status will be changed from `Pending` to `Completed`.
>
> Based on the payout options, the corresponding transaction will be completed successfully.

4.10 Safe Deposit Rental By Cash


The Teller can use the **Safe Deposit Rental By Cash** screen to make payment by cash for the safe deposit locker of the customer.

To make payment for the safe deposit locker:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **Safe Deposit Rental By Cash** or specify **Safe Deposit Rental By Cash** in the search icon bar and select the screen.

   The **Safe Deposit Rental By Cash** screen is displayed.

Figure 4-13 Safe Deposit Rental By Cash



2. On the **Safe Deposit Rental By Cash** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-15 Safe Deposit Rental By Cash - Field Description

Field	Description
Deposit Locker	Specify the deposit locker number. When you press the **Tab** key, the customer details and deposit locker details will be displayed in the **Customer Information** widget.
Rental Amount	Select the rental amount currency and specify the amount. **Note** By default, the rental currency is displayed as locker currency. If the `Multi-Currency Configuration` at Function Code indicator level is set as Y, it can be modified, and if it is N, then the default value cannot be modified.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Total Charges Configuration` at Function Code indicator level is set as Y.
Account Amount	Displays the rental amount in locker account currency. This amount will be derived based on the **Rental Amount** and **Exchange Rate**. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-15 (Cont.) Safe Deposit Rental By Cash - Field Description

Field	Description
Narrative	Displays the narrative as **Safe Deposit Rental By Cash**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the system will hand off the details to the FLEXCUBE Universal Banking system to create a 'Payment' transaction in the SD module. After the handoff status is successful in the Oracle Banking Branch, the system will update the transaction status as **Completed** and update the Till cash position (by increasing the till balance).

4.11 Recurring Deposit Payment by Cash


The **Recurring Deposit Payment by Cash** screen is used to make payment for the Recurring Deposit (RD) account of the customer by cash.

To make payment against the RD account:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **RD Payment – Cash** or specify **RD Payment – Cash** in the search icon bar and select the screen.

   The **Recurring Deposit Payment by Cash** screen is displayed.

Figure 4-14 Recurring Deposit Payment by Cash



2. On the **Recurring Deposit Payment by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-16 Recurring Deposit Payment by Cash - Field Description

Field	Description
RD Account	Specify a valid RD account number. When you press the **Tab** key, the corresponding account information will be displayed in the **Customer Information** widget. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Installments	Specify the number of installments.
Transaction Amount	Displays the local currency of the branch. Specify the payment amount. **Note** The user can select another currency from the drop-down values.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the transaction amount converted in terms of account amount based on the exchange rate. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-16 (Cont.) Recurring Deposit Payment by Cash - Field Description

Field	Description
Total Charge Amount	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **RD Payment by Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the cash is withdrawn successfully from the customer account. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

4.12 F23C Tax Payment by Cash

The **F23C Tax Payment By Cash** screen is used to capture data related to the F23C tax document for a customer and collect the corresponding tax by cash from the customer.


To perform F23C tax payment by cash:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **F23C Tax Payment - Cash** or specify **F23C Tax Payment - Cash** in the search icon bar and select the screen.

   The **F23C Tax Payment By Cash** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-15 F23C Tax Payment By Cash



2. On the **F23C Tax Payment By Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-17 F23C Tax Payment By Cash Screen - Field Description

Field	Description
Reference Number Type	Select the reference number types from the drop-down list. The drop-down list shows the following values: • **Reference Number Available** • **Reference Number Not Available**
Reference Number	Specify the reference number of the payment provided by the Public Authority.
Office or Institute Code	Specify the office or institute code that receives the payment.
Office or Institute Sub code	Specify the office or institute subcode that receives the payment.
Litigation	Specify the kind of litigation.
For a Total Amount	Displays the total tax amount.
Total Charge	Displays the total charge amount, which is computed by the system in the local currency of the branch.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 4-17 (Cont.) F23C Tax Payment By Cash Screen - Field Description

Field	Description
Exchange Rate	Displays the exchange rate based on the **Account Currency** and **Offset Account Currency**.
Payment Amount	Displays the amount paid by the customer. **Note** The currency of the amount paid defaults from the received currency.
Narrative	Displays the default narrative as **F23 Tax by Cash**, and it can be modified.

3. Click on the **Payment Data Details** data segment.

   The **Payment Data Details** data segment is displayed.

Figure 4-16 Payment Data Details



4. On the **Payment Data Details** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 4-18 Payment Data Details - Field Description

Field	Description
Tax Code	Specify the Tax Code.
Amount	Specify the tax amount.
Beneficiary Code	Specify the beneficiary institute code.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
7. After you specify the **Reference Number**, click **Pickup**.

   The system defaults the **Elaboration Date** in the section **Reference Number Available** with the current system date. In case you do not specify the **Reference Number**, then the **Principal Fiscal Code** needs to be specified. After which the system defaults the **Elaboration Date** in the section **Reference Number Not Available** with the current

Copyright © 2021, 2025, Oracle and/or its affiliates.

system date. It then adds up the Amounts in the **Payment Data Details** block and defaults the sum in the **For a total Amount** field.

The system posts the following accounting entries on save and authorization of the record:

Table 4-19 Accounting Entries Posted for Payment Amount

Dr/Cr	Description	Amount
Dr	Cash Account	For a Total Amount
Cr	Account maintained in ARC of the associated product	For a Total Amount

Table 4-20 Accounting Entries Posted for Charge Amount

Dr/Cr	Description	Amount
Dr	Cash Account	Charges amount computed as per ARC maintenance
Cr	Account maintained in ARC of the associated product	Charges amount computed as per ARC maintenance

The following validations are performed by the system:

- The system allows you to maintain a minimum of one row and a maximum of eight rows in the **Payment Data Details** multi-entry block. If you do not maintain the minimum row or exceed the maximum row, then the system displays an appropriate error message.
- If the **Principal Fiscal Code** and **Secondary Fiscal Code** fields have a value of 16 characters that is for non-individual customers the system validates the last character in the value as per the checksum algorithm for Fiscal Code. If the validation fails, then the system displays an appropriate error message. In the case of individual customers, where the **Principal Fiscal Code** and **Secondary Fiscal Code** field has a value of 11 characters, the system validates the last character in the value as per the checksum algorithm for a VAT number. If the validation fails, then the system displays an appropriate error message.
- The system validates only the data format of the fields specified.
- If the computed value for **Payment Amount** field value is less than or equal to 0, on pickup, the system displays an appropriate error message.

8. Once Pickup is completed, click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the deposit of tax amount is completed successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4.13 F24C Tax Payment By Cash


The **F24C Payment Details** screen is used to capture data related to the F24C tax document for a customer and collect the corresponding tax by cash from the customer.

To perform F24C tax payment by cash:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **F24C Tax Payment - Cash** or specify **F24C Tax Payment - Cash** in the search icon bar and select the screen.

   The **F24C Payment Details** screen is displayed.

Figure 4-17 F24C Payment Details



2. On the **F24C Payment Details** screen, specify the fields. For more information on fields, refer to the field description table.

Table 4-21 F24C Payment Details - Field Description

Field	Description
Total Tax Amount	Displays the total tax amount.
Payment Amount	Displays the amount to pay.
Narrative	Displays the default narrative as **F24 Tax by Cash**, and it can be modified.
Total Charge	Displays the total charge.

3. Specify the details in the **F24 Tax – By Cash** segment. For information on the fields based on the value selected for the **Form Type**, refer to the table.

Table 4-22 F24 Tax by Cash - Form Types and their References

Form Type	Reference Topic
Standard	Add Standard Details
Simplified	Add Simplified Details
Elements Identification	Add Element Identification Details

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-22 (Cont.) F24 Tax by Cash - Form Types and their References

Form Type	Reference Topic
Predefined	Add Predefined Details

On selection of an appropriate value from the **Form Type**, only the corresponding tab will be enabled for input. For example, if you select **F24 Standard** as the **Form Type** then only the tab **F24 Standard** will be enabled and all other tabs will be disabled. The **Principal Fiscal Code** needs to be specified.

4. After entering all the form details, click **Refresh** in the **F24 Payment Details**.

   The system adds up the Amounts and defaults the sum in the **Payment Amount** field. The system posts the following accounting entries on save and authorization of the record.

Table 4-23 Accounting Entries Posted for Payment Amount

Dr/Cr	Description	Amount
Dr	Cash Account	Final Section Amount of the corresponding tab which has been entered.
Cr	Account maintained in ARC of the associated product	Final Section Amount of the corresponding tab which has been entered.

Table 4-24 Accounting Entries Posted for Charge Amount

Dr/Cr	Description	Amount
Dr	Cash Account	Charges amount computed as per ARC maintenance
Cr	Income Account	Charges amount computed as per ARC maintenance

The system validates only the data format of the fields specified. If any such validations fail, the system displays an appropriate error message. If you maintain more than the specified number of rows in any of the below blocks, then the system displays an appropriate error message. The following list shows the number of rows, which can be maintained for each **Form Type**:

Table 4-25 Maintenance for Form Type

Form Type	Maintenance
Standard	In the **F24 Standard** tab, the system allows you to maintain only the following number of records: • up to a maximum of 6 rows in the **Tax** multi-record block. • up to a maximum of 4 rows in the **INPS** multi-record block. • up to a maximum of 4 rows in the **Region** multi-record block. • up to a maximum of 4 rows in the **IMU and Other Local Taxes** multi-record block. • up to a maximum of 4 rows in the **Insurance** multi-record block. • up to a maximum of 3 rows in the **Other Bodies** multi-record block. • up to a maximum of 7 rows in the **Excise** multi-record block.
Simplified	In the **F24 Simplified** tab, up to a maximum of 10 rows in the **Tax Details** multi-record block.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-25 (Cont.) Maintenance for Form Type

Form Type	Maintenance
Elements Identification	In the **F24 Elements Identification** tab, up to a maximum of 28 rows in the **Tax Details** multi-record block.
Predefined	In the **F24 Predefined** tab, up to a maximum of 1 row in the **Tax Details** multi-record block.

If the computed value for **Payment Amount** field value is less than or equal to 0, the system displays an appropriate error message. If the **Principal Fiscal Code** and **Secondary Fiscal Code** fields have a value of 16 characters that is for non-individual customers, the system validates the last character in the value as per the checksum algorithm for **Fiscal Code**. If the validation fails, then the system displays an appropriate error message. In the case of individual customers, where the **Principal Fiscal Code** and **Secondary Fiscal Code** field has a value of 11 characters, the system validates the last character in the value as per the checksum algorithm for a VAT number. If the validation fails, then the system displays an appropriate error message.

5. Once Pickup is completed, click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the deposit of tax amount is completed successfully.

- Add Standard Details
  You can add the F24 standard details in the **F24 Tax – By Cash** data segment.
- Add Simplified Details
  You can add the F24 simplified details in the **F24 Tax – By Cash** data segment.
- Add Element Identification Details
  You can add the details of the element identification in the **F24 Tax – By Cash** data segment.
- Add Predefined Details
  You can add the F24 predefined details in the **F24 Tax – By Cash** data segment.


4.13.1 Add Standard Details

You can add the F24 standard details in the **F24 Tax – By Cash** data segment.

Make sure that the transaction details are added to the transaction screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-18 F24 Tax By Cash - F24 Standard



To add the F24 standard details:

1. On the **F24 Tax – By Cash** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 4-26 F24 Standard - Field Description

Field	Description
Form Type	Select the **Standard** tax category from the drop-down list.
F24 Standard	Specify the fields.
Elaboration Date	Displays the elaboration date.
Principal Fiscal Code	Specify the debtor fiscal code.
Secondary Fiscal Code	Specify the secondary fiscal code.
Identity Code Secondary Fiscal Code	Specify the Identity code secondary fiscal code.
Total Final Payment	Specify the total amount to be paid.
Different Tax Year	Specify if the tax being paid is related to the current year or not.
Final Payment Fields	The system displays the total tax amount of each segment: • Tax Institution • INPS Institution • Region Institution • Local Institution • Insurance Institution • Other Institution • Excise

2. Specify the tax details. For information on the fields in the **Tax Details**, refer to Add Tax Details.
3. Specify the INPS details. For information on the fields in the **INPS**, refer to Add INPS Details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4. Specify the region details. For information on the fields in the **Region**, refer to Add Region Details.
5. Specify the details of the IMU and other local taxes. For information on the fields in the **IMU and Other Local Taxes**, refer to Add IMU and Other Local Taxes.
6. Specify the insurance details. For information on the fields in the **Insurance Details**, refer to Add Insurance Details.
7. Specify the details of the other bodies. For information on the fields in the **Other Bodies**, refer to Add Other Bodies.
8. Specify the excise details. For information on the fields in the **Excise**, refer to Add Excise Details.


- Add Tax Details
  You can add the details of the tax in the **Tax Details** segment.
- Add INPS Details
  You can add the details of the INPS in the **INPS Details** segment.
- Add Region Details
  You can add the details of the region in the **Region** segment.
- Add IMU and Other Local Taxes
  You can add the details of IMU and other local taxes in the **IMU and Other Local Taxes** segment.
- Add Insurance Details
  You can add the details of the insurance in the **Insurance Details** segment.
- Add Other Bodies
  You can add the details of the other bodies in the **Other Bodies** segment.
- Add Excise Details
  You can add the details of the excise in the **Excise** segment.

4.13.1.1 Add Tax Details

You can add the details of the tax in the **Tax Details** segment.

Make sure that the transaction details are added, and the **Form Type** is selected as **Standard**.

Figure 4-19 Tax Details



Copyright © 2021, 2025, Oracle and/or its affiliates.

To add the tax details:

On the **Tax Details** segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-27 Tax Details - Field Description


Field	Description
Tax Code	Specify the reason.
Instal.Reg/Prov	Specify the Instal.Reg/ Prov.
Year	Specify the year.
Debit Amount	Specify the amount to be paid.
Credit Amount	Specify the compensation amount.
Office Code	Specify the office code.
Document Code	Specify the document code.
Total Debit Amount (A)	Displays the total debit amount.
Total Credit Amount (B)	Displays the total compensation amount.
Final Section Amount (A-B)	Displays the final section amount.

4.13.1.2 Add INPS Details

You can add the details of the INPS in the **INPS Details** segment.

Make sure that the transaction details are added, and the **Form Type** is selected as **Standard**.

Figure 4-20 INPS Details



To add the INPS details:

On the **INPS Details** segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-28 INPS Details - Field Description


Field	Description
Office	Specify the office.
Reason	Specify the reason.
INPS Office Code	Specify the INPS office code.
Period (From)	Specify the date from when the amount is paid.
Period (To)	Specify the date till when the amount is paid.
Debit Amount	Specify the amount to be paid.
Credit Amount	Specify the compensation amount.
Total Debit Amount (C)	Displays the total debit amount.
Total Credit Amount (D)	Displays the total compensation amount.
Final Section Amount (C-D)	Displays the final section amount.

4.13.1.3 Add Region Details

You can add the details of the region in the **Region** segment.

Make sure that the transaction details are added, and the **Form Type** is selected as **Standard**.

Figure 4-21 Region



To add the region details:

On the **Region** segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-29 Region - Field Description


Field	Description
Region Code	Specify the region code.
Tax Code	Specify the tax code.
Installment	Specify the installment amount.
Year	Specify the year.
Debit Amount	Specify the amount to be paid.
Credit Amount	Specify the compensation amount.
Total Debit Amount (E)	Displays the total debit amount.
Total Credit Amount (F)	Displays the total compensation amount.
Final Section Amount (E-F)	Displays the final section amount.

4.13.1.4 Add IMU and Other Local Taxes

You can add the details of IMU and other local taxes in the **IMU and Other Local Taxes** segment.

Make sure that the transaction details are added, and the **Form Type** is selected as **Standard**.

Figure 4-22 IMU and Other Local Taxes



To add the details of IMU and other local taxes:

On the **IMU and Other Local Taxes** segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-30 IMU and Other Local Taxes - Field Description


Field	Description
Institution Code/Town Code	Specify the institution/town code.
Late Payment	Specify if the payment is late.
Bounding Var.	Specify the Bounding Var.
Down Payment	Specify the down payment.
Final Payment	Specify the final payment.
Building Nr	Specify the building number.
Tax Code	Specify the tax code.
Installment	Specify the installment amount.
Deduction	Specify the deduction amount.
Total Debit Amount (G)	Displays the Total Debit Amount.
Building Reference Number	Specify the building reference number.
Total Credit Amount (H)	Displays the Total Compensation Amount.
Final Section Amount (G-H)	Displays the Final Section Amount.

4.13.1.5 Add Insurance Details

You can add the details of the insurance in the **Insurance Details** segment.

Make sure that the transaction details are added, and the **Form Type** is selected as **Standard**.

Figure 4-23 Insurance Details



To add the insurance details:

On the **Insurance Details** segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-31 Insurance Details - Field Description


Field	Description
Office Code	Specify the office code.
Insurance Number	Specify the insurance number.
Insurance Account Code	Specify the insurance account code.
Reference Number	Specify the reference number.
Reason	Specify the reason.
Debit Amount	Specify the amount to be paid.
Credit Amount	Specify the compensation amount.
Total Debit Amount (I)	Displays the total debit amount.
Total Credit Amount (L)	Displays the total compensation amount.
Final Section Amount (I-L)	Displays the final section amount.

4.13.1.6 Add Other Bodies

You can add the details of the other bodies in the **Other Bodies** segment.

Make sure that the transaction details are added, and the **Form Type** is selected as **Standard**.

Figure 4-24 Other Bodies



To add the details of the other bodies:

On the **Other Bodies** segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-32 Other Bodies - Field Description


Field	Description
Institution Code	Specify the institution code.
Office Code	Specify the office code.
Reason	Specify the reason.
Insurance Reference Number	Specify the insurance reference number.
Period (From)	Specify the date from when the amount is paid.
Period (To)	Specify the date till when the amount is paid.
Debit Amount	Specify the amount to be paid.
Credit Amount	Specify the compensation amount.
Total Debit Amount (M)	Displays the total debit amount.
Total Credit Amount (N)	Displays the total compensation amount.
Final Section Amount (M-N)	Displays the final section amount.

4.13.1.7 Add Excise Details

You can add the details of the excise in the **Excise** segment.

Make sure that the transaction details are added, and the **Form Type** is selected as **Standard**.

Figure 4-25 Excise Details



To add the details of the excise:

On the **Tax Details** segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-33 Excise - Field Description


Field	Description
Institution	Specify the institution.
Province	Specify the province.
Tax Code	Specify the tax code.
Company Identification	Specify the company identification number.
Installment	Specify the installment amount.
Period/Month	Specify the month of tax payment.
Period/Year	Specify the year of tax payment.
Debit Amount	Specify the amount to be paid.
Office Code	Specify the office code.
Total Debit Amount (O)	Displays the total debit amount.
Document Code	Specify the document code.
Final Section Amount	Displays the final section amount.

4.13.2 Add Simplified Details

You can add the F24 simplified details in the **F24 Tax – By Cash** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 4-26 F24 Tax By Cash - F24 Simplified



Copyright © 2021, 2025, Oracle and/or its affiliates.

To add the F24 simplified details:

On the **F24 Tax – By Cash** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-34 F24 Simplified - Field Description

Field	Description
Form Type	Select the **Simplified** tax category from the drop-down list.
F24 Simplified	Specify the fields.
Elaboration Date	Displays the elaboration date.
Principal Fiscal Code	Specify the debtor fiscal code. **Note** For Individual customers, the allowed principal fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Secondary Fiscal Code	Specify the secondary fiscal code. **Note** For Individual customers, the allowed secondary fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Identity Code Secondary Fiscal Code	Specify the identity code secondary fiscal code.
Section	Specify the section.
Tax Code	Specify the tax code.
Institution Code	Specify the institution code.
Late Payment	Specify if the payment is late.
Bounding Var.	Specify the Bounding Var.
Down Payment	Specify the down payment.
Final Payment	Specify the final payment.
Building Nr	Specify the building number.
Installment	Specify the installment amount.
Year	Specify the year.
Deduction	Specify the deduction amount.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-34 (Cont.) F24 Simplified - Field Description


Field	Description
Debit Amount	Specify the amount to be paid.
Credit Amount	Specify the compensation amount.
Office Code	Specify the office code.
Document Code	Specify the document code.
Building Reference Number	Specify the building reference number.
Total Debit Amount (G)	Displays the total debit amount.
Total Credit Amount (H)	Specify the total compensation amount.
Final Section Amount (G-H)	Displays the final section amount.

4.13.3 Add Element Identification Details

You can add the details of the element identification in the **F24 Tax – By Cash** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 4-27 F24 Tax By Cash - Elements Identification



To add the details of the element identification:

On the **F24 Tax – By Cash** data segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-35 F24 Tax By Cash with Elements Identification - Field Description

Field	Description
Form Type	Select the **Elements Identification** tax category from the drop-down list.
F24 Elide	Specify the fields.
Elaboration Date	Displays the elaboration date.
Principal Fiscal Code	Specify the debtor fiscal code. **Note** For Individual customers, the allowed principal fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Secondary Fiscal Code	Specify the secondary fiscal code. **Note** For Individual customers, the allowed secondary fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Identity Code Secondary Fiscal Code	Specify the identity code secondary fiscal code.
Type of Vehicle/ Element	Specify the vehicle type.
Vehicle/ Element ID	Specify the vehicle ID.
Tax Code	Specify the tax code.
Year	Specify the year.
Debit Amount	Specify the amount to be paid.
Office Code	Specify the office code.
Document Code	Specify the document code.
Total Debit Amount	Displays the total amount to pay.
Final Section Amount	Displays the final section amount.


4.13.4 Add Predefined Details

You can add the F24 predefined details in the **F24 Tax – By Cash** data segment.

Make sure that the transaction details are added to the transaction screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-28 F24 Tax By Cash - F24 Predefined



To add the F24 predefined details:

On the **F24 Tax – By Cash** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-36 F24 Predefined - Field Description

Field	Description
Form Type	Select the **Predefined** tax category from the drop-down list.
F24 Predefined	Specify the fields.
Elaboration Date	Displays the elaboration date.
Principal Fiscal Code	Specify the debtor fiscal code. **Note** For Individual customers, the allowed principal fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-36 (Cont.) F24 Predefined - Field Description

Field	Description
Secondary Fiscal Code	Specify the secondary fiscal code. **Note** For Individual customers, the allowed secondary fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Identity Code Secondary Fiscal Code	Specify the identity code secondary fiscal code.
Tax Institution	Displays the tax Institution.
Payment ID	Specify the payment ID.
Amount to Pay	Specify the amount to be paid.
Total Debit Amount	Displays the total debit amount.
Final Section Amount	Displays the final section amount.

4.14 F23 Tax Payment by Account

The **F23 Tax Payment by Account** screen is used to capture data related to the F23 tax document for a customer and collect the corresponding tax by cash from the customer.


To perform F23 tax payment by account:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **F23 Tax Payment by Account** or specify **F23 Tax Payment by Account** in the search icon bar and select the screen.

   The **F23 Tax Payment by Account** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-29 F23 Tax Payment by Account



2. On the **F23 Tax Payment by Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-37 F23 Tax Payment By Account - Field Description

Field	Description
Reference Number Type	Select the reference number types from the drop-down list. The drop-down list shows the following values: • **Reference Number Available** • **Reference Number Not Available**
Reference Number	Specify the reference number of the payment provided by the public authority.
Office or Institute Code	Specify the office or institute code that receives the payment.
Office or Institute Sub code	Specify the office or institute subcode that receives the payment.
Litigation	Specify the kind of litigation.
For a Total Amount	Displays the total tax amount.
Total Charge	Displays the total charge amount, which is computed by the system in the local currency of the branch.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 4-37 (Cont.) F23 Tax Payment By Account - Field Description

Field	Description
Exchange Rate	Displays the exchange rate based on the **Account Currency** and **Offset Account Currency**.
Payment Amount	Displays the amount paid by the customer. **Note** The currency of the amount paid defaults from the received currency.
Narrative	Displays the default narrative as **F23 Tax by Account**, and it can be modified.

3. Click on the **Account Details** data segment.

   The **Account Details** data segment is displayed.

Figure 4-30 Account Details



4. On the **Account Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 4-38 Account Details - Field Description

Field	Description
Account Number	Specify the customer account number from which the tax is being paid. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Branch	Displays the branch code.
Account Description	Displays the description of the account number specified.
Account Amount	Displays the amount available in the account.
Net Amount	Displays the amount, which is the net total amount levied to the customer.

5. Click on the **Payment Data Details** data segment.

   The **Payment Data Details** data segment is displayed.

Figure 4-31 Payment Data Details



6. On the **Payment Data Details** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 4-39 Payment Data Details - Field Description

Field	Description
Tax Code	Specify the tax code.
Amount	Specify the tax amount.
Beneficiary Code	Specify the beneficiary institute code.

7. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
8. After you specify the **Reference Number**, corresponding fields are displayed for the user to input the details. Once you specify the **Payment Details** and click **Refresh**.

   The system computes the total amount, which can be with or without charges.

Copyright © 2021, 2025, Oracle and/or its affiliates.

If the **Reference Number** is not specified, the relevant fields are displayed for input in the section **Reference Number Not Available**. Once you specify the **Payment Details** and click **Refresh**, the system posts the following accounting entries on saving and authorization of the record:

Table 4-40 Accounting Entries Posted for Payment Amount

Dr/Cr	Description	Amount
Dr	Cash Account	For a Total Amount
Cr	Account maintained in ARC of the associated product	For a Total Amount

Table 4-41 Accounting Entries Posted for Charge Amount

Dr/Cr	Description	Amount
Dr	Cash Account	Charges amount computed as per ARC maintenance
Cr	Account maintained in ARC of the associated product	Charges amount computed as per ARC maintenance

The following validations are performed by the system:

- The system allows you to maintain a minimum of one row and a maximum of eight rows in the **Payment Data Details** multi-entry block. If you do not maintain the minimum row or exceed the maximum row, then the system displays an appropriate error message.
- If the **Principal Fiscal Code** and **Secondary Fiscal Code** fields have a value of 16 characters that is for non-individual customers the system validates the last character in the value as per the checksum algorithm for Fiscal Code. If the validation fails, then the system displays an appropriate error message. In the case of individual customers, where the **Principal Fiscal Code** and **Secondary Fiscal Code** field has a value of 11 characters, the system validates the last character in the value as per the checksum algorithm for a VAT number. If the validation fails, then the system displays an appropriate error message.
- The system validates only the data format of the fields specified.
- If the computed value for **Payment Amount** field value is less than or equal to 0, on pickup, the system displays an appropriate error message.

9. Once the pickup is completed, click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the deposit of tax amount is completed successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4.15 F24 Tax Payment By Account


The **F24 Tax Payment By Account** screen is used to capture data related to the F24 tax document for a customer and collect the corresponding tax by account from the customer.

To perform F24 tax payment by account:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **F24 Tax Payment By Account** or specify **F24 Tax Payment By Account** in the search icon bar and select the screen.

   The **F24 Tax Payment By Account** screen is displayed.

Figure 4-32 F24 Tax Payment By Account



2. On the **F24 Tax Payment By Account** screen, specify the fields. For more information on fields, refer to the field description table.

Table 4-42 F24 Tax Payment By Account - Field Description


Field	Description
Total Tax Amount	Displays the total tax amount.
Narrative	Displays the default narrative as **F24 Tax by Account**, and it can be modified.
Total Charge	Displays the total charge.
Payment Amount	Displays the amount to pay.

3. Click on the **Account Details** data segment.

   The **Account Details** data segment is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-33 Account Details



4. On the **Account Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-43 Account Details - Field Description

Field	Description
Account Number	Specify the customer account number from which the tax is being paid. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Branch	Displays the branch code.
Account Description	Displays the description of the account number specified.
Account Amount	Displays the amount available in the account.
Net Amount	Displays the amount, which is the net total amount levied to the customer.

5. Specify the details in the **F24 Tax By Account** segment. For information on the fields based on the value selected for the **Form Type**, refer to the table.

Table 4-44 F24 Tax By Account - Form Types and their References

Form Type	Reference Topic
Standard	Add Standard Details
Simplified	Add Simplified Details

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-44 (Cont.) F24 Tax By Account - Form Types and their References

Form Type	Reference Topic
Elements Identification	Add Element Identification Details
Predefined	Add Predefined Details

On selection of an appropriate value from the **Form Type**, only corresponding fields of the form will be displayed for input. For example, if you select **F24 Standard** as the Form Type, then only the fields of **F24 Standard** will be available. The **Principal Fiscal Code** needs to be specified.

6. After entering all the form details, click **Refresh** in the **F24 Payment Details**.

   The system adds up the Amounts and defaults the sum in the **Payment Amount** field. The system posts the following accounting entries on save and authorization of the record.

Table 4-45 Accounting Entries Posted for Payment Amount

Dr/Cr	Description	Amount
Dr	Cash Account	Final Section Amount of the corresponding tab, which has been entered.
Cr	Account maintained in ARC of the associated product	Final Section Amount of the corresponding tab which has been entered.

Accounting entries posted for the charge amount:

Table 4-46 Accounting Entries Posted for Charge Amount

Dr/Cr	Description	Amount
Dr	Cash Account	Charges amount computed as per ARC maintenance
Cr	Income Account	Charges amount computed as per ARC maintenance

The system validates only the data format of the fields specified. If any of such validations fail, the system displays an appropriate error message. If you maintain more than the specified number of rows in any of the below blocks, then the system displays an appropriate error message. The following list shows the number of rows, which can be maintained for each Form Type:

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-47 Maintenance for Form Type

Form Type	Maintenance
Standard	In the **F24 Standard** tab, the system allows you to maintain only the following number of records: • up to a maximum of 6 rows in the **Tax** multi-record block. • up to a maximum of 4 rows in the **INPS** multi-record block. • up to a maximum of 4 rows in the **Region** multi-record block. • up to a maximum of 4 rows in the **IMU and Other Local Taxes** multi-record block. • up to a maximum of 4 rows in the **Insurance** multi-record block. • up to a maximum of 3 rows in the **Other Bodies** multi-record block. • up to a maximum of 7 rows in the **Excise** multi-record block.
Simplified	In the **F24 Simplified** tab, up to a maximum of 10 rows in the **Tax Details** multi-record block.
Elements Identification	In the **F24 Elements Identification** tab, up to a maximum of 28 rows in the **Tax Details** multi-record block.
Predefined	In the **F24 Predefined** tab, up to a maximum of 1 row in the **Tax Details** multi-record block.

If the computed value for the **Payment Amount** field value is less than or equal to 0, the system displays an appropriate error message. If the **Principal Fiscal Code** and **Secondary Fiscal Code** fields have a value of 16 characters that is for non-individual customers the system validates the last character in the value as per the checksum algorithm for **Fiscal Code**.

If the validation fails, then the system displays an appropriate error message. In the case of individual customers, where the **Principal Fiscal Code** and **Secondary Fiscal Code** field has a value of 11 characters, the system validates the last character in the value as per the checksum algorithm for a VAT number. If the validation fails, then the system displays an appropriate error message.

7. Once Pickup is completed, click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the deposit of tax amount is completed successfully.

- Add Standard Details
  You can add the F24 standard details in the **F24 Tax By Account** data segment.
- Add Simplified Details
  You can add the F24 simplified details in the **F24 Tax By Account** data segment.
- Add Element Identification Details
  You can add the details of the element identification in the **F24 Tax By Account** data segment.
- Add Predefined Details
  You can add the F24 predefined details in the **F24 Tax By Account** data segment.


Copyright © 2021, 2025, Oracle and/or its affiliates.

4.15.1 Add Standard Details

You can add the F24 standard details in the **F24 Tax By Account** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 4-34 F24 Tax By Account - F24 Standard



To add the F24 standard details:

1. On the **F24 Tax By Account** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-48 F24 Standard - Field Description

Field	Description
Form Type	Select the **Standard** tax category from the drop-down list.
F24 Standard	Specify the fields.
Elaboration Date	Displays the elaboration date.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-48 (Cont.) F24 Standard - Field Description

Field	Description
Principal Fiscal Code	Specify the debtor fiscal code. **Note** For Individual customers, the allowed principal fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Secondary Fiscal Code	Specify the secondary fiscal code. **Note** For Individual customers, the allowed secondary fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Identity Code Secondary Fiscal Code	Specify the Identity code secondary fiscal code.
Total Final Payment	Specify the total amount to be paid.
Different Tax Year	Specify if the tax being paid is related to the current year or not.
Final Payment Fields	The system displays the total amount of each segment: • Tax Institution • INPS Institution • Region Institution • Local Institution • Insurance Institution • Other Institution • Excise

2. Specify the tax details. For information on the fields in the **Tax Details**, refer to Add Tax Details.
3. Specify the INPS details. For information on the fields in the **INPS**, refer to Add INPS Details.
4. Specify the region details. For information on the fields in the **Region**, refer to Add Region Details.
5. Specify the details of the IMU and other local taxes. For information on the fields in the **IMU and Other Local Taxes**, refer to Add IMU and Other Local Taxes.
6. Specify the insurance details. For information on the fields in the **Insurance Details**, refer to Add Insurance Details.
7. Specify the details of the other bodies. For information on the fields in the **Other Bodies**, refer to Add Other Bodies.
8. Specify the excise details. For information on the fields in the **Excise**, refer to Add Excise Details.


Copyright © 2021, 2025, Oracle and/or its affiliates.

4.15.2 Add Simplified Details

You can add the F24 simplified details in the **F24 Tax By Account** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 4-35 F24 Tax By Account - F24 Simplified



To add the F24 simplified details:

On the **F24 Tax By Account** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-49 F24 Simplified - Field Description

Field	Description
Form Type	Select the **Simplified** tax category from the adjoining drop-down list.
F24 Simplified	Specify the fields.
Elaboration Date	Displays the elaboration date.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-49 (Cont.) F24 Simplified - Field Description

Field	Description
Principal Fiscal Code	Specify the debtor fiscal code. **Note** For Individual customers, the allowed principal fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Secondary Fiscal Code	Specify the secondary fiscal code. **Note** For Individual customers, the allowed secondary fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Identity Code Secondary Fiscal Code	Specify the Identity code secondary fiscal code.
Section	Specify the section.
Tax Code	Specify the tax code.
Institution Code	Specify the institution code.
Late Payment	Specify if the payment is late.
Bounding Var.	Specify the Bounding Var.
Down Payment	Specify the down payment.
Final Payment	Specify the final payment.
Building Nr	Specify the building number.
Installment	Specify the installment amount.
Year	Specify the year.
Deduction	Specify the deduction amount.
Debit Amount	Specify the amount to be paid.
Credit Amount	Specify the compensation amount.
Office Code	Specify the office code.
Document Code	Specify the document code.
Building Reference Number	Specify the building reference number.
Total Debit Amount (G)	Displays the total debit amount.
Total Credit Amount (H)	Specify the total compensation amount.
Final Section Amount (G-H)	Displays the final section amount.


Copyright © 2021, 2025, Oracle and/or its affiliates.

4.15.3 Add Element Identification Details

You can add the details of the element identification in the **F24 Tax By Account** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 4-36 F24 Tax By Account - Elements Identification



To add the details of the element identification:

On the **F24 Tax – By Cash** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-50 F24 Tax By Cash with Elements Identification - Field Description

Field	Description
Form Type	Select the **Elide** tax category from the drop-down list.
F24 Elide	Specify the fields.
Elaboration Date	Displays the elaboration date.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-50 (Cont.) F24 Tax By Cash with Elements Identification - Field Description

Field	Description
Principal Fiscal Code	Specify the debtor fiscal code. **Note** For Individual customers, the allowed principal fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Secondary Fiscal Code	Specify the secondary fiscal code. **Note** For Individual customers, the allowed secondary fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Identity Code Secondary Fiscal Code	Specify the identity code secondary fiscal code.
Total Final Payment	Specify the total final payment.
Type of Vehicle/ Element	Specify the vehicle type.
Vehicle/ Element ID	Specify the vehicle ID.
Tax Code	Specify the tax code.
Year	Specify the year.
Debit Amount	Specify the amount to be paid.
Office Code	Specify the office code.
Document Code	Specify the document code.
Total Debit Amount	Displays the total amount to pay.
Final Section Amount	Displays the final section amount.


4.15.4 Add Predefined Details

You can add the F24 predefined details in the **F24 Tax By Account** data segment.

Make sure that the transaction details are added to the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 4-37 F24 Tax by Account - F24 Predefined



To add the F24 predefined details:

On the **F24 Tax – By Cash** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 4-51 F24 Predefined - Field Description

Field	Description
Form Type	Select the **Predefined** tax category from the drop-down list.
F24 Predefined	Specify the fields.
Elaboration Date	Displays the elaboration date.
Principal Fiscal Code	Specify the debtor fiscal code. **Note** For Individual customers, the allowed principal fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 4-51 (Cont.) F24 Predefined - Field Description

Field	Description
Secondary Fiscal Code	Specify the secondary fiscal code. **Note** For Individual customers, the allowed secondary fiscal code is 16 characters and for non-individual customers, this will be an 11-character VAT number.
Identity Code Secondary Fiscal Code	Specify the identity code secondary fiscal code.
Erario Institution	Displays the Erario Institution.
Payment ID	Specify the payment ID.
Amount to Pay	Specify the amount to be paid.
Total Debit Amount	Displays the total amount to pay.
Final Section Amount	Displays the final section amount.

Copyright © 2021, 2025, Oracle and/or its affiliates.

5

Miscellaneous Transactions

The Teller can use Miscellaneous Transactions to perform GL transactions against a customer's CASA account and GL account.

This topic contains the following subtopics:

- Miscellaneous Customer Debit
  The **Miscellaneous Customer Debit** screen is used to transfer funds from the customer account to GL.
- Miscellaneous Customer Credit
  The **Miscellaneous Customer Credit** screen is used to transfer funds from GL to the customer account.
- Miscellaneous GL Debit
  The **Miscellaneous GL Debit** screen is used to debit an amount from a GL account of the transaction branch and pay out the equivalent amount in cash.
- Miscellaneous GL Credit
  The **Miscellaneous GL Credit** screen is used to credit an amount to a GL account of the transaction branch by pay-in of equivalent amount in cash.
- Miscellaneous GL Transfer
  The **Miscellaneous GL Transfer** screen is used to transfer the amount from a GL account to another GL account.
- Miscellaneous Transfer
  The **Miscellaneous Transfer** screen is used to facilitate transfer between the two different GLs or customer accounts.

5.1 Miscellaneous Customer Debit

The **Miscellaneous Customer Debit** screen is used to transfer funds from the customer account to GL.

The customer account can be debited for various reasons, with a corresponding credit to a GL belonging to the transaction branch.


To transfer funds from the customer account to GL:

1. On the Homepage, from **Teller** mega menu, under **Miscellaneous**, click **Misc Customer Debit** or specify **Misc Customer Debit** in the search icon bar and select the screen.

   The **Miscellaneous Customer Debit** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 5-1 Miscellaneous Customer Debit



2. On the **Miscellaneous Customer Debit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 5-1 Miscellaneous Customer Debit - Field Description

Field	Description
Account Number	Specify the account number from which the funds need to be debited. **Note** The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Account Amount	Displays the account currency based on the account number specified. Specify the amount that needs to be debited from the account currency.
GL Account	Specify the GL account to which the funds need to be credited. **Note** You can also select the appropriate GL account from the list of values that displays all the valid GL accounts.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-1 (Cont.) Miscellaneous Customer Debit - Field Description

Field	Description
GL Branch	Displays the branch code of the transaction branch, and it can be modified.
GL Description	Displays the description of the selected GL account number.
GL Currency	By default, the account currency is displayed, and it can be modified.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into GL currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
GL Amount	Displays the amount in terms of GL currency. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-1 (Cont.) Miscellaneous Customer Debit - Field Description

Field	Description
Reference Number	Specify the reference number for the transaction, which is the original transaction reference or any invoice number.
Narrative	Displays the narrative as **Miscellaneous Customer Debit**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

5.2 Miscellaneous Customer Credit

The **Miscellaneous Customer Credit** screen is used to transfer funds from GL to the customer account.


The customer account can be credited for various reasons, with the corresponding debit to a GL belonging to the transaction branch.

To perform the miscellaneous customer credit:

1. On the Homepage, from **Teller** mega menu, under **Miscellaneous**, click **Misc Customer Credit** or specify **Misc Customer Credit** in the search icon bar and select the screen.

   The **Miscellaneous Customer Credit** screen is displayed.

Figure 5-2 Miscellaneous Customer Credit



Copyright © 2021, 2025, Oracle and/or its affiliates.

2. On the **Miscellaneous Customer Credit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 5-2 Miscellaneous Customer Credit - Field Description

Field	Description
Account Number	Specify the account number from which the funds need to be credited. **Note** In addition, you can use Oracle Banking Virtual Accounts. These Virtual Accounts are used as a routing account to credit the underlying physical account. The system displays an override or error message on the tab out of Account Number based on the account dormancy parameters.
Account Amount	Displays the account currency based on the account number specified. Specify the amount to be credited from the account currency.
GL Account	Specify the GL account from which the funds need to be debited. **Note** You can also select the appropriate GL account from the list of values that displays all the valid GL accounts.
GL Branch	Displays the branch code of the transaction branch and allows to modify.
GL Description	Displays the description of the selected GL account number.
GL Currency	By default, the account currency is displayed, and it can be modified.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into GL currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-2 (Cont.) Miscellaneous Customer Credit - Field Description

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
GL Amount	Displays the amount in terms of GL currency. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Reference Number	Specify the reference number for the transaction, which is the original transaction reference or any invoice number.
Narrative	Displays the narrative as **Miscellaneous Customer Credit**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the GL account is debited, and the customer account is credited to the extent of the **Account Amount**.

5.3 Miscellaneous GL Debit


The **Miscellaneous GL Debit** screen is used to debit an amount from a GL account of the transaction branch and pay out the equivalent amount in cash.

To perform miscellaneous GL debit:

1. On the Homepage, from **Teller** mega menu, under **Miscellaneous**, click **Misc GL Debit** or specify **Misc GL Debit** in the search icon bar and select the screen.

   The **Miscellaneous GL Debit** screen is displayed.

Figure 5-3 Miscellaneous GL Debit



2. On the **Miscellaneous GL Debit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-3 Miscellaneous GL Debit - Field Description

Field	Description
GL Account	Specify the GL account from which the funds need to be debited. **Note** You can also select the appropriate GL account from the list of values that displays all the valid GL accounts.
GL Description	Displays the description of the selected GL account number.
Transaction Amount	Specify the appropriate currency and the amount that has to be credited to the cash account in the specified currency. **Note** By default, the local currency of the branch is displayed. You can select another currency if required.
GL Currency	Displays the branch account currency and allows to modify if required.
GL Amount	Displays the amount which is credited to the GL account. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into GL currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-3 (Cont.) Miscellaneous GL Debit - Field Description

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Reference Number	Specify the reference number for the transaction.
Narrative	Displays the default narrative as **Miscellaneous GL Debit**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the cash balance of the Teller is updated successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

5.4 Miscellaneous GL Credit


The **Miscellaneous GL Credit** screen is used to credit an amount to a GL account of the transaction branch by pay-in of equivalent amount in cash.

To perform miscellaneous GL credit:

1. On the Homepage, from **Teller** mega menu, under **Miscellaneous**, click **Misc GL Credit** or specify **Misc GL Credit** in the search icon bar and select the screen.

   The **Miscellaneous GL Credit** screen is displayed.

Figure 5-4 Miscellaneous GL Credit



2. On the **Miscellaneous GL Credit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 5-4 Miscellaneous GL Credit - Field Description

Field	Description
GL Account	Specify the GL account to which the funds need to be credited. **Note** You can also select the appropriate GL account from the list of values that displays all the valid GL accounts.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-4 (Cont.) Miscellaneous GL Credit - Field Description

Field	Description
GL Amount	Displays the branch account currency and allows to modify if required. It also displays the amount which is credited to the GL account. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
GL Description	Displays the description of the selected GL account number.
Transaction Amount	Specify the appropriate currency and the amount that has to be debited from the cash account in the specified currency. **Note** By default, the local currency of the branch is displayed. You can select another currency if required.
Negotiated Exchange Rate	Specify the negotiated exchange rate if it is needed to perform the transaction using negotiated value. **Note** This field is applicable only if the transaction involves cross currency. If this option is selected, the **Negotiated Reference Number** field will become mandatory.
Negotiated Reference Number	Specify the reference number for the negotiated cost rate. **Note** This field is applicable only if the transaction involves cross currency.
Narrative	Displays the default narrative as **Miscellaneous GL Credit**, and it can be modified.
Reference Number	Specify the reference number for the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-4 (Cont.) Miscellaneous GL Credit - Field Description

Field	Description
Exchange Rate	Displays the exchange rate used to convert the transaction currency into GL currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves. On transaction completion, the cash balance of the Teller gets updated successfully.

5.5 Miscellaneous GL Transfer

The **Miscellaneous GL Transfer** screen is used to transfer the amount from a GL account to another GL account.

This transaction can be carried out in various allowed currencies.


To perform miscellaneous GL transfer:

1. On the Homepage, from **Teller** mega menu, under **Miscellaneous**, click **Misc GL Transfer** or specify **Misc GL Transfer** in the search icon bar and select the screen.

   The **Miscellaneous GL Transfer** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 5-5 Miscellaneous GL Transfer



2. On the **Miscellaneous GL Transfer** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 5-5 Miscellaneous GL Transfer - Field Description

Field	Description
From GL Account	Specify the GL account to which the funds need to be debited. **Note** You can also select the appropriate GL account from the list of values that displays all the valid GL accounts.
From GL Amount	Displays the branch account currency and allows to modify if required. It also displays the amount, which is debited from the GL account.
From GL Description	Displays the description of the selected GL account number.
GL Currency	Displays the branch currency and allows to modify if required.
From GL Branch	Click the search icon, and select the **From GL Branch** from the list of values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-5 (Cont.) Miscellaneous GL Transfer - Field Description

Field	Description
To GL Account	Specify the GL account to which the funds need to be credited. **Note** You can also select the appropriate GL account from the list of values that displays all the valid GL accounts.
To GL Amount	Displays the branch account currency and allows to modify if required. It also displays the amount, which is credited to the GL account.
To GL Description	Displays the description of the selected GL account number.
GL Currency	Displays the branch currency and allows to modify if required.
To GL Branch	Click the search icon, and select the **To GL Branch** from the list of values.
Narrative	Displays the default narrative as **Miscellaneous GL Transfer**, and it can be modified.
Reference Number	Specify the reference number for the transaction.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into GL currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

5.6 Miscellaneous Transfer

The **Miscellaneous Transfer** screen is used to facilitate transfer between the two different GLs or customer accounts.

This transaction can be carried out between:

- GL to GL
- GL to Customer Account
- Customer Account to GL

To facilitate transfer using this screen, maintain as per the sample given below:

- Maintain static tags for the function code ACCL in the SRV_TB_TX_STATIC_TAGS table.
- Maintain actions URLs for function code ACCL in the SRV_TB_BC_ACTIONS_URL table.
- For the **Function Code Definition** screen,
  - Enable **Support Child Function Code** field for the function code 1000.
  - Maintain the **Parent Function Code** as 1000 for the function code ACCL.
- Maintain the function code preferences for ACCL.
- Maintain settlement definition for the ACCL function code with the Transaction Account/ GL and Offset Account/ GL.


To perform miscellaneous transfer:

1. On the Homepage, from **Teller** mega menu, under **Miscellaneous**, click **Miscellaneous Transfer** or specify **Miscellaneous Transfer** in the search icon bar and select the screen.

   The **Miscellaneous Transfer** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 5-6 Miscellaneous Transfer



2. On the **Miscellaneous Transfer** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 5-6 Miscellaneous Transfer

Field	Description
Function Code	Click the search icon, and select the function code from the list of values, which contains only non-cash transactions.
Currency	Click the search icon, and select the currency from the list of values. **Note** By default, the currency field will default to the local branch currency, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-6 (Cont.) Miscellaneous Transfer

Field	Description
Query	Click **Query** to fetch the details. **Note** Based on the specified values of **Function Code** and **Currency**, the system populates **Debit Account** and **Credit Account** details. You can also modify the values.
Debit Account Details	Specify the fields under this section.
Debit Account	Click the search icon, and select the debit account number from the list of values.
Debit Account Name	Displays the name of the specified debit account.
Debit Account Branch	Click the search icon, and select the debit account branch from the list of values.
Debit Currency	Click the search icon, and select the debit currency from the list of values.
Debit Amount	Specify the amount that needs to be debited.
Credit Account Details	Specify the fields under this section.
Credit Account	Click the search icon, and select the credit account number from the list of values.
Credit Account Name	Displays the name of the specified credit account.
Credit Account Branch	Click the search icon, and select the credit account branch from the list of values.
Credit Currency	Click the search icon, and select the credit currency from the list of values.
Credit Amount	Displays the credit amount based on the exchange rate pickup. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Exchange Rate	Displays the exchange rate used to convert the transfer currency into transaction currency and it can be modified. **Note** If the transfer currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 5-6 (Cont.) Miscellaneous Transfer

Field	Description
Total Charges	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Additional Details	Specify the fields under this section.
Reference Number	Specify the reference number of the transaction.
Narrative	Displays the default narrative as **Miscellaneous Transfer**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

6 Transfers

The Teller can use Transfers to perform inter-bank transfers, intra-bank transfers, and cross-border transactions.

This topic contains the following subtopics:

- Account to Account Transfer
  The **Account to Account Transfer** screen is used to transfer funds from one account to another account within the bank.
- In-House Cheque Deposit
  The **In House Cheque Deposit** screen is used to capture in-house cheque deposit transactions for the customers.
- Domestic Transfer Against Account
  The **Domestic Transfer Against Account** screen is used to transfer funds from an account held with the bank to an account held with another bank, within the same country.
- Domestic Transfer Against Walk-in
  The **Domestic Transfer Against Walk-in** screen is used to accept cash from the walk-in customer and transfer funds to the account held with another bank within the same country.
- International Transfer Against Account
  The **International Transfer Against Account** screen is used to facilitate international transfer by debiting the account holder of the bank.
- International Transfer Against Walk-in
  The **International Transfer Against Walk-in** screen is used to facilitate international transfer by accepting cash from the walk-in customer.

6.1 Account to Account Transfer

The **Account to Account Transfer** screen is used to transfer funds from one account to another account within the bank.

The funding account and beneficiary account can be in different currencies and belong to different branches.


To perform account transfer:

1. On the Homepage, from **Teller** mega menu, under **Transfers**, click **Account to Account Transfer** or specify **Account to Account Transfer** in the search icon bar and select the screen.

   The **Account Transfer** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 6-1 Account Transfer



2. On the **Account Transfer** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 6-1 Account Transfer - Field Description

Field	Description
Debit Account	Specify the customer account from which the funds need to be debited.
Debit Amount	Displays the transaction account currency. Specify the transaction amount that needs to be debited from the customer account.
Credit Account	Specify the account to which the funds need to be credited. **Note** In addition, you can use Oracle Banking Virtual Accounts. These Virtual Accounts are used as a routing account to credit the underlying physical account.
Credit Account Name	Displays the description of the account number specified.
Credit Account Branch	Displays the branch code of the account number specified.
Credit Amount	Displays the amount in terms of the credit account currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-1 (Cont.) Account Transfer - Field Description

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate if it is needed to perform the transaction using negotiated value. **Note** This field is applicable only if the transaction involves cross currency. If this option is selected, the **Negotiated Reference Number** field will become mandatory.
Negotiated Reference Number	Specify the reference number for the negotiated cost rate. **Note** This field is applicable only if the transaction involves cross currency.
Exchange Rate	Displays the exchange rate used to convert the transaction account currency into credit account currency and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge (LCY)	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **Account Transfer**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the UBS for accounting.

6.2 In-House Cheque Deposit


The **In House Cheque Deposit** screen is used to capture in-house cheque deposit transactions for the customers.

To capture in-house cheque deposit transactions:

1. On the Homepage, from **Teller** mega menu, under **Transfers**, click **In House Cheque Deposit** or specify **In House Cheque Deposit** in the search icon bar and select the screen.

   The **In House Cheque Deposit** screen is displayed.

Figure 6-2 In House Cheque Deposit



2. On the **In House Cheque Deposit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-2 In House Cheque Deposit - Field Description

Field	Description
Debit Account	Specify the account number of the drawer.
Debit Account Name	Displays the name of the account.
Debit Account Branch	Displays the branch code of the account number specified.
Cheque Amount	Specify the currency and amount as mentioned in the cheque.
Cheque Number	Specify the cheque number. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Specify the date of issue as mentioned in the cheque.
Credit Account	Specify the account number that needs to be credited with the cheque amount.
Credit Amount	Displays the transaction amount based on the exchange rate. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges (LCY)	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-2 (Cont.) In House Cheque Deposit - Field Description

Field	Description
Reject Code	Select the reject code from the list of values, which are maintained in the **Reject Code Maintenance** screen. **Note** If the in house cheque deposit transaction needs to be rejected, you can reject it by specifying the appropriate reject code in this field. The transaction can be rejected for any of the following reasons: • Insufficient funds • Signature mismatch • Stale cheque
Reject Code Description	Displays the description of the specified reject code.
Narrative	Displays the default narrative as **In-House Cheque Deposit**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to UBS for accounting.

6.3 Domestic Transfer Against Account

The **Domestic Transfer Against Account** screen is used to transfer funds from an account held with the bank to an account held with another bank, within the same country.

Based on the payment type selected, the transaction is routed to the corresponding transaction network.


To perform domestic transfer against account:

1. On the Homepage, from **Teller** mega menu, under **Transfers**, click **Domestic Trf - Account** or specify **Domestic Trf - Account** in the search icon bar and select the screen.

   The **Domestic Transfer Against Account** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 6-3 Domestic Transfer Against Account



2. On the **Domestic Transfer Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 6-3 Domestic Transfer Against Account - Field Description

Field	Description
Remitter Account	Specify the customer account from which the funds need to be debited.
Transaction Amount	Displays the transaction account currency and it allows to select from drop-down values. Specify the transaction amount that needs to be debited from the customer account.
Cheque Number	Specify the cheque number of the customer account as provided by the customer. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Click the calendar icon and select the date on which the cheque has been issued.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-3 (Cont.) Domestic Transfer Against Account - Field Description

Field	Description
Account Amount	Displays the amount in terms of the remitter account currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Exchange Rate	Displays the exchange rate used to convert the transaction account currency into credit account currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charges	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **Domestic Transfer Against Account**, and it can be modified.

3. Specify the payment details. For information on the fields in the **Payment Details** segment, refer to Add Payment Details for Domestic Transfer.
4. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for outgoing payment creation and processing with external system status as

Copyright © 2021, 2025, Oracle and/or its affiliates.

Pending. After the transaction is processed and responded from the Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

> **Note**
>
> System shall automate the completion of payment transactions from Journal log, once the 'Success' notification is received from Oracle Banking Payments based on the flag Auto Processing as Y in TRANSACTION.SRV_TM_BC_PARAM_DTLS. (When Auto Processing is 'N', then Maker-Checker-Maker-Maker and when Auto Processing is Y then Maker-Checker-Maker).


- Add Payment Details for Domestic Transfer
  You can add the payment details for the domestic transfer in the **Payment Details** data segment.

6.3.1 Add Payment Details for Domestic Transfer

You can add the payment details for the domestic transfer in the **Payment Details** data segment.

Make sure that the transaction details are added to the screen.

Figure 6-4 Payment Details



Copyright © 2021, 2025, Oracle and/or its affiliates.

To add the payment details:

On the **Payment Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 6-4 Payment Details - Field Description

Field	Description
Remitter Details	Specify the fields.
Remitter Name	Displays the remitter description based on the remitter account number specified.
Address Line 1 to **Address Line 4**	Displays the remitter address details.
Communication Mode	Specify the mode of communication for the transaction. The drop-down values are **E-Mail** and **Phone**.
Mobile No	Specify the mobile number if the mode of communication is selected as **Phone**.
Email ID	Specify the email address if the mode of communication is selected as **E-Mail**.
Beneficiary Details	Specify the fields.
Payment Type	Select the payment type from the drop-down values.
Beneficiary Bank Code	Select the beneficiary bank code from the list of values. **Note** The LOV display all valid clearing bank codes maintained in the system.
Beneficiary Bank Name	Specify the name of the beneficiary bank. If the beneficiary bank code is selected, the system displays the description.
Beneficiary Account	Specify the account number of the beneficiary.
Account Type	Select the account type of the beneficiary from the drop-down list.
Account Name	Specify the account name of the beneficiary.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Remittance Information	Specify the fields.
Remittance Information Line 1 to **Remittance Information Line 4**	Specify the remittance information in free text format.

Copyright © 2021, 2025, Oracle and/or its affiliates.

6.4 Domestic Transfer Against Walk-in

The **Domestic Transfer Against Walk-in** screen is used to accept cash from the walk-in customer and transfer funds to the account held with another bank within the same country.


Based on the payment type selected, the transaction is routed to the corresponding transaction network.

To perform domestic transfer against walk-in:

1. On the Homepage, from **Teller** mega menu, under **Transfers**, click **Domestic Trf - Walkin** or specify **Domestic Trf - Walkin** in the search icon bar and select the screen.

   The **Domestic Transfer Against Walk-in** screen is displayed.

Figure 6-5 Domestic Transfer Against Walk-in



2. On the **Domestic Transfer Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 6-5 Domestic Transfer Against Walkin - Field Description

Field	Description
Transaction Amount	Select the transaction currency from the drop-down list. Specify the transaction amount that needs to be transferred.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-5 (Cont.) Domestic Transfer Against Walkin - Field Description

Field	Description
Total Charges	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **Domestic Transfer Against Walkin**, and it can be modified.

3. Specify the payment details. For information on the fields in the **Payment Details** segment, refer to Add Payment Details for Domestic Transfer.
4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

   Note

   The transaction is moved to authorization in case of any warning raised when the transaction saves.

   When you submit, the transaction details are handed off to the Oracle Banking Payments system for outgoing payment creation and processing with external system status as **Pending**. After the transaction is processed and responded from the Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

6.5 International Transfer Against Account

The **International Transfer Against Account** screen is used to facilitate international transfer by debiting the account holder of the bank.

You can remit in the currency of the customer account and transfer in another currency based on the request from the customer. If the transaction currency differs from the transfer currency, the exchange rate is populated to calculate the equivalent amount.


To perform international transfer against account:

1. On the Homepage, from **Teller** mega menu, under **Transfers**, click **International - Account** or specify **International - Account** in the search icon bar and select the screen.

   The **International Transfer Against Account** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 6-6 International Transfer Against Account



2. On the **International Transfer Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 6-6 International Transfer Against Account - Field Description

Field	Description
Remitter Account	Specify the customer account from which the funds need to be debited.
Transfer Amount	Specify the transfer account currency and the transfer amount that needs to be debited from the customer account.
Transaction Amount	Displays the remitter account currency based on the account number selected and the transaction amount based on the exchange rate. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-6 (Cont.) International Transfer Against Account - Field Description

Field	Description
Exchange Rate	Displays the exchange rate used to convert the transfer account currency into credit account currency, and it can be modified. **Note** If the transfer currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Total Charge Amount	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **International Transfer Against Account**, and it can be modified.

3. Specify the payment details. For information on the fields in the **Payment Details** segment, refer to Add Payment Details for International Transfer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

   > **Note**
   >
   > The transaction is moved to authorization in case of any warning raised when the transaction saves.

   When you submit, the transaction details are handed off to the Oracle Banking Payments system for outgoing payment creation and processing with external system status as **Pending**. After the transaction is processed and responded from Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

   > **Note**
   >
   > System shall automate the completion of payment transactions from Journal log, once the 'Success' notification is received from Oracle Banking Payments based on the flag Auto Processing as Y in TRANSACTION.SRV_TM_BC_PARAM_DTLS. (When Auto Processing is 'N', then Maker-Checker-Maker-Maker and when Auto Processing is Y then Maker-Checker-Maker).

- Add Payment Details for International Transfer
  You can add the payment details for the international transfer in the **Payment Details** data segment.


6.5.1 Add Payment Details for International Transfer

You can add the payment details for the international transfer in the **Payment Details** data segment.

Make sure that the transaction details are added to the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 6-7 Payment Details



To add the payment details:

On the **Payment Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-7 Payment Details - Field Description

Field	Description
Remitter Details	Specify the fields.
Remitter Name	Displays the remitter description based on the remitter account number specified.
Address Line 1 to **Address Line 4**	Displays the remitter address details.
Communication Mode	Specify the mode of communication for the transaction. The drop-down values are **E-Mail** and **Mobile No**.
Mobile No	Specify the mobile number. **Note** This field is mandatory if the **Communication Mode** is selected as **Mobile No**.
Email ID	Specify the email address. **Note** This field is mandatory if the **Communication Mode** is selected as **E-Mail**.
Beneficiary Details	Specify the fields.
Beneficiary Bank BIC Code	Select the beneficiary BIC code from the list of values. **Note** The LOV display all valid swift BIC codes maintained in the system.
Beneficiary Bank Code	Select the beneficiary bank code from the list of values. **Note** The LOV display all valid clearing bank codes maintained in the system.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-7 (Cont.) Payment Details - Field Description

Field	Description
Beneficiary Bank Name	Specify the name of the beneficiary bank. **Note** If the beneficiary bank code is selected, the system displays the description.
Receiver BIC Code	Specify the receiver BIC code from the list of values. **Note** The LOV displays all the valid swift BIC codes maintained in the system.
Beneficiary Account	Specify the account number of the beneficiary.
Account Type	Select the account type of the beneficiary from the drop-down list.
Account Name	Specify the account name of the beneficiary.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Remittance Information	Specify the fields.
Remittance Information Line 1 to **Remittance Information Line 4**	Specify the remittance information in free text format.
Instruction Details	Specify the details under this section.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-7 (Cont.) Payment Details - Field Description

Field	Description
Instruction Code 1 to **Instruction Code 6**	Select the instruction codes from the drop-down list, and specify the additional information. The drop-down values are as follows: • **CHQB** – Cheque, Pay beneficiary customer by cheque only. • **HOLD** – Hold, Beneficiary customer/claimant will call; pay upon identification. • **PHOB** – Phone Beneficiary, Advise/contact beneficiary/claimant by phone. • **PHOI** – Phone Intermediary, Advise the intermediary institution by phone. • **PHON** – Telephone, Advise account with institution by phone. • **REPA** – Related Payment, Payment has a related e-Payments reference. • **TELB** – Telecommunication, Advise/contact beneficiary/claimant by the most efficient means of telecommunication. • **TELE** – Telecommunication, Advise the account with the institution by the most efficient means of telecommunication. • **TELI** – Telecommunication, Advise the intermediary institution by the most efficient means of telecommunication. • **INTC** – Intra-Company Payment, A payment between two companies belonging to the same group. • **SDVA** – Same Day Value, Payment must be executed with same-day value to the beneficiary. • **CORT** – Corporate Trade, Payment is made in settlement of a trade, for example, foreign exchange deal, securities transaction. **Note** The field for additional information is disabled for the following codes: • **CHQB** • **INTC** • **SDVA** • **CORT**

6.6 International Transfer Against Walk-in

The **International Transfer Against Walk-in** screen is used to facilitate international transfer by accepting cash from the walk-in customer.

You can remit funds in transaction currency and transfer them in another currency based on the customer's request. If the transaction currency differs from the transfer currency, the exchange rate is populated to calculate the equivalent amount.


To perform international transfer against walk-in:

1. On the Homepage, from **Teller** mega menu, under **Transfers**, click **International - Walk-in** or specify **International - Walk-in** in the search icon bar and select the screen.

   The **International Transfer Against Walk-in** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 6-8 International Transfer Against Walk-in



2. On the **International Transfer Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 6-8 International Transfer Against Walk-in - Field Description

Field	Description
Transaction Amount	Specify the currency in which the cash is accepted from the walk-in customer and the transaction amount as requested by the customer.
Transfer Currency	Specify the currency in which the funds are to be transferred.
Transfer Amount	Displays the transfer amount based on the exchange rate pickup. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 6-8 (Cont.) International Transfer Against Walk-in - Field Description

Field	Description
Exchange Rate	Displays the exchange rate used to convert the transfer currency into transaction currency, and it can be modified. **Note** If the transfer currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Total Charge Amount	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **International Transfer Against Walk-in**, and it can be modified.

3. Specify the payment details. For information on the fields in the **Payment Details** segment, refer to Add Payment Details for International Transfer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for outgoing payment creation and processing with external system status as **Pending**. After the transaction is processed and responded from Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

> **Note**
>
> System shall automate the completion of payment transactions from Journal log, once the ‘Success’ notification is received from Oracle Banking Payments based on the flag Auto Processing as Y in TRANSACTION.SRV_TM_BC_PARAM_DTLS. (When Auto Processing is ‘N’, then Maker-Checker-Maker-Maker and when Auto Processing is Y then Maker-Checker-Maker).

Copyright © 2021, 2025, Oracle and/or its affiliates.

7

Clearing Transactions

The Teller can use screens under Clearing to perform the clearing transactions.

This topic contains the following subtopics:

- Cheque Deposit
  You can use the **Cheque Deposit** screen to capture the cheque deposit request submitted by the customer.
- Cheque Return
  The Teller can use the **Cheque Return** screen to initiate manual return of inward or outward clearing cheques.
- Inward Clearing Data Entry
  The Teller can use the **Inward Clearing Data Entry** screen to initiate the inward processing of bulk instruments.
- Outward Clearing Data Entry
  The Teller can use the **Outward Clearing Data Entry** screen to initiate the bulk deposit of instruments.

7.1 Cheque Deposit

You can use the **Cheque Deposit** screen to capture the cheque deposit request submitted by the customer.

This topic contains the following subtopics:

- Cheque Deposit Against Account
  The Teller can use the **Cheque Deposit** screen to carry out the cheque deposit transaction for a customer.
- Cheque Deposit Against GL
  The Teller can use the **Cheque Deposit** screen to carry out the cheque deposit transaction for credit of a GL account.

7.1.1 Cheque Deposit Against Account

The Teller can use the **Cheque Deposit** screen to carry out the cheque deposit transaction for a customer.


To capture the cheque deposit request:

1. On the Homepage, from **Teller** mega menu, under **Clearing**, click **Cheque Deposit** or specify **Cheque Deposit** in the search icon bar and select the screen.

   The **Cheque Deposit** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 7-1 Cheque Deposit



2. On the **Cheque Deposit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 7-1 Cheque Deposit (Account Mode) - Field Description

Field	Description
Cheque Amount	Specify the currency and amount mentioned in the cheque that needs to be deposited in the account.
Cheque Date	Specify the cheque issued date.
Deposit Mode	Select the deposit mode as **Account** from the drop-down values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 7-1 (Cont.) Cheque Deposit (Account Mode) - Field Description

Field	Description
Payee Account	Specify the customer account number in which the cheque needs to be deposited. When you press the **Tab** key, the following details are displayed: • Customer ID • Image • Signature • KYC Status • Account Balance • Address **Note** If the specified account number is a joint account holder, the joint holder details of the account can be viewed in the Customer Information Widget along with the mode of operation.
Cheque Number	Specify the MICR number displayed on the cheque.
Drawer Account	Specify the account number on which the cheque is drawn.
Drawer Name	Specify the name of the drawer account.
Network Code	Specify the network code. **Note** You can also select from the list of maintained clearing codes.
Routing Number	Specify the routing number for cheque clearance. The list of values will call the Oracle Banking Payments service to fetch the list of routing numbers based on the **Clearing Network Code** selected.
Cheque Deposit Date	Displays the current posting date as the cheque deposit date.
Account Amount	Displays the account amount.
Exchange Rate	Displays the exchange rate used to convert the cheque currency into transaction currency, and it can be modified. **Note** If the transfer currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 7-1 (Cont.) Cheque Deposit (Account Mode) - Field Description

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Total Charges (LCY)	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **Cheque Deposit**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for Outward Clearing transaction processing with external system status as **Pending**.

After the transaction is processed and responded from the Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

OBBRN will only do data capture and populate the request to OBPM for main leg accounting. Charge accounting will be posted to UBS from OBBRN.

> **Note**
>
> System shall automate the completion of payment transactions from Journal log, once the 'Success' notification is received from Oracle Banking Payments based on the flag Auto Processing as Y in TRANSACTION.SRV_TM_BC_PARAM_DTLS.

7.1.2 Cheque Deposit Against GL


The Teller can use the **Cheque Deposit** screen to carry out the cheque deposit transaction for credit of a GL account.

To capture the cheque deposit request:

1. On the Homepage, from **Teller** mega menu, under **Clearing**, click **Cheque Deposit** or specify **Cheque Deposit** in the search icon bar and select the screen.

   The **Cheque Deposit** screen is displayed.

Figure 7-2 Cheque Deposit



Copyright © 2021, 2025, Oracle and/or its affiliates.

2. On the **Cheque Deposit** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 7-2 Cheque Deposit (GL Mode) - Field Description

Field	Description
Cheque Amount	Specify the currency and amount mentioned in the cheque that needs to be deposited in the account.
Cheque Date	Specify the cheque issued date.
Deposit Mode	Select the deposit mode as **GL** from the drop-down values.
Payee GL	Specify the customer GL number in which the cheque needs to be deposited.
GL Description	Displays the description of the specified Payee GL.
GL Currency	Select the GL currency from the list of values.
Cheque Number	Specify the MICR number displayed on the cheque.
Drawer Account	Specify the account number on which the cheque is drawn.
Drawer Name	Specify the name of the drawer account.
Network Code	Specify the network code. **Note** You can also select from the list of maintained clearing codes.
Routing Number	Specify the routing number for cheque clearance. The list of values will call the Oracle Banking Payments service to fetch the list of routing numbers based on the **Network Code** selected.
Cheque Deposit Date	Displays the current posting date as the cheque deposit date.
Account Amount	Displays the account amount.
Exchange Rate	Displays the exchange rate used to convert the cheque currency into transaction currency, and it can be modified. **Note** If the transfer currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 7-2 (Cont.) Cheque Deposit (GL Mode) - Field Description

Field	Description
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.
Total Charges (LCY)	Displays the total charge amount, which is computed by the system. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **Cheque Deposit**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for Outward Clearing transaction processing with external system status as **Pending**.

After the transaction is processed and responded from the Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

7.2 Cheque Return

The Teller can use the **Cheque Return** screen to initiate manual return of inward or outward clearing cheques.


An inward cheque transaction may not be processed successfully for funds needed in the drawer account or due to stop payment of the cheque. In addition, an outward cheque transaction may get returned if the same is returned from the clearing house.

To perform cheque return:

1. On the Homepage, from **Teller** mega menu, under **Clearing**, click **Cheque Return** or specify **Cheque Return** in the search icon bar and select the screen.

   The **Cheque Return** screen is displayed.

Figure 7-3 Cheque Return



2. On the **Cheque Return** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 7-3 Cheque Return - Field Description

Field	Description
Drawer Account	Specify the drawer account number.
Cheque Number	Specify the cheque number.
Query	Click **Query** to fetch cheque details.
Clear	Click **Clear** to clear the cheque details.
Drawer Account	Displays the drawer account number.
Drawer Routing No	Displays the routing number of the specified drawer account.
Cheque Number	Displays the cheque number.
Cheque Amount	Displays the cheque amount.
Cheque Date	Displays the cheque date.
Payee Account	Displays the payee account number.
Payee Name	Displays the payee name.
Payee Routing No.	Displays the payee routing number.
Return Type	Displays the return type (**Inward** and **Outward**).
Reject Code	Select the reject code from the list of values.
Reject Reason	Displays the reason to reject.
Total Charges	Displays the total charge amount, which is computed by the system.
Narrative	Displays the default narrative as **Cheque Return**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

7.3 Inward Clearing Data Entry

The Teller can use the **Inward Clearing Data Entry** screen to initiate the inward processing of bulk instruments.

This screen supports to capture of bulk input of inward clearing transactions for multiple instrument types – Cheque, Bankers Cheque, and Demand Draft. It also supports bulk data entry of inward clearing transactions for single and multiple customer accounts.

To initiate the inward processing of bulk instruments:


1. On the Homepage, from **Teller** mega menu, under **Clearing**, click **Inward Clearing Data Entry** or specify **Inward Clearing Data Entry** in the search icon bar and select the screen.

   The **Inward Clearing Data Entry** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> Charges are not supported for this screen.

Figure 7-4 Inward Clearing Data Entry



2. On the **Inward Clearing Data Entry** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 7-4 Inward Clearing Data Entry - Field Description

Field	Description
New	Click **New** to create a new clearing transaction and generate the batch reference number.
Fetch	Click **Fetch** to enable the field **Batch Reference Number** and input or select from the list of values. The list of values fetches only the batches that are saved and not submitted.
Hold	Click **Hold** to save the data entry made as part of the specified batch number.
Batch Reference Number	Displays the unique batch number, which is system generated.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 7-4 (Cont.) Inward Clearing Data Entry - Field Description

Field	Description
Instrument Currency	Displays the current logged branch currency. **Note** You can also select the instrument currency from the drop-down values.
Total Amount	Displays the total batch amount in instrument currency.
Entry Details	Specify the fields.
Instrument Type	Select the instrument type from the drop-down values.
Drawer Account	Specify the drawer account number.
Account Name	Displays the name of the account number specified.
Account Branch	Displays the branch code of the account number specified.
Account Currency	Displays the currency of the account number specified.
Payee Account	Specify the payee account number. **Note** You can also select from the list of values.
Instrument No	Specify the instrument number.
Instrument Date	Specify the date of the instrument.
Instrument Amount	Specify the amount of the instrument.
Clearing Type	Specify the clearing type. **Note** You can also select from the list of values.
Drawer Routing No	Specify the routing number. **Note** You can also select from the list of values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 7-4 (Cont.) Inward Clearing Data Entry - Field Description

Field	Description
Payee Routing Number	Specify the routing number of the cheque. **Note** You can also select from the list of values.
Narrative	Displays the default narrative as **Inward Clearing Data Entry**, and it can be modified.
Add Entry	Click **Add Entry** to add multiple records in the table and allow modifying or deleting if required.
Reset	Click **Reset** to clear the inputted entry details before you add the entries.

3. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On submission of data entry, the individual instrument details will be handed off to Oracle Banking Payments using Inward Clearing Service.

7.4 Outward Clearing Data Entry

The Teller can use the **Outward Clearing Data Entry** screen to initiate the bulk deposit of instruments.

This screen supports to capture of bulk input of outward clearing transactions for multiple instrument types – Cheque, Bankers Cheque, and Demand Draft. It also supports bulk data entry of outward clearing transactions for single and multiple customer accounts.

To initiate the bulk deposit of instruments:


1. On the Homepage, from **Teller** mega menu, under **Clearing**, click **Outward Clearing Data Entry** or specify **Outward Clearing Data Entry** in the search icon bar and select the screen.

   The **Outward Clearing Data Entry** screen is displayed.

> **Note**
>
> Charges are not supported for this screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 7-5 Outward Clearing Data Entry



2. On the **Outward Clearing Data Entry** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 7-5 Outward Clearing Data Entry - Field Description

Field	Description
New	Click **New** to create a new clearing transaction and generate the batch reference number.
Fetch	Click **Fetch** to enable the field **Batch Reference Number** and input or select from the list of values. The list of values fetches only the batches that are saved and not submitted.
Hold	Click **Hold** to save the data entry made as part of the specified batch number.
Batch Reference Number	Displays the unique batch number, which is system generated.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 7-5 (Cont.) Outward Clearing Data Entry - Field Description

Field	Description
Instrument Currency	Displays the current logged branch currency. **Note** You can also select the instrument currency from the drop-down values.
Total Amount	Displays the total batch amount in instrument currency.
Entry Details	Specify the fields.
Payee Account	Specify the payee account number.
Account Name	Displays the name of the payee account number specified.
Account Currency	Displays the currency of the payee account number specified.
Account Branch	Displays the branch code of the payee account number specified.
Instrument Type	Select the instrument type from the drop-down values.
Drawer Account	Specify the drawer account number.
Drawer Name	Specify the name of the drawer account.
Instrument No	Specify the instrument number.
Instrument Date	Specify the date of the instrument.
Instrument Amount	Specify the amount of the instrument.
Clearing Type	Select the clearing type for the deposited instrument.
Drawer Routing No	Specify the routing number of the cheque. **Note** You can also select from the list of values.
Narrative	Displays the default narrative as **Outward Clearing Data Entry**, and it can be modified.
Add Entry	Click **Add Entry** to add multiple records in the table, and it allows modifying or deleting if required.
Reset	Click **Reset** to clear the inputted entry details before you add the entries.

3. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

On submission of data entry, the individual instrument details will be handed off to the Oracle Banking Payments using Outward Clearing Service.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8 Remittances

The Teller can use Remittances to issue demand drafts and banker's cheques, perform payment or cancellation of the issued remittances and perform further operations on the issued remittances.

This topic contains the following subtopics:

- Banker's Cheque
  The screens related to the Banker's Cheque (BC) can be used to issue BC, perform payment or cancellation of the issued BC, and perform further operations on the issued BC.
- Demand Drafts
  The screens related to the Demand Drafts (DD) can be used to issue DD, perform payment or cancellation of the issued DD, and perform further operations on the issued DD.
- Cash Remittance
  The screens related to the Cash Remittance can be used to issue remittance, perform payment or cancellation of the issued remittance, and perform further operations on the issued remittance.
- Travellers Cheque
  This sub-section describes the various screens used to perform the remittances related to Travellers Cheque. The screens are described in the following topics:
- Instrument Status Update
  The **Instrument Status Update** screen is used to change the status of used instrument numbers from ‘Used’ to ‘Unused’. This screen is used only when an unused instrument is marked as 'Used' by the application.
- Instrument Details Inquiry
  The **Instrument Details Inquiry** screen is to inquire details of the instrument for the DD and BC.
- Inventory Integration
  This topic describes about the Inventory Integration.

8.1 Banker's Cheque

The screens related to the Banker's Cheque (BC) can be used to issue BC, perform payment or cancellation of the issued BC, and perform further operations on the issued BC.

This topic contains the following subtopics:

- BC Issue Against Account
  The Teller can use the **BC Issue Against Account** screen to issue a BC against the CASA of a customer.
- BC Issue Against Walk-in
  The Teller can use the **BC Issue Against Walk-in** screen to issue a BC by cash to the walk-in customers.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- BC Issue Against GL
  The Teller can use the **BC Issue Against GL** screen to issue a BC against a GL account.
- BC Print and Reprint
  The Teller can use the **BC Print-Reprint** screen to print a BC. It is also used to re-print the BC if it is not properly printed or to issue duplicate instruments.
- BC Operations
  The Teller can use the **BC Operations** screen to handle the life cycle processing of Banker's Cheque (BC) that is already issued.
- Multi BC Issuance
  The Teller can use the **Multi BC Issuance** screen to issue banker's cheques against multiple beneficiaries.

8.1.1 BC Issue Against Account


The Teller can use the **BC Issue Against Account** screen to issue a BC against the CASA of a customer.

To issue a BC against the savings account:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Issue - Account** or specify **BC Issue - Account** in the search icon bar and select the screen.

   The **BC Issue Against Account** screen is displayed.

Figure 8-1 BC Issue Against Account



2. On the **BC Issue Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-1 BC Issue Against Account - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-1 (Cont.) BC Issue Against Account - Field Description


Field	Description
Issuing Bank Name	Specify the name of the issuing bank.
Issuing Branch Code	Displays the code of the logged-in branch.
Branch Name	Displays the description of issuing branch.
Payable Bank Code	Select the payable bank code. The list of values contains the bank codes maintained using the **External Bank Code Maintenance** screen. **Note** To remit funds within the same bank, select the logged-in bank code as payable bank code. To remit funds across banks, select the necessary bank code as payable bank code. The **Payable Branch Code** and **Payable Branch Name** fields will be enabled after you specify the **Payable Bank Code**.
Payable Bank Name	Displays the name of the selected bank code.
Payable Branch Code	Select the branch code of the payable bank. The list of values contains the corresponding branch codes maintained using the **Bank Code Maintenance** screen.
Payable Branch Name	Displays the branch name of the selected branch code.
BC Amount	Select the BC currency from the drop-down list and specify the BC amount.
BC Date	Select the date that needs to be mentioned in the BC. **Note** By default, the current posting date is displayed.
MICR No	Specify the MICR number and validate. If not specified, the system generates the MICR number based on the maintenance setup.
BC No	Displays the BC number.
Payee Details	Specify the fields.
Payee Name	Specify the payee name on which the BC is drawn.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Identification Type	Select the identification type of the payee from the drop-down list.
Payee Identification Number	Specify the identification number of the payee.
Narrative	Displays the default narrative as **BC Issuance Account**, and it can be modified.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-2 Funding Details



4. In the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-2 Funding Details - Field Description

Field	Description
Drawer Account	Specify the account number of the customer who has requested the BC.
Drawer Name	Displays the name of the specified drawer account number.
Cheque Number	Specify the cheque number of the drawer account. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Specify the date as mentioned in the cheque.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-2 (Cont.) Funding Details - Field Description

Field	Description
Exchange Rate	Displays the exchange rate used to convert the BC currency into account currency, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the transaction amount converted in terms of account amount based on the exchange rate. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Mode of Charge	Select the mode of charge from the following drop-down values (**Account** or **Other Account**).
Charge Account	Specify the charge account number. The following conditions apply based on the value selected for Mode of Charge: • If the **Mode of Charge** is selected as **Account**, the system will default the **Drawer Account**. • If Mode of Charge is selected as **Other Account**, the user needs to manually capture another account number for collection of charges. This account needs to belong to the same currency as the Drawer Account Currency.
Total Charges	Displays the total charges applicable for the BC issuance. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as `Y`.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for instruments processing with external system status as **Pending**.

After the transaction is processed and responded from the Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

> **Note**
>
> System shall automate the completion of payment transactions from Journal log, once the 'Success' notification is received from Oracle Banking Payments based on the flag Auto Processing as Y in TRANSACTION.SRV_TM_BC_PARAM_DTLS. (When Auto Processing is 'N', then Maker-Checker-Maker-Maker and when Auto Processing is Y then Maker-Checker-Maker).

8.1.2 BC Issue Against Walk-in


The Teller can use the **BC Issue Against Walk-in** screen to issue a BC by cash to the walk-in customers.

To issue a BC to the walk-in customers:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Issue - Walk-in** or specify **BC Issue - Walk-in** in the search icon bar and select the screen.

   The **BC Issue Against Walk-in** screen is displayed.

Figure 8-3 BC Issue Against Walk-in



2. On the **BC Issue Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-3 BC Issue Against Walk-in - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Bank Name	Specify the name of the issuing bank.
Issuing Branch Code	Displays the code of the logged-in branch.
Branch Name	Displays the description of issuing branch.
Payable Bank Code	Select the payable bank code. The list of values contains the bank codes maintained using the **External Bank Code Maintenance** screen. **Note** To remit funds within the same bank, select the logged-in bank code as payable bank code. To remit funds across banks, select the necessary bank code as payable bank code. The fields **Payable Branch Code** and **Payable Branch Name** will be enabled after you specify the **Payable Bank Code**.
Payable Bank Name	Displays the name of the selected bank code.
Payable Branch Code	Select the branch code of the payable bank. The list of values contains the corresponding branch codes maintained using the **Bank Code Maintenance** screen.
Payable Branch Name	Displays the branch name of the selected branch code.
BC Amount	Select the BC currency from the drop-down list and specify the BC amount.
BC Date	Select the date that needs to be mentioned in the BC. **Note** By default, the current posting date is displayed.
BC No	Specify the instrument number and validate. If not specified, the system generates the BC number based on the maintenance setup.
MICR Number	Displays the MICR number.
Payee Details	Specify the fields.
Payee Name	Specify the payee name on which the BC is drawn.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Identification Type	Select the identification type of the payee from the drop-down list.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 8-3 (Cont.) BC Issue Against Walk-in - Field Description

Field	Description
Payee Identification Number	Specify the identification number of the payee.
Narrative	Displays the default narrative as **BC Issuance Against Walk-in**, and it can be modified.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Figure 8-4 Funding Details



4. In the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-4 Funding Details - Field Description

Field	Description
Transaction Amount	Specify the transaction currency in which the walk-in customer deposits the cash.
Drawer Name	Specify the name of the drawer.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Identification Type	Select the identification type of the payee from the drop-down list.
Identification Number	Specify the identification number of the payee.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-4 (Cont.) Funding Details - Field Description

Field	Description
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charges	Displays the total charges applicable for the BC issuance. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as Y.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
7. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for instruments processing with external system status as **Pending**.

After the transaction is processed and responded from the Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

8.1.3 BC Issue Against GL

The Teller can use the **BC Issue Against GL** screen to issue a BC against a GL account.


To issue a BC against a GL account:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Issue - GL** or specify **BC Issue - GL** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **BC Issue Against GL** screen is displayed.

Figure 8-5 BC Issue Against GL



2. On the **BC Issue Against GL** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-5 BC Issue Against GL - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Bank Name	Specify the name of the issuing bank.
Issuing Branch Code	Displays the logged-in branch code.
Branch Name	Displays the description of issuing branch.
Payable Bank Code	Select the payable bank code. The list of values contains the bank codes maintained using the **External Bank Code Maintenance** screen. **Note** To remit funds within the same bank, select the logged-in bank code as payable bank code. To remit funds across banks, select the necessary bank code as payable bank code. The fields **Payable Branch Code** and **Payable Branch Name** will be enabled after you specify the **Payable Bank Code**.
Payable Bank Name	Displays the name of the selected bank code.
Payable Branch Code	Select the branch code of the payable bank. The list of values contains the corresponding branch codes maintained using the **Bank Code Maintenance** screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-5 (Cont.) BC Issue Against GL - Field Description

Field	Description
Payable Branch Name	Displays the branch name of the selected branch code.
BC Amount	Select the BC currency from the drop-down list and the BC amount.
BC Date	Select the date that needs to be mentioned in the BC. **Note** By default, the current posting date is displayed.
BC No	Specify the instrument number and validate. **Note** If not specified, the system generates the BC number based on the maintenance setup.
MICR Number	Displays the MICR number.
Payee Details	Specify the fields.
Payee Name	Specify the payee name on which the BC is drawn.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Identification Type	Select the identification type of the payee from the drop-down list.
Payee Identification Number	Specify the identification number of the payee.
Narrative	Displays the default narrative as **BC Issuance Against GL**, and it can be modified.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Figure 8-6 Funding Details



4. In the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-6 Funding Details - Field Description

Field	Description
GL Account	Select the account number of the GL against which the BC is issued from the LOV.
GL Description	Displays a brief description of the general ledger.
Drawer Name	Specify the name of the drawer.
Identification Type	Select the identification type of the payee from the drop-down list.
Identification Number	Specify the identification number of the payee.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for instruments processing with external system status as **Pending**.

After the transaction is processed and responded from the Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

8.1.4 BC Print and Reprint

The Teller can use the **BC Print-Reprint** screen to print a BC. It is also used to re-print the BC if it is not properly printed or to issue duplicate instruments.

The system keeps a track of such reprints so that the bank officials or auditors can determine the reasons and validity of multiple instrument printing.


To print or reprint a BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Print-Reprint** or specify **BC Print-Reprint** in the search icon bar and select the screen.

   The **BC Print-Reprint** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-7 BC Print-Reprint



2. On the **BC Print-Reprint** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-7 BC Print-Reprint - Field Description

Field	Description
Bankers Cheque No	Specify the BC number of the instrument that you need to print or re-print.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch Code	Select the branch code where the instrument is issued from the LOV.
Instrument Currency	Specify the instrument currency.
Print Type	Select the type **Print** or **Reprint** from the drop-down list.
Query	Click **Query** to fetch details of the BC transaction.
Issuing Branch Code	Displays the logged-in branch code.
BC Date	Displays the date mentioned in the BC.
BC Amount	Displays the BC currency and the BC amount.
Drawer Name	Displays the name of the drawer.
BC Status	Displays the status of the BC.
Beneficiary Details	Specify the fields.
Beneficiary Name	Displays the beneficiary's name.
Identification Details	Displays the identification details of the beneficiary.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-7 (Cont.) BC Print-Reprint - Field Description

Field	Description
Reprint Count	Specify the count of the current reprint operation. **Note** This is applicable only for the reprint option.
Narrative	Displays the default narrative as **Print/Reprint**, and it can be modified.

3. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

8.1.5 BC Operations

The Teller can use the **BC Operations** screen to handle the life cycle processing of Banker's Cheque (BC) that is already issued.

This topic contains the following subtopics:

- BC Inquiry
  The Teller can use the **BC Operations** screen to inquire about the details of BC.
- BC Revalidation
  The Teller can use the **BC Operations** screen to revalidate an instrument that is in expired status.
- BC Duplicate Issue
  The Teller can use the **BC Operations** screen to issue the instrument if the customer or banker lost the instrument or if the instrument is damaged.
- BC Payment by Account
  The Teller can use the **BC Operations** screen to make payment against a BC.
- BC Payment by Cash
  The Teller can use the **BC Operations** screen to make payment against a BC.
- BC Payment by GL
  The Teller can use the **BC Operations** screen to make payment against a BC.
- BC Refund by Account
  The Teller can use the **BC Operations** screen to refund the amount against a BC.
- BC Refund by Cash
  The Teller can use the **BC Operations** screen to refund the amount against a BC.
- BC Refund by GL
  The Teller can use the **BC Operations** screen to refund the amount against a BC.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Cancel BC by Account
  The Teller can use the **BC Operations** screen to cancel a BC.
- Cancel BC by Cash
  The Teller can use the **BC Operations** screen to cancel a BC.
- Cancel BC by GL
  The Teller can use the **BC Operations** screen to cancel a BC.

8.1.5.1 BC Inquiry


The Teller can use the **BC Operations** screen to inquire about the details of BC.

To inquire the details of BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-8 BC Operations - Inquiry



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-8 BC Operations (Inquiry) - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Bank Name	Specify the name of the issuing bank.
BC Number	Specify the BC number of the instrument.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-8 (Cont.) BC Operations (Inquiry) - Field Description

Field	Description
Issue Branch	Select the branch code where the instrument is issued from the LOV. After you specify the **Issue Branch Code** and **Bankers Cheque No**, press the **Tab** key. The system will make a service call to the Oracle Banking Payments and fetch the banker's cheque details.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Inquiry** from the drop-down list.
Query	Click this button to fetch instrument details. **Note** Queries are allowed only when the instrument issuance Transactions is marked as completed.
BC Details	Displays the details of BC under this segment.
Issue Branch	Displays the BC issuing branch.
Payable Bank Code	Displays the payable bank code.
Payable Branch	Displays the payable branch for the BC.
MICR No	Displays the MICR number.
Issue Date	Displays the issue date mentioned in the BC.
Issue Mode	Displays the issue mode of the BC.
Bankers Cheque Status	Displays the status of the BC.
Narrative	Displays narrative captured during **BC Issuance**.
Revalidation Date	Displays the date of BC revalidation.
Duplicate Issue Date	Displays the duplicate issue date of BC.
Liquidation Date	Displays the liquidation date of BC.
Liquidation Mode	Displays the liquidation mode of BC.
Beneficiary Details	Displays the beneficiary details.
Beneficiary Name	Displays the beneficiary's name.
Beneficiary Account	Displays the beneficiary account number.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1.
Credit Amount	Displays the credit amount.
Beneficiary Address 1 and **Beneficiary Address 2**	Displays the address of the beneficiary.
Identification Type	Displays the identification type of the beneficiary.
Identification Number	Displays the identification number of the beneficiary.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.1.5.2 BC Revalidation

The Teller can use the **BC Operations** screen to revalidate an instrument that is in expired status.

When a customer requests for revalidation of an instrument that is in expired status, Teller can validate the instrument details and initiate revalidation of BC. The system will allow for revalidation only if:


- Revalidation is allowed at the Instrument type level
- The instrument is not liquidated, canceled, or refunded
- The instrument is issued, revalidated, or duplicate issued but not liquidated/refunded/canceled
- Rule based authorization is not supported for revalidation

To revalidate an instrument:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-9 BC Operations - Revalidate



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-9 BC Operations (Revalidate) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-9 (Cont.) BC Operations (Revalidate) - Field Description

Field	Description
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Revalidate** from the drop-down list.
Revalidation Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Revalidation Date	Select the revalidation date. **Note** By default, the system date is displayed as the revalidation date.
New Expiry Date	Displays the new expiry date based on the specified revalidation date.
Mode of Charge	Select the mode of charge from the drop-down values (**Account** or **Cash**).
Charge Account	Specify the charge account number. The following conditions apply based on the value selected for Mode of Charge: • If the **Mode of Charge** is selected as **Account**, the system will default the **Drawer Account**. • If Mode of Charge is selected as **Other Account**, the user needs to manually capture another account number for collection of charges. This account needs to belong to the same currency as the Drawer Account Currency.
Narrative	Displays the default narrative as **BC Revalidation**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View BC Details** data segment to view the additional details of the BC.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification

Copyright © 2021, 2025, Oracle and/or its affiliates.

from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. The transaction accounting is not applicable for the transaction. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

8.1.5.3 BC Duplicate Issue

The Teller can use the **BC Operations** screen to issue the instrument if the customer or banker lost the instrument or if the instrument is damaged.

In case of a request raised by the customer, additional charges will be deducted while issuing again. The system will allow for duplicate issue only if:


- The duplicate issue is allowed at the instrument type level
- The instrument is not liquidated, canceled, or refunded
- The instrument is issued or revalidated but not liquidated/refunded/canceled
- Rule based authorization is not supported for duplicate issue

To issue a duplicate instrument:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-10 BC Operations - Duplicate Issue



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-10 BC Operations (Duplicate Issue) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-10 (Cont.) BC Operations (Duplicate Issue) - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Duplicate Issue** from the drop-down list.
Duplicate Issue Details	Specify the details under this segment.
Duplicate Issue Date	By default, the current system date is displayed as a duplicate issue date, and it can be modified.
Duplicate BC No	Specify the duplicate banker's cheque number.
Duplicate MICR No	Specify the duplicate MICR number.
Requested By	Select from the drop-down values (**Customer** or **Bank**).
Mode of Charge	Select the mode of charge from the drop-down values (**Account** or **Cash**).
Charge Account	Specify the charge account number. The following conditions apply based on the value selected for Mode of Charge: • If the **Mode of Charge** is selected as **Account**, the system will default the **Drawer Account**. • If Mode of Charge is selected as **Other Account**, the user needs to manually capture another account number for collection of charges. This account needs to belong to the same currency as the Drawer Account Currency.
Narrative	Displays the default narrative as **BC Duplication**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View BC Details** data segment to view the additional details of the BC.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

8.1.5.4 BC Payment by Account

The Teller can use the **BC Operations** screen to make payment against a BC.

The BC payment is credited to the beneficiary customer account when the operation mode is **Account**.


Copyright © 2021, 2025, Oracle and/or its affiliates.

To make payment against a BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-11 BC Operations - Payment by Account



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-11 BC Operations (Payment by Account) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Payment Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-11 (Cont.) BC Operations (Payment by Account) - Field Description

Field	Description
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **BC Payment by Account**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View BC Details** data segment to view the additional details of the BC.

> **Note**
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

If the payment transaction needs to be reversed then the same has to be invoked from SJ log.

8.1.5.5 BC Payment by Cash

The Teller can use the **BC Operations** screen to make payment against a BC.


The BC payment is made by cash to the beneficiary when the operation mode is **Cash**.

To make payment against a BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-12 BC Operations - Payment by Cash



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-12 BC Operations (Payment by Cash) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.
Payment Details	Specify the details under this segment.
Transaction Amount	Specify the transaction currency and transaction amount.
Beneficiary Name	Specify the beneficiary name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **BC Payment by Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click on the **View BC Details** data segment to view the additional details of the BC.

   Note

   This data segment is non-editable.

6. Click **Submit**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

If the payment transaction needs to be reversed then the same has to be invoked from EJ log.

8.1.5.6 BC Payment by GL

The Teller can use the **BC Operations** screen to make payment against a BC.


The BC payment is credited to the GL account when the operation mode is **GL**.

To make payment against a BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-13 BC Operations - Payment by GL



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-13 BC Operations (Payment by GL) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Payment Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Currency	Displays the currency of the specified GL account.
GL Branch	Displays the branch code of the specified GL account.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **BC Payment by GL**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View BC Details** data segment to view the additional details of the BC.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

If the payment transaction needs to be reversed then the same has to be invoked from SJ log.

8.1.5.7 BC Refund by Account

The Teller can use the **BC Operations** screen to refund the amount against a BC.


The BC refund amount is credited to the beneficiary customer account when the operation mode is **Account**.

To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-14 BC Operations - Refund by Account



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-14 BC Operations (Refund by Account) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Refund Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as `BC Refund by Account`, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View BC Details** data segment to view the additional details of the BC.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

8.1.5.8 BC Refund by Cash

The Teller can use the **BC Operations** screen to refund the amount against a BC.


The BC refund is made by cash to the beneficiary when the operation mode is **Cash**.

To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-15 BC Operations - Refund by Cash



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-15 BC Operations (Refund by Cash) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.
Refund Details	Specify the details under this segment.
Transaction Amount	Specify the transaction currency and transaction amount.
Beneficiary Name	Specify the beneficiary name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the account amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **BC Refund by Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click on the **View BC Details** data segment to view the additional details of the BC.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> This data segment is non-editable.

6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

8.1.5.9 BC Refund by GL

The Teller can use the **BC Operations** screen to refund the amount against a BC.


The BC payment is credited to the GL account when the operation mode is **GL**.

To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-16 BC Operations - Refund by GL



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-16 BC Operations (Refund by GL) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Refund Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Currency	Displays the currency of the specified GL account.
GL Branch	Displays the branch code of the specified GL account.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **BC Refund by GL**, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View BC Details** data segment to view the additional details of the BC.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

8.1.5.10 Cancel BC by Account

The Teller can use the **BC Operations** screen to cancel a BC.


The BC cancellation amount is credited to a customer account when the operation mode is **Account**.

To cancel a BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Figure 8-17 BC Operations - Cancel by Account



Copyright © 2021, 2025, Oracle and/or its affiliates.

2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-17 BC Operations (Cancel by Account) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Cancel Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-17 (Cont.) BC Operations (Cancel by Account) - Field Description

Field	Description
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **BC Cancel by Account**, and it can be modified.

3. Click on the **View BC Details** data segment to view the additional details of the BC.

> **Note**
>
> This data segment is non-editable.

4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

8.1.5.11 Cancel BC by Cash

The Teller can use the **BC Operations** screen to cancel a BC.

The BC cancellation amount is paid by cash to the beneficiary when the operation mode is **Cash**.


To cancel a BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-18 BC Operations - Cancel by Cash



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-18 BC Operations (Cancel by Cash) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.
Cancel Details	Specify the details under this segment.
Transaction Amount	Specify the transaction currency and transaction amount.
Beneficiary Name	Specify the beneficiary name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-18 (Cont.) BC Operations (Cancel by Cash) - Field Description

Field	Description
Total Charge Amount	Displays the account amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **BC Cancel by Cash**, and it can be modified.

3. Click on the **View BC Details** data segment to view the additional details of the BC.

> **Note**
>
> This data segment is non-editable.

4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

8.1.5.12 Cancel BC by GL

The Teller can use the **BC Operations** screen to cancel a BC.

The BC cancellation amount is credited to the GL account when the operation mode is **GL**.


To cancel a BC:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **BC Operations** or specify **BC Operations** in the search icon bar and select the screen.

   The **BC Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-19 BC Operations - Cancel by GL



2. On the **BC Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-19 BC Operations (Cancel by GL) - Field Description

Field	Description
BC Number	Specify the BC number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
BC Currency	Specify BC Currency to query instrument details.
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Cancel Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Currency	Displays the currency of the specified GL account.
GL Branch	Displays the branch code of the specified GL account.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-19 (Cont.) BC Operations (Cancel by GL) - Field Description

Field	Description
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **BC Cancel by GL**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View BC Details** data segment to view the additional details of the BC.

> **Note**
> This data segment is non-editable.

5. Click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting hand off. In case of reject notification from the Oracle Banking Payments, the system will discard the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.1.6 Multi BC Issuance

The Teller can use the **Multi BC Issuance** screen to issue banker's cheques against multiple beneficiaries.

This topic contains the following subtopics:

- Multi BC Issuance Against Account
  The Teller can use the **Multi BC Issuance** screen to issue BCs against multiple beneficiaries for a single remitter account.
- Multi BC Issuance Against Cash
  The Teller can use the **Multi BC Issuance** screen to issue BC against Cash GL for walk-in customers.

8.1.6.1 Multi BC Issuance Against Account

The Teller can use the **Multi BC Issuance** screen to issue BCs against multiple beneficiaries for a single remitter account.


To issue BC against multiple beneficiaries:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Multi BC Issuance** or specify **Multi BC Issuance** in the search icon bar and select the screen.

   The **Multi BC Issuance Account** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-20 Multi BC Issuance - Account



2. On the **Multi BC Issuance Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-20 Multi BC Issuance Account - Field Description

Field	Description
New	Click **New** to generate a batch reference number.
Batch Reference	Displays the auto-generated batch reference number.
BC Currency	Select the BC currency from the LOV.
Issue Mode	Select the issue mode as **Account** from the drop-down values.
Drawer Account	Specify the remitter account number. When you press the **Tab** key, the **Account Description**, **Remitter Name**, and **Address** of the remitter account will be populated.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-20 (Cont.) Multi BC Issuance Account - Field Description

Field	Description
Drawer Name	Displays the name of the specified remitter account number.
Address Line 1 to **Address Line 4**	Displays the address of the specified remitter account number.
Cheque Number	Specify the cheque number. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Specify the issue date of the cheque.
Total BC Amount	Displays the total sum of the multiple BC amount inputs, which is computed by the system.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Charge Account	Specify the charge account number. **Note** By default, the drawer account number will be displayed as a charge account, and it can be modified.
Total (Account Amount)	Displays the total amount available in the specified charge account.
Entry Details	Specify the fields.
Payee Name	Specify the name of the payee.
Payable Bank Code	Select the payable bank code from the list of values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-20 (Cont.) Multi BC Issuance Account - Field Description

Field	Description
Payable Bank Name	Displays the bank name of the specified payable bank code.
Payable Branch Code	Select the payable branch code from the list of values.
Payable Branch Name	Displays the bank name of the specified payable branch code.
BC Amount	Specify the BC amount.
MICR Number	Specify the MICR number.
BC Number	Specify the BC number.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Narrative	Displays the default narrative as **Multi BC Issuance**, and it can be modified.
Add Entry	After filling the necessary fields, click **Add Entry** to add a new entry.
Reset	Click **Reset** to reset the added entries.

3. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system creates an individual BC transaction and hand-off individual BC issue requests to Oracle Banking Payments system. Once the individual BC transaction is created in Oracle Banking Payments, the system will hand off for the accounting to FLEXCUBE Universal Banking by debiting Customer Account/Cash GL for the individual BC amounts and crediting the intermediary bridge GL. But the charge debit will be a consolidated entry. In case of any rejection from Oracle Banking Payments, the system will not consider the transaction for accounting to FLEXCUBE Universal Banking during console entry.

8.1.6.2 Multi BC Issuance Against Cash

The Teller can use the **Multi BC Issuance** screen to issue BC against Cash GL for walk-in customers.


To issue BC against cash:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Multi BC Issuance** or specify **Multi BC Issuance** in the search icon bar and select the screen.

   The **Multi BC Issuance Cash** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-21 Multi BC Issuance Cash



2. On the **Multi BC Issuance Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-21 Multi BC Issuance Cash - Field Description

Field	Description
New	Click **New** to generate a batch reference number.
Batch Reference	Displays the auto-generated batch reference number.
BC Currency	Select the BC currency from the list of values.
Issue Mode	Select the issue mode as **Cash** from the drop-down values.
Transaction Currency	Select the transaction currency from the list of values.
Drawer Name	Specify the name of the drawer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-21 (Cont.) Multi BC Issuance Cash - Field Description

Field	Description
Address Line 1 to **Address Line 4**	Specify the address of the drawer.
Identification Type	Select the identification type from the drop-down values.
Payee Identification Number	Specify the identification number of the Payee.
Total BC Amount	Displays the total sum of the multiple BC amount inputs, which is computed by the system.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Total (Account Amount)	Displays the total amount available in the specified charge account.
Entry Details	Specify the fields.
Payee Name	Specify the payee name.
Payable Bank Code	Select the payable bank code from the list of values.
Payable Bank Name	Displays the bank name of the specified payable bank code.
Payable Branch Code	Select the payable branch code from the list of values.
Payable Branch Name	Displays the bank name of the specified payable branch code.
BC Amount	Specify the BC amount and currency.
MICR Number	Specify the MICR number.
BC Number	Specify the BC number.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Narrative	Displays the default narrative as **Multi BC Issuance**, and it can be modified.
Add Entry	After filling the necessary fields, click **Add Entry** to add a new entry.
Reset	Click **Reset** to reset the added entries.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system creates an individual BC transaction and hand-off individual BC issue requests to Oracle Banking Payments system. Once the individual BC transaction is created in Oracle Banking Payments, the system will hand off for the accounting to FLEXCUBE Universal Banking by debiting Customer Account/Cash GL for the individual BC amounts and crediting the intermediary bridge GL. But the charge debit will be a consolidated entry. In case of any rejection from Oracle Banking Payments, the system will not consider the transaction for accounting to FLEXCUBE Universal Banking during console entry.

8.2 Demand Drafts

The screens related to the Demand Drafts (DD) can be used to issue DD, perform payment or cancellation of the issued DD, and perform further operations on the issued DD.

This topic contains the following subtopics:

- DD Issue Against Account
  The Teller can use the **DD Issue Against Account** screen to issue a DD against the CASA of a customer.
- DD Issue Against Walk-in
  The Teller can use the **DD Issue Against Walk-in** screen to issue a DD by cash to the walk-in customers.
- DD Issue Against GL
  The Teller can use the **DD Issue Against GL** screen to issue a DD against a GL account.
- DD Print and Reprint
  The Teller can use the **DD Print-Reprint** screen to print a DD. It is also used to reprint the DD if it is not properly printed or to issue duplicate instruments.
- DD Operations
  The Teller can use the **DD Operations** screen to handle the life cycle processing of DD that is already issued.

8.2.1 DD Issue Against Account

The Teller can use the **DD Issue Against Account** screen to issue a DD against the CASA of a customer.


To issue a DD against the savings account:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Issue - Account** or specify **DD Issue - Account** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **DD Issue Against Account** screen is displayed.

Figure 8-22 DD Issue Against Account



2. On the **DD Issue Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-22 DD Issue Against Account - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Bank Name	Specify the name of the issuing bank.
Issuing Branch Code	Displays the logged-in branch code.
Branch Name	Displays the branch description of issuing branch.
Payable Bank Code	Select the payable bank code. The list of values contains the bank codes maintained using the **External Bank Code Maintenance** screen. **Note** • To remit funds within the same bank, select the logged-in bank code as payable bank code. To remit funds across banks, select the necessary bank code as payable bank code. The fields **Payable Branch Code** and **Payable Branch Name** will be enabled after you specify the **Payable Bank Code**. • If the Instrument Currency is FCY and the Payable Bank code selected is External Bank, then the Instrument Type will be **Demand Draft-FCY** (DF).
Payable Bank Name	Displays the name of the selected bank code.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 8-22 (Cont.) DD Issue Against Account - Field Description

Field	Description
Payable Branch Code	Select the branch code of the payable bank. The list of values contains the corresponding branch codes maintained using the **Bank Code Maintenance** screen.
Payable Branch Name	Displays the branch name of the selected branch code.
DD Amount	Specify the DD currency and DD amount.
DD Date	Specify the date that needs to be mentioned in the DD.
MICR No	Displays the MICR number.
DD No	Specify the instrument number and validate. If not specified, the system generates the DD number based on the maintenance setup.
Payee Details	Specify the fields.
Payee Name	Specify the payee name on which the DD is drawn.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Narrative	Displays the narrative as **DD Issuance Account** and it can be modified.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Figure 8-23 Funding Details



4. On the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-23 Funding Details - Field Description

Field	Description
Drawer Account	Specify the account number of the customer who has requested the DD.
Drawer Name	Displays the name of the specified drawer account number.
Cheque Number	Specify the cheque number of the drawer account. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Specify the date as mentioned in the cheque.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Account Amount	Displays the account amount in account currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Mode of Charge	Select the mode of charge from the following drop-down values (**Account** or **Other Account**).
Charge Account	Specify the charge account number. The following conditions apply based on the value selected for Mode of Charge: • If the **Mode of Charge** is selected as **Account**, the system will default the **Drawer Account**. • If Mode of Charge is selected as **Other Account**, the user needs to manually capture another account number for collection of charges. This account needs to belong to the same currency as the Drawer Account Currency.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-23 (Cont.) Funding Details - Field Description

Field	Description
Total Charges	Displays the total charges applicable for the DD issuance. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

   Note

   The transaction is moved to authorization in case of any warning raised when the transaction saves.

   When you submit, the transaction details are handed off to the Oracle Banking Payments system for instruments processing with external system status as **Pending**.

   After the transaction is processed and responded from Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

8.2.2 DD Issue Against Walk-in

The Teller can use the **DD Issue Against Walk-in** screen to issue a DD by cash to the walk-in customers.


To issue a DD to a walk-in customer:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Issue - Walk-in** or specify **DD Issue - Walk-in** in the search icon bar and select the screen.

   The **DD Issue Against Walk-in** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-24 DD Issue Against Walk-in



2. On the **DD Issue Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-24 DD Issue Against Walk-in - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Bank Name	Specify the name of the issuing bank.
Issuing Branch Code	Displays the logged-in branch code.
Branch Name	Displays the branch description of issuing branch.
Payable Bank Code	Select the payable bank code. The list of values contains the bank codes maintained using the **External Bank Code Maintenance** screen. **Note** • To remit funds within the same bank, select the logged-in bank code as payable bank code. To remit funds across banks, select the necessary bank code as payable bank code. The fields **Payable Branch Code** and **Payable Branch Name** will be enabled after you specify the **Payable Bank Code**. • If the Instrument Currency is FCY and the Payable Bank code selected is External Bank, then the Instrument Type will be **Demand Draft-FCY** (DF).
Payable Bank Name	Displays the name of the selected bank code.
Payable Branch Code	Select the branch code of the payable bank. The list of values contains the corresponding branch codes maintained using the **Bank Code Maintenance** screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 8-24 (Cont.) DD Issue Against Walk-in - Field Description

Field	Description
Payable Branch Name	Displays the branch name of the selected branch code.
DD Amount	Specify the DD currency and DD amount.
DD Date	Specify the date that needs to be mentioned in the DD.
MICR No	Displays the serial number.
DD No	Specify the instrument number and validate. **Note** If not specified, the system generates the DD number based on the maintenance setup.
Payee Details	Specify the fields.
Payee Name	Specify the payee name on which the DD is drawn.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Narrative	Displays the narrative as **DD Issuance against Walk-in**, and it can be modified.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Figure 8-25 Funding Details



4. On the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

Note

The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-25 Funding Details - Field Description

Field	Description
Transaction Amount	Specify the transaction currency, the currency in which the walk-in customer deposit the cash.
Drawer Name	Specify the name of the drawer.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Identification Type	Select the identification type of the payee from the drop-down list.
Identification Number	Specify the identification details of the payee.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charges applicable for the DD issuance. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.

5. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
6. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
7. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for instruments processing with external system status as **Pending**.

After the transaction is processed and responded from Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.2.3 DD Issue Against GL


The Teller can use the **DD Issue Against GL** screen to issue a DD against a GL account.

To issue a DD against a GL:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Issue - GL** or specify **DD Issue - GL** in the search icon bar and select the screen.

   The **DD Issue Against GL** screen is displayed.

Figure 8-26 DD Issue Against GL



2. On the **DD Issue Against GL** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-26 DD Issue Against GL - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Bank Name	Specify the name of the issuing bank.
Issuing Branch Code	Displays the logged-in branch code.
Branch Name	Displays the branch description of issuing branch.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-26 (Cont.) DD Issue Against GL - Field Description

Field	Description
Payable Bank Code	Select the payable bank code. The list of values contains the bank codes maintained using the **External Bank Code Maintenance** screen. **Note** • To remit funds within the same bank, select the logged-in bank code as payable bank code. To remit funds across banks, select the necessary bank code as payable bank code. The fields **Payable Branch Code** and **Payable Branch Name** will be enabled after you specify the **Payable Bank Code**. • If the Instrument Currency is FCY and the Payable Bank code selected is External Bank, then the Instrument Type will be **Demand Draft-FCY** (DF).
Payable Bank Name	Displays the name of the selected bank code.
Payable Branch Code	Select the branch code of the payable bank. The list of values contains the corresponding branch codes maintained using the **Bank Code Maintenance** screen.
Payable Branch Name	Displays the branch name of the selected branch code.
DD Amount	Specify the DD currency and DD amount.
DD Date	Specify the date that needs to be mentioned in the DD.
MICR No	Displays the serial number.
DD No	Specify the instrument number and validate. **Note** If not specified, the system generates the DD number based on the maintenance setup.
Payee Details	Specify the fields.
Payee Name	Specify the payee name on which the DD is drawn.
Address Line 1 to **Address Line 4**	Specify the address of the payee.
Narrative	Displays the narrative as **DD Issuance Against GL**, and it can be modified.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-27 Funding Details



4. On the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-27 Funding Details - Field Description

Field	Description
GL Account	Select the account number of the GL against which the BC is issued from the LOV.
GL Description	Displays a brief description of the general ledger.
Drawer Name	Specify the name of the drawer.
Identification Type	Select the identification type of the payee from the drop-down list.
Identification Number	Specify the identification number of the payee.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

When you submit, the transaction details are handed off to the Oracle Banking Payments system for instruments processing with external system status as **Pending**.

After the transaction is processed and responded from Oracle Banking Payments with appropriate status, the Teller selects the transaction from **Journal Log** and completes the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.2.4 DD Print and Reprint

The Teller can use the **DD Print-Reprint** screen to print a DD. It is also used to reprint the DD if it is not properly printed or to issue duplicate instruments.


The system maintains track of reprints so that the bank officials or auditors can determine the reasons and validity of multiple instrument printing.

To print or reprint a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Print-Reprint** or specify **DD Print-Reprint** in the search icon bar and select the screen.

   The **DD Print-Reprint** screen is displayed.

Figure 8-28 DD Print-Reprint



2. On the **DD Print-Reprint** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-28 DD Print-Reprint - Field Description

Field	Description
Demand Draft No	Specify the DD number of the instrument that you need to print or reprint.
Issuing Bank Code	Specify the code of the issuing bank.
Instrument Type	Select the instrument type from the drop-down list. • **Demand Draft** • **Demand Draft-FCY**
Issue Branch Code	Select the branch code where the instrument is issued from the LOV.
Instrument Currency	Specify the instrument currency.
Print Type	Select the type **Print** or **Reprint** from the drop-down list.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-28 (Cont.) DD Print-Reprint - Field Description

Field	Description
Query	Click **Query** to fetch details of DD print or reprint.
Issuing Branch Code	Displays the logged-in branch code.
DD Date	Displays the date mentioned in the DD.
DD Amount	Displays the DD currency and the DD amount.
Drawer Name	Displays the name of the drawer.
DD Status	Displays the status of the DD.
Beneficiary Details	Specify the fields.
Beneficiary Name	Displays the beneficiary's name.
Identification Details	Displays the identification details of the beneficiary.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Reprint Count	Specify the count of the current reprint operation. **Note** This field is applicable only for the reprint option.
Narrative	Displays the default narrative as **Print/Reprint**, and it can be modified.

3. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

8.2.5 DD Operations

The Teller can use the **DD Operations** screen to handle the life cycle processing of DD that is already issued.

This topic contains the following subtopics:

- DD Inquiry
  The Teller can use the **DD Operations** screen to inquire about the details of DD.
- DD Revalidation
  The Teller can use the **DD Operations** screen to revalidate an instrument that is in expired status.
- DD Duplicate Issue
  The Teller can use the **DD Operations** screen to issue the instrument if the customer or banker lost the instrument or if the instrument is damaged.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- DD Payment by Account
  The Teller can use the **DD Operations** screen to make payment against a DD. Payment of Foreign Currency Demand Drafts (Instrument Type - DF) is not allowed.
- DD Payment by Cash
  The Teller can use the **DD Operations** screen to make payment against a DD. Payment of Foreign Currency Demand Drafts (Instrument Type - DF) is not allowed.
- DD Payment by GL
  The Teller can use the **DD Operations** screen to make payment against a DD. Payment of Foreign Currency Demand Drafts (Instrument Type - DF) is not allowed.
- DD Refund by Account
  The Teller can use the **DD Operations** screen to refund the amount against a DD.
- DD Refund by Cash
  The Teller can use the **DD Operations** screen to refund the amount against a DD.
- DD Refund by GL
  The Teller can use the **DD Operations** screen to refund the amount against a DD.
- Cancel DD by Account
  The Teller can use the **DD Operations** screen to cancel a DD.
- Cancel DD by Cash
  The Teller can use the **DD Operations** screen to cancel a DD.
- Cancel DD by GL
  The Teller can use the **DD Operations** screen to cancel a DD.

8.2.5.1 DD Inquiry


The Teller can use the **DD Operations** screen to inquire about the details of DD.

To inquire the details of DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-29 DD Operations - Inquiry



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-29 DD Operations (Inquiry) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV. After you specify the **Issue Branch Code** and **Demand Draft No**, press the **Tab** key. The system will make a service call to Oracle Banking Payments and fetch the demand draft details.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Inquiry** from the drop-down list.
Query	Click this button to fetch instrument details.
Demand Draft Details	Displays the details of DD under this segment.
Issue Branch	Displays the logged-in branch code.
Payable Branch	Displays the payable branch for the DD.
Payable Bank Code	Displays the payable bank code.
Demand Draft Amount	Displays the DD currency and the DD amount.
MICR No	Displays the MICR number.
Issue Date	Displays the issue date mentioned in the DD.
Issue Mode	Displays the issue mode of the DD.
Demand Draft Status	Displays the status of the DD.
Narrative	Displays the default narrative as **Demand Draft Inquiry**, and it can be modified.
Revalidation Date	Displays the date of DD revalidation.
Duplicate Issue Date	Displays the duplicate issue date of DD.
Liquidation Date	Displays the liquidation date of DD.
Liquidation Mode	Displays the liquidation mode of DD.
Beneficiary Details	Displays the details.
Beneficiary Name	Displays the beneficiary's name.
Beneficiary Account	Displays the beneficiary account number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-29 (Cont.) DD Operations (Inquiry) - Field Description

Field	Description
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1.
Credit Amount	Displays the credit amount.
Beneficiary Address 1 and **Beneficiary Address 2**	Displays the address of the beneficiary.
Identification Type	Displays the identification type of the beneficiary.
Identification Number	Displays the identification number of the beneficiary.

8.2.5.2 DD Revalidation

The Teller can use the **DD Operations** screen to revalidate an instrument that is in expired status.

When a customer requests for revalidation of an instrument that is in expired status, Teller can validate the instrument details and initiate revalidation of DD. The system will allow for revalidation only if:

- Revalidation is allowed at the Instrument type level
- The instrument is not liquidated, canceled, or refunded
- The instrument is issued, revalidated, or duplicate issued but not liquidated/refunded/canceled
- Rule based authorization is not supported for revalidation


To revalidate a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-30 DD Operations - Revalidate



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-30 DD Operations (Revalidate) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Revalidate** from the drop-down list.
Revalidation Date	Select the revalidation date. **Note** By default, the system date is displayed as a revalidation date.
New Expiry Date	Displays the new expiry date based on the specified revalidation date.
Mode of Charge	Select the mode of charge from the drop-down values (**Account** or **Cash**).

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-30 (Cont.) DD Operations (Revalidate) - Field Description

Field	Description
Charge Account	Specify the charge account number. The following conditions apply based on the value selected for Mode of Charge: • If the **Mode of Charge** is selected as **Account**, the system will default the **Drawer Account**. • If Mode of Charge is selected as **Other Account**, the user needs to manually capture another account number for collection of charges. This account needs to belong to the same currency as the Drawer Account Currency.
Narrative	Displays the default narrative as **Demand Draft Revalidation**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View Demand Draft Details** data segment to view the additional details of the DD.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

8.2.5.3 DD Duplicate Issue

The Teller can use the **DD Operations** screen to issue the instrument if the customer or banker lost the instrument or if the instrument is damaged.

In case of a request raised by the customer, additional charges will be deducted while issuing again. The system will allow for duplicate issues only if:

- The duplicate issue is allowed at the instrument type level
- The instrument is not liquidated, canceled, or refunded
- The instrument is issued or revalidated but not liquidated/refunded/canceled
- Rule based authorization is not supported for duplicate issue


Copyright © 2021, 2025, Oracle and/or its affiliates.

To issue a duplicate DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-31 DD Operations - Duplicate Issue



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-31 DD Operations (Duplicate Issue) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Duplicate Issue** from the drop-down list.
Duplicate Issue Details	Specify the details under this segment.
Duplicate Issue Date	By default, the current system date is displayed as a duplicate issue date, and it can be modified.
Duplicate Demand Draft Number	Specify the duplicate demand draft number.
Duplicate MICR No	Specify the duplicate MICR number.
Requested By	Select from the drop-down values (**Customer** or **Bank**).

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-31 (Cont.) DD Operations (Duplicate Issue) - Field Description

Field	Description
Mode of Charge	Select the mode of charge from the drop-down values (**Account** or **Cash**).
Charge Account	Specify the charge account number. The following conditions apply based on the value selected for Mode of Charge: • If the **Mode of Charge** is selected as **Account**, the system will default the **Drawer Account**. • If Mode of Charge is selected as **Other Account**, the user needs to manually capture another account number for collection of charges. This account needs to belong to the same currency as the Drawer Account Currency.
Narrative	Displays the default narrative as **Demand Draft Duplication**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View Demand Draft Details** data segment to view the additional details of the DD.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

8.2.5.4 DD Payment by Account

The Teller can use the **DD Operations** screen to make payment against a DD. Payment of Foreign Currency Demand Drafts (Instrument Type - DF) is not allowed.

The DD payment is credited to the beneficiary customer account when the operation mode is **Account**.


To make payment against a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-32 DD Operations - Payment by Account



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-32 DD Operations (Payment by Account) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Payment Details	Specify the details under this segment.
Beneficiary Account	Specify the beneficiary account number.
Beneficiary Name	Specify the beneficiary name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-32 (Cont.) DD Operations (Payment by Account) - Field Description

Field	Description
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **DD Operations**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
> This data segment is non-editable.

5. Click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

If the payment transaction needs to be reversed then the same has to be invoked from SJ log.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.2.5.5 DD Payment by Cash

The Teller can use the **DD Operations** screen to make payment against a DD. Payment of Foreign Currency Demand Drafts (Instrument Type - DF) is not allowed.


The DD payment is made by cash to the beneficiary when the operation mode is **Cash**.

To make payment against a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-33 DD Operations - Payment by Cash



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-33 DD Operations (Payment by Cash) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.
Payment Details	Specify the details under this segment.
Transaction Amount	Specify the transaction currency and transaction amount.
Beneficiary Name	Specify the beneficiary name.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-33 (Cont.) DD Operations (Payment by Cash) - Field Description

Field	Description
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Demand Draft Payment by Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
> This data segment is non-editable.

6. Click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification

Copyright © 2021, 2025, Oracle and/or its affiliates.

from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

If the payment transaction needs to be reversed then the same has to be invoked from EJ log.

8.2.5.6 DD Payment by GL

The Teller can use the **DD Operations** screen to make payment against a DD. Payment of Foreign Currency Demand Drafts (Instrument Type - DF) is not allowed.


The DD payment is credited to the GL account when the operation mode is **GL**.

To make payment against a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-34 DD Operations - Payment by GL



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-34 DD Operations (Payment by GL) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-34 (Cont.) DD Operations (Payment by GL) - Field Description

Field	Description
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Payment Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Currency	Displays the currency of the specified GL account.
GL Branch	Displays the branch code of the specified GL account.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **DD Operations**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

If the payment transaction needs to be reversed then the same has to be invoked from SJ log.

8.2.5.7 DD Refund by Account

The Teller can use the **DD Operations** screen to refund the amount against a DD.


The DD refund amount is credited to the beneficiary customer account when the operation mode is **Account**.

To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-35 DD Operations - Refund by Account



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-35 DD Operations (Refund by Account) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Refund Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-35 (Cont.) DD Operations (Refund by Account) - Field Description

Field	Description
Narrative	Displays the default narrative as **Demand Draft Refund by Account**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

8.2.5.8 DD Refund by Cash

The Teller can use the **DD Operations** screen to refund the amount against a DD.

The DD refund is made by cash to the beneficiary when the operation mode is **Cash**.


To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-36 DD Operations - Refund by Cash



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-36 DD Operations (Refund by Cash) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.
Refund Details	Specify the details under this segment.
Transaction Amount	Specify the transaction currency and transaction amount.
Beneficiary Name	Specify the beneficiary's name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-36 (Cont.) DD Operations (Refund by Cash) - Field Description

Field	Description
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the account amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **Demand Draft Refund by Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
> This data segment is non-editable.

6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for

Copyright © 2021, 2025, Oracle and/or its affiliates.

the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

8.2.5.9 DD Refund by GL

The Teller can use the **DD Operations** screen to refund the amount against a DD.


The DD payment is credited to the GL account when the operation mode is **GL**.

To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-37 DD Operations - Refund by GL



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-37 DD Operations (Refund by GL) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Refund** from the drop-down list.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-37 (Cont.) DD Operations (Refund by GL) - Field Description

Field	Description
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Refund Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Currency	Specify the currency of the specified GL account.
GL Branch	Select the branch code from the list of values.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Demand Draft Refund by GL**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
> This data segment is non-editable.

5. Click **Submit**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

8.2.5.10 Cancel DD by Account

The Teller can use the **DD Operations** screen to cancel a DD.


The DD cancellation amount is credited to a customer account when the operation mode is **Account**.

To cancel a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-38 DD Operations - Cancel by Account



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-38 DD Operations (Cancel by Account) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Cancel Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-38 (Cont.) DD Operations (Cancel by Account) - Field Description

Field	Description
Narrative	Displays the default narrative as **DD Cancel by Account**, and it can be modified.

3. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
>
> This data segment is non-editable.

4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

8.2.5.11 Cancel DD by Cash

The Teller can use the **DD Operations** screen to cancel a DD.

The DD cancellation amount is paid by cash to the beneficiary when the operation mode is **Cash**.


To cancel a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-39 DD Operations - Cancel by Cash



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-39 DD Operations (Cancel by Cash) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.
Cancel Details	Specify the details under this segment.
Transaction Amount	Specify the transaction currency and transaction amount.
Beneficiary Name	Specify the beneficiary's name.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-39 (Cont.) DD Operations (Cancel by Cash) - Field Description

Field	Description
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the account amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as **DD Cancel by Cash**, and it can be modified.

3. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
> This data segment is non-editable.

4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.2.5.12 Cancel DD by GL

The Teller can use the **DD Operations** screen to cancel a DD.


The DD cancellation amount is credited to the GL account when the operation mode is **GL**.

To cancel a DD:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **DD Operations** or specify **DD Operations** in the search icon bar and select the screen.

   The **DD Operations** screen is displayed.

Figure 8-40 DD Operations - Cancel by GL



2. On the **DD Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-40 DD Operations (Cancel by GL) - Field Description

Field	Description
Demand Draft Number	Specify the DD number of the instrument.
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch	Select the branch code where the instrument is issued from the LOV.
DD Currency	Specify DD Currency to query instrument details.
Instrument Type	Select the instrument type from the drop-down list. The option are: • **Demand Draft** • **Demand Draft-FCY**
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Refund Details	Specify the details under this segment.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-40 (Cont.) DD Operations (Cancel by GL) - Field Description

Field	Description
GL Account	Specify the GL account number.
GL Currency	Displays the currency of the specified GL account.
GL Branch	Displays the branch code of the specified GL account.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as Y.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as Y.
Narrative	Displays the default narrative as `DD Cancel by GL`, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **View DD Details** data segment to view the additional details of the DD.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the details to the payments product processor (Oracle Banking Payments) for processing. When you get a success notification from Oracle Banking Payments, the system will update the transaction status as **Success** and mark for charges accounting handoff. The transaction accounting is not applicable for the transaction. In case of reject notification from Oracle Banking Payments, the system will discard the transaction.

8.3 Cash Remittance

The screens related to the Cash Remittance can be used to issue remittance, perform payment or cancellation of the issued remittance, and perform further operations on the issued remittance.

This topic contains the following subtopics:

- Cash Remittance Issue
  The **Cash Remittance Issue** screen is used to remit funds across branches of the same bank and across banks.
- Cash Remittance Operations
  The Teller can use the **Cash Remittance Operations** screen to handle the life cycle processing of cash remittance that is already completed.
- Inward Remittance Registration
  The **Inward Remittance Registration** screen is used to register an inward remittance and create a remittance instrument.

8.3.1 Cash Remittance Issue

The **Cash Remittance Issue** screen is used to remit funds across branches of the same bank and across banks.

This topic contains the following subtopics:

- Cash Remittance Issue Against Account
  The **Cash Remittance Issue Against Account** screen is used to remit funds across branches of the same bank and across banks. Reversal of cash remittance issuance is supported through SJ.
- Cash Remittance Issue Against Cash
  The **Cash Remittance Issue Against Cash** screen is used to remit funds across branches of the same bank and across banks. Reversal of cash remittance issuance is supported through EJ.
- Cash Remittance Issue Against GL
  The **Cash Remittance Issue Against GL** screen is used to remit funds across branches of the same bank and across banks. Reversal of cash remittance issuance is supported through SJ.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.3.1.1 Cash Remittance Issue Against Account

The **Cash Remittance Issue Against Account** screen is used to remit funds across branches of the same bank and across banks. Reversal of cash remittance issuance is supported through SJ.


The cash remittance is performed against the remitter's account when the issuing mode is **Account**.

To perform cash remittance issue against account:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Issue** or specify **Cash Remittance Issue** in the search icon bar and select the screen.

   The **Cash Remittance Issue Against Account** screen is displayed.

Figure 8-41 Cash Remittance Issue Against Account



2. On the **Cash Remittance Issue Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-41 Cash Remittance Issue Against Account - Field Description


Field	Description
Issuing Branch Code	Displays the code of the home branch.
Issuing Branch Name	Displays the name of the issuing branch code.
Payable Bank Code	Select the payable bank code from the list of values. **Note** To remit funds within the same bank, select the logged-in bank code as payable bank code. To remit funds across banks, select the necessary bank code as payable bank code.
Payable Bank Name	Displays the name of the selected bank code.
Payable Branch Code	Select the branch code of the payable bank. The list of values contains the corresponding branches maintained for the payable bank code.
Payable Branch Name	Displays the branch name of the selected branch code.
Remittance Amount	Specify the cash remittance currency and amount, which needs to be transferred.
Remittance Date	Select the date of cash remittance.
Remittance No	Specify the cash remittance number.
Test Key No	Specify the test key number. **Note** This field is applicable only for the inter bank remittances.
Issue Mode	Select the issue mode from the drop-down values (**Account**, **Cash**, or **GL**).
Beneficiary Details	Specify the fields.
Beneficiary Name	Specify the name of the beneficiary.
Beneficiary Account	Specify the account number of the beneficiary.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type.
Identification No	Specify the identification number.
Narrative	Displays the default narrative as **Cash Remittance Issuance**, and it can be modified.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-42 Funding Details



4. In the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-42 Funding Details - Field Description

Field	Description
Remitter Account	Specify the remitter account number.
Remitter Name	Displays the name of the specified remitter account.
Address Line 1 to **Address Line 4**	Displays the address of the specified remitter account.
Cheque Number	Specify the cheque number. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Specify the issue date of the cheque.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-42 (Cont.) Funding Details - Field Description

Field	Description
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Identification Type	Select the identification type.
Identification No	Specify the identification number.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.3.1.2 Cash Remittance Issue Against Cash

The **Cash Remittance Issue Against Cash** screen is used to remit funds across branches of the same bank and across banks. Reversal of cash remittance issuance is supported through EJ.


The cash remittance is performed against the cash from the remitter when the issuing mode is **Cash**.

To perform cash remittance issue against cash:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Issue** or specify **Cash Remittance Issue** in the search icon bar and select the screen.

   The **Cash Remittance Issue Against Cash** screen is displayed.

Figure 8-43 Cash Remittance Issue Against Cash



2. On the **Cash Remittance Issue Against Cash** screen, specify the fields. For more information on fields, refer to Table 8-41.


> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Figure 8-44 Funding Details



4. In the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-43 Funding Details - Field Description

Field	Description
Transaction Amount	Displays the transaction currency and amount. **Note** By default, the currency field will default to local branch currency and it can be modified.
Remitter Name	Specify the name of the remitter.
Address Line 1 to **Address Line 4**	Displays the address of the remitter.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-43 (Cont.) Funding Details - Field Description

Field	Description
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Identification Type	Select the identification type.
Identification Number	Specify the identification number.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
7. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.3.1.3 Cash Remittance Issue Against GL

The **Cash Remittance Issue Against GL** screen is used to remit funds across branches of the same bank and across banks. Reversal of cash remittance issuance is supported through SJ.


The cash remittance is performed against a GL account when the issuing mode is **GL**.

To perform cash remittance issue against GL:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Issue** or specify **Cash Remittance Issue** in the search icon bar and select the screen.

   The **Cash Remittance Issue Against GL** screen is displayed.

Figure 8-45 Cash Remittance Issue Against GL



2. On the **Cash Remittance Issue Against GL** screen, specify the fields. For more information on fields, refer to Table 8-41.


> **Note**
>
> The fields marked as **Required** are mandatory.

3. Click on the **Funding Details** data segment.

   The **Funding Details** data segment is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-46 Funding Details



4. In the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-44 Funding Details - Field Description

Field	Description
GL Account	Specify the GL account number.
GL Description	Displays the description of the specified GL account number.
GL Currency	Select the GL currency from the list of values.
Remitter Name	Specify the name of the remitter.
Address Line 1 to **Address Line 4**	Displays the address of the remitter.
Identification Type	Select the identification type.
Identification Number	Specify the identification number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-44 (Cont.) Funding Details - Field Description

Field	Description
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Account Amount	Displays the GL amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Mode of Charge	Select the mode of charge from the drop-down values.

5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves.

8.3.2 Cash Remittance Operations

The Teller can use the **Cash Remittance Operations** screen to handle the life cycle processing of cash remittance that is already completed.

This topic contains the following subtopics:

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Cash Remittance Inquiry
  The Teller can use the **Cash Remittance Operations** screen to inquire about the details of the issued cash remittance.
- Cash Remittance Payment by Account
  The Teller can use the **Cash Remittance Operations** screen to make payment against a cash remittance. Reversal of cash remittance payment is supported through Electronic Journal/Service Journal.
- Cash Remittance Payment by Cash
  The Teller can use the **Cash Remittance Operations** screen to make payment against a cash remittance. Reversal of cash remittance payment is supported through Electronic Journal/Service Journal.
- Cash Remittance Payment by GL
  The Teller can use the **Cash Remittance Operations** screen to make payment against a cash remittance. Reversal of cash remittance payment is supported through Electronic Journal/Service Journal.
- Cash Remittance Refund by Account
  The Teller can use the **Cash Remittance Operations** screen to refund the amount against a cash remittance.
- Cash Remittance Refund by Cash
  The Teller can use the **Cash Remittance Operations** screen to refund the amount against a cash remittance.
- Cash Remittance Refund by GL
  The Teller can use the **Cash Remittance Operations** screen to refund the amount against a cash remittance.
- Cancel Cash Remittance by Account
  The Teller can use the **Cash Remittance Operations** screen to cancel a cash remittance.
- Cancel Cash Remittance by Cash
  The Teller can use the **Cash Remittance Operations** screen to cancel a cash remittance.
- Cancel Cash Remittance by GL
  The Teller can use the **Cash Remittance Operations** screen to cancel a cash remittance.

8.3.2.1 Cash Remittance Inquiry

The Teller can use the **Cash Remittance Operations** screen to inquire about the details of the issued cash remittance.

When you select the operation mode as **Inquiry**, the fields related to cash remittance inquiry will be displayed.


To inquire about the details of cash remittance:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-47 Cash Remittance Inquiry



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-45 Cash Remittance Operations (Inquiry) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch Code	Select the branch code where the cash remittance is issued from the LOV.
Operation Mode	Select the type **Inquiry** from the drop-down list.
Remittance No	Specify the cash remittance number.
Test Key No	Specify the test key number. **Note** This field is applicable only for the inter bank remittances.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-45 (Cont.) Cash Remittance Operations (Inquiry) - Field Description

Field	Description
Query	Click this icon to fetch the cash remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Cash Remittance No**, the system will make a service call to the Oracle Banking Payments and fetch the cash remittance details.
Remittance Details	Displays the details of cash remittance under this segment.
Issue Branch	Displays the logged-in branch code.
Payable Bank Code	Displays the payable bank code for the cash remittance.
Payable Branch Code	Displays the payable branch code for the cash remittance.
Remittance Amount	Displays the currency and the amount of the cash remittance.
Issue Date	Displays the issue date mentioned in the cash remittance.
Remittance Status	Displays the status of the cash remittance.
Remittance No	Displays the cash remittance number.
Test Key No	Displays the test key number.
Narrative	Displays the default narrative as **Cash Remittance Inquiry**, and it can be modified.
Issue Mode	Displays the issue mode of the Cash Remittance.
Liquidation Date	Displays the liquidation date of Cash Remittance.
Liquidation Mode	Displays the liquidation mode of Cash Remittance.
Beneficiary Details	Specify the fields.
Beneficiary Name	Displays the beneficiary's name.
Beneficiary Account	Displays the beneficiary account number.
Address Line 1 to **Address Line 4**	Displays the address of the beneficiary.
Identification Type	Displays the identification type of the beneficiary.
Identification Number	Displays the identification number of the beneficiary.
Funding Details	Funding details are displayed under this segment.
Remitter Account	Displays the account number of the remitter.
Remitter Name	Displays the remitter name.
Address Line 1 to **Address Line 4**	Displays the address of the beneficiary.
Cheque Number	Displays the cheque number.
Cheque Date	Displays the date mentioned in the cheque.
Exchange Rate	Displays the exchange rate.
Account Amount	Displays the amount that needs to be debited from the remitter account.
Identification Type	Displays the identification type of the remitter.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-45 (Cont.) Cash Remittance Operations (Inquiry) - Field Description

Field	Description
Identification Number	Displays the identification number of the remitter.

8.3.2.2 Cash Remittance Payment by Account

The Teller can use the **Cash Remittance Operations** screen to make payment against a cash remittance. Reversal of cash remittance payment is supported through Electronic Journal/ Service Journal.


The cash remittance payment is credited to the beneficiary customer account when the operation mode is **Account**.

To make payment against a cash remittance:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Figure 8-48 Cash Remittance Operations (Payment by Account)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-46 Cash Remittance Operations (Payment by Account) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-46 (Cont.) Cash Remittance Operations (Payment by Account) - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch Code	Select the branch code where the remittance is issued from the LOV.
Remittance No	Specify the remittance number.
Test Key No	Specify the test key number.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Query	Click **Query** to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
Beneficiary Account	Specify the beneficiary account number.
Beneficiary Name	Specify the beneficiary's name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-46 (Cont.) Cash Remittance Operations (Payment by Account) - Field Description

Field	Description
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Payment**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **Remittance Details** data segment to view the additional details of the remittance.

> **Note**
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

8.3.2.3 Cash Remittance Payment by Cash

The Teller can use the **Cash Remittance Operations** screen to make payment against a cash remittance. Reversal of cash remittance payment is supported through Electronic Journal/ Service Journal.

The cash remittance payment is made by cash to the beneficiary when the operation mode is **Cash**.


To make payment against a cash remittance:

Copyright © 2021, 2025, Oracle and/or its affiliates.

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Figure 8-49 Cash Remittance Operations (Payment by Cash)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-47 Cash Remittance Operations (Payment by Cash) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Branch Code	Select the branch code where the remittance is issued.
Test Key No	Specify the test key number.
Remittance No	Specify the remittance number.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-47 (Cont.) Cash Remittance Operations (Payment by Cash) - Field Description

Field	Description
Query	Click **Query** to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
Transaction Amount	Displays the transaction currency and a transaction amount. **Note** By default, the local branch currency is displayed as transaction currency and it can be modified.
Beneficiary Name	Specify the beneficiary's name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification No	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Payment**, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click on the **Remittance Details** data segment to view the additional details of the remittance.

> **Note**
>
> This data segment is non-editable.

6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

8.3.2.4 Cash Remittance Payment by GL

The Teller can use the **Cash Remittance Operations** screen to make payment against a cash remittance. Reversal of cash remittance payment is supported through Electronic Journal/ Service Journal.

The cash remittance payment is credited to the GL account when the operation mode is **GL**.


To make payment against a cash remittance:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-50 Cash Remittance Operations (Payment by GL)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-48 Cash Remittance Operations (Payment by GL) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Branch Code	Select the branch code where the remittance is issued.
Remittance No	Specify the remittance number of the instrument.
Test Key No	Specify the test key number.
Operation Type	Select the type **Payment** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Query	Click **Query** to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Description	Displays the description of the specified GL account number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-48 (Cont.) Cash Remittance Operations (Payment by GL) - Field Description

Field	Description
GL Currency	Displays the branch local currency of the specified GL account. **Note** You can also select a currency from the list of values.
Beneficiary Name	Specify the beneficiary name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
GL Amount	Displays the GL amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Payment**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4. Click on the **Remittance Details** data segment to view the additional details of the remittance.

> **Note**
>
> This data segment is non-editable.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

8.3.2.5 Cash Remittance Refund by Account

The Teller can use the **Cash Remittance Operations** screen to refund the amount against a cash remittance.


The refund amount is credited to the beneficiary customer account when the operation mode is **Account**.

To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Figure 8-51 Cash Remittance Operations (Refund by Account)



Copyright © 2021, 2025, Oracle and/or its affiliates.

2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-49 Cash Remittance Operations (Refund by Account) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch Code	Select the branch code where the remittance is issued.
Remittance No	Specify the remittance number.
Test Key No	Specify the test key number.
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Query	Click this icon to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to the Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-49 (Cont.) Cash Remittance Operations (Refund by Account) - Field Description

Field	Description
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Refund**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **Remittance Details** data segment to view the additional details of the remittance.

> **Note**
> This data segment is non-editable.

5. Click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.3.2.6 Cash Remittance Refund by Cash

The Teller can use the **Cash Remittance Operations** screen to refund the amount against a cash remittance.


The cash remittance refund is made by cash to the beneficiary when the operation mode is **Refund**.

To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Figure 8-52 Cash Remittance Operations (Refund by Cash)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-50 Cash Remittance Operations (Refund by Cash) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch Code	Select the branch code where the remittance is issued.
Remittance No	Specify the remittance number.
Test Key No	Specify the test key number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-50 (Cont.) Cash Remittance Operations (Refund by Cash) - Field Description

Field	Description
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.
Query	Click this icon to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
Transaction Amount	Displays the transaction currency and transaction amount. **Note** By default, the local branch currency is displayed as a transaction currency, and it can be modified.
Beneficiary Name	Specify the beneficiary name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charge Amount	Displays the account amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-50 (Cont.) Cash Remittance Operations (Refund by Cash) - Field Description

Field	Description
Narrative	Displays the default narrative as **Cash Remittance Operation by Refund**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click on the **Remittance Details** data segment to view the additional details of the remittance.

> **Note**
>
> This data segment is non-editable.

6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

8.3.2.7 Cash Remittance Refund by GL

The Teller can use the **Cash Remittance Operations** screen to refund the amount against a cash remittance.

The refund amount is credited to the GL account when the operation mode is **GL**.


To refund the amount:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-53 Cash Remittance Operations (Refund by GL)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-51 Cash Remittance Operations (Refund by GL) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Branch Code	Select the branch code where the remittance is issued.
Remittance No	Specify the remittance number.
Test Key No	Specify the test key number.
Operation Type	Select the type **Refund** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Query	Click **Query** to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Description	Displays the description of the specified GL account number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-51 (Cont.) Cash Remittance Operations (Refund by GL) - Field Description

Field	Description
GL Currency	Specify the currency of the specified GL account.
Beneficiary Name	Specify the beneficiary name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification No	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
GL Amount	Displays the GL amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Refund**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **Remittance Details** data segment to view the additional details of the remittance.

Note

This data segment is non-editable.

Copyright © 2021, 2025, Oracle and/or its affiliates.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

8.3.2.8 Cancel Cash Remittance by Account

The Teller can use the **Cash Remittance Operations** screen to cancel a cash remittance.


The cancellation amount is credited to a customer account when the operation mode is **Account**.

To cancel a cash remittance:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Figure 8-54 Cash Remittance Operations (Cancel by Account)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-52 Cash Remittance Operations (Cancel by Account) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Branch Code	Select the branch code where the remittance is issued.
Remittance No	Specify the remittance number of the instrument.
Test Key No	Specify the test key number.
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **Account** from the drop-down values.
Query	Click **Query** to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification No	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-52 (Cont.) Cash Remittance Operations (Cancel by Account) - Field Description

Field	Description
Account Amount	Displays the account amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Cancel**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **Remittance Details** data segment to view the additional details of the remittance.

> **Note**
> This data segment is non-editable.

5. Click **Submit**.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.3.2.9 Cancel Cash Remittance by Cash

The Teller can use the **Cash Remittance Operations** screen to cancel a cash remittance.


The cancellation amount is paid by cash to the beneficiary when the operation mode is **Cash**.

To cancel a cash remittance:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Figure 8-55 Cash Remittance Operations (Cancel by Cash)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-53 Cash Remittance Operations (Cancel by Cash) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issuing Branch Code	Select the branch code where the remittance is issued.
Remittance No	Specify the remittance number.
Test Key No	Specify the test key number.
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **Cash** from the drop-down values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-53 (Cont.) Cash Remittance Operations (Cancel by Cash) - Field Description

Field	Description
Query	Click **Query** to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
Transaction Amount	Displays the transaction currency and transaction amount. **Note** By default, the local branch currency is displayed as a transaction currency, and it can be modified.
Beneficiary Name	Specify the beneficiary name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification No	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the account amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Cancel**, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click on the **Remittance Details** data segment to view the additional details of the remittance.

> **Note**
>
> This data segment is non-editable.

6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

8.3.2.10 Cancel Cash Remittance by GL

The Teller can use the **Cash Remittance Operations** screen to cancel a cash remittance.

The cancellation amount is credited to the GL account when the operation mode is **GL**.


To cancel a cash remittance:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Cash Remittance Operations** or specify **Cash Remittance Operations** in the search icon bar and select the screen.

   The **Cash Remittance Operations** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-56 Cash Remittance Operations (Cancel by GL)



2. On the **Cash Remittance Operations** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-54 Cash Remittance Operations (Cancel by GL) - Field Description

Field	Description
Remittance Type	Select the **Remittance Type** from the drop-down list. RI = Remittance-Inward RO = Remittance-Outward
Issuing Bank Code	Specify the code of the issuing bank.
Issue Branch Code	Select the branch code where the instrument is issued.
Remittance No	Specify the remittance number of the instrument.
Test Key No	Specify the test key number.
Operation Type	Select the type **Cancel** from the drop-down list.
Operation Mode	Select the operation mode as **GL** from the drop-down values.
Query	Click **Query** to fetch the remittance details. **Note** When you click this icon, after you specify the **Issue Branch Code** and **Remittance No**, the system will make a service call to Oracle Banking Payments and fetch the remittance details.
Beneficiary Details	Specify the details under this segment.
GL Account	Specify the GL account number.
GL Description	Displays the description of the specified GL account number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-54 (Cont.) Cash Remittance Operations (Cancel by GL) - Field Description

Field	Description
GL Currency	Specify the currency of the specified GL account.
Beneficiary Name	Specify the beneficiary name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification No	Specify the identification number of the beneficiary.
Exchange Rate	Displays the exchange rate, and it can be modified. **Note** If the transaction currency is the same as the account currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
GL Amount	Displays the GL amount. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **Cash Remittance Operation by Cancel**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click on the **Remittance Details** data segment to view the additional details of the remittance.

Note

This data segment is non-editable.

Copyright © 2021, 2025, Oracle and/or its affiliates.

5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

   > **Note**
   >
   > The transaction is moved to authorization in case of any warning raised when the transaction saves.

   On transaction submission, the system will hand off the request to Oracle Banking Payments using Instrument Pay Service. If the remittance is issued by another bank, the Oracle Banking Branch has to provide the test key number during handoff for validation. On transaction completion, the Oracle Banking Branch will hand off accounting to FLEXCUBE Universal Banking for the main leg.

8.3.3 Inward Remittance Registration

The **Inward Remittance Registration** screen is used to register an inward remittance and create a remittance instrument.

During inward registration, the specified test key will be validated internally to proceed with registration.


To register an inward remittance:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Inward Remittance Registration** or specify **Inward Remittance Registration** in the search icon bar and select the screen.

   The **Inward Remittance Registration** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-57 Inward Remittance Registration



2. On the **Inward Remittance Registration** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-55 Inward Remittance Registration - Field Description

Field	Description
Inward Remittance Reference	Specify the inward remittance reference issued by the external bank during registration of the remittance.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-55 (Cont.) Inward Remittance Registration - Field Description

Field	Description
Remittance Amount	Specify the remittance currency and amount. **Note** By default, the logged-in branch local currency is displayed as remittance currency, and it can be modified.
Issuing Bank Code	Specify the code of the external issuing bank.
Issuing Bank Name	Displays the name of the specified external issuing bank.
Issue Branch Code	Specify the branch code of the external issuing bank.
Issue Branch Name	Displays the name of the specified external issuing branch.
Payable Bank Code	Specify the payable bank code.
Payable Bank Name	Displays the payable bank name.
Payable Branch Code	Specify the payable branch code.
Payable Branch Name	Displays the payable branch name.
Remittance Date	Select the issue date of the TT.
Remittance No	Specify the remittance number of the TT.
Test Key No	Specify the test key number.
Narrative	Displays the default narrative as **Inward Remittance Registration**, and it can be modified.
Beneficiary Details	Specify the details under this segment.
Beneficiary Account	Displays the beneficiary account number.
Beneficiary Name	Displays the beneficiary's name.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification No	Specify the identification number of the beneficiary.
Beneficiary Phone No	Specify the phone number of the beneficiary.
Funding Details	Specify the fields.
Remitter Account	Specify the account number of the remitter.
Remitter Name	Displays the name of the specified remitter account.
Address Line 1 to **Address Line 4**	Displays the address of the specified remitter account.
Identification Type	Select the identification type of the beneficiary from the drop-down values.
Identification Number	Specify the identification number of the beneficiary.
Identification Type	Select the identification type.
Identification Number	Specify the identification number.
Remitter Phone No	Specify the phone number of the remitter.

3. Click **Submit**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

8.4 Travellers Cheque

This sub-section describes the various screens used to perform the remittances related to Travellers Cheque. The screens are described in the following topics:

This topic contains the following subtopics:

- TC Sale by Other Modes
  The Teller can use the **TC Sale by Other Modes** screen to issue TC against the customer's CASA or a GL account.
- TC Sale Against Walk-in
  The Teller can use the **TC Sale Against Walk-in** screen to sell TC to a walk-in customer by cash.
- TC Purchase Against Account
  The Teller can use the **TC Purchase Against Account** screen to purchase TC from a customer and the credit the equivalent amount to the customer account.
- TC Purchase Against Walk-in
  The Teller can use the **TC Purchase Against Walk-in** screen to purchase TC from a walk-in customer and pay out the equivalent amount in cash.

8.4.1 TC Sale by Other Modes

The Teller can use the **TC Sale by Other Modes** screen to issue TC against the customer's CASA or a GL account.

To issue TC against various modes:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **TC Sale by Other Modes** or specify **TC Sale by Other Modes** in the search icon bar and select the screen.

   The **TC Sale by Other Modes** screen is displayed.
2. On the **TC Sale by Other Modes** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-56 TC Sale by Other Modes - Field Description

Field	Description
Issuing Bank Code	Displays the code of the issuing bank.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-56 (Cont.) TC Sale by Other Modes - Field Description

Field	Description
Issuing Bank Name	Displays the name of the issuing bank.
Issuing Branch Code	Displays the code of the issuing branch.
Branch Name	Displays the name of the issuing branch.
Issuer Code	Click the search icon and select the issuer code from the list of values. **Note** The list of values provides the HO code of the logged-in branch and the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified **Issuer Code**.
Issue Mode	Select the mode of issue from the drop-down values (`By Account` or `By GL`).
TC Amount	Select the TC currency from the drop-down values, and specify the TC Amount.
TC Date	Select the date of the TC. **Note** By default, the current posting date is displayed.
Account Number	Specify the account number of the customer. When you press the **Tab** key, the system defaults the **Account Name**. **Note** This field is applicable only if the **Issue Mode** is selected as `By Account`.
Account Name	Displays the name of the account. **Note** This field is applicable only if the **Issue Mode** is selected as `By Account`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-56 (Cont.) TC Sale by Other Modes - Field Description

Field	Description
Account Amount	Displays the account amount based on the **Exchange Rate**, **TC Amount**, and **Account Number** selected. **Note** This field is applicable only if the **Issue Mode** is selected as `By Account`.
GL Number	Click the search icon, and select the GL number from the list of values. **Note** This field is applicable only if the **Issue Mode** is selected as `By GL`.
GL Description	Displays the description of the specified GL account. **Note** This field is applicable only if the **Issue Mode** is selected as `By GL`.
GL Amount	Displays the account amount based on the **Exchange Rate**, **TC Amount**, and **Account Number** selected. **Note** This field is applicable only if the **Issue Mode** is selected as `By GL`.
Cheque Number	Specify the cheque number.
Cheque Date	Specify the date of the cheque.
Exchange Rate	Displays the exchange rate. **Note** If the TC currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-56 (Cont.) TC Sale by Other Modes - Field Description

Field	Description
Total Charge Amount	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **TC Sale Against Account** or **TC Sale Against GL** based on the selected issue mode.
Beneficiary Details	Specify the fields under this section.
Beneficiary Name	Specify the name of the beneficiary.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.

3. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Sell TC.
4. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the TC position (TC outflow) is updated to the teller position for the combination of Issuer Code, TC Currency, TC Denom code, and Series to the extent of TC denomination units being purchased.

In addition, during transaction completion, the system updates the TC Status as **Used** for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number. Following main transaction accounting entries is triggered for Account mode at Oracle Banking Branch:

- Dr Customer Account for TC Amount
- Cr Int. Susp GL for TC Amount

Following main transaction accounting entries is triggered for Account mode at Oracle Banking Branch:

- Dr Cash GL for TC Amount
- Cr Int. Susp GL for TC Amount

Oracle Banking Payments will pass the credit leg accounting (Debit - Int. Susp GL and Credit - TC GL) for TC Issuance. During handoff, Oracle Banking Branch needs to pass the intermediary bridge GL as a Debit account in the request.

Copyright © 2021, 2025, Oracle and/or its affiliates.


- Add TC Denominations to Sell TC
  You can add the denomination details for the TC in the **TC Denominations** data segment.

8.4.1.1 Add TC Denominations to Sell TC

You can add the denomination details for the TC in the **TC Denominations** data segment.

Make sure that the transaction details are added to the transaction screen.

Figure 8-58 TC Denominations



To add the denomination details:

On the **TC Denominations** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 8-57 TC Denominations - Field Description

Field	Description
Denom Code	Specify the TC denomination code from the list of values.
Currency	Displays the default TC Currency.
Series	Specify the series of the TC Denom Code that needs to be sold from Teller's Till. **Note** The list of values contains the valid TC series that are available with the Teller TC position. On click of LOV, the search criterion field will have **Series**, and the result criterion will display the **Series** and **Start Number**.
Count	Specify the count of the TC.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-57 (Cont.) TC Denominations - Field Description

Field	Description
Start Number	Display the starting number of the series. **Note** Based on the series selected, the system will populate the **Start Number** available for the combination of **Currency**, **TC Denom Code**, and **Series**.
End Number	Displays the end number, which is the sum of the start number and the count.
TC Amount	Displays the TC Amount, which is the product of the denomination and the count.
Total TC Amount	Displays the total TC amount along with the currency.
Denomination Amount	Displays the denomination amount along with the currency.

8.4.2 TC Sale Against Walk-in

The Teller can use the **TC Sale Against Walk-in** screen to sell TC to a walk-in customer by cash.


To sell TC to a walk-in customer:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **TC Sale Against Walk-in** or specify **TC Sale Against Walk-in** in the search icon bar and select the screen.

   The **TC Sale Against Walk-in** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-59 TC Sale Against Walk-in



2. On the **TC Sale Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-58 TC Sale Against Walk-in - Field Description

Field	Description
Issuing Bank Code	Displays the code of the issuing bank.
Issuing Bank Name	Displays the name of the issuing bank.
Issuing Branch Code	Displays the code of the issuing branch.
Issuing Branch Name	Displays the name of the issuing branch.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-58 (Cont.) TC Sale Against Walk-in - Field Description

Field	Description
Issuer Code	Click the search icon, and select the issuer code from the list of values. **Note** The list of values provides the HO code of the logged-in branch and the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified **Issuer Code**.
TC Amount	Select the TC currency from the drop-down values, and specify the TC Amount.
TC Date	Select the date of the TC. **Note** By default, the current posting date is displayed.
Transaction Amount	Select the transaction currency from the drop-down values. When you press the **Tab** key, the system displays the transaction amount based on the **Exchange Rate**, **TC Amount**, and **Account Number** selected.
Exchange Rate	Displays the exchange rate. **Note** If the TC currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Total Charge Amount	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **TC Sale Against Walk-in**, and it can be modified.
Beneficiary Details	Specify the fields.
Beneficiary Name	Specify the name of the beneficiary.
Identification Type	Select the identification type from the drop-down values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-58 (Cont.) TC Sale Against Walk-in - Field Description

Field	Description
Identification Number	Specify the identification number.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.

3. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
4. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Sell TC.
5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction submission, the TC position (TC outflow) is updated to the teller position for the combination of Issuer Code, TC Currency, TC denom Code, and Series to the extent of TC denomination units being purchased.

In addition, during transaction completion, the system updates the TC status as **Used** for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number. Following main transaction accounting entries are triggered for this transaction at Oracle Banking Branch.

- Dr Cash GL for TC Amount
- Cr Int. Susp GL for TC Amount

Oracle Banking Payments will pass the credit leg accounting (Debit - Int. Susp GL and Credit - TC GL) for TC Issuance. During handoff, Oracle Banking Branch needs to pass the intermediary bridge GL as a Debit account in the request.

8.4.3 TC Purchase Against Account

The Teller can use the **TC Purchase Against Account** screen to purchase TC from a customer and the credit the equivalent amount to the customer account.


To purchase TC from a customer:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **TC Purchase Against Account** or specify **TC Purchase Against Account** in the search icon bar and select the screen.

   The **TC Purchase Against Account** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-60 TC Purchase Against Account



2. On the **TC Purchase Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-59 TC Purchase Against Account - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank. **Note** By default, the logged-in bank code is displayed.
Issuing Bank Name	Displays the name of the issuing bank specified.
Issuing Branch Code	Specify the code of the issuing branch. **Note** By default, the logged-in branch code is displayed.
Branch Name	Displays the name of the issuing branch specified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-59 (Cont.) TC Purchase Against Account - Field Description

Field	Description
Issuer Code	Click the search icon and select the issuer code from the list of values. **Note** The list of values provides the HO code of the logged-in branch and the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified **Issuer Code**.
TC Amount	Select the TC currency from the drop-down values, and specify the TC Amount.
Purchase Date	Select the purchase date of the TC. **Note** By default, the current posting date is displayed.
Account Number	Specify the account number of the Customer. When you press the **Tab** key, the system defaults the **Account Name**.
Account Name	Displays the name of the account.
Account Amount	Displays the account amount based on the **Exchange Rate**, **TC Amount**, and **Account Number** selected.
Exchange Rate	Displays the exchange rate. **Note** If the TC currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Total Charge Amount	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **TC Purchase Against Account**, and it can be modified.
Beneficiary Details	Specify the fields under this section.
Beneficiary Name	Specify the name of the beneficiary.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-59 (Cont.) TC Purchase Against Account - Field Description

Field	Description
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.

3. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Purchase TC.
4. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

The following conditions apply for the TC status:

- If the system finds the TC for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number, the TC status will be updated to **Purchased**.
- If the record is not found for the above-mentioned combination, during transaction completion, the system creates individual TC records for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number with TC status as **Purchased**.

Following main transaction accounting entries is triggered for this transaction at Oracle Banking Branch:

- Dr Int. Bridge GL for TC Amount
- Cr Customer Account for Customer Account Amount

Oracle Banking Payments will pass the debit leg accounting (Debit – TC GL and Credit – Int. Bridge GL) for TC Purchase. During handoff, the Oracle Banking Branch needs to pass the intermediary bridge GL as a credit account in the request.

- Add TC Denominations to Purchase TC
  You can add the denomination details for the TC in the **TC Denominations** data segment.


8.4.3.1 Add TC Denominations to Purchase TC

You can add the denomination details for the TC in the **TC Denominations** data segment.

Make sure that the transaction details are added to the transaction screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-61 TC Denominations



To add the denomination details:

On the **TC Denominations** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 8-60 TC Denominations - Field Description

Field	Description
Denom Code	Specify the TC denomination code from the list of values.
Currency	Displays the default TC Currency.
Series	Specify the series of the TC Denom Code that is being purchased from the Agent. **Note** You can also select from the list of values if the bank is purchasing the TC which is already sold.
Count	Specify the count of the TC.
Start Number	Specify the starting number of the series for a new purchase of TC. **Note** You can also select from the list of values if the bank is purchasing the TC which is already sold.
End Number	Displays the end number, which is the sum of the start number and the count.
TC Amount	Displays the TC Amount, which is the product of the denomination and the count.
Total TC Amount	Displays the total TC amount along with the currency.
Denomination Amount	Displays the denomination amount along with the currency.

Copyright © 2021, 2025, Oracle and/or its affiliates.

8.4.4 TC Purchase Against Walk-in


The Teller can use the **TC Purchase Against Walk-in** screen to purchase TC from a walk-in customer and pay out the equivalent amount in cash.

To purchase TC from a walk-in customer:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **TC Purchase Against Walk-in** or specify **TC Purchase Against Walk-in** in the search icon bar and select the screen.

   The **TC Purchase Against Walk-in** screen is displayed.

Figure 8-62 TC Purchase Against Walk-in



2. On the **TC Purchase Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-61 TC Purchase Against Walk-in - Field Description

Field	Description
Issuing Bank Code	Specify the code of the issuing bank. **Note** By default, the logged-in bank code is displayed.
Issuing Bank Name	Displays the name of the issuing bank specified.
Issuing Branch Code	Specify the code of the issuing branch. **Note** By default, the logged-in branch code is displayed.
Issuing Branch Name	Displays the name of the issuing branch specified.
Issuer Code	Click the search icon and select the issuer code from the list of values. **Note** The list of values provides the HO code of the logged-in branch and the issuer codes maintained in the **Issuer Code Maintenance** screen.
Issuer Code Description	Displays the description of the specified **Issuer Code**.
TC Amount	Select the TC currency from the drop-down values, and specify the TC Amount.
Purchase Date	Select the purchase date of the TC. **Note** By default, the current posting date is displayed.
Account Amount	Displays the account amount based on the **Exchange Rate**, **TC Amount**, and **Account Number** selected.
Exchange Rate	Displays the exchange rate. **Note** If the TC currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-61 (Cont.) TC Purchase Against Walk-in - Field Description

Field	Description
Total Charge Amount	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **TC Purchase Against Walk-in**, and it can be modified.
Beneficiary Details	Specify the fields under this section.
Beneficiary Name	Specify the name of the beneficiary.
Identification Type	Select the identification type from the drop-down values.
Identification Number	Specify the identification number.
Address Line 1 to **Address Line 4**	Specify the address of the beneficiary.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Specify the TC denomination details. For information on the fields in the **TC Denominations** segment, refer to Add TC Denominations to Purchase TC.
5. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

   Note

   The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

   The following conditions apply for the TC status:

   - If the system finds the TC for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number, the TC status will be updated to **Purchased**.
   - If the record is not found for the above-mentioned combination, during transaction completion, the system creates individual TC records for the combination of TC Currency, Issuer Code, TC Denom Code, Series, and TC Number with TC status as **Purchased**.

   Following main transaction accounting entries is triggered for this transaction at Oracle Banking Branch:

   - Dr Int. Bridge GL for TC Amount
   - Cr Cash GL for Transaction Amount

Copyright © 2021, 2025, Oracle and/or its affiliates.

Oracle Banking Payments will pass the debit leg accounting (Debit – TC GL & Credit – Int. Bridge GL) for TC Purchase. During handoff, the Oracle Banking Branch needs to pass the intermediary bridge GL as a credit account in the request.

8.5 Instrument Status Update

The **Instrument Status Update** screen is used to change the status of used instrument numbers from ‘Used’ to ‘Unused’. This screen is used only when an unused instrument is marked as 'Used' by the application.


To use an used instrument numbers:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Instrument Status Update** or specify **Instrument Status Update** in the search icon bar and select the screen.

> **Note**
>
> Make sure that authorization is enabled for this screen.

The **Instrument Status Update** screen is displayed.

Figure 8-63 Instrument Status Update



2. On the **Instrument Status Update** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-62 Instrument Status Update - Field Description

Field	Description
Instrument Type	Select the instrument type from the drop-down list. • **Demand Draft** • **Bankers Cheque** • **Demand Draft-FCY**
Branch	Click search icon and select the branch code from the list of values.
Currency	Click search icon and select the currency code from the list of values.
Instrument Number	Specify the instrument number.

3. Click **Submit**.

   The screen displays the information message based on the conditions below:

   - If the instrument number is used, it will change the status from 'Used' to 'Unused' and displays the message as **Status is updated to Unused**.
   - If the instrument number is unused, it displays the message as **Status is already Unused**.
   - If the entered instrument number is incorrect, it displays the message as an **Invalid Instrument!**.

> **Note**
>
> If the IV Integration Parameter is activated, the Instrument Status Update in Branch is not applicable and the system restricts user access to the screen.

8.6 Instrument Details Inquiry

The **Instrument Details Inquiry** screen is to inquire details of the instrument for the DD and BC.


To inquire the details of the instrument:

1. On the Homepage, from **Teller** mega menu, under **Remittances**, click **Instrument Details Inquiry** or specify **Instrument Details Inquiry** in the search icon bar and select the screen.

   The **Instrument Details Inquiry** screen displays.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 8-64 Instrument Details Inquiry



2. On the **Instrument Details Inquiry** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 8-63 Instrument Details Inquiry - Field Description

Field	Description
Issuing Branch Code	Click **Search** icon and select the branch code where the instrument is issued from the list of values.
Instrument Number	Specify the instrument number.
Instrument Currency	Specify the instrument currency.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 8-63 (Cont.) Instrument Details Inquiry - Field Description

Field	Description
Instrument Type	Select the instrument type from the drop-down list. The available options are: • **Demand Draft** • **Bankers Cheque** • **Demand Draft - FCY**
Query	Click this button to fetch the instrument details.
Instrument Details	Displays the instrument details under this segment.
Issue Branch	Displays the logged-in branch code.
Payable Branch	Displays the payable branch for the instrument.
Payable Bank Code	Displays the payable bank code.
Instrument Amount	Displays the instrument currency and the instrument amount.
MICR No	Displays the MICR number.
Issue Date	Displays the issue date mentioned in the instrument.
Issue Mode	Displays the issue mode of the instrument.
Instrument Status	Displays the status of the instrument.
Narrative	Displays the status of the instrument.
Revalidation Date	Displays the instrument revalidation date.
Duplicate Issue Date	Displays the duplicate issue date of the instrument.
Liquidation Date	Displays the liquidation date of the instrument.
Liquidation Mode	Displays the liquidation mode of the instrument.
Beneficiary Details	Specify the fields.
Beneficiary Name	Displays the beneficiary's name.
Beneficiary Account	Displays the account number of the beneficiary.
Exchange Rate	Displays the exchange rate.
Credit Amount	Displays the credit amount.
Beneficiary Address 1 & Beneficiary Address 2	Displays the address of the beneficiary.
Identification Type	Displays the identification type of the beneficiary.
Identification Number	Displays the identification number of the beneficiary.

8.7 Inventory Integration

This topic describes about the Inventory Integration.

Instrument Number generation without Inventory (FCUBS-IV) Integration:

When the Instrument Number generation mode is set to Auto in OBPM, the next instrument number will be generated by Payments as per the Inventory Maintenance. Instrument Number Maintenance in Branch is not Applicable.

When Instrument Number generation mode is set to Manual in OBPM.

- If Instrument Number should be auto Generated by Branch during DD Issuance. Then the Generate instrument number should be enabled in Instrument Number Maintenance in OBBRN.
- If Instrument Number should be manually input by Branch User during DD Issuance. Then the Generate instrument number should be disabled in Instrument Number Maintenance in OBBRN.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Instrument Number generation with Inventory (FCUBS-IV) Integration:

If the IV Integration Parameter is enabled (UBS) and OBPM Instrument Number Generation Type is set to Auto , then there will be no Instrument number Maintenance in OBBRN.

DD & BC Issuance - On submit OBPM will fetch the Next instrument number from IV to be assigned to the transaction and pass to OBBRN in Response.

DD and BC Issuance Reversal - OBPM will send the instrument number to IV to be updated as unused, and then pass the response to OBBRN.

DD & BC Duplication - On submit OBPM will fetch the Next instrument number from IV to be assigned to the transaction and pass to OBBRN in Response for Duplicate request. The Original Instrument number will be marked as Cancelled in OBPM.

If the IV Integration Parameter is enabled (UBS) and OBPM Instrument Number Generation Type is set to Manual , then there will be no Instrument number Maintenance in OBBRN.

(**Note:** Instrument length should not be maintained in OBPM)

DD & BC Issuance - On submit OBBRN will fetch the next instrument number from IV for the given Issuer Code, Instrument Type, Instrument Currency Combination on submit. If the transaction failed while calling IV, then the transaction will be available in the sent back queue and User will be able to discard the transaction.

Note:

If maker Manually inputs the Instrument number, then UBS will validate the instrument number. DD and BC Issuance Reversal - OBBRN to make call to IV for de-utilisation and marked the Instrument to Unused.

DD & BC Duplication - On submit OBBRN will fetch the Next instrument number from IV to be assigned to the transaction for Duplicate request. This is then passed to OBPM to update the Duplicate Instrument number and mark the Original Instrument as Cancelled in OBPM.

DD & BC Cancel - Branch will send a cancellation request to OBPM.

DD & BC Refund - Branch will send a cancellation request to OBPM.

Copyright © 2021, 2025, Oracle and/or its affiliates.

9

Term Deposit Transactions

A deposit with a fixed tenure is called a time deposit or Term Deposits (TD). You can open, redeem, and top-up a term deposit using the TD transactions.

This topic contains the following subtopics:

- TD Account Opening
  The Teller can use the **TD Account Opening** screen to open a term deposit account.
- TD Redemption Against Cash
  The Teller can use the **TD Redemption Against Cash** screen to initiate manual redemption of the cash from a term deposit account.
- TD Redemption Against Account
  The Teller can use the **TD Redemption Against Account** screen to initiate manual redemption of the cash from a term deposit account.
- TD Top-Up Against Account
  The Teller can use the **TD Top-Up Against Account** screen to initiate the top-up for a term deposit account.
- TD Top-Up Against Cash
  The Teller can use the **TD Top-Up Against Cash** screen to initiate the top-up for a term deposit account.

9.1 TD Account Opening

The Teller can use the **TD Account Opening** screen to open a term deposit account.

The following details are necessary to open a term deposit account:

- Deposit details
- Funding details
- Joint Holder details
- Payout details
- Rollover details


To open a term deposit account:

1. On the Homepage, from **Teller** mega menu, under **Term Deposit**, click **TD Account Opening** or specify **TD Account Opening** in the search icon bar and select the screen.

   The **TD Account Opening** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 9-1 TD Account Opening



2. On the **TD Account Opening** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-1 TD Account Opening - Field Description

Field	Description
Customer ID	Select the Customer ID from the list of values.
Customer Name	Displays the name of the specified Customer ID.
Mode of Operation	Select the mode of operations from the drop-down list. The drop-down list shows the following values: • **Single** • **Jointly** • **Either Anyone or Survivor** • **Former or Survivor** • **Mandate Holder**
Account Type	Select the account type (**Single** or **Joint**).
Deposit Product	Specify the deposit product (FCUBS Account Class) from the list of values fetched from FLEXCUBE Universal Banking System.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-1 (Cont.) TD Account Opening - Field Description

Field	Description
Deposit Product Description	Displays the description of the specified deposit product.
Deposit Account Description	Specify the description of the deposit account.
Deposit Account Opening Date	Specify the account opening date of the deposit account.
Deposit Amount	Specify the currency and amount for the term deposit.
Deposit Tenor	Specify the tenor of deposit in days/months/years.
Maturity Amount	Displays the maturity amount along with the currency.
Simulate	Click **Simulate** to fetch the interest data for the given account class.
Auto-Renewal	Select if auto-renewal is required for the deposit account after maturity.

3. Specify the funding details. For information on the fields in the **Funding Details** segment, refer to Add Funding Details.
4. Specify the joint holder details. For information on the fields in the **Joint Holders** segment, refer to Add Joint Holders Details.
5. Specify the payout details. For information on the fields in the **Payout Details** segment, refer to Add Payout Details.
6. Specify the interest details. For information on the fields in the **Interest Details** segment, refer to Add Interest Details.
7. Specify the rollover details. For information on the fields in the **Rollover Details** segment, refer to Add Rollover Details.
8. Specify the denomination details. For information on the fields in the **Denomination Details** segment, refer to Add Denomination Details.
9. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. When you submit, the transaction details are handed off to the Term Deposit module in FLEXCUBE Universal Banking for the TD account opening process.
> Both TD account opening by cash and TD account opening by account can be viewed from the electronic journal log after submission.

- Add Funding Details
  The **Funding Details** data segment is used to add the details of the pay-by option for the TD.
- Add Joint Holders Details
  The **Joint Holders** data segment is used to add the details of the joint holders for the TD.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Add Payout Details
  The **Payout Details** data segment is used to add the details of the maturity payment for the TD.
- Add Interest Details
  The **Interest Detail** data segment is used to add the details of the interest for the TD.
- Add Rollover Details
  The **Rollover Details** data segment is used to add the parameters for auto-renewal of the TD account.

9.1.1 Add Funding Details

The **Funding Details** data segment is used to add the details of the pay-by option for the TD.

The prerequisites are as follows:

1. Make sure that the deposit details are added to the **TD Account Opening** screen. For more information, refer to TD Account Opening.
2. After you specify the deposit details, click on the **Funding Details** data segment.

Figure 9-2 Funding Details (Cash)





Figure 9-3 Funding Details (Account)



Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 9-4 Funding Details (GL)





Figure 9-5 Funding Details (Multi Mode)



The pay-by option can be selected as **Cash**, **Account**, **GL**, or **Multi Mode** based on the requirement.

To add the funding details:

On the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-2 Funding Details - Field Description

Field	Description
Pay By	Select or **Cash**, **Account**, **GL**, **Multi Mode** for the pay-in option.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-2 (Cont.) Funding Details - Field Description

Field	Description
Transaction Amount	Displays the Transaction amount in the Deposit Currency for **Pay by Cash**, **GL** and **Account Mode**. **Note** By default, branch currency will be shown and allow for editing. In addition, the system defaults the transaction amount based on the transaction currency selected.
Account Number	Specify the account number from which the deposit account needs to be funded. **Note** This field is applicable only if the **Pay By** is selected as **Account**.
Account Branch	Displays the branch of the selected account number. **Note** This field is applicable only if the **Pay By** is selected as **Account**.
Account Amount	Displays the currency of the selected account number and the calculated account amount based on the exchange rate. **Note** This field is applicable only if the **Pay By** is selected as **Account**. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-2 (Cont.) Funding Details - Field Description

Field	Description
Exchange Rate	Displays the exchange rate used to convert the deposit currency into account or transaction currency, and it can be modified. **Note** If the deposit currency is the same as the account or transaction currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Percentage	Specify the **Percentage** of Payin for the selected mode in case of Pay By Multi Mode option.
Amount	Specify the **Amount** of Payin for the selected mode in case of Pay By Multi Mode option.
Offset Account	Input the **Offset Account** for Account Mode in case of Pay By Multi Mode option.
Offset Branch	Defaulted to the Transaction Branch in case of Cash and GL Mode. Defaulted to the Account Branch in case of Account mode.
Offset Currency	Defaulted to the Transaction Currency in case of Cash and GL Mode. Defaulted to the Account Currency in case of Account mode.

9.1.2 Add Joint Holders Details


The **Joint Holders** data segment is used to add the details of the joint holders for the TD.

The prerequisites are as follows:

1. Make sure that the deposit details are added to the **TD Account Opening** screen. For more information, refer to TD Account Opening.
2. Specify the funding details. For more information, refer to Add Funding Details.
3. After you specify the funding details, click on the **Joint Holders** data segment.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 9-6 Joint Holders



This data segment is applicable only if the account type is maintained as **Joint**.

To add the details of the joint holders:

On the **Joint Holders** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 9-3 Joint Holders - Field Description

Field	Description
Joint Holder ID	Select the customer ID, which is considered as a joint account holder for the deposit account.
Joint Holder Name	Displays the customer name as joint holder name.
Relationship	Select the relationship of the joint account holder from the drop-down list.
Joint Holder's Type	Select the joint holder's type from the drop-down list.

9.1.3 Add Payout Details


The **Payout Details** data segment is used to add the details of the maturity payment for the TD.

The prerequisites are as follows:

1. Make sure that the deposit details are added to the **TD Account Opening** screen. For more information, refer to TD Account Opening.
2. Specify the funding details. For more information, refer to Add Funding Details.
3. Specify the details of the joint holders. For more information, refer to Add Joint Holders Details.
4. After you specify the details of the joint holders, click on the **Payout Details** data segment.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 9-7 Payout Details



In this data segment, you can add the parameters for automatic payout through either account transfer, banker's cheque, or demand draft. For the discounted deposit type product, you are required to maintain interest payout instructions.

To add the payout details:

On the **Payout Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-4 Payout Details - Field Description

Field	Description
Component Type	Select the component type from the drop-down list. (**Principal** or **Interest**).
Repayment By	Select the repayment option from the drop-down list (**Account**, **Bankers Cheque**, or **Demand Draft**).
Payment Account	Specify the account to which the repayment is to be made. **Note** This field allows you to input only if repayment is by account.
Account Branch	Displays the account branch based on the payment account selected.
Beneficiary Name	Specify the name of the beneficiary for the payout of BC or DD drawn. **Note** This field allows you to input only if the repayment is by BC or DD.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-4 (Cont.) Payout Details - Field Description

Field	Description
Beneficiary Address 1 to **Beneficiary Address 4**	Specify the address of the beneficiary for the payout.


9.1.4 Add Interest Details

The **Interest Detail** data segment is used to add the details of the interest for the TD.

The prerequisites are as follows:

1. Make sure that the deposit details are added to the **TD Account Opening** screen. For more information, refer to TD Account Opening.
2. Specify the funding details. For more information, refer to Add Funding Details.
3. Specify the details of the joint holders. For more information, refer to Add Joint Holders Details.
4. Specify the payout details. For more information, refer to Add Payout Details.
5. After you specify the payout details, click on the **Interest Detail** data segment.

Figure 9-8 Interest Detail



Copyright © 2021, 2025, Oracle and/or its affiliates.

To add the interest details:

On the **Interest Detail** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-5 Interest Detail - Field Description

Field	Description
Product Details	Displays the details of the deposit product.
Select	Select the check box to populate the Effective Date.
Waiver	Displays the waiver applicability (**Y** or **N**).
Product Status	Displays the product status code.
Continue Variance on Rollover	Displays the following applicability of variance: • **Y** – If the variance is to be continued on rollover. • **N** – If the variance is not continued on rollover.
Effective Date	Displays the effective date of the deposit product.
Select	Select the check box to populate the user-defined values.
Date	Displays the effective date.
Status	Displays the product status.
User Defined Values	Displays the user-defined values of the deposit product.
Element	Displays the element code. You can edit the value based on the requirements.
Value	Displays the value. You can edit the value based on the requirements.
Rate Code	Displays the rate code. You can edit the value based on the requirements.
Deposit Rate Code	Displays the deposit rate code. You can edit the value based on the requirements.
Variance	Displays the variance. You can edit the value based on the requirements.

9.1.5 Add Rollover Details

The **Rollover Details** data segment is used to add the parameters for auto-renewal of the TD account.


The prerequisites are as follows:

1. Make sure that the deposit details are added to the **TD Account Opening** screen. For more information, refer to TD Account Opening.
2. Specify the funding details. For more information, refer to Add Funding Details.
3. Specify the details of the joint holders. For more information, refer to Add Joint Holders Details.
4. Specify the payout details. For more information, refer to Add Payout Details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

5. Specify the interest details. For more information, refer to Add Interest Details.
6. After you specify the interest details, click on the **Rollover Details** data segment.

Figure 9-9 Rollover Details



To add the rollover details:

On the **Rollover Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-6 Rollover Detail - Field Description

Field	Description
Renewal Option	Specify the renewal option from the following drop-down values: • **Account Class Tenor** • **Account Tenor** • **Independent** **Note** This field is mandatory to input if auto-renewal is selected.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-6 (Cont.) Rollover Detail - Field Description

Field	Description
Renewal Type	Specify the renewal type from the following drop-down values: • **Principal** • **Interest** • **Principal + Interest** • **Special Amount** **Note** This field is mandatory to input if auto-renewal is selected.
Renewal Amount	Specify the renewal amount and renewal currency. **Note** The renewal currency is displayed as a deposit currency.
Renewal Tenor	Specify the renewal tenor in days/months/year.

9.2 TD Redemption Against Cash

The Teller can use the **TD Redemption Against Cash** screen to initiate manual redemption of the cash from a term deposit account.

It is accomplished by the pre-mature redemption either in full or part, ahead of the maturity date or after the maturity date when TD is in grace days without maturing.


To perform TD redemption against cash:

1. On the Homepage, from **Teller** mega menu, under **Term Deposit**, click **TD Redemption - Cash** or specify **TD Redemption - Cash** in the search icon bar and select the screen.

   The **TD Redemption Against Cash** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 9-10 TD Redemption Against Cash



2. On the **TD Redemption Against Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-7 TD Redemption Against Cash - Field Description

Field	Description
Deposit Account	Specify the deposit account number.
Query	Click **Query** to fetch the deposit details.
Deposit Details	Specify the fields.
Customer ID	Displays the Customer ID of the deposit account number.
Account Name	Displays the account description of the deposit account.
Principal Amount	Click **Compute** to get the amount paid at the time of term deposit booking.
Interest Amount	Displays the default rate of interest at which the interest amount is calculated.
Tax Amount	Displays the amount to be deducted towards tax.
Interest Rate	Click **Compute** to get the current interest rate applicable after partial or full redemption.
Maturity Amount	Displays the current maturity amount after partial or full redemption.
Total Payout Amount	Displays the total payout amount.
Redemption Details	Specify the fields.
Redemption Mode	Select the redemption mode from the drop-down list (**Partial Redemption** or **Full Redemption**).

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-7 (Cont.) TD Redemption Against Cash - Field Description

Field	Description
Redemption Amount	Specify as mentioned below: • If the **Redemption Mode** is selected as **Partial Redemption**, specify the redemption amount. • If the **Redemption Mode** is selected as **Full Redemption**, it displays the principal amount as redemption amount.
Waive Penalty	Check this box to waive the penalty for redeeming the term deposit. **Note** This is applicable only if the **Redemption Mode** is selected as **Full Redemption**.
Waive Interest	Check this box to waive the interest for redeeming the term deposit. **Note** This is applicable only if the **Redemption Mode** is selected as **Full Redemption**.
Redemption Payout Amount	The host determines and gives out the redemption payout amount, which is the sum of the redemption amount and interest, minus taxes.
Simulate	Click **Simulate**. When you click the **Simulate** button, the system calculates the redemption payout amount.
Narrative	Displays the default narrative as **Term Deposit Redemption Against Cash**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any warning raised when the transaction saves. When you submit, the transaction details are handed off to the Term Deposit module in FLEXCUBE Universal Banking for the TD redemption process.

Copyright © 2021, 2025, Oracle and/or its affiliates.

9.3 TD Redemption Against Account

The Teller can use the **TD Redemption Against Account** screen to initiate manual redemption of the cash from a term deposit account.


It is accomplished by the pre-mature redemption either in full or part, ahead of the maturity date or after the maturity date when TD is in grace days without maturing.

To perform TD redemption against account:

1. On the Homepage, from **Teller** mega menu, under **Term Deposit**, click **TD Redemption - Account** or specify **TD Redemption - Account** in the search icon bar and select the screen.

   The **TD Redemption Against Account** screen is displayed.

Figure 9-11 TD Redemption Against Account



2. On the **TD Redemption Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-8 TD Redemption Against Account - Field Description

Field	Description
Deposit Account	Specify the deposit account number.
Account Branch	Displays the branch of the deposit account.
Query	Click **Query** to fetch the deposit details.
Deposit Details	Specify the fields.
Customer ID	Displays the Customer ID of the deposit account number.
Account Name	Displays the account description of the deposit account.
Principal Amount	Click **Compute** to get the amount paid at the time of term deposit booking.
Interest Amount	Displays the default rate of interest at which the interest amount is calculated.
Tax Amount	Displays the amount to be deducted towards tax.
Interest Rate	Click **Compute** to get the current interest rate applicable after partial or full redemption.
Maturity Amount	Displays the current maturity amount after partial/full redemption.
Total Payout Amount	Displays the total payout amount.
Redemption Details	Specify the fields.
Redemption Mode	Select the redemption mode from the drop-down list (**Partial Redemption** or **Full Redemption**).
Redemption Amount	Specify as mentioned below: • If the **Redemption Mode** is selected as **Partial Redemption**, specify the redemption amount. • If the **Redemption Mode** is selected as **Full Redemption**, it displays the principal amount as redemption amount.
Waive Penalty	Check this box to waive the penalty for redeeming the term deposit. **Note** This is applicable only if the **Redemption Mode** is selected as **Full Redemption**.
Waive Interest	Check this box to waive the interest for redeeming the term deposit. **Note** This is applicable only if the **Redemption Mode** is selected as **Full Redemption**.
Redemption Payout Amount	The host determines and gives out the redemption payout amount, which is the sum of the redemption amount and interest, minus taxes.
Simulate	Click **Simulate**. When you click the **Simulate** button, the system calculates the redemption payout amount.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-8 (Cont.) TD Redemption Against Account - Field Description

Field	Description
Offset Account	Specify the offset account number to which the redeemed funds are to be paid.
Offset Account Amount	The system defaults the amount in the offset account number.
Offset Account Branch	The system defaults the branch of the offset account number.
Offset Account Name	The system defaults the description of the offset account number.
Exchange Rate	Displays the exchange rate applicable for the transaction based on the deposit currency and offset account currency. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **TD Redemption**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. When you submit, the transaction details are handed off to the Term Deposit module in FLEXCUBE Universal Banking for the TD redemption process.

9.4 TD Top-Up Against Account

The Teller can use the **TD Top-Up Against Account** screen to initiate the top-up for a term deposit account.

The top-up for a term deposit can be done after the opening date and before the maturity date.


To initiate the top-up for a term deposit:

1. On the Homepage, from **Teller** mega menu, under **Term Deposit**, click **TD Topup - Cash** or specify **TD Topup - Cash** in the search icon bar and select the screen.

   The **TD Top-Up Against Account** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 9-12 TD Top-Up Against Account



2. On the **TD Top-Up Against Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-9 TD Top-Up Against Account - Field Description

Field	Description
Deposit Account	Specify the deposit account number for which the top-up amount is to be added.
Account Branch	Displays the branch of the deposit account number.
Query	Click **Query**, to fetch the deposit details.
Deposit Details	Specify the fields.
Original Deposit Amount	Displays the original deposit amount of the deposit account.
Principal Balance	Displays the principal balance of the deposit account.
Customer ID	Displays the customer ID of the deposit account number.
Account Name	Displays the account description of the deposit account number.
Interest Rate	Displays the interest rate of the deposit account.
Deposit Tenor	Displays the tenor of the deposit account.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-9 (Cont.) TD Top-Up Against Account - Field Description

Field	Description
Interest Amount	Displays the calculated interest amount of the deposit account.
Maturity Amount	Displays the amount available on the maturity of the deposit account.
Top-Up Details	Specify the fields.
Offset Account	Specify the offset account from which the top-up amount needs to be debited.
Offset Account Branch	Displays the branch of the specified offset account.
Account Amount	Displays the top-up amount that is added to the deposit amount. The top-up currency is defaulted to deposit account currency.
Value Date	Specify the date on which the TD top-up needs to be effective.
Narrative	Displays the default narrative as **Term Deposit Top-Up**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. When you submit, the transaction details are handed off to the Term Deposit module in FLEXCUBE Universal Banking for the TD top-up processing.

9.5 TD Top-Up Against Cash

The Teller can use the **TD Top-Up Against Cash** screen to initiate the top-up for a term deposit account.

The top-up for a term deposit can be done after the opening date and before the maturity date.


To initiate the top-up for a term deposit:

1. On the Homepage, from **Teller** mega menu, under **Term Deposit**, click **TD Topup - Cash** or specify **TD Topup - Cash** in the search icon bar and select the screen.

   The **TD Top-Up Against Cash** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 9-13 TD Top-Up Against Cash



2. On the **TD Top-Up Against Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 9-10 TD Top-Up Against Cash - Field Description

Field	Description
Deposit Account	Specify the deposit account number for which the top-up amount needs to be added.
Query	Click **Query** to fetch the deposit details.
Deposit Details	Specify the fields.
Original Deposit Amount	Displays the principal amount at the time of TD account opening.
Principal Balance	Displays the principal balance of the deposit account.
Customer ID	Displays the customer ID of the deposit account number.
Account Name	Displays the account description of the deposit account number.
Interest Amount	Displays the calculated interest amount of the deposit account.
Interest Rate	Displays the interest rate of the deposit account.
Deposit Tenor	Displays the tenor of the deposit account.
Interest Amount	Displays the calculated interest amount of the deposit account.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 9-10 (Cont.) TD Top-Up Against Cash - Field Description

Field	Description
Maturity Amount	Displays the amount available on the maturity of the deposit account.
Top-Up Details	Specify the fields.
Top-Up Amount	Specify the top-up amount that is added to the deposit amount. The top-up currency is defaulted to deposit account currency.
Value Date	Specify the date on which the TD top-up needs to be effective.
Narrative	Displays the default narrative as **Term Deposit Top-Up**, and it can be modified.

3. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves. When you submit, the transaction details are handed off to the Term Deposit module in FLEXCUBE Universal Banking for the TD top-up processing.

Copyright © 2021, 2025, Oracle and/or its affiliates.

10

Credit Card Transactions

The Teller can use the screens related to credit card transactions to perform credit card advances and payments.

This topic contains the following subtopics:

- Credit Card Advance by Cash
  The Teller can use the **Advance by Cash** screen to disburse the credit card advance in cash to a walk-in customer against the credit card.
- Credit Card Advance by Transfer
  The Teller can use the **Advance by Transfer** screen to transfer the credit card advance amount to a customer's account.
- Credit Card Payment by Cash
  The Teller can use the **Credit Card Payment by Cash** screen to accept cash from a walk-in customer and make a credit card payment.
- Credit Card Payment by Non-Cash Modes
  The Teller can use the **Credit Card Payment** screen to make credit card payments by debiting a walk-in customer's account or clearing a cheque.
- Stop Card Request
  The Teller can use the **Stop Card Request** screen to block the credit card of a customer.

10.1 Credit Card Advance by Cash

The Teller can use the **Advance by Cash** screen to disburse the credit card advance in cash to a walk-in customer against the credit card.


To perform credit card advance by cash:

1. On the Homepage, from **Teller** mega menu, under **Credit Card**, click **Advance by Cash** or specify **Advance by Cash** in the search icon bar and select the screen.

   The **Advance by Cash** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 10-1 Advance by Cash



2. On the **Advance by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 10-1 Advance by Cash - Field Description

Field	Description
Credit Card	Specify the credit card number against which the cash advance is to be made. When you press the **Tab** key, the customer details and card details will be displayed in the **Customer Information** widget.
Advance Amount	Select the transaction currency from the drop-down values and specify the advance amount.
Advance Tenor	Specify the tenor in Days/Months/Years.
Document Type	Select from the drop-down list. The values in the drop-down list are mentioned below: • **Address Document** • **Identity Document** • **Financial Document** • **General Document**
Document Number	Specify the document number. **Note** This field is mandatory only if the document type is selected.
Approval Reference Number	Specify the approval reference if already approved.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 10-1 (Cont.) Advance by Cash - Field Description

Field	Description
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Account Amount	Display the account amount along with the currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Total Charges (LCY)	Displays the total charges applicable for the cash advance. **Note** This field is displayed only if `Total Charges Configuration` at Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Advance by Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the cash is disbursed successfully to the walk-in customer against the credit card.

Copyright © 2021, 2025, Oracle and/or its affiliates.

10.2 Credit Card Advance by Transfer


The Teller can use the **Advance by Transfer** screen to transfer the credit card advance amount to a customer's account.

To perform credit card advance by transfer:

1. On the Homepage, from **Teller** mega menu, under **Credit Card**, click **Advance by Transfer** or specify **Advance by Transfer** in the search icon bar and select the screen.

   The **Advance by Transfer** screen is displayed.

Figure 10-2 Advance by Transfer



2. On the **Advance by Transfer** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 10-2 Advance by Transfer - Field Description

Field	Description
Credit Card	Specify the credit card number against which the cash advance is to be made. When you press the **Tab** key, the customer details and card details will be displayed in the **Customer Information** widget.
Advance Amount	Select the transaction currency from the drop-down values and specify the advance amount.
Advance Tenor	Specify the tenor in Days/Months/Years.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 10-2 (Cont.) Advance by Transfer - Field Description

Field	Description
Beneficiary Account	Specify the beneficiary account number to which the amount needs to be transferred.
Beneficiary Name	Displays the name based on the specified beneficiary account number.
Account Branch	Displays the branch based on the specified beneficiary account number.
Document Type	Select from the drop-down list. The values in the drop-down list are mentioned below: • **Address Document** • **Identity Document** • **Financial Document** • **General Document**
Document Number	Specify the document number. **Note** This field is mandatory only if the document type is selected.
Approval Reference Number	Specify the approval reference if already approved.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Account Amount	Display the account amount along with the currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 10-2 (Cont.) Advance by Transfer - Field Description

Field	Description
Total Charges	Displays the total charges applicable for the cash advance. **Note** This field is displayed only if `Total Charges Configuration` at Function Code indicator level is set as `Y`.
Narrative	Displays the narrative as **Advance by Transfer**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the advance against the credit card is transferred successfully to the account of the walk-in customer.

10.3 Credit Card Payment by Cash

The Teller can use the **Credit Card Payment by Cash** screen to accept cash from a walk-in customer and make a credit card payment.


To perform credit card payment by cash:

1. On the Homepage, from **Teller** mega menu, under **Credit Card**, click **Payment by Cash** or specify **Payment by Cash** in the search icon bar and select the screen.

   The **Credit Card Payment by Cash** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 10-3 Credit Card Payment by Cash



2. On the **Credit Card Payment by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 10-3 Credit Card Payment by Cash - Field Description

Field	Description
Credit Card	Specify the credit card number for which the payment is to be made. When you press the **Tab** key, the customer details and card details will be displayed in the **Customer Information** widget.
Payment Amount	Select the transaction currency from the drop-down values and specify the payment amount. **Note** If `Multi-Currency` and `Total Charges Configuration` are set as Y, then the currency in the **Payment Amount** field defaults credit card currency, and it can be modified. If it is set as N, then the Payment currency is defaulted and displayed.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 10-3 (Cont.) Credit Card Payment by Cash - Field Description

Field	Description
Credit Amount	Display the credit amount along with the currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Total Charges	Displays the total charges applicable for the credit card payment. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Credit Card Payment by Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the credit card payment is done successfully.

10.4 Credit Card Payment by Non-Cash Modes

The Teller can use the **Credit Card Payment** screen to make credit card payments by debiting a walk-in customer's account or clearing a cheque.

This topic contains the following subtopics:

- Credit Card Payment by Account
  The Teller can use the **Credit Card Payment by Account** screen to make credit card payments by debiting a walk-in customer's account.
- Credit Card Payment by Clearing Cheque
  The Teller can use the **Credit Card Payment by Clearing Cheque** screen to make credit card payments by clearing a cheque.

Copyright © 2021, 2025, Oracle and/or its affiliates.

10.4.1 Credit Card Payment by Account

The Teller can use the **Credit Card Payment by Account** screen to make credit card payments by debiting a walk-in customer's account.


The fields in this screen are displayed based on the **Account** payment mode.

To make credit card payment by account:

1. On the Homepage, from **Teller** mega menu, under **Credit Card**, click **Credit Card Payment** or specify **Credit Card Payment** in the search icon bar and select the screen.

   The **Credit Card Payment by Account** screen is displayed.

Figure 10-4 Credit Card Payment by Account



2. On the **Credit Card Payment by Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 10-4 Credit Card Payment by Account - Field Description

Field	Description
Payment Mode	Select the payment mode as **Account**.
Credit Card	Specify the credit card number for which the payment is to be made. When you press the **Tab** key, the customer details and card details will be displayed in the **Customer Information** widget.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 10-4 (Cont.) Credit Card Payment by Account - Field Description

Field	Description
Payment Amount	Select the transaction currency from the drop-down values and specify the payment amount. **Note** If `Multi-Currency` and `Total Charges Configuration` is set as `Y`, then the currency in the **Payment Amount** field to default credit card currency and can be modified. If it is set as `N`, then Payment currency is defaulted and displayed.
Debit Amount	Specify the account number from which the amount is to be debited.
Cheque Number	Specify the cheque number. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Specify the date mentioned in the cheque.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as `Y`.
Credit Amount	Display the credit amount along with the currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 10-4 (Cont.) Credit Card Payment by Account - Field Description

Field	Description
Total Charge Amount	Displays the total charges applicable for the credit card payment. **Note** This field is displayed only if `Total Charges Configuration` at Function Code indicator level is set as `Y`.
Narrative	Displays the narrative as **Credit Card Payment by Account**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charges** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the credit card payment is done successfully.

10.4.2 Credit Card Payment by Clearing Cheque

The Teller can use the **Credit Card Payment by Clearing Cheque** screen to make credit card payments by clearing a cheque.

The fields in this screen are displayed based on the **Clearing Cheque** payment mode.


To make credit card payment by clearing cheque:

1. On the Homepage, from **Teller** mega menu, under **Credit Card**, click **Credit Card Payment** or specify **Credit Card Payment** in the search icon bar and select the screen.

   The **Credit Card Payment by Cheque** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 10-5 Credit Card Payment by Cheque



2. On the **Credit Card Payment by Cheque** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 10-5 Credit Card Payment by Clearing Cheque - Field Description

Field	Description
Payment Mode	Select the payment mode as **Clearing Cheque**.
Credit Card	Specify the credit card number for which the payment is to be made. When you press the **Tab** key, the customer details and card details will be displayed in the **Customer Information** widget.
Cheque Amount	Select the transaction currency from the drop-down values and specify the payment amount. **Note** If `Multi-Currency` and `Total Charges Configuration` is set as `Y`, then the currency in **Payment Amount** field to default credit card currency and it can be modified. If it is set as `N`, then Payment currency is defaulted and displayed.
Cheque Number	Specify the cheque number from which the amount is to be drawn.
Cheque Date	Specify the date of the cheque.
Routing Number	Specify the routing number of the cheque.
Drawer Name	Specify the drawer name.
Drawer Account	Specify the drawer account number.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 10-5 (Cont.) Credit Card Payment by Clearing Cheque - Field Description

Field	Description
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Credit Amount	Display the credit amount along with the currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Total Charge Amount	Displays the total charges applicable for the credit card payment. **Note** This field is displayed only if `Total Charges Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Credit Card Payment by Clearing Cheque**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the credit card payment is done successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

10.5 Stop Card Request


The Teller can use the **Stop Card Request** screen to block the credit card of a customer.

To block a credit card:

1. On the Homepage, from **Teller** mega menu, under **Credit Card**, click **Stop Card** or specify **Stop Card** in the search icon bar and select the screen.

   The **Stop Card Request** screen is displayed.

Figure 10-6 Stop Card Request



2. On the **Stop Card Request** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 10-6 Stop Card Request - Field Description

Field	Description
Card Number	Specify the credit card number, which needs to be blocked. When you press the **Tab** key, the system will fetch and display the following details: • **Customer ID** • **Account Number** • **Branch** • **Reference Number**
Customer ID	Displays the Customer ID for the credit card number specified.
Account Number	Displays the account number for the credit card number specified.
Branch	Displays the branch for the credit card number specified.
Reference Number	Displays the reference number for the credit card number specified.
Card Status	Select the card status (**Active** or **Inactive**) from the drop-down list.

Copyright © 2021, 2025, Oracle and/or its affiliates.

3. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the credit card will be blocked successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

11

Loan Transactions

The loan transactions are used to perform loan disbursement and loan repayment transactions.

This topic contains the following subtopics:

- Loan Disbursement by Cash
  The Teller can use the **Loan Disbursement by Cash** screen to disburse the loan by cash.
- Loan Repayment by Cash
  The Teller can use the **Loan Repayment by Cash** screen to accept repayment of a loan by cash.

11.1 Loan Disbursement by Cash


The Teller can use the **Loan Disbursement by Cash** screen to disburse the loan by cash.

To perform loan disbursement by cash:

1. On the Homepage, from **Teller** mega menu, under **Loan Transactions**, click **Loan Disbursement by Cash** or specify **Loan Disbursement by Cash** in the search icon bar and select the screen.

   The **Loan Disbursement by Cash** screen is displayed.

Figure 11-1 Loan Disbursement by Cash



2. On the **Loan Disbursement by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 11-1 Loan Disbursement by Cash - Field Description

Field	Description
Loan Account	Specify the loan account number. When you press the **Tab** key, the customer details and loan account details will be displayed in the **Customer Information** widget.
Disbursement Amount	Select the disbursement currency and specify the disbursement amount. **Note** By default, the loan account currency is displayed as disbursement currency. If `Multi-Currency Configuration` is set as `Y`, it can be modified and if it is `N`, then the default value cannot be modified.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as `Y`.
Total Charges (LCY)	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Total Charges Configuration` at Function Code indicator level is set as `Y`.
Account Amount	Displays the total cash to be disbursed to the customer in loan account currency. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code indicator level is set as `Y`. If the loan account currency is different from disbursement currency, then the system will derive the account amount based on the exchange rate.
Narrative	Displays the narrative as **Loan Disbursement By Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.

Copyright © 2021, 2025, Oracle and/or its affiliates.

4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

On transaction submission, the transaction details are handed off to the respective product processor to trigger disbursement and on transaction completion, the cash is disbursed successfully to the walk-in customer against the loan account.

11.2 Loan Repayment by Cash


The Teller can use the **Loan Repayment by Cash** screen to accept repayment of a loan by cash.

To perform loan repayment by cash:

1. On the Homepage, from **Teller** mega menu, under **Loan Transactions**, click **Loan Repayment by Cash** or specify **Loan Repayment by Cash** in the search icon bar and select the screen.

   The **Loan Repayment by Cash** screen is displayed.

Figure 11-2 Loan Repayment by Cash



2. On the **Loan Repayment by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 11-2 Loan Repayment by Cash - Field Description

Field	Description
Loan Account	Specify the loan account number. When you press the **Tab** key, the customer details and loan account details will be displayed in the **Customer Information** widget.
Repayment Amount	Select the repayment currency and specify the repayment amount. **Note** By default, the loan account currency is displayed as repayment currency.
Account Branch	Specify the branch code.
Query	Click this icon to fetch the details of loan account based on the branch code.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Total Charges (LCY)	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Total Charge Configuration` at Function Code indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 11-2 (Cont.) Loan Repayment by Cash - Field Description

Field	Description
Account Amount	Displays the repayment amount in loan account currency. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code indicator level is set as `Y`. If the loan account currency is different from repayment currency, then the system will derive the account amount based on the exchange rate.
Narrative	Displays the narrative as **Loan Repayment By Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

   Note

   The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

On transaction submission, the transaction details are handed off to the respective product processor to trigger disbursement, and on transaction completion, the loan amount is repaid successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

12

Islamic Transactions

The Teller can use the following screens to perform various Islamic transactions.

This topic contains the following subtopics:

- Murabaha Payment by Cash
  The Teller can use the **Murabaha Payment by Cash** screen to accept cash to repay the Murabaha loan amount.
- Islamic Down Payment by Cash
  The Teller can use the **Islamic Down Payment by Cash** screen to accept down payment by cash for an Islamic loan account.
- Islamic TD Account Opening
  The Teller can use the **Islamic TD Account Opening** screen to open an Islamic TD account.

12.1 Murabaha Payment by Cash


The Teller can use the **Murabaha Payment by Cash** screen to accept cash to repay the Murabaha loan amount.

To perform Murabaha payment by cash:

1. On the Homepage, from **Teller** mega menu, under **Islamic Transactions**, click **Murabaha Payment by Cash** or specify **Murabaha Payment by Cash** in the search icon bar and select the screen.

   The **Murabaha Payment by Cash** screen is displayed.

Figure 12-1 Murabaha Payment by Cash



Copyright © 2021, 2025, Oracle and/or its affiliates.

2. On the **Murabaha Payment by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 12-1 Murabaha Payment by Cash - Field Description

Field	Description
Murabaha Account	Specify the Murabaha account number. When you press the **Tab** key, the customer details and Murabaha account details will be displayed in the **Customer Information** widget.
Repayment Amount	Select the repayment currency and specify the repayment amount. **Note** By default, the repayment currency is displayed as financing account currency. If the `Multi-Currency Configuration` at the Function Code indicator level is set as `Y`, it can be modified, and if it is `N`, then the default value cannot be modified.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as `Y`.
Total Charge Amount	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as `Y`.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 12-1 (Cont.) Murabaha Payment by Cash - Field Description

Field	Description
Account Amount	Displays the repayment amount in loan account currency. This amount will be derived based on the **Repayment Amount** and **Exchange Rate**. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Murabaha Payment By Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

On transaction completion, the loan repayment details are handed off to the Islamic Financing module using the payment service. It is accomplished by handing off the entries to the accounting system (Dr Cash GL and Cr Int. Bridge GL) as maintained in the Accounting Definition screen, and the system updates the Till cash position.

12.2 Islamic Down Payment by Cash

The Teller can use the **Islamic Down Payment by Cash** screen to accept down payment by cash for an Islamic loan account.


To perform Islamic down payment by cash:

1. On the Homepage, from **Teller** mega menu, under **Islamic Transactions**, click **Islamic Down Payment by Cash** or specify **Islamic Down Payment by Cash** in the search icon bar and select the screen.

   The **Islamic Down Payment by Cash** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 12-2 Islamic Down Payment by Cash



2. On the **Islamic Down Payment by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 12-2 Islamic Down Payment by Cash - Field Description

Field	Description
Financing Account	Specify the financing account number. When you press the **Tab** key, the customer details and financing account details will be displayed in the **Customer Information** widget.
Down Payment Amount	Select the down payment currency and specify the amount. **Note** By default, the down payment currency is displayed as financing account currency. If the `Multi-Currency Configuration` at the Function Code indicator level is set as Y, it can be modified, and if it is N, then the default value cannot be modified.
Exchange Rate	Displays the exchange rate. **Note** If the transaction currency is the same as the account currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 12-2 (Cont.) Islamic Down Payment by Cash - Field Description

Field	Description
Total Charges	Displays the total charges in the branch local currency. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Account Amount	Displays the down payment amount in loan account currency. This amount will be derived based on the **Down Payment Amount** and **Exchange Rate**. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Islamic Down Payment By Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

On transaction completion, the loan repayment details are handed off to the Islamic Financing module. It is accomplished by handing off entries to the accounting system (Dr Cash GL and Cr Int. Bridge GL) as maintained in the Accounting Definition screen, and the system updates the Till cash position.

12.3 Islamic TD Account Opening

The Teller can use the **Islamic TD Account Opening** screen to open an Islamic TD account.

The following details are necessary to open an Islamic TD account:

- Deposit details

Copyright © 2021, 2025, Oracle and/or its affiliates.


- Funding details
- Joint Holder details
- Payout details
- Rollover details

To open an Islamic TD account:

1. On the Homepage, from **Teller** mega menu, under **Islamic Transactions**, click **Islamic TD Account Opening** or specify **Islamic TD Account Opening** in the search icon bar and select the screen.

   The **Islamic TD Account Opening** screen is displayed.

Figure 12-3 Islamic TD Account Opening



2. On the **Islamic TD Account Opening** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 12-3 Islamic TD Account Opening - Field Description

Field	Description
Customer ID	Select the Customer ID from the list of values.
Customer Name	Displays the name of the specified Customer ID.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 12-3 (Cont.) Islamic TD Account Opening - Field Description

Field	Description
Mode of Operation	Select the mode of operations from the drop-down list. The drop-down list shows the following values: • **Single** • **Jointly** • **Either Anyone or Survivor** • **Former or Survivor** • **Mandate Holder**
Account Type	Select the account type (**Single** or **Joint**).
Deposit Product	Specify the deposit product. Click **Fetch** to select the appropriate product type.
Deposit Product Description	Displays the description of the specified deposit product.
Deposit Account Description	Specify the description of the deposit account.
Deposit Account Opening Date	Specify the account opening date of the deposit account.
Deposit Amount	Specify the deposit amount along with the currency.
Deposit Tenor	Specify the deposit tenor in Days/Months/Years.
Profit Rate	Specify the profit rate.

3. Specify the funding details. For information on the fields in the **Funding Details** segment, refer to Add Funding Details for Islamic TD.
4. Specify the joint holder details. For information on the fields in the **Joint Holders** segment, refer to Add Joint Holders for Islamic TD.
5. Specify the payout details. For information on the fields in the **Payout Details** segment, refer to Add Payout Details for Islamic TD.
6. Specify the rollover details. For information on the fields in the **Rollover Details** segment, refer to Add Rollover Details for Islamic TD.
7. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
8. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the loan repayment details are handed off to the Islamic Financing TD module for account creation.

- Add Funding Details for Islamic TD
  The **Funding Details** data segment is used to add the details of the pay-by option for the Islamic TD.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Add Joint Holders for Islamic TD
  The **Joint Holders** data segment is used to add the details of the joint holders for the Islamic TD.
- Add Payout Details for Islamic TD
  The **Payout Details** data segment is used to add the details of the maturity payment for the Islamic TD.
- Add Rollover Details for Islamic TD
  The **Rollover Details** data segment is used to add the parameters for auto-renewal of the Islamic TD account.

12.3.1 Add Funding Details for Islamic TD

The **Funding Details** data segment is used to add the details of the pay-by option for the Islamic TD.

The prerequisites are as follows:

1. Make sure that the deposit details are added to the **Islamic TD Account Opening** screen. For more information, refer to Islamic TD Account Opening.
2. After you specify the deposit details, click on the **Funding Details** data segment.

Figure 12-4 Funding Details (Cash)





Figure 12-5 Funding Details (Account)



The pay-by option can be selected as **Cash** or **Account** based on the requirement.

To add the funding details:

On the **Funding Details** data segment, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 12-4 Funding Details - Field Description

Field	Description
Pay By	Select **Account** or **Cash** for the pay-in option.
Account Number	Specify the account number from which the deposit account needs to be funded. **Note** This field is applicable only if the **Pay By** is selected as **Account**.
Account Branch	Displays the branch of the selected account number. **Note** This field is applicable only if the **Pay By** is selected as **Account**.
Account Amount	Displays the currency of the selected account number and the calculated account amount based on the exchange rate. **Note** This field is applicable only if the **Pay By** is selected as **Account**.
Cheque Number	Specify the cheque number of the account. **Note** This field is applicable only if the **Pay By** is selected as **Account**.
Cheque Date	Specify the date as mentioned in the cheque. **Note** This field is applicable only if the **Pay By** is selected as **Account**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 12-4 (Cont.) Funding Details - Field Description

Field	Description
Transaction Amount	Specify the transaction currency if the **Pay By** is selected as **Cash**. **Note** By default, branch currency will be shown and allow for editing. In addition, the system defaults the transaction amount based on the transaction currency selected.
Exchange Rate	Displays the exchange rate used to convert the deposit currency into account or transaction currency, and it can be modified. **Note** If the deposit currency is the same as the account or transaction currency, the system will display the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.

12.3.2 Add Joint Holders for Islamic TD


The **Joint Holders** data segment is used to add the details of the joint holders for the Islamic TD.

The prerequisites are as follows:

1. Make sure that the deposit details are added to the **Islamic TD Account Opening** screen. For more information, refer to Islamic TD Account Opening.
2. Specify the funding details. For more information, refer to Add Funding Details for Islamic TD.
3. After you specify the funding details, click on the **Joint Holders** data segment.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 12-6 Joint Holders



This data segment is applicable only if the account type is maintained as **Joint**.

To add the details of the joint holders:

On the **Joint Holders** data segment, specify the fields. For more information on fields, refer to the field description table.

Table 12-5 Joint Holders - Field Description

Field	Description
Joint Holder ID	Select the customer ID which is considered as joint account holder for the deposit account.
Joint Holder Name	Displays the customer name as joint holder name.
Relationship	Select the relationship of the joint account holder from the drop-down list.
Joint Holder's Type	Select the joint holder's type from the drop-down list.

12.3.3 Add Payout Details for Islamic TD


The **Payout Details** data segment is used to add the details of the maturity payment for the Islamic TD.

The prerequisites are as follows:

1. Make sure that the deposit details are added to the **Islamic TD Account Opening** screen. For more information, refer to Islamic TD Account Opening.
2. Specify the funding details. For more information, refer to Add Funding Details for Islamic TD.
3. Specify the details of the joint holders. For more information, refer to Add Joint Holders for Islamic TD.
4. After you specify the details of the joint holders, click on the **Payout Details** data segment.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 12-7 Payout Details



In this data segment, you can add the parameters for automatic payout through either account transfer, banker's cheque, or demand draft.

To add the payout details:

On the **Payout Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 12-6 Payout Details - Field Description

Field	Description
Component Type	Select the component type from the drop-down list. (**Principal** or **Profit**).
Repayment By	Select the repayment option from the drop-down list (**Account**, **Bankers Cheque**, or **Demand Draft**).
Payment Account	Specify the account to which the repayment is to be made. This field allows you to input only if repayment is by account.
Account Branch	Displays the account branch based on the payment account selected.
Beneficiary Name	Specify the name of the beneficiary for the payout of BC or DD drawn. **Note** This field allows you to input only if the repayment is by BC or DD.
Beneficiary Address 1 to **Beneficiary Address 4**	Specify the address of the beneficiary for the payout.

12.3.4 Add Rollover Details for Islamic TD


The **Rollover Details** data segment is used to add the parameters for auto-renewal of the Islamic TD account.

The prerequisites are as follows:

Copyright © 2021, 2025, Oracle and/or its affiliates.

1. Make sure that the deposit details are added to the **Islamic TD Account Opening** screen. For more information, refer to Islamic TD Account Opening.
2. Specify the funding details. For more information, refer to Add Funding Details for Islamic TD.
3. Specify the details of the joint holders. For more information, refer to Add Joint Holders for Islamic TD.
4. Specify the payout details. For more information, refer to Add Payout Details for Islamic TD.
5. After you specify the payout details, click on the **Rollover Details** data segment.

Figure 12-8 Rollover Details



To add the rollover details:

On the **Rollover Details** data segment, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 12-7 Rollover Detail - Field Description

Field	Description
Auto Renewal	Select if auto-renewal is required for the deposit account.
Renewal Type	Specify the renewal type from the following drop-down values: • **Principal** • **Principal + Profit** • **Special Amount** • **Profit** **Note** This field is mandatory to input if auto-renewal is selected.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 12-7 (Cont.) Rollover Detail - Field Description

Field	Description
Renewal Amount	Specify the renewal amount and renewal currency. **Note** The renewal currency is displayed as the deposit currency.
Renewal Tenor	Specify the renewal tenor in days/months/year.

Copyright © 2021, 2025, Oracle and/or its affiliates.

13

Bill Payments

The bill payment transactions are used to make payments for various utility bills.

This topic contains the following subtopics:

- Bill Payment by Cash
  The Teller can use the **Bill Payment by Cash** screen to make utility bill payments by cash.
- Bill Payments by Other Modes
  The bill payment transactions are used to make payments for various utility bills. Utility bill payments can be performed for the Institutions, which are already maintained in product processors. The bill payment can be made by account and clearing cheque.

13.1 Bill Payment by Cash

The Teller can use the **Bill Payment by Cash** screen to make utility bill payments by cash.


Utility bill payment can be performed for the institutions, which are already maintained in product processors.

To make bill payment by cash:

1. On the Homepage, from **Teller** mega menu, under **Bill Payments**, click **Bill Payment by Cash** or specify **Bill Payment by Cash** in the search icon bar and select the screen.

   The **Bill Payment by Cash** screen is displayed.

Figure 13-1 Bill Payment by Cash



2. On the **Bill Payment by Cash** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 13-1 Bill Payment by Cash - Field Description

Field	Description
Utility Provider ID	Click the search icon, and select the utility provider ID from the list of values.
Utility Provider Name	Displays the name of the specified utility provider ID.
Settlement Account	Displays the account number of the specified utility provider ID.
Account Currency	Displays the account currency of the settlement account.
Account Description	Displays the account description of the settlement account.
Consumer Number	Specify the consumer number.
Bill Number	Specify the bill number.
Bill Date	Specify the bill date.
Bill Amount	Select the currency from the drop-down values, and specify the bill amount that needs to be paid.
Transaction Amount	Select the transaction currency from the drop-down values. The transaction amount is displayed based on the exchange rate.
Exchange Rate	Displays the exchange rate. **Note** If the bill currency is the same as the Transaction currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Bill Payment By Cash**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the denomination details. For information on the fields in the **Denomination** segment, refer to Add Denomination Details.
5. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the main leg accounting (Dr Cash GL and Cr Institution ID account GL) and charge accounting details are handed off to the Accounting System.

Copyright © 2021, 2025, Oracle and/or its affiliates.

13.2 Bill Payments by Other Modes

The bill payment transactions are used to make payments for various utility bills. Utility bill payments can be performed for the Institutions, which are already maintained in product processors. The bill payment can be made by account and clearing cheque.

This topic contains the following subtopics:

- Bill Payment by Account
  The Teller can use the **Bill Payment by Account** screen to make utility bill payments against an account.
- Bill Payment by Clearing Cheque
  The Teller can use the **Bill Payment** screen to make utility bill payment by clearing cheque.

13.2.1 Bill Payment by Account

The Teller can use the **Bill Payment by Account** screen to make utility bill payments against an account.

Utility bill payment can be performed for the institutions, which are already maintained in product processors.

To make utility bill payment by account:


1. On the Homepage, from **Teller** mega menu, under **Bill Payments**, click **Bill Payment by Other Modes** or specify **Bill Payment by Account** in the search icon bar and select the screen.

   The **Bill Payment by Account** screen is displayed.

> **Note**
>
> By default, the system displays the **Bill Payment by Account** screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 13-2 Bill Payment by Account



2. On the **Bill Payment by Account** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 13-2 Bill Payment by Account - Field Description

Field	Description
Payment Mode	Select the payment mode type from the drop-down list. The values are: • Account • Clearing Cheque
Utility Provider ID	Click the search icon, and select the utility provider ID from the list of values.
Utility Provider Name	Displays the name of the specified utility provider ID.
Settlement Account	Displays the account number of the specified utility provider ID.
Account Currency	Displays the account currency of the settlement account.
Account Description	Displays the account description of the settlement account.
Consumer Number	Specify the consumer number.
Bill Number	Specify the bill number.
Bill Date	Specify the bill date.
Bill Amount	Select the currency from the drop-down values, and specify the bill amount that needs to be paid.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 13-2 (Cont.) Bill Payment by Account - Field Description

Field	Description
Account Number	Specify the account number against which the bill payment needs to be done.
Account Name	Displays the name of the specified account number.
Cheque Number	Specify the cheque number, if the amount needs to be debited through the cheque. **Note** The system validates the status of the cheque and prompts an error message if incase of a Used or Stopped or Invalid cheque.
Cheque Date	Specify the cheque date, if the amount needs to be debited through the cheque.
Account Amount	Displays the amount that needs to be debited based on the exchange rate.
Exchange Rate	Displays the exchange rate. **Note** If the bill currency is the same as the Transaction currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Bill Payment Against Account**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the main leg accounting (Dr Cash GL and Cr Institution ID account GL) and charge accounting details are handed off to the Accounting System.

Copyright © 2021, 2025, Oracle and/or its affiliates.

13.2.2 Bill Payment by Clearing Cheque

The Teller can use the **Bill Payment** screen to make utility bill payment by clearing cheque.

Utility bill payment can be performed for the institutions, which are already maintained in product processors.


To make utility bill payment by account:

1. On the Homepage, from **Teller** mega menu, under **Bill Payments**, click **Bill Payment by Other Modes** or specify **Bill Payment by Clearing Cheque** in the search icon bar and select the screen.

   The **Bill Payment by Clearing Cheque** screen is displayed.

> **Note**
>
> By default, the system displays the **Bill Payment by Account** screen.

Figure 13-3 Bill Payment by Clearing Cheque



2. On the **Bill Payment by Clearing Cheque** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 13-3 Bill Payment by Clearing Cheque - Field Description

Field	Description
Payment Mode	Select the payment mode type from the drop-down list. The values are: • Account • Clearing Cheque

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 13-3 (Cont.) Bill Payment by Clearing Cheque - Field Description

Field	Description
Utility Provider ID	Click the search icon, and select the utility provider ID from the list of values.
Utility Provider Name	Displays the name of the specified utility provider ID.
Settlement Account	Displays the account number of the specified utility provider ID.
Account Currency	Displays the account currency of the settlement account.
Account Description	Displays the account description of the settlement account.
Consumer Number	Specify the consumer number.
Bill Number	Specify the bill number.
Bill Date	Specify the bill date.
Bill Amount	Select the currency from the drop-down values, and specify the bill amount that needs to be paid.
Cheque Amount	Displays the currency and bill amount value.
Clearing Type	Click Search icon, and select clearing network code from the drop-down values.
Routing Number	Specify the routing number.
Drawer Account	Specify the drawer account.
Drawer Name	Specify the drawer name.
Cheque Number	Specify the cheque number, if the amount needs to be debited through the cheque.
Cheque Date	Specify the cheque date, if the amount needs to be debited through the cheque.
Exchange Rate	Displays the exchange rate. **Note** If the bill currency is the same as the Transaction currency, the system displays the exchange rate as 1. This field is displayed only if `Multi-Currency Configuration` at the Function Code indicator level is set as Y.
Narrative	Displays the narrative as **Bill Payment by Clearing Cheque**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the main leg accounting (Dr Cash GL and Cr Institution ID account GL) and charge accounting details are handed off to the Accounting System.

Copyright © 2021, 2025, Oracle and/or its affiliates.

14

Session Teller Transactions

The Teller can use the screens under the **Teller Session** menu to perform financial transactions for customer accounts in a teller session.

The cash transactions can be performed only when the teller session is started, refer to Start Teller Session to start a teller session. The Teller can enter the denomination details for a teller session in the Stop Teller Session screen. Denomination tracking must be enabled for this functionality.

This topic contains the following subtopics:

- Cash Deposit
  The **Cash Deposit** screen is used to deposit the cash in a CASA through a Teller Session.
- Cash Withdrawal
  The **Cash Withdrawal** screen is used to withdraw funds from the CASA account of the customer.
- FX Sale Against Walk-in
  The **FX Sale Against Walk-in** screen is used to sell a foreign currency to a walk-in customer in return for the equivalent amount received in the local currency.
- FX Purchase Against Walk-in
  The **FX Purchase Against Walk-in** screen is used to buy foreign currency from walk-in customers.
- Loan Repayment by Cash
  The Teller can use the **Loan Repayment by Cash** screen to accept cash from a walk-in customer to repay the loan amount.

14.1 Cash Deposit

The **Cash Deposit** screen is used to deposit the cash in a CASA through a Teller Session.

Cash can be deposited in either account currency or any foreign currency that is allowed. Whenever any transaction in foreign currency is posted to the account, it is converted to the account currency based on the maintained exchange rate for the transaction.


To deposit the cash through a Teller Session:

1. On the Homepage, click **Teller**. On the Teller Mega Menu, under **Session Teller Transactions**, click **Cash Deposit** or specify the **Cash Deposit** in the search icon bar and select the screen.

   The **Cash Deposit** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 14-1 Cash Deposit



2. On the **Cash Deposit** screen, specify the fields. For more information on fields, refer to Table 4-1.

> **Note**
>
> The fields marked as **Required** are mandatory.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

   The `Transaction Completed Successfully` information message is displayed.

14.2 Cash Withdrawal

The **Cash Withdrawal** screen is used to withdraw funds from the CASA account of the customer.

The withdrawal is subject to the availability of a sufficient balance or available credit limit. When the transaction is performed, it updates the available balance in the CASA account immediately.


To withdraw the cash through a Teller Session:

1. On the Homepage, click **Teller**. On the Teller Mega Menu, under **Session Teller Transactions**, click **Cash Withdrawal** or specify the **Cash Withdrawal** in the search icon bar and select the screen.

   The **Cash Withdrawal** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 14-2 Cash Withdrawal



2. On the **Cash Withdrawal** screen, specify the fields. For more information on fields, refer to Table 4-3.

> **Note**
>
> The fields marked as **Required** are mandatory.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

On transaction completion, the cash is withdrawn successfully from the customer account. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

14.3 FX Sale Against Walk-in

The **FX Sale Against Walk-in** screen is used to sell a foreign currency to a walk-in customer in return for the equivalent amount received in the local currency.


To sell a foreign currency to the walk-in customer:

1. On the Homepage, from **Teller** mega menu, under **Customer Transaction**, click **FX Sale - Walk-in** or specify **FX Sale - Walk-in** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **FX Sale Against Walk-in** screen is displayed.

Figure 14-3 FX Sale Against Walk-in



2. On the **FX Sale Against Walk-in** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 14-1 FX Sale Against Walk-in - Field Description

Field	Description
Amount Sold	Select the applicable currency from the drop-down list and specify the amount that needs to be sold to the walk-in customer.
Currency Received	Select the currency that you have received from the customer in return for the currency sold. You can select the appropriate code from the adjoining option list that displays all the currency codes maintained in the system.
Allow Denom Variance	Select if the denomination-wise variance needs to be applied for the transaction. **Note** If the parameter at function code indicator is set as Y, this option will be selected by default, and it can be modified. If the parameter at the function code indicator is set as N, then this option will be disabled.
Beneficiary Name	Specify the name of the beneficiary customer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 14-1 (Cont.) FX Sale Against Walk-in - Field Description

Field	Description
Beneficiary Address 1 to **Beneficiary Address 4**	Specify the address of the beneficiary.
Identification Type	Select the type of identification provided by the customer from the drop-down list.
Identification Number	Specify the identification number provided by the customer.
Exchange Rate	Displays the exchange rate used to convert the transaction currency into account currency, and it can be modified. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as Y.
Negotiated Exchange Rate	Specify the negotiated exchange rate that should be used for foreign currency transactions between the treasury and the branch. You need to specify the negotiated exchange rate only when the currencies involved in the transaction are different. **Note** This field is applicable only if the transaction involves cross currency and only if cross currency enabled and `Negotiated_Rate_Enabled Configuration` at Function Code Indicator level is set as Y.
Negotiated Reference Number	Specify the unique reference number that should be used for negotiation of cost rate, in foreign currency transaction. If you have specified the negotiated cost rate, then you need to specify the negotiated reference number also. **Note** Accounting system books the online revaluation entries based on the difference in exchange rate between the negotiated exchange rate and transaction rate.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 14-1 (Cont.) FX Sale Against Walk-in - Field Description

Field	Description
Amount Received	Displays the amount received and currency from the customer. **Note** The currency of the amount received will be defaulted from **Currency Received**. The amount received will be calculated based on the **Amount Sold** and the **Exchange Rate**. This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Total Charges	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Total Charges Configuration` at Function Code Indicator level is set as `Y`.
Narrative	Displays the default narrative as **FX Sale (Walk-in)**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Specify the FX In Denomination details. For information on the fields in the **FX In Denomination Details** segment, refer to Add Denomination Details.
5. Specify the FX Out Denomination details. For information on the fields in the **FX Out Denomination Details** segment, refer to Add Denomination Details.
6. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the teller cash position to the equivalent of "Sold currency" is deducted, and "Received currency" is incremented. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

Copyright © 2021, 2025, Oracle and/or its affiliates.

14.4 FX Purchase Against Walk-in


The **FX Purchase Against Walk-in** screen is used to buy foreign currency from walk-in customers.

To buy foreign currency from a walk-in customer:

1. On the Homepage, click **Teller**. On the Teller Mega Menu, under **Session Teller Transactions**, click **FX Purchase Against Walk-in** or specify the **FX Purchase Against Walk-in** in the search icon bar and select the screen.

   The **FX Purchase Against Walk-in** screen is displayed.

Figure 14-4 FX Purchase Against Walk-in



2. On the **FX Purchase Against Walk-in** screen, specify the fields. For more information on fields, refer to Table 4-8.

> **Note**
>
> The fields marked as **Required** are mandatory.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.

4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any approval warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.

On transaction completion, the teller cash position is updated based on the currency of the **Amount Bought** and the **Amount Paid** fields. For more information on transaction submission and validations, refer to *Step 5* in Cash Deposit.

14.5 Loan Repayment by Cash


The Teller can use the **Loan Repayment by Cash** screen to accept cash from a walk-in customer to repay the loan amount.

To make loan repayment by cash:

1. On the Homepage, click **Teller**. On the Teller Mega Menu, under **Session Teller Transactions**, click **Loan Repayment by Cash** or specify the **Loan Repayment by Cash** in the search icon bar and select the screen.

   The **Loan Repayment by Cash** screen is displayed.

Figure 14-5 Loan Repayment by Cash



2. On the **Loan Repayment by Cash** screen, specify the fields. For more information on fields, refer to Table 11-2.

> **Note**
>
> The fields marked as **Required** are mandatory.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Note

The transaction is moved to authorization in case of any approval warning raised when the transaction saves. On transaction completion, the loan amount is repaid successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

15

Journal Log

The Teller or Supervisor can use screens under the **Journal Log** menu to view the status of transactions performed by them. It is also used to resubmit or reject an incomplete transaction or reverse a completed transaction.

This topic contains the following subtopics:

- About Electronic and Servicing Journals
  In the **Electronic Journal** and **Servicing Journal** screens, Tellers can view the status of the transactions performed only by them and Supervisors can view the status of the transactions performed by them and other Tellers.
- Electronic Journal
  Tellers and Supervisors can use the **Electronic Journal** screen to view the status of the cash transactions performed by them on the posting date.
- Servicing Journal
  Tellers and Supervisors can use this screen to view the status of the non-cash transactions performed by them on the posting date.
- Types of Transaction Status
  Transactions can be queries from the Journal Log based on the below **Transaction Status**.
- Reassign Transactions
  Tellers and Supervisors can use the **Reassign Transactions** screen to re-assign the transactions that are pending approval to the other Supervisor or to unlock a locked transaction.
- Natural Electronic Journal
  Tellers and Supervisors can use the **Natural Electronic Journal** screen to view the status of the cash transactions performed by them on the posting date.

15.1 About Electronic and Servicing Journals

In the **Electronic Journal** and **Servicing Journal** screens, Tellers can view the status of the transactions performed only by them and Supervisors can view the status of the transactions performed by them and other Tellers.

Common Operations

> **Note**
>
> The failed records during execution are displayed in **SRV_TB_BC_EJ_LOG** table.

These screens are used to perform the following operations:

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-1 Operations in Journal Log

Operation	Description
View Status	View the status of all transactions performed by the logged-in Teller ID.
Reverse Completed Transactions	Reverse the completed transaction posted by Teller during the day and the previous day. The following conditions apply for the reversal of both current and previous day transactions: • If the reversal of a transaction is performed within the purge days configured. • If the reversal allowed flag is enabled at the function indicator level for the function code. **Note** • During the reversal of both cash and non-cash transactions, the transaction date will be the date on which reversal is initiated and accounting will be handed off with the transaction date. • During the reversal of cash transactions, till update will be done on the date of reversal for the respective teller ID who has initiated the reversal from the journal log. • On transaction reversal , a Teller Remark window will appear, prompting the Teller to capture remarks before submission for approval. Earlier captured remarks will be auto-populate, enabling the Teller to add or modify them.
Re-submit Incomplete Transactions	Re-submit the incomplete transactions performed by the logged-in Teller ID, that are either: • Approved by the supervisor and moved to Teller EJ log for re-submission. • Processed by an external system (for example, Oracle Banking Payments) and responded to Teller with the status as **Success**.
Reject Incomplete Transactions	Reject the incomplete transactions that are either: • Rejected by an external system (for example, Oracle Banking Payments) with the status as **Reject**. • Prompted with error due to processing validations.
View Approval History	View the approval history to see the list of all transactions that are either approved or rejected by the logged-in approver ID.
Approve or Reject Transactions	Approve or Reject the transactions that are assigned to the logged-in Approver ID during the day.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-1 (Cont.) Operations in Journal Log

Operation	Description
Discard of Reversal Transactions	When the approver rejects the reversal request, the transaction is marked as rejected and the teller discards the rejected status, the transaction is moved to the discarded transaction.

In the tile and grid views, the transactions are displayed for all statuses by default. The status can be changed using the filters option. If the user closes the screen with a status other than All, the selected status will default until the browser tab is closed. The following conditions apply for the default status:

Table 15-2 Conditions for Default Status

Condition	Description
The browser tab is not closed	The transactions will be displayed for the previously selected status if the screen is launched again.
The browser tab is closed and the user logs in to the application in a new tab or window	The transactions will be displayed for all statuses if the screen is launched.

Common Icons, Actions, and Shortcut Keys

Users can perform one of the following actions on the **Electronic Journal** and **Servicing Journal** screens:

Table 15-3 Symbols

Icon	Description
	Click on this icon to display the details in the tile view.
	Click on this icon to display the details in the grid view.

After filling the necessary fields in the **Electronic Journal** and **Servicing Journal** screens, you can do one of the following steps:

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-4 Basic Actions

Action	Description
Fetch	Click **Fetch** to get the list of transactions based on the query criteria specified. When you click **Fetch**, the following details are displayed for each transaction: • **Function Code and Screen Name** • **Transaction Reference Number** • **Teller Sequence Number** • **Transaction Amount** • **Account Number** • **Teller ID** • **Teller Remarks** • **Supervisor ID** • **Supervisor Remarks**
Clear	Click **Clear** to clear the specified values.

Users can also navigate to necessary the transaction; perform the operations using the shortcut keys as follows:

1. Press the **Tab** key, and navigate to the list of transactions in grid view.
2. Use **Up**/**Down** arrow keys to select the necessary transaction.
3. Use **Left**/**Right** arrow keys to select the icon.
4. Press **Spacebar** to view the operations applicable to the selected transaction.
5. Use **Up**/**Down** arrow keys to select the necessary operation.

15.2 Electronic Journal

Tellers and Supervisors can use the **Electronic Journal** screen to view the status of the cash transactions performed by them on the posting date.

For information on the common operations and icons on this screen, refer to About Electronic and Servicing Journals .


To view the status of the cash transactions:

1. On the Homepage, from **Teller** mega menu, under **Journal Log**, click **Electronic Journal** or specify **Electronic Journal** in the search icon bar and select the screen.

   The **Electronic Journal** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-1 Electronic Journal



2. On the **Electronic Journal** screen, specify the details. For more information on fields, refer to the field description table.

Table 15-5 Electronic Journal - Field Description


Field	Description
Teller ID	Click Search icon and select the Teller ID from the list of values.
Branch Posting Date	Specify the branch posting date for which the inquiry is to be made. **Note** By default, the current posting date is displayed.
Transaction Status	Select the transaction status from the drop-down values.
Transaction Reference	Select the transaction reference from the drop-down values.

3. Click  icon to filter the results on the tile/grid view based on the search criteria.

The **Filters** overlays screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-2 Filters (Electronic Journal)



4. On the **Filters** overlays screen, specify the details to fetch the records. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-6 Filters - Field Description

Field	Description
Teller ID	Specify the Teller ID. **Note** You can also click the search icon and select the Teller ID from the list of values.
Function Code	Specify the function code for which the inquiry is to be made. **Note** You can also click the search icon and select the function code from the list of values.
Branch Posting Date	Specify the branch posting date for which the inquiry is to be made. **Note** By default, the current posting date is displayed.
Transaction Status	Select the transaction status from the drop-down values. **Note** By default, **Sent Back** status is selected.
Transaction Reference	Specify the transaction reference number.
Account Number	Specify the account number. **Note** You can also click the search icon and select the account number from the list of maintained account numbers.
Teller Sequence Prefix	Click the search icon and select from the list of values.
Transaction Currency	Click the search icon and select the transaction currency from the list of values.
From Sequence Number	Specify the start number of the sequence range.
To Sequence Number	Specify the end number of the sequence range.
From Transaction Time	Specify the start time for filtering transactions executed within the given time range.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-6 (Cont.) Filters - Field Description

Field	Description
To Transaction Time	Specify the end time for filtering transactions executed within the given time range.
From Amount Range	Specify the “from” amount of the amount range.
To Amount Range	Specify the “to” amount of the amount range.

5. Click **Apply**.

The **Electronic Journal** screen displays.

Figure 15-3 Electronic Journal (List View) - Completed Transaction Status






Figure 15-4 Electronic Journal (List View) - Sent Back Transaction Status




You can perform any of the following actions in this screen:

- Click  icon to view the transaction information. This screen provides the details of the transactions handed off to the external system.

  The **Transaction Info** pop-up screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 15-5 Transaction Info



- Click **View** button to view the transaction details. The following details are displayed based on the transaction status in the filters:
  - Transaction Reference
  - Transaction Status
  - Time Stamp
  - Teller ID
  - Teller Remarks
  - Approval Time Stamp
  - Supervisor ID
  - Supervisor Remarks
  - Override Info 
    Click **Override Info** icon to view the details for approval flow request.
- Click  icon to submit the transaction.
- Click  icon to discard the transaction.
- Click  icon to view advice.
- Click  icon to reverse the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-6 Electronic Journal (Grid View)



15.3 Servicing Journal

Tellers and Supervisors can use this screen to view the status of the non-cash transactions performed by them on the posting date.


For information on the common operations and icons on this screen, refer to About Electronic and Servicing Journals.

To view the status of the non-cash transactions:

1. On the Homepage, from **Teller** mega menu, under **Journal Log**, click **Servicing Journal** or specify **Servicing Journal** in the search icon bar and select the screen.

   The **Servicing Journal** screen is displayed.

Figure 15-7 Servicing Journal



2. On the **Servicing Journal** screen, specify the details. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-7 Servicing Journal - Field Description

Field	Description
Teller ID	Click Search icon and select the Teller ID from the list of values.
Branch Posting Date	Specify the branch posting date for which the inquiry is to be made. **Note** By default, the current posting date is displayed.
Transaction Status	Select the transaction status from the drop-down values.
Transaction Reference	Select the transaction reference from the drop-down values.

3. Click




icon to filter the results on the tile/grid view based on the search criteria.

The **Filters** overlays screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-8 Filters (Servicing Journal)



4. On the **Filters** overlays screen, specify the details to fetch the records. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-8 Filters - Field Description

Field	Description
Teller ID	Specify the Teller ID. **Note** You can also click the search icon and select the Teller ID from the list of values.
Function Code	Specify the function code for which the inquiry is to be made. **Note** You can also click the search icon and select the function code from the list of values.
Branch Posting Date	Specify the branch posting date for which the inquiry is to be made. **Note** By default, the current posting date is displayed.
Transaction Status	Select the transaction status from the drop-down values. **Note** By default, **Sent Back** status is selected.
Transaction Reference	Specify the transaction reference number.
Account Number	Specify the account number. **Note** You can also click the search icon and select the account number from the list of maintained account numbers.
Teller Sequence Prefix	Click the search icon and select from the list of values.
Transaction Currency	Click the search icon and select the transaction currency from the list of values.
From Sequence Number	Specify the start number of the sequence range.
To Sequence Number	Specify the end number of the sequence range.
From Transaction Time	Specify the start time for filtering transactions executed within the given time range.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-8 (Cont.) Filters - Field Description

Field	Description
To Transaction Time	Specify the end time for filtering transactions executed within the given time range.
From Amount Range	Specify the “from” amount of the amount range.
To Amount Range	Specify the “to” amount of the amount range.

5. Click **Apply**.

The **Servicing Journal** screen displays.

Figure 15-9 Servicing Journal (List View) - Completed Transaction Status





Figure 15-10 Servicing Journal (List View) - Sent Back Transaction Status




You can perform any of the following actions in this screen:

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Click  icon to view the transaction information. This screen provides the details of the transactions handed off to the external system.

  The **Transaction Info** pop-up screen is displayed.


Figure 15-11 Transaction Info



- Click **View** button to view the transaction details. The following details are displayed based on the transaction status in the filters:
  - Transaction Reference
  - Transaction Status
  - Time Stamp
  - Teller ID
  - Teller Remarks
  - Approval Time Stamp
  - Supervisor ID
  - Supervisor Remarks
  - Override Info 
    Click **Override Info** icon to view the details for approval flow request.
- Click  icon to submit the transaction.
- Click  icon to discard the transaction.
- Click  icon to view advice.
- Click  icon to reverse the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-12 Servicing Journal (Grid View)



15.4 Types of Transaction Status

Transactions can be queries from the Journal Log based on the below **Transaction Status**.

- **All**: User can view all Transactions initiated by the **Teller ID**.
- **Completed**: View all transactions initiated by the **Teller ID** and are in Completed Status.
- **Sent Back**: View all transaction initiated by the Teller and are in **Sent Back** Status for further action by the teller/ Maker of the transaction.
- **Discarded**: All Transactions that initiated by the **Teller ID** selected in the query and are Discarded.
- **Reversed**: All Transactions that initiated by the **Teller ID** selected in the query and are Reversed.
- **Pending Approval**: All Transactions that are awaiting approval and the Logged in User (Checker) has the necessary privileges to approve.
- **Rejected**: All Transactions that initiated by the **Teller ID** selected and are Rejected.
- **Approved**: All the transactions that have been approved by the **Teller ID** selected in Query.
- **Sent for Approval**: All transactions that are initiated by the logged in user (Maker) and are in **Pending Approval** Status.

15.5 Reassign Transactions

Tellers and Supervisors can use the **Reassign Transactions** screen to re-assign the transactions that are pending approval to the other Supervisor or to unlock a locked transaction.


To reassign the Supervisor ID:

1. On the Homepage, from **Teller** mega menu, under **Journal Log**, click **Reassign Transactions** or specify **Reassign Transactions** in the search icon bar and select the screen.

   The **Reassign Transactions** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-13 Reassign Transactions



2. On the **Reassign Transactions** screen, specify the details fetch the records.

   For more information on fields, refer to the field description table.

Table 15-9 Reassign Transactions - Field Description

Field	Description
Branch Posting Date	Specify the branch posting date for which the inquiry is to be made. **Note** By default, the current posting date is displayed.
Teller ID	Select the Teller ID from the list of values.
Function Code	Specify the function code for which the inquiry is to be made. **Note** You can also click the search icon and select from the list of the maintained function codes.
Account Number	Specify the account number. **Note** The LOV fetches a list of the maintained account numbers.
Teller Sequence Prefix	Select from the list of values.
From Sequence Number	Specify the start number of the sequence range.
To Sequence Number	Specify the end number of the sequence range.
From Transaction Time	Specify the start time for filtering transactions executed within the given time range.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-9 (Cont.) Reassign Transactions - Field Description

Field	Description
To Transaction Time	Specify the end time for filtering transactions executed within the given time range.
From Amount Range	Specify the “from” amount of the amount range.
To Amount Range	Specify the “to” amount of the amount range.
Journal Log Type	Select the type from the drop-down values (**Electronic Journal** or **Servicing Journal**).
Transaction Status	Select the transaction status from the drop-down values (**Sent Back** or **Pending Approval**).


3. After you specify the necessary fields, you can perform one of the following actions:

Table 15-10 Basic Actions

Action	Description
Fetch	Click **Fetch** to get the list of transactions based on the query criteria specified. When you click **Fetch**, the following details are displayed for each transaction: • **Function Code and Screen Name** • **Transaction Reference Number** • **Teller Sequence Number** • **Transaction Amount** • **Account Number** • **Teller ID** • **Teller Remarks** • **Supervisor ID** • **Supervisor Remarks**
Clear	Click **Clear** to clear the transaction list.

The transactions fetched based on the search criteria are displayed in Tile View. In the Tile View, you can click the necessary icons to perform the operations.

Figure 15-14 List of Transactions



In the transaction record, you can perform one of the following operations:

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-11 Actions for Transaction Record

Action	Description
	Click on this icon to unlock the transaction.
	Click on this icon to reassign the Supervisor ID for the transaction.

15.6 Natural Electronic Journal

Tellers and Supervisors can use the **Natural Electronic Journal** screen to view the status of the cash transactions performed by them on the posting date.


For information on the common operations and icons on this screen, refer to About Electronic and Servicing Journals.

To view the status of the cash transactions:

1. On the Homepage, from **Teller** mega menu, under **Journal Log**, click **Natural Electronic Journal** or specify **Natural Electronic Journal** in the search icon bar and select the screen.

   The **Natural Electronic Journal** screen is displayed.

Figure 15-15 Natural Electronic Journal



2. On the **Natural Electronic Journal** screen, specify the details.

   For more information on fields, refer to the field description table.

Table 15-12 Natural Electronic Journal - Field Description

Field	Description
Natural Language Query	Specify the search **Query** in the natural language to fetch transaction details based on the desired filters resolved from natural language query.
	Click the **Speech Recognition Start button** to retrieve transaction details using the specified filters from a natural language query.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 15-12 (Cont.) Natural Electronic Journal - Field Description


Field	Description
Submit	Click the **Submit** option to fetch the transaction details from the query entered in natural language.
Teller ID	Click Search icon and select the **Teller ID** from the list of values.
Branch Posting Date	Specify the branch posting date for which the inquiry is to be made. **Note:** By default, the current posting date is displayed.
Transaction Status	Select the Transaction Status from the drop-down values.
Transaction Reference	Specify the transaction reference number.
Function Code	Click Search icon and select the Function Code from the list of values.
Account Number	Click Search icon and select the Account Number from the list of values.
Transaction Currency	Click Search icon and select the Transaction Currency from the list of values.

3. Click  icon to filter the results on the tile/grid view based on the search criteria.

   The **Filters** overlays screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-16 Filters (Natural Electronic Journal)



4. On the **Filters** overlays screen, specify the details to fetch the records.

   For more information on fields, refer to the field description table.

Table 15-13 Filters - Field Description

Field	Description
Teller ID	Specify the Teller ID. **Note:** You can also click the search icon and select the Teller ID from the list of values.
Function Code	Specify the function code for which the inquiry is to be made. **Note:** You can also click the search icon and select the Teller ID from the list of values.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 15-13 (Cont.) Filters - Field Description

Field	Description
Branch Posting Date	Specify the branch posting date for which the inquiry is to be made. **Note:** By default, the current posting date is displayed.
Account Number	Specify the account number. **Note:** You can also click the search icon and select the Teller ID from the list of maintained account numbers.
Teller Sequence Prefix	Click the search icon and select from the list of values.
Transaction Status	Select the transaction status from the drop-down values. **Note:** By default, **Sent Back** status is selected.
Transaction Reference	Specify the transaction reference number.
From Sequence Number	Specify the start number of the sequence range.
To Sequence Number	Specify the end number of the sequence range.
From Transaction Time	Specify the start time for filtering transactions executed within the given time range.
To Transaction Time	Specify the end time for filtering transactions executed within the given time range.
From Amount Range	Specify the “from” amount of the amount range.
To Amount Range	Specify the “to” amount of the amount range.
Transaction Currency	Click the search icon and select the transaction currency from the list of values.

5. After you specify the necessary fields, click **Apply** to fetch the transaction details.


   The **Natural Electronic Journal** screen displays.

Figure 15-17 Natural Electronic Journal (List View) - Completed Transaction Status



Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 15-18 Natural Electronic Journal (List View) - Sent Back Transaction Status



You can perform any of the following actions in this screen:

- Click  icon to view the transaction information. This screen provides the details of the transactions handed off to the external system.

  The **Transaction Info** pop-up screen is displayed.

Figure 15-19 Transaction Info




- Click **View** button to view the transaction details. The following details are displayed based on the transaction status in the filters:
  - Transaction Reference
  - Transaction Status
  - Time Stamp
  - Teller ID
  - Teller Remarks
  - Approval Time Stamp
  - Supervisor ID
  - Supervisor Remarks
  - Override Info 
    Click **Override Info** icon to view the details for approval flow request.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- Click  icon to submit the transaction.
- Click  icon to discard the transaction.
- Click  icon to view advice.
- Click  icon to reverse the transaction.

Figure 15-20 Natural Electronic Journal (Grid View)



Function Code	Transaction Reference	Teller Sequence	Transaction Currency	Transaction Amount	Account Number	Account Name	Teller ID	Teller Remarks	Transaction Status	Action
1401- Cash Deposit	006253340007f438	241	GBP	GBP 10,000.00	1006000000000020	NA	REMOTLR7	Auto Approval	Completed	
1401- Cash Deposit	006253340007f437	240	GBP	GBP 10,000.00	1006000000000020	NA	REMOTLR7	No Comments	Completed	
1401- Cash Deposit	006253340007f358	238	GBP	GBP 10,000.00	1006000000000020	NA	REMOTLR7	Auto Approval	Completed	
1401- Cash Deposit	006253340007f357	237	GBP	GBP 10,000.00	1006000000000020	NA	REMOTLR7	No Comments	Completed	
1401- Cash Deposit	006253340007f185	235	USD	USD 150.00	1006000000000020	NA	REMOTLR7	No Comments	Completed	
1401- Cash Deposit	006253340007f183	234	USD	USD 150.00	1006000000000020	NA	REMOTLR7	No Comments	Completed	
1401- Cash Deposit	006253340007f180	232	GBP	GBP 10,000.00	1006000000000020	NA	REMOTLR7	Auto Approval	Completed	
1401- Cash Deposit	006253340007f165	227	GBP	GBP 100.00	1006000000000155	JOHN DOE	REMOTLR7	No Comments	Completed	
1401- Cash Deposit	006253340007f151	226	GBP	GBP 10,000.00	1006000000000020	NA	REMOTLR7	No Comments	Completed	
1401- Cash Deposit	006253340007f150	225	GBP	GBP 10,000.00	1006000000000020	NA	REMOTLR7	No Comments	Completed	

Copyright © 2021, 2025, Oracle and/or its affiliates.

16
Prediction

The screen under the **Prediction** menu is used to predict the number of service counters.

This topic contains the following subtopics:

- Teller Service Counters Prediction
  The **Teller Service Counters Prediction** screen is used to predict the number of Teller service counters required for the specified days.
- Cash Prediction
  The **Cash Prediction** screen is used to predict the amount of liquid cash required to prevent shortage and overage of branch cash for a respective currency for the next N number of days i.e. cash required for the branch to work efficiently for that respective day.
- Large Language Model Training
  The topic describes about the Large Language Model (LLMs) Training.

16.1 Teller Service Counters Prediction


The **Teller Service Counters Prediction** screen is used to predict the number of Teller service counters required for the specified days.

To predict the number of Teller service counters:

1. On the Homepage, from **Teller** mega menu, under **Prediction**, click **Teller Service Counters Prediction** or specify **Teller Service Counters Prediction** in the search icon bar and select the screen.

   The **Teller Service Counters Prediction** screen is displayed.

Figure 16-1 Teller Service Counters Prediction



2. On the **Teller Service Counters Prediction** screen, specify the details fetch the records. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Table 16-1 Teller Service Counters Prediction - Field Description

Field	Description
Current Service Time (Minutes)	Specify the time to service business transactions at the Teller counter.
Branch Customer Lounge Capacity (Persons)	Specify the number of persons that can be accommodated at one time in the physical service area of the Branch.
Physical Teller Counters (Number)	Specify the physical teller counters available at the branch.
Planned Queue Waiting Time (Minutes)	Specify the waiting time to be achieved at the queue.
Prediction Days	Specify the number of days in the future where the Teller counters are required to be predicted.

3. Click **Go**.

   The predicted value of Teller service counters is displayed. A sample prediction of Teller service counters based on certain values is shown below.

Figure 16-2 Teller Service Counters Prediction - Sample



16.2 Cash Prediction

The **Cash Prediction** screen is used to predict the amount of liquid cash required to prevent shortage and overage of branch cash for a respective currency for the next N number of days i.e. cash required for the branch to work efficiently for that respective day.


To predict the Branch Cash:

1. On the Homepage, from **Teller** mega menu, under **Prediction**, click **Cash Prediction** or specify **Cash Prediction** in the search icon bar and select the screen.

   The **Cash Prediction** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 16-3 Cash Prediction



2. On the **Cash Prediction** screen, specify the details fetch the records.

> **Note**
>
> The fields marked as **Required** are mandatory.


Table 16-2 Cash Prediction - Field Description

Field	Description
Prediction Days	Specify the number of days in the future where the branch cash are required to be predicted.
Currency	Click the  icon and select the currency from the list.

3. Click **Go**.

The predicted value of Branch Cash is displayed. A sample prediction of Branch Cash based on certain values is shown below.

Figure 16-4 Cash Prediction - Sample



Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 16-3 Branch Cash Flow Prediction - Field Description

Field	Description
Cash in Hand	The cash on hand accurately reflects the total cash held by the branch.
Predicted Amount	The predicted cash needed at the branch for the upcoming specified number of days is shown by the anticipated amount.
Upper Bound	The Upper Bound indicates the maximum amount of cash that the branch requires during the following specified number of prediction days.
Lower Bound	The Lower Bound specifies the amount of cash the branch require on available for the upcoming number of prediction days.

16.3 Large Language Model Training


The topic describes about the Large Language Model (LLMs) Training.

To view the LLMs Training:

1. On the Homepage, from **Teller** mega menu, under **Prediction**, click **LLMs Training** or specify **LLMs Training** in the search icon bar and select the screen.

   The **LLMs Training** screen is displayed.

Figure 16-5 Large Language Training



2. On the **LLMs Training** screen, specify the fields.

   For more information on fields, refer to the field description table.

Table 16-4 LLMs Training - Field Description

Field	Description
Usecase Name	The function of training the LLM for the user is to identify the usecase.
Subcase Name	The specific subcase that is a part of a usecase.
Document Category	The directory on the server where all documents are generally stored and subcase is trained on the directory.

Copyright © 2021, 2025, Oracle and/or its affiliates.


3. Displays the **Prompt**. The dynamic prompt which can be used to query the LLM for the subcase.
4. Click the **Drop file** option to upload the LLM Training Document. Upload multiple PDF documents for which the user wants to the LLM.

> **Note**
>
> Upload at least one file to proceed with Gen-AI model training.

5. Click **Submit**.

   Displays the **Success** Pop-up screen.

Figure 16-6 Success



Copyright © 2021, 2025, Oracle and/or its affiliates.

17

Customer Service

The screens under the **Customer Service** menu are used for customer services and inquiries.

This topic contains the following subtopics:

- Cheque Status Inquiry
  The Teller can use the **Cheque Status Inquiry** screen to query the details of a cheque by specifying the account number and cheque number of the customer.
- Stop Cheque Request
  The Teller can use the **Stop Cheque Request** screen to initiate stop payment of cheque as requested by the customer.
- Cheque Book Request
  The **Cheque Book Request** screen is used to initiate the cheque book request for a customer account.
- Passbook Issue
  The Teller can use the **Passbook Issue** screen to issue a new passbook for a customer account.
- Passbook Update
  The Teller can use the **Passbook Update** screen to update the passbook of a customer account.
- Passbook Status Change
  The Teller can use the **Passbook Status Change** screen to initiate the status change for a passbook of a customer account.
- Passbook Reprint
  The Teller can use the **Passbook Reprint** screen to reprint the passbook of a customer account.
- Account Balance Inquiry
  The Teller can use the **Account Balance Inquiry** screen to inquire about the account balance details of a customer account.
- Account Statement Request
  The Teller can use the **Account Statement Request** screen to initiate an account statement request for a customer account.
- Customer Address Update
  The Teller can use the **Customer Address Update** screen to initiate a service request to update the customer address details.
- Account Address Update
  The Teller can use the **Account Address Update** screen to initiate a service request to update the address details of the customer account.
- Customer Contact Update
  The **Customer Contact Update** screen is used to initiate a service request to update the customer contact details.
- Cheque Book Status Change
  The **Cheque Book Status Change** screen is used to change the status of a cheque book.

Copyright © 2021, 2025, Oracle and/or its affiliates.

17.1 Cheque Status Inquiry


The Teller can use the **Cheque Status Inquiry** screen to query the details of a cheque by specifying the account number and cheque number of the customer.

To query the details of a cheque:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Cheque Status Inquiry** or specify **Cheque Status Inquiry** in the search icon bar and select the screen.

   The **Cheque Status Inquiry** screen is displayed.

Figure 17-1 Cheque Status Inquiry



2. On the **Cheque Status Inquiry** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-1 Cheque Status Inquiry - Field Description

Field	Description
Account Number	Specify the account number for which the cheque status needs to be enquired.
Cheque Number	Specify the cheque number.
Query	Click **Query** to fetch the details of the cheque.
Clear	Click **Clear** to clear the details.
Account Name	Displays the name of the account holder.
Account Branch	Displays the account branch code.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-1 (Cont.) Cheque Status Inquiry - Field Description

Field	Description
Customer ID	Displays the customer ID of the account.
Cheque Status	Displays the status of the cheque (**Used**, **Unused**, or **Stopped**).
Value Date	Displays the date specified on the cheque.
Cheque Amount	Displays the cheque amount.
Beneficiary	Displays the name of the beneficiary.

17.2 Stop Cheque Request

The Teller can use the **Stop Cheque Request** screen to initiate stop payment of cheque as requested by the customer.


A stop payment request is an instruction given by a customer to the bank directing it to stop payment against a Cheque. This instruction can be based on a single cheque or a range of cheque numbers.

To initiate stop payment of cheque:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Stop Cheque Request** or specify **Stop Cheque Request** in the search icon bar and select the screen.

   The **Stop Cheque Request** screen is displayed.

Figure 17-2 Stop Cheque Request



2. On the **Stop Cheque Request** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-2 Stop Cheque Request - Field Description

Field	Description
Account Number	Specify the account number for which you need to enforce a stop payment.
Cheque Number	Specify the cheque number on which the stop payment is to be enforced.
Select Multiple Cheques	Select this option to enforce stop payment on multiple cheques of the customer account.
Cheque Amount	Specify the cheque amount for which the cheque is drawn. The cheque currency is defaulted to account currency.
Effective Date	Specify the date on which the cheque is drawn.
Expiry Date	Specify the expiry date of the cheque.
Reason Type	Specify the type of stop payment (**Stop** or **Lost**).
Total Charge Amount	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Multi-Currency Configuration` at the Function Code Indicator level is set as `Y`.
Narrative	The system displays the default narrative as **Stop Cheque Request**, and it can be modified. You can specify the reason/purpose for which the stop payment is issued.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   The request is handed off to the core FLEXCUBE Universal Banking system to update the stop payment status in Customer Accounts Maintenance to indicate the presence of a stop payment instruction for the customer account.

17.3 Cheque Book Request

The **Cheque Book Request** screen is used to initiate the cheque book request for a customer account.


To initiate the cheque book request:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Cheque Book Request** or specify **Cheque Book Request** in the search icon bar and select the screen.

   The **Cheque Book Request** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 17-3 Cheque Book Request



2. On the **Cheque Book Request** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-3 Cheque Book Request - Field Description

Field	Description
Account Number	Specify the account number for which the cheque book request is to be initiated.
Cheque Book Type	Click the search icon, and select the checkbook type from the list of values.
Number of Leaves	Select the number of leaves from the following drop-down values: • **10** • **25** • **50** • **100**
First Cheque Number	Specify the number of the first cheque.
Request Date	By default, the current posting date is displayed as the request date.
Request Status	Select the request status from the drop-down values (**Requested** or **Delivered**).
Deliver To	Specify the mode of delivery (**Branch** or **Post**).

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-3 (Cont.) Cheque Book Request - Field Description

Field	Description
Address Line 1 to **Address Line 4**	Specify the address of the Customer if the delivery mode is selected as **Post**. **Note** By default, the address of the customer account is displayed, and it can be modified.
Narrative	Displays the default narrative as **Cheque Book Request**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   The request is handed off to the core FLEXCUBE Universal Banking system for the cheque book issuance of the customer account.

17.4 Passbook Issue

The Teller can use the **Passbook Issue** screen to issue a new passbook for a customer account.


To issue a new passbook:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Passbook Issue** or specify **Passbook Issue** in the search icon bar and select the screen.

   The **Passbook Issue** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 17-4 Passbook Issue



2. On the **Passbook Issue** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-4 Passbook Issue - Field Description

Field	Description
Account Number	Specify the account number for which the passbook needs to be issued.
Account Currency	Displays the currency of the specified account number.
Account Name	Displays the name of the specified account number.
Account Branch	Displays the branch code of the specified account number.
Account Open Date	Displays the account opening date.
Customer ID	Displays the customer ID.
Address Line 1 to **Address Line 4**	Specify the address of the customer.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-4 (Cont.) Passbook Issue - Field Description

Field	Description
Passbook Number	Displays the passbook number that needs to be issued. **Note** The passbook number is generated based on the instrument number maintenance.
Passbook Status	By default, the passbook status is displayed as **Issued**.
Total Charge Amount	Displays the total charge amount, which is computed by the system in the local currency of the branch. **Note** This field is displayed only if `Multi-Currency Configuration` at Function Code Indicator level is set as `Y`.
Passbook Category	Click the search icon, and select the passbook category from the list of values.
Narrative	Displays the default narrative as **Passbook Issue**, and it can be modified.
Old Passbook Details	Specify the fields.
Passbook Number	Displays the old passbook number that is issued to the customer account.
Issue Date	Displays the issue date of the old passbook.
Status Movement	Displays the current status of the passbook.
Status Change Date	Displays the date on which the current status got modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   The passbook issue request is handed off to the FLEXCUBE Universal Banking system to update the passbook issue request for the customer account.

17.5 Passbook Update

The Teller can use the **Passbook Update** screen to update the passbook of a customer account.


To update the passbook:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Passbook Update** or specify **Passbook Update** in the search icon bar and select the screen.

   The **Passbook Update** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 17-5 Passbook Update



2. On the **Passbook Update** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-5 Passbook Update - Field Description

Field	Description
Account Number	Specify the account number for which the passbook needs to be updated.
Account Branch	Displays the branch code of the specified account number.
Account Name	Displays the name of the specified account number.
Passbook Number	Displays the passbook number that needs to be updated.
Start Line	Specify the start line of the passbook to enter the transaction details.
Previous Balance	Displays the previous balance in the passbook.
Compression Required	Check this box to modify the defaulted values related to transaction compression.
Compression Start Date	Displays the compression start date.
Compression End Date	Displays the compression end date.

3. Click **Submit**.

   The request is handed off to the core FLEXCUBE Universal Banking system to fetch and update the passbook statement of the customer account.

17.6 Passbook Status Change

The Teller can use the **Passbook Status Change** screen to initiate the status change for a passbook of a customer account.


To initiate the status change of a passbook:

Copyright © 2021, 2025, Oracle and/or its affiliates.

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Passbook Status Change** or specify **Passbook Status Change** in the search icon bar and select the screen.

   The **Passbook Status Change** screen is displayed.

Figure 17-6 Passbook Status Change



2. On the **Passbook Status Change** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-6 Passbook Status Change - Field Description

Field	Description
Account Number	Specify the account number for which the passbook status change is required.
Account Branch	Displays the branch code of the specified account number.
Account Name	Displays the name of the specified account number.
Customer ID	Displays the customer ID of the specified account number.
Passbook Number	Displays the current passbook number of the customer account.
Issue Date	Displays the date of issue of the current passbook number.
Passbook Status	Select the passbook status to be changed from the following drop-down values: • **Active** • **Close** • **Reissue**

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-6 (Cont.) Passbook Status Change - Field Description

Field	Description
Status Description	Displays the description of the selected status.
Status Change Date	Displays the current posting date as the status change date.
Narrative	Displays default the narrative as **Passbook Status Change**, and it can be modified.
Old Passbook Details	Specify the fields.
Passbook Number	Displays the old passbook number of the customer account.
Issue Date	Displays the issue date of the old passbook.
Status Movement	Displays the current status of the old passbook number.
Status Description	Displays the description of the status of the old passbook number.
Status Change Date	Displays the date on which the old passbook is modified.

3. Click **Submit**.

   The request is handed off to the FLEXCUBE Universal Banking system for updating the status change of the old passbook number.

17.7 Passbook Reprint


The Teller can use the **Passbook Reprint** screen to reprint the passbook of a customer account.

To reprint the passbook:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Passbook Reprint** or specify **Passbook Reprint** in the search icon bar and select the screen.

   The **Passbook Reprint** screen is displayed.

Figure 17-7 Passbook Reprint



2. On the **Passbook Reprint** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-7 Passbook Reprint - Field Description

Field	Description
Account Number	Specify the account number for which the passbook needs to be updated.
Account Branch	Displays the branch code of the specified account number.
Account Name	Displays the name of the specified account number.
Account Currency	Displays the account currency.
Reprint Basis	Select the reprint basis from the following options: • **Reporting Based on Transaction** • **Reporting Based on Date**
Last Number of Transactions	Specify the last number of transactions. **Note** This field is enabled only if **Reprint Basis** is selected as **Transaction**.
From Date	Specify the date from which the transactions need to be printed. **Note** This field is enabled only if **Reprint Basis** is selected as **Date**.
To Date	Displays the current date. **Note** This field is enabled only if **Reprint Basis** is selected as **Date**.
Narrative	Displays the narrative as **Passbook Reprint**, and it can be modified.

3. Click **Submit**.

The request is handed off to the core FLEXCUBE Universal Banking system to fetch the details and reprint the passbook of the customer account.

Copyright © 2021, 2025, Oracle and/or its affiliates.

17.8 Account Balance Inquiry


The Teller can use the **Account Balance Inquiry** screen to inquire about the account balance details of a customer account.

To inquire about the account balance details:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Account Balance Inquiry** or specify **Account Balance Inquiry** in the search icon bar and select the screen.

   The **Account Balance Inquiry** screen is displayed.

Figure 17-8 Account Balance Inquiry



2. On the **Account Balance Inquiry** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-8 Account Balance Inquiry - Field Description


Field	Description
Customer Account	Specify the account number for which the account balance needs to be enquired.
Query	Click **Query** to fetch and display the details.
Clear	Click **Clear** to clear the details.
Account Currency	Displays the currency for which the account balance needs to be enquired.
Account Name	Displays the name of the specified account number.
Account Class	Displays the account class of the specified account number.
Account Class Description	Displays the description of the account class.
Account Open Date	Displays the date on which the account is opened.
Account Type	Displays the type of the account.
Mode of Operation	Displays the mode of operation.
Balance Details	Specify the fields.
Current Balance	Displays the current balance of the account.
Uncollected	Displays the uncollected balance.
Blocked	Displays the blocked balance.
Available	Displays the balance available in the specified account.
Total Available	Displays the total available balance.
Book Balance	Displays the book balance.
Sweep Enabled	Check this box if sweep needs to be enabled.
Sweep Eligible Balance	Displays the sweep eligible balance.
ILM Sweep Eligible Balance	Displays the ILM sweep eligible balance.
Temporary Overdraft Limit	Displays the temporary overdraft limit.
Net Balance	Displays the net balance.
Passbook Balance	Displays the passbook balance.
Account Status	Specify the fields.
Posting Allowed	Select this checkbox if posting is allowed for the account.
Stop Payment	Select this checkbox if stop payment is allowed for the account.
No Credit	Select this checkbox if credit is not allowed for the account.
Debit Override	Select this checkbox if debit override is allowed for the account.
Overdraft	Select this checkbox if the overdraft is allowed for the account.
Dormant	Select this checkbox if the account is dormant.
Frozen	Select this checkbox if the account is frozen.
No Debit	Select this checkbox if the debit is not allowed for the account.
Credit Override	Select this checkbox if credit override is allowed for the account.
Status Change Automatic	Select this checkbox if the automatic status change is allowed.

3. Click on the **Interest and Charges Details** data segment.

   The **Interest and Charges Details** data segment is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 17-9 Interest and Charges Details



4. On the **Interest and Charges Details** segment, view the details. For more information on fields, refer to the field description table.

Table 17-9 Interest And Charge Details - Field Description

Field	Description
Accrued Interest (Dr)	Displays the debit accrued interest.
Accrued Interest (Cr)	Displays the credit accrued interest.
Interest Due	Displays the interest due.
Charges Due	Displays the charges due.
Last Interest Debit	Displays the last interest debit.
Last Interest Credit	Displays the last interest credit.
Last DR Activity	Displays the last DR activity.

5. Click on the **Turnover Details** data segment.

   The **Turnover Details** data segment is displayed.

Figure 17-10 Turnover Details



6. On the **Turnover Details** segment, view the details. For more information on fields, refer to the field description table.

Table 17-10 Turnover Details - Field Description

Field	Description
Opening	Displays the opening turnover details.
Daily Turnover (Dr)	Displays the debit daily turnover.
Daily Turnover (Cr)	Displays the credit daily turnover.
Current (ACY)	Displays the current (ACY).

Copyright © 2021, 2025, Oracle and/or its affiliates.

17.9 Account Statement Request


The Teller can use the **Account Statement Request** screen to initiate an account statement request for a customer account.

To initiate account statement request:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Account Statement Req** or specify **Account Statement Req** in the search icon bar and select the screen.

   The **Account Statement Request** screen is displayed.

Figure 17-11 Account Statement Request



2. On the **Account Statement Request** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-11 Account Statement Request - Field Description

Field	Description
Customer Account	Specify the account number for which the account statement needs to be requested.
Account Name	Displays the name of the specified account number.
Request Date	Displays the current posting date as the request date.
Statement Type	Specify the type of statement requested (**Detailed** or **Summary**).
From Date	Specify the start date for the date range.
To Date	Specify the end date for the date range.
Balance Type	Specify if the account statement needs to be generated based on Book Date or Value Date.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-11 (Cont.) Account Statement Request - Field Description

Field	Description
Narrative	Displays the default narrative as **Account Statement**, and it can be modified.

3. Specify the charge details. For information on the fields in the **Charge Details** segment, refer to Charge Details.
4. Click **Submit**.

   The request is handed off to the FLEXCUBE Universal Banking system to initiate an account statement request.

17.10 Customer Address Update


The Teller can use the **Customer Address Update** screen to initiate a service request to update the customer address details.

To update the customer address:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Cust Address Update** or specify **Cust Address Update** in the search icon bar and select the screen.

   The **Customer Address Update** screen is displayed.

Figure 17-12 Customer Address Update



2. On the **Customer Address Update** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-12 Customer Address Update - Field Description

Field	Description
Customer Number	Specify the customer number for which the address details need to be updated.
Customer Name	Displays the customer name for the customer number specified.
Correspondence Address	Specify the fields.
Address Line 1 to **Address Line 4**	Displays the maintained address details, and it can be modified.
Country Code	Displays the maintained address details, and it can be modified.
Permanent Address	Specify the fields.
Same as Correspondence Address	Select this checkbox to populate the **Correspondence Address** to **Permanent Address**.
Address Line 1 to **Address Line 4**	Displays the maintained address details, and it can be modified.
Country Code	Displays the maintained Country code, and it can be modified.
Residential Address	Specify the fields.
Same as Permanent Address	Select this checkbox to populate the **Permanent Address** details to **Residential Address**.
Address Line 1 to **Address Line 4**	Displays the maintained address details, and it can be modified.
Country Code	Displays the maintained country code, and it can be modified.
Narrative	Displays the default narrative as **Customer Address Update**, and it can be modified.
Review and Submit	Click **Review and Submit** to review the request details and submit.

3. Click **Submit**.

   The request details are handed off to the FLEXCUBE Universal Banking system for the customer address update.

17.11 Account Address Update

The Teller can use the **Account Address Update** screen to initiate a service request to update the address details of the customer account.


To update the account address:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Account Address Update** or specify **Account Address Update** in the search icon bar and select the screen.

   The **Account Address Update** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 17-13 Account Address Update



2. On the **Account Address Update** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-13 Account Address Update - Field Description

Field	Description
Account Number	Specify the customer account number for which the address details need to be updated.
Account Branch	Displays the customer name for the customer number specified.
Correspondence Address	Specify the fields.
Address Line 1 to **Address Line 4**	Displays the maintained address details, and it can be modified.
Country Code	Displays the maintained address details, and it can be modified.
Narrative	Displays the default narrative as **Account Address Update**, and it can be modified.
Review and Submit	Click **Review and Submit** to review the request details and submit.

3. Click **Submit**.

   The request details are handed off to the FLEXCUBE Universal Banking system for the account address update.

17.12 Customer Contact Update

The **Customer Contact Update** screen is used to initiate a service request to update the customer contact details.


To update the customer contact details:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Cust Contact No Update** or specify **Cust Contact No Update** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **Customer Contact Update** screen is displayed.

Figure 17-14 Customer Contact Update



2. On the **Customer Contact Update** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-14 Customer Contact Update - Field Description

Field	Description
Customer Number	Specify the customer number for which the contact details need to be updated.
Customer Name	Displays the customer name for the customer number specified.
Customer Details	Specify the fields.
Mobile Phone	Displays the mobile number, and it can be modified.
Work Phone	Displays the work phone number, and it can be modified.
Residential Phone	Displays the residential phone number, and it can be modified.
Fax Phone	Displays the fax phone number, and it can be modified.
Preferred Contact Time	Displays the preferred contact time, and it can be modified.
Preferred Communication Mode	Displays the communication mode, and it can be modified.
Email Address	Displays the email id of the customer, and it can be modified.
Alternate Email Address	Displays the alternate email id of the customer, and it can be modified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-14 (Cont.) Customer Contact Update - Field Description

Field	Description
Narrative	Displays the default narrative as **Contact Details Update**, and it can be modified.
Review and Submit	Click **Review and Submit** to review the request details and submit.

3. Click **Submit**.

   The request details are handed off to the FLEXCUBE Universal Banking system for updating customer contact details.

17.13 Cheque Book Status Change


The **Cheque Book Status Change** screen is used to change the status of a cheque book.

To change the cheque book status:

1. On the Homepage, from **Teller** mega menu, under **Customer Service**, click **Cheque Book Status Change** or specify **Cheque Book Status Change** in the search icon bar and select the screen.

   The **Cheque Book Status Change** screen is displayed.

Figure 17-15 Cheque Book Status Change



2. On the **Cheque Book Status Change** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 17-15 Cheque Book Status Change - Field Description

Field	Description
Account Number	Specify the account number for which the cheque book status needs to be changed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 17-15 (Cont.) Cheque Book Status Change - Field Description

Field	Description
First Cheque Number	Specify the number of the first cheque.
Cheque Book Type	Select the cheque book type.
Request Status	Select the status that needs to be updated for the cheque book. The drop-down values are as follows: • **Delivered** • **Requested** • **Destroyed**
Narrative	Displays the default narrative as **Cheque Book Status Change**, and it can be modified.

3. Click **Submit**.

The request is handed off to the core FLEXCUBE Universal Banking system to change the status of the cheque book.

A teller sequence number is generated, and the `Transaction Completed Successfully` information message is displayed.

> **Note**
>
> The transaction is moved to authorization in case of any warning raised when the transaction saves.

Copyright © 2021, 2025, Oracle and/or its affiliates.


18

Branch Dashboard

The Branch Dashboard facilitates the integration of data from multiple screens and displays it as a dashboard on the application landing page.

It provides a comprehensive and consolidated snapshot in tiny windows to access information quickly. Thus, helping the bank staff to analyze, monitor, and make better decisions, which in turn helps to save time and cost. To access the Branch Dashboard, select **Dashboard** from the main menu.

Figure 18-1 Dashboard



The Branch Dashboard is designed to display the widgets distributed in rows without the vertical scroll bar. The widgets are as follows:


- Till Cash Position
- Inventory in Hand
- My Transaction Status
- Customer Search
- Current Till Position
- Frequent Customer Operations
- Frequent Branch Operations
- Customer Service Request
- Notifications
- Alerts
- Frequent Links
- Business Activity Monitoring

Copyright © 2021, 2025, Oracle and/or its affiliates.

Till Cash Position

This widget displays the currency-wise cash position of the Teller Id, which includes **Opening Balance**, **Total Debit**, and **Total Credit**, which happened for the day, and the Closing Balance. In addition, the system displays the denomination-wise count for the closing balance amount. The **FILTERS** option can be used to display Till cash position based on the currency, branch code, and date.


Figure 18-2 Till Cash Position



Inventory in Hand

This widget displays the list of inventory available with the branch.

Figure 18-3 Inventory in Hand



Copyright © 2021, 2025, Oracle and/or its affiliates.


> **Note**
>
> With Inventory (IV) Integration enabled, the Dashboard widget for Inventory in Hand is not Supported.

My Transaction Status

This widget displays the total transaction count performed by the logged-in Teller. Each slice represents the status-wise count of the transactions performed by the Teller.

The **FILTERS** option can be used to display transaction status based on the branch code, branch date, and transaction type (Cash/Non-Cash).


Figure 18-4 My Transaction Status



Customer Search

The Teller can use this widget to query and find a specific customer account. For more information on this segment, refer to Customer Search.

Figure 18-5 Customer Search



Copyright © 2021, 2025, Oracle and/or its affiliates.

Current Till Position

This widget displays the Till amount available for the logged-in Teller ID. The **FILTERS** option can be used to display the current Till amount based on the currency. The minimum and maximum values are fetched from the user preferences.

If the Logged in user is a Till and Vault user, then by default the Current till Position will be display and the user can use the Filter Option for select Till/Vault in addition to Currency Code. If the Logged in User is a Vault only User, then by default the system will display the Current Vault Position on Login.

Figure 18-6 Current Till Position





Figure 18-7 Current Vault Position




Copyright © 2021, 2025, Oracle and/or its affiliates.

Frequent Customer Operations

The Teller can use this widget to launch one of the frequently used **Customer Transactions** screens from the landing page. This option is easy to access instead of using **Menu Item Search** or navigating through the menu to process transactions.

Figure 18-8 Frequent Customer Operations




> **Note**
>
> The system displays an error message stating that the User does not have rights to access this screen if the user is trying to access the restricted screen in the widget.

Frequent Branch Operations

The Teller can use this widget to launch one of the frequently used **Branch Operations** screens from the landing page. This option is easy to access instead of using **Menu Item Search** or navigating through Menu to process transactions.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 18-9 Frequent Branch Operations




> **Note**
>
> The system displays an error message stating that the User does not have rights to access this screen if the user is trying to access the restricted screen in the widget.

Customer Service Request

The Teller can use this widget to launch one of the frequently used **Customer Service** screens from the landing page. This option is easy to access instead of using **Menu Item Search** or navigating through Menu to process transactions.

Figure 18-10 Customer Service Request




Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The system displays an error message stating that the User does not have rights to access this screen if the user is trying to access the restricted screen in the widget.

Notifications

The Teller can use this widget to view the bank-specific notifications or instructions provided for the bank staff. Generation of the notifications to be configured at the back-end.

Figure 18-11 Notifications




Alerts

The Teller is alerted through this widget on the user-specific information based on which the Teller has to act accordingly. Generation of the alerts to be configured at the back-end.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 18-12 Alerts



Frequent Links

The Teller can use this widget to access the frequently used links to refer for transaction submission and other operational activities during the day.

Figure 18-13 Frequent Links




Copyright © 2021, 2025, Oracle and/or its affiliates.

Business Activity Monitoring

The Teller can use this widget to access the Business Activity Monitoring to view the all transaction status of branch.

Figure 18-14 Business Activity Monitoring



Copyright © 2021, 2025, Oracle and/or its affiliates.

19

Branch Maintenance

The branch maintenance screens are used to perform the maintenance for processing the branch transactions.

This topic contains the following subtopics:

- Common Actions for Branch Maintenance
  The screens under the **Branch Maintenance** menu contain common icons to perform all or a few of the basic actions.
- Teller Branch Parameters
  The **Teller Branch Parameters Maintenance** screen is used to set the teller preferences for a branch.
- Branch Role Limits
  The **Branch Role Limits** screen is used to set the input and authorization limits for a specific role.
- Branch User Preferences
  The **Branch User Limits** screen is used to set preferences like Till/Vault Indicator, currency holding preferences, and currency limit preferences for the branch user.
- Denominations
  The **Denominations Maintenance** screen is used to maintain the standard currency denominations for each currency that the bank deals with.
- Charge Definitions
  The **Charge Definition Maintenance** screen is used to maintain the charge definitions.
- Function Code Definitions
  The **Function Code Definition** screen is used to specify the preferences for the function code.
- Function Code Preferences
  The **Function Code Preferences** screen is used to define the workflow preferences (validation preferences and authorization preferences) for a function code.
- Default Authorizer
  The **Default Authorizer** screen is used to define the default authorizer who can authorize a specific function code for a branch user.
- Accounting and Settlements
  The **Settlements Definition** screen is used to define the settlement and accounting parameters that are applicable for processing the branch transactions involving a function code.
- Instrument Numbers
  The **Instrument Number Maintenance** screen is used to maintain the instrument type for each branch.
- Inter Branch Transit Account
  The **Inter Branch Transit Account** screen is used to maintain inter-branch transit account for each branch using the receiving branch, vault, and currency combination.

Copyright © 2021, 2025, Oracle and/or its affiliates.

- External System
  The **External System Maintenance** screen is used to define the parameters for the external system.
- Channel Limits
  The **Channel Limits** screen is used to maintain the channel limits for a particular customer group.
- Account Group
  The **Account Group Maintenance** screen is used to create groups of the account codes, and these groups can be used for charge calculation.
- Branch Group
  The **Branch Group Maintenance** screen is used to create groups of the branch codes, and these groups can be used for charge calculation.
- Customer Group
  The **Customer Group Maintenance** screen is used to create groups of the customer codes, and these groups can be used for charge calculation.
- Create Charge Pricing
  The **Create Charge Pricing Maintenance** screen is used to maintain the charge pricing.
- View Charge Pricing
  The **View Charge Pricing Maintenance** screen is used to view the summary and details of charge pricing IDs.
- Charge Condition Group
  The **Charge Condition Group Maintenance** screen is used to create groups of the charge condition codes.
- Charge Decisions
  The **Charge Decision Maintenance** screen is used to maintain the charge decisions.
- Charge Decision Enquiry
  The **Charge Decision Enquiry** screen is used to inquire about the details of charge definition and charge pricing for the specified search criteria.
- Reject Codes
  The **Reject Code Maintenance** screen is used to maintain the reject codes.
- Clearing Network Codes
  The **Clearing Network** screen is used to maintain the clearing network codes.
- Denomination Variations
  The **Denomination Variation Maintenance** screen is used to maintain the denomination-wise variations.
- External Bank Codes
  The **External Bank Code** screen is used to maintain the bank codes and branch codes.
- Issuer Codes
  The **Issuer Code Maintenance** screen is used to maintain the issuer codes for TC transactions.
- Utility Providers
  The **Utility Provider Maintenance** screen is used to link the utility provider with a settlement account.
- Account Entitlement Restriction
  This screen is used to maintain the Account Entitlement Group by grouping the set of Customer accounts. To process this screen, type **Account Entitlement Restriction** in the **Menu Item Search** located at the left corner of the application toolbar and select the appropriate screen (or) do the following steps:

Copyright © 2021, 2025, Oracle and/or its affiliates.

- GST Rule Maintenance
  The **GST Rule Maintenance** screen is to maintain rule details applicable for collecting the SGST and CGST or IGST on charge collection on a particular screen. User will be able to maintain the different rates applicable for case.
- GST Branch Parameters
  The **GST Branch Parameters** screen is used to maintain the GST Identification Number (GSTIN) for the servicing branch and assign the GL codes for crediting the collected SGST, CSGT, and IGST respectively for a given GST state.
- Customer Account GST Parameters
  On the **Customer Account GST Parameter** screen, the user is responsible for maintaining the GST Identification Number (GSTIN) applicable for a customer account within the GST state code.

19.1 Common Actions for Branch Maintenance

The screens under the **Branch Maintenance** menu contain common icons to perform all or a few of the basic actions.

The following are the symbols/icons you are likely to find in the branch maintenance screens:

Table 19-1 Symbols

Icon	Description
	Click this icon to search the configured records based on the specified search criteria. The input fields to search the records are displayed based on the maintenance screen.
	Click this icon to reset the search results to the default summary view.
	Click this icon to add a new record.

Table 19-2 Common Actions for Maintenance Screens

Icon	Description
Save	Click **Save** to save the changes and view the configured details in the summary view.
Cancel	Click **Cancel** to terminate the operation.

On the records displayed in the summary view, you can perform one of the following actions:

Table 19-3 Common Actions for Records

Action	Description
New	Create a new record.
Unlock	Modify the details and save.
Delete	Delete an unauthorized record.
Authorize	Authorize the record.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-3 (Cont.) Common Actions for Records

Action	Description
Close	Close the record.
Reopen	Re-open a closed record.
Audit	Audit the record.

19.2 Teller Branch Parameters


The **Teller Branch Parameters Maintenance** screen is used to set the teller preferences for a branch.

To maintain teller branch parameters:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Teller Branch Parameters Maintenance** or specify **Teller Branch Parameters Maintenance** in the search icon bar and select the screen.

   The **Teller Branch Parameters Maintenance** summary screen is displayed.

Figure 19-1 Teller Branch Parameters Maintenance (Summary)




2. Click the  icon.

   The **Teller Branch Parameters Maintenance** (New) screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-2 Teller Branch Parameters Maintenance (New)



3. On the **Teller Branch Parameters Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-4 Teller Branch Parameter Maintenance - Field Description

Field	Description
Branch Code	Select the branch code from the list of the available options.
Description	Displays the description of the branch.
Denomination Tracking Required	Specify the denomination that needs to be tracked for the **Vault**, **Till and Vault**, or **None**. The descriptions of the drop-down values are given below: • **Till and Vault** - To track denomination for Tills and Vault. By default, this option is selected. • **Vault** - To track denomination only for Vault, if a Vault is involved in the transaction. • **None** - To indicate that denomination tracking is not required for any transaction.
Currency Code	Specify the currency for which the **Minimum Cash Holding Limit** or **Maximum Cash Holding Limit** is to be maintained for the branch.
Minimum Cash Holding Limit	Specify the minimum cash holding limit for the branch.
Maximum Cash Holding Limit	Specify the maximum cash holding limit for the branch. **Note** The maximum cash holding amount must not be less than the minimum cash holding amount.
Action	Click the necessary icon to edit, save, or delete a row.

4. Click **Save**.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The summary view is displayed with the configured teller branch parameters.

19.3 Branch Role Limits


The **Branch Role Limits** screen is used to set the input and authorization limits for a specific role.

To maintain branch role limits:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Branch Role Limits** or specify **Branch Role Limits** in the search icon bar and select the screen.

   The **Branch Role Limits** summary screen is displayed.

Figure 19-3 Branch Role Limits (Summary)




2. Click the  icon.

   The **Branch Role Limits Maintenance** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-4 Branch Role Limits Maintenance



3. On the **Branch Role Limits Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-5 Branch Role Limits Maintenance - Field Description

Field	Description
Role ID	Select the role ID for which the limit preferences are to be set.
Role Description	Displays the role description for the selected **Role ID**.
Supervisor Role	Select if the defined role is a designated supervisor of the branch who has the authorization rights.
Limit Currency	Select the currency code in which the limits are to be specified.
Input Limit	Specify the transaction input limit for a single transaction.
Authorization Limit	Specify the maximum amount that the role is allowed to process while authorizing a transaction.
Action	Click the necessary icon to edit, save, or delete a row.

4. Click **Save**.

   The summary view is displayed with the configured branch role limits.

19.4 Branch User Preferences

The **Branch User Limits** screen is used to set preferences like Till/Vault Indicator, currency holding preferences, and currency limit preferences for the branch user.


To maintain branch user preferences:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Branch User Limits** or specify **Branch User Limits** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **Branch User Limits** summary screen is displayed.


Figure 19-5 Branch User Limits (Summary)



2. Click the  icon.

   The **User Preferences** screen is displayed.

Figure 19-6 User Preferences



3. On the **User Preferences** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-6 User Preferences - Field Description

Field	Description
Branch Code	Click the search icon, and select the branch code from the list of values.
User ID	Click the search icon, and select the user ID for which the branch preferences are to be maintained.
Till/Vault Indicator	Select from the following drop-down values: • **Till** • **Vault** • **Both** • **None**
Shortage/Overage GL	**Note** Currently not used, meant for future use.
Carry Forward Allowed	Select if the funds are allowed to carry forward for the next day.
Inter Branch Transactions Allowed	Select if the transfer between the branches is allowed.
Receive Email	Select if the Teller needs to receive emails for approval of transactions.
Receive Notification	Select if the Teller needs to receive notifications in Dashboard.
Currency Holding Preferences	Specify the fields.
Currency Code	Click the search icon, and select the currency code to specify the cash holding preferences.
Minimum Balance	Specify the minimum balance to be maintained for the Till or Vault.
Maximum Balance	Specify the maximum balance to be maintained for the Till or Vault.
Currency Limit Preferences	Specify the fields.
Currency Code	Click the search icon, and select the currency in which the limits (transactions amounts) will be expressed.
Max Transaction Amount	Specify the maximum transaction amount allowed that the user can enter in a single transaction.
Authorization Limit	Specify the maximum amount that the user (to which the limit role is associated) is allowed to process while authorizing a transaction.

4. Click **Save**.

   The summary view is displayed with the configured user preferences.

19.5 Denominations

The **Denominations Maintenance** screen is used to maintain the standard currency denominations for each currency that the bank deals with.

For example, the denominations for the currency USD can be maintained as follows:

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-7 Denominations Maintenance for USD Currency


CCY CODE	DENM CODE	DESCRIPTION	VALUE	NOTE / COIN
USD	D100	100 dollars	100	NOTE
USD	D50	50 dollars	50	NOTE
USD	D20	20 dollars	20	NOTE
USD	D10	10 dollars	10	NOTE
USD	D5	5 dollars	5	NOTE
USD	D1N	1 dollar	1	NOTE
USD	D1C	1 dollar	1	COIN
USD	C25	25 cents	0.25	COIN
USD	C10	10 cents	0.1	COIN
USD	C5	5 cents	0.05	COIN
USD	C1	1 cent	0.01	COIN

To maintain denominations:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Denominations Maintenance** or specify **Denominations Maintenance** in the search icon bar and select the screen.

   The **Denominations Maintenance** summary screen is displayed.

Figure 19-7 Denominations Maintenance (Summary)




2. Click the  icon.

   The **Denomination Maintenance** (New) screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-8 Denomination Maintenance



3. On the **Denomination Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-8 Denomination Maintenance - Field Description

Field	Description
Currency Code	Specify the currency for which the currency denomination is to be maintained.
Currency Description	Specify the description of the currency code.
Denomination Type	Select the denomination type.
Denomination Details	Specify the fields.
Denomination ID	Specify the denomination code.
Description	Specify the description of the denomination code.
Value	Specify the numeric value of the denomination code.
Sequence Number	Specify the number such that the denomination codes will be displayed in the same sequence maintained.
Type	Specify the type as **Coin** or **Note**.
Large Denomination	Select if a particular denomination is to be maintained as a large denomination.
Action	Click the necessary icon to edit, save, or delete a row.

4. Click **Save**.

   The summary view is displayed with the configured denominations.

Copyright © 2021, 2025, Oracle and/or its affiliates.

19.6 Charge Definitions


The **Charge Definition Maintenance** screen is used to maintain the charge definitions.

To maintain charge definitions:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Charge Definition Maintenance** or specify **Charge Definition Maintenance** in the search icon bar and select the screen.

   The **Charge Definition Maintenance** summary screen is displayed.


Figure 19-9 Charge Definition Maintenance (Summary)



2. Click the  icon.

   The **Charge Definition Maintenance** (New) screen is displayed.

Figure 19-10 Charge Definition Maintenance (New)



Copyright © 2021, 2025, Oracle and/or its affiliates.

3. On the **Charge Definition Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-9 Charge Definition Maintenance - Field Description

Field	Description
Charge Code	Specify the charge code.
Charge Description	Specify the description of the charge code.
Charge Category	Select the charge category (**Standard** or **Tax**).
Charge Credit Account	Specify the charge credit account for the transaction. You can also select the GL from the list of values or the *DR_LEG*/*CR_LEG*. **Note** • If *DR_LEG*/*CR_LEG* is selected, the corresponding debit/credit account of the transaction will be considered for the charge processing. For example, if the charge code is defined with **Charge Debit Account** as *DR_LEG* for a cash deposit function code, the charge will be collected from cash GL. Hence, the customer is expected to deposit cash including the charge amount. For such a charge code, the **Charge by Cash** field will be displayed as **Yes** in the charges data segment of the transaction screen. • Income GL in Charge Definition GL should not be the same as cash GL (offset Account/GL) maintained in Settlements Definition.
Charge Debit Account	Specify the charge debit account for the transaction. You can also select the GL from the list of values or the *DR_LEG*/*CR_LEG*. **Note** If *DR_LEG*/*CR_LEG* is selected, the corresponding debit/credit account of the transaction will be considered for the charge processing. For example, if the charge code is defined with **Charge Debit Account** as *DR_LEG* for a cash deposit function code, the charge will be collected from cash GL. Hence, the customer is expected to deposit cash including the charge amount. For such a charge code, the **Charge by Cash** field will be displayed as **Yes** in the charges data segment of the transaction screen.
Credit Transaction Code	Click the search icon and select the credit transaction code from the list of values.
Debit Transaction Code	Click the search icon and select the debit transaction code from the list of values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-9 (Cont.) Charge Definition Maintenance - Field Description

Field	Description
Pricing Source System	Specify the pricing source system. You can also select from the list of values. **Note** When OPDS is enabled, then the LOV will also fetch the values for the Pricing Source system - **OPDS-RP** from the Pricing Source System maintenance screen. To enable OPDS pricing, set PARAM_VALUE as **Y** for the `OPDS_INTEGRATED` in the SRV_TM_BC_PARAM_DTLS table
Pricing Source Description	Displays the description of the pricing source.
EDE Code	Displays the details of charge codes added to the table.
EDE Code	Specify the EDE Code. You can also select from the list of values.
EDE Description	Displays the description of the EDE code.
Action	Click the necessary icon to save, edit, or delete the values of a row.

4. Click **Save**.

   The summary view is displayed with the configured details of charge definitions.

19.7 Function Code Definitions

The **Function Code Definition** screen is used to specify the preferences for the function code.

For the list of function codes and the respective screen names, refer to List of Function Codes.


To maintain function code definitions:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Function Code Definition** or specify **Function Code Definition** in the search icon bar and select the screen.

   The **Function Code Definition** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-11 Function Code Definition



2. Click the  icon.

The **Function Code Definition** (New) screen is displayed.

Figure 19-12 Function Code Definition



Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> In **Function Code Definition** screen, reversal allowed flag will not be enabled for BC Payment Reversal, DD Payment Reversal, and Cash Remittance Reversal. The system displays an error message stating that the Reversal is not supported, making reversal allowed as N.

3. On the **Function Code Definition** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-10 Function Code Definition - Field Description

Field	Description
Function Code	Select from the list function codes that are factory shipped. For the list of function codes and the respective screen names, refer to List of Function Codes.
Function Code Description	Displays the description of the function code.
Transaction Limit	Specify the maximum transaction amount allowed for this function code in branch currency.
Support Child Function Code	Select if the specified function code needs to act as the parent function code.
Parent Function Code	Specify the applicable parent function code. **Note** This field is enabled only if the **Support Child Function Code** is not selected.
Next Date Transaction Allowed	Select if the next day transaction posting needs to be allowed for the specified function code.
Charge Details	Specify the fields.
Apply Charges	Specify if charges are applicable for this transaction.
Exchange Rate Details	Specify the fields.
Rate Code	Select the rate code for the transaction code.
Rate Type	Select the rate type for the transaction code.
Override Limit	Specify the override limit. The system displays the default override limit currency as GBP.
Stop Limit	Specify the stop limit. The system displays the default stop-limit currency as GBP.
Additional Preferences	Specify the fields.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-10 (Cont.) Function Code Definition - Field Description

Field	Description
Reversal Allowed	Specify if the reversal is allowed for the transaction. **Note** Reversal allowed will be disabled for remittances and clearing transactions. Hence, reversal will not be enabled in the journal log.
Reversal Requires Authorization	Specify if the authorization is required for a reversal transaction.
Reversal includes charges	Specify if the charges are to be reversed along with transaction reversal.
Reversal Advice Name	Specify the reversal advice name.
Input Slip Name	Specify the input slip name.
Input Slip Confirmation	Select if the input slip confirmation is required for the transaction. If this option is selected for a transaction screen, the **Input-Slip** button will be displayed on the screen. On the specified transaction screens, you can click **Input-Slip** to view the input slip before transaction submission. Once you click **Input-Slip**, the system validates mandatory fields. In addition, you can perform any of the following actions: • **Confirm and Print** – This icon is enabled only if Input Slip Confirmation is selected in the **Function Code Definition** screen. In addition, the transaction can be submitted only if the receipt is confirmed. Click this button to confirm and print the receipt. • **Print** – Click **Print** to print the generated slip and provide it to the customer. • **Close** – Click **Close** to close the generated receipt. **Note** If the mandatory fields are not filled, the system shows an error message **Value is required**, wherever applicable.
Transaction Alert Preference	Select the alert notification preference from the drop-down list. The values are mentioned below: **Email** – the system sends an email notification of the transactions to the registered email ID of the customer. **Note** The setup for Plato alerts needs to be completed and Kafka topics need to be created to enable e-mail alerts. For information on setup, refer to *Oracle Banking Branch Installation Guide*.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-10 (Cont.) Function Code Definition - Field Description

Field	Description
Advices	This section allows selecting multiple advices for the Function Code.
Advice Name	Select the advice name from the list of values.

4. Click **Save**.

   The summary view is displayed with the configured function code definitions.

19.8 Function Code Preferences

The **Function Code Preferences** screen is used to define the workflow preferences (validation preferences and authorization preferences) for a function code.

For the list of function codes and the respective screen names, refer to List of Function Codes. The rule-based authorization option in this screen is used to configure multi-level authorization with AND or OR condition. The multi-level authorization feature is described with the following example.

The sample user roles are considered as follows:

- *JUNIOR TELLER* (Supervisor enabled)
- *SENIOR TELLER1*
- *SENIOR TELLER2*
- *OFFICER LEVEL1*
- *OFFICER LEVEL2*
- *BRANCH MANAGER*

The sample values for limits and roles maintained are as below:

Table 19-11 Sample Values for Multi-level Authorization

Transaction Limit	Primary Authorization	Alternate Authorization
50,000 to 9,99,999	*SENIOR TELLER2*, *OFFICER LEVEL1*, and *OFFICER LEVEL2*	*OFFICER LEVEL2* and *BRANCH MANAGER*
10,00,000 to 99,99,99,99,999	*SENIOR TELLER1* and *OFFICER LEVEL1*	*OFFICER LEVEL2* or *BRANCH MANAGER*

The approval needs to be provided by the roles configured with AND or OR condition defined either in the primary authorization path or in the alternate authorization path. Based on the sample values provided, the following are some possible scenarios for multi-level authorization:

Table 19-12 Examples for Multi-Level Authorization

Condition	Authorization Process
Teller with *JUNIOR TELLER* role inputs a cash deposit transaction of amount 10,000	The transaction gets completed automatically without authorization.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-12 (Cont.) Examples for Multi-Level Authorization


Condition	Authorization Process
Teller with *JUNIOR TELLER* role input a cash deposit of 60,000	The transaction gets assigned to all the roles mentioned in Primary and Alternate Authorization paths. For example, when a user with the *OFFICER LEVEL2* role picks the transaction and authorizes it, the transaction gets assigned to the other three roles in the Primary and Alternate paths. Further, based on the user who picks for approval, the corresponding path will be chosen by the system. If a user with *BRANCH MANAGER* Role picks the transaction for approval, the system identifies the Alternate Path for approval and ends the authorization process. If a user with *SENIOR TELLER2* role picks the transaction and authorizes, then the corresponding Primary Path will be chosen by the system for *OFFICER LEVEL1* to authorize the transaction.
Teller inputs an account transfer of 20,00,000	The transaction gets assigned to all the roles mentioned in Primary and Alternate Authorization paths. When a user with *BRANCH MANAGER* role or *OFFICER LEVEL2* role picks the transaction and authorizes it, the system identifies the path as Alternate and ends the authorization process. Else if a user with *OFFICER LEVEL1* picks the transaction and authorizes it, the system identifies the path as Primary for *SENIOR TELLER1* to authorize the transaction.

To maintain function code preferences:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Function Code Preferences** or specify **Function Code Preferences** in the search icon bar and select the screen.

   The **Function Code Preferences** summary screen is displayed.

Figure 19-13 Function Code Preferences (Summary)



2. Click the  icon.

   The **Function Code Preferences** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-14 Function Code Preferences




Figure 19-15 Rule-Based Authorization





Figure 19-16 Transaction Limit Check



3. On the **Function Code Preferences** screen, specify the fields. For more information on fields, refer to the field description table.

Copyright © 2021, 2025, Oracle and/or its affiliates.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-13 Function Code Preferences - Field Description

Field	Description
Branch Code	Select the branch code from the list of values. **Note** The list of values should have the ***.*** for the "All" option.
Branch Description	Displays the description of the branch code.
Function Code	Specify the function code. The list of values displays the valid function codes.
Function Code Description	Displays the description of the function code.
General Preferences	Specify the fields. This segment can be used to configure single-level authorization of the preferences with the use of the **Authorizer Role** field.
Teller Sequence Request	Select this option to generate the Teller sequence number.
Teller Sequence Prefix	Specify the prefix for the generation of the Teller sequence number. **Note** This is mandatory only if the **Teller Sequence Request** is selected.
Validation Preferences	Specify the fields.
Charges Amendable	Select if the charges are allowed to modify for the transaction.
Exchange Rate Amendable	Select if the exchange rate is allowed to modify for the transaction.
Rule-Based Authorization	Select if the rule-based authorization is required for the transaction. **Note** Assignment mode to be defined as 'Auto' if Rule based auth flag is selected.
Signature Verification Required	Select if the Teller needs to verify the customer’s signature while submitting the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-13 (Cont.) Function Code Preferences - Field Description

Field	Description
Email Approval Required	Select if authorization through email is required for a transaction. **Note** If this option is selected in override confirmation, then an email will be sent as per the assignment mode maintained. This email will be sent to the selected approver or a list of approvers associated with the role maintained. The approvers will get an email for authorization only if receive email flag is selected in the **User Preferences** screen. Once the email is received, Approver can either approve or reject the transaction. When you click the **Approve** or **Reject**, an email will be automatically opened in the system where the approver can type their comments. The setup for Plato alerts needs to be completed and Kafka topics need to be created to enable e-mail alerts. For information on setup, refer to *Oracle Banking Branch Installation Guide*.
Memo Alerts Verification Required	Enable this toggle button to enable memo alerts verification which is required during submission of a transaction. **Note** • If the parameter is ON then the confirmation is required in all screens where the memo is present. **Note** If the Teller submits the transaction without verifying the memo alerts, then the system displays an error message stating that "Please Verify Memo Alerts and Proceed". • If the memo is not present for a customer or account, then the transaction will go through without a memo confirmation. • If the parameter is OFF then no confirmation is required for memo alerts.
Authorization Preferences	Specify the fields.
Authorization required for Interbranch Transaction	Select if the authorization is required for the inter-branch transaction.
Authorization required for Charge Amendment	Select if the authorization is required in case you have amended the charge defaulted by the system.
Authorization required for Exchange Rate Amendment	Select if the authorization is required in case you have amended the exchange rate defaulted by the system.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-13 (Cont.) Function Code Preferences - Field Description

Field	Description
Authorization required by Default	Select if the authorization is required by default for the transaction. **Note** • To enable a two-step authorization process, maintain the value as **Y** in the `FINISHTXN_ON_APP` parameter in the **SRV_TM_BC_PARAM_DTLS** table. • If notification is also required on approval in the two step process, then both the parameters `FINISHTXN_ON_APP` and `TWO_STEP_SYNC` need to be enabled.
Assignment Mode	Select to indicate whether remote authorization assignment is the automatic or manual operation for the transaction.
Authorizer Role	Select the role of the authorizers. The users belonging to this role are the valid authorizers for this workflow. **Note** This field is applicable, if assignment mode is **Manual** or if assignment mode is **Auto** and no default authorizer is maintained for the user.
Rule-Based Authorization	Specify the fields. This segment can be used to configure multi-level authorization of the preferences with the use of **Supervisor Role ID** and **Alternate Supervisor Role ID** fields. **Note** Rule Based Authorization cannot be applied for customer servicing transactions.
Currency	Select the currency of the transaction from the LOV.
From Amount	Specify the "From" cap amount.
To Amount	Specify the "To" cap amount.
Amend Charge	Select from the drop-down values (**Yes**, **No** or **Both**).
Amend Rate	Select from the drop-down values (**Yes**, **No** or **Both**).
Interbranch Transaction	Select from the drop-down values (**Yes**, **No** or **Both**).
Supervisor Role ID	Select the supervisor role ID from the list of values. The following conditions apply to this field: • More than one role can be added for authorization. • If multiple roles are added, it is not mandatory to authorize in sequential order of the roles added. • The roles added in this field are considered for the primary level of authorization.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-13 (Cont.) Function Code Preferences - Field Description

Field	Description
Supervisor Role Logical Operator	Select the logical operator AND or OR. If AND is chosen, all the Supervisor role specified in primary path has to authorize the transaction. If OR is chosen, either of the Supervisor role has to authorize the transaction.
Alternate Supervisor Role ID	Select the alternate role ID from the list of values. The following conditions apply to this field: • More than one role can be added for authorization. • If multiple roles are added, it is not mandatory to authorize in sequential order of the roles added. • The roles added in this field are considered for the secondary level of authorization.
Alternate Supervisor Role Logical Operator	Select the logical operator AND or OR. If AND is chosen, all the Supervisor role specified in primary path has to authorize the transaction. If OR is chosen, either of the Supervisor role has to authorize the transaction.
Transaction Limit Check	Specify the details under this section. Double-click on a row to enable the fields.
Transaction Currency	Click the search icon, and select the transaction currency from the list of values.
Transaction Amount	Specify the transaction amount.
Action	Click the necessary icon to save, edit, or delete the values of a row.

4. Click **Save**.

   The summary view is displayed with the configured function code preferences.

19.9 Default Authorizer

The **Default Authorizer** screen is used to define the default authorizer who can authorize a specific function code for a branch user.

Once it is defined, the system automatically routes the transactions of this function code to the default authorizer defined for the branch user.


To maintain default authorizer:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Default Authorizer** or specify **Default Authorizer** in the search icon bar and select the screen.

   The **Default Authorizer** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-17 Default Authorizer (Summary)



2. Click the  icon.

The **Default Authorizer** (New) screen is displayed.

Figure 19-18 Default Authorizer



3. On the **Default Authorizer** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-14 Default Authorizer - Field Description

Field	Description
User ID	Select the user ID from the list of values. The list consists of user IDs for which a default authorizer needs to be maintained.
User Name	Displays the name of the user, when you select the user ID.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-14 (Cont.) Default Authorizer - Field Description

Field	Description
Branch Code	Select the branch code from the list of values. This field is enabled if the **All** option is selected in the **User ID** field. **Note** If a specific authorizer is selected, then the system will default the home branch as branch code.
Branch Name	Displays the branch name, when you select the **Branch Code**.
Default Authorizer	Select the default authorizer from the list of values, if it is already set while assigning the transaction. If the mode assigned is **Manual**, it allows changing the default authorizer. Select the authorizer ID from the adjoining option list. The options list consists of authorizers who are mapped to a role with **Savings Authorizer** flag value as **Y** or **All** option.
Description	Displays the description.

4. Click **Save**.

   The summary view is displayed with the configured default authorizer.

19.10 Accounting and Settlements

The **Settlements Definition** screen is used to define the settlement and accounting parameters that are applicable for processing the branch transactions involving a function code.


To maintain accounting and settlements:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Settlements Definition** or specify **Settlements Definition** in the search icon bar and select the screen.

   The **Settlements Definition** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-19 Settlements Definition (Summary)



2. Click the  icon.

   The **Accounting Settlement** screen is displayed.

Figure 19-20 Accounting Settlement



3. On the **Accounting Settlement** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-15 Accounting Settlement - Field Description

Field	Description
Function Code	Select the function code for which the accounting details need to be defined from the list of values.
Function Code Description	Displays the description of the selected function code.
Branch	Select the branch for which the accounting details need to be defined from the list of values. **Note** The value ***.*** indicates the "All" option.
Currency	Select the currency for which the accounting details need to be defined from the list of values. **Note** The value ***.*** indicates the "All" option.
Transaction Account/GL	Select the transaction account or GL from the list of values. The list of values displays all valid GLs maintained. This field is kept blank if the transaction account needs to be selected from the transaction screen. **Note** LOV query will fetch the Nostro type of accounts for 9009 and 9010 function codes. For other function codes, only GL accounts will be fetched from LOV.
Offset Account/GL No	Select the offset account or GL from the list of values. The list of values displays all valid GLs maintained. **Note** LOV query will fetch the Nostro type of accounts for 9009 and 9010 function codes. For other function codes, only GL accounts will be fetched from LOV.
Transaction Code for Debit	Select the transaction code used for debit accounting from the list of values.
Transaction Code for Credit	Select the transaction code used for credit accounting from the list of values.
Main Leg Accounting Required	Select to pass the main accounting entries along with the charges defined in the transaction code.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-15 (Cont.) Accounting Settlement - Field Description

Field	Description
Netting Charge Required	**Note** This field is meant for future use.
Profit Reval GL	Specify the profit revaluation GL details. **Note** This field is used during accounting only when the transaction involves negotiated exchange rate.
Loss Reval GL	Specify the loss revaluation GL details. **Note** This field is used during accounting only when the transaction involves negotiated exchange rate.

4. Click **Save**.

   The summary view is displayed with the configured accounting details.

19.11 Instrument Numbers

The **Instrument Number Maintenance** screen is used to maintain the instrument type for each branch.


To maintain instrument numbers:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Instrument Number Maintenance** or specify **Instrument Number Maintenance** in the search icon bar and select the screen.

   The **Instrument Number Maintenance** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-21 Instrument Number Maintenance (Summary)




2. Click the + icon.

   The **Instrument Number Maintenance** (New) screen is displayed.

3. On the **Instrument Number Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Figure 19-22 Instrument Number Maintenance (New)



Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-16 Instrument Number Maintenance - Field Description

Field	Description
Instrument Type	Specify the instrument type for which the instrument maintenance needs to be done. Select the type of Instrument Type from below values: • **Demand Draft** • **Bankers Cheque** • **Demand Draft-FCY**
Branch	Select the branch code from the list of values.
Instrument Currency	Click **Search** icon and select the currency code from the list of values.
Issuing Bank Code	Click **Search** icon and select the bank code from the list of values.
Generate Instrument Number	Specify Generate Instrument Number as Yes/No by selecting the radio-button. When Instrument Number generation mode is set to Manual in OBPM. • If Instrument Number should be auto Generated by Branch during DD Issuance. Then the Generate instrument number should be enabled in Instrument Number Maintenance in OBBRN. • If Instrument Number should be manually input by Branch User during DD Issuance. Then the Generate instrument number should be disabled in Instrument Number Maintenance in OBBRN.
Instrument Number	Specify the cheque number for which the instrument maintenance needs to be done.
Number of Leaves	Specify the number of leaves.

4. Click **Save**.

   The summary view is displayed with the configured instrument number.

> **Note**
>
> If the IV Integration Parameter is activated, the Instrument Number Maintenance in Branch is not applicable and the system restricts user access to the screen.

19.12 Inter Branch Transit Account

The **Inter Branch Transit Account** screen is used to maintain inter-branch transit account for each branch using the receiving branch, vault, and currency combination.


To maintain inter-branch transit account:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Inter Branch Transit Account** or specify **Inter Branch Transit Account** in the search icon bar and select the screen.

   The **Inter Branch Transit Account** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-23 Inter Branch Transit Account (Summary)



2. Click the + icon.

The **Inter Branch Transit Account Maintenance** screen is displayed.

Figure 19-24 Inter Branch Transit Account Maintenance



3. On the **Inter Branch Transit Account Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-17 Inter Branch Transit Account Maintenance - Field Description

Field	Description
Branch Code	Select the branch code from the list of values, which provides all the branch codes maintained in the system.
Branch Name	Display the description of the selected branch code.
Receiving Branch	Specify the destination branch to which the cash is transferred.
Branch Name	Display the description of the selected Receiving Branch code.
Currency	Specify the currency of the cash.
Transit Account	Specify the transit account that is used to track the movement of cash.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-17 (Cont.) Inter Branch Transit Account Maintenance - Field Description

Field	Description
Action	Click the necessary icon to edit, save, or delete a row.

4. Click **Save**.

   The summary view is displayed with the configured inter-branch transit account.

19.13 External System

The **External System Maintenance** screen is used to define the parameters for the external system.


The parameters are defined whenever there is an external system call to the Oracle Banking Branch external API. Only the registered users can make the external system call to process the transaction.

To maintain external system:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **External System Maintenance** or specify **External System Maintenance** in the search icon bar and select the screen.

   The **External System Maintenance** summary screen is displayed.

Figure 19-25 External System Maintenance (Summary)




2. Click the  icon.

   The **External System Maintenance** (New) screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-26 External System Maintenance (New)



3. On the **External System Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-18 External System Maintenance - Field Description

Field	Description
External System Code	Specify the system code of the registered external system.
External System Name	Specify the name of the registered external system.
Function Code	Specify the function code of the transaction, which needs to be performed through the external system. You can also select from the list of values.
On Warning	Select from the drop-down list. The values in the drop-down list are mentioned below: • **Ignore** – Select if you need to ignore the override raised and process the transaction until completion. • **Error** – Select if you need to show the error message and stop the transaction.
On Approval	Select from the drop-down list. The values in the drop-down list are mentioned below: • **Ignore** – Select if you need to ignore the override raised and process the transaction until completion. • **Error** – Select if you need to show the error message and stop the transaction.
Incoming User Type	Select the incoming user type from the drop-down values. The values in the drop-down list are mentioned below: • **User** – User appearing in the payload to process the transaction. • **Default User** – Default user that is maintained to process the transaction. • **Role** – Role appearing in the payload to process the transaction. • **Default Role** – Default role that is maintained to process the transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-18 (Cont.) External System Maintenance - Field Description

Field	Description
Default User	Specify the default user maintained. **Note** This field is applicable only if the **Incoming User Type** is selected as **Default User**.
Default Role	Specify the default role maintained. **Note** This field is applicable only if the **Incoming User Type** is selected as **Default Role**.
External Initiation	Select if you need to log the transaction into Journal Log with the status **Initiated**.
Till Update	Select if you need to update the Till.
Authorization required by Default	Select if you need to raise an override even if it is **N** in function preference.
Action	Click the necessary icon to edit, save, or delete a row.

4. Click **Save**.

   The summary view is displayed with the configured details of external system maintenance.

19.14 Channel Limits

The **Channel Limits** screen is used to maintain the channel limits for a particular customer group.


To maintain channel limits:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Channel Limits** or specify **Channel Limits** in the search icon bar and select the screen.

   The **Channel Limits** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-27 Channel Limits (Summary)



2. Click the + icon.

   The **Channel Limits Maintenance** screen is displayed.

Figure 19-28 Channel Limits Maintenance



3. On the **Channel Limits Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-19 Function Code Definition - Field Description

Field	Description
Account Group	Click the search icon and select account group from the list of values. **Note** The list of values provides the account groups that are maintained in the **Account Group Maintenance** screen.
Channel	Select value from the drop-down list. **Note** By default, the value is selected as **Branch**.
Currency	Select the currency from the list of values.
Max Withdrawal Limit Per Day	Specify the maximum amount for the cash withdrawal transactions per day.
No. of Transactions Per Day	Specify the maximum limit for the number of cash withdrawal transactions per day.

4. Click **Save**.

   The summary view is displayed with the configured details of channel limits maintenance.

19.15 Account Group

The **Account Group Maintenance** screen is used to create groups of the account codes, and these groups can be used for charge calculation.


To maintain account group:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Account Group Maintenance** or specify **Account Group Maintenance** in the search icon bar and select the screen.

   The **Account Group Maintenance** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-29 Account Group Maintenance (Summary)



2. Click the  icon.

   The **Account Group Maintenance** (New) screen is displayed.

Figure 19-30 Account Group Maintenance (New)



3. On the **Account Group Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-20 Account Group Maintenance - Field Description

Field	Description
Account Group Code	Specify the account group code.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-20 (Cont.) Account Group Maintenance - Field Description

Field	Description
Account Group Code Description	Specify the description of the account group code.
Add Accounts	Specify the fields.
Account Number	Specify the account number. You can also select from the list of values.
Account Group Code	Displays the account group code.
Action	Click the necessary icon to save, edit, or delete the values of a row.

4. Click **Save**.

   The summary view is displayed with the configured details of account groups.

19.16 Branch Group


The **Branch Group Maintenance** screen is used to create groups of the branch codes, and these groups can be used for charge calculation.

To maintain branch group:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Branch Group Maintenance** or specify **Branch Group Maintenance** in the search icon bar and select the screen.

   The **Branch Group Maintenance** summary screen is displayed.

Figure 19-31 Branch Group Maintenance (Summary)




2. Click the  icon.

   The **Branch Group Maintenance** (New) screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-32 Branch Group Maintenance (New)



3. On the **Branch Group Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-21 Branch Group Maintenance - Field Description

Field	Description
Branch Group Code	Specify the branch group code.
Branch Group Code Description	Specify the description of the branch group code.
Add Branch	Specify the fields.
Branch Code	Specify the branch code. You can also select from the list of values.
Branch Group Code	Displays the description for the specified branch code.
Action	Click the necessary icon to save, edit, or delete the values of a row.

4. Click **Save**.

   The summary view is displayed with the configured details of branch groups.

19.17 Customer Group

The **Customer Group Maintenance** screen is used to create groups of the customer codes, and these groups can be used for charge calculation.


To maintain customer group:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Customer Group Maintenance** or specify **Customer Group Maintenance** in the search icon bar and select the screen.

   The **Customer Group Maintenance** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-33 Customer Group Maintenance (Summary)



2. Click the  icon.

   The **Customer Group Maintenance** (New) screen is displayed.

Figure 19-34 Customer Group Maintenance (New)



3. On the **Customer Group Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-22 Customer Group Maintenance - Field Description

Field	Description
Customer Group Code	Specify the customer group code.
Customer Group Code Description	Specify the description of the customer group code.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-22 (Cont.) Customer Group Maintenance - Field Description

Field	Description
Customers Added	Displays the details of customer numbers added to the table.
Customer Number	Specify the customer number. You can also select from the list of values. **Note** You cannot add the same customer number in two different groups.
Customer Name	Displays the description for the specified customer number.
Actions	Click the necessary icon to save, edit, or delete the values of a row.

4. Click **Save**.

   The summary view is displayed with the configured details of customer groups.

19.18 Create Charge Pricing


The **Create Charge Pricing Maintenance** screen is used to maintain the charge pricing.

To maintain charge pricing:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Create Charge Pricing Maintenance** or specify **Create Charge Pricing Maintenance** in the search icon bar and select the screen.

   The **Create Charge Pricing Maintenance** summary screen is displayed.

Figure 19-35 Create Charge Pricing Maintenance



2. On the **Create Charge Pricing Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

Note

The fields marked as **Required** are mandatory.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-23 Create Charge Pricing Maintenance - Field Description

Field	Description
Application Code	Specify the application code.
Charge Pricing Description	Specify the description of the charge pricing.
Pricing Category	Select the pricing category. The drop-down list has the following values: • **Fixed Amount** • **Fixed Percent** • **Tier Based Amount** • **Tier Based Percent**
Pricing Method	Select the pricing method. The drop-down values will vary based on the **Pricing Category**.
Pricing Currency	Select the pricing currency.
Rate Code	Click the search icon and select the rate code from the list of values.
Rate Type	Select the rate type from the drop-down values.
Charge in Transaction Currency	Select if the charges are needed in the transaction currency.
Min/Max Validation Criteria	Select the criteria (**Amount** or **Percentage**) for minimum or maximum validation.
Min Charge Amount/ Percent	Specify the minimum charge amount or percentage. **Note** Based on the value selected in the **Min/Max Validation Criteria**, this field gets enabled.
Max Charge Amount/ Percent	Specify the maximum charge amount or percentage. **Note** Based on the value selected in the **Min/Max Validation Criteria**, this field gets enabled.

3. Click **Save**.

   The summary view is displayed with the configured details of charge pricing.

19.19 View Charge Pricing

The **View Charge Pricing Maintenance** screen is used to view the summary and details of charge pricing IDs.


To view charge pricing maintenance:

On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **View Charge Pricing Maintenance** or specify **View Charge Pricing Maintenance** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **View Charge Pricing Maintenance** is displayed.

Figure 19-36 View Charge Pricing Maintenance



You can view a summary of the configured records for the charge pricing details on this screen.

19.20 Charge Condition Group


The **Charge Condition Group Maintenance** screen is used to create groups of the charge condition codes.

To maintain charge condition group:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Charge Condition Group Maintenance** or specify **Charge Condition Group Maintenance** in the search icon bar and select the screen.

   The **Charge Condition Group Maintenance** summary screen is displayed.

   Figure 19-37 Charge Condition Group Maintenance (Summary)




2. Click the + icon.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **Charge Condition Group Maintenance** screen is displayed.

Figure 19-38 Charge Condition Group Maintenance (New)



3. On the **Charge Condition Group Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-24 Charge Condition Group Maintenance - Field Description

Field	Description
Charge Condition Group Code	Specify the charge group code.
Charge Condition Group Code Description	Specify the description of the charge group code.
Parameter 1 to **Parameter 5**	Select the parameters 1 to 5. For more information on Parameters, refer to Additional Information on Parameters.
Charge Details	Specify the fields.
Value 1 to **Value 5**	Specify the values 1 to 5. You can also select from the list of values.
Charge Pricing Rule ID	Specify the charge pricing rule ID. You can also select from the list of values.
Charge Pricing Rule Description	Displays the description for specified charge pricing rule ID.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-24 (Cont.) Charge Condition Group Maintenance - Field Description

Field	Description
Reset	Click **Reset** to reset the charge group details added.
Add Charge Group	Click **Add Charge Group** to add the charge group details specified.
Charge Groups Added	Displays the details of charge groups added to the table.

4. Click **Save**.

   The summary view is displayed with the configured groups of the charge condition codes.

- Additional Information on Parameters
  The **Parameters** field on the **Charge Condition Group Maintenance** screen needs to be selected based on the specified conditions.

19.20.1 Additional Information on Parameters

The **Parameters** field on the **Charge Condition Group Maintenance** screen needs to be selected based on the specified conditions.

There will be a few parameters like Customer Group, Account Group, or Branch group will be pre-shipped. Customers need to choose the parameters, group them, and name them with the group codes. A rule will be attached to the group code so that based on the group used corresponding rule will be applied for calculation.

If the Charge Condition Group Maintenance is made with a specific parameter, the CHG_PARAM_TAGS column in the SRV_TB_TX_STATIC_TAGS table of transaction schema needs to be updated. For example, if Parameter 1 is selected as a utility provider, it needs to be updated as below:

```
{
"UtilityProvider": "$.institutionID",
"P2": "",
"P3": "",
"P4": "",
"P5": ""
}
```

For the other options in **Parameter** field, the JSON needs to be updated as follows:

Table 19-25 Options for Parameter Fields

Option	Value
Account Group	`"AccountGroup": ""`
Customer Group	`"CustomerGroup": ""`
Transaction Branch Group	`"TransactionBranchGroup": ""`
To Account Branch Group	`"ToAccountBranchGroup": ""`
To Account Branch	`"ToAccountBranch": "$.toAccountBranch"` `<$.toAccountBranch has to be replaced with the field id as per the FID that captures To Account Branch>`

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-25 (Cont.) Options for Parameter Fields

Option	Value
Account Currency	`"AccCcy": "$.AccCcy"` `<$.AccCcy has to be replaced with the field id as per the FID that captures Account Currency>`
Utility Provider	`"UtilityProvider": "$.institutionID"` `<$.institutionID has to be replaced with the field id as per the FID that captures Utility Provider>`

19.21 Charge Decisions


The **Charge Decision Maintenance** screen is used to maintain the charge decisions.

To maintain charge decisions:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Charge Decision Maintenance** or specify **Charge Decision Maintenance** in the search icon bar and select the screen.

   The **Charge Decision Maintenance** summary screen is displayed.

Figure 19-39 Charge Decision Maintenance (Summary)




2. Click the  icon.

   The **Charge Decision Maintenance** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-40 Charge Decision Maintenance (New)



3. On the **Charge Decision Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-26 Charge Decision Maintenance - Field Description

Field	Description
Function Code	Specify the function code. You can also select from the list of values.
Branch	Specify the branch code. You can also select from the list of values.
Currency	Specify the currency code. You can also select from the list of values.
Inter Branch	Select the inter-branch requirement from the following drop-down values: • **Yes** • **No** • **Both**
Charge Details	Specify the fields.
Charge Code	Specify the charge code. You can also select from the list of values.
Charge Description	Displays the description of the charge code specified.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-26 (Cont.) Charge Decision Maintenance - Field Description

Field	Description
Charge Pricing Rule ID	Specify the charge-pricing rule ID. You can also select from the list of values. **Note** • You can choose the pricing rule ID to apply charge or choose a group code from which the pricing rule will be picked for calculation. You can only define the rule or group. Either the rule can be used, or a group can be used. • When OPDS is enabled, then the list of values will fetch the values from the charge code maintenance screen. To enable OPDS pricing, set PARAM_VALUE as **Y** for the `OPDS_INTEGRATED` in the SRV_TM_BC_PARAM_DTLS table.
Charge Pricing Rule Description	Displays the description of the charge-pricing rule ID specified.
Charge Basis	Specify the charge basis. You can also select from the list of values.
Charge Condition Group	Specify the charge condition group. You can also select from the list of values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-26 (Cont.) Charge Decision Maintenance - Field Description

Field	Description
Charge Preference	To capture the charge preference options, if a charge is flagged for tracking due to insufficient funds. The available drop-down options are: • **Part Waive/Part Debit**: If there is some amount in the account but not sufficient to collect the full charge, the system will collect the available amount and waive off the remaining amount. No tracking would be done for the waived amount. For example, If the charge amount is Rs. 100 and there is Rs. 70 in the customer account, then Rs. 70 would be collected as the charge and the remaining Rs. 30 would be waived off. • **Part Track/ Part Debit**: If there is some amount in the account but not sufficient to collect the full charge, the system will collect the available amount and track the remaining amount. For example, If the charge amount is Rs. 100 and there is Rs. 70 in the customer account, then Rs. 70 would be collected as the charge and the remaining Rs. 30 would be tracked for collection. • **Full Waive**: The full charge amount would be waived off if the amount in the account does not cover the charge fully. For example, If the charge amount is Rs. 100 and there is Rs. 70 in the account, the entire Rs. 100 charge would be waived off. • **Full Track**: If the account does not have sufficient amount to cover the charge, the entire amount will be tracked. For example, If the charge is Rs. 100 and the amount in the account is Rs. 70, no charge would be collected, instead an amount block for Rs. 100 would be created and this would be tracked till closure. • **Force Debit**: In this case, the charge amount would be forcibly debited to the customer's account. For example, If the charge is Rs. 100 and the customer account has Rs. 70, then the system would forcibly debit the customer account of Rs. 100 resulting in the customer account balance becoming Rs. -30. No Tracking of amounts is done in this case. • **Reject**: Under this option, the entire transaction would be rejected if the amount in the customer account did not have sufficient amount for the charge. For example, If the transaction is a Cash Withdrawal of Rs. 500 and the charge is Rs. 100, then if the customer account balance is less than Rs. 600, then the entire transaction would be rejected. The customer can withdraw a maximum of Rs. 400.
Action	Click the necessary icon to save, edit, or delete the values of a row.
Reset	Click **Reset** to reset the charges added.
Add charges	Click **Add Charges** to add the charge decisions specified.
Charges Added	Displays the details of charge decisions added to the table. Once you add an account to the table, you can click the necessary icon to edit or delete the added entry.

4. Click **Save**.

   The summary view is displayed with the configured details of charge decisions.

Copyright © 2021, 2025, Oracle and/or its affiliates.

19.22 Charge Decision Enquiry


The **Charge Decision Enquiry** screen is used to inquire about the details of charge definition and charge pricing for the specified search criteria.

To inquire about the charge decision details:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Charge Decision Enquiry** or specify **Charge Decision Enquiry** in the search icon bar and select the screen.

   The **Charge Decision Enquiry** summary screen is displayed.

Figure 19-41 Charge Decision Enquiry



2. On the **Charge Decision Enquiry** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-27 Charge Decision Enquiry - Field Description

Field	Description
Function Code	Click the search icon and select function code from the list of values.
Branch	Click the search icon and select branch code from the list of values.
Currency	Click the search icon and select currency code from the list of values.
Inter Branch	Select the value for inter-branch from the drop-down list.
Fetch	Click **Fetch** to fetch the details based on the specified search criteria.
Charge Code	Displays the charge code.
Charge Pricing Rule ID	Displays the charge pricing rule ID.
Charge Basis	Displays the charge basis.
Charge Condition Group	Displays the charge condition group.
Charge Definition	Displays the charge definition details. For information on fields refer to Charge Definitions.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-27 (Cont.) Charge Decision Enquiry - Field Description

Field	Description
Charge Pricing	Displays the charge pricing details. For information on fields refer to Create Charge Pricing.

19.23 Reject Codes

The **Reject Code Maintenance** screen is used to maintain the reject codes.


The reject codes maintained in this screen are used to reject the cheque withdrawal transactions with the appropriate reject code.

To maintain reject codes:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Reject Code Maintenance** or specify **Reject Code Maintenance** in the search icon bar and select the screen.

   The **Reject Code Maintenance** summary screen is displayed.

Figure 19-42 Reject Code Maintenance (Summary)




2. Click the + icon.

   The **Reject Code Maintenance** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-43 Reject Code Maintenance (New)



3. On the **Reject Code Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-28 Reject Code Maintenance - Field Description

Field	Description
Reject Code	Specify the reject code. This code indicates the reason for rejecting a clearing transaction.
Reject Code Description	Specify the description of the reject code.
Applicable For	Select from the radio list from the following drop-down values: • **Inward Return** • **Outward Return** • **Both Inward and Outward Return** • **Inhouse Cheques**

4. Click **Save**.

   The summary view is displayed with the configured details of reject codes.

19.24 Clearing Network Codes

The **Clearing Network** screen is used to maintain the clearing network codes.


To maintain clearing network codes:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Clearing Network** or specify **Clearing Network** in the search icon bar and select the screen.

   The **Clearing Network** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-44 Clearing Network (Summary)



2. Click the  icon.

   The **Clearing Network Maintenance** screen is displayed.

Figure 19-45 Clearing Network Maintenance



3. On the **Clearing Network Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-29 Clearing Network Maintenance - Field Description

Field	Description
Clearing Network Code	Specify the clearing network code.
Clearing Network Description	Specify the description of the clearing network code.

4. Click **Save**.

   The summary view is displayed with the configured details of network codes.

Copyright © 2021, 2025, Oracle and/or its affiliates.

19.25 Denomination Variations

The **Denomination Variation Maintenance** screen is used to maintain the denomination-wise variations.


In some countries, the local banking practice is to buy various FX currency denominations with different rates and lower denominations, which becomes a lower rate. This screen helps to apply rates for different denominations.

To maintain denomination variations:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Denomination Variation Maintenance** or specify **Denomination Variation Maintenance** in the search icon bar and select the screen.

   The **Denomination Variation Maintenance** summary screen is displayed.

Figure 19-46 Denomination Variation Maintenance (Summary)




2. Click the  icon.

   The **Denomination Variation Maintenance** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-47 Denomination Variation Maintenance (New)



3. On the **Denomination Variation Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-30 Denomination Variation Maintenance - Field Description

Field	Description
Currency 1	Select the currency from the list of values.
Currency 2	Select the currency from the list of values.
Maintenance Country	Select the country code from the list of values.
Rate Type	Select the rate type from the list of values.
Denomination ID	Select the denomination ID from the list of values.
Buy Variance	Specify the buy variance.
Sell Variance	Specify the sell variance.

4. Click **Save**.

   The summary view is displayed with the configured details of denomination-wise variations.

19.26 External Bank Codes

The **External Bank Code** screen is used to maintain the bank codes and branch codes.


To maintain external bank codes:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **External Bank Code** or specify **External Bank Code** in the search icon bar and select the screen.

   The **External Bank Code** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-48 External Bank Code (Summary)



2. Click the + icon.

The **External Bank Code** screen is displayed.

Figure 19-49 External Bank Code (New)



3. On the **External Bank Code** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-31 External Bank Code - Field Description

Field	Description
Bank Code	Specify the bank code.
Bank Name	Specify the name of the bank.
Branch Code	Specify the branch code.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-31 (Cont.) External Bank Code - Field Description

Field	Description
Branch Name	Specify the branch name.
Branch Address 1 to **Branch Address 4**	Specify the address of the branch.

4. Click **Save**.

   The summary view is displayed with the configured details of external bank and branch codes.

19.27 Issuer Codes


The **Issuer Code Maintenance** screen is used to maintain the issuer codes for TC transactions.

To maintain issuer codes:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Issuer Code Maintenance** or specify **Issuer Code Maintenance** in the search icon bar and select the screen.

   The **Issuer Code Maintenance** summary screen is displayed.

Figure 19-50 Issuer Code Maintenance (Summary)




2. Click the + icon.

   The **Issuer Code Maintenance** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-51 Issuer Code Maintenance (New)



3. On the **Issuer Code Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-32 Issuer Code Maintenance - Field Description

Field	Description
Issuer Code	Specify the issuer code.
Issuer Code Description	Specify the description of the issuer code.

4. Click **Save**.

   The summary view is displayed with the configured details of issuer codes.

19.28 Utility Providers

The **Utility Provider Maintenance** screen is used to link the utility provider with a settlement account.

The examples of utility providers are as follows:

- Electricity
- Gas
- Water


To maintain utility providers:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Utility Provider Maintenance** or specify **Utility Provider Maintenance** in the search icon bar and select the screen.

   The **Utility Provider Maintenance** summary screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.


Figure 19-52 Utility Provider Maintenance (Summary)



2. Click the  icon.

   The **Utility Provider Maintenance** screen is displayed.

Figure 19-53 Utility Provider Maintenance (New)



3. On the **Utility Provider Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-33 Utility Provider Maintenance - Field Description

Field	Description
Provider ID	Click the search icon, and select the provider ID from the list of values.
Provider Description	Specify the description of the utility provider.
Provider Settlement Account	Click the search icon, and select the provider settlement account from the list of values.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-33 (Cont.) Utility Provider Maintenance - Field Description

Field	Description
Account Currency	If the Settlement Account is a GL, then Specify the currency in which the Bill needs to be Settled. If the Settlement Account is a CASA. Then the system defaults this to the account currency and is non-editable.
Account Description	Displays the Description of the Settlement Account.
Branch Code	If the Settlement Account is a GL, then Specify the Branch Code to which the Bill needs to be Settled. If the Settlement Account is a CASA. Then the system defaults this to the account Branch and is non-editable.

4. Click **Save**.

   The summary view is displayed with the configured details of utility providers.


19.29 Account Entitlement Restriction

This screen is used to maintain the Account Entitlement Group by grouping the set of Customer accounts. To process this screen, type **Account Entitlement Restriction** in the **Menu Item Search** located at the left corner of the application toolbar and select the appropriate screen (or) do the following steps:

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance**, click **Account Entitlement Restriction** or specify **Account Entitlement Restriction** in the search icon bar and select the screen.

   The **Account Entitlement Restriction** summary screen is displayed.

Figure 19-54 Account Entitlement Restriction (Summary)




2. Click the  icon.

   The **Account Entitlement Restriction** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-55 Account Entitlement Restriction (New)



3. On the **Account Entitlement Restriction** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-34 Account Entitlement Restriction - Field Description

Field	Description
Account Entitlement Code	Click search icon, and select the account entitlement code from the list of values.
Restriction Type	Select restriction type from the radio list. The available options are: • Allowed • Disallowed
Function Code Details	Specify the fields.
Function Code	Click search icon, and select the function code from the list of values.
Function Code Description	Displays the description of the function code.

4. Click **Save**.

   The summary view is displayed with the configured details of utility providers.

19.30 GST Rule Maintenance

The **GST Rule Maintenance** screen is to maintain rule details applicable for collecting the SGST and CGST or IGST on charge collection on a particular screen. User will be able to maintain the different rates applicable for case.

This topic contains the following sub topics:

- Create GST Rule Maintenance
- View GST Rule Maintenance


Copyright © 2021, 2025, Oracle and/or its affiliates.

19.30.1 Create GST Rule Maintenance

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance** → **GST Rule Maintenance**, click **Create GST Rule Maintenance** or specify **Create GST Rule Maintenance** in the search icon bar and select the screen.

   The **Create GST Rule Maintenance** screen is displayed.

Figure 19-56 Create GST Rule Maintenance



2. On the **Create GST Rule Maintenance** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-35 Create GST Rule Maintenance - Field Description

Field	Description
Rule Code	The rule code gives the option to select the type of GST. Select the rule code from the drop-down values. The available options are: • **SGST/CGST**: SGST is a GST system component and it is a tax levied by the state government on intrastate supplies of goods and services. CGST is a tax levied on intrastate supplies of both goods and services by the central government and collected by it for its coffers. • **IGST**: IGST is a tax levied on all interstate supplies of goods and/or services or across two or more states/union territories.
State Code	Click **Search** icon and select the state code from the list. **Note** The state code is applicable only for the SGST and CGST.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table 19-35 (Cont.) Create GST Rule Maintenance - Field Description

Field	Description
State Description	Displays the description based on the state code selection.
Rate	Specify the GST Rate. GST rates refer to the percentage rates of tax imposed on the sale of goods or services under the CGST, SGST, and IGST acts.


3. Click **Save**.

19.30.2 View GST Rule Maintenance

- On the Homepage, from **Teller** mega menu, under **Branch Maintenance → GST Rule Maintenance**, click **View GST Rule Maintenance** or specify **View GST Rule Maintenance** in the search icon bar and select the screen.

  The **View GST Rule Maintenance** screen is displayed.

Figure 19-57 View GST Rule Maintenance



19.31 GST Branch Parameters

The **GST Branch Parameters** screen is used to maintain the GST Identification Number (GSTIN) for the servicing branch and assign the GL codes for crediting the collected SGST, CSGT, and IGST respectively for a given GST state.

This topic contains the following sub topics:

- Create GST Branch Parameters
- View GST Branch Parameters


19.31.1 Create GST Branch Parameters

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance → GST Branch Parameters**, click **Create GST Branch Parameters** or specify **Create GST Branch Parameters** in the search icon bar and select the screen.

Copyright © 2021, 2025, Oracle and/or its affiliates.

The **Create GST Branch Parameters** screen is displayed.

Figure 19-58 Create GST Branch Parameters



2. On the **Create GST Branch Parameters** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-36 Create GST Branch Parameters - Field Description

Field	Description
Branch Code	Click **Search** icon and select the branch code from the list of values.
Branch Name	Displays the description based on the branch code selection.
GST State Code	Click **Search** icon and select the GST state code from the list of values.
GSTIN	Specify the valid GSTIN number. It is a unique 15 digit identification number assigned to every taxpayer registered under the GST regime.
SGST GL	Click **Search** icon and select the SGST GL from the list of values. GL codes to be used for crediting the collected SGST.
CGST GL	Click **Search** icon and select the CGST GL from the list of values. GL codes to be used for crediting the collected CGST.
IGST GL	Click **Search** icon and select the IGST GL from the list of values. GL codes to be used for crediting the collected IGST.

3. Click **Save**.


19.31.2 View GST Branch Parameters

- On the Homepage, from **Teller** mega menu, under **Branch Maintenance → GST Branch Parameters**, click **View GST Branch Parameters** or specify **View GST Branch Parameters** in the search icon bar and select the screen.

  The **View GST Branch Parameters** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-59 View GST Branch Parameters



19.32 Customer Account GST Parameters

On the **Customer Account GST Parameter** screen, the user is responsible for maintaining the GST Identification Number (GSTIN) applicable for a customer account within the GST state code.

The user will have an option to exempt the collection of GST on their account. For each customer account, the GST State Code and GSTIN must be maintained.

This topic contains the following sub topics:

- Create Customer Account GST Parameters
- View Customer Account GST Parameters


19.32.1 Create Customer Account GST Parameters

1. On the Homepage, from **Teller** mega menu, under **Branch Maintenance → Customer Account GST Parameters**, click **Create Customer Account GST Parameters** or specify **Create Customer Account GST Parameters** in the search icon bar and select the screen.

   The **Create Customer Account GST Parameters** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-60 Create Customer Account GST Parameters



2. On the **Create Customer Account GST Parameters** screen, specify the fields. For more information on fields, refer to the field description table.

> **Note**
>
> The fields marked as **Required** are mandatory.

Table 19-37 Create Customer Account GST Parameters - Field Description

Field	Description
Customer Account	Click **Search** icon and select the customer account number.
GST State Code	Click **Search** icon and select the state code.
GSTIN	Specify the GSTIN number. It is a unique 15 digit identification number assigned to every taxpayer registered under the GST regime.
GST Exempt	Enable this toggle button to exempt GST for the transactions initiated for the corresponding customer account. **Note** If it is not enabled, the GST will be calculated.

3. Click **Save**.


19.32.2 View Customer Account GST Parameters

- On the Homepage, from **Teller** mega menu, under **Branch Maintenance → Customer Account GST Parameters**, click **View Customer Account GST Parameters** or specify **View Customer Account GST Parameters** in the search icon bar and select the screen.

  The **View Customer Account GST Parameters** screen is displayed.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Figure 19-61 View Customer Account GST Parameters



Copyright © 2021, 2025, Oracle and/or its affiliates.

A

List of Functional Activity Codes

This topic provides the functional activity codes available in Oracle Banking Branch.

Below tables provide the list of Functional Activity codes that should be Mapped to the user role.

- Table A-1 lists all the Functional Activity codes needed for the login of the application.
- Table A-2 lists the list of maintenance screens required for Branch teller.
- Table A-3 lists the actions for each of the screens of Table A-2. If you need granular access for the maintenance screens table A-3 can be used.
- Table A-4 lists the Functional Activity codes For Transaction screens.
- Table A-5 provides the list of Functional Activity codes for the widgets.
- Table A-6 provides the list of Functional Activity codes for the API.

Table A-1 List of Functional Activity Codes for SMS-Login

Functional Activity Code	Description
OBRC_FA_CONFIG_MASTER	GetConfigMaster
OBRC_FA_GRID_CONFIG	Get grid configuration
OBRC_FA_PROCESS_CONFIG	Get all process Config
OBRC_FA_SCREEN_CONFIG	GetScreenConfig
SMS_FA_MENU_DASHBOARD_VIEW	Menu View
SMS_FA_USER_LOGIN	User Login

Table A-2 List of Functional Activity codes to be mapped to appear in menu for maintenanace screen

Fuctional Activity Code	Screen Name and Functional Activity Description
REMO_FA_REJECTCODE_GETAL_MENU	Reject Code Maintenance
SRV_FA_ACCGRP_GETAL_MENU	Account Group Maintenance
SRV_FA_ACC_ENT_RESTRICTION_MENU	Account Entitlement Restriction
SRV_FA_ACC_GETAL_MENU	Settlements Definition
SRV_FA_AUTHMAIN_GETAL_MENU	Default Authorizer
SRV_FA_BANKCOD_GETAL_MENU	External Bank Code Maintenance
SRV_FA_BC_FUNCTNPREF_GETAL_MENU	Function Code Preferences
SRV_FA_BRANCHGRP_GETAL_MENU	Branch Group Maintenance
SRV_FA_BUSINESSPROCESS_VIEW	Business Process Maintenance
SRV_FA_CHANNELMT_GETAL_MENU	Channel Limits

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-2 (Cont.) List of Functional Activity codes to be mapped to appear in menu for maintenanace screen

Fuctional Activity Code	Screen Name and Functional Activity Description
SRV_FA_CHARGEDEF_MAINT_GETAL_MENU	Charge Definition Maintenance
SRV_FA_CHARGEGRP_GETAL_MENU	Charge Condition Group Maintenance
SRV_FA_CHARGEPICK_GETAL_MENU	Charge Decision Maintenance
SRV_FA_CREATE_PRCRULE_MENU	Charge Pricing Maintenance
SRV_FA_CUSTGRP_GETAL_MENU	Customer Group Maintenance
SRV_FA_DENOMWISEVAR_GETAL_MENU	Denomination Variance Maintenance
SRV_FA_DENOM_GETAL_MENU	Denominations Maintenance
SRV_FA_EXTRNLSYS_GETAL_MENU	External System Maintenance
SRV_FA_FUNCCODE_DEFIN_GET_MENU	Function Code Definition
SRV_FA_GET_PRCRULE_MENU	Charge Pricing Maintenance
SRV_FA_IBTRANSITACC_GETAL_MENU	Inter Branch Transit Account
SRV_FA_ISSUERCOD_GETAL_MENU	Issuer Code Maintenance
SRV_FA_NTWRKCOD_GETAL_MENU	Clearing Network
SRV_FA_PAYINSTR_GETAL_MENU	Instrument Number Maintenance
SRV_FA_ROLELMT_GETALL_MENU	Branch Role Limits
SRV_FA_TELLER_GETALL_MENU	Teller Branch Parameter Maintenance
SRV_FA_USER_PREF_GET_MENU	Branch User Limits
SRV_FA_UTILITYPROV_GETAL_MENU	Utility Provider Maintenance
SRV_FA_GST_MAINT_SAVERECORD_MENU	GST rule maintenance save record
SRV_FA_GST_MAINT_GETALL_MENU	GST rule maintenance get all available records
SRV_FA_GST_BRANCH_PARAMETERS_SAVERECORD_MENU	GST Branch maintenance save record
SRV_FA_GST_BRANCH_PARAMETERS_GETALL_MENU	GST Branch maintenance get all available records
SRV_FA_GST_CUST_ACC_PARAMETERS_SAVERECORD_MENU	GST Cust account parameters maintenance save record
SRV_FA_GST_CUST_ACC_PARAMETERS_GETALL_MENU	GST Cust account parameters maintenance get all available records

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
REMO_FA_REJECTCODE_AUTHORIZE	This is to check the status of the reject code authorization.	Reject Code Maintenance	Authorize
REMO_FA_REJECTCODE_AUTHQUERY	This is to query a reject code authorization.	Reject Code Maintenance	Authorize
REMO_FA_REJECTCODE_CLOSERECORD	This is to close a record for a reject code.	Reject Code Maintenance	Close
REMO_FA_REJECTCODE_DELETE	This is to delete a reject code.	Reject Code Maintenance	Delete
REMO_FA_REJECTCODE_GETALL	This is for reject code get all.	Reject Code Maintenance	Summary Screen View
REMO_FA_REJECTCODE_GETBYID	This is for the reject code get by ID.	Reject Code Maintenance	Detailed View
REMO_FA_REJECTCODE_GETHISTORY	This is to get a history of the reject code.	Reject Code Maintenance	History
REMO_FA_REJECTCODE_MODIFYRECORD	This is to get a modified record for the reject code.	Reject Code Maintenance	Unlock
REMO_FA_REJECTCODE_REOPENRECORD	This is to reopen the record for the reject code.	Reject Code Maintenance	Reopen
REMO_FA_REJECTCODE_SAVERECORD	This is to get a saved record for the reject code.	Reject Code Maintenance	Create
SRV_FA_ACC_AUTHORIZE	This is for account authorization.	Account Group Maintenance	Authorize
SRV_FA_ACC_AUTHQUERY	This is to authorize a query.	Account Group Maintenance	Authorize
SRV_FA_ACC_CLASS_GRP_GETALL	This is for the list of values of the service account class group.	Account Group Maintenance	Summary Screen View

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_ACC_CLOSERECORD	This is for account close record.	Account Group Maintenance	Close
SRV_FA_ACC_CLOSE_CASH_SUBMIT	This is for on-submit account closure cash.	Account Group Maintenance	Create
SRV_FA_ACC_CLOSE_SUBMIT	This is for on-account closure account submission.	Account Group Maintenance	Unlock
SRV_FA_ACC_CLS_SUBMIT	This is for on-account closure submission.	Account Group Maintenance	Reopen
SRV_FA_ACC_DELETE	This is for account deletion.	Account Group Maintenance	Delete
SRV_FA_ACC_ENT_RESTRICTIONN_REOPEN	This is for account restriction reopen.	Account Entitlement Restriction	Reopen
SRV_FA_ACC_ENT_RESTRICTION_AUTHORIZE	This is for account restriction authorization.	Account Entitlement Restriction	Authorize
SRV_FA_ACC_ENT_RESTRICTION_AUTHQUERY	This is for an account restriction authorization query.	Account Entitlement Restriction	Authorize
SRV_FA_ACC_ENT_RESTRICTION_CLOSE	This is to close a record for account restriction.	Account Entitlement Restriction	Close
SRV_FA_ACC_ENT_RESTRICTION_DELETE	This is to delete a record for account restriction.	Account Entitlement Restriction	Delete
SRV_FA_ACC_ENT_RESTRICTION_GETBY_ID	This is to get all by ID for account restriction.	Account Entitlement Restriction	Detailed View
SRV_FA_ACC_ENT_RESTRICTION_HISTORY	This is for account restriction history.	Account Entitlement Restriction	History

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_ACC_ENT_RESTRICTION_MODIFY	This is for the account restriction modification record.	Account Entitlement Restriction	Unlock
SRV_FA_ACC_ENT_RESTRICTION_REJECT	This is for account restriction rejection.	Account Entitlement Restriction	Reject
SRV_FA_ACC_ENT_RESTRICTION_SAVE	This is for account restriction save.	Account Entitlement Restriction	Create
SRV_FA_ACC_GRP_AUTHORIZE	This is for account group authorization.	Settlements Definition	Authorize
SRV_FA_ACC_GRP_AUTH_QUERY	This is for the account group authorization query.	Settlements Definition	Authorize
SRV_FA_ACC_GRP_CLOSE_RECORD	This is for the account group close record.	Settlements Definition	Close
SRV_FA_ACC_GRP_DELETE	This is for account group deletion.	Settlements Definition	Delete
SRV_FA_ACC_GRP_GETALL	This is for account group get-all.	Settlements Definition	Summary Screen View
SRV_FA_ACC_GRP_GETBYID	This is for the account group get by ID.	Settlements Definition	Detailed View
SRV_FA_ACC_GRP_GET_HISTORY	This is for the account group to get history.	Settlements Definition	History
SRV_FA_ACC_GRP_MODIFY_RECORD	This is to modify a record for the account group.	Settlements Definition	Unlock

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_ACC_GRP_REOPEN_RECORD	This is to reopen a record for the account group.	Settlements Definition	Reopen
SRV_FA_ACC_GRP_SAVERECORD	This is to save a record for the account group.	Settlements Definition	Create
SRV_FA_AUTHMAINTENANCE_AUTHORIZE	This is for maintenance authorization.	Default Authorizer	Authorize
SRV_FA_AUTHMAINTENANCE_AUTHQUERY	This is for a maintenance authorization query.	Default Authorizer	Authorize
SRV_FA_AUTHMAINTENANCE_CLOSE	This is for maintenance close.	Default Authorizer	Close
SRV_FA_AUTHMAINTENANCE_DELETE	This is for maintenance delete.	Default Authorizer	Delete
SRV_FA_AUTHMAINTENANCE_GETALL	This is for maintenance getall.	Default Authorizer	Summary Screen View
SRV_FA_AUTHMAINTENANCE_GETBYID	This is for maintenance get by ID.	Default Authorizer	Detailed View
SRV_FA_AUTHMAINTENANCE_GETHISTORY	This is for maintenance get history.	Default Authorizer	History
SRV_FA_AUTHMAINTENANCE_MODIFY	This is for maintenance modification.	Default Authorizer	Unlock
SRV_FA_AUTHMAINTENANCE_NEW	This is for maintaining a new record.	Default Authorizer	Create
SRV_FA_AUTHMAINTENANCE_REOPEN	This is for the maintenance reopen record.	Default Authorizer	Reopen
SRV_FA_BANK_CODE_AUTHORIZE	This is for bank code configuration to authorize.	External Bank Code Maintenance	Authorize

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_BANK_CODE_AUTH_QUERY	This is for bank code configuration to authorize a query.	External Bank Code Maintenance	Authorize
SRV_FA_BANK_CODE_CLOSE_RECORD	This is for bank code configuration to close a record.	External Bank Code Maintenance	Close
SRV_FA_BANK_CODE_DELETE	This is for bank code configuration for deletion.	External Bank Code Maintenance	Delete
SRV_FA_BANK_CODE_GETALL	This is the bank code configuration for getall.	External Bank Code Maintenance	Summary Screen View
SRV_FA_BANK_CODE_GETBYID	This is the bank code configuration to get by ID.	External Bank Code Maintenance	Detailed View
SRV_FA_BANK_CODE_GET_HISTORY	This is the bank code configuration to get history.	External Bank Code Maintenance	History
SRV_FA_BANK_CODE_MODIFY_RECORD	This is for bank code configuration to modify a record.	External Bank Code Maintenance	Unlock
SRV_FA_BANK_CODE_REJECT	This is the bank code configuration for rejection.	External Bank Code Maintenance	Reject
SRV_FA_BANK_CODE_REOPEN_RECORD	This is to reopen the record for bank code configuration.	External Bank Code Maintenance	Reopen
SRV_FA_BANK_CODE_SAVERECORD	This is to save a record for bank code configuration.	External Bank Code Maintenance	Create
SRV_FA_BC_EXTERNAL_SYSTEM_AUTHORIZE	This is to authorize an external system.	External System Maintenance	Authorize

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_BC_EXTERNAL_SYSTEM_AUTHQUERY	This is to query external system authorization.	External System Maintenance	Authorize
SRV_FA_BC_EXTERNAL_SYSTEM_CLOSE	This is to close the external system.	External System Maintenance	Close
SRV_FA_BC_EXTERNAL_SYSTEM_DELETE	This is to delete the external system.	External System Maintenance	Delete
SRV_FA_BC_EXTERNAL_SYSTEM_GETALL	This is for external system getall.	External System Maintenance	Summary Screen View
SRV_FA_BC_EXTERNAL_SYSTEM_GETBYID	This is for the external system get by ID.	External System Maintenance	Detailed View
SRV_FA_BC_EXTERNAL_SYSTEM_GETHISTORY	This is for the external system to get history.	External System Maintenance	History
SRV_FA_BC_EXTERNAL_SYSTEM_MODIFYRECORD	This is to modify a record for an external system.	External System Maintenance	Unlock
SRV_FA_BC_EXTERNAL_SYSTEM_REJECT	This is for external system rejection.	External System Maintenance	Reject
SRV_FA_BC_EXTERNAL_SYSTEM_REOPEN	This is for the external system to reopen.	External System Maintenance	Reopen
SRV_FA_BC_EXTERNAL_SYSTEM_SAVERECORD	This is to save records for the external system.	External System Maintenance	Create
SRV_FA_BC_FUNCTION_PREF_AUTHORIZE	This is for function code preference authorization.	Function Code Preferences	Authorize

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_BC_FUNCTION_PREF_AUTHQUERY	This is for function code pref authorization query.	Function Code Preferences	Authorize
SRV_FA_BC_FUNCTION_PREF_CLOSE	This is for function code pref close.	Function Code Preferences	Close
SRV_FA_BC_FUNCTION_PREF_DELETE	This is for function code pref delete.	Function Code Preferences	Delete
SRV_FA_BC_FUNCTION_PREF_GETALL	This is for function code pref get all.	Function Code Preferences	Summary Screen View
SRV_FA_BC_FUNCTION_PREF_GETBYID	This is for function code pref get if.	Function Code Preferences	Detailed View
SRV_FA_BC_FUNCTION_PREF_GETHISTORY	This is for function code pref get history.	Function Code Preferences	History
SRV_FA_BC_FUNCTION_PREF_MODIFYRECORD	This is for function code pref modify record.	Function Code Preferences	Unlock
SRV_FA_BC_FUNCTION_PREF_REJECT	This is for function code pref reject.	Function Code Preferences	Reject
SRV_FA_BC_FUNCTION_PREF_REOPEN	This is for function code pref reopen.	Function Code Preferences	Reopen
SRV_FA_BC_FUNCTION_PREF_SAVERECORD	This is for function code pref save record.	Function Code Preferences	Create
SRV_FA_BC_IBTRANSIT_ACC_AUTHORIZE	This is to transit account authorization.	Inter Branch Transit Account	Authorize
SRV_FA_BC_IBTRANSIT_ACC_AUTHQUERY	This is to transit account authorize query.	Inter Branch Transit Account	Authorize
SRV_FA_BC_IBTRANSIT_ACC_CLOSE	This is to close the transit account.	Inter Branch Transit Account	Close

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_BC_IBTRANSIT_ACC_DELETE	This is to delete the transit account.	Inter Branch Transit Account	Delete
SRV_FA_BC_IBTRANSIT_ACC_GETALL	This is to transit account getall.	Inter Branch Transit Account	Summary Screen View
SRV_FA_BC_IBTRANSIT_ACC_GETBYID	This is to transit account get by ID.	Inter Branch Transit Account	Detailed View
SRV_FA_BC_IBTRANSIT_ACC_GETHISTORY	This is to transit account get history.	Inter Branch Transit Account	History
SRV_FA_BC_IBTRANSIT_ACC_MODIFYRECORD	This is to transit the account modify the record.	Inter Branch Transit Account	Unlock
SRV_FA_BC_IBTRANSIT_ACC_REJECT	This is to transit account rejection.	Inter Branch Transit Account	Reject
SRV_FA_BC_IBTRANSIT_ACC_REOPEN	This is to transit account reopen.	Inter Branch Transit Account	Reopen
SRV_FA_BC_IBTRANSIT_ACC_SAVERECORD	This is to transit account save the record.	Inter Branch Transit Account	Create
SRV_FA_BRANCH_GRP_AUTHORIZE	This is for branch group authorization.	Branch Group Maintenance	Authorize
SRV_FA_BRANCH_GRP_AUTH_QUERY	This is for branch group authorize query.	Branch Group Maintenance	Authorize
SRV_FA_BRANCH_GRP_CLOSE_RECORD	This is for the branch group close record.	Branch Group Maintenance	Close
SRV_FA_BRANCH_GRP_DELETE	This is for branch group delete records.	Branch Group Maintenance	Delete
SRV_FA_BRANCH_GRP_GETALL	This is for branch group getall.	Branch Group Maintenance	Summary Screen View

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_BRANCH_GRP_GETBYID	This is for branch groups get by ID.	Branch Group Maintenance	Detailed View
SRV_FA_BRANCH_GRP_GET_HISTORY	This is for the branch group get history.	Branch Group Maintenance	History
SRV_FA_BRANCH_GRP_MODIFY_RECORD	This is for the branch group modification record.	Branch Group Maintenance	Unlock
SRV_FA_BRANCH_GRP_REOPEN_RECORD	This is for the branch group to reopen a record.	Branch Group Maintenance	Reopen
SRV_FA_BRANCH_GRP_SAVERECORD	This is for the branch group to save records.	Branch Group Maintenance	Create
SRV_FA_BUSINESSPROCESS_AUTHORIZE	Business Process Authorize	Business Process Maintenance	Authorize
SRV_FA_BUSINESSPROCESS_AUTHQUERY	Business process authquery	Business Process Maintenance	Authorize
SRV_FA_BUSINESSPROCESS_CLOSE	Business Process Close	Business Process Maintenance	Close
SRV_FA_BUSINESSPROCESS_DELETE	Business Process Delete	Business Process Maintenance	Delete
SRV_FA_BUSINESSPROCESS_NEW	Business Process Creation	Business Process Maintenance	Create
SRV_FA_BUSINESSPROCESS_PUT	Business Process Update	Business Process Maintenance	Unlock
SRV_FA_BUSINESSPROCESS_REJECT	Business process reject	Business Process Maintenance	Reject
SRV_FA_BUSINESSPROCESS_REOPEN	Business Process Reopen	Business Process Maintenance	Reopen
SRV_FA_BUSINESSPROCESS_SUMMARY	Business Process View	Business Process Maintenance	Summary Screen View
SRV_FA_BUSINESSPROCESS_VIEW	Business Process View	Business Process Maintenance	Detailed View

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_CHANNEL_LIMIT_AUTHORIZE	This is for the channel limit authorize save.	Channel Limits	Authorize
SRV_FA_CHANNEL_LIMIT_AUTHQUERY	This is for channel limit authorize query.	Channel Limits	Authorize
SRV_FA_CHANNEL_LIMIT_CLOSERECORD	This is to close a record for channel limit.	Channel Limits	Close
SRV_FA_CHANNEL_LIMIT_DELETE	This is to delete the channel limit.	Channel Limits	Delete
SRV_FA_CHANNEL_LIMIT_FETCHDATA	This is to fetch data for channel limit.	Channel Limits	Detailed View
SRV_FA_CHANNEL_LIMIT_GETALL	This is to get all the details for the channel limit.	Channel Limits	Summary Screen View
SRV_FA_CHANNEL_LIMIT_GETBYID	This is for channel limit details by ID.	Channel Limits	Detailed View
SRV_FA_CHANNEL_LIMIT_GETHISTORY	This is for channel limit details by history.	Channel Limits	History
SRV_FA_CHANNEL_LIMIT_MODIFYRECORD	This is for channel limit details to modify a record.	Channel Limits	Unlock
SRV_FA_CHANNEL_LIMIT_REOPENRECORD	This is for channel limit details to reopen the record.	Channel Limits	Reopen
SRV_FA_CHANNEL_LIMIT_SAVERECORD	This is for channel limit save.	Channel Limits	Create
SRV_FA_CHARGE_DEF_MAINTENANCE_AUTHORIZE	This is for charge definition maintenance authorization.	Charge Definition Maintenance	Authorize

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_CHARGE_DEF_MAINTENANCE_AUTHQ	This is for charge definition maintenance authenticatio n.	Charge Definition Maintenance	Authorize
SRV_FA_CHARGE_DEF_MAINTENANCE_CLOSE	This is to close charge definition maintenance.	Charge Definition Maintenance	Close
SRV_FA_CHARGE_DEF_MAINTENANCE_DELETE	This is to delete charge definition maintenance.	Charge Definition Maintenance	Delete
SRV_FA_CHARGE_DEF_MAINTENANCE_GETALL	This is for charge definition maintenance to get all entries.	Charge Definition Maintenance	Summary Screen View
SRV_FA_CHARGE_DEF_MAINTENANCE_GETBYID	This is a charge definition maintenance obtained by ID.	Charge Definition Maintenance	Detailed View
SRV_FA_CHARGE_DEF_MAINTENANCE_HISTORY	This is for charge definition maintenance history.	Charge Definition Maintenance	History
SRV_FA_CHARGE_DEF_MAINTENANCE_MODIFY	This is for charge definition maintenance modification.	Charge Definition Maintenance	Unlock
SRV_FA_CHARGE_DEF_MAINTENANCE_REOPEN	This is to reopen charge definition maintenance.	Charge Definition Maintenance	Reopen
SRV_FA_CHARGE_DEF_MAINTENANCE_SAVE	This is to save a charge for definition maintenance.	Charge Definition Maintenance	Create
SRV_FA_CHARGE_GROUP_AUTHORIZE	This is for charge group authorization.	Charge Condition Group Maintenance	Authorize

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_CHARGE_GROUP_AUTHQ	This is for charge group authenticatio n.	Charge Condition Group Maintenance	Authorize
SRV_FA_CHARGE_GROUP_CLOSE	This is to close the charge group.	Charge Condition Group Maintenance	Close
SRV_FA_CHARGE_GROUP_DELETE	This is to delete a charge group.	Charge Condition Group Maintenance	Delete
SRV_FA_CHARGE_GROUP_GETALL	This is to get all entries for the charge group.	Charge Condition Group Maintenance	Summary Screen View
SRV_FA_CHARGE_GROUP_GETBYID	This is for the charge group get by ID.	Charge Condition Group Maintenance	Detailed View
SRV_FA_CHARGE_GROUP_HISTORY	This is for charge group history.	Charge Condition Group Maintenance	History
SRV_FA_CHARGE_GROUP_MODIFY	This is to modify the charge group.	Charge Condition Group Maintenance	Unlock
SRV_FA_CHARGE_GROUP_REOPEN	This is to reopen the charge group.	Charge Condition Group Maintenance	Reopen
SRV_FA_CHARGE_GROUP_SAVE	This is to save a charge group.	Charge Condition Group Maintenance	Create
SRV_FA_CHARGE_PICK_AUTHORIZE	This is for charge pick-up authorization.	Charge Decision Maintenance	Authorize
SRV_FA_CHARGE_PICK_AUTHQ	This is for charge pick-up authenticatio n.	Charge Decision Maintenance	Authorize
SRV_FA_CHARGE_PICK_CLOSE	This is to close a charge pick-up.	Charge Decision Maintenance	Close

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_CHARGE_PICK_DELETE	This is to delete charge pick-up.	Charge Decision Maintenance	Delete
SRV_FA_CHARGE_PICK_GETALL	This is for charge pick-up up get all entries.	Charge Decision Maintenance	Summary Screen View
SRV_FA_CHARGE_PICK_GETBYID	This is for charge pick up get by ID.	Charge Decision Maintenance	Detailed View
SRV_FA_CHARGE_PICK_HISTORY	This is for charge pick-up history.	Charge Decision Maintenance	History
SRV_FA_CHARGE_PICK_MODIFY	This is to modify charge pick up.	Charge Decision Maintenance	Unlock
SRV_FA_CHARGE_PICK_REOPEN	This is to reopen charge pick up.	Charge Decision Maintenance	Reopen
SRV_FA_CHARGE_PICK_SAVE	This is to save a charge for pick up.	Charge Decision Maintenance	Create
SRV_FA_CUST_GRP_AUTHORIZE	This is to authorize the customer group.	Customer Group Maintenance	Authorize
SRV_FA_CUST_GRP_AUTH_QUERY	This is to query customer group authorization.	Customer Group Maintenance	Authorize
SRV_FA_CUST_GRP_CLOSE_RECORD	This is for the customer group close record.	Customer Group Maintenance	Close
SRV_FA_CUST_GRP_DELETE	This is for customer group deletion.	Customer Group Maintenance	Delete
SRV_FA_CUST_GRP_GETALL	This is to get all customers for the customer group.	Customer Group Maintenance	Summary Screen View

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_CUST_GRP_GETBYID	This is for the customer group get by ID.	Customer Group Maintenance	Detailed View
SRV_FA_CUST_GRP_GET_HISTORY	This is for the customer group to get history.	Customer Group Maintenance	History
SRV_FA_CUST_GRP_MODIFY_RECORD	This is to modify a record for the customer group.	Customer Group Maintenance	Unlock
SRV_FA_CUST_GRP_REOPEN_RECORD	This is to reopen the record for the customer group.	Customer Group Maintenance	Reopen
SRV_FA_CUST_GRP_SAVERECORD	This is to save a record for the customer group.	Customer Group Maintenance	Create
SRV_FA_DENOMINATIONS_AUTHORIZE	This is to authorize denominations.	Denominations Maintenance	Authorize
SRV_FA_DENOMINATIONS_AUTH_QUERY	This is for denominations to authorize queries.	Denominations Maintenance	Authorize
SRV_FA_DENOMINATIONS_CLOSE_RECORD	This is to close the denomination record.	Denominations Maintenance	Close
SRV_FA_DENOMINATIONS_DELETE	This is to delete the denomination record.	Denominations Maintenance	Delete
SRV_FA_DENOMINATIONS_GETALL	This is to get all denominations.	Denominations Maintenance	Summary Screen View
SRV_FA_DENOMINATIONS_GETBYID	This is to get denominations by ID.	Denominations Maintenance	Detailed View
SRV_FA_DENOMINATIONS_GETHISTORY	This is to get denominations by history.	Denominations Maintenance	History

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_DENOMINATIONS_MODIFY_RECORD	This is to modify the denomination record.	Denominations Maintenance	Unlock
SRV_FA_DENOMINATIONS_REOPEN_RECORD	This is to modify denominations and reopen the record.	Denominations Maintenance	Reopen
SRV_FA_DENOMINATIONS_SAVERECORD	This is to modify denominations and save records.	Denominations Maintenance	Create
SRV_FA_DENOMWISEVAR_FEAT_AUTHORIZE	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Authorize
SRV_FA_DENOMWISEVAR_FEAT_AUTH_QUERY	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Authorize
SRV_FA_DENOMWISEVAR_FEAT_CLOSE_RECORD	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Close
SRV_FA_DENOMWISEVAR_FEAT_DELETE	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Delete

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_DENOMWISEVAR_FEAT_GETALL	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Summary Screen View
SRV_FA_DENOMWISEVAR_FEAT_GETBYID	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Detailed View
SRV_FA_DENOMWISEVAR_FEAT_GET_HISTORY	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	History
SRV_FA_DENOMWISEVAR_FEAT_MODIFY_RECORD	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Unlock
SRV_FA_DENOMWISEVAR_FEAT_REOPEN_RECORD	This application programming interface is for the denomination-wise variance feature.	Denomination Variance Maintenance	Reopen

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_DENOMWISEVAR_FEAT_SAVERECORD	This application programming interface is for the denomination -wise variance feature.	Denomination Variance Maintenance	Create
SRV_FA_FUNC_CODE_DEFIN_AUTHORIZE	This is to authorize function code definition.	Function Code Definition	Authorize
SRV_FA_FUNC_CODE_DEFIN_AUTHQUERY	This is to authorize function code definition to authorize query.	Function Code Definition	Authorize
SRV_FA_FUNC_CODE_DEFIN_CLOSE	This is to close the function code definition.	Function Code Definition	Close
SRV_FA_FUNC_CODE_DEFIN_DELETE	This is to delete the function code definition.	Function Code Definition	Delete
SRV_FA_FUNC_CODE_DEFIN_GET	This is for function code definition get all.	Function Code Definition	Summary Screen View
SRV_FA_FUNC_CODE_DEFIN_GETBY_ID	This is for function code definition get by ID.	Function Code Definition	Detailed View
SRV_FA_FUNC_CODE_DEFIN_HISTORY	This is for function code definition history.	Function Code Definition	History
SRV_FA_FUNC_CODE_DEFIN_POST	This is to save a record for function code definition.	Function Code Definition	Create
SRV_FA_FUNC_CODE_DEFIN_PUT	This is to modify a record for function code definition.	Function Code Definition	Unlock

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_FUNC_CODE_DEFIN_REOPEN	This is to reopen a record for function code definition.	Function Code Definition	Reopen
SRV_FA_FUNC_CODE_REJECT	This is to reject a record for function code definition.	Function Code Definition	Reject
SRV_FA_ISSUERCODE_AUTHORIZE	This is for issuer code authorization.	Issuer Code Maintenance	Authorize
SRV_FA_ISSUERCODE_AUTHQUERY	This is to issuer code auth query.	Issuer Code Maintenance	Authorize
SRV_FA_ISSUERCODE_CLOSERECORD	This is to issuer code close record.	Issuer Code Maintenance	Close
SRV_FA_ISSUERCODE_DELETE	This is for the issuer code deletion.	Issuer Code Maintenance	Delete
SRV_FA_ISSUERCODE_GETALL	This is for the issuer code to get all.	Issuer Code Maintenance	Summary Screen View
SRV_FA_ISSUERCODE_GETBYID	This is for the issuer code to get by id.	Issuer Code Maintenance	Detailed View
SRV_FA_ISSUERCODE_GETHISTORY	This is for the issuer code to get the history.	Issuer Code Maintenance	History
SRV_FA_ISSUERCODE_MODIFYRECORD	This is for the issuer code to modify a record.	Issuer Code Maintenance	Unlock
SRV_FA_ISSUERCODE_REOPENRECORD	This is for the issuer code to reopen the record.	Issuer Code Maintenance	Reopen
SRV_FA_ISSUERCODE_SAVERECORD	This is for the issuer code to save the record.	Issuer Code Maintenance	Create
SRV_FA_ISSUER_CODE_REJECT	This is for the issuer code reject.	Issuer Code Maintenance	Reject

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_NETWORKCODE_AUTHORIZE	This is to reject network code authorization.	Clearing Network	Authorize
SRV_FA_NETWORKCODE_AUTHQUERY	This is for the rejected network code to authorize a query.	Clearing Network	Authorize
SRV_FA_NETWORKCODE_CLOSERECORD	This is for the rejected network code to close a record.	Clearing Network	Close
SRV_FA_NETWORKCODE_DELETE	This is to reject network code deletion.	Clearing Network	Delete
SRV_FA_NETWORKCODE_GETALL	This is for the rejected network code to get all.	Clearing Network	Summary Screen View
SRV_FA_NETWORKCODE_GETBYID	This is for the rejected network code get by ID.	Clearing Network	Detailed View
SRV_FA_NETWORKCODE_GETHISTORY	This is to get the history of the rejected network code.	Clearing Network	History
SRV_FA_NETWORKCODE_MODIFYRECORD	This is to modify a record for the rejected network code.	Clearing Network	Unlock
SRV_FA_NETWORKCODE_REJECT	This is to reject the network code.	Clearing Network	Reject
SRV_FA_NETWORKCODE_REOPENRECORD	This is to reopen a record for the rejected network code.	Clearing Network	Reopen

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_NETWORKCODE_SAVERECORD	This is to save a record of the rejected network code.	Clearing Network	Create
SRV_FA_PAY_INSTR_AUTHORIZE	This is for payment instrument authorization.	Instrument Number Maintenance	Authorize
SRV_FA_PAY_INSTR_AUTHQUERY	This is to payment instrument auth query.	Instrument Number Maintenance	Authorize
SRV_FA_PAY_INSTR_CLOSE	This is to pay the instrument close record.	Instrument Number Maintenance	Close
SRV_FA_PAY_INSTR_DELETE	This is to payment instrument.	Instrument Number Maintenance	Delete
SRV_FA_PAY_INSTR_GETALL	This is to payment instrument get all.	Instrument Number Maintenance	Summary Screen View
SRV_FA_PAY_INSTR_GETBYID	This is for the payment instrument get by ID.	Instrument Number Maintenance	Detailed View
SRV_FA_PAY_INSTR_GETHISTORY	This is to payment instrument get history.	Instrument Number Maintenance	History
SRV_FA_PAY_INSTR_MODIFYRECORD	This is for payment instruments to modify records.	Instrument Number Maintenance	Unlock
SRV_FA_PAY_INSTR_REJECT	This is for the payment instrument rejection.	Instrument Number Maintenance	Reject
SRV_FA_PAY_INSTR_REOPEN	This is for payment instruments to reopen the record.	Instrument Number Maintenance	Reopen

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_PAY_INSTR_SAVERECORD	This is to payment instrument to save the record.	Instrument Number Maintenance	Create
SRV_FA_PROVIDERMAINT_AUTHORIZE	This is to provide maintenance authorization.	Utility Provider Maintenance	Authorize
SRV_FA_PROVIDERMAINT_AUTHQUERY	This is to provide maintenance auth query.	Utility Provider Maintenance	Authorize
SRV_FA_PROVIDERMAINT_CLOSERECORD	This is to provide a maintenance close record.	Utility Provider Maintenance	Close
SRV_FA_PROVIDERMAINT_DELETE	This is to provide maintenance delete.	Utility Provider Maintenance	Delete
SRV_FA_PROVIDERMAINT_GETALL	This is to provide maintenance get all.	Utility Provider Maintenance	Summary Screen View
SRV_FA_PROVIDERMAINT_GETBYID	This is for the provider maintenance by ID.	Utility Provider Maintenance	Detailed View
SRV_FA_PROVIDERMAINT_GETHISTORY	This is to provide maintenance get history.	Utility Provider Maintenance	History
SRV_FA_PROVIDERMAINT_MODIFYRECORD	This is to provide maintenance and modify the record.	Utility Provider Maintenance	Unlock
SRV_FA_PROVIDERMAINT_REJECT	This is to maintenance reject.	Utility Provider Maintenance	Reject
SRV_FA_PROVIDERMAINT_REOPENRECORD	This is to provide maintenance records.	Utility Provider Maintenance	Reopen
SRV_FA_PROVIDERMAINT_SAVERECORD	This is to provide maintenance save records.	Utility Provider Maintenance	Create

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_ROLEBASEDLIMIT_APPROVE	This is to role-based limit authorization.	Branch Role Limits	Authorize
SRV_FA_ROLEBASEDLIMIT_AUTHQ	This is role based limit auth query.	Branch Role Limits	Authorize
SRV_FA_ROLEBASEDLIMIT_CLOSE	This is to close a role-based limit record.	Branch Role Limits	Close
SRV_FA_ROLEBASEDLIMIT_DELETE	This is to delete a role-based limit record.	Branch Role Limits	Delete
SRV_FA_ROLEBASEDLIMIT_GETALL	This is to Get an electronic journal log by source reference number.	Branch Role Limits	Summary Screen View
SRV_FA_ROLEBASEDLIMIT_GETBYID	This is to get a record by ID for the Role-based limit record.	Branch Role Limits	Detailed View
SRV_FA_ROLEBASEDLIMIT_GETBYROLEID	This is to get a record by Role ID for the Role-based limit record.	Branch Role Limits	Detailed View
SRV_FA_ROLEBASEDLIMIT_HISTORY	This is to Get an electronic journal log by source reference number.	Branch Role Limits	History
SRV_FA_ROLEBASEDLIMIT_REJECT	This is to reject a role-based limit record.	Branch Role Limits	Reject
SRV_FA_ROLEBASEDLIMIT_REOPEN	This is to reopen a role-based limit record.	Branch Role Limits	Reopen
SRV_FA_ROLEBASEDLIMIT_SAVE	This is to save a role-based limit record.	Branch Role Limits	Create

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_ROLEBASEDLIMIT_UPDATE	This is to modify a role-based limit record.	Branch Role Limits	Unlock
SRV_FA_TELLER_AUTHORIZE	Authorize the teller branch maintenance record by given ID.	Teller Branch Parameter Maintenance	Authorize
SRV_FA_TELLER_AUTH_QUERY	Retrieves the teller branch maintenance record by given ID.	Teller Branch Parameter Maintenance	Authorize
SRV_FA_TELLER_CLOSE_RECORD	This is to close the teller branch maintenance record by given ID.	Teller Branch Parameter Maintenance	Close
SRV_FA_TELLER_DELETE	This is to delete the teller branch maintenance record by the given ID.	Teller Branch Parameter Maintenance	Delete
SRV_FA_TELLER_GETALL	This is to get all valid teller branch maintenance.	Teller Branch Parameter Maintenance	Summary Screen View
SRV_FA_TELLER_GETBYID	Retrieves the teller branch maintenance record by the ID.	Teller Branch Parameter Maintenance	Detailed View
SRV_FA_TELLER_GET_HISTORY	Retrieves the teller branch maintenance record by the ID.	Teller Branch Parameter Maintenance	History
SRV_FA_TELLER_MODIFY_RECORD	This is to Update the electronic journal log by source reference number.	Teller Branch Parameter Maintenance	Unlock

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_TELLER_REOPEN_RECORD	Reopen the teller branch maintenance record by the ID.	Teller Branch Parameter Maintenance	Reopen
SRV_FA_TELLER_SAVERECORD	This is to Add an electronic journal log by source reference number.	Teller Branch Parameter Maintenance	Create
SRV_FA_USER_AUTHORIZE	This is to Authorize the user-maintenance by given ID.	Branch User Limits	Authorize
SRV_FA_USER_AUTHQUERY	Retrieves the user maintenance by given ID.	Branch User Limits	Authorize
SRV_FA_USER_CLOSE	Close the user maintenance by given ID.	Branch User Limits	Close
SRV_FA_USER_DELETE	This is to delete the electronic journal log by source reference number.	Branch User Limits	Delete
SRV_FA_USER_HISTORY	Retrieves the user preferences for user IDs open for the current branch date.	Branch User Limits	History
SRV_FA_USER_PREF_BYID	Get user preferences by ID.	Branch User Limits	Detailed View
SRV_FA_USER_PREF_GET	This is to get all valid user maintenance.	Branch User Limits	Summary Screen View
SRV_FA_USER_PREF_GETBY_ID	Retrieves the user maintenance by ID.	Branch User Limits	Detailed View

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_USER_PREF_POST	Adds a new user maintenance.	Branch User Limits	Create
SRV_FA_USER_PREF_PUT	This is to modify user preferences.	Branch User Limits	Unlock
SRV_FA_USER_PREF_ROLE	Get user preferences by till/vault indicator.	Branch User Limits	Detailed View
SRV_FA_USER_REOPEN	This is to reopen the user.	Branch User Limits	Reopen
SRV_FA_USER_VIEWCHANGES	This is to view user preferences changes	Branch User Limits	History
SRV_FA_UTILITYPROVIDER_AUTHORIZE	This is to authorize Utility Provider	Utility Provider Maintenance	Authorize
SRV_FA_UTILITYPROVIDER_AUTHQUERY	Retrieves theUtility Provider maintenance record by given ID.	Utility Provider Maintenance	Authorize
SRV_FA_UTILITYPROVIDER_CLOSERECORD	This is to close Utility Provider	Utility Provider Maintenance	Close
SRV_FA_UTILITYPROVIDER_DELETE	This is to delete Utility Provider	Utility Provider Maintenance	Delete
SRV_FA_UTILITYPROVIDER_GETALL	Get all valid provider maintenance.	Utility Provider Maintenance	Summary Screen View
SRV_FA_UTILITYPROVIDER_GETBYID	Retrieves the provided maintenance by ID.	Utility Provider Maintenance	Detailed View
SRV_FA_UTILITYPROVIDER_GETHISTORY	Retrieves the provided maintenance by ID.	Utility Provider Maintenance	History
SRV_FA_UTILITYPROVIDER_MODIFYRECORD	This is to modify Utility Provider	Utility Provider Maintenance	Unlock
SRV_FA_UTILITYPROVIDER_REJECT	This is to reject.	Utility Provider Maintenance	Reject

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_UTILITYPROVIDER_REOPENRECORD	Reopens the provider maintenance by given ID.	Utility Provider Maintenance	Reopen
SRV_FA_UTILITYPROVIDER_SAVERECORD	Adds a new provider maintenance.	Utility Provider Maintenance	Create
SRV_FA_AUTHQ_ID_PRC_RULE	This is to authorize a prc rule.	Charge Pricing Maintenance	Authorize
SRV_FA_AUTH_PRC_RULE	This is to authorize the rule.	Charge Pricing Maintenance	Authorize
SRV_FA_CLOSE_PRC_RULE	This is to close the price rule.	Charge Pricing Maintenance	Close
SRV_FA_COPY_PRC_RULE	This is for the price rule copy.	Charge Pricing Maintenance	Copy
SRV_FA_CREATE_PRC_RULE	This is to create a price rule.	Charge Pricing Maintenance	Create
SRV_FA_DELETE_PRC_RULE	This is for price rule deletion.	Charge Pricing Maintenance	Delete
SRV_FA_MODIFY_PRC_RULE	This is for the price rule modify.	Charge Pricing Maintenance	Unlock
SRV_FA_REOPEN_PRC_RULE	This is to price rule reopen.	Charge Pricing Maintenance	Reopen
SRV_FA_GST_MAINT_GETBYID	GST rule maintenance get by record ID	GST Rule Maintenance	-
SRV_FA_GST_MAINT_AUTHORIZE	GST rule maintenance authorize record	GST Rule Maintenance	-
SRV_FA_GST_MAINT_MODIFYRECORD	GST rule maintenance modify record	GST Rule Maintenance	-
SRV_FA_GST_MAINT_AUTHQUERY	GST rule maintenance query unauthorized records	GST Rule Maintenance	-

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_GST_MAINT_GETHISTORY	GST rule maintenance fetch record history	GST Rule Maintenance	-
SRV_FA_GST_MAINT_DELETE	GST rule maintenance delete record	GST Rule Maintenance	-
SRV_FA_GST_MAINT_CLOSERECORD	GST rule maintenance close record	GST Rule Maintenance	-
SRV_FA_GST_MAINT_REOPENRECORD	GST rule maintenance reopen closed record	GST Rule Maintenance	-
SRV_FA_GST_MAINT_REJECT	GST rule maintenance reject record	GST Rule Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_GETBYID	GST Branch maintenance get by record ID	GST Branch Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_AUTHORIZE	GST Branch maintenance authorize record	GST Branch Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_MODIFYRECORD	GST Branch maintenance modify record	GST Branch Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_AUTHQUERY	GST Branch maintenance query unauthorized records	GST Branch Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_GETHISTORY	GST Branch maintenance fetch record history	GST Branch Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_DELETE	GST Branch maintenance delete record	GST Branch Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_CLOSERECORD	GST Branch maintenance close record	GST Branch Maintenance	-
SRV_FA_GST_BRANCH_PARAMETERS_REOPENRECORD	GST Branch maintenance reopen closed record	GST Branch Maintenance	-

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_GST_BRANCH_PARAMETERS_REJECT	GST Branch maintenance reject record	GST Branch Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_GETBYID	GST Cust account parameters maintenance get by record ID	GST Cust Account Parameters Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_AUTHORIZE	GST Cust account parameters maintenance authorize record	GST Cust Account Parameters Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_MODIFYRECORD	GST Cust account parameters maintenance modify record	GST Cust Account Parameters Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_AUTHQUERY	GST Cust account parameters maintenance query unauthorized records	GST Cust Account Parameters Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_GETHISTORY	GST Cust account parameters maintenance fetch record history	GST Cust Account Parameters Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_DELETE	GST Cust account parameters maintenance delete record	GST Cust Account Parameters Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_CLOSERECORD	GST Cust account parameters maintenance close record	GST Cust Account Parameters Maintenance	-
SRV_FA_GST_CUST_ACC_PARAMETERS_REOPENRECORD	GST Cust account parameters maintenance reopen closed record	GST Cust Account Parameters Maintenance	-

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-3 (Cont.) List of Functional Activity codes corresponding to each action of maintenanace screen

Fuctional Activity Code	Functional Activity Description	Screen Name	Action
SRV_FA_GST_CUST_ACC_PARAMETERS_REJECT	GST Cust account parameters maintenance reject record	GST Cust Account Parameters Maintenance	-
SRV_FA_GET_DENOMINATIONS_REJECT	Denominatio n Reject	Denomination Reject	-
SRV_FA_GET_USER_PREF_REJECT	User Preference Reject	User Preference Reject	-
SRV_FA_ACC_MAINT_REJECT	Account Maintenance Reject	Account Maintenance Reject	-
SRV_FA_TELLER_BRANCH_PARAM_ REJECT	Teller Branch Param Reject	Teller Branch Param Reject	-
SRV_FA_CHARGE_DEF_REJECT	Charge definition Reject	Charge Definition Reject	-
SRV_FA_GET_CHARGE_PICK_REJECT	Charge pickup Reject	Charge Pickup Reject	-
SRV_FA_GET_BRANCH_GROUP_REJECT	Branch group Reject	Branch Group Reject	-
SRV_FA_GET_CUST_GROUP_REJECT	Customer group Reject	Customer Group Reject	-
SRV_FA_GET_ACC_GROUP_REJECT	Account Group Reject	Account Group Reject	-
SRV_FA_GET_DENOM_VAR_REJECT	Denominatio n variance Reject	Denomination Variance Reject	-
SRV_FA_DEF_AUTH_REJECT	-	Auth Reject	-
SRV_FA_CHANNEL_REJECT	Auth Reject	Channel Reject	-
SRV_FA_REJECT_CODE_REJECT	Reject Code Reject	Reject Code Reject	-
SRV_FA_DELETE_PRC_RULE_PUT	Delete Price Rule Update	Delete Price Rule Update	-
SRV_FA_GET_CHARGE_GROUP_REJECT	Charge group Reject	Charge Group Reject	-

Table A-4 List of Functional Activity codes to be mapped to appear in menu for transaction screen

Functional Activity Code	Screen Name and Functional Activity Description
REMO_FA_CC_PAY_BY_CASH	Payment By Cash

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-4 (Cont.) List of Functional Activity codes to be mapped to appear in menu for transaction screen

Functional Activity Code	Screen Name and Functional Activity Description
REMO_FA_CREDIT_CARD_PAYMENT	Credit Card Payment
SRV_FA_ACCOUNT_BALANCE	Account Balance Inquiry
SRV_FA_ACCOUNT_STATEMENT_REQUEST	Account Statement Request
SRV_FA_ACC_TRF_DCT	Account Transfer
SRV_FA_BC_ISSUANCE_ACC	BC Issue - Account
SRV_FA_BC_ISSUANCE_GL	BC Issue - GL
SRV_FA_BC_ISSUANCE_WALKIN	BC Issue - Walk-in
SRV_FA_BC_OPERATIONS	BC Operations
SRV_FA_BC_PRINT_REPRINT	BC Print-Reprint
SRV_FA_BILL_PAY_BY_ACCOUNT	Bill Payment by Other Modes
SRV_FA_BILL_PAY_BY_CASH	Bill Payment by Cash
SRV_FA_BOOK_OVERAGE	Book Overage
SRV_FA_BOOK_SHORTAGE	Book Shortage
SRV_FA_BRANCH_BREACHING_LIMITS	Branch Breach Limits
SRV_FA_BUYCASH_FROM_CURRENCYCHEST	Buy Cash from Ccy Chest
SRV_FA_CASH_DEPOSIT	Cash Deposit
SRV_FA_CASH_DEPOSIT_TELLER	Cash Deposit
SRV_FA_CASH_WITHDRAWAL	Cash Withdrawal
SRV_FA_CASH_WITHDRAWL_TELLER	Cash Withdrawal
SRV_FA_CC_ADV_BY_CASH	Advance By Cash
SRV_FA_CC_ADV_BY_TRANSFER	Advance By Transfer
SRV_FA_CC_STOP_CARD_REQ	Stop Card
SRV_FA_CHARGE_DECISION_ENQUIRY	Charge Decision Enquiry
SRV_FA_CHEQUE_BOOK_REQUEST	Cheque Book Request
SRV_FA_CHEQUE_BOOK_STATUS_CHANGE	Cheque Book Status Change
SRV_FA_CHEQUE_DEPOSIT	Cheque Deposit
SRV_FA_CHEQUE_RETURN	Cheque Return
SRV_FA_CHEQUE_STATUS_INQUIRY	Cheque Status Inquiry
SRV_FA_F23A_TAX	F23 Tax Payment By Account
SRV_FA_CLOSE_BRANCH_BATCH	Close Branch Batch
SRV_FA_CLOSE_TELLER_BATCH	Close Teller Batch
SRV_FA_CLOSE_VAULT_BATCH	Close Vault Batch
SRV_FA_CLOSOUT_NEW_MENU	Close Out Withdrawal
SRV_FA_CLSOUTWITHDRAWAL_MULTIMODE_SAVE	Close Out Withdrawal By Multi Mode
SRV_FA_CURRENT_OPEN_TILLS	Current Open Tills
SRV_FA_DD_ISSUANCE_ACC	DD Issue - Account
SRV_FA_DD_ISSUANCE_GL	DD Issue - GL
SRV_FA_DD_ISSUANCE_WALKIN	DD Issue - Walk-in
SRV_FA_DD_OPERATIONS	DD Operations
SRV_FA_DD_PRINT_REPRINT	DD Print-Reprint

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-4 (Cont.) List of Functional Activity codes to be mapped to appear in menu for transaction screen

Functional Activity Code	Screen Name and Functional Activity Description
SRV_FA_DENOMINATION_EXCHANGE	Denomination Exchange
SRV_FA_DEPOSIT_RENTAL_CASH	Safe Deposit Rental By Cash
SRV_FA_EJREASSIGN	Reassign Transactions
SRV_FA_ELECTRONIC_JOURNAL_LOG_CASH	Electronic Journal
SRV_FA_ELECTRONIC_JOURNAL_LOG_NON_CASH	Servicing Journal
SRV_FA_F23C_TAX	F23 Tax Payment By Cash
SRV_FA_F24C_TAX	F24C Tax Payment-Cash
SRV_FA_F24A_TAX	F24C Tax Payment-Account
SRV_FA_FT_TRANSFER_ACCOUNT	Domestic Transfer - Account
SRV_FA_FT_TRANSFER_WALKIN	Domestic Transfer - Walk-in
SRV_FA_FX_PURCHASE_AGAINST_ACC	FX Purchase - Account
SRV_FA_FX_PURCHASE_WALKIN	FX Purchase - Walk-in
SRV_FA_FX_PURCHASE_WALKIN_TELLER	FX Purchase - Walk-in
SRV_FA_FX_SALE_AGAINST_ACC	FX Sale - Account
SRV_FA_FX_SALE_WALKIN	FX Sale - Walk-in
SRV_FA_FX_SALE_WALKIN_TELLER	FX Sale - Walk-in
SRV_FA_GL_TRANSFER	Misc GL Transfer
SRV_FA_INHOUSE_CHQ_DEP	In House Cheque Deposit
SRV_FA_INHOUSE_CHQ_DEP_DIR	In House Cheque Deposit
SRV_FA_INSTR_UP_MENU	Instrument Status Update
SRV_FA_INTRBRANCH_SAVE_	Inter Branch Txn Input
SRV_FA_INTRBRANCH__LIQ_	Inter Branch Txn Liq
SRV_FA_INT_BRANCH_TXN_REQ	Inter Branch Txn Req
SRV_FA_INT_TRANSFER_ACC	International - Account
SRV_FA_INT_TRANSFER_WALKIN	International - Walk-in
SRV_FA_INWARD_CLEARING	Inward Clearing Data Entry
SRV_FA_INWARD_REMITTANCE	Inward Registration
SRV_FA_ISLAMIC_DOWN_PAYMENT_BY_CASH	Islamic Down Payment By Cash
SRV_FA_ISLAMIC_TD_ACCOUNT_OPENING	Islamic TD Account Opening
SRV_FA_ISSUE	Issue
SRV_FA_LOAN_DISBURSEMENT_BY_CASH	Loan Disbursement By Cash
SRV_FA_LOAN_REPAYMENT_BY_CASH	Loan Repayment By Cash
SRV_FA_LOAN_REPAYMENT_BY_CASH_TELLER	Loan Repayment By Cash
SRV_FA_MISC_CUST_CREDIT	Misc Customer Credit
SRV_FA_MISC_CUST_DEBIT	Misc Customer Debit
SRV_FA_MISC_GL_CREDIT	Misc GL Credit
SRV_FA_MISC_GL_DEBIT	Misc GL Debit
SRV_FA_MISC_TRANSFER	Miscellaneous Transfer
SRV_FA_MULTI_BC_ISSUANCE	Multi BC Issuance
SRV_FA_MURABAHA_PAYMENT_BY_CASH	Murabaha Payment By Cash

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-4 (Cont.) List of Functional Activity codes to be mapped to appear in menu for transaction screen

Functional Activity Code	Screen Name and Functional Activity Description
SRV_FA_OPEN_BRANCH_BATCH	Open Branch Batch
SRV_FA_OPEN_TELLER_BATCH	Open Teller Batch
SRV_FA_OPEN_VAULT_BATCH	Open Vault Batch
SRV_FA_OPERATIONS	Operations
SRV_FA_OUTWARD_CLEARING	Outward Clearing Data Entry
SRV_FA_PASSBOOK_ISSUE	Passbook Issue
SRV_FA_PASSBOOK_STATUS_CHANGE	Passbook Status Change
SRV_FA_PASSBOOK_UPDATE	Passbook Update
SRV_FA_PB_REPRINT	Passbook Reprint
SRV_FA_RD_PAYMENT_CASH	RD Payment - Cash
SRV_FA_SELLCASH_TO_CURRENCYCHEST	Sell Cash to Ccy Chest
SRV_FA_STOP_CHEQUE_BOOK	Stop Cheque Request
SRV_FA_TC_BUY_FROM_AGENT	Buy TC From Agent
SRV_FA_TC_BUY_FROM_HO	Buy TC From HO
SRV_FA_TC_BUY_FROM_VAULT	Buy TC From Vault
SRV_FA_TC_DENOM_ENQUIRY	TC Denomination Enquiry
SRV_FA_TC_SALE_TO_HO	Return TC To HO
SRV_FA_TD_ACCOPEN_AGAINST_CASH	TD Account Opening
SRV_FA_TD_REDEMPTION_AGAINST_ACCOUNT	TD Redemption - Account
SRV_FA_TD_REDEMPTION_AGAINST_CASH	TD Redemption - Cash
SRV_FA_TD_TOPUP_AGAINST_ACCOUNT	TD Topup - Account
SRV_FA_TD_TOPUP_AGAINST_CASH	TD Topup - Cash
SRV_FA_TELLER_PREDICTION	Teller Prediction
SRV_FA_TELLER_TOTALS_POSITION	Branch Total Position
SRV_FA_TILL_VAULT_POSITION	Till Vault Position
SRV_FA_TRANSFERCASH_FROM_TILL	Buy Cash from Till
SRV_FA_TRANSFERCASH_FROM_VAULT	Buy Cash from Vault
SRV_FA_TRANSFERCASH_TO_TILL	Sell Cash to Till
SRV_FA_TRANSFERCASH_TO_VAULT	Sell Cash to Vault
SRV_FA_TX_END_TELLER_SESSION_TXN	Stop Teller Session
SRV_FA_TX_SAVE_TELLER_SESSION_TXN	Start Teller Session
SRV__FA_TC_RETURN_TO_VAULT	Return TC to Vault
SRV_FA_CASH_WITHDRAWL	Cheque Withdrawal
SRV_FA_BOOK_VAULT_OVERAGE	Book Vault Overage
SRV_FA_BOOK_VAULT_SHORTAGE	Book Vault Shortage
SRV_FA_CASH_PREDICTION	Cash Prediction
SRV_FA_LLMS_TRAINING	LLMS Training
SRV_FA_NATURAL_EJ_LOG_CASH	Natural Electronic Journal Log
SRV_FA_CUST_ACC_ADDRESS_UPDATE	Account Address Update Menu

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-4 (Cont.) List of Functional Activity codes to be mapped to appear in menu for transaction screen

Functional Activity Code	Screen Name and Functional Activity Description
SRV_AAURQ_APP_STAGE	Account Address Update Menu
SRV_AAURQ_APP_SUBMIT_UBS	Account Address Update Menu
SRV_FA_CUST_ADDR_UPD	Customer Address Update
SRV_CAURQ_APP_STAGE	Customer Address Update
SRV_CAURQ_APP_SUBMIT_UBS	Customer Address Update
SRV_FA_CUST_CONT_DETAILS_UPDATE	Customer Contact No Update
SRV_CCURQ_APP_STAGE	Customer Contact No Update
SRV_CCURQ_APP_SUBMIT_UBS	Customer Contact No Update
SRV_FA_TC_PUR_ACC	TC Purchase By Account
SRV_FA_TC_PURCHASE_WALKIN	TC Purchase Walk-in
SRV_FA_TCPURC_INITIATION_TASK	TC Purchase Walk-in
SRV_FA_TCPURC_APPROVE	TC Purchase Walk-in
SRV_FA_TC_SAL_ACCGL	TC Sale By Other Modes
SRV_FA_TC_SALE_WALKIN	TC Sale Walk-in
SRV_FA_TCSALE_INITIATION_TASK	TC Sale Walk-in
SRV_FA_TCSALE_APPROVE	TC Sale Walk-in
SRV_FA_MENU_INSTR_INQUIRY	Instrument Details Inquiry

Table A-5 List of Functional Activity codes for Widgets

Functional Activity Code	Description
REMO_FA_TILL_CASH_POSITION	This is for till cash position.
REMO_FA_TRANSACTION_STATUS	This is for transaction status.
REMO_FA_ALERTS	This is for Teller alerts.
REMO_FA_CURRENT_TILL_POSITION	This is for the current till position.
REMO_FA_CUSTOMER_SEARCH	This is for the customer panel search.
REMO_FA_CUSTOMER_SERVICE_REQUESTS	This is for the customer service requests.
REMO_FA_FREQUENT_BRANCH_OPERATIONS	This is for the frequent branch operations.
REMO_FA_FREQUENT_CUSTOMER_OPS	This is for frequent customer operations.
REMO_FA_FREQUENT_LINKS	This is for the frequent links.
REMO_FA_INVENTORY_IN_HAND	This is for inventory in hand.
REMO_FA_NOTIFICATIONS	This is for notifications.
SRV_FA_BUSI_ACT_MONI	Business Activity Monitoring

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-6 List of Functional Activity codes for common Transaction

Functional Activity Code	Description
SRV_FA_OBBRN_BASE	Common Transaction Functional Activity

Table A-7 List of Functional Activity codes for API

Functional Activity Code	API Name	Functional Activity Codes Description
SRV_FA_EXTERNAL_CASH_DEPOSIT_EXECUTESUBMIT	Cash Deposit Service API	Perform Cash deposit transaction using external system
SRV_FA_EXTERNAL_CASH_WITHDRAWAL_SAVE	Cash Withdrawal Service API	Perform Cash Withdrawal transaction using external system
OBBRN_FA_EXT_MISC_DEBIT	Miscellaneous Debit Service API	Perform External miscellaneous Debittransaction using external system
SRV_FA_EXT_MISCGLREQUEST	Miscellaneous Credit Service API	Perform External miscellaneous credittransaction using external system
SRV_FA_EXTERNAL_ACCOUNT_BALANCE_EXECUTESUBMIT	Account balance enquiry Service API	Perform Account balance enquirytransaction using external system
SRV_FA_EXTERNAL_ACCOUNT_TRANSFER_EXECUTESUBMIT	Account to Account Transfer Service API	Perform Account to Account transfer transaction using external system
OBBRN_FA_TXN_SERVICE_REV	Cash Deposit and Cash withdrawal Reversal API	Perform External Cash Deposit and Cash Withdrawal Reversal transaction using external system

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table A-7 (Cont.) List of Functional Activity codes for API

Functional Activity Code	API Name	Functional Activity Codes Description
OBBRN_FA_TRANSACTION_SERVICE_TILL_UPD	Transaction Till Service API	Perform External Cash Deposit, Cash Withdrawal other supported cash related transactions using external system
OBBRN_FA_TRANSACTION_SERVICE_TILL_UPD_REVR	Transaction Till Reversal API	Perform same day Reversal of transactions done using Transaction till service API
OBBRN_FA_TILL_UPD	Till Update Service API	Perform Till update transaction using external system
OBBRN_FA_TILL_SERVICE_TILL_UPD_REVR	Till Update Reversal API	Perform Reversal of till update transactions done using till update API

Copyright © 2021, 2025, Oracle and/or its affiliates.

B

Error Codes and Messages

The error codes and messages that are available for the Oracle Banking Branch application are provided in this appendix. The error codes with the prefix GCS apply only to the maintenance screens, and the remaining error codes apply to all the transaction screens.

Table B-1 Error Codes and Messages

Error Code	Message
CLMO-AC-003	Source stage value should be either Y/N not valid
CLMO-AC-017	DatasegmentCode not valid
CLMO-AC-018	DocumentType Code not valid
CLMO-AC-020	Life cycle not valid
CLMO-AC-023	Unable to $1 Business Process as $2 data segment has the following dependencies $3 in lifecycle $4
CLMO-AC-024	Unable to $1 Business Process as the mandatory data segments $2 for the $3 lifecycle have not been mapped!
CLMO-AC-026	In $1 stage of $2 Business Process
CLMO-AC-027	Record already exist with same Lifecycle and Business Product
CLMO-AC-028	At $1 in $2 stage of $3 Business Process
CLMO-AC-029	At $1 in $2 stage of $3 Business Process
CLMO-AC-030	Business Product Code is Invalid
GCS-AUTH-01	Record Successfully Authorized
GCS-AUTH-02	Valid modifications for approval were not sent. Failed to match
GCS-AUTH-03	Maker cannot authorize
GCS-AUTH-04	No valid unauthorized modifications found for approval.
GCS-CLOS-002	Record Successfully Closed
GCS-CLOS-01	Record Already Closed
GCS-CLOS-02	Record Successfully Closed
GCS-CLOS-03	Unauthorized record cannot be closed
GCS-COM-001	Record does not exist
GCS-COM-002	Invalid version sent
GCS-COM-003	Please Send Proper ModNo
GCS-COM-004	Please send makerId in the request

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
GCS-COM-005	Request is Null. Please Resend with Proper Values
GCS-COM-006	Unable to parse JSON
GCS-COM-007	Request Successfully Processed
GCS-COM-008	Modifications should be consecutive.
GCS-COM-009	Resource ID cannot be blank or "null".
GCS-COM-010	You have successfully cancelled $1.
GCS-COM-011	Argghhh, $1 failed to update.
GCS-DEL-001	Record deleted successfully
GCS-DEL-002	Record(s) deleted successfully
GCS-DEL-003	Modifications didnt match valid unauthorized modifications that can be deleted for this record
GCS-DEL-004	Send all unauthorized modifications to be deleted for record that is not authorized even once.
GCS-DEL-005	Only Maker of first version of record can delete modifications of record that is not once authorized.
GCS-DEL-006	No valid unauthorized modifications found for deleting
GCS-DEL-007	Failed to delete. Only maker of the modification(s) can delete.
GCS-MOD-001	Closed Record cannot be modified
GCS-MOD-002	Record Successfully Modified
GCS-MOD-003	Record marked for close
GCS-MOD-004	Only maker of the record can modify before once auth
GCS-MOD-005	Not amendable field
GCS-MOD-006	Natural Key cannot be modified
GCS-MOD-007	Pssstt, only the maker can modify the pending records.
GCS-OPEN-01	Teller Batch Record Already Opened
GCS-REOP-003	Successfully Reopened
GCS-REOP-004	Unauthorized record cannot be reopened
GCS-REOP-01	Unauthorized Record cannot be Reopened
GCS-REOP-02	Failed to Reopen the Record
GCS-REOP-03	Successfully Reopened
GCS-SAV-001	Record already exists
GCS-SAV-002	Record Saved Successfully.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
GCS-SAV-003	Congratulations!! The record is saved and validated successfully.
GCS-SAV-004	Currency Code should be unique
GCS-SAV-005	Min cash holding should be lesser than Max cash holding
GCS-VAL-001	Congratulations!! Your record is successfully validated.
RM_BC_CV_01	Amount Limit Exceeded for Account Number
RM_BC_CV_02	Amount Limit Exceeded for Customer Type
RM_BC_CV_03	Amount Limit Exceeded for Product Class
RM_BC_MA_01	Netting Charges Required Should be (Y/N).
RM_BC_MA_02	Main Leg Accounting Required Should be (Y/N).
RM_BC_MN_01	Invalid function code for till/vault indicator
RM_BC_MN_02	Invalid transaction type for till/vault indicator
RM_BC_OB_08	Please close the previous day batch
RM_BC_OB_09	User is not allowed to open the Teller batch
RM_BC_OB_10	Teller batches should be closed before closing the branch/vault batch
RM_BC_OB_11	Vault batch should be closed before closing the branch batch
RM_BC_TB_10	Teller batch is already opened
RM_BC_TB_11	Teller batch is already closed
RM_BC_VA_01	Supervisor Id is not present for manual assignment.
RM_CS_BC_01	Invalid Instrument No
RM_CS_BC_02	Instrument is already in Used status
RM_CS_BC_03	Instrument is not in INIT status to Print/ Reprint
RM_CS_BC_04	Instrument Number Already Liquidate
RM_CS_DD_04	Incorrect DD details
RM_CT_AC_03	Account Type mismatch.... Exception Occured
RM_CT_AC_04	Invalid Account Number
RM_CT_AC_06	Both Account cannot be Customer Accounts
RM-IN-TX-01	Payments Service is not Reachable
RM_TR_EX_01	Unhandled Exception Occured
RM_TX_CX_01	Authorization required for Charge Amendment.
RM_TX_EX_01	Authorization required for inter branch Transaction.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
RM-AD-EC-01	Failed in ECA
RM-AD-HH-01	Failed in Host Handoff
RM-AD-PM-03	Failed in payment
RM-AD-UB-01	Failed in DDA system
RM-AD-VM-01	Invalid Account Number
RM-AD-VM-02	VAM Service is down
RM-BC-AC-01	Failed in Accounting
RM-BC-BP-01	Please Enter the entire Branch Parameter Detail values
RM-BC-CH-01	Minimum Charge Greeater Than Maximum Charge
RM-BC-CH-02	Please Enter the proper charge code
RM-BC-CH-03	Charge Fields Cannot be empty
RM-BC-CH-04	Please Enter Mininmum and Maximum Charges
RM-BC-CP-03	Function code should not be empty
RM-BC-EJ-01	Record Not Found
RM-BC-EJ-02	Record Updation Failed..
RM-BC-EX-01	Unhandled Exception Occured
RM-BC-EX-02	Transaction Timed Out
RM-BC-EX-03	Unhandled Exception Occured
RM-BC-ML-01	Email Account not Valid
RM-BC-OB-01	Branch batch is already open for the current date
RM-BC-OB-02	Branch batch can be opened only by supervisor
RM-BC-OB-03	Vault batch is open for the current or previous date
RM-BC-OB-04	User does not have rights to access this screen
RM-BC-OB-05	Teller batch is open for the current or previous date
RM-BC-OB-06	Please complete the pending transactions in the Electronic Journal log
RM-BC-OB-07	Branch batch is not opened
RM-BC-OB-08	Please close the previous day batch
RM-BC-OB-10	Teller batches should be closed before closing the branch/vault batch
RM-BC-OB-11	Vault batch should be closed before closing the branch batch
RM-BC-OB-16	Teller batch is closed
RM-BC-OB-17	Teller batch is not opened for the user

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
RM-BC-OB-18	Teller batch is already open
RM-BC-OB-19	Teller batch is closed
RM-BC-OB-20	Invalid Currency Code
RM-BC-OB-21	Authlimit Breached
RM-BC-OB-22	Transaction limit breached at role level
RM-BC-OB-23	Wrong token
RM-BC-OB-24	Branch batch is already closed
RM-BC-OB-25	Vault batch is already closed
RM-BC-OB-26	User is not allowed to open/close the teller batch
RM-BC-OB-27	Vault batch is not opened
RM-BC-OB-29	Please maintain denomination tracking in Branch Parameter
RM-BC-OB-30	Denomination Amount is not equal to transaction amount
RM-BC-OB-31	Insufficient Amount available in Till/Vault
RM-BC-OB-32	Logged in user ID and Teller Id cannot be same
RM-BC-OB-33	Invalid Input TellerId
RM-BC-OB-34	Current Denomination balance is less than zero for $1
RM-BC-PM-01	Record Successfully Updated
RM-BC-RT-01	Failed in getting the exchange rate
RM-BC-RT-02	Failed to fetch Branch Accounting Tags
RM-BC-TF-01	User not Verified Signature
RM-BC-TF-02	Transaction involves Inter Bank Accounts
RM-BC-TF-03	Default Charge Amount was modified
RM-BC-TF-04	Default Exchange Rate was modified
RM-BC-TF-05	Amount exceeds limit for this transaction
RM-BC-TF-06	Authorisation required. Amount exceeds limit for the transaction
RM-BC-TF-07	Transaction & Electronic Journal ID needs to be Enter..
RM-BC-TF-08	Invalid Txn_Ref_Number found for given EJId
RM-BC-TR-07	Invalid Input!!
RM-BC-UL-01	User Limit Transaction Amount breached
RM-BC-UL-02	Authorizer Limit Transaction Amount breached
RM-BC-UL-03	User Limit Holding Minimum Amount breached
RM-BC-UL-04	User Limit Holding Maximum Amount breached

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
RM-BC-UP-01	Amount exceeds limit for this transaction
RM-BC-UP-02	Minimum charge amount should be applied
RM-BC-UP-03	Amount exceeds limit for this transaction
RM-BC-UP-04	Authorisation amount breached.
RM-BC-UP-05	Till maximum balance breached
RM-BC-UP-06	Till minimum balance breached
RM-BC-UP-07	Authoriser role limit breached
RM-BC-UP-08	Teller role limit breached
RM-BC-UP-09	Transaction requires approval.
RM-BC-UR-01	Submit URL not maintained
RM-BC-VA-01	Till open
RM-BC-VA-02	Vaultl open
RM-BC-VA-03	Pending txn
RM-BC-VA-10	Invalid Status
RM-BC-XR-01	Exchange not Maintained
RM-BC-XT-01	Failed in getting the exchange rate
RM-CH-LM-01	Channel limit not found for Account class group
RM-CH-LM-02	Channel limit details not found
RM-CH-LM-03	Channel limit details found for transaction currency
RM-CH-LM-04	Number of Withdrawal breached
RM-CH-LM-05	Withdrawal Limit breached
RM-CM-OR-001	Failed to initiate.
RM-CM-OR-002	Transaction is successfully initiated.
RM-CM-OR-003	Invalid action
RM-CM-OR-004	$1 is not submitted
RM-CM-OR-005	Cannot proceed with submit as the action is not initiated.
RM-CM-OR-006	Cannot proceed with submit as the information is incomplete.
RM-CM-OR-007	Failed to submit.
RM-CM-OR-008	Record successfully submitted.
RM-CM-OR-009	$1 is in-progress
RM-CM-OR-010	Aw, snap! An unexpected exception occurred, try again.
RM-CM-OR-011	Invalid request.
RM-CM-OR-012	Cannot proceed with submit as the action is not initiated.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
RM-CM-OR-013	Cannot find the provided information.
RM-CM-OR-014	Record is not yet submitted by $1
RM-CM-OR-015	Record already unlocked by $1.
RM-CS-OB-01	Invalid denomination found
RM-CS-OB-02	Invalid denomination found for given currency or denomination type
RM-CS-OB-03	Transaction Number Already Exist
RM-CS-OB-04	Data Not Found
RM-CS-OB-05	Amount mismatch
RM-CS-OB-50	SanctionRefNo is already Present.
RM-CS-TF-07	MinCash excedes the MaxCash Value
RM-CT-AC-01	Charges are not maintained
RM-CT-AC-02	Charges should not be maintained
RM-CT-AC-04	Failed to get the account
RM-EX-CS-01	User is an Invalid User.
RM-EX-CS-02	Account number is invalid.
RM-EX-CS-03	Source Reference Number Already Present
RM-EX-CS-05	NegotiatedExchangeRate is not provided
RM-EX-CS-06	NegotiationReferenceNumber is not provided
RM-EX-PY-05	NegotiatedExchangeRate is not provided
RM-EX-PY-06	NegotiationReferenceNumber is not provided
RM-PA-EQ-01	Record not Found.
RM-PY-AC-01	From account and to account are same
RM-PY-AC-02	Account number not entered for field $1
RM-PY-BC-01	Bank code or bank BIC code not entered
RM-PY-BC-02	Please enter either bank code or bank BIC code
RM-PY-CL-01	Payee account and drawer account are same
RM-PY-CL-02	Drawer account number and instrument number combination are same
RM-PY-CL-03	Invalid Batch Number
RM-PY-CR-01	Remittance number not found
RM-PY-CR-02	Remittance number is already issued/used
RM-PY-CR-03	Please provide Remittance number/Test Key number
RM-PY-CR-04	Invalid Remittance number/Test Key number
RM-PY-CR-05	Remittance numbers are not maintained
RM-PY-CR-06	Maintained remittance numbers are all USED ones
RM-PY-IN-01	Instrument details not found

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
RM-TD-SL-01	No Maintanance found for Term Deposit opening
RM-TD-SL-02	Offset GL account not found
RM-TN-RV-02	The transaction Status should be pending
RM-TR-EX-01	Unhandled Exception Occured
RM-TS-TB-10	Teller batch not opened yet
RM-TX-BE-01	Unhandled Exception Occured
RM-TX-CA-01	Charge amount limit Breached from Min Max Amount
RM-TX-CA-02	Charge amount limit Breached from Min Max Pecentage
RM-TX-CC-01	Add provided Currency to the Till
RM-TX-ET-01	Session should be Opened before closing.
RM-TX-ET-02	Amount $1 $2 has to be given by the customer.
RM-TX-ET-03	Amount $1 $2 has to be given to the customer.
RM-TX-ET-04	The incoming cash amount in the session is exceeding by $1 $2.Do you want to proceed.
RM-TX-ET-05	Open Teller Sessions are present. Cannot proceed with the operation.
RM-TX-ET-06	Teller Session Transactions not completed.Cannot proceed with the operation.
RM-TX-EX-01	Unhandled Exception Occured
RM-TX-HH-01	Failed in Host Handoff
RM-TX-LC-01	Transaction is locked
RM-TX-LI-00	Amount exceeds the limit of transaction.
RM-TX-NL-01	Unhandled Exception Occured
RM-TX-OC-01	Branch Info not available
RM-TX-OC-02	Function Code definition not maintained
RM-TX-OC-03	Function Code preferences not maintained
RM-TX-OC-04	Branch Parameter maintenance not found
RM-TX-OC-05	User preferences not maintained
RM-TX-OC-06	Default authorizer not maintained for the user
RM-TX-OC-07	Function Indicator entry not found
RM-TX-OC-08	Record status is null in Function Code Definition Screen
RM-TX-OC-09	Record status is closed in Function Code Definition Screen
RM-TX-OC-10	Record status is null in User Preferences Screen
RM-TX-OC-11	Record status is closed in User Preferences Screen

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
RM-TX-OC-12	Record status is null in Function Code Preferences Screen
RM-TX-OC-13	Record status is closed in Function Code Preferences Screen
RM-TX-PM-01	Transaction status is pending, waiting for the notification from payment system
RM-TX-PM-03	Failed in payment system
RM-TX-RV-01	The transaction Status should be completed
RM-TX-RV-02	Only maker can reverse the transaction
RM-TX-RV-03	Authorization required for reversal
RM-TX-RV-04	Minimum teller branch ccy holding limit breached
RM-TX-RV-05	Maximum teller branch ccy holding limit breached
RM-TX-SL-01	Unhandled Exception Occured
RM-TX-ST-01	The incoming cash amount in the session is exceeding by $1.Do you want to proceed.
RM-TX-ST-02	Total inflow cash amount remaining after this transaction is $1.
RM-TX-ST-03	Another open session in progress for the entered Customer No
RM-TX-ST-04	Another open session in progress for the Teller
RM-TX-ST-05	Teller session needs to be opened to perform this transaction.
RM-TX-ST-06	This transaction is not allowed inside the teller session
RM-TX-TO-01	Unhandled Exception Occured
RPM-AC-003	Source stage value should be either Y/N not valid
RPM-AC-017	DatasegmentCode not valid
RPM-AC-018	DocumentType Code not valid
RPM-AC-020	Life cycle not valid
RPM-AC-023	Unable to $1 Business Process as $2 data segment has the following dependencies $3 in lifecycle $4
RPM-AC-024	Unable to $1 Business Process as the mandatory data segments $2 for the $3 lifecycle have not been mapped!
RPM-AC-026	In $1 stage of $2 Business Process
RPM-AC-027	Record already exist with same Lifecycle and Business Product
RPM-AC-028	At $1 in $2 stage of $3 Business Process
RPM-AC-029	At $1 in $2 stage of $3 Business Process

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table B-1 (Cont.) Error Codes and Messages

Error Code	Message
RPM-AC-030	Business Product Code is Invalid
RT-F23-001	Error. Enter at least one row in Payment Data Details
RT-F23-002	Error. Cannot enter more than eight records in Payment Data Details
RT-F23-006	Error. Mandatory Field Payment Type Cannot be Null.
RT-F23-007	Error. Fiscal Code has to be 11 or 16 character long.
RT-F23-008	Error. Fiscal code does not meet checksum algorithm validations
RT-F23-017	Error. Enter at least one field in either Reference Number Available or Reference Number Not Available.
RT-F23-019	Error. Both Reference Number and Primary fiscal code cannot be null.
RT-F23-020	Invalid character entered for Tax Code
RT-F24-099	Payment Amount Cannot be Zero/Negative
RT-F24-101	Payment amount should not Be Blank
RT-F24-114	Principal fiscal code is mandatory
UBS-BC-UB-01	No More Payments
UBS-BC-UB-02	Invalid Settlement Account for the Contract

Copyright © 2021, 2025, Oracle and/or its affiliates.

C

List of Function Codes

The list of function codes and their respective names for all the transaction screens of the Oracle Banking Branch application are provided in this appendix.

Table C-1 List of Function Codes

Function Code	Screen Name
0006	Account to Account Transfer
0007	In-House Cheque Deposit
1000	Miscellaneous Transfer
1001	Cash Withdrawal
1002	Cash Withdrawal (Teller Session)
1005	Miscellaneous GL Transfer
1008	Miscellaneous Customer Debit
1009	TC Sale Against Account
1010	BC Issue Against Account
1013	Cheque Withdrawal
1014	DD Issue Against Account
1025	Bill Payment by Cash
1060	Miscellaneous GL Debit
1075	Bill Payment by Account
1320	Close-out Withdrawal by Account
1321	Close-out Withdrawal by Cash
1401	Cash Deposit
1403	Cash Deposit (Teller Session)
1404	Domestic Transfer Against Account
1405	Domestic Transfer Against Walk-in
1406	International Transfer Against Account
1407	International Transfer Against Walk-in
1408	Miscellaneous Customer Credit
1409	Interbranch Transaction Request
1410	Interbranch Transaction Input
1411	Interbranch Liquidation Input
1412	TC Purchase Against Account
1421	RD Payment by Cash
1460	Miscellaneous GL Credit
1461	Credit Card Advance by Cash
1462	Credit Card Advance by Transfer

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table C-1 (Cont.) List of Function Codes

Function Code	Screen Name
1471	Credit Card Payment by Cash
1472	Credit Card Payment
1472CA	Credit Card Payment by Account
1472CG	Credit Card Payment by Clearing Cheque
3401	Safe Deposit Rental by Cash
5001	Loan Disbursement by Cash
5401	Loan Repayment by Cash
5402	Murabaha Payment by Cash
5403	Islamic Down Payment by Cash
5404	Loan Repayment by Cash (Teller Session)
5555	Inward Clearing Data Entry
6001	Open Branch Batch
6002	Close Branch Batch
6005	Electronic Journal
6501	Cheque Deposit (Account)
6514	Outward Clearing Data Entry
6520	Cheque Deposit (GL)
6560	Cheque Return
7001	Open Vault Batch
7002	Close Vault Batch
7005	Servicing Journal
7010	Passbook Update
7011	Passbook Reprint
7030	Passbook Issue
7031	Passbook Status Change
7040	Teller Total Position
7551	Book Shortage
7552	Book Overage
7553	Book Vault Shortage
7554	Book Vault Overage
7787	Multi BC Issuance (Account)
7788	Multi BC Issuance (Cash)
8003	TC Purchase Against Walk-in
8004	FX Purchase Against Walk-in
8008	FX Purchase Against Walk-in (Teller Session)
8203	FX Sale Against Walk-in
8204	FX Sale Against Walk-in (Teller Session)

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table C-1 (Cont.) List of Function Codes

Function Code	Screen Name
8205	TC Sale Against GL
8206	FX Sale Against Account
8207	FX Purchase against Account
8222	TC Sale Against Walk-in
8301	BC Issue Against Walk-in
8302	BC Issue Against GL
8305	DD Issue Against Walk-in
8306	DD Issue Against GL
8316	Cash Remittance Issue (Cash)
8317	Cash Remittance Issue (GL)
8318	Cash Remittance Issue (Account)
8319	Cash Remittance Operations (Inquiry)
8320	Cash Remittance Operations (Payment – Account)
8321	Cash Remittance Operations (Payment – Cash)
8322	Cash Remittance Operations (Payment – GL)
8324	Cash Remittance Operations (Refund – Account)
8325	Cash Remittance Operations (Refund – Cash)
8326	Cash Remittance Operations (Refund – GL)
8327	Cash Remittance Operations (Cancel – Account)
8328	Cash Remittance Operations (Cancel – Cash)
8329	Cash Remittance Operations (Cancel – GL)
8330	Inward Cash Remittance
8450	DD Operations
8550	BC Operations
9001	Open Teller Batch
9002	Close Teller Batch
9005	Buy Cash from Till
9006	Sell Cash to Till
9007	Buy Cash from Vault
9008	Sell Cash to Vault
9009	Buy Cash from Currency Chest
9010	Sell Cash to Currency Chest
9011	Buy TC From Agent
9012	Current Open Tills
9015	Buy TC From HO
9016	Return TC to HO
9017	Buy TC From Vault

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table C-1 (Cont.) List of Function Codes

Function Code	Screen Name
9018	Return TC to Vault
9020	View Available TC with Vault
9401	Start Teller Session
9402	Stop Teller Session
AADU	Account Address Update
ACBL	Account Balance Inquiry
ACST	Account Statement Request
BCRP	BC Print-Reprint
CADU	Customer Address Update
CCTU	Customer Contact Details Update
CDBK	Stop Card
CQIN	Cheque Status Inquiry
CQRQ	Cheque Book Request
CQSC	Cheque Book Status Change
CQST	Stop Cheque Request
DDRP	DD Print-Reprint
DNEX	Denomination Exchange
VNEX	Vault Denomination Exchange
F23A	F23 Tax Payment by Account
F23C	F23C Tax Payment by Cash
F24A	F24 Tax Payment by Account
F24C	F24C Tax Payment by Cash
REAN	Reassign Transactions
TDI1	Islamic TD Account Opening
TDO1	TD Account Opening
TDR1	TD Redemption Against Cash
TDR2	TD Redemption Against Account
TDT1	TD Top-Up Against Cash
TDT2	TD Top-Up Against Account
TVQB	Branch Breaching Limits
TVQR	Till Vault Position

Copyright © 2021, 2025, Oracle and/or its affiliates.

D
Advices

The formats of various advices that are available for the Oracle Banking Branch application are provided in this appendix.

Advice format

User can select the **locale** to generate the advice in their preferred language.

Figure D-1 Advice Format - Locale




Table D-1 Advices

Advices	Sample Files
Account Transfer	Account Transfer
Cash Deposit	Cash Deposit
Cash Withdrawl	Cash Withdrawal
Cheque Deposit	Cheque Deposit
Cheque Withdrawal	Cheque Withdrawal
DD Issue Against Account	DD Issue Against Account
Domestic Transfer	Domestic Transfer

The advice is supported by those screens.

1. Account Transfer
2. BC Issue
3. BC Liquidation
4. Book Overage
5. Book Shortage
6. Buy Cash

Copyright © 2021, 2025, Oracle and/or its affiliates.

7. Cash Deposit
8. Cash Withdrawal
9. Cheque Deposit
10. Cheque Withdrawal
11. DD Issue Against Account
12. Domestic Transfer Against Account
13. FX Purchase Account
14. FX Purchase Walkin
15. FX Sale Account
16. FX Sale Walkin
17. InHouse Cheque Deposit
18. Miscellaneous Customer Credit
19. Miscellaneous Customer Debit
20. Miscellaneous GL Credit
21. Miscellaneous GL Debit
22. Passbook Issue
23. Passbook Update

Copyright © 2021, 2025, Oracle and/or its affiliates.

E

Order of Replacing Parameters with Wild Card Entries

The order of replacing parameters with wild card entries is required for the Accounting and Settlements Definition and Charge Decision Maintenance.

Table E-1 Order for Accounting and Settlements Definition

Function Code	Branch	Currency
Function Code	Txn Branch	Txn Currency
Function Code	*.*	Txn Currency
Function Code	Txn Branch	*.*
Function Code	*.*	*.*

Table E-2 Order for Charge Pickup

Function Code	Txn Branch	Txn Currency	Inter Branch
Function Code	Txn Branch	Txn Currency	Y
Function Code	Txn Branch	Txn Currency	N
Function Code	*.*	Txn Currency	Y
Function Code	*.*	Txn Currency	N
Function Code	Txn Branch	*.*	Y
Function Code	Txn Branch	*.*	N

Table E-3 Order for Charge Group

Parameter1	Parameter2	Parameter3	Parameter4	Parameter5
Parameter1	Parameter2	Parameter3	Parameter4	Parameter5
Parameter1	Parameter2	Parameter3	Parameter4	*.*
Parameter1	Parameter2	Parameter3	*.*	Parameter5
Parameter1	Parameter2	*.*	Parameter4	Parameter5
Parameter1	*.*	Parameter3	Parameter4	Parameter5
.	Parameter2	Parameter3	Parameter4	Parameter5
.	*.*	Parameter3	Parameter4	Parameter5
Parameter1	*.*	*.*	Parameter4	Parameter5
Parameter1	Parameter2	*.*	*.*	Parameter5
Parameter1	Parameter2	Parameter3	*.*	*.*
Parameter1	Parameter2	*.*	*.*	*.*
Parameter1	*.*	*.*	*.*	Parameter5

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table E-3 (Cont.) Order for Charge Group

Parameter1	Parameter2	Parameter3	Parameter4	Parameter5
.	*.*	*.*	Parameter4	Parameter5
.	*.*	*.*	*.*	Parameter5
Parameter1	*.*	*.*	*.*	*.*
.	*.*	*.*	*.*	*.*

Copyright © 2021, 2025, Oracle and/or its affiliates.

F

Static Maintenance Parameters

The descriptions for the column names of the significant parameters in the static maintenance tables are provided in this appendix. If required, the user needs to modify these parameters in the respective static maintenance tables.

Table F-1 Columns in SRV_TM_BC_FUNCTION_INDICATOR Table

Column Name	Description
CROSS_CCY_ENABLED	This column indicates whether the cross-currency is allowed for a transaction or not. The user can modify this flag to enable/disable the cross-currency configuration. Possible values are as follows: • **Y** – Yes • **N** – No **Note** When the value is set to **N**, the **Exchange Rate** fields will be hidden.
DENOM_VARIANCE	This column indicates the applicability of denomination variance. The user can modify this flag to enable/disable the denomination variance. Possible values are as follows: • **Y** – Yes • **N** – No **Note** This flag applies only to the function codes – 8004, 8203, 8206, and 8207.
IS_NEGOTIATED_RATE_ENABLED	This column indicates whether the **Negotiated Exchange Rate** field is required on the screen or not. The user can modify this flag to enable/disable the **Negotiated Exchange Rate** for a specified screen. Possible values are as follows: • **Y** – Yes • **N** – No
IS_REVERSAL_SUPP	This column indicates whether the transaction reversal is supported or not. The user can modify this flag to enable/disable the reversal for a particular transaction. Possible values are as follows: • **Y** – Yes • **N** – No

Copyright © 2021, 2025, Oracle and/or its affiliates.

Table F-1 (Cont.) Columns in SRV_TM_BC_FUNCTION_INDICATOR Table

Column Name	Description
IS_TELLER_SEQ_REQ	This column indicates whether the Teller Sequence Number generation is required or not. The user can modify this flag to enable/disable the Teller Sequence Number generation for a particular transaction. Possible values are as follows: • **Y** – Yes • **N** – No
IS_TOT_CHARGES_REQ	This column indicates whether the **Total Charges** field is required on the screen or not. The user can modify this flag to enable/disable the **Total Charges** for a particular transaction. Possible values are as follows: • **Y** – Yes • **N** – No

Table F-2 Columns in SRV_TB_BC_ARCHIVAL Table

Column Name	Description
ARCHIVAL_DAYS	This column indicates the number of days required for the archival. The user can modify this flag to update the number of days.
BRANCH_CODE	This column indicates the Branch Code, based on which the lookup of Archival details will happen. It refers to the branch in which the archival will happen. The user can modify this flag to update the Branch Code.

Copyright © 2021, 2025, Oracle and/or its affiliates.

Index

A

Account Address Update, *18*
Account Balance Inquiry, *13*
Account Entitlement Restriction, *61*
Account Group Maintenance, *37*
Account Statement Request, *16*
Account to Account Transfer, *1*
Alerts, *7*

B

BC Issue Against Account, *2*
BC Issue Against GL, *9*
BC Issue Against Walk-in, *6*
BC Operations - Cancel by Account, *33*
BC Operations - Cancel by Cash, *35*
BC Operations - Cancel by GL, *37*
BC Operations - Duplicate Issue, *19*
BC Operations - Inquiry, *15*
BC Operations - Payment by Account, *20*
BC Operations - Payment by Cash, *23*
BC Operations - Payment by GL, *25*
BC Operations - Refund by Account, *27*
BC Operations - Refund by Cash, *29*
BC Operations - Refund by GL, *31*
BC Operations - Revalidate, *17*
BC Print-Reprint, *12*
Bill Payment by Account, *3*
Bill Payment by Cash, *1*
Bill Payment by Clearing Cheque, *6*
Book Overage, *23*
Book Shortage, *20*
Book Vault Overage, *26*
Book Vault Shortage, *25*
Branch Breach Limits, *10*
Branch Group Maintenance, *39*
Branch Role Limits, *6*
Branch Total Position, *13*
Branch User Limits, *7*
Business Activity Monitoring, *9*
Buy Cash from Currency Chest, *12*
Buy Cash from Till, *18*
Buy Cash from Vault, *15*
Buy TC from Agent, *2*
Buy TC from Head Office, *4*
Buy TC from Vault, *6*

C

Cash Deposit, *2*
Cash Deposit (Teller Session), *1*
Cash Prediction, *2*
Cash Remittance Issue Against Account, *87*
Cash Remittance Issue Against Cash, *91*
Cash Remittance Issue Against GL, *94*
Cash Remittance Operations - Cancel by Account, *116*
Cash Remittance Operations - Cancel by Cash, *119*
Cash Remittance Operations - Cancel by GL, *121*
Cash Remittance Operations - Inquiry, *97*
Cash Remittance Operations - Payment by Account, *100*
Cash Remittance Operations - Payment by Cash, *102*
Cash Remittance Operations - Payment by GL, *105*
Cash Remittance Operations - Refund by Account, *108*
Cash Remittance Operations - Refund by Cash, *111*
Cash Remittance Operations - Refund by GL, *113*
Cash Withdrawal, *7*
Cash Withdrawal (Teller Session), *2*
Channel Limits Maintenance, *35*
Charge Condition Group Maintenance, *44*
Charge Decision Enquiry, *51*
Charge Decision Maintenance, *47*
Charge Definition Maintenance, *12*
Cheque Book Request, *4*
Cheque Book Status Change, *21*
Cheque Deposit Against Account, *1*
Cheque Deposit Against GL, *5*
Cheque Return, *8*
Cheque Status Inquiry, *2*
Cheque Withdrawal, *10*
Clearing Network, *53*
Close Branch Batch, *19*
Close Out Withdrawal, *27*
Close Out Withdrawal by Multi Mode, *33*
Close Teller Batch, *14*

Copyright © 2021, 2025, Oracle and/or its affiliates.

Close Vault Batch, *16*
Create Charge Pricing Maintenance, *42*
Create Customer Account GST Parameters, *66*
Create GST Branch Parameters, *64*
Create GST Rule Maintenance, *63*
Credit Card Advance by Cash, *1*
Credit Card Advance by Transfer, *4*
Credit Card Payment by Account, *9*
Credit Card Payment by Cash, *6*
Credit Card Payment by Cheque, *11*
Current Open Tills, *8*
Current Till Position, *4*
Customer Address Update, *17*
Customer Contact Update, *19*
Customer Group Maintenance, *40*
Customer Search, *3*
Customer Service Request, *6*

D

DD Issue Against Account, *46*
DD Issue Against GL, *54*
DD Issue Against Walk-in, *50*
DD Operations - Cancel by Account, *79*
DD Operations - Cancel by Cash, *81*
DD Operations - Cancel by GL, *84*
DD Operations - Duplicate Issue, *63*
DD Operations - Inquiry, *59*
DD Operations - Payment by Account, *65*
DD Operations - Payment by Cash, *68*
DD Operations - Payment by GL, *70*
DD Operations - Refund by Account, *72*
DD Operations - Refund by Cash, *74*
DD Operations - Refund by GL, *77*
DD Operations - Revalidate, *61*
DD Print-Reprint, *57*
Default Authorizer Maintenance, *24*
Denomination Exchange, *21*
Denomination Variation Maintenance, *55*
Denominations Maintenance, *9*
Domestic Transfer Against Account, *6*
Domestic Transfer Against Walk-in, *11*

E

Electronic Journal, *4*
External Bank Code, *56*
External System Maintenance, *33*

F

F23 Tax Payment by Account, *60*
F23C Tax Payment by Cash, *40*
F24 Tax Payment By Account, *65*
F24C Tax Payment By Cash, *44*
Frequent Branch Operations, *5*
Frequent Customer Operations, *5*
Frequent Links, *8*
Function Code Definition, *14*
Function Code Preferences, *18*
FX Purchase Against Account, *20*
FX Purchase Against Walk-in, *24*
FX Purchase Against Walk-in (Teller Session), *7*
FX Sale Against Account, *14*
FX Sale Against Walk-in, *17*, *3*

I

In-House Cheque Deposit, *4*
Instrument Details Inquiry, *144*
Instrument Number Maintenance, *29*
Instrument Status Update, *143*
Inter Branch Transaction Input, *27*
Inter Branch Transaction Liquidation, *29*
Inter Branch Transaction Request, *25*
Inter Branch Transit Account Maintenance, *31*
International Transfer Against Account, *12*
International Transfer Against Walk-in, *19*
Inventory in Hand, *2*
Inventory Integration, *146*
Inward Clearing Data Entry, *9*
Inward Remittance Registration, *124*
Islamic Down Payment by Cash, *3*
Islamic TD Account Opening, *5*
Issuer Code Maintenance, *58*

L

Large Language Model Training, *4*
Loan Disbursement by Cash, *1*
Loan Repayment by Cash, *3*
Loan Repayment by Cash (Teller Session), *8*

M

Miscellaneous Customer Credit, *4*
Miscellaneous Customer Debit, *1*
Miscellaneous GL Credit, *10*
Miscellaneous GL Debit, *7*
Miscellaneous GL Transfer, *12*
Miscellaneous Transfer, *15*
Multi BC Issuance - Account, *40*
Multi BC Issuance - Cash, *43*
Murabaha Payment by Cash, *1*
My Transaction Status, *3*

N

Natural Electronic Journal, *19*
Notifications, *7*

Copyright © 2021, 2025, Oracle and/or its affiliates.

O

Open Branch Batch, *3*
Open Teller Batch, *6*
Open Vault Batch, *4*
Outward Clearing Data Entry, *12*

P

Passbook Issue, *6*
Passbook Reprint, *11*
Passbook Status Change, *9*
Passbook Update, *8*

R

Reassign Transactions, *16*
Recurring Deposit Payment by Cash, *38*
Reject Code Maintenance, *52*
Return TC to HO, *11*
Return TC to Vault, *8*

S

Safe Deposit Rental By Cash, *36*
Sell Cash to Currency Chest, *14*
Sell Cash to Till, *20*
Sell Cash to Vault, *17*
Servicing Journal, *10*
Settlements Definition, *26*
Start Teller Session, *28*
Stop Card Request, *14*
Stop Cheque Request, *3*
Stop Teller Session, *30*

T

TC Denomination Enquiry, *2*
TC Purchase Against Account, *135*
TC Purchase Against Walk-in, *140*
TC Sale Against Walk-in, *132*
TC Sale by Other Modes, *127*
TD Account Opening, *1*
TD Redemption Against Account, *16*
TD Redemption Against Cash, *13*
TD Top-Up Against Account, *18*
TD Top-Up Against Cash, *20*
Teller Branch Parameters Maintenance, *4*
Teller Service Counters Prediction, *1*
Till Cash Position, *2*
Till Vault Position, *11*

U

Utility Provider Maintenance, *59*

V

Vault Denomination Exchange, *22*
View Charge Pricing Maintenance, *43*
View Customer Account GST Parameters, *67*
View GST Branch Parameters, *65*
View GST Rule Maintenance, *64*

Copyright © 2021, 2025, Oracle and/or its affiliates.